United States Department of the Interior Heritage Conservation and Recreation Service

National Register of Historic Places Inventory—Nomination Form

For HCRS use only received FEB 2.4 1982 date entered MAR 2.5 198

See instructions in *How to Complete National Register Forms*Type all entries—complete applicable sections

1. Name	9			
historic August	us M. Garrison Hous	se		
and/or common				The Tay May 1966
	Han-			
2. Loca	tion			
street & number	600 Pecan St.		N/1	not for publication
city, town Texar	kana	N/A vicinity of	congressional district	Fourth
state Arkansas	code	05 county	Miller	code 091
3. Class	ification			
district building(s) structure	Ownership public X_ private both Public Acquisition in process being considered	Status occupied unoccupied work in progress Accessible X yes: restricted yes: unrestricted no	Present Use agriculture commercial educational entertainment government industrial military	museum park X private residence religious scientific transportation other:
4. Owne	er of Proper	ty		
name Wayne Ga	rrison			
street & number 6				
city, town Texar		N/A vicinity of	state	Arkansas
5. Locat	tion of Lega	l Descripti	on	
courthouse, registi	ry of deeds, etc. Miller	County Courthouse		
street & number 4				
city, town Tex	arkana,		state	Arkansas
6. Repre	esentation i	n Existing	Surveys	
title <mark>Urban Devel</mark>	opment Action Grant	Survey has this pr	operty been determined ele	egible? yes X no
date June 1978			federal stat	e county _X local
depository for surv	vey records City of	Texarkana City Ha	111	
city, town Texark	ana		state	Arkansas

7. Description

Condition X excellent	deteriorated	Check one _X_ unaltered	Check one _X_ original site	
good fair	ruins unexposed	altered	moved date	

Describe the present and original (if known) physical appearance

The Garrison House occupies a picturesque corner site in Texarkana's oldest residential neighborhood. Raised on a brick foundation wall above the elevated landscaped grade, the two-and-one-half story wood frame structure terminating in a hip roof with cross gables and a round corner turret seems to tower over the street. Built in 1895, the house's asymmetrical yet gracefully massed proportions and its rich array of decorative woodwork exemplify the Queen Anne Style.

The principal (west) elevation of the house takes full advantage of the prominent corner siting. Though the elevation's broad cross gable clearly establishes a west orientation, the building turns the corner on a forty-five degree angled wall that holds the principal entrance to the house. The decoratively articulated entrance to the house's one-story wrap-around porch makes a distinctive statement of entry, visually embracing the Classically framed paneled front door with transom. Four concrete steps (originally built of wood) lead up to the porch entrance which is defined by the gable roof that projects from the building's chamfered southwest corner. Two pairs of turned columns supported on and terminating in square piers frame the entrance and their interior brackets suggest an arch over the porch threshold. Scrolled brackets enrich the outer corners of the columns which carry a cornice and simple frieze decorated with a band of scallops. The porch entrance's gable end rests on this simple entablature and is richly decorated with an Eastlake - influenced design of spindles radiating toward the gable peak, brackets and decorative horizontal and vertical banding.

The wrap-around porch continues along the principal elevation to meet a large chamfered half-hexagon shaped bay that projects from the northwest corner of the house. The two front bays of the shed-roofed porch are articulated in a manner consistent with the design of the entrance element with like detailed columns with exterior brackets supporting an overhanging cornice and interior brackets creating an arched motif. Imbricated shingles face the bell-cast portion of the porch roof where it meets the second floor balcony. This balcony, situated toward the center of the west elevation just south of the chamfered bay, repeats the design of the bracketed porch columns but has an elaborate wood frieze of a series of box-like recilinear shapes which terminate in a shallow arch. The balcony door and its transom are articulated in the same fashion as the front door. One of the building's broad cross gables roofs both the second floor balcony and the chamfered bay. This gable end is filled with Eastlake-inspired decoration. A bank of three windows pierces the gable end. Imbricated shingles cover the lower half of the gable while diagonal boards appear in the upper half. peak of the gable features a triangular wood panel, with cut-out decoration, that rests upon a row of brackets. The eaves of the gable terminate in cornice-like soffits. The chamfered bay itself is articulated with corner boards, base moulding and cornice moulding. One-over-one light rectangular double-hung windows pierce both the first and second floor walls of each side of the chamfered bay. Their classically detailed surrounds, with prominent cornices and scalloped bands under the sills, are consistent with those that appear elsewhere on the house. A panel composed of narrow diagonal wood bands appears between the first and second stories in the frontmost side of the chamfered bay. Spindled brackets with pendants span the angled sides of the chamfered bay beneath the cornice moulding.

United States Department of the Interior Heritage Conservation and Recreation Service

National Register of Historic Places Inventory—Nomination Form

For HCRS use only received FEB 2.4 1982 date entered

Continuation sheet

Item number

7

Page 2

A round two-story turret rises above the southwest corner of the house complementing the verticality of the chamfered bay and balancing the dominant front gable. The turret is faced with imbricated shingles, except at its base where wood shakes meet the porch roof below. The upper stage of the tower is slightly narrower and shorter than the lower story which corresponds to the second floor of the house. Three windows, detailed like those of the front elevation, appear in the lower stage of the tower while three smaller double-hung windows with upper lights of cathedral glass appear in the upper story. The tower terminates in a conical roof set upon a series of narrow brackets that encircle the top of the turret.

The delineation of the south side of the building reflects the design of the principal facade providing appropriately attractive frontage on the street. The west end of this facade is enriched by a three-bay long continuation of the front-porch and the lofty profile of the corner turret rising above the building's hip roof. At the center of the elevation, a cross gable extends over a half-hexagon shaped chamfered bay. The facades of the bay are articulated in the same manner as the front elevation's chamfered bay with like detailed windows in each side, corner boards, baseboard moulding and spindled brackets with pendants articulating the gable corners over the angled walls of the bay. Here, dentiling embellishes the bay's cornice board below the overhanging gable. While similarly conceived, this gable end differs from the wide gable that distinguishes the front elevation. The south gable is faced with imbricated shingles and terminates, under the gable peak, in a bracketed panel decorated with narrow bands of wood forming a rectilinear pattern that recalls the box-like design of the frieze that enriches the principal elevation's second floor balcony. A half-oculus window pierces the gable end. The east end of the south elevation is lower in height than the front of the building featuring an overhanging screened sleeping porch under a box cornice on the second floor and a range of four windows piercing the first floor of the facade.

Though proportionally similar to the south elevation, the north side of the building is not as finely appointed. Here too a cross gable roofed center bay projects slightly but it lacks the chamfered walls that distinguish the other projecting bays. The gable end, however, repeats exactly the design of the south gable end. The east extreme of the south facade features a screened sleeping porch on the second floor above a one-story kitchen porch on plain wood posts. Corner boards define the formal planes of the south elevation and its cornice moulding and overhanging roof line cornice also relate it to the other facades of the building. Window details are consistent among all four elevations of the house.

The east facade of the house appears as a gable-roofed arm projecting from the rear of the building and flanked by shed-roofed sleeping porches that appear on the north and south sides of the building. This rear facade is related to the more attractively detailed sides of the building by its corner boards, cornice mouldings, box cornice and Classically detailed window surrounds. A pair of small rectangular windows penetrate the gable end of the roof.

United States Department of the Interior Heritage Conservation and Recreation Service

National Register of Historic Places Inventory—Nomination Form

For HCRS use only received FEB 2 4 1982 date entered

Continuation sheet

Item number

7

Page

The finely crafted woodwork that so enriches the exterior of the Garrison House is reflected in the equally impressive design and wood decoration of its interior spaces. On the first floor three parlor rooms separated by pocket doors with transoms radiate off the entrance foyer that occupies the southwest corner of the house. A spindled frieze appears over the pocket door that leads from the foyer into the front parlor The decorative detailing of the foyer establishes the interior wood craftsmanship exhibited throughout the house which features baseboard mouldings, picture mouldings, and beaded door surrounds with bulls-eye corner blocks that terminate in a crown-shaped element. All interior window frames are articulated in the same fashion as the door surrounds. An extraordinary example of jig-saw cut woodwork occurs in the frieze that spans the double-door opening between the front and rear parlors. This element consists of an array of intertwinning sinuous shapes, foliated forms and some spindlework. The staircase, located in the entrance foyer, also reflects the Eastlake-inspired wood esthetic. It is composed of square beaded balusters with decorative brackets under the banister. Brackets that embellish the staircase profile reiterate the design of these brackets.

A one-story hip roofed wood frame garage is located on the property just east of the house.

8. Significance

Period prehistoric 1400–1499 1500–1599 1600–1699 1700–1799X 1800–1899 1900–	Areas of Significance—C archeology-prehistoric agriculture architecture art commerce communications	community planning conservation economics education engineering exploration/settlement	military music philosophy	religion science sculpture social/ humanitarian theater transportation other (specify)
Specific dates	1895	Builder/Architect	unknown	

Statement of Significance (in one paragraph)

Outstanding among the late-nineteenth and early-twentieth century residences that line Pecan Street, many of which have suffered the loss of their original integrity to alteration and deterioration, the finely crafted and exuberantly decorated Garrison House presents a noteworthy example of the type of dwelling that housed Texarkana's eminent citizens around the turn of the century. Built in 1895 for locally prominent lawyer Augustus M. Garrison, the house represents a period when Texarkana was a new and thriving railroad and lumber center. Displaying the fullest integrity of original fabric on both interior and exterior, the Garrison House presents a pristine example of the esthetically pleasing Queen Anne architecture that distinguished the late Victorian era. The house is especially effective in conveying the decorative aspects of the style. Its pleasantly massed asymmetrical proportions featuring chamfered bay and lofty turret provide an energetic context for the profuse decorative woodwork that embellishes the house. Of particular note are the Eastlakeinfluenced spindles, bands, brackets and shingles that enrich the gable ends of the house, the scroll-bracketed turned porch columns, the scalloped decoration of the porch frieze, and especially the finely cut screen that forms the frieze of the second floor balcony. Cathedral lights and bracketing of the turret enrich the esthetic. Equally impressive is the fluent articulation of the exterior of the house in the consistently fine wood craftsmanship and decoration of the interior spaces, particularly the beaded and bracketed balusters of the staircase, the beaded woodwork of the window and door surrounds, and the brilliant decorative frieze that separates the front and rear parlors. The house is currently the home of Augustus Garrison's son Wayne.

ct. Co 0, P.

9. Major	Bibliographica	al Referen	ces	M NOT VERIFIED
Jennings, <u>Texar</u> Texarkana City Interview with The Daily Texar	we, The History of Mill kana Pioneer Families, T Directories, 1890-1950, Wayne Garrison, 18 Noven kanian (Texarkana, AR-T)	exarkana, Arkansa Texarkana, Arkans ber 1980 (). "Car Injuries	as; 1962, Tex sas; 1890-195	0 Polks Southern Dire
	graphical Data	EXTREME TO THE RESIDENCE OF THE		76 (358) (400) (41)
Acreage of nominate Quadrangle name UMT References	ed property <u>less than 1 ac</u> Texarkana Quadrangle	cre Handing Control	Quadrang	le scale 1:24000
A 1 5 4 0 3 2 Zone Easting	6 6 0 3 6 9 9 1 6 0 Northing	B Zone	Easting	Northing
C		D		
	description and justification Lot 8, Block 22, Origin	nal Town of Texar	kana	
List all states and	d counties for properties ove	rlapping state or cou	ınty boundaries	eng arangan nya masa
state	code	county		code
state	code	county		code
11. Form	Prepared By			
name/title Ethel	Goodstein, Architectura	l Historian	tops for calls	sirovizantes (1600) Supri
organization Arka	nsas Historic Preservat	ion Program dat	e 24 Novemb	per 1980
street & number Su	ite 500, Continental Bu	ilding tele	ephone (501)	371-2763
city or town Lit	tle Rock	sta	te AR	
12. State	e Historic Pres	ervation C	Officer C	ertification
The evaluated signif	icance of this property within the	e state is:		
r	national state	_X_ local		
665), I hereby nomin	tate Historic Preservation Officer ate this property for inclusion in eria and procedures set forth by	the National Register a	nd certify that it h	as been evaluated
State Historic Preser	rvation Officer signature	With	YX	Ly
title JHPC			date	2-16-82
Aller	that this property is included in	the National Register Entered in the National Registe	date	3/25/82
y Keeper of the Natio	onal Register			
Attest: Chief of Registration	n		date	
Office Of Flogiotians				


NATIONAL REGISTER OF HISTORIC PLACES	United States Department of the Inter National Park Service
EVALUATION / RETURN SHEET	820,0212
Property: Garrison, House Augustus M.)	2/2/22-218
Property: Dan Floure Hagasius 1	Working No. 24182-788
State, County: AR, Miller Federal Agency:	Fed. Reg. Date:
rederal Agency.	
resubmission	Action:ACCEPT_3/25/
nomination by person or local government	tional Register REJECT
owner objection	photos 4
appeal	maps
	balla to nortsorbress
Substantive Review:samplerequest	appealNR decision
Reviewer's comments:	
	Recom. / Criteria
	Reviewer
	Discipline
	Date
	see continuation sheet
1. Name	
2. Location	y5 beanserS mad 3y
3. Classification	
Category Ownership Status Present Use	
Public Acquisition Accessible	o and a full residue in any layer for a publicage for the second section of the sect
4. Owner of Property	
5. Location of Legal Description	
6. Representation in Existing Surveys	
	19/00/23
has this property been determined eligible? yes	Taffic of
	Tamin Single On the Contract of the Contract o
7. Description	no sosta son
ondition excellent deteriorated unaitered original site good ruins altered moved date rair unexposed	Tamb 8 9 9 9 9 9 9 9 9 9 9 9 9 9 9 9 9 9 9
Check one Check one excellent deteriorated unaltered original site opposed fair unexposed when the present and original (If known) physical appearance	S. Ciner Nage on Other
7. Description Check one Check one excellent deteriorated unaltered original site original site moved date fair unexposed Summary paragraph	S. Ciner. Nace of the concerning this nominal stand was a concerning this nominal standard was a concerning this nominal was a concerning this concerning
7. Description	State on the content of the contents of the co
7. Description Condition Excellent	S Giner on Concerning this nominal stemed with the concerning this nominal stemed with the concerning this concerning the concerning th
7. Description Condition Check one Check one carcellent deteriorated unattered original site original site and fair unexposed Concribe the present and original (M known) physical appearance summary paragraph completeness Clarity alterations/integrity	Attentions concerning this nominal
7. Description Condition Excellent deteriorated unaltered original site original site altered moved date good ruins altered moved date fair unexposed Describe the present and eriginal (if known) physical appearance summary paragraph completeness clarity	Tanis and San Control of the Control

8. Significance		
Period Areas of Significance—Check and justify below		
Specific dates Builder/Architect Statement of Significance (in one paragraph)		
Control of the second of the s		4
summary paragraph		
completeness		
clarity applicable criteria		
justification of areas checked		
relating significance to the resource		
context		
relationship of integrity to significance		
justification of exception		
other		
fledom, / Criticita	,	
Verbal boundary description and justification 11. Form Prepared By	ib ancaser axifnetadus com	amen 1
12. State Historic Preservation	Officer Certification	
The evaluated significance of this property within the state is:	<u> </u>	
national state local		
State Historic Preservation Officer signature		
title date		
13. Other	lating Surveys	x 3 av 1 av
Maps		
Photographs		
Other		
Questions concerning this nomina	tion may be directed to	
Signed	Date	_ Phone: 202 272 - 3504
olylica	_ Date	_ Filolie. 202 212-3504



Augustus Garrison House
Texarkana, Arkansas Miller County
Bob Dunn, Photographer
May, 1981
Negative at Ark. Hist. Pres. Program
Southwest elevation taken from southwest
Number 1 of 6

FEB 2 4 1982



Augustus Garrison House Texarkana, Arkansas Bob Dunn, Photographer May, 1981 Negative at Ark. Hist. Pres. Program North elevation taken from the northwest Number 2 of 6


FEB 2 4 1982

NW sile



Augustus Garrison House
Texarkana, Arkansas (Miller County)
Bob Dunn, Photographer
May, 1981
Negative at Ark. Hist. Pres. Program
Southeast elevation taken from southeast
Number 3 of 6

FEB 2 4 1982




Augustus Garrison House Texarkana, Arkansas (Miller County) Bob Dunn, Photographer May, 1981 Negative at Ark. Historic Preservation Program Southeast elevation taken from southeast Number 4 of 6

FEB 2 4 1982


East

58



Augustus Garrison House
Texarkana, Arkansas (Miller County)
Bob Dunn, Photographer
May, 1981
Corner of northeast elevation taken from
northeast
Number 5 of 6


FEB 2 4 1982



Augustus Garrison House Texarkana, Arkansas Bob Dunn, Photographer May, 1981 Negative at Arkansas Historic Preservation Program Rear (northeast elevation) Number 6 of 6

FEB 2 4 1982

Non NE





ARKANSAS HISTORIC PRESERVATION PROGRAM

Suite 500, Continental Building · Markham and Main · Little Rock, Arkansas 72201

Phone: (501) 371-2763

February 17, 1982

Ms. Carol D. Shull Acting Keeper of the National Register United States Department of the Interior National Park Service 440 G Street N.W. Washington D.D. 20240

Re: National Register nominations:
Garrison House, Texarkana, Arkansas
Bank of Kingston, Kingston, Arkansas
Terry Block Building, Bentonville, Arkansas

NATIONIA!

Dear Ms. Shull:

We are enclosing for your review three nominations for the National Register of Historic Places. The properties are: Augustus Garrison House, Texarkana, Arkansas; Bank of Kingston, Kingston, Arkansas; Terry Block Building, Bentonville, Arkansas. The Arkansas Historic Preservation Program has complied with all applicable nominating procedures and notification requirements in the nomination process.

I would like to bring to your attention that the Terry Block Building in Bentonville, Arkansas was granted a preliminary certification of significance August 4, 1980 and a preliminary certification of rehabilitation on August 1, 1980.

Thank you for your consideration in this matter.

Sincerely,

Wilson Stiles

State Historic Preservation Officer

Enclosure

WS/js

ENTRIES IN THE NATIONAL REGISTER OF HISTORIC PLACES

STATE ARKANSAS

Date Entered MARCH 25, 1982

Name

Location

Bank of Commerce

El Dorado Union County

Garrison, Augustus M., House

Texarkana Miller County

Notified

Honorable Dale Bumpers Honorable David H. Pryor Honorable Beryl F. Anthony, Jr.

Southwest Regional Office, NPS

State Historic Preservation Officer Mr. Wilson Stiles Director, Arkansas Historic Preservation Program Continental Building, Suite 500 Markham and Main Streets Little Rock, Arkansas 72201