


United States Department of the Interior
National Park Service

National Register of Historic Places Registration Form



This form is for use in nominating or requesting determinations for individual properties and districts. See instructions in *How to Complete the National Register of Historic Places Registration Form* (National Register Bulletin 16A). Complete each item by marking "X" in the appropriate box or by entering the information requested. If any item does not apply to the property being documented, enter "N/A" for "not applicable." For functions, architectural classification, materials, and areas of significance, enter only categories and subcategories from the instructions. Place additional entries and narrative items on continuation sheets (NPS Form 10-900a). Use a typewriter, word processor, or computer, to complete all items.

1. Name of Property

Historic name Henry Owen Shuey House

Other names/site number _____

2. Location

street & number 5218 16th Avenue NE not for publication

city or town Seattle vicinity

State Washington code WA county King code 033 zip code 98105

3. State/Federal Agency Certification

As the designated authority under the National Historic Preservation Act of 1986, as amended, I hereby certify that this nomination request for determination of eligibility meets the documentation standards for registering properties in the National Register of Historic Places and meets the procedural and professional requirements set forth in 36 CFR Part 60. In my opinion, the property meets does not meet the National Register criteria. I recommend that this property be considered significant nationally statewide locally. (See continuation sheet for additional comments.)

[Signature]
Signature of certifying official/Title

10/23/02
Date

State or Federal agency and bureau

In my opinion, the property meets does not meet the National Register criteria. (See continuation sheet for additional comments.)

Signature of certifying official/Title

Date

State or Federal agency and bureau

4. National Park Service Certification

I, hereby, certify that this property is:

- entered in the National Register.
 ___ See continuation sheet
- determined eligible for the National Register.
 ___ See continuation sheet
- determined not eligible for the National Register.
- removed from the National Register.
- other (explain:)

[Signature]
Signature of the Keeper
Edson H. Beall

Date of Action
12-5-02

5. Classification

Ownership of Property

(Check as many boxes as apply)

- private
- public-local
- public-State
- public-Federal

Category of Property

(Check only one box)

- building(s)
- district
- site
- structure
- object

Number of Resources within Property

(Do not incl. previously listed resources in the count.)

Contributing	Non-Contributing	
2	1	buildings
		sites
		structures
		objects
2	1	Total

Name of related multiple property listing:

(Enter "N/A" if property is not part of a multiple property listing.)

Number of contributing resources previously listed in the National Register

6. Functions or Use

Historic Functions

(Enter categories from instructions)

DOMESTIC: Single Dwelling

DOMESTIC: Multiple Dwelling

Current Functions

(Enter categories from instructions)

DOMESTIC: Single Dwelling

7. Description

Architectural Classification

(Enter categories from instructions)

LATE 19TH AND 20TH CENTURY REVIVALS:

Neo-Classical Revival

Materials

(Enter categories from instructions)

foundation Concrete

walls Wood-frame

roof Composition Shingles

other Brick Chimneys

Narrative Description

(Describe the historic and current condition of the property.)

SEE CONTINUATION SHEET

8. Statement of Significance

Applicable National Register Criteria

(Mark "x" in one or more boxes for the criteria qualifying the property for National Register listing.)

Areas of Significance

(Enter categories from instructions)

COMMERCE

ARCHITECTURE

Period of Significance

1908-1918

Significant Dates

1908 (Construction Date)

Significant Person

(Complete if Criterion B is marked above)

Shuey, Henry Owen

Cultural Affiliation

Architect/Builder

Bell, E. S. (Architect)

A Property is associated with events that have made a significant contribution to the broad patterns of our history.

B Property is associated with the lives of persons significant in our past.

C Property embodies the distinctive characteristics of a type, period, or method of construction or represents the work of a master, or possesses high artistic values, or represents a significant and distinguishable entity whose components lack individual distinction.

D Property has yielded, or is likely to yield, information important in prehistory or history.

Criteria Considerations

(Mark "x" in all the boxes that apply.)

Property is:

A owned by a religious institution or used for religious purposes.

B removed from its original location.

C a birthplace or grave.

D a cemetery.

E a reconstructed building, object, or structure.

F a commemorative property.

G less than 50 years old or achieving significance within the past 50 years.

Narrative Statement of Significance

(Explain the significance of the property.) - SEE CONTINUATION SHEET

9. Major Bibliographical References

Bibliography

(Cite the books, articles, and other sources used in preparing this form.) SEE CONTINUATION SHEET

Previous documentation on file (NPS):

- preliminary determination of individual listing (36 CFR 67) has been requested
- previously listed in the National Register
- previously determined eligible by the National Register
- designated a National Historic Landmark
- # _____

Primary location of additional data:

- State Historic Preservation Office
- Other State agency
- Federal agency
- Local government
- University
- Other

Name of repository:

10. Geographical Data

Acreage of Property Less than one acre

UTM References

(Place additional UTM References on a continuation sheet.)

1	<input type="text" value="10"/> Zone	<input type="text" value="5"/> <input type="text" value="51"/> <input type="text" value="865"/> Easting	<input type="text" value="52"/> <input type="text" value="79"/> <input type="text" value="350"/> Northing	3	<input type="text"/> Zone	<input type="text"/> <input type="text"/> <input type="text"/> Easting	<input type="text"/> <input type="text"/> <input type="text"/> Northing
2	<input type="text"/> Zone	<input type="text"/> <input type="text"/> <input type="text"/> Easting	<input type="text"/> <input type="text"/> <input type="text"/> Northing	4	<input type="text"/> Zone	<input type="text"/> <input type="text"/> <input type="text"/> Easting	<input type="text"/> <input type="text"/> <input type="text"/> Northing

Verbal Boundary Description

(Describe the boundaries of the property.) The northern 1/3 of Lots 2 and 3, Block 3, Boren & Denny's Addition to the City of Seattle. Parcel # 093900-0085

Boundary Justification

(Explain why the boundaries were selected.) The boundary includes those sections of Lots 2 and 3 on the SW corner of Third Avenue and Cherry Street historically associated with the hotel building.

11. Form Prepared By

name/title Phillip Seven Esser

organization Historic Preservation Services date June 11, 2002

street & number 318 Terry Avenue North Suite B telephone 206 818 8700

city or town Seattle state WA zip code 98109

Additional Documentation

Submit the following items with the completed form:

Continuation Sheets

Maps

- A **USGS map** (7.5 or 15 minute series) indicating the property's location.
- A **Sketch map** for historic districts and properties having large acreage or numerous resources.

Photographs

Representative **black and white photographs** of the property.

Additional items

(Check with the SHPO or FPO for any additional items.)

Property Owner (Complete this item at the request of the SHPO or FPO.)

name Steven F. Schellings & Rebecca Geisler (Shuey House, LLC)

street & number 5218 16th Avenue NE telephone 206 528-7776

city or town Seattle state WA zip code 98105

United States Department of the Interior
National Park Service

National Register of Historic Places Continuation Sheet - [HENRY OWEN SHUEY HOUSE, SEATTLE, WA]

Section number 7

Page 1 of 8

DESCRIPTION

Built in 1908, the Henry Owen Shuey house is located at 16th Avenue in the heart of the University District in Seattle, Washington. Founded in 1851, the City of Seattle is located on Puget Sound, 113 miles from the U.S.-Canadian border. Seattle is a commercial, cultural and advanced technology hub of the U.S. Pacific Northwest and is a major port city for trans-Pacific and European trade. The greater Seattle area is a leading center for advanced technology in aerospace, computer software, biomedicine, electronics, medical equipment, and environmental engineering. Other major industries include wood products, aircraft, and fish processing.

Setting

The house is located in a residential district, developed in a grid pattern at the crest of a gently rising hilltop in the heart of the University District, just north of the University of Washington campus. The neighborhood is comprised of early twentieth century homes, built closely together with an eclectic range of Colonial Revival, Tudor Revival, Craftsman style, and Neo-Classical styles. The neighborhood's streetscape is richly landscaped with manicured lawns and mature plantings, including large mature trees (*See Photo #2*).

The large, imposing and formal house is the only one in the immediate area that sits on more than one building lot. Built on southernmost portion of a three-lot plot, the house sits up from the street level following the gently upward grade to the east, which is divided by a low, scored concrete retaining wall and metal fence (*See Photo #3*). At the street level is a sidewalk with a grassy planting strip containing three small, evenly spaced, Queen Anne Cherry trees. Concrete steps and a walkway lead to a large concrete staircase at the base of the porch. The northern half of the site contains a lawn area with a garage stylistically similar to the house and a small storage shed. A poured concrete driveway divides the site from the street to the service alley at the east end of the site. Tall wooden fencing in a variety of styles runs the perimeter of the north, east and southern boundaries of the property, with the exception of the southeast corner which contains an indentation with a concrete slab parking area and access to the basement stairs. The east end of the property contains an area with raised decking and a ground level paved brick patio. A classically inspired pergola sits atop the fencing in this area (*See Photo #7*).

United States Department of the Interior
National Park Service

National Register of Historic Places Continuation Sheet - [HENRY OWEN SHUEY HOUSE, SEATTLE, WA]

Section number 7 Page 2 of 8

Architectural Description

Exterior

Designed by architect E.S. Bell for banker H. O. Shuey, the 1908 house is a large, two-story, wood-frame, Neo-classical style single-family residence with a three-bay rectangular plan, hipped roof and a large projecting, classically inspired front porch. The house is sited in a north-south orientation with the west, or primary, elevation facing the street. The poured concrete foundation, punctuated by window wells, is parge-coated with a cement veneer, scored to mimic rectangular, coursed ashlar stone blocks. A water table runs the perimeter of the house. The exterior walls are clapboard sided in cedar with engaged red-brick chimney stacks that terminate above the roof line. All the siding and trim are painted white. The windows are mostly one-over-one, wood-frame double hung sash. Decorative windows include stained-glass panels in the dining room and stair hall, and stylistically similar beveled-glass leaded windows in the front parlor (living room), dining room (dining/family area), and entrance hall. Large overhanging eaves at the roofline, dining room bay window, and northeastern porch area all feature beveled board soffits with elongated modillions (*See Photo #11*). The roof, with large hipped dormers, is covered in composition shingles.

An offset, full-height projecting porch flanked by fluted columns and capitals, crowned by a classical pediment, dominates the asymmetrical west elevation (*See Photo #5*). At the northern half of the first floor porch is a single-panel front door, with an egg and dart trim molding. Flanking the door are decorative beveled-glass leaded sidelights that sit on paneled, pedestal-type moldings. The southern portion of the porch consists of a one-over-one wood-frame double hung sash; the top sash made up of a beveled-glass leaded window. The hollow, two-story, old-growth fir columns are comprised of three pieced sections. An entasis, or slight bulging in the lower middle section, was incorporated into the columns to minimize the optical illusion that occurs with tall columns, creating a "thinning" effect in the middle section. A hollow, cylindrical load-bearing member is contained within the interior space of the column. The Greek Ionic capitals atop the columns are cast plaster, the design modeled on the capitals from the Erechtheion temple in Athens, considered the most important monument of the Greek Ionic style (*See Photo #8*). The raised porch has a painted wood floor and a beaded board ceiling with two brass "lantern"

United States Department of the Interior
National Park Service

National Register of Historic Places Continuation Sheet - [HENRY OWEN SHUEY HOUSE, SEATTLE, WA]

Section number 7 Page 3 of 8

style light fixtures. Italian Renaissance style balustrades run between the columns and the house on either end of the porch, capped by oversized handrails (*See Photo #9*). The second floor of the porch is enclosed by clapboard siding and has a double, one-over-one wood-frame double hung sash. The pediment has a deeply recessed tympanum with a bulls-eye window and a pitched course of composition shingles along the roofline (*See Photo #10*). The southern portion of the remainder of the west elevation consists of a single one-over-one wood-frame double hung sash at each floor level. The first floor window has a beveled-glass leaded window in the upper sash. At the first floor level of the northern portion of the west elevation is a large bay window with a picture window topped by a decorative leaded-glass fixed transom in the central portion. It is flanked by double-hung sash with similarly decorative upper sash. The entire bay is covered by an overhanging eave, the underside of the bay finished in beveled boards. Above the bay window on the second floor level is a paired double-hung sash.

Various-sized windows punctuate the asymmetrical north elevation, all simple double-hung sash (*See Photo #6*). The western section contains a large sash at the first floor and a slightly smaller one offset to the west at the second floor. At the east-central section of the first floor is a triple set of small sash. Above these windows, offset to the east, is a bay window with paired sash flanked by single sash. The underside of the bay contains decorative modillions similar to the eaves. Directly to the west of the bay is a very small sash. The easternmost portion of the elevation contains an integrated porch defined by individual overhanging eaves at both floor levels, distinct from the primary roofline eaves. The first floor level contains a single, double-hung sash, the second level, paired sash. At the roof is a centrally placed hipped dormer with paired sash.

A symmetrical, two-story projecting porch described in the north elevation dominates the northern portion of east elevation (*See Photo #7*). A door-frame, centrally placed at the first floor level, contains two single-light store doors flanked by sidelights. The southern portion of the façade has a triple, double-hung sash, while the northern part has a paired sash with a single store door at the southern end. The second level contains three sets of triple-sash interspersed with and terminated by classically-inspired, recessed panel pilaster moldings. The return section contains paired sash on both levels. Centered with the porch on the roof is a centrally placed hipped dormer with paired sash. The remainder of the southern

United States Department of the Interior
National Park Service

National Register of Historic Places Continuation Sheet - [HENRY OWEN SHUEY HOUSE, SEATTLE, WA]

Section number 7

Page 4 of 8

portion of the east elevation is dominated by an engaged red brick chimney stack, stepped in on the southern side at both the first and second levels, punched through the eave and roof, and terminated by three symmetrical, square, decorative molded concrete chimney caps. To the south of the chimney stack at the first floor level is a fixed, single light, horizontally oriented window protecting stained-glass windows behind. Adjacent to the porch return section and directly north of the chimney stack at the second level is a small double-hung sash.

The south elevation contains elements all stylistically identical to the north and east elevations. The chimney stack on the west end is stepped at the second level and a flanked by sash windows at both levels, except the first floor easternmost, which is a fixed, decorative beveled leaded-glass pane. A bay window at the easternmost end sits atop a paired double-hung sash.

Interior

The single panel front door with decorative sidelights opens to an entrance hall that has a simple paneled dado capped with a bolection mold chair rail, cavetto cornice molding and a large open passage leading to the front parlor (living room) on the south elevation. To the east is the focal point of the entrance hall, a passageway to the stairhall that features carved wooden Ionic columns on pedestals, topped by a broken entablature that is bridged by a flattened elliptical arch (*See Photo #16*). The centerpiece of the arch is a simple keystone with a raised, carved letter "S" (*See Photo #17*). The arch spandrels are made up of recessed panels. The north elevation consists of a small doorway, offset to the east, leading to the dining room (family room).

The front parlor (living room) is a large rectangular room with a nine-section coffered, or boxed beam ceiling with a centrally mounted decorative stained glass hanging light fixture surrounded by four identical smaller fixtures mounted to the beams. The symmetrically placed windows on the south and west elevations all have decorative leaded beveled glass top sash. Centered on the south elevation is a fireplace made up of ashlar cut, rectangular cut stone blocks with rusticated block quoining and mantel course, crowned by a simple dark-stained, classical molding (*See Photo #18*). The east elevation has a large opening with two double-panel pocket doors.

United States Department of the Interior
National Park Service

National Register of Historic Places Continuation Sheet - [HENRY OWEN SHUEY HOUSE, SEATTLE, WA]

Section number 7

Page 5 of 8

The back parlor (dining room) is stylistically similar to the front parlor. Four identical small, glass shade fixtures mounted to the beams surround a centrally placed hanging chandelier. The south elevation consists of a centrally placed, paired double hung sash. The east elevation has a passage door on the north end, a decorative three-section stained-glass window on the south end (*See Photo #22*), and at the center a white-painted, stylistically similar fireplace to the front parlor (*See Photo #21*). The north elevation contains a passage on the west end leading to the stairhall.

The northern portion of the first floor consists of a large open area, which contains the dining room (family room), and a contemporary kitchen. The dining room (family room) is stylistically identical to the front hall with the exception of a two-thirds height dado paneling. The west elevation reflects the bay window projection described in the west elevation exterior description above (*See Photos #23 & 24*). The walls are covered in mid-20th century wallpaper. The rectangular kitchen area to the east consists of a long service island and bank of pantry space on the south elevation. A passage on the eastern portion of the south elevation leads to the basement stairs and an 'L' shaped powder room that runs behind the main staircase.

Running the length of the eastern portion of the first floor from the kitchen to the back parlor (dining room) is a sun room with dark-stained china cabinetry and bar sink on the west elevation, a bank of windows and doors on the east. The northernmost area contains a mud room.

The stairhall is a continuation of the entrance hall with dado paneling running the length of the walls up to the landing and continuing up through to the upstairs passage hall (*See Photos #25 & 26*). At the base of the staircase are two passage doors opposite each other to the north and south, leading to the kitchen and back parlor (dining room). The doorway to the south of the staircase leads to the powder room described above. The staircase consists of a wide flight leading to a wide landing and a smaller reverse flight continuing to the second floor. At the landing is a small fixed door on the north elevation. The stair ends of the return flight are finished in with a simplified, applied scroll pattern, typical of the Georgian and Colonial Revival style. The newel posts are square with recessed panels trimmed with an egg and dart molding and wrapping the post towards the top is a small Greek key molding. The balusters are simple, with Colonial Revival type turnings.

United States Department of the Interior
National Park Service

National Register of Historic Places Continuation Sheet - [HENRY OWEN SHUEY HOUSE, SEATTLE, WA]

Section number 7 Page 6 of 8

The east elevation of the stair hall is dominated by a concave set of five rectangular, identical stained-glass windows set atop a curved, bull-nosed window seat (See *Photo #26*). The majority of the panels consist of Kokomo glass from the famed specialty glass company in Kokomo, Indiana. The window seat has a large radiator grill comprised of wide, interwoven metal strips. The decorative pattern of the polychrome windows consists of a flame atop an elongated pole surrounded by a laurel wreath.

The upstairs hall is 'L' shaped by virtue of the staircase and is oriented to serve the bedrooms to the north and south through the use of Craftsman inspired passageways (See *Photo #27*). The framed passageways feature tapered, square columns on pedestals. Above the dado on the west elevation is a small, paneled access door. On the south end of this elevation is a doorway with a single light transom window. The doorway leads to a bedroom that features a door on the west end leading to the front porch. The south passageway leads to a set of unfinished doors that lead to a small anteroom off which sits a large bedroom to the west and a large bathroom to the east. The bedroom has a single window on the south elevation and a door on the west elevation leading to the porch. A small passage with a closet on the east elevation leads to the large bathroom whose floor is entirely covered in tile. In the projecting bay window area at the south end of the room is a large free-standing contemporary bathtub and on the northern end of the east elevation is a fireplace with a French Rococo style surround. At the north elevation is a separate water closet on the west end and a glass-enclosed shower stall to the east.

The northern passageway in the second floor hallway leads to bedrooms on the northwest and to the northeast, with a bathroom between. A door on the east elevation in the northeast bedroom leads to the porch extension on the east end of the house, connects to a larger room of the porch in which the back portion of the stairhall stained glass windows are placed. A door at the southwest end of the room leads back to the large bathroom described above.

The attic area is accessed through a door adjacent to the north passageway in the upstairs hall. The full staircase opens to a central space that reflects the roof structure above. To the north and south are two bedrooms with headroom provided by the large dormers. On the east end is a small, full bathroom with bathtub. A large storage area in the porch gable is accessed through a small door on the west

United States Department of the Interior
National Park Service

National Register of Historic Places Continuation Sheet - [HENRY OWEN SHUEY HOUSE, SEATTLE, WA]

Section number 7

Page 7 of 8

elevation.

The majority of the basement consists of a series of finished living space, rental rooms with a common kitchen and living area. The service portion of the basement has mechanical equipment room, and a separate storage room.

Evolution

The majority of the exterior of the house remains intact, with some exceptions. On the interior, the majority of the formal rooms remain intact, the most notable changes occurring in the kitchen and back porch areas. The remainder of interior changes have been made to the southern end of the second floor.

The first and most dramatic change to the exterior occurred in 1954-55, when the second floor of the front porch was enclosed. Originally an open-air porch, the area was enclosed by Italian Renaissance balustrades matching those remaining on the first floor (*See Photo #1*). At some point a stylistically similar roofline balustrade was removed from the bay window on the west elevation.

Minor changes over time include the removal and replacement of a "wheel" window in the pediment bulls-eye opening, replacement of numerous interior and exterior light fixtures, removal of bull-nose edges on the concrete front porch steps, and changes to finishes. At some point the north elevation of the entrance hall was altered, a small door put in place of pocket doors, similar to the doors separating the front and back parlors (living/dining room). Over the course of the middle part of the 20th century, walls dividing portions of the interior have been added and removed, serving to divide the large spaces into individual dwelling units.

In 1991 a major attempt to rehabilitate the house was undertaken. From 1991 to 1999, deteriorated areas of the exterior were repaired, especially the eaves on the southeast corner of the house, where extensive water damage from the roof had occurred. Soffit boards and modillions were fabricated to match the originals. The house was completely stripped and repainted. The owner removed and replaced the handrails on the front porch balustrades.

United States Department of the Interior
National Park Service

National Register of Historic Places Continuation Sheet - [HENRY OWEN SHUEY HOUSE, SEATTLE, WA]

Section number 7

Page 8 of 8

The current owners have undertaken significant structural and mechanical upgrades since they purchased the house in 2000. In addition, numerous deteriorated windows were replaced, using care in retaining the original architectural character. Repairs to the inlaid floor perimeter detailing were undertaken as well as the replacement of damaged planks. In the kitchen area an interior chimney was removed, and a new contemporary kitchen was built. New cabinetry, doors and windows were installed in the sun room. Where door and window molding was replaced, care was taken in matching the style consistent with the original moldings. The basement living area was completely remodeled, and the service area includes an all new mechanical equipment room and storage area.

Continuing plans to retain the architectural integrity of the house are underway. For example, the enclosed porch on the west elevation is scheduled to be returned to its original condition, as is the north elevation in the entrance hall, the original doors having been salvaged. The original window wheel in the pediment bulls-eye will be returned after rehabilitation.

United States Department of the Interior
National Park Service

National Register of Historic Places Continuation Sheet - [HENRY OWEN SHUEY HOUSE, SEATTLE, WA]

Section number 8 Page 1 of 6

STATEMENT OF SIGNIFICANCE

The Henry Owen Shuey house is significant under *Criteria B*, due to the role of its developer and occupant in the history of the development of Seattle, Washington. His contributions both before and after his career in Seattle also contribute to the history of the western United States.

The Henry Owen Shuey house is also significant under *Criteria C*, due to the distinctive architectural characteristics of the house and property.

Henry Owen Shuey played a significant role in the growth of Seattle in the late 19th and early 20th centuries as a very successful banker and developer of residential properties. Philanthropic by nature, his success came largely through the trust he engendered with a reputation for integrity. During his career in Seattle, Shuey assisted more than a thousand families in securing reasonable loans with which to purchase or build homes. He built a home for his family in the University District, utilizing two and a half building lots. Unique to the neighborhood, the large, formal Neo-Classical house stands as an excellent example of the period, utilizing elements of the Craftsman style on the interior.

Henry Owen Shuey (1861-1932)

Born in Bainbridge, Indiana on April 29, 1861, Henry Owen Shuey was one of three boys born to Daniel and Nancy Own Shuey. The Shuey family is of French Huguenot descent, some of whom relocated to Germany and emigrated to America in 1734. Henry was raised on a farmstead where his father raised stock and crops. His father died when he was only seven years old, but he remained on the farm with his mother, attending country schools and working on the farmstead. He worked his way through school, attending both Valparaiso University (then the Northern Indiana Normal School) and the Central Indiana Normal College. In 1884 he married Lucina Hestletine (Hessie) Sherrill, a local woman, and soon moved to Kansas where he established a town. The name of town is not known but he is known to have erected a livery stable, hotel, and other first buildings.

In 1888 Shuey relocated to Seattle, working as an insurance salesman for forty dollars a month. He then began selling fire insurance and expanded into loans,

United States Department of the Interior
National Park Service

National Register of Historic Places Continuation Sheet - [HENRY OWEN SHUEY HOUSE, SEATTLE, WA]

Section number 8 Page 2 of 6

building a thriving business. He also became secretary and manager of the Equitable Building, Loan, and Investment Association in 1894. Eventually he worked his way into banking circles establishing himself as a receiver for the Seattle Savings Bank in 1897 and was president of the Home Builders Finance Company. In addition to establishing the H.O. Shuey & Company banking firm and the Bank of Baliard, he was one of the principal organizers of the Citizens National Bank of Seattle, which later obtained a national charter.

Clarence B. Bagley's *History of Seattle* describes the basis for Shueys success as one mans commitment to the welfare of the community as a whole by encouraging saving practices for wage earners, providing easy terms for payment and, as a developer, providing options for home buyers. As a man of considerable means, H.O. Shuey owned a substantial amount of land both in Seattle and within the state. He was in a position to loan money to have a house built by a private contractor on one of his properties, or have it built for the buyer. His business interests included mortgage loans, real estate sales, insurance, rents, collections, and investments, and helped people start businesses of their own.

Details of Shuey's successes are lauded in numerous write-ups of the period. Early in his career he was asked to straighten out a situation in which the secretary of the Home Builders Finance Company had embezzled a large sum of the shareholder's money. He ultimately became president of the firm. In 1903 he was earning over twenty-five thousand dollars per year, and in 1907 it was reported that he had never had a loss or any claim against him. By 1916, after 22 years as president, the Equitable Building, Loan, and Investment Association had never paid investors less than 6% return per year.

H.O. Shuey's philanthropic tendencies were also greatly lauded. His association with numerous charities and organizations shows that his professed commitment to the well-being of the community was not in vain. He was a director of the Young Man's Christian Association (YMCA), and served as a trustee for of the Washington Children's Homefinding Society. A member of the Christian church, he was known to have been instrumental in the building of several mission churches in the city and helped to build numerous churches in the state. He also served as a church elder and held numerous posts in his church. He appears to have had no political ambitions and never held any office.

United States Department of the Interior
National Park Service

National Register of Historic Places Continuation Sheet – [HENRY OWEN SHUEY HOUSE, SEATTLE, WA]

Section number 8 Page 3 of 6

In 1922, thinking he was retiring to Southern California, Shuey quickly became active in Los Angeles, once again developing homes for people with moderate incomes. He was instrumental in forming the Home Builders Finance Company of Los Angeles and served as president for several years. He died on December 16, 1932 from injuries caused by being struck by an automobile while crossing the street in front of his house in Los Angeles.

Shuey's family life is not well-documented. His first wife, Lucina Hesteline Sherrill, was actually a cousin of A.A. and D.T. Denny, the founders of Seattle. Together they had two boys, Charles E. who died at six years old, and Clyde Sherrill, who survived him. He married a second time, in 1925. His wife, Olga Odessa (Williams) Miller had also graduated from Valparaiso University in Indiana. Shuey's brother, Thomas J., came to Seattle in 1906 from Abingdon, Illinois and served as the first full-time minister of the University Christian church in Seattle. His son, R.F. Shuey is listed as cashier for the H.O. Shuey Company in a 1907 biography.

Quoted in a 1916 *Collier's* article, Shuey sums up his life philosophy... "my one ambition has been to help people to build homes and pay for them...It's sort of a religion with me to help a man get a home." Noted Seattle historian Clarence Bagley, in a literary flourish, describes H.O. Shuey's contribution: "He possesses in large measure that enterprising spirit that recognizes no obstacles, which has dominated the west and which has made possible the marvelous development of Seattle."

House and Property

Two permits were issued to H.O. Shuey on August 14th, 1908 to build a two-story frame dwelling, and 18' x 20' garage. Shuey had the house built and lived there with his wife and son until 1917, when he sold the University Park house and moved to the Queen Ann neighborhood. In 1918, he sold the house to S.A. Cardz for \$17,000 in cash, one of the largest real estate transactions in the University District that year.

The house was sold again in 1924 to Robert & Ola D. McClelland. In 1928, after Robert's death, his widow converted the house to a rooming house. While no records of change of use from a single-family residence to a duplex are recorded until 1967, tax records from the 1930s identify the house as a two-story rooming house. In

United States Department of the Interior
National Park Service

National Register of Historic Places Continuation Sheet – [HENRY OWEN SHUEY HOUSE, SEATTLE, WA]

Section number 8 Page 4 of 6

1952, the house was sold to Flora C. Brown, who continued to use it as a rooming house. In 1971, the house was purchased by Ralph Patrick, who was issued a permit to alter the basement unit that same year. From 1973 to 1980 the house was owned by Russell Bucklin, and from 1981 to 1991, owned by Eileen Shaw. In 1991, Dave and Sheri Berglund purchased the house, utilizing the space as a Christian boarding house and undertaking the first serious rehabilitation. The house was sold to the current owners, Steve Schellings and Rebecca Geisler, who live there with their two sons. The house remains a boarding house, but is limited to the basement and the attic, which is utilized as a bed and breakfast.

The fact that the house sits on more than two building lots, only one of a few to do so in the University Park neighborhood, is indicative of the resources of H.O. Shuey. The large, imposing house is by far the most formal and grandiose amidst its more restrained architectural neighbors. The stylistically similar garage, and driveway cutting through the wide property to the back alley speaks to the importance of the owner as someone special, someone of means. Interestingly, however, it is known that Shuey could have afforded a far more expensive and elaborate home by 1908. Despite its stance, the house is restrained and not overly showy. It reflects the values of a self-made man who was grounded in moral values and yet well-educated enough to want to express himself through a tasteful, traditional design. It can be argued that it is the perfect bankers home – tasteful and well-appointed, but not garish or wasteful. The house was featured in Frank Calvert's 1913 publication, "Homes of the Pacific Coast."

The most typical aspect of the Neo-Classical style in the design of the exterior of the house is the full-height central entry porch that does not encompass the entire façade. Other common elements of the style found on the house are bay windows, bay window roof balustrade (removed), and an oculus window. Classical decorative elements include a pediment supported by classical columns, Italian Renaissance balustrades, dentil moldings, modillion brackets, paneled pilasters, a perimeter frieze above the first floor and a full entablature at the roof line.

The architectural expression of the interior is primarily a hybrid mix of Neo-Classicism and Craftsman styles. In plan, the first floor reflects more of a 19th century pattern with the placement of the more traditional front and back parlors (living and dining rooms), divided by a large opening with doors. Elements of Neo-

United States Department of the Interior
National Park Service

National Register of Historic Places Continuation Sheet - [HENRY OWEN SHUEY HOUSE, SEATTLE, WA]

Section number 8

Page 5 of 6

Classicism in the design are include the carved classical columns on pedestals in the entrance hall, egg and dart moldings, and decorative stained glass and beveled-glass window panels. The Craftsman style is evident in the plain, dark-stained dado paneling, three-quarter height paneling in the dining room (dining/family room area), dark-stained coffered, or box beam ceilings in the front and back parlors (living and dining rooms), and tapered square-column passages on the second floor. Common to the formal living areas of the interior is fir flooring with repeating perimeter inlay in polychrome hardwoods, dark stained woodwork, egg & dart trim moldings, tall ceilings, and smooth textured, painted walls. The most important interior spaces retain an unusual amount of original fabric and have weathered numerous changes while retaining its most significant interpretive, historic qualities.

University District

The house sits in the most upscale residential neighborhood in the University District. Home to the University of Washington since 1895, it is located in the northeast section of the city, north of the Portage Bay part of Lake Union. Its major developments were spurred on by developer James Moore (1861-1929), the 1895 move of the Territorial University from downtown to what was then called Brooklyn, and the Alaska-Yukon-Pacific Exposition on the University of Washington campus in 1909. In recent years, the downtown area has been threatened by the development of nearby malls. It is a neighborhood of restaurants, cafes, a renowned street fair, and a farmer's market. Significant landmarks include the University Book Store, University Inn, and the Meany Hotel.

In 1890, Harry Cowan, a specialist in clearing townsites, cleared 100 acres of what would become the University district for developer James Moore. The district streets were graded and lots sold quickly. In the spring of 1891, the state legislature's campus committee had recommended section 16 as the new home for the University, which at the time was located in downtown Seattle. Not originally incorporated within the city of Seattle, the inhabitants of the new development voted to join the city on May 4, 1891. While the expansion did not include Ballard, Laurelhurst, and part of Ravenna, it more than doubled the territory of Seattle.

By 1906, it was clear that the University of Washington campus would be the chosen location for the Alaska-Yukon-Pacific Exposition, This provided a tremendous impetus

United States Department of the Interior
National Park Service

National Register of Historic Places Continuation Sheet - [HENRY OWEN SHUEY HOUSE, SEATTLE, WA]

Section number 8

Page 6 of 6

for development of the district and the city as a whole. Seattle had grown more than five-fold by 1910, mostly to the north in the direction of the University District. The University Park Addition was platted by Charles Moore in 1906. A scheme to boost to the development of the University District was the brainchild of English-born capitalist Charles Cowen. Cowen spurred on efforts at cleaning up the appearance of the district, in anticipation of the expected millions of visitors to the Exhibition.

The 1908, No-Classical style Henry Owen Shuey house retains a high degree of historic as well as architectural integrity. The role it played was short-lived, but remains as a testament to the man who played such a significant role in providing affordable homes to so many people. The house retains the unique characteristics of the combination of prevailing period styles and reflects the nature of the man who built it. The house represents the involvement of a significant man who contributed to the history of the United States by being important participant in the development of the City of Seattle.

United States Department of the Interior
National Park Service

National Register of Historic Places Continuation Sheet - [HENRY OWEN SHUEY HOUSE, SEATTLE, WA]

Section number _____

Page 1 of 3

BIBLIOGRAPHY

- Bagley, Clarence. *History of Washington*. Chicago: S. J. Clark Publishing Company, 1916.
- Chappelle, Robert. "The Shuey Mansion." Special Project, Environmental Science. University of Washington, Seattle, 1994.
- Chauncey, Joseph. "Schellings Residence: As Built Drawings," Architectural Drawings. Seattle, Washington: Boxwood Architectural Firm, 23 May, 2001.
- City of Seattle. "Inspector of Buildings Building Permit." Permit # 64743 & 67545. Department of Construction and Land Use, August 14, 1908.
- David Berglund. Phone Interview. Edited by Phillip S. Esser. Seattle, Washington, June 7, 2002.
- Dorpat, Paul. "University District -- Thumbnail History." In History Link. <http://www.historylink.org/output.CFM?file_ID=3380>. 18 June (updated May 2002) 2001.
- "Ex-Banker's Rites to Be Tomorrow." *Los Angeles Times*, 19 December 1932, 14.
- Garrett, Elisabeth Donaghy. *At Home: The American Family 1750-1870*. New York: Harry N. Abrams, Incorporated, 1990.
- Greg Lundgren. Designer, Seattle Stained Glass. Edited by Phillip S. Esser. Seattle, Washington, June 11, 2002.
- Harris, Cyril M. *Illustrated Dictionary of Historic Architecture*. New York: Dover Books, 1977.

United States Department of the Interior
National Park Service

National Register of Historic Places Continuation Sheet - [HENRY OWEN SHUEY HOUSE, SEATTLE, WA]

Section number _____

Page 2 of 3

"Henry Owen Shuey." In *Representative Citizens of the City of Seattle and County of King*, 146-48. New York & Chicago: The Lewis Publishing Company, 1903.

"Henry Owen Shuey." In *California of the South: A History*, 457-59. Los Angeles: S.J. Clarke Publishing Co., Inc., 1933.

King County Assessor. "Property Assessment." 882390-0620, Property Records and Research. Puget Sound Regional Archives. Bellevue, Washington, 1937-1973.

King County Department of Assessments. "Lot Map," Parcel # 882390-0620. Seattle, Washington, June 4, 2002.

_____. "Real Property Characteristics Parcel # 882390-0620." Property Tax Assessment. Seattle, Washington, June 4, 2002.

McAlester, Virginia and Lee. *A Field Guide to American Houses*. New York: Alfred A. Knopf, Inc., 1994.

"Nelle G. Shuey." *Seattle Times*, 27 August 1963.

Phillips, Steven J. *Old House Dictionary: An Illustrated Guide to American Domestic Architecture 1600-1940*. Lakewood, Colorado: The Preservation Press (National Trust for Historic Preservation), 1994.

"Shuey, Henry Owen." In *Sketches of Washingtonians*, 278-79. Seattle, Washington: Wellington C. Wolfe & Co., 1907.

Tobin, Carol. *Buildings Considered for University District Historic Inventory (Draft)*. Inventory. Seattle, Washington, 2002.

United States Department of the Interior
National Park Service

National Register of Historic Places Continuation Sheet - [HENRY OWEN SHUEY HOUSE, SEATTLE, WA]

Section number _____

Page 3 of 3

_____. *Historic Property Inventory Form*. Henry Owen Shuey House. Seattle, WA: State Office of Archaeology and Historic Preservation, Washington, 2002.

United States Geological Survey. *Seattle North Washington*. United States Department of the Interior, 1983.

United States Department of the Interior
National Park Service

National Register of Historic Places Continuation Sheet - [HENRY OWEN SHUEY HOUSE, SEATTLE, WA]

Section number _____

Page 1 of 1

ADDITIONAL DOCUMENTATION


Photographs

Photographs #2-27 listed below were taken by Phillip S. Esser on May 22, 2002. A 35mm camera was used and the black & white negatives are with the owners.


Historic photograph #1 was taken in 1938 and was provided by Puget Sound Regional Archives, Bellevue, Washington.

- 1) Historic Photograph - View from west
- 2) Context - View from northwest
- 3) House & Property - View from southwest
- 4) House & Property - View from northwest
- 5) North & west elevations - View from northwest
- 6) North elevation - View from north
- 7) South & east elevations - View from southeast
- 8) Porch column detail, west elevation - View from southwest
- 9) Porch column & balustrade detail, west elevation - View from northwest
- 10) Pediment detail, west elevation - View from west
- 11) Eaves detail, north elevation - View from east
- 12) Chimney detail, east elevation - View from southwest
- 13) Garage, south & west elevations - View from southwest
- 14) Entrance hall, west elevation - View to northwest
- 15) View from front parlor (living room) to entrance hall - View to northeast
- 16) Entrance hall, east elevation - View to east
- 17) Passage detail, entrance hall, east elevation - View to east
- 18) Front parlor (living room) south & west elevations - View to southwest
- 19) Front parlor (living room) south & east elevations - View to southeast
- 20) Back parlor (dining room) south & west elevations - View to southwest
- 21) Back parlor (dining room), fireplace detail, east elevation - View to northeast
- 22) Back parlor (dining room), stained-glass detail, east elevation - View to east
- 23) Dining room (family room), north, west and south elevations - View to west
- 24) Dining room (family room), beveled glass detail, west elevation, View to SW
- 25) Stair hall, east elevation - View to east
- 26) Second floor stair hall, east elevation - View to east
- 27) Second floor hall - View to south

5218 16th Avenue NE Seattle, WA




Microsoft Expedia
0 ml 0.2 0.4 0.6 0.8
Streets98



H. O. Shuey House
 5218 16th Avenue NE
 Seattle
 King County, Washington

Easting: 5 51 ~~66~~ 865
Northing: 52 79 350



SEATTLE NORTH, WASHINGTON
N4737.5—W12215/7.5X15

1983

80'
40'
78'
76'
75000'N
47°37'30"

THE INFORMATION CONTAINED HEREIN IS FOR YOUR INFORMATION ONLY AND IS NOT TO BE USED FOR ANY OTHER PURPOSE.

H. O. Shuey House

5218 16th Avenue


Seattle, WA


University Park Addition

Block: 4


Lots: 35 FT N 23, 24-25

Parcel # 882390-0620






KING COUNTY DEPT. OF ASSESSMENTS



N.E. 52ND ST.

N.E. 52ND ST.



N.E. 52ND ST.


N.E. 52ND ST.

University Park.

ADDITION TO THE CITY OF SEATTLE

Scale: 1"=100'

C.M. ANDERSON ENGINEERING CO.



DESCRIPTION

This plot of University Park Addition to the City of Seattle, occupies the west one-half (1/2) of the south west quarter (1/4) of Section nine (9) Township twenty-five (25) North of Range four (4) east, Willamette Meridian, King County, Wash.

The width of all Avenues, Streets, Alleys, and the dimensions of all lots are as shown upon the map in fact.

The initial point is the South West Corner of Section Nine (9) Township Twenty-five (25) North of Range Four (4) East, from which the South-west corner of Block One (1) is north (along the West line of this tract), thirty-five (35) feet, and east (parallel with the south line of this tract) twenty-five (25) feet.

All courses refer to the City Standard Meridian.

Stone Monuments are set at street intersections shown thus —

DEDICATION

Know all men by these presents, That the Moore Investment Co. a corporation duly organized and existing under the laws of the State of Washington, and having its principal place of business in the City of Seattle, owners in its entirety of the described tract, does hereby declare this plot of University Park Addition to the City of Seattle, and hereby dedicates to the use of the public, forever, all the Avenues, Streets and alleys shown hereon.

In witness whereof said corporation has caused its name to be subscribed and corporate seal affixed by its Manager, this 15th day of September, 1906.

Signed and sealed
In presence of:—
C.M. Anderson
N.W. Jordan



Moore Investment Company
By James A. Moore
Its Manager.

ACKNOWLEDGMENT

State of Washington } S.S.
County of King }

On this 15th day of September, A.D. 1906, before me personally appeared James A. Moore, to me known to be the Manager of the corporation that executed the within and foregoing instrument, and acknowledged the said instrument to be the free and voluntary act and deed of said corporation, for the uses and purposes therein mentioned, and on oath stated that he was authorized to execute said instrument and that the seal affixed is the corporate seal of said corporation.

In witness whereof I have hereunto set my hand and affixed my official seal the day and year in this certificate first above written.



M.R. Wood
Notary Public in and for the State of
Washington, residing in Seattle.

Examined and approved this 20 day of September, A.D. 1906.
R.H. Thomson
City Engineer.

Approved by Ordinance No 14235 of the City of Seattle,
Approved by me the 20th day of September 1906




W.H. Hickman Moore
Mayor
Attest H.W. Carroll
City Comptroller and Ex-Officio City Clerk
By E.W. Melbe Deputy.

STATE UNIVERSITY GROUNDS

422674

Filed for record at request of James A. Moore
Sep. 28, 1906, at 4:21 P.M. and recorded in
Vol. 13 of Plats page 65, Records of King
County, Washington.

By J.P. Agnew
County Auditor
Deputy Recorder




SITE PLAN
Scale: 1" = 10'-0"



H. O. Shuey House
5218 16th Avenue
Seattle, WA

NOT TO SCALE




H. O. Shuey House
 5218 16th Avenue
 Seattle, WA



FIRST FLOOR PLAN

SCALE: 1/4" = 1'-0"

NOT TO SCALE




SECOND FLOOR PLAN

SCALE: 1/4" = 1'-0"

H. O. Shuey House
 5218 16th Avenue
 Seattle, WA

NOT TO SCALE



H. O. Shuey House
 5218 16th Avenue
 Seattle, WA

THIRD FLOOR PLAN
 Scale: 1/4" = 1'-0"



NOT TO SCALE



NORTH ELEVATION

SCALE: 1/4" = 1'-0"


LOCATION OF ORIGINAL WINDOW OPENINGS

LOCATION OF ORIGINAL WINDOW OPENINGS

DEMO EXISTING ENCLOSURE AND ADD RAIL.

H. O. Shuey House
5218 16th Avenue
Seattle, WA

NOT TO SCALE



BUILDING SECTION
Scale: 1/4" = 1'-0"

H. O. Shuey House

5218 16th Avenue
Seattle, WA


NOT TO SCALE



A. O. Shney

Residence of Mr. H. O. Shuey

5218 Sixteenth Avenue Northeast



MODERN type of colonial architecture is seen in the home of Mr. Shuey. ¶ It is a finely constructed house, and with the broad pillared porch carrying the balcony of the second floor, and great width of the house proper, has an air of strength and dignity. ¶ The interior is beautifully furnished, and is finished in selected native fir. ¶ It was designed by Mr. E. S. Bell. ¶ It is one of the best homes in this section of Seattle, and is an example of the many fine dwellings being constructed throughout the city by the owner.