United States Department of the Interior National Park Service

National Register of Historic Places Inventory—Nomination Form

For NPS use only

received AUG | 4 |985 date entered SEP | 2 |985

See instructions in *How to Complete National Register Forms* Type all entries—complete applicable sections

1. Name

historic	Stoner, Lycurgus	s, House					
and or common	Edna Brown House						
2. Loca	tion						
street & number	Manhattan Road,	North of 550 South	Road N/A	not for publication			
city, town	Greencastle	X vicinity of					
state	Indiana co	de 018 county	Putnam	code 133			
3. Class	sification						
Category district X building(s) structure site object	Ownership public _X_ private both Public Acquisition in process being considered N/A	Status X occupied unoccupied work in progress Accessible yes: restricted yes: unrestricted no	Present Use agriculture X commercial educational entertainment government industrial military	museum park private residence religious scientific transportation other:			
4. Own	er of Prope	erty					
name	H. Wayne and	Paula E. Mark					
street & number	R. 3, Box 588	· · · · · · · · · · · · · · · · · · ·					
city, town	Greencastle	X vicinity of	state I	ndiana 46135			
5. Loca	tion of Leg	al Descripti	on				
courthouse, regis	try of deeds, etc.	Putnam County Courtho	useRecorder's Office	, deed			
street & number							
city, town	6	Greencastle	state	Indiana			
6. Repr	esentation	in Existing	Surveys				
	listoric Sites and / #133-530-45003		operty been determined eligit	ole?yes _Xno			
date	April, 1982		federal state	county local			
depository for su	r vey records Indiana	Department of Natur	ral Resources				
city, town	Indiana	polis	state	Indiana			

.

7. Description

Condition			
excelle	ent		deteriorate
X good	1	# 1 C	ruins

fair

	Check one		
deteriorated	unaltered		
ruins	X altered		
unexposed			

Check one _____ original site ____ moved date _ ٠

Describe the present and original (if known) physical appearance

The Stoner House is located on a one acre lot which was originally part of a large farm. The residence is a large $2\frac{1}{2}$ story vernacular structure with Eastlake and Italianate elements. Irregular in plan, the bevel-sided structure has six gables which intersect the main roof. A one story gable roofed area is located on the rear of the structure. The house rests on a stone foundation.

Facing west, the main facade (Photos #2 and #3) is four bays wide and has a projecting gable on the north end. A one story porch fronts the remaining facade, which contains three bays, the main entry and two windows. The entry is positioned in the innermost bay and has a single leaf door with a glass panel above and decorative wood below. Above the door is a rectangular transom surmounted by a pedimented head which outlines a triangular. form above the opening, with a bullseye at the apex and ornamental blocks at the corners. The original brass doorbell is still functional (Photo #5). The windows are double-hung sash with single lights and wood surrounds and sills. Each window is surmounted by a pedimented window head identical to the one above the main door. All windows are of this design. The front porch has a shed roof supported by four round posts which rest on square piers. It is probably a replacement of the original porch. Above the porch, the second level has three windows aligned with the lower level bays. The projecting gable on the north end of the main facade has a window centered on each of the first two levels. Above the second level windows are two gabled attic areas; one is in the projecting gable and the other is above the two southernmost windows. Each gable is covered with diagonally-laid wood forming triangles flanking a diamond. A shuttered opening with the same surrounds as the other exterior bays is centered in each gable. A cornice follows the rake of the gable and the gable returns, with ornate scroll brackets below each. The cornice continues around the eaves. The main facade has a wood water table which extends around the exterior and wood corner board which are repeated on the other facades.


The south side facade (Photo #1) has a two-bay wide porch flanked by a projecting gable on the west end and a one-story rear section. The porch has a shed roof supported by narrow posts. It shelters an entry and a window, which are framed by decorative engaged wood posts, probably evidence of the original porch's appearance. The door is identical to the main entry. Above the porch, the second level has two windows aligned with the main level bays. The projecting gabled area on the west end has a decorated, three-sided bay window on the main level; it contains three windows surmounted by a plain frieze with ornate scroll brackets which support a molded cornice. A wood panel is below each window. Above the projecting bay a window is centered on the second level. The gabled attic area is identical to those on the main facade except for a small centered window. The rear section has three bays. A door identical to the other doors is positioned offcenter in the middle bay, flanked by two windows.

The north side facade (Photo #2) has three windows on the first two levels with two gabled attic areas identical to those on the main exterior.

The rear facade also has a gabled attic area. A large porch is located on the north end of the rear exterior.

The structure has a tin roof which has been resurfaced with a black roofing compound. Originally, there were four chimneys; two remain. One of the chimneys is brick and is positioned on the ridge of the south gable of the main facade. The other is located at the east end of the same ridge.

8. Significance



Statement of Significance (in one paragraph)

The Lycurgus Stoner House is significant as a fine example of a composite style Victorian farm house. The house combines the bracketed eaves, projecting bay windows, and round-arched fireplaces of the Italianate style, with decorative detailing on window heads and interior woodwork that is more in the Eastlake mode. Except for alterations to the porches, the house has exceptional integrity both inside and out, and as such is one of the finest rural homes in the county.

Lycurgus Stoner returned home after serving in the Indiana Volunteer Infantry in the Civil War, and purchased a tract of bottom land on Big Walnut Creek, as well as the land upon which this house stands. He married Elvira Boone in 1867, and together they had eight children. Stoner had the house built in 1883-84.

Lycurgus and his brother, Peter, operated a successful partnership involving farming and livestock breeding for 28 years. In addition, Lycurgus was a director of the First National Bank of Greencastle for several years.

The Stoners' daughter, Maude, married Edward Houck, and they purchased her parents' home in 1916. The house remained in the family until 1942. Louis H. and Hildegarde H. Dirks owned the property from 1943 until 1960, when it was sold to Edna A. Brown. The present owners purchased it from her estate in 1984.

Rated "Outstanding" in the Putnam County survey, the house is presently used as an antique shop.

· 7

9. Major Bibliographical References

- 1. History of Putnam County, Indiana. Weik, 1910. B. F. Bowens & Co., Publisher. Indianapolis.
- 2. Putnam County History, Indiana Sesquicentennial. 1966. No publisher listed.


10. Geographical Data

Acreage of nominated property <u>One acre</u> Quadrangle name <u>Reelsville</u>	Quadrangle scale 1:24000		
UT M References			
A 1 6 5 0 7 3 9 0 4 3 8 1 3 7 0 Zone Easting Northing	B	Northing	
	FLI		
G			
Verbal boundary description and justification	:	· · ·	

Please see continuation sheet

	nd counties for prope	rties ove	rlapping state	or county bou	ndaries
state N/A		code	county	·····	code
state		code	county		code
11. Form	n Prepareo	l By			
name/title	Paula E. Mark				
organization	N/A		· . •	date	January 28, 1985
street & number	R. 3, Box 588			telephone	317/653-5600
city or town	Greencastle			state	Indiana 46135
12. Stat	te Historic	within the			er Certificatior
12. Stat	nificance of this property national s State Historic Preservat	within the late ion Officer iclusion in	e state is: X local r for the National the National Rec the National Pa	Historic Preserr gister and certify rk Service.	vation Act of 1966 (Public Law 89- v that it has been evaluated
12. State The evaluated sign As the designated 665), I hereby nom according to the ci State Historic Pres	nificance of this property national s State Historic Preservat inate this property for ir	within the tate ion Officer iclusion in et forth by re	e state is: X local for the National the National Reg the National Par	Historic Preservister and certify	vation Act of 1966 (Public Law 89- v that it has been evaluated
12. Stat The evaluated sign As the designated 665), I hereby nom according to the cr State Historic Pres title Indiana	nificance of this property nationals State Historic Preservat inate this property for ir riteria and procedures s servation Officer signatu State Historic Pre	within the tate ion Officer iclusion in et forth by re eservati	e state is: X local for the National the National Reg the National Par on Officer the National Reg	Historic Preser gister and certify rk Service.	vation Act of 1966 (Public Law 89- that it has been evaluated that it has been evaluated that 7-24-85
12. Stat The evaluated sign As the designated 665), I hereby nom according to the cri State Historic Pres title Indiana For NPS use on I hereby cert	nificance of this property nationals State Historic Preservat inate this property for ir riteria and procedures s servation Officer signatu State Historic Pre-	within the tate ion Officer iclusion in et forth by re eservati	e state is: X local for the National the National Reg the National Par on Officer	Historic Preser gister and certify rk Service.	vation Act of 1966 (Public Law 89- that it has been evaluated

National Register of Historic Places Inventory—Nomination Form



OMB No. 1024-0018

Expires 10-31-87

Continuation sheet	Stoner House	Item number	7 and 10	Page 1
--------------------	--------------	-------------	----------	--------

Inside the main entry is an L-shaped foyer; it is six feet wide and runs 19 feet, turning north for an additional 17 feet. The foyer has two pairs of top hung pocket doors which open into the parlor on the north side and the music room on the south side (Photo #6). Single doors in the foyer lead to the dining room, a bedroom, and a closet.

The open, curved floating stairway makes its ascent where the foyer turns north (Photo #7). The second floor foyer opens into five bedrooms and a back stairway, which leads down to the kitchen. A bathroom was installed at the base of the back stairs approximately 20 years ago and is in poor condition.

Handsome, wormy chestnut woodwork adorns all of the downstairs rooms, except the work room, and the second level foyer. Most of the woodwork has never been painted and is in good condition. The woodwork on the first level has a different design in each room; for example, the music room has a lyre design over each window and door frame (Photo #8). The walls and ceilings are plaster and the floors are poplar, with some evidence of settling. A metal fireplace in the music room is functional, while the fireplace in the dining room has been closed up. Both fireplaces were painted to resemble marble (Photos #9 and #10). The house was originally illuminated with carbide light, but was electrified when power was brought to the area.

Originally, a detached summer kitchen stood at the northeast corner of the house. Its footings were removed about four years ago. A small shed still remains on the property.

Item No. 10

Beginning at a point 251.95 feet North and 152.23 feet East of the Southwest corner of the Southeast quarter of the Northwest quarter of Section 12, Township 13 North, Range 5 West which point of beginning is on the East right-of-way line of the Greencastle-Manhattan Road; thence from said point of beginning North 24°40 minutes East 183.24 feet with said East right-of-way line; thence leaving said East right-of-way line South 69° 29 minutes East 205.87 feet; thence South 21° 12 minutes West 109.90 feet; thence South 25° 20 minutes West 75.04 feet; thence North 86° 57 minutes West 62.57 feet; thence South 87° 20 minutes West 53.36 feet; thence North 65° 47 minutes West 43.06 feet; thence North 36° 25 minutes West 71.36 feet to the point of beginning, containing 1.00 acre, more or less.