1, Historic Name (s)		22. ADD/County	
Yenowine- Kennedy House Original Owner		Jefferson/Jef:	ferson
		23. Zoning Classification	
Present Name		Magisterial District 2	
Kennedy House		24. U.S.G. S. Quadrant (15'/75')	
3. Owner's Name		Jeffersontown	
John Kennedy, William Kennedy		25, UTM, Reference	
4. Owner's Address		1   .	10 421210171210
P.O. Box 18081 Louisville KY		16 62226	
5. Location S. Side Taylorsville Rd		Zone Eastin 26. Prehistoric Site	Northing Object
		Historic Site	Structure
4420 Taylorsville Rd., 7/10 mi 6. Open to Public 7. Visible from road	8. Ownership	•	Structure
Yes No X Yes X No	Private	Building X  27. District Yes	No X
9. Local Contact/OrganizationJefferson Count		Name:	NO 22
Office of Historic Preservation	- : : : : : : : : : : : : : : : : : : :	Name.	
Office of miscorne ficaetacte	Federal	29 Significance Evoluction	
10. Site Plan with North Arrow B37 L12	11. Architect	28. Significance Evaluation	<b>`</b>
المواد المسادات والمراج والماكون المناب المناب والمناب	11. Architect	29. Status	D-4-
Taylotaville Rd.	12. Builder	· ·	Date
	12. Builder	National Landmark	
The second secon	12 Days	National Register	
	2nd 1/2 19th century	Landmark Certificate  Kentucky Survey	1977
	<del></del>		1
	14. Style	Local Landmark	
	15. Original Use	HABS/HAER	1
	Residence	30. Theme Archit	ecture
	16. Present Use	Primary <u>ATCIII U</u> Secondary	
	Residence	Other	
3 3 3	17. Condition	31. Endangered	Yes
se boundary description, page	[	31. Endengered	No
nree, and attached aerial photo	Exterior GOOd	32.	NO
		32.	
18. DescriptionFour-bay, as metrical brick I house. One story pedimented porch over front entry. Brick			
			ATTACH
cornice, 3-course jack arches. One story will.		Į	PHOTO
Interior end chimneys. Interior: chair rails, matching parlor mantles, 2 rear door-transoms.		·	
Early 1860 changes: Entry hall and stairs and a			
small room made from one of the two downstairs			
rooms. Also the first room of the will added		'	
which had no entry from main block. (NEXT PAGE)  19. HistoryAlexander Kennedy(1841-1926) purchased this			
house ca.1863. Mambers of the Kennedy family state that the house was built ca.1835 by Seabolt			
for one of the Kennedys. (Alexander Kennedy married			
Josephine Seabolt in 1862). I	<b>T</b>		
gests that the house was built		Roll No.	
Yenowine Kennedy by her father		1	
Amanda Yenowine married John M		Direction	<del></del>
After Amanda's death, it was s	Old by ner(NEXT PAG.		No service No.
This house is signific	ant og the only	33. Tape No.	Negative No.
		34. Prepared by:	
asymmetrical four-bay brick house in the		Carol B. Tobe,	Researcher
county. The original plan was unique			
and the alterations that were made around mid contury do not datract from the in-		35. Organization Teffers	on County
tegrity of the house.			storic Preservatio
		36. Date 5 September	
21. Source of Information Louisvilte Chancery Ct. #17925		37, Revision Dates	38. Staff Review
Louisville Times Jan. 5, 1959, Sec 1			
History Ohio Falls Cities and	Their Counties,	1	
See Next Page	·		

JUL 1 1980

### 18. Continued

Front entry enlarged-panelled door with oval molding forms.

# 19. Continued

husband to his brother Alexander Kennedy. Alexander was one of the five children of John Kennedy, a pioneer from Maryland. He was a farmer who raised Jersey cattle. Alexander's children, John, and twins Florence and Nettie were born in the house and the sisters lived there until their deaths. The house remains in the Kennedy family. A nearby Elementary School is named for Alexander Kennedy.

#### 20. Continued

Alexander Kennedy was from a pioneer family and was a wellknown farmer in the area. The nearby Alex R. Kennedy Elementary School honors him.

## 21. Continued

Federick Papers Jobsob-History of Early Jefferson and Southeastern Jefferson County Jefferson County Deed Books William Kennedy, Michael Kennedy

# Additional Information Requested by NPS

JF-222 Yenowine-Kennedy House 4220 Taylorsville Road


October 26, 1982


The Yenowine-Kennedy house is a four-bay, two-story, brick I house with a one-story, tetrastyle porch. The original plan (according to family oral history) was apparently a hall-parlor plan with two rooms on each story. There is no discernible trace of an earlier staircase. In the 1860s, after purchasing the house from his brother, Alexander Kennedy is believed to have built a dividing wall and stairway in one of the first-story rooms, thus creating an entrance hall and a smaller room. He also added the first room of the one-story ell, but did not cut a door from the main block. Access to this ell was from a rear porch. At the same time Kennedy lengthened the main doorway to accomodate a taller, paneled door.

The original hall-parlor plan of the Kennedy house is not often found in Jefferson County houses. The center-passage I - house was a more papular building style in the nineteenth century. Although the current floor plan is center-passage plan, the asymmetrical, four-bay facade is evidence of the original hall-parlor plan. See attached sketch plan.

# Boundary Description

The boundary of the Yenowine-Kennedy house nomination is shown as a red line on the attached aerial photo. (SCALE: 1" = 200') The nominated site contains approximately 5725 sq. ft. and includes the house. There are no significant outbuildings.





First story after 1860s Changes

