

RECEIVED 2280

OCT 17 2000

RECEIVED
FEB 2 2000

United States Department of the Interior
National Park Service

REGISTER OF HISTORIC PLACES
NATIONAL PARK SERVICE

1292

National Register of Historic Places Registration Form

This form is for use in nominating or requesting determinations for individual properties and districts. See instructions in *How to Complete the National Register of Historic Places Registration Form* (National Register Bulletin 16A). Complete each item by marking "x" in the appropriate box or by entering the information requested. If an item does not apply to the property being documented, enter "N/A" for "not applicable." For functions, architectural classification, materials, and areas of significance, enter only categories and subcategories from the instructions. Place additional entries and narrative items on continuation sheets (NPS Form 10-900a). Use a typewriter, word processor, or computer, to complete all items.

1. Name of Property

historic name Midtown Historic District
other names/site number N/A

2. Location

street & number See Continuation Sheet N/A not for publication
city or town Mobile N/A vicinity
state Alabama code AL county Mobile code 093 zip code 36606

3. State/Federal Agency Certification

As the designated authority under the National Historic Preservation Act, as amended, I hereby certify that this nomination request for determination of eligibility meets the documentation standards for registering properties in the National Register of Historic Places and meets the procedural and professional requirements set forth in 36 CFR Part 60. In my opinion, the property meets does not meet the National Register criteria. I recommend that this property be considered significant nationally statewide locally. (See continuation sheet for additional comments.)
Elizabeth Brown 8-31-01
Signature of certifying official/Title Date
Alabama Historical Commission (State Historic Preservation Office)
State of Federal agency and bureau

In my opinion, the property meets does not meet the National Register criteria. (See continuation sheet for additional comments.)

Signature of certifying official/Title Date

State or Federal agency and bureau

4. National Park Service Certification

I hereby certify that the property is:
 entered in the National Register. See continuation sheet.
 determined eligible for the National Register See continuation sheet.
 determined not eligible for the National Register.
 removed from the National Register.
 other, (explain) _____

Signature of the Keeper Edson H. Beall Date of Action 11/29/01

Name of Property

County and State

5. Classification

Ownership of Property (Check as many boxes as apply)

Category of Property (Check only one box)

Number of Resources within Property (Do not include previously listed resources in the count.)

- Ownership options: private, public-local, public-State, public-Federal

- Category options: building(s), district, site, structure, object

Table with 2 columns: Contributing, Noncontributing. Rows for buildings, sites, structures, objects, Total.

Name of related multiple property listing (Enter "N/A" if property is not part of a multiple property listing.)

N/A

Number of contributing resources previously listed in the National Register

18

6. Function or Use

Historic Functions

(Enter categories from instructions)

- Historic Functions: DOMESTIC/single dwelling, DOMESTIC/multiple dwelling, DOMESTIC/secondary structure, LANDSCAPE/park, RELIGION/church, COMMERCE/business

Current Functions

(Enter categories from instructions)

- Current Functions: DOMESTIC/single dwelling, DOMESTIC/multi-family, DOMESTIC/secondary structure, LANDSCAPE/park, RELIGION/church, COMMERCE/business

7. Description

Architectural Classification

(Enter categories from instructions)

- Architectural Classification: Greek Revival, Queen Anne, Bungalow/craftsman, Colonial Revival, Tudor Revival

Materials

(Enter categories from instructions)

- Materials: foundation brick, concrete; walls wood; weatherboard, brick, stucco, asbestos; roof asphalt, ceramic tile

SEE CONTINUATION SHEET

Narrative Description

(Describe the historic and current condition of the property on one or more continuation sheets.)

See continuation sheets

Name of Property

County and State

8. Statement of Significance

Applicable National Register Criteria

(Mark "x" in one or more boxes for the criteria qualifying the property for National Register listing.)

- A Property is associated with events that have made a significant contribution to the broad patterns of our history.
B Property is associated with the lives of persons significant in our past.
C Property embodies the distinctive characteristics of a type, period, or method of construction or represents the work of a master, or possesses high artistic values, or represents a significant and distinguishable entity whose components lack individual distinction.
D Property has yielded, or is likely to yield, information important in prehistory or history.

Criteria Considerations

(Mark "x" in all the boxes that apply.)

Property is: N/A

- A owned by a religious institution or used for religious purposes.
B removed from its original location.
C a birthplace or grave.
D a cemetery.
E a reconstructed building, object, or structure.
F a commemorative property.
G less than 50 years of age or achieved significance within the past 50 years.

Narrative Statement of Significance See Cont. Sheet (Explain the significance of the property on one or more continuation sheets.)

9. Major Bibliographical References

Bibliography See Continuation Sheet

(Cite the books, articles, and other sources used in preparing this form on one or more continuation sheets.)

Previous documentation on file (NPS): N/A

- preliminary determination of individual listing (36 CFR 67) has been requested
previously listed in the National Register
previously determined eligible by the National Register
designated a National Historic Landmark
recorded by Historic American Buildings Survey
recorded by Historic American Engineering Record

Areas of Significance

(Enter categories from instructions)

Community Planning and Development

Architecture

Period of Significance

1840, 1843, c.1850, 1851, c. 1870, 1897

c. 1900 to c. 1950

Significant Dates

N/A

Significant Person

(Complete if Criterion B is marked above)

N/A

Cultural Affiliation

N/A

Architect/Builder

Hutchisson, C.L., Sr.

Hutchisson, C.L., Jr.

Rogers, George

Holmes, N.H., Sr.

Primary location of additional data:

- State Historic Preservation Office
Other State agency
Federal agency
Local government
University
Other

Name of repository:

Mobile Historic Development Commission

Midtown District

Name of Property

Mobile, Co., AL.

County and State

10. Geographical Data

Acreeage of Property 467

UTM References

(Place additional UTM references on a continuation sheet.)

1 1 6 3 9 4 4 6 0 3 3 9 5 2 4 0
Zone Easting Northing
2 1 6 3 9 5 2 4 0 3 3 9 5 8 0 0

3 1 6 3 9 6 4 8 0 3 3 9 5 8 2 0
Zone Easting Northing
4 1 6 3 9 6 5 2 0 3 3 9 4 0 0 0

See continuation sheet

Verbal Boundary Description SEE CONTINUATION SHEET 5 1 6 - 3 9 6 0 2 0 - 3 3 9 4 0 0 0
(Describe the boundaries of the property on a continuation sheet.)

Boundary Justification SEE CONTINUATION SHEET

(Explain why the boundaries were selected on a continuation sheet.)

11. Form Prepared By

name/title John Sledge/Architectural Historian

organization Mobile Historic Development Commission date March 1, 2000

street & number 205 Government Street telephone (334) 208-7281

city or town Mobile state AL zip code 36602

Additional Documentation

Submit the following items with the completed form:

Continuation Sheets

Maps

A USGS map (7.5 or 15 minute series) indicating the property's location.

A Sketch map for historic districts and properties having large acreage or numerous resources.

Photographs

Representative black and white photographs of the property.

Additional items

(Check with the SHPO or FPO for any additional items)

Property Owner

(Complete this item at the request of SHPO or FPO.)

name multiple owners

street & number telephone

city or town state zip code

Paperwork Reduction Act Statement: This information is being collected for applications to the National Register of Historic Places to nominate properties for listing or determine eligibility for listing, to list properties, and to amend existing listings. Response to this request is required to obtain a benefit in accordance with the National Historic Preservation Act, as amended (16 U.S.C. 470 et seq.).

Estimated Burden Statement: Public reporting burden for this form is estimated to average 18.1 hours per response including time for reviewing instructions, gathering and maintaining data, and completing and reviewing the form. Direct comments regarding this burden estimate or any aspect of this form to the Chief, Administrative Services Division, National Park Service, P.O. Box 37127, Washington, DC 20013-7127; and the Office of Management and Budget, Paperwork Reductions Projects (1024-0018), Washington, DC 20503.

**United States Department of the Interior
National Park Service**

**National Register of Historic Places
Continuation Sheet**

**MID TOWN HISTORIC DISTRICT
Mobile
Mobile County, AL**

Section number 2 Page 1

The Midtown Historic District is generally bounded by the Old Dauphin Way Historic District to the east, Airport Boulevard to the south, Fielder Place to the west and Spring Hill Avenue to the north. Within these boundaries are all or parts of the following streets:

Airport Boulevard	Lorraine Street
Ashland Place	Margaret Street
Audubon Place	Mohawk Street
Benedict Place	Murray Street
Bienville Avenue	Myrtle Avenue
Camilla Court	Old Government Street
North Carlen Street	Old Shell Road
South Carlen Street	Rickarby Street
Clearmont Street	Seminole Street
Conti Street	Silverwood
Crenshaw Street	South Street
Dauphin Street	Spring Hill Avenue
Demouy Avenue	Stonewall Place
Elizabeth Place	Summerville Court
Elizabeth Street	Terrace Street
Emogene Street	Topic Street
Fielder Place	Tuscaloosa Street
Florence Place	Upham Street
Frazer Court	Van Hueval Street
North Fulton Street	Westwood Street
South Fulton Street	Williams Street
Glenwood Street	Wilcox Street
Government Street	Wisteria Avenue
Homer Street	Woodlands Avenue
Homewood Street	
Hunter Avenue	
Japonica Avenue	
Keenan Street	

**United States Department of the Interior
National Park Service**

**National Register of Historic Places
Continuation Sheet**

**MID TOWN HISTORIC DISTRICT
Mobile
Mobile County, AL**

Section number 2 Page 2

MIDTOWN HISTORIC DISTRICT STREET ADDRESSES

Airport Boulevard-1850, 1866-76, 1880, 1900, 1910, 1912-16, 1918, 2000, 2000-B, 2004, 2006, 2008, 2010, 2016 end

Ashland Place Avenue-2150, 2151, 2153, 2155, 2201, 2203 end

Audubon Place- 1, 2, 3, 4, 5, 7, 8, 9, 10, 11, 12, 13, 14, 15, 16, 17, 18, 19, 20, 21, 22, 23, 24, 25, 26, 27, 28 end

Benedict Place-1, 2, 3, 4, 5, 6, 7, 9, 10, 12, 13, 14, 15, 16, 17, 18, 19, 20, 21, 22, 23, 24, 25, 26, 27 end

Bienville Avenue-1, 3, 4, 5, 6, 7, 8, 9, 10, 11, 12, 14, 15, 16, 17, 19, 20, 21, 22, 23, 24, 25, 26, 50, 51, 52, 53, 54, 55, 56, 57, 58, 59, 60, 61, 63, 64, 100, 101, 103, 104, 105, 106, 107, 108, 109, 110, 111, 112, 113, 114, 115, 117, 119, 121, 122, 123, 124, 125, 126 end

Camilla Court-1, 2 end

North Carlen Street-2, 4, 106, 108, 109, 110, 111, 112, 113, 114, 115, 116, 117, 118, 119, 121, 122, 123, 124, 125, 126, 127, 128, 129, 130, 131, 132, 133, 134, 135, 136, 137, 138, 139, 143, 144, 145, 146 end

South Carlen Street-8, 10, 11, 12, 13, 14, 15, 16, 17, 18, 19, 20, 21, 22, 23, 25, 27, 29, 31, 33, 50, 51, 52, 53, 55, 57, 59, 100 (Murphy High), 101, 105, 107, 109, 111, 113, 115, 117, 119, 121, 123, 125, 127, 159, 161, 182, 184, 185, 187, 188, 215 end

Clearmont Street-1807, 1809, 1811, 1813, 1815, 1817, 1819, 1820, 1822, 1826, 1837, 1839, 1843, 1901, 1905, 1907, 1909, 1911, 1913, 1915, 1917, 1919, 1921, 1923, 1957, 1959, 1961, 2003, 2104, 2105, 2156, 2157, 2159, 2161, end

Conti Street-1824, 1826, 1828, 1830, 1837 end

**United States Department of the Interior
National Park Service**

**National Register of Historic Places
Continuation Sheet**

**MID TOWN HISTORIC DISTRICT
Mobile
Mobile County, AL**

Section number 2 Page 3

Crenshaw Street-4, 5, 6, 8, 10, 12, 21, 25, 50, 52, 54, 56, 59, 61, 63, 68, 70, 100, 101, 102, 103, 104, 105, 106, 107, 108, 109, 110, 111, 112, 113, 114, 115, 116, 117, 118, 119, 122, 150, 152, 153, 154, 155, 156, 157, 159, 160, 161, 162, 163, 165, 167, 169, 171, 225A, 225, 254, 255, 256, 257, 258, 259, 260, 261, 262, 263, 264, 266, 267 end

Dauphin Street-1804, 1806, 1807, 1808, 1809, 1814, 1815, 1816, 1817, 1818, 1819, 1820, 1821, 1822, 1826, 1827, 1828, 1831, 1832, 1833, 1835, 1851, 1852, 1853, 1855, 1856, 1858, 1860, 1861, 1900, 1901, 1905, 1906, 1907, 1908, 1911, 1912, 1953, 2000, 2003, 2004, 2005, 2007, 2008, 2009, 2011, 2012, 2013, 2014, 2016, 2017, 2020, 2021, 2050, 2051, 2052, 2053, 2054, 2055, 2056, 2057, 2058, 2061, 2062, 2067, 2069, 2071, 2073, 2150, 2151, 2153, 2154, 2155, 2156, 2157, 2158, 2159, 2162, 2164, 2166, 2200, 2201, 2202, 2203, 2204, 2206, 2208, 2209, 2251, 2252, 2255, 2300, 2302, 2303, 2304, 2306, 2310, 2312, 2314, 2316, 2318, 2320, 2322, 2400, 2402, 2404, 2406, 2408, 2450, 2452, 2454, 2456, 2458, 2460 end

Demouy Avenue-3, 4, 5, 7, 8, 9, 10, 12, 13, 14, 15, 16, 17, 18, 19, 20, 21, 22, 23, 50, 51, 52, 53, 54, 55, 56, 57, 58, 59, 60, 61, 62, 63, 64, 100, 102, 104, 105, 106, 107, 108, 109, 110, 111, 112, 113, 115, 116, 117, 118, 120, 121, 122 end

Elizabeth Place-1, 2, 3, 4, 5, 6, 7, 8, 9, 10, 11, 12, 13, 14, 15, 16, 17, 18, 19, 21, 22, 23, 24, 25, 26 end

Elizabeth Street-2205 end

Emogene Street-2004, 2005, 2010, 2054, 2103, 2104, 2105, 2156, 2158, 2159 end

Fielder Place-3 end

Florence Place-100, 102, 103, 104, 105, 106, 107, 108, 109, 110, 111, 112, 113, 114, 115, 116, 117, 118, 119, 120, 121, 122, 123, 124, 125, 126, 127, 128, 129, 130, 131, 132, 133, 134, 135, 136, 137, 138, 139, 140, 141, 142, 143, 144, 145, 146, 147, 148 end

Frazer Court-104, 108, 112, 117, 121, 125 end

North Fulton Street-3, 6, 7, 8, 9, 11 end

**United States Department of the Interior
National Park Service**

**National Register of Historic Places
Continuation Sheet**

**MID TOWN HISTORIC DISTRICT
Mobile
Mobile County, AL**

Section number 2 Page 4

South Fulton Street-8, 50, 51, 52 1/2, 53, 55, 56, 57, 58, 59, 60, 61, 62, 63, 64, 65, 66, 67, 68, 69, 71, 75, 100, 102, 103, 104, 105, 106, 107, 108, 109, 110, 111, 112, 114, 115, 116, 117, 118, 119, 120, 150, 151, 152, 153, 155, 156, 157, 158, 159, 160, 161, 162, 163, 164, 165, 166, 167, 169, 170, 200, 201, 202, 203, 204, 205, 206, 207, 208, 209, 210, 211, 212, 213, 214, 215, 253, 255, 256, 257, 259, 261, 263 end

Glenwood Street-50, 51, 52, 53, 54, 55, 56, 57, 58, 60, 61, 62, 63, 64, 65, 66, 67, 68, 69, 70, 71, 72, 100, 101, 102, 103, 104, 105, 106, 107, 108, 109, 110, 111, 112, 113, 114, 115, 116, 117, 118, 119, 121, 122, 150, 151, 152, 153, 154, 155, 156, 159, 160, 161, 162, 163, 164, 165, 166, 167, 170, 200, 201, 203, 206, 207, 208, 210, 211, 213, 214, 215 end

Government Street-1800 (Memorial Park) end

Homer Street-8, 10, 12, 16, 18, 20 end

Homewood Street-2156, 2157, 2158, 2159, 2160, 2161, 2200, 2202, 2204, 2206, 2207, 2208, 2209 end

Hunter Avenue-1804, 1806, 1808, 1810, 1814, 1813, 1815, 1853, 1854, 1855, 1856, 1857, 1859, 1861, 1863, 1865, 1901, 1903, 1905, 1906, 1907, 1908, 1909, 1910, 1911, 1912, 1913, 1914, 1915, 1916, 1917, 1920, 1921, 1922, 1950, 1951, 1953, 1955, 1957, 1960, 1961, 1963 end

Japonica Avenue- 1, 2, 4, 6, 7, 8, 9, 10, 11, 14, 15, 16, 17, 18, 19, 20, 21, 22, 25, 26 end

Keenan Street-150, 152, 154, 155, 157, 158, 159, 161, 162, 163, 164, 166, 200, 201, 202, 203, 204, 205, 206, 208 end

Lorraine Street-No addresses

Margaret Street-106, 108, 110, 112, 114, 116, 118, 120, 123, 124, 125, 126, 127, 128, 129, 130, 131, 133, 134, 135, 137, 139, 142 end

Mohawk Street-1, 2, 3, 5, 6, 7, 8, 9, 10, 11, 12, 13, 14, 15, 16, 18, 50, 51, 52, 53, 54, 55, 56, 57, 58, 59, 61, 62, 100, 101, 103, 104, 105, 107, 108, 109, 110, 111, 112, 113, 114,

**United States Department of the Interior
National Park Service**

**National Register of Historic Places
Continuation Sheet**

**MID TOWN HISTORIC DISTRICT
Mobile
Mobile County, AL**

Section number 2 Page 5

115, 116, 117, 118, 119, 120, 121, 122, 123, 150, 151, 152, 153, 154, 155, 156, 157, 158,
159, 160, 161, 162, 163, 164, 165, 166, 167, 168, 169, 170, 171, 200, 201, 203, 204, 205,
206, 207, 208, 209, 210, 211, 253, 256, 257, 259, 260, 261, 262, 263, 264, 265, 266, 268
end

Murray Street-1814, 1816 end

Myrtle Avenue-1900, 1902, 1903, 1904, 1905, 1906, 1907, 1908, 1910, 1911, 1912, 1914,
1915, 1916, 1917, 1918, 1920, 1950, 1951, 1952, 1953, 1954, 1955, 1956, 1957, 1958,
1959, 1960, 1961, 1964 end

Old Government Street-1806, 1810, 1820, 1852, 1854, 1856, 1858, 1860, 1864, 1865,
1866, 1867, 1868, 1869, 1900, 1901, 1902, 1903, 1904, 1905, 1906, 1907, 1908, 1909,
1910, 1911, 1912, 1913, 1914, 1915, 1916, 1917, 1918, 1920, 1921, 1923, 1948, 1951,
1952, 1954, 1955, 1956, 1957, 1958, 1960, 2007, 2008, 2009, 2010, 2050, 2051, 2053,
2054, 2055, 2056, 2057, 2058, 2059, 2104, 2106, 2108, 2150, 2151, 2153, 2154, 2155,
2156, 2157, 2158, 2159, 2200, 2201, 2202, 2203, 2204, 2205, 2206, 2207, 2208, 2209,
2250, 2252, 2254, 2255, 2256, 2257, 2258, 2259 end

Old Shell Road-1801, 1803, 1805, 1807, 1809, 1811, 1813, 1815, 1817, 1819, 1823, 1824,
1825, 1829, 1831, 1835, 1838, 1840, 1842, 1844, 1850, 1851, 1852, 1854, 1856, 1857,
1858, 1861, 1900, 1901, 1903, 1905, 1907, 1911, 1915, 2000, 2001, 2005, 2006, 2008,
2009, 2010, 2015, 2019, 2025, 2051, 2053, 2055, 2058, 2062, 2064, 2065, 2068, 2150,
2151, 2165, 2166, 2167, 2169, 2170, 2175, 2179, 2181, 2315, 2317, 2321 end

Rickarby Street-7, 8, 9, 10, 11, 12, 13, 14, 15, 16, 18, 19, 20, 21, 22, 51, 52, 54 end

Seminole Street- 253, 255, 257, 259, 261, 263, 265 end

Silverwood-51, 52, 53, 54, 55, 56, 57, 58, 59, 60, 61, 62, 63, 64, 65, 66, 67, 68, 69, 71,
120, 123, 124, 125, 126, 127, 128, 129, 130, 131, 132, 133, 134, 135, 136, 137, 138, 139,
140, 141, 143, 145 end

South Street-10, 11, 12, 13, 14, 15, 16, 17, 18, 19, 20, 21, 23, 24, 25, 26, 28, 30, 32, 34,
36, 108, 110, 112, 114, 118, 122, 124, 128, 150, 152, 156, 160, 162, 164, 166, 168, 180,
181, 182, 183, 185, 186, 188, 191 end

**United States Department of the Interior
National Park Service**

**National Register of Historic Places
Continuation Sheet**

**MID TOWN HISTORIC DISTRICT
Mobile
Mobile County, AL**

Section number 2 Page 6

Spring Hill Avenue-1805, 1809, 1811, 1815, 1851, 1855, 1901, 1903, 1951, 1955, 1957,
1959, 2059, 2067 end

Stonewall Place-160, 161, 162, 163 end

Summerville Court-200, 201, 204, 205, 206, 209, 210, 212, 214, 215, 217, 218, 2058,
2059, 2063, 2066 end

Terrace Street-2056, 2058, 2060 end

Topic Street-No addresses

Tuscaloosa Street-150, 152 end

Upham Place-2101, 2103, 2105, 2106, 2107, 2108 end

Upham Street-9, 10, 11, 13, 66, 107, 119, 122, 123, 204, 208, 214, 218 end

Van Hueval Street-7, 9, 11, 14, 13-15, 17, 19, 20, 21, 23, 25, 29 end

Westwood Street-1, 2, 3, 5, 7, 9, 12, 14, 16, 18, 20, 21, 22, 24, 26, 50, 52, 56, 57, 58, 59,
60, 61, 62, 63, 70, 100, 101, 102, 103, 105, 107, 110, 111, 113, 114, 115, 116, 117, 118,
120, 121, 122, 123, 150, 152, 154, 156, 158, 211, 213, 250, 254, 255, 256, 257, 258, 259,
260, 261, 262, 263, 264, 265, 266, 267, 268, 269 end

Williams Street-50, 51, 52, 54, 57, 59, 60, 61, 62, 63, 64, 65, 101, 103, 105, 106, 108,
110, 111, 112, 113, 114, 115, 116, 117, 120, 121, 122, 123, 124, 125, 128, 129, 151, 152,
154, 155, 156, 157, 159, 160, 161, 162, 163, 164, 165, 166, 167, 168, 169, 170, 171, 180,
182, 184, 186, 200, 204, 206, 208, 250, 252, 254, 256, 258, 260, 262, 300, 304, 307-11
end

Wilcox Street-No addresses

Wisteria Avenue-5, 7, 8, 9, 10, 12, 14 end

Woodlands Avenue-200, 202, 203, 204, 205, 206, 207, 208, 210, 211, 213, 215 end

**United States Department of the Interior
National Park Service**

**National Register of Historic Places
Continuation Sheet**

**MID TOWN HISTORIC DISTRICT
Mobile
Mobile County, AL**

Section number 7 Page 1

7. Architectural Classification

Art Deco
Beaux Arts

Gothic Revival
International
Mission Revival
Neo Classical Revival

Spanish Revival
other:

 creole cottage
 gulf coast cottage
 minimal traditional
 ranch
 shotgun

**United States Department of the Interior
National Park Service****National Register of Historic Places
Continuation Sheet****MID TOWN HISTORIC DISTRICT
Mobile
Mobile County, AL**Section number 7 Page 2

7. Narrative Description

The Midtown Historic District consists of all or part of 78 blocks in the city of Mobile, Alabama. The Old Dauphin Way Historic District abutts the Midtown District on the east, running the length of Houston Street, whereas the southern, western and northern borders of the Midtown District are irregular, conforming to the greatest concentrations of contributing resources. The southeast corner of the district is anchored by Memorial Park (# 1004), a landscaped World War I memorial park with a freestanding colonnade, fountain and mature live oak trees. The southern boundary runs for some distance along the north side of Airport Boulevard, a heavily commercialized corridor. The western boundary jogs around a 1950s neighborhood and industrial plant, before taking in a series of streets lined by early post-World War II era housing. The northern boundary skirts the Ashland Place Historic District at the northwest corner, then runs along Spring Hill Avenue, excluding a large pocket of non-contributing buildings and back to the point of beginning at the northwestern border of the Old Dauphin Way Historic District at Houston Street.

Though there are a few ante-bellum buildings within this district, the area mostly developed between 1900 and 1950. Dominating the district is Murphy High School (built 1926, NR 1982, # 162) which is a series of stuccoed Mission Revival buildings set on an expansive, live oak shaded campus bounded by Carlen Street to the east, Clearmont Street to the south, South Street to the west and Wilcox Street to the north. On the northern end of the Murphy campus is the Carlen historic house museum (1843, NR 1981, # 1178), a modest frame Creole Cottage. Much of the land in the Midtown District was originally part of the Carlen House's accompanying farmland.

A number of important residential streets run east-west through this district. Because the city grew from east to west, buildings along these streets progress in age as one travels west. These streets include Old Government Street in the southern section, and Dauphin Street, Old Shell Road and Spring Hill Avenue north of the Murphy campus. Each of these streets has a distinctive character, Dauphin featuring the grandest architecture, some of them architect designed, a mix of Victorian (1826 Dauphin Street, #

**United States Department of the Interior
National Park Service****National Register of Historic Places
Continuation Sheet****MID TOWN HISTORIC DISTRICT
Mobile
Mobile County, AL**Section number 7 Page 3

344) and early 20th century revival styles (1835 Dauphin Street, # 350). Many of these houses are two stories. The most important building on Dauphin Street is Trinity Episcopal Church (1853, moved to Dauphin Street 1946, NR 1990, # 359), a brick Gothic Revival structure not far from Murphy High School. Dauphin Street is lined with mature live oak trees, as well as some palms and pines. The street is a four lane artery into the downtown and is heavily traveled. Old Shell Road is a narrow two-lane road lined by live oaks. It is the historic route out to Spring Hill, several miles west of the district, now in the city limits but at one time a retreat for the wealthy. The houses along Old Shell Road are more modest than those along Dauphin, and include a mix of styles from vernacular cottages (1813 Old Shell Road, # 1099) to Bungalows (1817 Old Shell Road, # 1101) to minimal traditional houses (2175 Old Shell Road, # 1155). Spring Hill Avenue, along the district's northern border, is, like Dauphin Street, four laned and heavily traveled. A median runs down the center, planted with azaleas, and live oaks and palms line each side of the road. The houses along Spring Hill Avenue are of grand scale, a number representing the Spanish Revival style of architecture (1851 Spring Hill Avenue, # 1278). Old Government Street in the southern portion of the district, is, by contrast, a quiet residential street lined by live oaks and palms. Along its eastern end are a number of turn of the century houses, larger than the norm for the district (1810 Old Government Street, # 1006). Towards the west the houses become more modest bungalows and minimal traditional cottages (2058 Old Government, # 1062, 2151 Old Government Street, # 1068).

A number of the north-south streets in the Midtown District have strong thematic architectural flavors, due to their being developed in small portions at specific times (see plat map). These streets include Florence Place (developed in 1926 with a strong Mission Revival feel, # 537, 538, 541), Silverwood (developed in 1927 and dominated by bungalows # 1188, 1192, 1204), Bienville Avenue (developed in 1920 and dominated by bungalows # 78, 81, 85) and Benedict Place (developed in 1941 and dominated by minimal traditional cottages, # 50, 62). Bienville Avenue is one of the most spectacular streets in the district, with a live oak canopy running virtually its entire length. Florence Place and Silverwood feature live oak trees as well as period street lights and entrance gates with the names of the streets.

**United States Department of the Interior
National Park Service****National Register of Historic Places
Continuation Sheet****MID TOWN HISTORIC DISTRICT
Mobile
Mobile County, AL**Section number 7 Page 4

The Midtown Historic District is overwhelmingly residential in character, interspersed with Murphy High School, several churches and a few businesses. Of the nearly 1500 buildings in this district, over 85% are contributing structures, and there are only a handful of vacant lots. The area came within the city limits largely between 1915 and 1931, though many of the streets were platted somewhat earlier (Rickarby Street in 1902 and Myrtle Avenue and much of Old Government Street in 1904 for example). By 1926, when Murphy High School was constructed, all of the streets within the district were platted with the exception of Elizabeth Place, Benedict Place, Audubon Place and Japonica Avenue to the west, all of which were platted after 1939.

The architectural character of the Midtown District slowly changes as one travels from east to west within the district. Along the eastern ends of Dauphin Street, Old Shell Road and Old Government Street are one and two story Queen Anne cottages, American Foursquares and Colonial Revival houses. As one travels west, the buildings become revival cottages, bungalows and minimal traditional houses. Certain streets such as Bienville Avenue and Florence Place are very distinctive, with one story frame bungalows and stucco Mission Revival houses, whereas other streets, such as Fulton, are more mixed.

With the exception of a number of grand houses already noted, the preponderance of architecture is modest and middle class. Among the older houses are a few Queen Anne cottages (8 Rickarby Street, # 1162) and numerous American Foursquares especially along Daupin and Old Government Streets (1806 Dauphin Street, # 333, 1868 Old Government Street, # 1017). The many bungalows in this district are typically one story, frame structures with recessed or attached porches, more often than not featuring battered, boxed columns on brick plinths, knee braces and Craftsman windows and doors (112 Bienville Avenue, # 121, 56 Bienville Avenue, # 103, 110 Demouy Avenue, # 486). The district includes many revival styles, including Neo-Classical Revival (1814 Dauphin Street, # 336), Colonial Revival (1810 Old Government Street, # 1006), Dutch Colonial Revival (1901 Old Shell Road, # 1122), Spanish Colonial Revival (1851 Springhill Avenue, # 1278), English Cottage Revival (183 South Street, # 1269), and Tudor Revival (210 and 211 Woodlands Avenue, #s 1497, 1498). Most of the houses constructed between 1935 and 1950 are minimal traditional cottages, and these

**United States Department of the Interior
National Park Service****National Register of Historic Places
Continuation Sheet****MID TOWN HISTORIC DISTRICT
Mobile
Mobile County, AL**Section number 7 Page 5

dominate the western reaches of the district. Like their older cousins, these houses are typically frame, but feature multi-paned windows, battered brick entrance surrounds and little ornament (165 Crenshaw Street, # 312, 71 Silverwood # 1205).

A number of local architects did work in the Midtown Historic District and their work survives. These men include George Rogers (Memorial Park, 1918, # 1004, Murphy High School, 1926, # 162), C. L. Hutchisson, Sr. (1901 Old Shell Road, 1922, # 1122), C. L. Hutchisson, Jr. (2056 Dauphin Street, 1936, first FHA house in Mobile, # 389) and Nicholas Holmes, Sr. (205 Woodlands Avenue, 1928, # 1493).

Virtually all of the houses in the Midtown District rest on their original lots, few of which have been subdivided. Though some lots are large and semi-wooded, by far the majority are small urban lots averaging 50 feet in width by 120 feet in length. Most of the lots are informally landscaped, and feature creape myrtles, pecan trees and palms in the yards. Flower boxes are common on many houses. The houses themselves are constructed most commonly of frame, though brick and stucco are common, and by the 1940s asbestos siding was being used. As such, in a number of cases this should be considered a contributing material original to the house (165 Crenshaw Street, # 312). In recent years, many building owners have put aluminum or vinyl siding over the original frame (2013 Dauphin Street, # 377, 2012 Dauphin Street, # 376), but because the buildings retain their overall form, mass, and original windows and doors, they are considered contributing buildings in the district. There are hundreds of small outbuildings in this district, primarily small garages and tool sheds, some contemporary with the houses but many not. Outbuildings were counted only when they had an independent address. Memorial Park is an important non-structural contributing element in this district, featuring as it does a historic fountain and colonnade. A number of the streets in the Midtown District feature original street lights and gates, these were not counted but do enhance the ambience of the district.

The non-contributing buildings in the district include buildings constructed after 1950, both residential and commercial, and extensively unsympathetically altered historic buildings. The latter include buildings which have lost their character and feel

**United States Department of the Interior
National Park Service**

**National Register of Historic Places
Continuation Sheet**

**MID TOWN HISTORIC DISTRICT
Mobile
Mobile County, AL**

Section number 7 Page 6

through the infilling of porches or the addition of modern wings or rooms. The non-contributing buildings are identified on the district map.

Existing National Register Properties in the District

Carlen House (# 1178)
Murphy High School (# 162) Six resources associated with this nomination
Century 21 Building (# 1005)
Trinity Episcopal Church (# 359)
Azalea Court Apartments (# 1007)
Greene-Marston House (# 368)
Houses in Florence Place (#s 537, 538, 541, 552, 553, 563, 577)

Archaeological Component

Although no formal archaeological survey has been made of this district area, the potential for subsurface remains is good. Buried portions may contain significant information that may be useful in interpreting the entire area.

Inventory

The following information was compiled from historic research and field surveys by John Sledge, architectural historian with the Mobile Historic Development Commission. During 1997 and 1998 Mr. Sledge did a thorough survey of the entire district, photographing and describing both the contributing and noncontributing buildings. Backyard outbuildings and detached garages were not counted separately in the inventory unless the associated main house no longer exists and/or the ancillary structure is a major one that has retained its own significance. Most construction dates are circa, based on the period of development of the particular street on which a building is located and the architectural characteristics of the building itself. In the cases of exact dates, these were obtained by oral interviews with residents, contemporary newspaper accounts and in some cases,

**United States Department of the Interior
National Park Service**

**National Register of Historic Places
Continuation Sheet**

**MID TOWN HISTORIC DISTRICT
Mobile
Mobile County, AL**

Section number 7 Page 7

title and tax work coupled with city directory references. Houses with names refer to first occupants or early prominent residents. Business names reflect current occupation. During the data entry phase of this project, two buildings were inadvertently entered twice, and these duplications have been removed, at numbers 82 and 1092, however, because of sequencing problems, these numbers were left in, and are marked "void."

Other numbers omitted during processing include: 46, 178, 196, 318, 358, 1150, 1223, and 1277

Inventory Key

These are also marked "void" in the inventory.

Each property description begins with an inventory number (these run upward sequentially), then features the name of the house or business if relevant, then the street address, then the date, architectural description, frame and roll number of the photograph depicting the property in the files of the Mobile Historic Development Commission, and lastly "C" for contributing and "N" for non-contributing.

United States Department of the Interior
National Park Service

National Register Of Historic Places

Section Number 7 Page 8

MID TOWN HISTORIC DISTRICT
Mobile
Mobile County, AL

- 1 HEMINGWAY'S 1850 AIRPORT BLVD c. 1925. Spanish Revival style. This one story, stuccoed commercial structure features storefronts on both Old Government Street and Airport Boulevard. The Old Government Street elevation features red ceramic tile roof with three small gables. Airport Boulevard elevation features modern glass and aluminum store fronts with canvas awnings above. The building is shaped like a wedge to conform to the lot. 5 1000 C
- 2 1866 AIRPORT BLVD c. 1960. One story, brick commercial building with flat roof, multiple windows and doors. 7 1000 N
- 3 1880 AIRPORT BLVD c. 1980. One story, stuccoed modern commercial building with picture windows, aluminum doors, and awnings. 8 1000 N
- 4 BLOOMER'S FLORIST 1900 AIRPORT BLVD c. 1930. Bungalow, one story, frame with offset gable porch, now filled in with glass, awning across porch, exposed rafters and purlins. 9 1000 C
- 5 1910 AIRPORT BLVD c. 1930. Two story, frame, gable roof to the sides, garage apartment, with two automobile bays and two 6/6 windows upstairs. 10 1000 C
- 6 1912 AIRPORT BLVD c. 1955. Two story brick commercial building with flat roof, large windows, open interior stairwell. 11 1000 N
- 7 1918 AIRPORT BLVD c. 1970. Two story, brick and glass commercial building with large roof balcony above one story portion, large glass windows. 12 1000 N
- 8 SHANGHAI RESTAURANT 2000 AIRPORT BLVD c. 1960. One story, frame, gable front roof, large sign in gable, parking all around. 13 1000 N
- 9 2000 B AIRPORT BLVD c. 1960. Two story, asbestos sided apartment, gable roof sides, plate glass infill at southeast corner first floor. 14 1000 N

c 3
n 6

United States Department of the Interior
National Park Service

National Register Of Historic Places
Continuation Sheet

Section Number 7 Page 9

MID TOWN HISTORIC DISTRICT
Mobile
Mobile County, AL

-
- 10 ANTIQUES 2006 AIRPORT BLVD c. 1960. One story, cinderblock with massive square mass southwest corner, pierced cinderblock wall screens entrance. 16 1000 N
- 11 PALMER STUDIO 2008 AIRPORT BLVD c. 1940. Bungalow, one story, cross gable, chimney up facade, unsympathetic alterations include vinyl siding, glass filled porch and ornamental iron porch columns. 17 1000 N
- 12 DOGWOOD ANTIQUES 2010 AIRPORT BLVD c. 1930. Bungalow, one story, gable roof front with offset attached gable porch, square brick pillars at porch, louvered vent in gable, casement windows. 18 1000 C
- 13 BELL STAINED GLASS 2016 AIRPORT BLVD c. 1930, Craftsman, two story, brick, low hip roof, 3/1 windows, one story wing to west with multiple storefronts. 20 1000 C
- 14 2150 ASHLAND PLACE AVE C. 1940. Cottage Revival, one story brick, gable roof sides, offset gable entrance with classical door surround, chimney adjacent at facade, pair small dormers with 3/3 windows, 12/12 window center of facade, pair of square diamond pane windows to side. 28 1037 C
- 15 2151 ASHLAND PLACE AVE c. 1940. Raised Gulf Coast cottage with gable roof sides, recessed porch and boxed columns, entrance with sidelights but no transom, 6/6 windows. 27 1037 C
- 16 2153 ASHLAND PLACE AVE c. 1940. Cottage Revival. One and a half story, brick, cross gable, shed roof porch over entrance, chimney at facade, pair frame gabled dormers above with 6/6 windows. 29 1037 C
- 17 2155 ASHLAND PLACE AVE c. 1960, Ranch style, one story, frame, gable roof sides, attached shed roof porch. 30 1037 N
- 18 2201 ASHLAND PLACE AVE c. 1935. Colonial Revival, extensively remodled to the point that it no longer retains its original integrity, two story, frame shiplapped siding, classical door surround. 31 1037 N

26 5 48
120 4 125

United States Department of the Interior
National Park Service

National Register Of Historic Places
Continuation Sheet

Section Number 7 Page 10

MID TOWN HISTORIC DISTRICT
Mobile
Mobile County, AL

-
- 19 2203 ASHLAND PLACE AVE c. 1940, Cottage Revival, two story, brick, gable roof sides, shed roof with paneled box columns at offset entrance, chimney at facade, one story room at west elevation. 32 1037 C
- 20 1 AUDUBON PL c. 1955. Ranch style, one story brick, cross gable, attached shed roof porch, awning over window, louvered vent in gable. 6 1035 N
- 21 2 AUDUBON PL c. 1945. Colonial Revival, two story, frame, gable roof sides, five bay facade with central entrance, gable porch with paired columns, 6/6 windows. 5 1035 C
- 22 3 AUDUBON PL c. 1945. One story, shiplapped siding, cross gable, recessed porch with square posts and curved bargeboard, 6/6 windows. 7 1035 C
- 23 4 AUDUBON PL 1840. Greek Revival/Gulf Coast Cottage, one and a half story, frame, gable roof sides, recessed porch covers facade, boxed columns and balustrade, 6/6 windows, four panel door with sidelights and transom, three dormers above with 6/6 windows. House originally faced Dauphin Street and was a dairy owned by a Col. Deas, but was moved 1939 when Audubon Street was opened. This is one of the oldest houses in the Midtown Historic District, and is of extraordinary significance. 4 1035 C
- 24 5 AUDUBON PL c. 1945. Cottage Revival, one story, brick, cross gable, louvered lunette in gable, entrance does not face street but rather is in side of front gable, multi-light windows with shutters. 8 1035 C
- 25 7 AUDUBON PL c. 1955. One story, asbestos sided, gable roof sides, gable portico over stoop, 12/12 windows flank entrance. 9 1035 N
- 26 8 AUDUBON PL c. 1945. Cottage Revival, one story frame, cross gable, 6/6 windows, louvered lunette in gable, recessed entrance with stoop. 3 1035 C
- 27 9 AUDUBON PL c. 1940. Tudor Revival, one story brick, cross gable, half-timbering in front entrance gable, chimney at facade, casement windows. 10 1035 C
- 26 7
1035 C

United States Department of the Interior
National Park Service

National Register Of Historic Places
Continuation Sheet

Section Number 7 Page 11

MID TOWN HISTORIC DISTRICT
Mobile
Mobile County, AL

- 28 10 AUDUBON PL c. 1945. One and a half story, brick, gable roof sides, two dormers with 6/6 windows, central entrance with 12/12 windows flanking. 2 1035 C
- 29 11 AUDUBON PL c. 1945. Colonial Revival, one story, frame, gable roof sides, pair bay windows with multi-light windows flank recessed entrance with six panel door, carriage lamps bracket door. 11 1035 C
- 30 12 AUDUBON PL c. 1945. One story brick, cross gable, small hip roof over stoop supported on decorative iron posts, louvered vent in front gable, box cornice with closed return. 1 1035 C
- 31 12 AUDUBON PL c. 1945. Two story, frame, hip roof, casement windows, awning over front door. 12 1035 C
- 32 14 AUDUBON PL c. 1940. Colonial Revival, two story, brick, gable roof sides, three frame dormers above with 6/6 sash, one story sun room with iron balustrade above, 6/6 windows with shutters. 35 1034 C
- 33 15 AUDUBON PL c. 1940. Bungalow, one story, cross gables, round topped entrance, aluminum siding. 13 1035 N
- 34 16 AUDUBON PL c. 1955. Colonial Revival, one story, brick with gable roof sides, attached gable portico with paired slender columns. 34 1034 N
- 35 17 AUDUBON PL c. 1945. Colonial Revival, one story, frame, gable roof sides, gable portico with paired columns, 12/12 windows, interior chimney. 14 1035 C
- 36 18 AUDUBON PL c. 1940. One story, vinyl sided, infilled porch, aluminum windows, hip roof with asbestos shingles. 33 1034 N

cb 6 cs
nd 5 ns

United States Department of the Interior
National Park Service

National Register Of Historic Places
Continuation Sheet

Section Number 7 Page 12

MID TOWN HISTORIC DISTRICT
Mobile
Mobile County, AL

-
- 37 19 AUDUBON PL c. 1945. One story, asbestos sided, 12/12 windows, central entrance with gable roof on square posts over stoop. 15 1035 C
- 38 20 AUDUBON PL c. 1955. Ranch style house, one story, brick, cross gable, attached shed roof porch. 32 1034 N
- 39 21 AUDUBON PL c. 1945. Colonial Revival, one and a half story, frame, gable roof sides, three bay facade, bay windows with paired 12/12 windows flank entrance, pair dormers above with 8/8 windows. 16 1035 C
- 40 22 AUDUBON PL c. 1940. Colonial Revival, two story, gable roof sides, frame, central entrance with canvas awning, paired 6/6 windows, dentil course. 31 1034 C
- 41 23 AUDUBON PL c. 1945. One story, frame, gable roof sides, four bay facade, awning over entrance, 6/6 windows with shutters. 17 1035 C
- 42 24 AUDUBON PL ca. 1955. Ranch style house, one story, brick, cross gable, metal awning over stoop. 30 1034 N
- 43 25 AUDUBON PL c. 1945. Colonial Revival, one and a half story, frame, gable roof sides, three bay facade, gable portico at entrance, flanked by 8/8 windows, pair gabled dormers above the 6/6 windows. 18 1035 C
- 44 26 AUDUBON PL c. 1940. One story, cross gable, exposed rafters, frame, gabled entrance with modern iron railings, variety of windows, including 6/6, 8/8 and one 12/24 at street elevation. 29 1034 C
- 45 27 AUDUBON PL c. 1945. One and a half story, frame, gable roof sides, three bay facade, gable portico over entrance, 12/12 windows, pair gable dormers above with 6/6 windows. 19 1035 C

United States Department of the Interior
National Park Service

National Register Of Historic Places
Continuation Sheet

Section Number 7 Page 13

MID TOWN HISTORIC DISTRICT
Mobile
Mobile County, AL

46 VOID

47 1 BENEDICT PL c. 1945. Cottage Revival, one and a half story, brick, gable roof sides, three bay facade, shed roof porch covers entrance with ornamental iron supports, paired 6/6 windows flank entrance, pair gable roof dormers above, sun room north elevation. 33 1035 C

48 2 BENEDICT PL c. 1960. One story, brick, gable roof sides, large multi-light window at facade. 32 1035 N

49 3 BENEDICT PL c. 1950. One story, vinyl sided, gable roof sides, attached gable roof over porch with ornamental iron supports, flanked by 12/12 windows. 34 1035 N
Front facade also contains replacement materials: brick wainscoting

50 4 BENEDICT PL c. 1945. One story, frame, gable roof sides, six bay facade, six panel door, full height 9/9 windows, pair gabled dormers above with 6/6 windows. 31 1035 C

51 5 BENEDICT PL c. 1950. One story, brick, ^{vener}gable roof sides, attached gable porch with ornamental iron supports and railing, 12/12 windows. 35 1035 N

52 6 BENEDICT PL c. 1945. Craftsman, one story, frame, gable roof sides, attached gable porch at entrance with craftsman balustrade, exposed rafters, 6/6 windows. 30 1035 C

53 7 BENEDICT PL c. 1980. One story, cross gable, vinyl sided, two bay garage at facade, attached shed roof porch with box columns. 1 1036 N

54 9 BENEDICT PL c. 1955. One story, brick, gable roof sides, multi-light windows at facade, interior chimney. 2 1036 N

63
5

United States Department of the Interior
National Park Service

National Register Of Historic Places
Continuation Sheet

Section Number 7 Page 14

MID TOWN HISTORIC DISTRICT
Mobile
Mobile County, AL

-
- 55 10 BENEDICT PL c. 1960. One story, brick, cross gable, awnings over windows and entrance, framed gable with louvered vent. 29 1035 N
- 56 12 BENEDICT PL c. 1945. One story, asbestos sided, cross gable, 8/8 windows, awning over entrance, louvered vent in front gable. 28 1035 C
- 57 13 BENEDICT PL c. 1955. One story, cross gable, frame, 6/6 windows, gabled entrance at side with slender turned posts. 3 1036 N
- 58 14 BENEDICT PL c. 1945. One story, frame, gable roof sides, three bay facade, gable over entrance, flanked by 12/12 windows. 27 1035 C
- 59 15 BENEDICT PL c. 1955. One story, gable roof sides, asbestos sided, gable over stoop with ornamental iron supports, interior chimney. 4 1036 N
- 60 16 BENEDICT PL c. 1945. One story, frame, gable roof sides, four bay facade, gable porch with square posts and railing, 8/8 windows, picture window at south end. 26 1035 C
- 61 17 BENEDICT PL c. 1955. One story, cross gable, vinyl sided, 8/8 windows, inset entrance, interior chimney. 5 1036 N
- 62 18 BENEDICT PL c. 1945. One story, asbestos sided, cross gable with inset entrance, 12/12 windows, awning over window in gable, louvered vent above. 25 1035 C
- 63 19 BENEDICT PL c. 1950. One story, gable roof sides, frame, end chimney, three bay facade, multi-light windows, shed roof over stoop with wall brackets. 6 1036 C

C65 25
26 27

United States Department of the Interior
National Park Service

National Register Of Historic Places
Continuation Sheet

Section Number 7 Page 15

MID TOWN HISTORIC DISTRICT
Mobile
Mobile County, AL

-
- 64 20 BENEDICT PL c. 1945. Colonial Revival, one story, frame, gable roof sides, four bay facade, 12/12 windows, gable over stoop, dentil course. 24 1035 C
- 65 21 BENEDICT PL c. 1970. Ranch style house, one story brick, gable roof, canvas awning over one window. 7 1036 N
- 66 22 BENEDICT PL c. 1960. One story, frame, cross gable, shed roof porch with balustrade. 23 1035 N
- 67 23 BENEDICT PL c. 1955. Ranch style house, one story, brick, cross gable, interior chimney, 6/6 windows. 8 1036 N
- 68 24 BENEDICT PL c. 1980. One and a half story, frame, gable roof sides, kick off shed roof porch, balustrade, framed chimney, 6/6 windows. 22 1035 N
- 69 25 BENEDICT PL c. 1950. Cottage Revival, one and a half story, brick, gable roof sides, asbestos shingle, three bay facade, hip roof over stoop with tripled square posts each corner, 8/8 windows, pair frame gabled dormers above. 9 1036 C
- 70 26 BENEDICT PL c. 1950. One story, frame, gable roof sides, 8/8 windows, awning over entrance. 21 1035 N This house has replacement siding and a new porch.
- 71 27 BENEDICT PL c. 1960. One story, brick, low hip roof, carport, hip roof over porch with slender iron supports. 10 1036 N
- 72 28 BENEDICT PL c. 1960. Ranch style, one story, brick, gable roof sides, carport recessed porch with two by four railing. 20 1035 N

26 2 05
20 2 00

United States Department of the Interior
National Park Service

National Register Of Historic Places
Continuation Sheet

Section Number 7 Page 16

MID TOWN HISTORIC DISTRICT
Mobile
Mobile County, AL

- 73 1 BIENVILLE AVE c. 1925. Bungalow, one story, frame, gable roof front, three bay facade, attached, offset shed roof porch with battered brick columns and brick knee wall with stone cap, craftsman windows and door, horizontal window in dormer with louvers above. 1 1013 C
- 74 3 BIENVILLE AVE c. 1925. Bungalow, one story, frame, gable roof front, three bay facade, inset porch with battered column on brick plinth at corner, 9/1 windows, louvered vent and knee braces in gable. 2 1013 C
- 75 4 BIENVILLE AVE c. 1925. Bungalow, one and a half story, frame, hip roof with hip roof dormer, recessed porch covers facade, square posts on brick plinths, multi-light door, 9/1 windows, exposed rafters. 25 1014 C
- 76 5 BIENVILLE AVE c. 1945. Craftsman, two story, gable roof sides, stuccoed second story, asbestos sided first story, three bay facade, attached gabled porch with square brick columns, paired 3/1 windows, exposed rafters. 3 1013 C
- 77 6 BIENVILLE AVE c. 1930. Bungalow, one and a half story, stucco, gable roof sides, kick off shed roof porch covers facade, battered boxed columns, one bay infilled with casement windows, shed roof dormer above, exposed rafters. 24 1014 C
- 78 7 BIENVILLE AVE c. 1925. Bungalow, one story, frame, cross gable, attached shed roof porch with battered columns on brick plinths, screened, louvered vent and knee braces in gable. 4 1013 C
- 79 8 BIENVILLE AVE c. 1930. Bungalow, one story, jerkin-head gable front, brick, attached offcenter jerkin-head gable porch with square brick columns, picture window adjacent porch, other windows 1/1, pair louvered vents in porch gable. 23 1014 C
- 80 9 BIENVILLE AVE c. 1925. Bungalow, one and a half story, gable roof sides, frame, kick off shed roof porch covers facade, tripled box columns with capitals at corners, clapboarded knee wall and screened, large shed roof dormer with bank of awning windows, exposed rafters. 5 1013 C
- 81 10 BIENVILLE AVE c. 1925. Bungalow, one and a half story, frame, gable roof sides, recessed porch with paired and tripled boxed columns on brick plinths, balustrade, porte-cochere, gable dormer above. 22 1014 C

cb 9
22

United States Department of the Interior
National Park Service

National Register Of Historic Places
Continuation Sheet

Section Number 7 Page 17

MID TOWN HISTORIC DISTRICT
Mobile
Mobile County, AL

~~82~~ VOID

- 83 11 BIENVILLE AVE c. 1925. Bungalow, one story, cross gable, frame, inset porch with paneled boxed columns on brick plinths, 9/1 windows, chimney up front gable, purlins, exposed rafters, interior chimney. 6 1013 C
- 84 12 BIENVILLE AVE c. 1925. Bungalow, one story, gables front, attached offcenter shed roof porch with square brick columns, casement windows, purlins, louvered vent in main gable. 21 1014 C
- 85 14 BIENVILLE AVE c. 1925. Bungalow, one and a half story, gable roof front, frame, inset porch with paneled boxed columns on brick plinths, casement windows, knee braces in gable, exposed rafters. 20 1014 C
- 86 15 BIENVILLE AVE c. 1925. Bungalow, one story, frame, hip roof, attached offset gable porch with box columns on plinths, paired 3/1 windows, exposed rafters, chimney side elevation and interior. 7 1013 C
- 87 16 BIENVILLE AVE c. 1925. Cottage Revival, two story, stucco, cross gable on hip, 6/6 windows, chimney at front gable, offcenter entrance, exposed rafters. 19 1014 C
- 88 17 BIENVILLE AVE c. 1925. Bungalow, one story, frame, gable roof sides, attached offcenter gable porch with square brick columns, 9/1 windows, craftsman door with sidelights, exposed rafters, interior chimney. 8 1013 C
- 89 19 BIENVILLE AVE c. 1925. Bungalow, one story, frame, hip roof with hip roof dormer with louvered vents, inset porch with ornamental iron support, 6/1 windows, exposed rafters. 9 1013 C
- 90 20 BIENVILLE AVE c. 1940. One story, gable roof sides, frame, paired 6/6 windows, off center entrance with gable over steps supported on paired columns, exposed rafters. 18 1014 C

28 5
72 2

United States Department of the Interior
National Park Service

National Register Of Historic Places
Continuation Sheet

Section Number 7 Page 18

MID TOWN HISTORIC DISTRICT
Mobile
Mobile County, AL

-
- 91 21 BIENVILLE AVE c. 1925. Bungalow, one story, frame, hip roof with attached gable porch with Tuscan columns, Craftsman door with sidelights and transom, craftsman windows, interior chimney, exposed rafters. 10 1013 C
- 92 22 BIENVILLE AVE c. 1925. Bungalow, one story, cross gable, recessed porch with square brick columns, casement windows, multi-light door with sidelights, knee braces in gable, exposed rafters. 17 1014 C
- 93 23 BIENVILLE AVE c. 1925. Bungalow, one story, frame, gable roof front, attached gable porch filled in with clapboarding and three 6/6 windows, interior chimney. 11 1013 C
- 94 24 BIENVILLE AVE c. 1925. Bungalow, one story, frame, gable roof front, recessed porch covers facade, battered, boxed columns on brick plinths, entrance features sidelights and transom, horizontal window in gable, dentil course, open trusswork in gable, purlins, exposed rafters. 16 1014 C
- 95 25 BIENVILLE AVE c. 1925. Bungalow, one and a half story, frame, gable roof sides, gable over stoop supported by wall brackets, brick knee wall across porch, shed roof dormer with bank windows, interior chimney, exposed rafters. 12 1013 C
- 96 26 BIENVILLE AVE c. 1925. Bungalow, one story, frame, gable roof sides, kick off shed roof porch covers facade, multi-light door with transom, tripled 9/1 windows each side, gabled dormer above with louvered vent and quarter fan lights each side, exposed rafters, one interior, one exterior chimney. 15 1014 C
- 97 50 BIENVILLE AVE c. 1925. Bungalow, one story, frame, cross gable, attached shed roof porch covers most of facade, supported on square brick columns, entrance features sidelights, 4/1 windows, vented gable above entrance. 14 1014 C
- 98 51 BIENVILLE AVE c. 1925. Bungalow, one story, jerkin-head gable roof sides, attached shed roof porch on ornamental iron supports, 9/1 windows, exposed rafters. 13 1013 C
- 99 52 BIENVILLE AVE c. 1925. Bungalow, one story, cross gable, vinyl sided, infilled porch, awning over stoop. 13 1014 N

6 8

United States Department of the Interior
National Park Service

National Register Of Historic Places
Continuation Sheet

Section Number 7 Page 19

MID TOWN HISTORIC DISTRICT
Mobile
Mobile County, AL

-
- 100 53 BIENVILLE AVE c. 1925. Bungalow, one story, three bay facade, frame, gable roof front, attached offcenter gable porch with square brick columns on stucco plinths, 3/1 windows, purlins in gables, louvered vent in main gable. 14 1013 C
- 101 54 BIENVILLE AVE c. 1925. Bungalow, one story, frame, gable roof front, recessed porch covers facade, battered, boxed columns on stuccoed plinths, casement windows, fan light over entrance, modified palladian window in gable, knee braces and exposed rafters. 12 1014 C
- 102 55 BIENVILLE AVE c. 1925. Bungalow, one story, frame, gable roof sides, attached gable porch with tripled square posts on brick plinths, screened, 3/1 windows, exposed rafters. 15 1013 C
- 103 56 BIENVILLE AVE c. 1925. Bungalow, one story, frame, gable roof front, recessed porch covers facade, paneled boxed columns on brick plinths, screened and one bay infilled with casement windows with a pent above, purlins and louvered vent in gable. 11 1014 C
- 104 57 BIENVILLE AVE c. 1925. Bungalow, one story, vinyl sided, cross gable, gable over steps supported on ornamental iron support on brick plinth, 3/1 windows, interior chimney. 16 1013 C
- 105 58 BIENVILLE AVE c. 1925. Bungalow, one story, frame, gable roof front, attached offset gable porch supported on battered boxed columns, knee braces in gable, 9/1 windows, pair dormers each side elevation, exposed rafters. 10 1014 C
- 106 59 BIENVILLE AVE c. 1925. Bungalow, one story, frame, gable roof front, attached offset gable porch supported on square brick columns, purlins in gables, shingled main gable, 3/1 windows. 17 1013 C
- 107 60 BIENVILLE AVE c. 1935. Bungalow, one story, cross gable, boxed cornice, closed return, eyebrow dormer, Craftsman windows, louvered vent in gable. 9 1014 C
- 108 61 BIENVILLE AVE c. 1925. Bungalow, one story, frame, gable roof front, recessed porch covers facade, square posts on brick plinths at corners, ornamental iron posts added flanking steps, horizontal light in gable, exposed purlins, louvered vent, exposed rafters. 18 1013 C

269

United States Department of the Interior
National Park Service

National Register Of Historic Places
Continuation Sheet

Section Number 7 Page 20

MID TOWN HISTORIC DISTRICT
Mobile
Mobile County, AL

- 109 63 BIENVILLE AVE c. 1925. Bungalow, one story, frame, gable roof front, attached offset shed roof porch with box columns on stone plinths, jalousied window infill in one bay of porch, stone chimney up facade, 8/1 window. 19 1013 C
- 110 64 BIENVILLE AVE c. 1925. Bungalow, one and a half story, gable roof front, stucco, recessed porch with brick columns and arched openings, screened, pair of lights in gable, gable dormers, exposed rafters. 8 1014 C
- 111 100 BIENVILLE AVE c. 1925. Bungalow, one story, gable roof sides, frame, kick off shed roof porch covers facade, brick supports, gabled dormer, end chimney, shed roof dormer with casement windows in rear ell. 7 1014 C
- 112 101 BIENVILLE AVE c. 1930. Cottage Revival, one story, brick, cross gable roof, gabled entrance with boxed cornice, closed return, arched windows to one side of entrance, paired 6/1 windows opposite side, rounded louvered vent in front gable. 10 1013 C
- 113 104 BIENVILLE AVE c. 1925. Bungalow, one story, frame, hip roof with offcenter attached gable porch supported on box columns on brick plinths, purlins in gable, exposed rafters, interior chimney, paired windows. 6 1014 C
- 114 105 BIENVILLE AVE c. 1925. Bungalow, one story, frame, gable roof front, recessed porch covers facade, box columns on brick plinths, three bay facade, paired 9/1 windows, multi-light door with sidelights, nine pane light flanked by louvers in gable, knee braces, exposed rafters. 22 1013 C
- 115 106 BIENVILLE AVE c. 1925. Bungalow, one story, frame, hip roof with attached offcenter gable porch supported on tripled columns, screened, canvas awnings over windows, lunette over entrance, lunette in gable, knee braces in gable, exposed rafters. 5 1014 C
- 116 107 BIENVILLE AVE c. 1925. Bungalow, one story, frame, gable roof sides, attached gable porch with square brick columns, three bay facade, knee braces, exposed rafters. 23 1013 C
- 117 108 BIENVILLE AVE c. 1930. Bungalow, one story, cross gable, frame, attached, offcenter gable porch, screened, modern flat roof carport to one side, louvered vents in gable, exposed rafters. 4 1014 C

167

United States Department of the Interior
National Park Service

National Register Of Historic Places
Continuation Sheet

Section Number 7 Page 21

MID TOWN HISTORIC DISTRICT
Mobile
Mobile County, AL

- 118 109 BIENVILLE AVE c. 1925. Bungalow, one and a half story, frame, gable roof front, attached offcenter gable porch with battered, paneled, boxed columns on brick plinths, dentil course, eight light window in gable, exposed purlins and rafters, three bay facade, paired 6/1 windows, craftsman door, pop-up gable sun room center of building with 1/1 windows, exposed rafters. 24 1013 C
- 119 110 BIENVILLE AVE c. 1935. Bungalow, one story, cross gables, frame, attached gable over entrance supported by ornamental iron columns, burglar bars over entrance and windows. 3 1014 C
- 120 111 BIENVILLE AVE c. 1925. Bungalow, one story, frame, gable roof sides, attached gable porch with battered stucco columns, screened, eight panel light in gable, knee braces, exposed rafters. 25 1013 C
- 121 112 BIENVILLE AVE c. 1925. Bungalow, one story, frame, hip roof with hip roof dormer, three bay facade, recessed porch covers facade, supported by square posts on brick plinths, french doors have replaced one of the 8/1 windows, main entrance wood door with window, exposed rafters. 2 1014 C
- 122 113 BIENVILLE AVE c. 1925. Bungalow, one story, frame, hip roof, recessed porch covers facade and includes porte-cochere, battered box columns on brick plinths, craftsman door with sidelights, casement windows. 26 1013 C
- 123 114 BIENVILLE AVE c. 1925. Bungalow, one story, frame, cross gables, attached offset gable porch supported on iron posts, 9/1 windows, shingled gables. 1 1014 C
- 124 115 BIENVILLE AVE c. 1925. Bungalow, one story, frame, gable roof front, attached offcenter gable porch with battered boxed columns on brick plinths, screened, knee braces, exposed rafters. 27 1013 C
- 125 117 BIENVILLE AVE c. 1925. Bungalow, one story, vinyl sided, gable roofs front, attached offcenter hip roof porch infilled, craftsman windows, knee braces. 28 1013 N
- 126 119 BIENVILLE AVE c. 1925. Bungalow, one story, frame, gable roof front, attached offcenter gable porch with brick supporting columns and arch, screened, craftsman windows, louvered vent, exposed purlins and rafters. 29 1013 C

cb 8
1

United States Department of the Interior
National Park Service

National Register Of Historic Places
Continuation Sheet

Section Number 7 Page 22

MID TOWN HISTORIC DISTRICT
Mobile
Mobile County, AL

- 127 121 BIENVILLE AVE c. 1925. Bungalow, one story, frame, gable roof front, three bay facade, recessed porch covers facade, one bay infilled with windows, paneled boxed columns on brick plinths, modified palladian window in gable, knee braces, exposed rafters. 30 1013 C
- 128 122 BIENVILLE AVE c. 1925. Bungalow, one story, frame, cross gables, attached gable porch with massive square box columns on brick plinths, three bay facade, craftsman windows, exposed rafters. 35 1013 C
- 129 123 BIENVILLE AVE c. 1925. Bungalow, one story, frame, hip roof with attached, offset gable porch with square brick columns, two bay facade, paired 6/1 windows, entrance flanked by casement windows, exposed purlins and rafters 31 1013 C
- 130 124 BIENVILLE AVE c. 1925. Bungalow, one story, frame, gable roof sides with gable dormer, recessed porch covers facade, ornamental iron supports on brick plinths, three bay facade, exposed purlins and rafters. 34 1013 C
- 131 125 BIENVILLE AVE c. 1925. Bungalow, one story, frame, gable roof front, three bay facade, recessed porch covers facade, battered boxed columns on brick plinths, screened, louvered vent in gable, exposed purlins and rafters. 32 1013 C
- 132 126 BIENVILLE AVE c. 1925. Bungalow, one story, gable roof front, attached offcenter gable porch with paneled boxed columns on brick plinths, 6/1 windows, multi-light door, louvered vents in gables, knee braces, exposed rafters. 33 1013 C
- 133 1 CAMILLA CT c. 1925. Bungalow, two story, frame, jerkin head gable front, three bay facade, multi-light entrance with sidelights, built out surround with ornamental baluster above, paired 3/1 windows one side, tripled 3/1 windows other side, set three large louvered vents in gable, attached two story porte cochere, upper story features frame siding and casement windows, supported on brick pillars, exposed rafters. 21 1006 C
- 134 2 CAMILLA CT c. 1925. Bungalow, two story, brick, jerkin head gable front, three bay facade, pair attached, hip roof porchs flank six panel entrance with hip roof cover and paired 6/6 windows above. Porchs brick first story with aluminum window and vinyl siding infill up to frame second story with tripled 6/6 windows. 22 1006 C
- 135 2 N CARLEN ST c. 1945. Colonial Revival, two story, asbestos sided, gable roof sides, three bay facade, classical gabled portico at entrance with box columns with capitals, 8/8 windows. 10 1017 C

66 9

11-11

United States Department of the Interior
National Park Service

National Register Of Historic Places
Continuation Sheet

Section Number 7 Page 23

MID TOWN HISTORIC DISTRICT
Mobile
Mobile County, AL

- 136 4 N CARLEN ST c. 1935. Bungalow, two story, hip roof, brick, garage apartment with upstairs entrance accessed by iron stairway, flanked by 3/1 windows, exposed rafters. 11 1017 C
- 137 11 S CARLEN ST c. 1970. Two story stucco theatre building, flat roof, two story ornamental iron gallery across facade, paired double aluminum doors. 12 1017 N
- 138 12 S CARLEN ST c. 1925. Bungalow, one story, frame, gable roof front, inset porch, column on brick plinths, Craftsman windows, knee braces, light and flanking louvered vent in gable, exposed rafters. 7 1017 C
- 139 13 S CARLEN ST c. 1940. Colonial Revival, one and a half story, frame, gable roof sides, attached gable over stoop with ornamental iron supports, three bay facade, 6/6 windows, pair gabled dormers with 6/6 windows. 13 1017 C
- 140 14 S CARLEN ST c. 1960. One story, brick, gable roof sides, gable over stoop with ornamental iron supports, picture window has been infilled as window at one end with metal covering. 6 1017 N
- 141 15 S CARLEN ST c. 1940. Vernacular, two story, frame, gable roof sides, three bay facade, inset porch covers two bays, ornamental iron supports, 8/8 windows, box cornice. 14 1017 C
- 142 16 S CARLEN ST c. 1955. One story, brick, cross gable, attached shed roof porch over stoop, paired 6/6 windows. 5 1017 N
- 143 17 S CARLEN ST c. 1940. Cottage, one story, frame, gable roof sides, attached gable porch at center bay with ornamental iron support, early picture window in facade flanked by 1/1 windows, exposed rafters. 15 1017 C
- 144 18 S CARLEN ST c. 1935. Bungalow, one story, frame, gable roof front, offcenter gable porch with Tuscan columns, three bay facade, entrance with transom, paired 1/1 windows one side, french doors the other, knee braces, louvered vent in gable, exposed rafters. 4 1017 C

16
3

United States Department of the Interior
National Park Service

National Register Of Historic Places
Continuation Sheet

Section Number 7 Page 24

MID TOWN HISTORIC DISTRICT
Mobile
Mobile County, AL

-
- 145 19 S CARLEN ST c. 1930. Bungalow, one story, frame, gable roof front, attached offcenter gable porch with square brick columns, metal awnings, timbered and stuccoed gable, louvered vent. 16 1017 C
- 146 20 S CARLEN ST c. 1935. Bungalow, one story, frame, gable roof front, recessed porch covers facade, battered boxed columns on brick plinths, unusual offcenter light in gable probably a later addition, exposed rafters. 3 1017 C
- 147 21 S CARLEN ST c. 1940. One story, gable roof sides, frame, three bay facade, bay window one side entrance. 17 1017 C
- 148 22 S CARLEN ST c. 1930. Bungalow, one story, frame, gable roof front, attached hip roof porch with battered boxed columns on brick plinths, five bay facade, horizontal light and louver in gable, exposed rafters. 2 1017 C
- 149 23 S CARLEN ST c. 1965. Brick veneer, one story, cross gable, concrete unroofed porch covers two bays of three bay facade, ornamental iron railing, six panel door. 18 1017 N
- 150 25 S CARLEN ST c. 1945. Cottage, one story, asbestos sided, cross gable, three bay facade, gable over stoop with wall bracket, paired 3/3 windows, boxed cornice closed return. 19 1017 C
- 151 27 S CARLEN ST c. 1940. Cottage, one story, asbestos sided, gable roof sides, gable over entrance, inset porch, screened, paired 6/6 windows, exposed rafters. 20 1017 C
- 152 29 S CARLEN ST c. 1945. Cottage, one story, gable roof sides, asbestos sided, three bay facade, attached gable porch with ornamental iron supports, paired 6/6 windows, exposed rafters. 21 1017 C
- 153 31 S CARLEN ST c. 1935. Cottage Revival, one story, brick, cross gable on hip with asbestos shingles, four bay facade, canvas bubble awning over entrance, casement and 6/6 windows, round top louvered vent in gable. 22 1017 C

26 8

United States Department of the Interior
National Park Service

National Register Of Historic Places
Continuation Sheet

Section Number 7 Page 25

MID TOWN HISTORIC DISTRICT
Mobile
Mobile County, AL

- 154 33 S CARLEN ST c. 1925. Spanish Colonial Revival, one story, stucco, flat roof with parapet, corner bay with hip roof in tower motif, pierced stucco gable at entrance bay, french doors with lunette one side, paired 6/6 windows in tower, pipe vents in wall above. 23 1017 C
- 155 50 S CARLEN ST c. 1925. Bungalow, one story, frame, gable roof front, recessed porch covers facade, pierced brick columns, Craftsman door with sidelights and fan transom, light and louvered vent in gable, exposed rafters. 1 1017 C
- 156 51 S CARLEN ST c. 1930. Cottage Revival, one story, brick, cross gable, inset porch with arched openings one end, paired 6/1 windows, round top louvered vent in side gable, chimney up front gable, one interior chimney, exposed rafters. 24 1017 C
- 157 52 S CARLEN ST c. 1910. Vernacular, one story, hip roof with hip roof dormer with louvered vent, recessed porch covers four bay facade, battered columns with brackets on brick plinths, entrance features transom, french doors with transoms in other bays. 35 1016 C
- 158 53 S CARLEN ST c. 1925. Bungalow, one story, frame, staggered pair of gable roofs front, inset entrance with pair brick columns, multi-light door, paired 3/1 windows, aluminum window in smaller front gable, louvered vent, exposed rafters. 25 1017 C
- 159 55 S CARLEN ST c. 1925. Bungalow, one story, gable roof sides, stucco, offcenter attached gable porch, square stuccoed columns, arched openings now screened, half-timbered gable with louvered vent, exposed rafters. 26 1017 C
- 160 57 S CARLEN ST c. 1950. Cottage Revival, one story, frame, gable roof sides, inset porch one end with concrete deck and ornamental iron supports and rails, early picture window flanked by 6/6 sash, interior chimney. 27 1017 C
- 161 59 S CARLEN ST c. 1950. Cottage Revival, one story, brick gable roof sides, 8/8 windows, infilled porch one end with aluminum windows, interior chimney. 28 1017 N
- 162 MURPHY HIGH SCHOOL 100 S CARLEN ST 1926. Mission Revival, George B. Rogers, Architect, NR 1982, complex of buildings on the west side of Carlen Street. 1) Main Academic Building; 2) Auditorium; 3) Domestic Arts Building; 4) Cafeteria; 5) Biology Building; 6) Manuel Training Shop. All Spanish Colonial Revival Style featuring red tile roofs, curvilinear gables, ornate low relief carvings and stuccoed exterior walls with straight or arched door and window openings. The Academic Building is the focal point with its central tower. 34 1016 C

7
1

United States Department of the Interior
National Park Service

National Register Of Historic Places
Continuation Sheet

Section Number 7 Page 26

MID TOWN HISTORIC DISTRICT
Mobile
Mobile County, AL

- 163 101 S CARLEN ST c. 1930. Bungalow, one story, frame, gable roof sides, recessed porch covers facade, battered brick columns support frame Tudor arches, paired 3/1 windows, Craftsman door, modern aluminum window center facade, two interior chimneys. 29 1017 C
- 164 105 S CARLEN ST c. 1930. Bungalow, one story, frame, gable sides, three bay facade, offcenter attached gable roof porch, massive battered boxed columns on brick plinths, purlins, light in gable, paired 4/1 windows flank Craftsman door. 30 1017 C
- 165 106 CARLEN ST c. 1925. Bungalow, one story, gable roof front, vinyl sided, recessed porch covers facade, battered stucco columns, knee braces and louvered vent in gable. 18 1041 C
- 166 107 S CARLEN ST c. 1940. Bungalow, one story, gable roof sides, frame, three bay facade, paired 3/1 windows flank multi-light entrance with multi-light sidelights, curved flat roof porch over stoop supported on boxed columns. 31 1017 C
- 167 108 N CARLEN ST c. 1950. One story, vinyl sided, gable roof sides, pair dormers, decorative gable over front door. 19 1041 N
- 168 109 N CARLEN ST c. 1935. Bungalow, one story, frame, gable roof sides, attached shed roof porch covers most of facade, paneled, boxed columns on frame plinths, 6/6 windows. 18 1042 C
- 169 109 S CARLEN ST c. 1930. Bungalow, one story, frame, gable roof sides, attached gable porch with battered, boxed columns on brick plinths, four bay facade, paired 3/1 windows, Craftsman entrance, pair french doors adjacent probably a later addition. 32 1017 C
- 170 110 N CARLEN ST c. 1925. Bungalow, one story, frame, gable roof front, attached offcenter gable porch with paired square posts on brick plinths, louvered vent in main gable, knee braces, 3/1 windows, exposed rafters. 20 1041 C
- 171 111 N CARLEN ST c. 1930. Bungalow, one story, cross gable, attached shed roof porch and portecochere with square brick columns, 6/6 windows, exposed rafters. 17 1042 C

CB 8
113

United States Department of the Interior
National Park Service

National Register Of Historic Places
Continuation Sheet

Section Number 7 Page 27

MID TOWN HISTORIC DISTRICT
Mobile
Mobile County, AL

- 172 111 S CARLEN ST c. 1925. Bungalow, one story, frame, gable roof front, offset gable porch with battered boxed columns on brick plinths, 3/1 windows, multi-light door, knee braces in gables, louvered vents, exposed rafters, awning across porch. 33 1017 C
- 173 112 N CARLEN ST c. 1955. One story, cross gable, asbestos siding, attached shed roof porch over side entrance, 6/6 windows, louvered vents in gable. 21 1041 N
- 174 113 N CARLEN ST c. 1930. Bungalow, one story, frame, jerkin-head gable roof front, inset porch, screened, attached to this is a flat roof porch with square posts on brick plinths, chimney up facade, pair 3/1 windows, purlins, louvered vents. 16 1042 C
- 175 113 S CARLEN ST c. 1939. Bungalow, one story, frame, gable roof front, three bay facade, offset gable porch with ornamental iron supports, 6/6 windows with paneled bottoms and shutters, probably later additions, louvered vent, exposed rafters, one exterior and one interior chimney. 34 1017 C
- 176 114 N CARLEN ST c. 1930. Bungalow, one story, gable roof sides, frame, inset porch with clapboarded knee wall and screened, chimney up front elevation, 3/1 windows, jerkin-head dormer above with louvered vents, purlins. 22 1041 C
- 177 115 N CARLEN ST c. 1930. Bungalow, one story, cross gable, frame, attached offcenter gable porch with battered boxed columns on brick plinths, burglar bars on windows. 15 1042 C
- 178 VOID
- 179 115 S CARLEN ST c. 1925. Bungalow, one story, gable roof sides, perma stone, three bay facade, attached gable porch with square brick columns, louvered vent, knee braces, exposed rafters. 35 1017 C
- 180 116 N CARLEN ST c. 1930/1970. Bungalow, gable roof front, brick and masonite sided, attached gable over entrance, bricked up to window sills on front, picture window at facade, exposed rafters. 23 1041 N

cb 6
23 2

United States Department of the Interior
National Park Service

National Register Of Historic Places
Continuation Sheet

Section Number 7 Page 28

MID TOWN HISTORIC DISTRICT
Mobile
Mobile County, AL

-
- 181 117 N CARLEN ST c. 1970. One story, vinyl sided, cross gable, recessed porch with ornamental iron supports, 6/6 windows. 14 1042 N
- 182 117 S CARLEN ST c. 1925. Bungalow, one story, frame, cross gable, inset porch extends as a gable roofed porte-cochere, square boxed columns on brick plinths, paired 3/1 windows, exposed rafters. 1 1018 C
- 183 118 N CARLEN ST c. 1930. Bungalow, one story, jerkin-head gable front, vinyl sided, chimney up facade, offcenter entrance flanked by 1/1 windows, other windows 3/1, louvered vents. 24 1041 C
- 184 119 N CARLEN ST c. 1930. Bungalow, one story, gable roof front, aluminum sided, offcenter gable porch with square posts, screed,. 13 1042 C
- 185 119 S CARLEN ST c. 1950. Two story, asbestos sided, cross gable, recessed porch with square posts, paired 6/6 windows, modern dormer, garage in one bay filled with aluminum windows. 2 1018 N
- 186 121 N CARLEN ST c. 1930. Bungalow, one story, jerkin-head gable roof front, frame, offcenter jerkin-head gabled porch with square posts on brick plinths, paired 3/1 windows, louvered vent, knee braces, exposed rafters. 12 1042 C
- 187 121 S CARLEN ST c. 1940. Colonial Revival, one and a half story, frame, gable roof sides, attached gable porch at entrance with square columns with capitals, pair large windows flank entrance, pair dormers above with 6/6 windows, screened porch one end, exterior chimney other side elevation. 3 1018 C
- 188 122 N CARLEN ST c. 1930/70. Bungalow, one story, gable roof front, aluminum sided, picture window, inset porch with battered column on brick plinth, knee braces, louvered vent. 25 1041 N
- 189 123 N CARLEN ST c. 1930. Bungalow, one story, cross gable, frame, inset porch with square stucco column, 6/1 windows, exposed rafters. 11 1042 C

eb 6

123 3

United States Department of the Interior
National Park Service

National Register Of Historic Places
Continuation Sheet

Section Number 7 Page 29

MID TOWN HISTORIC DISTRICT
Mobile
Mobile County, AL

-
- 190 123 S CARLEN ST c. 1925. Bungalow, one story, frame, cross gable, recessed porch covers facade, battered boxed columns on brick plinths, paired 6/1 windows flank offcenter multi-light door, interior chimney. 4 1018 C
- 191 124 N CARLEN ST c. 1930. Bungalow, one story, frame, gable sides, attached gable porch on center bay, square columns on brick plinths, 6/6 windows, exposed rafters. 26 1041 C
- 192 125 N CARLEN ST c. 1925. Bungalow, one story, cross gable, frame, recessed porch with battered colons on brick plinths, porte-cochere, 3/1 windows, knee braces, louvered vent, exposed rafters. 10 1042 C
- 193 125 S CARLEN ST c. 1925. International style, two story, stucco, bands of metal casement windows wrap building, flat concrete roof over entrance, brick water table, flat roof. 5 1018 C
- 194 126 N CARLEN ST c. 1930. Bungalow, one story, vinyl sided, jerkin-head gable roof front, metal awning over offcenter stoop, paired windows obscured by metal awning at facade, false shutters, louvered vents in gable. 27 1041 N
- 195 127 N CARLEN ST c. 1930. Bungalow, one story, drop sided, gable roof sides, attached gable porch with Tuscan columns, three bay facade, boxed cornice closed return, lunette louvered vent in gable, picture window in one bay, paired 6/6 windows in other. 9 1042 C
- 196 VOID
- 197 128 N CARLEN ST c. 1955. One story, asbestos sided, gable roof sides, gable over stoop with square posts, inset porch side elevation, interior chimney. 28 1041 N
- 198 129 N CARLEN ST c. 1930. Bungalow, one story, frame, jerkin-head gable front, inset porch with two by four railing, brick veneer on facade up to window sill, false shutters, louvered vent, exposed rafters. 8 1042 N

cb 5
1042

United States Department of the Interior
National Park Service

National Register Of Historic Places
Continuation Sheet

Section Number 7 Page 30

MID TOWN HISTORIC DISTRICT
Mobile
Mobile County, AL

-
- 199 130 N CARLEN ST c. 1925. Bungalow, one story, frame, gable roof front, recessed porch covers facade, battered, boxed columns on brick plinths, inset porch inside this, screened, purlins, louvered vent, exposed rafters. 29 1041 C
- 200 131 N CARLEN ST c. 1940. Bungalow, one story, frame, gable roof front, inset porch, square post, paired 6/6 windows, louvered vent, exposed rafters. 7 1042 C
- 201 132 N CARLEN ST c. 1930. Bungalow, one story, frame, staggered gable roofs front, inset porch with paneled, boxed column, paired 3/1 windows, board and batten gables, louvered vent in dominant gable, exposed rafters. 30 1041 C
- 202 133 N CARLEN ST c. 1930. Bungalow, one story, asbestos sided, gable roof front, inset porch, paneled, boxed column, screened, louvered vent and light in gable, windows and entrance boarded. 6 1042 C
- 203 134 N CARLEN ST c. 1930. Bungalow, one story, frame, gable roof front, offset gable porch with ornamental iron supports on brick plinths, paired craftsman windows flank wood door, large louvered vent in dominant gable. 31 1041 C
- 204 135 N CARLEN ST c. 1930. Bungalow, one story, frame, gable front, three bay facade, offset gable porch, battered columns on brick plinths, exposed rafters. 5 1042 C
- 205 136 N CARLEN ST c. 1925. Bungalow, one story, frame, gable roof front, recessed porch covers facade, boxed columns on brick plinths, infilled with 1/1 windows and clapboarding, metal awnings, louvered vent, exposed rafters. 32 1041 C
- 206 137 N CARLEN ST c. 1930. Bungalow, one story, frame, gable roof front, recessed porch covers facade, battered boxed columns on brick plinths, three bay facade, paired 3/1 windows flank Craftsman door, exposed rafters. 4 1042 C
- 207 138 N CARLEN ST c. 1965. Ranch style, one story, brick, gable roof front, flat roof over stoop, frame garage apartment in front, offset with flat carport attached. 33 1041 N

06 8

1041

United States Department of the Interior
National Park Service

National Register Of Historic Places
Continuation Sheet

Section Number 7 Page 31

MID TOWN HISTORIC DISTRICT
Mobile
Mobile County, AL

-
- 208 139 N CARLEN ST c. 1935. Bungalow, one story, frame, gable roof front, three bay facade, offcenter gable porch with square posts on brick plinths, paired 3/1 windows flank multi-light door, exposed rafters. 3 1042 C
- 209 143 N CARLEN ST c. 1940. Cottage Revival, one story, gable roof sides, asbestos sided, brick gabled surround at entrance, 6/6 windows, attached shed roof porch adjacent entrance with column, interior chimney, exposed rafters. 2 1042 C
- 210 144 N CARLEN ST c. 1900. Victorian cottage, one story, frame, gabled bay on hip, recessed porch abutts bay, non-historic ornamental iron columns and railing, 2/2 windows, louvered vent and pent in gable, boxed cornice. 34 1041 C
- 211 145 N CARLEN ST c. 1930/80. Bungalow, one story, vinyl sided, gable roof front, offcenter attached gable porch with brick columns, infilled with vinyl siding and large aluminum window, louvered vents in gable. 1 1042 N
- 212 146 N CARLEN ST c. 1930. Bungalow, one story, gable roof front, frame, recessed porch covers facade, square posts, lattice railing, knee braces, exposed rafters. 35 1041 C
- 213 159 S CARLEN ST c. 1925. Bungalow, one story, frame, gable roof sides, attached offcenter gable porch with square brick columns, 6/6 windows, modified Palladian window/vent in gable, boxed cornice, porte-cochere. 7 1018 C
- 214 161 S CARLEN ST c. 1925. Bungalow, one story, frame, cross gable, recessed porch covers facade, boxed battered columns on brick plinths, paired 3/1 windows, purlins, louvered vent, exposed rafters, exterior chimney. 8 1018 C
- 215 182 S CARLEN ST c. 1940. Cottage Revival, one story, stucco, gable roof sides, casement windows, attached gable entrance porch with arched opening accented by brickwork. 33 1016 C
- 216 184 S CARLEN ST c. 1940. Colonial Revival, frame, gable roof sides, three bay facade, gabled entrance surround with pilasters, 8/8 windows, attached gabled carport one end. 32 1016 C

cb 8

United States Department of the Interior
National Park Service

National Register Of Historic Places
Continuation Sheet

Section Number 7 Page 32

MID TOWN HISTORIC DISTRICT
Mobile
Mobile County, AL

- 217 185 S CARLEN ST c. 1930. Bungalow, one story, frame with vinyl siding added, cross gable, recessed porch with square posts, paired 3/1 windows. 9 1018 N
- 218 187 S CARLEN ST c. 1935. Cottage Revival, one story, brick, cross gable, inset porch with arched openings, paired 6/1 windows, boxed cornice closed return, louvered lunette vents in gables, exterior chimney. 10 1018 C
- 219 188 S CARLEN ST 1936. Colonial Revival, C. L. Hutchisson, Jr. Architect, two story, brick apartment building, three bay facade, gable roof sides with centered gable bay, six-panel entrance with sidelights and transom, Georgian surround, paired 6/6 windows, paired half lunette vents in gables. 31 1016 C
- 220 215 S CARLEN ST c. 1940. Garage apartment, two story, two auto bays below, gable roof front, inset porch, door boarded up, louvered vent, exposed rafters. 30 1016 C
- 221 8 S CARLEN ST c. 1945. One story, frame, pair of staggered gables front, inset entrance with square post with capital, paired 6/6 windows, louvered vent in secondary gable, interior chimney. 9 1017 C
- 222 10 S CARLEN ST c. 1910. Vernacular, one story, frame, hip roof, five bay facade, attached hip roof porch with square posts on brick plinths covers three bays, 2/2 windows, door with window and transom, porch is a later c. 1920s replacement, boxed cornice. 8 1017 C
- 223 1807 CLEARMONT ST c. 1950. One story, frame, gable roof sides, inset porch, multi-light windows, attached carport. 27 1005 C
- 224 1809 CLEARMONT ST c. 1925. Bungalow, one story, gable on hip, frame, attached gable porch wraps facade with gable to side, battered boxed columns on brick plinths, balustrade, six panel entrance with sidelights, paired 3/1 windows, louvered vent, exposed rafters, interior chimney. 26 1005 C
- 225 1811 CLEARMONT ST c. 1925. Bungalow, one story, frame, gable roof front, recessed porch covers three bay facade, boxed columns on brick plinths, entrance flanked by set french doors and paired 6/1 windows, modified Palladian window in gable, knee braces, exposed rafters. 25 1005 C

eb 5
ms

United States Department of the Interior
National Park Service

National Register Of Historic Places
Continuation Sheet

Section Number 7 Page 33

MID TOWN HISTORIC DISTRICT
Mobile
Mobile County, AL

-
- 226 1813 CLEARMONT ST c. 1925. Bungalow, one story, frame, staggered gable roofs front, attached offcenter gable porch with battered columns on brick plinths, pair entrances, one later, paired 3/1 windows, louvered vent, exposed rafters. 24 1005 C
- 227 1815 CLEARMONT ST c. 1925. Bungalow, one story, gable front, frame, attached offcenter gable porch with box columns, louvered vent, six panel front door with sidelights, 3/1 windows, exposed rafters. 23 1005 C
- 228 1817 CLEARMONT ST c. 1925. Bungalow, one story, gable on hip roof, frame, two bay facade, attached gable roof porch wraps facade, battered boxed columns on brick plinths, multi-light entrance with sidelights, louvered vent, purlins, exposed rafters. 22 1005 C
- 229 1819 CLEARMONT ST c. 1925. Bungalow, one story, vinyl sided, cross gable, attached shed roof porch with battered brick pillars covers half facade, interior chimney, multi-light door, paired 6/1 windows, purlins. 21 1005 C
- 230 1820 CLEARMONT ST c. 1925. Cottage Revival, two and a half story, stucco, gable roof sides, three bay facade, attached offcenter one story gable porch with stucco columns, glassed in, pair gable roof dormers, exterior chimney. 15 1005 C
- 231 1822 CLEARMONT ST c. 1925. Bungalow, one story, cross gable, frame, H-shape with attached shed roof porch with square brick columns between gables, 3/1 windows, entrance flanked by french doors, interior chimney, knee braces, exposed rafters. Modern carport to one side. 16 1005 C
- 232 1826 CLEARMONT ST c. 1945. Colonial Revival, one and a half story, frame, gable roof sides, three bay facade, attached gable over stoop supported on ornamental iron posts, paired 6/6 windows, pair dormers above, one story gable wings each side, slightly set back. 17 1005 C
- 233 1837 CLEARMONT ST c. 1945. Garage apartment, two story, frame, gable roof front, pair auto bays with double wooden doors, paired 3/1 windows above, attached gable entrance side elevation, louvered vent, exposed rafters. 20 1005 C
- 234 1839 CLEARMONT ST c. 1945. Gulf Coast Cottage Revival, one and a half stories on raised brick piers, frame, gable sides, attached gable porch covers three bays of five bay facade, boxed columns with capitals, 8/8 windows, pair gable dormers with 6/6 windows, exterior chimney. 19 1005 C

cb 7

United States Department of the Interior
National Park Service

National Register Of Historic Places
Continuation Sheet

Section Number 7 Page 34

MID TOWN HISTORIC DISTRICT
Mobile
Mobile County, AL

-
- 235 1843 CLEARMONT ST c. 1950. Cottage Revival, one story, brick, cross gable, H plan, kick-off shed roof porch with square posts, iron balustrade, paired 6/6 windows, interior chimney. 18 1005 C
- 236 1901 CLEARMONT ST c. 1960. Ranch house, one story, cross gable, frame, recessed porch covers facade, square posts with ornamental iron brackets, gables adjacent with metal window awnings, louvered vent. 28 1005 N
- 237 1905 CLEARMONT ST c. 1945. Two story, brick, gable roof front, hip roof wing with paired 8/8 windows, carport below, modern double glass doors in facade, paired 8/8 windows adjacent, louvered vent. 29 1005 C
- 238 1907 CLEARMONT ST c. 1950. Minimal Traditional, one and a half story, brick veneer over frame, three bay facade, 12/12 windows flank hip roof over stoop with ornamental iron supports, three gable dormers with 6/6 windows. 30 1005 N
- 239 1909 CLEARMONT ST c. 1925. Bungalow, one story, brick gable roof sides, five bay facade, water table, attached gable porch covers three bays, square brick pillars, stucco with half timbering in gable, 3/1 windows, exposed rafters, exterior chimney. 31 1005 C
- 240 1911 CLEARMONT ST c. 1945. Minimal Traditional, one and a half story, frame, gable roof sides, inset porch with square posts, four bay facade, 8/8 windows, pair dormers with 12/12 windows, interior chimney. 32 1005 C
- 241 1913 CLEARMONT ST c. 1935. Cottage Revival, one and a half story, brick, gable roof sides, six bay facade, 6/6 windows, gable with wall brackets over entrance, arched window one end, pair gabled dormers with 6/6 windows, interior chimney. 33 1005 C
- 242 1915 CLEARMONT ST c. 1945. Colonial Revival, one story, frame, gable roof sides, three bay facade, gable with classical surround at entrance, flanked by 12/12 windows with ornamental iron burglar bars, pair gabled dormers with 6/6 windows, exterior chimney. 34 1005 C
- 243 1917 CLEARMONT ST c. 1925. Bungalow, one story, frame, hip roof with hip roof projecting bay, attached gable with square posts at entrance adjacent, multi-light front door with narrow sidelights, light in gable, exterior chimney. 35 1005 C

26 7

27 7

United States Department of the Interior
National Park Service

National Register Of Historic Places
Continuation Sheet

Section Number 7 Page 35

MID TOWN HISTORIC DISTRICT
Mobile
Mobile County, AL

-
- 244 1919 CLEARMONT ST c. 1950. Minimal Traditional, one story, brick, gable roof sides, attached gable over entrance with iron supports, six panel door, 12/12 windows, exterior chimney. 1 1006 C
- 245 1921 CLEARMONT ST c. 1930. Cottage Revival, one story, brick, gable roof sides, gabled garage attached fronts street, solid door, metal casement windows, garage features wooden car door, octagonal light above and louvered vent above that. 2 1006 C
- 246 1923 CLEARMONT ST c. 1925. Bungalow, one story, frame, gable roof sides, attached gable porch with pierced brick columns, paired 3/1 windows, attached gabled screen porch one end, exposed rafters. 3 1006 C
- 247 1957 CLEARMONT ST c. 1925. Bungalow, one story, gable roof front, frame and brick, two bay facade, inset porch (originally a full porch now sympathetically half filled in) with square boxed column on brick plinth, ornamental iron railing, Craftsman door with sidelights and transom, paired Craftsman windows, brick veneer up to window sill level on facade, Craftsman light with flanking louvers in gable, purlins, exposed rafters. 4 1006 C
- 248 1959 CLEARMONT ST c. 1930. Bungalow, one story, frame, staggered gables front, attached gabled porte-cochere extends across half of facade as porch, original wndows replaced with metal picture window. 5 1006 N
- 249 1961 CLEARMONT ST c. 1925. Bungalow, one story, frame, hip roof, attached off center gabled porch with battered columns on brick plinths, Craftsman door, paired 1/1 windows, light flanked by louvered vents in gable, purlins, exposed rafters. 6 1006 C
- 250 2003 CLEARMONT ST c. 1925. Bungalow, one story, gable roof front, frame, recessed porch covers facade, battered columns on brick plinths, paired 3/1 windows flank solid door, gabled porte cochere, purlins, exposed rafters. 7 1006 C
- 251 2104 CLEARMONT ST c. 1960. Two story garage apartment, gable roof sides, 6/6 windows, side entrance first story, wood stairway at gable end with shed roof covered doorway, exposed rafters. 9 1006 N
- 252 2105 CLEARMONT ST c. 1950. Two story, brick, gable roof sides, two bay facade, side entrance with metal awning, pair shuttered windows. 8 1006 C
- 16 2

United States Department of the Interior
National Park Service

National Register Of Historic Places
Continuation Sheet

Section Number 7 Page 36

MID TOWN HISTORIC DISTRICT
Mobile
Mobile County, AL

- 253 2156 CLEARMONT ST c. 1950. Two story garage apartment, gable roof sides, frame, three open automobile bays, pair 6/6 windows above with false shutter motif, shed roof entrance with metal steps one end. 13 1006 C
- 254 2157 CLEARMONT ST c. 1960. Two story, garage apartment, gable roof sides, double auto bays with solid panels, entrance adjacent with gable over stoop, paired 3/1 windows above. 10 1006 N
- 255 2159 CLEARMONT ST c. 1960. One story, asbestos sided, gable roof sides, attached shed roof porch with ornamental iron supports, carport one end, paired 6/6 windows and picture window with flanking lights, exposed rafters. 11 1006 N
- 256 2161 CLEARMONT ST c. 1925. Bungalow, two story, stucco with brick quoins, gable roof sides, three bay facade, attached gable porch with iron supports on brick plinths, gable stuccoed and half timbered, paired 3/1 windows, exposed rafters. 12 1006 C
- 257 1824 CONTI ST c. 1950. Two story garage apartment, gable roof sides, asbestos sided, one auto bay one end with solid panels, central horizontal panel door, pair doors other end with flat roof porch with ornamental iron supports, paired 6/6 windows above. 16 1006 C
- 258 1826 CONTI ST c. 1925. Bungalow, one story, frame, hip roof, offcenter gable porch with square brick pillars, three bay facade, paired 3/1 windows, modern front door, knee braces, louvered vent, exposed rafters. 17 1006 C
- 259 1828 CONTI ST c. 1945. Minimal Traditional, one story, vinyl sided, cross gable, attached gable over entrance with ornamental iron supports, aluminum windows, louvered vent. 18 1006 N
- 260 1830 CONTI ST c. 1950. Minimal Traditional, one story, gable roof sides, three bay facade, attached offcenter gable porch with ornamental iron supports, 8/8 windows, six panel door, small louvered lunette in gable, exterior chimney. 19 1006 C
- 261 1837 CONTI ST c. 1925. Bungalow, one story, vinyl sided, gable roof front, three bay facade, attached offcenter gable porch with square brick columns, screened, paired 3/1 windows, louvered vents, exterior chimney. 20 1006 C

26
27

United States Department of the Interior
National Park Service

National Register Of Historic Places
Continuation Sheet

Section Number 7 Page 37

MID TOWN HISTORIC DISTRICT
Mobile
Mobile County, AL

-
- 262 4 CRENSHAW ST c. 1925. Bungalow, one story, gable roof front, vinyl sided, inset porch with pierced brick column, two bay facade, louvered vent. 28 1030 C
- 263 5 CRENSHAW ST c. 1945. Minimal Traditional, one story, gable roof sides, frame, three bay facade, 8/8 windows with ornamental shutters, six panel door with fabric awning over stoop. 29 1030 C
- 264 6 CRENSHAW ST c. 1950. Minimal Traditional, one story, gable roof front, vinyl sided, aluminum windows and door, louvered vent. 27 1030 N
- 265 8 CRENSHAW ST c. 1945. Minimal Traditional, one story, gable roof front, frame, attached hip roof porch with ornamental iron supports abutts gable bay, 6/6 windows with fabric awnings, louvered vent. 26 1030 C
- 266 10 CRENSHAW ST c. 1950. Minimal Traditional, one story, gable roof front, vinyl sided, three bay facade, inset porch with ornamental iron supports, metal awnings over windows, chimney at facade, louvered vent. 25 1030 C
- 267 12 CRENSHAW ST c. 1955. Minimal Traditional, one story, gable roof sides, vinyl sided, four bay facade, 6/6 windows with one false shutter apiece, attached gable over stoop with wall brackets. 24 1030 N
- 268 21 CRENSHAW ST c. 1925. Bungalow, one story, gable roof front, frame, gable on hip porch with square posts and balustrade, three bay facade, louvered vent, exposed rafters. 30 1030 C
- 269 25 CRENSHAW ST c. 1925. Bungalow, one and a half story, gable roof sides, frame, recessed porch covers facade, Tuscan columns, three bay facade, paired 6/1 windows, shed roof dormer above with three horizontal lights, end chimney. 31 1030 C
- 270 50 CRENSHAW ST c. 1945. Minimal Traditional, one story, cross gable, frame, attached gable over entrance stoop, tripled 6/1 windows one side, gable bay other side. Gables are stuccoed with half-timbering, exposed rafters. 23 1030 C

cb =
10

United States Department of the Interior
National Park Service

National Register Of Historic Places
Continuation Sheet

Section Number 7 Page 38

MID TOWN HISTORIC DISTRICT
Mobile
Mobile County, AL

-
- 271 52 CRENSHAW ST 1997. Neo Creole, one and a half story, frame, gable roof sides, recessed porch covers facade, box columns, fanlight over door, three dormers, aluminum windows with flat baked enamel finish. 22 1030 N
- 272 54 CRENSHAW ST c. 1940. Cottage Revival, one story, cross gable, frame, inset porch with arched opening and ornamental iron support, paired 6/1 windows in front gable, louvered vent above, tripled diamond paned windows adjacent, exposed rafters. 21 1030 C
- 273 56 CRENSHAW ST c. 1980. Neo-Creole, one story, gable roof sides, three bay facade, recessed porch covers facade, square posts with balustrade, 9/1 aluminum windows. 20 1030 N
- 274 59 CRENSHAW ST c. 1945. Minimal Traditional, one story, gable roof sides, frame, four bay facade, 8/8 windows, attached gable over entrance with ornamental iron supports. 32 1030 C
- 275 61 CRENSHAW ST c. 1945. Minimal Traditional, one story, gable front with hip wing, frame, six panel door with canvas awning over stoop, 6/1 windows with shutters, narrow louvered vent in gable, box cornice closed return. 33 1030 C
- 276 63 CRENSHAW ST c. 1925. Bungalow, one story, frame, gable sides, paired 6/6 windows, attached gable porch at center bay has been infilled with multi-light windows, exposed rafters. 34 1030 C
- 277 68 CRENSHAW ST c. 1940. Minimal Traditional, one story, cross gable, vinyl sided, recessed porch in one gable, brick arched openings, infilled with jalousies and vinyl, tripled 3/1 windows. 19 1030 N
- 278 70 CRENSHAW ST c. 1925. Bungalow, one story, hip roof, frame, offcenter gable porch with square brick pillars and brick arches, heavy brick balustrade, multi-light door with round top transom, paired 3/1 windows flank, louvered vent in gable, scalloped bargeboard, exposed rafters. 18 1030 C
- 279 100 CRENSHAW ST c. 1960. Ranch Style, one story, gable roof sides, brick, shed roof porch with ornamental iron supports covers two bays of three bay facade, metal casement windows. 17 1030 N

ch 5
100

United States Department of the Interior
National Park Service

National Register Of Historic Places
Continuation Sheet

Section Number 7 Page 39

MID TOWN HISTORIC DISTRICT
Mobile
Mobile County, AL

-
- 280 101 CRENSHAW ST c. 1955. One story, gable roof sides, asbestos sided, attached gable porch at entrance with ornamental iron supports. 35 1030 N
- 281 102 CRENSHAW ST c. 1925. Bungalow, one story, hip roof, frame, attached gable porch covers most of three bay facade, square posts, screened, stucco knee wall, entrance features fan light transom and sidelights, light with flanking louvers in gable, box cornice closed return. 16 1030 C
- 282 103 CRENSHAW ST c. 1930. Bungalow, one story, cross gable, vinyl sided, offcenter porch has been infilled with aluminum windows, tripled 3/1 windows in main gable. 1 1031 C
- 283 104 CRENSHAW ST c. 1970. Ranch Style, one story, brick, hip roof, recessed porch with slender columns and balustraded, aluminum windows. 15 1030 N
- 284 105 CRENSHAW ST c. 1945. Minimal Traditional, one story, gable roof sides, asbestos sided, attached gable with iron supports at entrance, inset screened porch adjacent, paired 12/12 windows. 2 1031 C
- 285 106 CRENSHAW ST c. 1960. One story, gable roof sides, frame, attached hip roof porch at entrance with iron supports, windows shaded by metal awnings, exterior chimney. 14 1030 N
- 286 107 CRENSHAW ST c. 1950. Minimal Traditional, one story, gable roof sides, brick, three bay facade, six panel door sheltered by attached gable, pair 6/6 windows one side, casement windows other side, boxed cornice. 3 1031 C
- 287 108 CRENSHAW ST c. 1935. Bungalow, one story, cross gable, frame, recessed porch, screened opens into gabled porte cochere with battered columns on brick plinths, paired 3/1 windows, 6/6 window in gable. 13 1030 C
- 288 109 CRENSHAW ST c. 1930. Bungalow, one and a half story, cross gable, aluminum sided, recessed porch with battered column on brick knee wall abutts front gable, gable features tripled 3/1 windows shaded by canvas awning, 3/1 window above, boxed cornice closed return. 4 1031 C

United States Department of the Interior
National Park Service

National Register Of Historic Places
Continuation Sheet

Section Number 7 Page 40

MID TOWN HISTORIC DISTRICT
Mobile
Mobile County, AL

-
- 289 110 CRENSHAW ST c. 1940. Bungalow, one story, gable roof front, asbestos sided, offcenter gable porch with square brick pillars and screened, paired 6/6 windows, louvered vent, exposed rafters. 12 1030 C
- 290 111 CRENSHAW ST c. 1950. Minimal Traditional, one story, gable roof sides, inset porch covers two bays of three bay facade, ornamental iron supports, picture window and six panel door, paired 6/6 windows, louvered vent. 5 1031 C
- 291 112 CRENSHAW ST c. 1945. Minimal Traditional, one story, cross gable, frame, attached gable with slender non-historic turned posts at entrance, paired 3/1 windows, louvered vent. 11 1030 C
- 292 113 CRENSHAW ST c. 1925. Bungalow, one story, cross gable, frame, recessed porch abutts dominant front gable, square brick column, tripled 3/1 windows with light and louvered vents in gable, boxed cornice closed return. 6 1031 C
- 293 114 CRENSHAW ST c. 1980. One and a half story, gable roof sides, vinyl sided, inset center bay with entrance, Bermuda shutters on all windows, pair gable dormers above with Bermuda shutters. 10 1030 N
- 294 115 CRENSHAW ST c. 1925. Bungalow, one story, gable roof sides, frame, attached gable porch with square brick pillars, gabled porte cochere extends to one side with square pillars, tripled and paired 3/1 windows, hip roof dormer with louvered vent, knee braces, exposed rafters. 7 1031 C
- 295 116 CRENSHAW ST c. 1960. One story, cross gable, brick, inset porch with ornamental iron support, 8/8 windows, six panel door, box cornice closed return. 9 1030 N
- 296 117 CRENSHAW ST c. 1945. One story, hip roof, asbestos sided, hip roof projecting block with inset porch, open wood columns with "x" pattern, round four light window adjacent. 8 1031 C
- 297 118 CRENSHAW ST c. 1930. Bungalow, one story, cross gable, frame, recessed porch abutts front gable, square brick pillar and knee wall, tripled 3/1 windows, box cornice, closed return. 8 1030 C

CL 2

CL 2

United States Department of the Interior
National Park Service

National Register Of Historic Places
Continuation Sheet

Section Number 7 Page 41

MID TOWN HISTORIC DISTRICT
Mobile
Mobile County, AL

-
- 298 119 CRENSHAW ST c. 1960. One story, gable roof sides, vinyl sided, four bay facade, 6/6 windows, awning over entrance. 1 1031 N
- 299 122 CRENSHAW ST c. 1970. Ranch Style, one story, hip roof, inset porch, aluminum windows, four bay facade, box cornice. 7 1030 N
- 300 150 CRENSHAW ST c. 1920. Bungalow, one and a half story, high hip roof, frame, recessed porch covers five bay facade, square posts and balustraded, 6/1 windows, hip roof dormers each elevation with casement windows, exposed rafters. 6 1030 C
- 301 152 CRENSHAW ST c. 1960. One story, gable roof sides, brick, attached combination hip roof porch and porte cochere with ornamental iron supports, paired 3/1 windows. 5 1030 N
- 302 153 CRENSHAW ST c. 1945. Colonial Revival, two story, gable roof sides, brick, attached shed roof porch with full height box columns covers porch, 8/8 windows, six panel door, end chimney, shuttered first floor windows. 10 1031 C
- 303 154 CRENSHAW ST c. 1925. Bungalow, one story, gable front, frame, three bay facade, attached offcenter gable with square pillars, gabled porte cochere, louvered vent, exposed rafters. 4 1030 C
- 304 155 CRENSHAW ST c. 1930. Bungalow, one story, hip roof, frame, attached offcenter gable porch with box columns, louvered vent. 11 1031 C
- 305 156 CRENSHAW ST c. 1925. Bungalow, one story, gable roof front, frame, offcenter gable porch with square brick pillars and screened, 6/1 windows, louvered vent in porch gable, exposed rafters. 3 1030 C
- 306 157 CRENSHAW ST c. 1945. Cottage Revival, one story, cross gable, asbestos sided, curving shed roof porch abutts gable bay, square posts, 6/1 windows. 12 1031 C

cb L

11

United States Department of the Interior
National Park Service

National Register Of Historic Places
Continuation Sheet

Section Number 7 Page 42

MID TOWN HISTORIC DISTRICT
Mobile
Mobile County, AL

-
- 307 159 CRENSHAW ST c. 1945. Minimal Traditional, one story, gable roof sides, frame, three bay facade, attached gable porch with ornamental iron supports, solid door, flanking paired 9/9 windows with ornamental iron burglar panels lower half of sash, boxed cornice closed return. 13 1031 C
- 308 160 CRENSHAW ST c. 1960. Ranch Style, one story, brick, cross gable, recessed porch with ornamental iron supports abutts dominant gable, metal casement windows. 2 1030 N
- 309 161 CRENSHAW ST c. 1945. Minimal Traditional, one story, gable roof sides, frame, three bay facade, 12/12 windows flank six panel door with gabled classical surround. 14 1031 C
- 310 162 CRENSHAW ST c. 1925. Bungalow, one story, gable roof front, frame, recessed porch covers three bay facade, square brick pillars, side entrance with sidelights, louvered vent, purlins, exposed rafters. 1 1030 C
- 311 163 CRENSHAW ST c. 1960. One story, cross gable, asbestos sided, recessed porch adjacent front gable, paired windows, screened, louvered vent. 15 1031 N
- 312 165 CRENSHAW ST c. 1950. Minimal Traditional, one story, cross gable, asbestos sided, inset porch, paired 6/6 windows, round top louvered vent. 16 1031 C
- 313 167 CRENSHAW ST c. 1930. Bungalow, one story, gable sides, frame, attached gable porch at center bay of three bay facade, square posts and balustraded, door with window, flanked by 3/1 windows, louvered vent, exposed rafters, end chimney. 17 1031 C
- 314 169 CRENSHAW ST c. 1945. Minimal Traditional, one and a half story, frame, gable roof sides, three bay facade, attached gable at entrance with ornamental iron supports, six panel door, flanked by 12/12 windows, pair dormers with six light windows, exposed rafters. 18 1031 C
- 315 171 CRENSHAW ST c. 1960. One story, gable sides, asbestos sided, attached gable porch with iron supports, metal awnings over windows. 19 1031 N

16 C
17 E

United States Department of the Interior
National Park Service

National Register Of Historic Places
Continuation Sheet

Section Number 7 Page 43

MID TOWN HISTORIC DISTRICT
Mobile
Mobile County, AL

- 316 225 CRENSHAW ST c. 1930. Bungalow, one story, cross gable, frame, prominent center projecting bay with aluminum windows, knee braces, louvered vent, exposed rafters. 22 1031 C
- 317 225 CRENSHAW ST c. 1935. Cottage Revival, cross gable, brick, attached shed roof porch with square posts, two bay facade, 6/6 window, louvered vent above, one story outbuilding in yard. 20 1031 C
- 318
- 319 254 CRENSHAW ST c. 1935. Colonial Revival, one story, cross gable, asbestos sided, recessed porch under cross gable, Tuscan columns, classical surround at entrance, louvered vent in gable. 35 1029 C
- 320 256 CRENSHAW ST c. 1950. Minimal Traditional, one story, gable roof sides, asbestos sided, attached offcenter gable porch with ornamental iron supports, attached flat roof carport, multi-light window with sidelights right of door, 6/6 sash to left. 34 1029 C
- 321 257 CRENSHAW ST c. 1925. Bungalow, one story, frame, hip roof, three bay facade, paired 3/1 windows, recessed porch with square posts covers facade, gable above, louvered vent, exposed rafters. 32 1031 C
- 322 258 CRENSHAW ST c. 1935. Bungalow, one story, vinyl sided, cross gable, recessed porch covers half facade, screened, paired 3/1 windows in gable. 33 1029 C
- 323 259 CRENSHAW ST c. 1940. Minimal Traditional, one story, gable roof front, frame, attached offcenter gable porch with square posts and balustrade, side entrance, 6/6 windows, louvered vents, box cornice. 24 1031 C
- 324 260 CRENSHAW ST c. 1975. Ranch house, one story, low hip roof, brick, inset porch with car bay with metal door, round steel supports. 32 1029 N

26 7 25
225 2 225

United States Department of the Interior
National Park Service

National Register Of Historic Places
Continuation Sheet

Section Number 7 Page 44

MID TOWN HISTORIC DISTRICT
Mobile
Mobile County, AL

-
- 325 261 CRENSHAW ST c. 1945. Minimal Traditional, one story, cross gable, frame, inset porch, screened with metal awnings, exterior chimney, boxed cornice. 25 1031 C
- 326 262 CRENSHAW ST c. 1950. Minimal Traditional, one story, cross gable, frame, attached shed roof porch covers three bays, ornamental iron posts, 8/8 window in front gable. 31 1029 C
- 327 263 CRENSHAW ST c. 1945. Minimal Traditional, one story, gable roof sides, frame, three bay facade, attached gable porch with square posts at entrance, flanked by 6/6 windows, multi-light door, exposed rafters. 26 1031 C
- 328 264 CRENSHAW ST c. 1925. Bungalow, one story, jerkin head gable front, vinyl sided, three bay facade, offcenter jerkin head gable porch with pierced brick columns, paired 3/1 windows. 30 1029 C
- 329 267 CRENSHAW ST c. 1925. Bungalow, one story, gable roof front, frame, three bay facade, offcenter attached gable porch with square posts, entrance flanked by metal casement windows on one side and aluminum windows on the other, purlins, louvered vents, exposed rafters. 27 1031 C
- 330 1820 DAUPHIN ST c. 1910. Colonial Revival, two story, hip roof, frame, three bay facade, attached one story flat roof, balustraded porch covers facade, Tuscan columns and balustraded first story, central hall entrance, flanking 9/1 windows, Palladian window center bay second story. 21 1007 C
- 331 1808 DAUPHIN ST c. 1910. American Foursquare, two story, hip roof, frame, three bay facade, attached two story hip roof porch, Ionic columns first story, Tuscan columns and balustraded second story, side hall entrance features door with window, sidelights and transom, classical surround, pair multi-light doors adjacent, full height window in third bay, 1/1 windows, exposed rafters. 17 1007 C
- 332 1804 DAUPHIN ST c. 1910. American Foursquare, two story, hip roof, frame, three bay facade, 1/1 windows, entrance with sidelights and transom, attached one story flat, balustraded roof porch covers facade, Tuscan columns below, two interior chimneys with corbeled caps. 15 1007 C
- 333 1806 DAUPHIN ST c. 1910. American Foursquare, two story, hip roof, vinyl sided, attached one story flat roof porch with modern iron balustrade above and Ionic columns for support covers facade, double front doors with transom, full height windows, exterior chimney. 16 1007 C

United States Department of the Interior
National Park Service

National Register Of Historic Places
Continuation Sheet

Section Number 7 Page 45

MID TOWN HISTORIC DISTRICT
Mobile
Mobile County, AL

- 334 1807 DAUPHIN ST c. 1925. Spanish Colonial Revival, one story, cross jerkin head gable, ceramic tile roof, stucco, ell plan, four bay facade, two entrances, one in each ell, doors not visible due to elaborate ornamental iron burglar screens, transoms, shed roof over entrance facing street, end chimney, round louvered vents, 6/6 windows. 25 1010 C
- 335 1809 DAUPHIN ST c. 1910. American Foursquare, two story, hip roof, frame, two bay facade, side entrance, wood door with window, sidelights and transom, 1/1 windows, box cornice, side chimney. 24 1010 C
- 336 1814 DAUPHIN ST c. 1910. Neo-Classical Revival, two story, hip roof, frame, attached full height gabled pedimented portico with Ionic columns and full entablature, louvered vent, side hall entrance with sidelights and transom, attached one story flat roof porch covers facade, and runs behind the portico, Ionic columns and balustraded deck, French door with transom open onto deck, boxed cornice, stuccoed interior chimney with corbeled cap. 18 1007 C
- 337 1815 DAUPHIN ST c. 1925. Tudor Revival, one story, cross gables, stucco, ell plan, entrance under attached gable with half-timbering, paired square posts, casement windows with planter boxes, dominant gable at facade features attached clock between windows, clapboarded gable, chimney at front with paired pots, one interior chimney with pots, secondary gable west adjacent dominant gable with half-timbering, no cornice. 23 1010 C
- 338 1816 DAUPHIN ST c. 1910. American Foursquare, two story, hip roof, frame, two bay facade, recessed porch covers facade, Ionic columns at first story, Tuscan columns and balustraded second story, side hall entrance with sidelights and transom, 1/1 windows, exposed rafters, bay window west elevation. 19 1007 C
- 339 1817 DAUPHIN ST c. 1925. Tudor Revival, one story, cross gable, ell plan, stucco, attached offcenter gable porch at front gable, paired square posts with brackets, half-timbering, multi-light door, casement windows, brick single shoulder chimney at facade, louvered vents. 22 1010 C
- 340 1818 DAUPHIN ST c. 1910. American Foursquare, two story, hip roof, frame, three bay facade, recessed porch covers facade, first story features two front doors with transoms, infilled bay with casement windows with transoms, second story Ionic columns and balustraded, exterior stuccoed chimney with corbeled cap. 20 1007 N
- 341 1819 DAUPHIN ST c. 1955. One and a half story, cross gable on hip roof, stucco and brick, three bay facade with carport west adjacent, attached offcenter hip roof porch with ornamental iron supports and drop frieze, metal casement windows, hip roof dormers east and west elevations, box cornice, triangular louvered vent in gable, paired 6/6 windows in front gable. 21 1010 N
- 342 1821 DAUPHIN ST c. 1930. Minimal Traditional, two story gable roof sides, frame, three bay facade, centered entrance, six panel door, attached one story gable porch on Tuscan columns over entrance, paired 6/1 windows, shed pent divides first and second story. 20 1010 C

United States Department of the Interior
National Park Service

National Register Of Historic Places
Continuation Sheet

Section Number 7 Page 46

MID TOWN HISTORIC DISTRICT
Mobile
Mobile County, AL

- 343 1822 DAUPHIN ST c. 1900. Victorian, one story, hip roof, frame, five bay facade, recessed porch covers facade, Tuscan columns and balustraded, entrance features double doors with transom, slide-by windows, interior chimneys, box cornice closed return, hip roof dormers side elevations. 22 1007 C
- 344 1826 DAUPHIN ST c. 1900. Queen Anne Style, one story, gable on hip roof, five bay facade, attached hip roof porch covers facade, turned posts and balustraded with gable over steps, front door with window, full height windows, round top louver in dominant gable, two interior chimneys with corbeled caps. 23 1007 C
- 345 1827 DAUPHIN ST c. 1955. Ranch Style, one story, hip roof, four bay facade, brick, six panel door inset in one corner of front block, square post, metal casement windows, interior chimney, box cornice. 19 1010 N
- 346 1828 DAUPHIN ST c. 1910. American Foursquare, two story, hip roof, frame, two bay facade, recessed porch covers facade, Ionic columns, entrance with window, sidelights and transom, french doors with transoms at second story, 1/1 windows at side elevations, interior chimney, exposed rafters. 24 1007 C
- 347 1831 DAUPHIN ST c. 1925. Tudor Revival, one story, cross gables, stucco, ceramic tile roof, ell plan, entrance center of facade with shed roof porch extending east from front gable, paired square posts with brackets, half-timbering in gables, side chimney. 18 1010 C
- 348 1832 DAUPHIN ST 1916. Bungalow, C. L. Hutchisson, Sr. Architect, two story, gable roof front, frame, two bay facade, attached one story shed roof porch covers facade and partially wraps west elevation, Tuscan columns, entrance features sidelights and transom, Craftsman window adjacent with sidelights, paired 9/1 windows above, stuccoed and half timbered gable with knee braces, three small 1/1 windows, exposed rafters. 25 1007 C
- 349 1833 DAUPHIN ST c. 1945. Minimal Traditional, one and a half story, gable roof sides, brick, four bay facade, centered entrance slightly inset, six panel door, tripled 6/6 windows east adjacent with ornamental iron below, paired 6/6 windows with shutters, pair gable dormers with 6/6 windows, interior chimney, round top louvered vent, box cornice. 17 1010 C
- 350 1835 DAUPHIN ST 1912. Neo-Classical Revival, C. L. Hutchisson, Sr. architect, two story, cross gable, ell plan, vinyl sided, three bay facade, side hall plan, wood door with sidelights, fan transom, French doors with transoms, 6/6 windows second story, full height recessed porch covers facade, Ionic columns, full entablature, dentil course, lunette louvered vent in gable, Ionic column at corner of ell, two exterior chimneys, two story modern studio rear of property with privacy fence. 16 1010 C
- 351 1851 DAUPHIN ST c. 1910. American Foursquare, two story, hip roof, frame, two bay facade, full height recessed porch covers facade, paired paneled boxed columns, side hall plan, multi-light door with sidelights, tripled 9/6 windows with eared surround, box cornice, interior chimney. 15 1010 C

United States Department of the Interior
National Park Service

National Register Of Historic Places
Continuation Sheet

Section Number 7 Page 47

MID TOWN HISTORIC DISTRICT
Mobile
Mobile County, AL

- 352 1852 DAUPHIN ST c. 1945. Minimal Traditional, one and a half story, gable roof sides, brick, four by two bays, attached gable at entrance with square posts, paired 4/1 windows, interior chimney, boxed cornice closed return. 26 1007 C
- 353 1853 DAUPHIN ST c. 1910. American Foursquare, two story, high hip roof, frame, two bay facade, attached one story hip roof porch covers facade, paneled boxed columns, side hall plan, wood door with window, sidelights and transom, 1/1 windows with shutters, interior chimney with corbeled cap, box cornice, wood picket fence with gate around house. 14 1010 C
- 354 1855 DAUPHIN ST c. 1910. American Foursquare, two story, hip roof, vinyl sided, two bay facade, attached one story hip roof porch covers facade and wraps around east elevation, Tuscan columns, side hall plan, four panel door with sidelights, 1/1 windows, box cornice, interior chimney, picket fence with gate. 13 1010 C
- 355 1856 DAUPHIN ST c. 1925. Bungalow, one story, gable roof front, frame, recessed porch covers facade, square stuccoed pillars, screened, horizontal multi-light window in gable, knee braces, tripled 9/1 windows, exposed rafters. 27 1007 C
- 356 1858 DAUPHIN ST c. 1925. Bungalow, one story, gable roof sides, frame, recessed porch covers facade, with gable at center bay on paired square posts on brick plinths, screened with iron balustrade, knee braces, louvered vent, exposed rafters, interior chimney. 28 1007 C
- 357 1860 DAUPHIN ST c. 1930. Colonial Revival, one story, cross gable, frame, three bay facade, recessed porch with boxed columns and balustrade covers facade, six panel door with sidelights and transom, 6/1 windows, lunette louvered vent in gable, exposed rafters, two exterior chimneys. 29 1007 C
- 358 VOID
- 359 1900 DAUPHIN ST 1853, moved 1946. Gothic Revival, Trinity Episcopal Church, Frank Willis and James Dudley, Architects in 1853, C.L. Hutchisson, Jr., Architect for 1946 move from downtown, NR 1990, brick, rectangular nave with chancel, side aisles, sacristy and a tower at the southwest corner, two story with a basement raised eighteen brick courses above ground and a stone water table, facade divided into three divisions with the tower on the west, central bay and side aisle on the east. 30 1007 C
- 360 1901 DAUPHIN ST c. 1955. Ranch Style, one story, hip roof, brick, three bay facade, door with oval glass, inset porch with ornamental iron corner support, metal casement windows with shutters, box cornice. 11 1010 N

United States Department of the Interior
National Park Service

National Register Of Historic Places
Continuation Sheet

Section Number 7 Page 48

MID TOWN HISTORIC DISTRICT
Mobile
Mobile County, AL

- 361 1905 DAUPHIN ST c. 1920. Colonial Revival, two story, hip roof, vinyl sided, three bay facade, off center entrance, six panel door with sidelights and transom, attached hip roof one story porch covers stoop, tripled Tuscan columns each corner, tripled 6/1 windows west adjacents, bank metal casement windows east adjacent, box cornice. 10 1010 C
- 362 1906 DAUPHIN ST c. 1945. Colonial Revival, two story, brick, gable roof sides, attached full height shed roof porch with box columns covers facade, five bay facade, double doors with transom, balcony above at center bay only, 6/6 windows with shutters. 32 1007 C
- 363 1907 DAUPHIN ST c. 1910. Vernacular, one story, gable on hip roof front, frame, three bay facade, central hall plan, wood door with window, transom in classical surround, attached hip roof porch over stoop, box columns with capitals, 2/2 windows with shutters, box cornice. 9 1010 C
- 364 1908 DAUPHIN ST c. 1930. Two story, hip roof, frame, four bay facade, side hall entrance, attached one story flat roof balustraded porch covers facade, iron supports with elaborate brackets, balustraded first story, 6/6 windows, exposed rafters, exterior chimney. 33 1007 C
- 365 1911 DAUPHIN ST c. 1910. Neo-Classical Revival, two story, hip roof, frame, five bay facade, side entrance, four panel door with sidelights and transom, attached one story flat roof bracketed porch with Tuscan columns covers stoop, full height 9/1 windows at facade, three interior chimneys, box cornice. 8 1010 C
- 366 1912 DAUPHIN ST c. 1945. Colonial Revival, two story, hip roof, brick, three bay facade, attached one story portico at entrance, Tuscan columns and balustraded deck, six panel door with sidelights and fan transom, 12/12 windows with shutters, box cornice, eyebrow light in roof. 34 1007 C
- 367 1953 DAUPHIN ST c. 1925. Beaux Arts Style, two story, hip roof, stucco, three bay facade, central hall plan, four panel door with sidelights and lunetted transom, attached one story flat roof porch with Palladian opening, pair Ionic columns support arch matching lunette transom, square pillars at corner, iron railing on porch roof, entrance flanked by casement windows with lunette transoms, 8/8 windows second story, bracketed cornice, two end chimneys, one story porte-cochere east side, two story garage rear. 7 1010 C
- 368 2000 DAUPHIN ST 1851, 1903, 1910. Queen Anne, Greene-Marston House, Termite Hall, NR 1983, two and a half story, cross gable, original 1851 one and a half story cottage enlarged in 1903 and in 1910 first floor windows replaced by French doors with transoms, entrance features sidelights and transom, attached two story shed roof porch wraps around facade, turned posts with curved brackets create arcaded effect. second floor balustraded, bargeboard in gable, interior features oak wainscoting. 35 1007 C
- 369 2003 DAUPHIN ST c. 1920. Bungalow, two and a half story, hip roof, ceramic tile, stucco, three bay facade, central hall plan, wood door with window, sidelights, fan transom, pair lions in repose flank steps, recessed two story porch covers facade, first story features stucco pillars with capitals, second paired and tripled Tuscan columns on boxed plinths, balustraded, French doors flank entrance first floor,

United States Department of the Interior
National Park Service

National Register Of Historic Places
Continuation Sheet

Section Number 7 Page 49

MID TOWN HISTORIC DISTRICT
Mobile
Mobile County, AL

-
- 369 hip roof dormer with tripled windows with diamond lights, box cornice. 5 1010 C
- 370 2004 DAUPHIN ST c. 1910. Dutch Colonial Revival, one and a half story, gambrel roof sides, frame, three bay facade, recessed porch with massive Tuscan columns covers half of facade, 9/9 windows, shed roof dormer with 6/6 windows, interior chimney with pots. 1 1008 C
- 371 2005 DAUPHIN ST c. 1925. Bungalow, two story, hip roof, frame, three bay facade, inset central entrance, wood door, flanking bays feature paired 6/6 windows with corner brick pillars in west bay, this may have originally been open porch, hip roof between stories at facade, dentil course, paired 6/6 windows second floor, hip roof dormer with louvered vent, bracketed cornice. 4 1010 C
- 372 2007 DAUPHIN ST c. 1925. Working Man's Foursquare, one story, hip roof, frame, three bay facade, central hall plan,, recessed porch covers facade, paired box columns with capitals on low clapboarded plinths, wood door with window, transom, French doors flank entrance, transoms, hip roof dormer with louvered vent, exposed rafters, two chimneys, one interior one to side. 3 1010 C
- 373 2008 DAUPHIN ST c. 1925. Bungalow, one story, gable roof front, frame, recessed porch covers three bay facade, Craftsman door with sidelights, paired Craftsman windows, box columns on clapboarded knee wall, louvered vent in gable with Craftsman sidelights, knee braces, exposed rafters, exterior chimney. 2 1008 C
- 374 2009 DAUPHIN ST c. 1920. Bungalow, one and a half story, hip roof, frame, two bay facade, recessed porch covers facade, battered box columns on clapboarded plinths, balustraded, side entrance, six panel door with multi-light sidelights and transom, tripled 6/1 window west adjacent, hip roof dormer with louvered vent and flanking lights, exposed rafters. 12 1010 C
- 375 2011 DAUPHIN ST c. 1925. Bungalow, one story, gable roof sides, frame, two bay facade, inset porch covers half of facade, battered box column at corner on brick plinth, multi-light door with flanking narrow 6/1 windows with shutters, tripled 6/1 windows with shutters in east bay, stuccoed gable with verticle boards, purlins, exposed rafters, interior chimney. 1 1010 C
- 376 2012 DAUPHIN ST c. 1925. Bungalow, two story, hip roof, vinyl sided, attached one story hip roof porch over entrance with Tuscan columns on brick plinths, bay window above, entrance features sidelights and transom, paired 9/1 windows, hip roof dormer with louvered vent and flanking lights. 3 1008 C
- 377 2013 DAUPHIN ST c. 1910. Neoclassical Revival, two story, hip roof, aluminum sided, four bay facade, two story recessed porch covers facade with full height boxed columns with capitals, balustraded second story, 6/1 windows, door with window and transom, hip roof dormer with louvered vent, box cornice, interior chimney. 35 1009 C

United States Department of the Interior
National Park Service

National Register Of Historic Places
Continuation Sheet

Section Number 7 Page 50

MID TOWN HISTORIC DISTRICT
Mobile
Mobile County, AL

- 378 2014 DAUPHIN ST c. 1900. Vernacular, one story, gable roof sides, frame, four bay facade, recessed porch covers facade, slender Tuscan columns and balustraded, French doors in facade. 4 1008 C
- 379 2016 DAUPHIN ST c. 1900. Colonial Revival, one story, hip roof, frame, three bay facade, recessed porch covers facade, Tuscan columns and balustraded, front door has window and sidelights and transom, French doors flank entrance with transoms, exposed rafters. 5 1008 C
- 380 2017 DAUPHIN ST c. 1915. Working Man's Foursquare, one story, hip roof, frame, recessed porch with paired Tuscan columns on brick plinths covers facade and wraps east side where there is a separate entrance with sidelights, front door has large window, sidelights and transom, French doors, hip dormer above with Craftsman lights. 34 1009 C
- 381 2020 DAUPHIN ST c. 1900. Vernacular, one story, gable on hip roof front, frame, three bay facade, recessed porch with boxed columns covers facade, full height windows on facade, 2/2 windows side elevations, louvered vent, two interior chimneys with corbeled caps, boxed cornice. 6 1008 C
- 382 2021 DAUPHIN ST c. 1940. Colonial Revival, two story, gable on hip roof, three bay facade, attached one story gable porch with paired boxed columns, 6/6 windows, six panel door with sidelights. 33 1009 C
- 383 2050 DAUPHIN ST c. 1930. Bungalow, one and a half story,, gable roof sides, four bay facade, inset porch with pair round columns, pair dormers above with paired 1/1 windows, other windows 6/1. 7 1008 C
- 384 2051 DAUPHIN ST c. 1910. Workingman's Foursquare, one story, hip roof, frame, four bay facade, inset porch wraps east side, door with pair windows, sidelights and transom, ornamental iron supports, 2/2 windows, hip roof dormer with louvered vent, boxed cornice. 32 1009 C
- 385 2052 DAUPHIN ST c. 1940. Cottage Revival, one story, gable roof sides, frame and stucco, unusual center gable with arched carriageway below, recessed porch either side with square pillars on a stucco knee wall, two bays either side of carriageway, front door either side carriageway with paired 3/1 windows adjacent, louver vent in gable, exposed rafters. 8 1008 C
- 386 2053 DAUPHIN ST c. 1955. One story, gable on hip, brick, recessed porch covers facade, ornamental iron supports and railing, six panel door, tinted glass windows, louver in gable 31 1009 N

16 8
12

United States Department of the Interior
National Park Service

National Register Of Historic Places
Continuation Sheet

Section Number 7 Page 51

MID TOWN HISTORIC DISTRICT
Mobile
Mobile County, AL

- 387 2054 DAUPHIN ST c. 1965. International Style, one story, flat roof, brick, open carport, plate glass windows. 9 1008 N
- 388 2055 DAUPHIN ST c. 1910. American Foursquare, two story, hip roof, frame, three bay facade, recessed two story porch covers facade, Tuscan columns first and second story, balustraded second story, wood door with window, sidelights and transom, 2/2 windows, interior chimney, exposed rafters. 30 1009 C
- 389 2056 DAUPHIN ST 1936. Bungalow, C. L. Hutchisson, Jr. Architect, first FHA House in Mobile, one story, gable roof front, vinyl sided, three bay facade, recessed porch covers facade, pierced brick columns, multi-light door, paired windows, three pane light with flanking louvers in gable. 10 1008 C
- 390 2057 DAUPHIN ST c. 1945. Minimal Traditional, one and a half story, gable roof sides, three bay facade, attached gable bay with six panel door, 8/8 windows, pair gable dormers with 6/6 windows. 29 1009 C
- 391 2058 DAUPHIN ST c. 1900. Victorian, one story, frame, gable on hip roof, gabled bay window at facade, recessed porch with turned posts and balustrades abutts and wraps around east side, abutting gable wing, 6/6 windows, boxed cornice. 11 1008 C
- 392 2061 DAUPHIN ST c. 1925. Bungalow, one and a half story, gable roof front, frame, three bay facade, inset porch with Craftsman door, 9/1 window, battered stuccoed column, knee braces in gable, gabled dormers side elevations, exposed rafters, Craftsman window in front gable. 28 1009 C
- 393 2062 DAUPHIN ST c. 1970. Modern Commercial, one story, flat roof, cinderblock with brick facade, narrow windows from grade up, inset entrance. 12 1008 N
- 394 2067 DAUPHIN ST c. 1925. Bungalow, one story, gable roof front, frame, two bay facade, attached offcenter gable porch with battered columns on brick plinths, Craftsman door with sidelights, paired 2/2 windows, knee braces, louvered vent, interior chimney, exposed rafters. 27 1009 C
- 395 2069 DAUPHIN ST c. 1925. Bungalow, one story, gable roof front, frame, attached offcenter gable porch with square brick pillars and screened, casement windows, knee braces, exposed rafters. 26 1009 C

56 7
2

United States Department of the Interior
National Park Service

National Register Of Historic Places
Continuation Sheet

Section Number 7 Page 52

MID TOWN HISTORIC DISTRICT
Mobile
Mobile County, AL

- 396 2071 DAUPHIN ST c. 1925. Bungalow, one story, cross gable, frame, dominant gable front offcenter features stone chimney up front, knee braces, attached gable porch attached perpendicular, infilled with clapboarding and screened, square brick pillars, exposed rafters. 25 1009 C
- 397 2073 DAUPHIN ST c. 1940. Minimal Traditional, one story, gable roof sides with gable ell, frame, three bay facade, attached one story gable porch at entrance with square posts, louvered vent, tripled 3/1 windows one side, bank awning windows opposite, end chimney. 24 1009 C
- 398 2150 DAUPHIN ST c. 1940. Neo-Creole,, one and a half story,, gable roof sides,, recessed porch covers facade, square posts and balustraded, three bay facade, 8/8 windows, entrance features sidelights and transom, pair gable dormers with 6/6 windows, exterior chimney, box cornice. 13 1008 C
- 399 2151 DAUPHIN ST c. 1940. Bungalow, cross gable, frame, attached gable porch covers facade, infilled with aluminum windows, clapboarding, knee braces, louvered vent, exposed rafters. 23 1009 C
- 400 2153 DAUPHIN ST c. 1925. Bungalow, one story,, gable roof front, attached gable porch with box columns on brick plinths, recessed porch covers entire facade, boxed columns on brick plinths, paired 9/1 windows, Craftsman door, knee braces and louvered vents, exposed rafters, pair interior chimneys. 22 1009 C
- 401 2154 DAUPHIN ST c. 1905. Neoclassical Revival, two story, gable on hip roof, frame, three bay facade, side hall plan, recessed two story porch with full height Tuscan columns with full entablature, balcony behind columns at second floor, balustraded and supported on wall brackets, full height windows, entrance features oval window, sidelights and transom, modified Palladian window in gable, boxed cornice with eave brackets. 14 1008 C
- 402 2155 DAUPHIN ST c. 1910. Working Man's Foursquare, one story, hip roof, frame, three bay facade, recessed porch covers facade, Tuscan columns on clapboarded plinths, door with window, Craftsman sidelights and transom, porch wraps south elevation, multi-light door with transom here, hip roof dormer with louvered vents, exterior chimneys with corbeled caps. 21 1009 C
- 403 2156 DAUPHIN ST c. 1900. Queen Anne/Free Classic, two story, gable on hip roof, aluminum sided, three bay facade, attached one story hip roof porch covers facade, boxed columns on boxed bases, door features oval window, sidelights and transom, 1/1 windows, two story gable bay west end of facade, two interior chimneys. 15 1008 C
- 404 2157 DAUPHIN ST c. 1910. Working Man's Foursquare, one story, hip roof, frame, three bay facade, recessed porch covers facade, box columns, door with window and sidelights and transom, craftsman windows, hip roof dormer with louvered vent, boxed cornice. 20 1009 C

United States Department of the Interior
National Park Service

National Register Of Historic Places
Continuation Sheet

Section Number 7 Page 53

MID TOWN HISTORIC DISTRICT
Mobile
Mobile County, AL

- 405 2158 DAUPHIN ST c. 1925. Bungalow,, one and a half story, gable roof sides,, recessed porch covers facade, square brick pillars, west bay filled with multi-light window, door covered by ornamental iron burglar door, sidelights and transom, gable dormer with tripled 6/6 windows, lunette light above, purlins, interior chimney. 16 1008 C
- 406 2159 DAUPHIN ST c. 1960. Providence Baptist Church, two story, hip roof, brick, attached gabled portico with full height boxed columns with capitals and entablature, pair double six paneled wooden doors, three stained glass windows above, suspended light from portico ceiling, stanined glass windows to either side of portico, metal louvered vent in gable. 19 1009 N
- 407 2162 DAUPHIN ST c. 1910. Victorian, one story, gable on hip roof, four bay facade, attached shed roof porch covers facade, square columns with capitals and bases, full height 2/2/2 windows, double doors with windows, transom, louvered vent with flanking lights in gable, bargeboard in gable, boxed cornice. 17 1008 C
- 408 2164 DAUPHIN ST c. 1945. Minimal Traditional, one story,, gable roof sides, frame, attached gabled entrance, 6/6 windows, three by three bays, pair skylights in roof, end chimney. 18 1008 C
- 409 2166 DAUPHIN ST c. 1940. Neo-Palladian, one story, cross gable, stucco, extraordinary house, most likely architect-designed, though by whom is not known, very formal and classically proportioned, four bay facade with pair gables at facade, quoins at corners and around entrance and defining carport opening on east end of building, triangular louvered vents in gables, boxed cornice, closed return, 6/6 windows with shutters. 19 1008 C
- 410 2200 DAUPHIN ST c. 1900. Victorian, one story, high hip roof, frame, three bay facade, attached hip roof porch covers facade, Tuscan columns, gable dormer above with louver, 2/2 windows, four panel door with sidelights and transom, box cornice, interior brick chimney with corbeled cap. 20 1008 C
- 411 2201 DAUPHIN ST c. 1925. Cottage Revival, one story, stucco, cross gables, pair staggered gables slightly offcenter, entrance a round top wooden door with iron railings at steps, casement windows with fanlight one side, bank casement windows opposite, gable dormer with round top louvered vent, exterior chimney, exposed rafters. 18 1009 C
- 412 2202 DAUPHIN ST c. 1900. Neoclassical Revival, two story, gable on hip roof, frame, two bay facade, side hall plan, double doors with windows, sidelights and fan transom,, recessed porch covers facade, full height box columns with capitals, balcony at second floor window over entrance, balustraded with wall brackets, 1/1 windows, louver in gable, box cornice. 21 1008 C
- 413 2203 DAUPHIN ST c. 1945. Minimal Traditional, one story, gable roof sides, frame, grouped 3/1 windows, gable bay one end with purlins, interior chimney, entrance around side. 17 1009 C
- eb
- 220

United States Department of the Interior
National Park Service

National Register Of Historic Places
Continuation Sheet

Section Number 7 Page 54

MID TOWN HISTORIC DISTRICT
Mobile
Mobile County, AL

- 414 2204 DAUPHIN ST c. 1925. Bungalow, one story,, gable roof front, frame, attached gable porch offcenter with square brick columns, gable bay adjacent with tripled windows, knee braces, round vents in gables, interior chimney, exposed rafters. 22 1008 C
- 415 2206 DAUPHIN ST c. 1930. Bungalow, one story, gable roof front, vinyl sided, attached offcenter gable porch with square brick columns, plank raling, casement windows, door with multi-light windows above center. 23 1008 C
- 416 2208 DAUPHIN ST c. 1945. Minimal Traditional, one story,, gable roof sides, attached gable porch at center, six bay facade, two front doors, square stuccoed columns, 3/1 windows, exposed rafters, end chimney. 24 1008 C
- 417 2209 DAUPHIN ST c. 1945. Minimal Traditional, two story, gable roof sides, frame, three bay facade, attached hip roof porch over entrance, ornamental iron supports and frieze panel, 12/12 windows first floor, 6/6 second floor, end chimney. 16 1009 C
- 418 2251 DAUPHIN ST c. 1910. American Foursquare, two story, hip roof, frame, three bay facade, attached one story flat roof porch covers most of facade, paired boxed columns with capitals, screened, ornamental iron railing above, multi-light French doors, 6/6 windows, triangular louvered vent in roof, box cornice. 15 1009 C
- 419 2252 DAUPHIN ST c. 1935. Colonial Revival, two story, brick, gable roof sides, three bay facade, paired 6/6 windows, six panel door, gable above, end chimneys, one story gable wings east and west elevations. 25 1008 C
- 420 2255 DAUPHIN ST c. 1900. Queen Anne, one story, hip roof with gables front, frame, gabled bay with pent, 2/2 windows, board and batten gable with multi-light window and louvers above in gable, larger gable staggered behind with shingled gable and round louvered vent, entrance six panel door with classical surround, inset porch adjacent with Tudor arch, Tuscan column, ornamental iron railings above and below, boxed cornice. 14 1009 C
- 421 2300 DAUPHIN ST c. 1945. Minimal Traditional, one and a half story, gable roof sides, seven bay facade, 9/9 windows, six panel door, attached gable at entrance with round columns, pair gabled dormers with 6/6 window each, box cornice closed return. 26 1008 C
- 422 2302 DAUPHIN ST c. 1945. Minimal Traditional, one story, gable roof sides, frame, three bay facade with one bay gable roof sides wing, attached gable over entrance with paired slender columns, 12/12 windows, end chimney. 27 1008 C

United States Department of the Interior
National Park Service

National Register Of Historic Places
Continuation Sheet

Section Number 7 Page 55

MID TOWN HISTORIC DISTRICT
Mobile
Mobile County, AL

- 423 2303 DAUPHIN ST c. 1945. Minimal Traditional, one story, gable roof sides, frame, attached gable over entrance, ornamental iron supports, 9/9 windows, end chimney, gable wing one end. 13 1009 C
- 424 2304 DAUPHIN ST c. 1945. Cottage Revival, one story, brick, cross gable, attached gable over entrance with square posts, chimney adjacent, three bay facade, 12/12 windows. 28 1008 C
- 425 2306 DAUPHIN ST c. 1945. Minimal Traditional, one story, cross gable, brick, attached gable over entrance with ornamental iron supports, chimney adjacent, casement windows, metal awnings over some windows, louvered vent. 29 1008 C
- 426 2310 DAUPHIN ST c. 1945. Minimal Traditional, one story, hip roof, brick, five bay facade, attached hip roof over entrance with ornamental iron supports, 12/12 windows, corbeled cornice, box eaves, interior chimney. 30 1008 C
- 427 2312 DAUPHIN ST c. 1945. Minimal Traditional, one and a half story, gable roof sides, asbestos sided, three bay facade, attached gable over entrance with ornamental iron supports, three gabled dormers above with single pane windows, mixed windows at first story, 2/2 and 9/6, neither probably original, end chimney. 31 1008 C
- 428 2314 DAUPHIN ST c. 1950. Minimal Traditional, one story, gable roof sides, asbestos sided, three bay facade, attached gable over entrance with ornamental iron supports, six panel door, windows feature two horizontal panes over two horizontal panes. 32 1008 C
- 429 2316 DAUPHIN ST c. 1920. Vernacular, one story, gable on hip roof, frame, three bay facade, attached hip roof porch covers two bays, massive square brick pillars, wood door with window, 2/2 window in one bay, paired 4/4 windows in other bay, box cornice. 33 1008 C
- 430 2318 DAUPHIN ST c. 1945. Minimal Traditional, one story, gable roof sides, frame, inset, screened porch east side with square corner pillar, attached gable at entrance, square brick columns, paired 3/1 windows, round top louvered vent in gable, end chimney. 34 1008 C
- 431 2320 DAUPHIN ST c. 1945. Minimal Traditional, one story, gable roof sides, frame, four bay facade with gable wing east end, 6/6 windows, six panel door slightly inset. 35 1008 C

cb 9

United States Department of the Interior
National Park Service

National Register Of Historic Places
Continuation Sheet

Section Number 7 Page 56

MID TOWN HISTORIC DISTRICT
Mobile
Mobile County, AL

-
- 432 2322 DAUPHIN ST c. 1945. Minimal Traditional, one story, gable roof sides, frame with brick veneer facade, three bay facade, 6/6 windows, six panel door, one interior and one exterior chimney. 1 1009 N
- 433 2400 DAUPHIN ST c. 1945. Minimal Traditional, one story, cross gable, brick, four bay facade, no porch, 12/12 windows, chimney at facade. 2 1009 C
- 434 2402 DAUPHIN ST c. 1945. Minimal Traditional, one story, gable roof sides, frame, three bay facade, attached gable with wall brackets over entrance, six panel door, multi-light window one side, 8/8 window other side. 3 1009 C
- 435 2404 DAUPHIN ST c. 1955. Garage apartment, two story, asbestos sided, gable roof sides, two auto bays first story with wood doors and windows at top, paired 6/6 windows second story with metal awnings, staircase east end. 4 1009 N
- 436 2406 DAUPHIN ST c. 1945. Minimal Traditional, one story, gable roof sides, frame, attached gable over entrance with ornamental iron supports, six panel door with sidelights and fan transom, paired 8/8 windows. 5 1009 C
- 437 2408 DAUPHIN ST c. 1945. Minimal Traditional, one story, gable roof sides, frame, three bay facade with gable wing one end, paired 6/6 windows, attached gable at entrance with paired columns, six panel door with sidelights, interior chimney, metal awning over windows in wing. 6 1009 C
- 438 2450 DAUPHIN ST c. 1945. Minimal Traditional, one story, cross gable, frame, three bay facade, side entrance with attached gable supported on ornamental iron supports, six panel door with sidelights and fan transom, chimney adjacent with round top niche, 12/12 window center bay, inset screened porch with ornamental iron balustrade and canvas awning adjacent, pair gabled dormers above, lunette vent in porch gable. 7 1009 C
- 439 2452 DAUPHIN ST c. 1945. Minimal Traditional, gable roof sides, frame, gable ell rear, three bay facade, attached gable over entrance with Tuscan columns, paired 9/9 windows one side, multi-light window other side, end chimney, louvered vents. 8 1009 C
- 440 2454 DAUPHIN ST c. 1950. Minimal Traditional, one story, cross gable, frame, three bay facade, L shape, recessed porch with ornamental iron supports, multi-light window, ornamental iron burglar door, window screen and bargeboard in front gable. 9 1009 C

United States Department of the Interior
National Park Service

National Register Of Historic Places
Continuation Sheet

Section Number 7 Page 57

MID TOWN HISTORIC DISTRICT
Mobile
Mobile County, AL

-
- 441 2456 DAUPHIN ST c. 1945. Minimal Traditional, one story, cross gable, frame, L shape, paired 6/6 windows, no porch, entrance in side of front L, box cornice. 10 1009 C
- 442 2458 DAUPHIN ST c. 1930. Bungalow, one story, brick, gable roof sides, attached gable porch central portion of house, arched openings with ornamental iron infill, round top entrance with ornamental iron burglar door, brick steps with cheeks, round top louver vent, paired 3/1 windows flank porch, exposed rafters, end chimney. 11 1009 C
- 443 2460 DAUPHIN ST c. 1965. One story, cross gable L plan, frame with brick veneer facade, recessed porch abutts front gable, ornamental iron posts, 9/9 windows. 12 1009 N
- 444 3 DEMOUY AVE c. 1975. Two story, frame over brick, hip roof, gable over entrance supported on square posts, paired 6/6 windows. 26 1014 N
- 445 4 DEMOUY AVE 1913. Bungalow, two story, hip roof, frame, three bay facade, attached one story hip roof porch covers facade, corners supported by box, paneled pillars with capitals, Tuscan columns flank steps, multi-light front door with transom flanked by French doors, paired 6/1 windows above, hip roof dormer with light and flanking louvers, side chimney, exposed rafters, one story hip wing rear. 9 1016 C
- 446 5 DEMOUY AVE c. 1925. Bungalow, one story, gable roof sides, frame, gable over stoop on square posts, inset side porch, craftsman windows, interior chimney. 27 1014 C
- 447 7 DEMOUY AVE c. 1925. Bungalow, one story, frame, hip roof with hip roof dormer, three bay facade, recessed porch covers facade, boxed columns on brick plinths, canvas awnings across porch, exposed rafters. 28 1014 C
- 448 8 DEMOUY AVE c. 1930. One story, gable roof front with hip wing, frame, attached hip roof porch covers facade, turned posts and balustrade are modern additions, paired 6/1 windows, lattice vent in gable. 8 1016 C
- 449 9 DEMOUY AVE c. 1925. Bungalow, one story, frame, gable roof front, offset gable porch with square brick columns has been infilled with large glass windows, casement windows in facade, knee braces in gable, exposed rafters. 29 1014 C

United States Department of the Interior
National Park Service

National Register Of Historic Places
Continuation Sheet

Section Number 7 Page 58

MID TOWN HISTORIC DISTRICT
Mobile
Mobile County, AL

- 450 10 DEMOUY AVE c. 1925. Bungalow, one story, brick foundation, gable roof front, frame, four bay facade, attached offcenter gable porch with square, paneled box columns and balustrade, multi-light door with transom, 3/1 windows, horizontal light in gable, purlins, exposed rafters, side chimney. 7 1016 C
- 451 12 DEMOUY AVE c. 1945. Two story, hip roof, brick, three bay facade, side entrance with attached one story roof over stoop with slender Tuscan columns, paired 8/8 windows, interior chimney, box cornice. 6 1016 C
- 452 13 DEMOUY AVE c. 1925. Bungalow, one story, frame, cross gable, attached gable roof porch with square brick columns, louvered vent in gable, casement windows, entrance features sidelights and transom. 30 1014 C
- 453 14 DEMOUY AVE c. 1925. Bungalow, one story, hip roof, frame, attached offcenter hip roof porch with tripled Tuscan columns, double doors with transom, flanking casement windows with transoms, casement windows, exposed rafters, side chimney. 5 1016 C
- 454 15 DEMOUY AVE c. 1925. Bungalow, one and a half story, frame, gable roof sides, recessed porch covers three bay facade, square posts, gable dormer with casement windows, end chimney. 31 1014 C
- 455 16 DEMOUY AVE c. 1945. Minimal Traditional, one and a half story, frame, gable roof sides, three bay facade, recessed porch covers facade, ornamental iron columns, corner columns paired and rest on stucco plinths, six panel door with sidelights and transom, tripled 9/1 windows one side, paired 9/1 windows the other side, gable dormer above with tripled 4/4 windows, two story garage rear. 4 1016 C
- 456 17 DEMOUY AVE c. 1925. Bungalow, one and a half story, gable roof front, frame, offcenter shed roof porch with massive, battered stucco columns, Craftsman windows, multi-light door with sidelights, three 3/1 windows in gable, exposed rafters. 32 1014 C
- 457 18 DEMOUY AVE c. 1925. Bungalow, one and a half story, hip roof, frame, three bay facade, attached hip roof porch center bay, battered brick columns, four panel door with sidelights, casement windows, hip roof clerestory with casement windows, exposed rafters. 3 1016 C
- 458 19 DEMOUY AVE c. 1925. Bungalow, two stories, frame, hip roof, three bay facade, paired 6/1 windows, hip roof over stoop with square brick columns, multi-light door, exposed rafters. 33 1014 C

CS 9
110

United States Department of the Interior
National Park Service

National Register Of Historic Places
Continuation Sheet

Section Number 7 Page 59

MID TOWN HISTORIC DISTRICT
Mobile
Mobile County, AL

- 459 20 DEMOY AVE c. 1925. Bungalow, one story, gable roof front, frame, three bay facade,, recessed porch covers facade, square brick pillars and knee wall, Craftsman door flanked by tripled window arrangements, each 9/1 with flanking 6/1, 6/1 window in gable with flanking 4/1 lights, knee braces, louvered vent, side chimney, exposed rafters. 2 1016 C
- 460 21 DEMOY AVE c. 1925. Bungalow, one story, frame, gable roof front, recessed porch covers facade, battered, boxed columns on brick plinths, offcenter entrance, multi-light door with 9/1 windows flanking and pair 9/1 windows in other bay, dentil course, knee braces and pair 4/1 lights in gable, exposed rafters, exterior chimney. 34 1014 C
- 461 22 DEMOY AVE c. 1925. Bungalow, two story, cross gable, brick, water table, recessed one story porch with square brick pillars abutts two gable bay, six panel door with sidelights and fan transom, paired windows, small purlins. 1 1016 C
- 462 23 DEMOY AVE c. 1925. Bungalow, one story, frame, cross gable, offcenter gable porch partially infilled with multi-light windows, entrance has sidelights, louvered vents and knee braces in gable, exposed rafters, exterior chimney. 35 1014 C
- 463 50 DEMOY AVE c. 1925. Bungalow, one story, gable on hip roof, stucco three bay facade, recessed porch covers facade, stuccoed pillars with arches, inlaid tilework on faces of pillars, multi-light door with sidelights, paired 3/1 windows each side, side chimney, interior chimney, exposed rafters. 35 1015 C
- 464 51 DEMOY AVE c. 1930. Bungalow, one story, gable roof front with gabled porch perpendicular, square brick pillars, ornamental iron supports on brick plinths flank steps, porch infilled with frame, multi-light door with flanking picture windows, knee braces, louvered vent. 1 1015 C
- 465 52 DEMOY AVE c. 1925. Bungalow, one and a half story, hip roof, vinyl sided, three bay facade, recessed porch covers facade, brick pillars, screened, hip clerestory with 3/1 windows, side chimney. 34 1015 C
- 466 53 DEMOY AVE c. 1925. English Cottage Revival, one story, cross gable, brick, three bay facade, staggered gables at entrance, awning over doorway, arched tripled 6/6 windows one side, 6/6 window other, front chimney, box cornice closed return, round top louvered vent in gables. 2 1015 C
- 467 54 DEMOY AVE c. 1925. Bungalow, one story, hip roof, frame, attached offcenter gable porch with square brick pillars, knee wall, 6/1 windows flank six panel door with transom, side chimney, exposed rafters. 33 1015 C

United States Department of the Interior
National Park Service

National Register Of Historic Places
Continuation Sheet

Section Number 7 Page 60

MID TOWN HISTORIC DISTRICT
Mobile
Mobile County, AL

- 468 55 DEMOUY AVE c. 1925. English Cottage Revival, one story, gable sides, frame, three bay facade, gable entrance with wood door and rounded brick steps, bubble awning, flanking Tudor lights, front chimney, paired 6/1 windows. 3 1015 C
- 469 56 DEMOUY AVE c. 1925. Bungalow, one and a half story, jerkin head gable sides, frame, attached shed roof porch with port-cochere covers facade, box columns on brick plinths, full height brick columns either side gable over entrance, shed roof dormer with set five horizontal windows, knee braces, brackets around porch, end chimney. 32 1015 C
- 470 57 DEMOUY AVE c. 1925. English Cottage Revival, one story, cross gable, frame, three bay facade, attached gable with battered brick supports at entrance, round top door, Tudor windows either side, round vent in dominant offcenter gable, small gable dormer with Tudor pane, end chimney and rear ell. 4 1015 C
- 471 58 DEMOUY AVE c. 1925. Bungalow, one story, gable roof front,, recessed porch covers facade, tripled box columns on brick plinths, six panel door flanked by paired 6/1 windows, dentil course, paired louvered vents, knee braces, bargeboard, exposed rafters, end chimney. 31 1015 C
- 472 59 DEMOUY AVE c. 1925. Bungalow, one and a half story, gable sides, frame, three bay facade, six panel door flanked by Craftsman casement windows floor to ceiling, attached one story flat roof porch with Tuscan columns wraps house and forms porte-cochere, shed roof dormer above with three sets casement Craftsman windows, end chimney. 5 1015 C
- 473 60 DEMOUY AVE c. 1925. Bungalow, one story, gable roof front, frame, attached offcenter gable porch with battered box columns on brick plinths, dentil course, tripled louver vent, bargeboard, knee braces, Craftsman door flanked by paired Craftsman windows, attached one story, flat roof porte-cochere adjacent porch with paneled battered box columns on brick plinths, exposed rafters. 30 1015 C
- 474 61 DEMOUY AVE c. 1925. Bungalow, one story, gable roof front, frame, attached offcenter gable porch with square brick columns, screened, louvered vent, purlins, exposed rafters, side chimney, casement windows. 6 1015 C
- 475 62 DEMOUY AVE c. 1925. Bungalow, one story, gable on hip roof, brick, three bay facade, attached offcenter hip roof porch with square brick columns, louvered screen over front door, flanked by paired 3/1 windows, box cornice, end chimney. 29 1015 C
- 476 63 DEMOUY AVE c. 1930. Minimal Traditional, one and a half story, gable roof sides, frame, six panel door with lunette transom, curved shelter, casement windows, inset porch north end with box columns on brick plinths, screened, exposed rafters, end chimney, outbuilding in rear is gable sides with a tin roof, frame with grouped 6/6 windows. 7 1015 C
- cb 9*
- 100*

United States Department of the Interior
National Park Service

National Register Of Historic Places
Continuation Sheet

Section Number 7 Page 61

MID TOWN HISTORIC DISTRICT
Mobile
Mobile County, AL

- 477 64 DEMOUY AVE c. 1925. Bungalow, one story, gable roof front, asbestos sided, attached offcenter gable with paired box columns on stuccoed plinths, Craftsman door with sidelights, paired 3/1 windows flank, pair four pane lights in gable, purlins, exposed rafters. 28 1015 C
- 478 100 DEMOUY AVE c. 1930. Bungalow, one story, gable roof front, frame, three bay facade, attached offcenter gable porch with square posts on brick piers, wraps around as another gable, paired 3/1 windows flank six panel door, purlins, esposed rafters. 27 1015 C
- 479 102 DEMOUY AVE c. 1925. Dutch Colonial Revival, one and a half story, gambrel roof sides, frame, five bay facade, six panel door with sidelights, attached shed roof porch covers facade, square posts, plain railing, paired 6/6 windows, shed roof dormer with three bays, paired 6/6 windows flank smaller pair 6/6 windows, two interior chimneys. 26 1015 C
- 480 104 DEMOUY AVE c. 1925. Bungalow, one story, gable roof front, attached offcenter gable porch with tripled brick columns on brick plinths, screened, tinted glass infill, knee braces, louvered vents, tripled Craftsman windows with fabric awning, exposed rafters. 25 1015 C
- 481 105 DEMOUY AVE c. 1930. Bungalow, one story, gable roof front, brick, attached offcenter gable porch with battered columns on brick plinths, infilled with tinted glass, Craftsman windows, louvered vent, knee braces, exposed rafters. 9 1015 C
- 482 106 DEMOUY AVE c. 1925. Bungalow, one story, gable roof front, frame, two bay facade, attached offcenter gable porch with ornamental iron supports on brick plinths, knee braces, louvered vent, exposed rafters, paired 3/1 windows, interior chimney. 24 1015 C
- 483 107 DEMOUY AVE c. 1925. Bungalow, one story, hip roof, frame, two bay facade, six panel door with flanking four pane lights, paired 6/1 windows, attached offcenter gable porch with battered box columns on stucco plinths, purlins, light in gable, exposed rafters, interior chimney. 10 1015 C
- 484 108 DEMOUY AVE c. 1925. Bungalow, one story, gable roof front, frame,, recessed porch covers facade,, battered, boxed columns on brick plinths, two bay facade, six panel door, tripled 6/1 windows adjacent, louvered vent in gable, attached shed roof porte-cochere, exposed rafters. 23 1015 C
- 485 109 DEMOUY AVE c. 1930. Bungalow, one story, gable front, frame, attached offcenter gable with tripled columns on brick plinths, screened, metal awning, knee braces, exposed rafters, interior chimney. 11 1015 C

cb 7
22

United States Department of the Interior
National Park Service

National Register Of Historic Places
Continuation Sheet

Section Number 7 Page 62

MID TOWN HISTORIC DISTRICT
Mobile
Mobile County, AL

- 486 110 DEMOUY AVE c. 1925. Bungalow, one story, frame, gable roof front, three bay facade, attached offcenter gable porch with battered box columns on brick plinths, six panel door flanked by tripled 6/1 windows one side, tripled tinted vertical lights opposite, louvered vent, exposed rafters, kick-off shed roof porte-cochere. 22 1015 C
- 487 111 DEMOUY AVE c. 1925. Bungalow, one story, jerkin head gable roof sides, frame, three bay facade, front door has six lights, wide chimney adjacent, inset porch in one bay now filled with glass, brick knee wall, 6/6 windows, louvered vent in gables. 12 1015 C
- 488 112 DEMOUY AVE c. 1960. Ranch Style, one story, cross gable, brick, four bay facade, windows have metal awnings, attached shed roof porch at front door with ornamental iron post, ridge chimney. 21 1015 N
- 489 113 DEMOUY AVE c. 1925. Bungalow, one story, gable on hip front, frame, recessed porch covers facade and becomes porte-cochere, fat Tuscan columns on stuccoed plinths, screened, exposed rafters. 13 1015 C
- 490 115 DEMOUY AVE c. 1925. Bungalow, one story, gable roof front, frame, three bay facade, six panel door center with lunette transom, attached gable on wall brackets, flanking casement windows, half-timbered gable with louvered vent, side porch with Tuscan columns, screened, exposed rafters, interior chimney. 14 1015 C
- 491 116 DEMOUY AVE c. 1925. Bungalow, one story, gable roof front, frame, recess porch covers facade, square brick columns, aluminum awning infill, gabled porte-cochere, round top vent in gable, exposed rafters. 20 1015 C
- 492 117 DEMOUY AVE c. 1925. Bungalow, one story, cross gable, frame, four bay facade, entrance flanked by gables with paired Craftsman windows, horizontal lights in gable, exposed rafters. 15 1015 C
- 493 118 DEMOUY AVE c. 1925. Bungalow, one story, cross jerkin head gable roof, frame, inset porch with square brick columns, six panel door, board and batten adjacent with paired 3/1 windows, light in gable, end chimney, exposed rafters. 19 1015 C
- 494 120 DEMOUY AVE c. 1925. Bungalow, one story, gable front, vinyl sided,, recessed porch covers facade, six panel door with sidelights, facade window covered with siding. 18 1015 N

United States Department of the Interior
National Park Service

National Register Of Historic Places
Continuation Sheet

Section Number 7 Page 63

MID TOWN HISTORIC DISTRICT
Mobile
Mobile County, AL

- 495 121 DEMOUY AVE c. 1925. Bungalow, one story, cross jerkin head gable, frame, attached jerkin head gable roof porch with square posts, shed roof porch to one side with square post, Craftsman door, casement windows, horizontal louvered vent, exposed rafters, end chimney. 16 1015 C
- 496 122 DEMOUY AVE c. 1925. International Style, two story, flat roof, stucco and brick, apartment building with paired 6/6 windows, central entrance, inset first and second story porchs with fluted corner columns and screened. 17 1015 C
- 497 1 ELIZABETH PL c. 1965. Ranch Style, one story, gable roof sides, brick, four bay facade, offcenter entrance with storm door, casement windows. 23 1036 N
- 498 2 ELIZABETH PL c. 1940. Minimal Traditional, one story, gable roof sides, frame, three bay facade, attached gable porch with Tuscan columns, ornamental iron balustrade covers most of facade, paired 6/6 windows flank six panel door, box cornice, end chimney. 22 1036 C
- 499 3 ELIZABETH PL c. 1940. One and a half story, gable roof sides, brick, four bay facade, six panel door, bay window south side with three 6/6 windows, attached one story porch, screened, south side, shed roof frame dormer with two 3/1 windows, end chimney. 24 1036 C
- 500 4 ELIZABETH PL c. 1940. Minimal Traditional, one story, gable roof sides, frame, four bay facade, attached gable over entrance with ornamental iron supports, six panel door, flanking 8/8 windows, gable wing with awning windows south side, interior chimney, box cornice. 21 1036 C
- 501 5 ELIZABETH PL c. 1940. Minimal Traditional, one story, gable roof sides, brick, three bay facade, attached porch over entrance with slender Tuscan columns, flanking 8/8 windows, attached, screened gable porch north end, end chimney. 25 1036 C
- 502 6 ELIZABETH PL c. 1940. Minimal Traditional, one story, gable roof sides, frame, five bay facade, six panel door with sidelights, 6/6 windows, end chimney. 20 1036 C
- 503 7 ELIZABETH PL c. 1940. Minimal Traditional, one story, gable roof sides, brick, three bay facade, six panel door, attached hip porch over entrance with ornamental iron posts, flanking paired 6/6 windows, end chimney, box cornice. 26 1036 C

26 8
212

United States Department of the Interior
National Park Service

National Register Of Historic Places
Continuation Sheet

Section Number 7 Page 64

MID TOWN HISTORIC DISTRICT
Mobile
Mobile County, AL

- 504 8 ELIZABETH PL c. 1940. Minimal Traditional, one and a half story, gable roof sides, three bay facade, brick, six panel door, 9/9 windows, pair large dormers with 6/6 windows, end chimney. 19 1036 C
- 505 9 ELIZABETH PL c. 1950. Cottage Revival, one and a half story, cross gable, brick, four bay facade, pair staggered gable bays south end of facade, entrance in smaller gable, door with six lights, 8/8 windows, chimney at facade, box cornice. 27 1036 C
- 506 10 ELIZABETH PL c. 1940. Colonial Revival, one and a half story, frame, H plan, gable roof sides mass with flanking one story gable front wings, center mass three bay facade, gable wings two bays, attached shed roof porch covers center section, box columns with capitals, six panel door with sidelights and fan transom, flanking French doors, 6/6 windows in wings, round louvered vents, pair gable dormers with 6/6 windows, interior chimney, box cornice closed return. 18 1036 C
- 507 11 ELIZABETH PL c. 1940. Minimal Traditional, one story, gable roof sides, frame, five bay facade, six panel door, attached gable over entrance with square posts with capitals, 6/6 windows, box cornice. 28 1036 C
- 508 12 ELIZABETH PL c. 1940. Bungalow, one story, gable roof sides, frame, attached offcenter gable porch with square posts and balustrade, attached pent with brackets off porch posts, paired 3/1 windows, triangular louvered vents, end chimney with corbeled cap. 17 1036 C
- 509 13 ELIZABETH PL c. 1965. Ranch Style, one story, gable roof sides, three bay facade, attached shed roof over entrance with ornamental iron supports, metal casement windows, box cornice. 29 1036 N
- 510 14 ELIZABETH PL c. 1940. Colonial Revival, one story, gable roof sides, brick, three bay facade, door has lunette light and flanking brick pilasters, metal casement windows with shutters, end chimney with corbeled cap, box cornice. 16 1036 C
- 511 15 ELIZABETH PL c. 1940. Minimal Traditional, one story, cross gable, frame, six bay facade, six panel door in center gable with 12/12 window adjacent, round top louver vent in gable, smaller 6/6 windows south bays, box cornice. 30 1036 C
- 512 16 ELIZABETH PL c. 1955. Ranch Style, one story, cross gable, brick, pair picture windows with flanking lights, inset entrance with six panel door, triangular louver in gablem interior chimney. 15 1036 N

24 F
1036 C

United States Department of the Interior
National Park Service

National Register Of Historic Places
Continuation Sheet

Section Number 7 Page 65

MID TOWN HISTORIC DISTRICT
Mobile
Mobile County, AL

- 513 17 ELIZABETH PL c. 1940. Minimal Traditional, one story, cross gable, L plan three bay facade, attached shed roof porch abutts gable wing, ornamental iron supports, paired 6/6 windows in gable, six panel door with tripled multi-light windows north side, end chimney, box cornice, closed return. 31 1036 C
- 514 18 ELIZABETH PL c. 1940. One story, hip roof, frame, three bay facade,, recessed porch covers facade, square posts and balustrade, six panel door with sidelights and transom, French doors, box cornice. 14 1036 C
- 515 19 ELIZABETH PL c. 1940. Minimal Traditional, one story, cross gable, L plan, frame, four bay facade, attached shed roof over entrance with ornamental iron support, abutts gable wing, 8/8 windows, box cornice, closed return, louver vent. 32 1036 C
- 516 21 ELIZABETH PL c. 1940. Minimal Traditional, one story, cross gable, frame, center gable with entrance, attached gable over entrance with iron supports, louvered vent, hexagonal window north side, interior chimney, box cornice closed return. 33 1036 C
- 517 22 ELIZABETH PL c. 1940. Colonial Revival, two story, gable roof sides, frame, three bay facade, attached one story gable over entrance with ornamental iron supports, six panel door with sidelights, paired 6/6 windows, one story flat roof balustraded wing north side, box cornice. 13 1036 C
- 518 23 ELIZABETH PL c. 1955. Ranch Style, one story, gable roof sides, brick, inset entrance, multi-light windows, interior chimney. 34 1036 N
- 519 24 ELIZABETH PL c. 1980. Eclectic, one story, hip roof, four bay facade, recessed porch covers three bays, bay window adjacent with 6/6 windows, turned posts and balustrade, 9/6 windows, box cornice. 12 1036 N
- 520 25 ELIZABETH PL c. 1955. Ranch Style, one story, gable roof sides, brick, casement windows, six panel door, box cornice with round purlins along facade. 35 1036 N
- 521 26 ELIZABETH PL c. 1940. Minimal Traditional, one story, hip roof, frame, inset porch with square posts, paired 9/6 windows, box cornice. 11 1036 C

26 6
11 3

United States Department of the Interior
National Park Service

National Register Of Historic Places
Continuation Sheet

Section Number 7 Page 66

MID TOWN HISTORIC DISTRICT
Mobile
Mobile County, AL

- 522 2205 ELIZABETH ST c. 1940. Two story garage apartment, gable roof sides, asbestos sided, pair auto bays with double wooden doors, paired 6/6 windows above, attached gable with wall brackets one end over entrance with stairway. 33 1006 C
- 523 2004 EMOGENE ST c. 1940. Cottage Revival, one story, brick, gable roof sides, three bay facade, round top solid wood door with battered gable brick surround, bank casement windows one side, screened arched topped openings other. 23 1006 C
- 524 2005 EMOGENE ST c. 1945. Minimal Traditional, one story, frame, gable roof sides, four bay facade, 12/12 windows, gable with engaged columns at entrance, six panel door, interior chimney. 25 1006 C
- 525 2010 EMOGENE ST c. 1940. Colonial Revival, one and a half story, vinyl sided, gable roof sides, five bay facade, gable over entrance with square posts, shed roof dormers above, 6/6 windows, one story flat roof wing one end with awning over windows. 24 1006 C
- 526 2054 EMOGENE ST c. 1970. One story, gable roof sides, series of three strutures joined together, vinyl sided and asbestos sided, aluminum windows, chimney at facade, gable porch over one entrance with iron supports, shed roof porch over other entrance. This appears to be two houses joined by a two bay hyphen. The hyphen features 6/6 windows. 26 1006 N
- 527 2103 EMOGENE ST c. 1940. Colonial Revival, one story, gable roof sides, frame, four bay facade, gable with engaged columns at entrance, louvered screen covers door, paired 8/1 windows flank entrance, sun room one end with box column and tripled 6/6 windows. 28 1006 C
- 528 2104 EMOGENE ST c. 1980. Two story, gable roof front, inverted board and batten, pair multi-light windows at first story, wrap around shed roof porch braced off of house, paired 6/6 windows above, louvered vent. 27 1006 N
- 529 2105 EMOGENE ST c. 1980. One and a half story, frame, gable roof sides, paired 6/1 windows at first story, grouped 9 light windows at half story, attached offcenter shed roof porch with infill, pair skylights. 29 1006 N
- 530 2156 EMOGENE ST c. 1965. Ranch house, one story, brick, gable roof sides, attached gable over stoop with ornamental iron supports, casement windows, multi-light door. 30 1006 N

cb 5
no 4

United States Department of the Interior
National Park Service

National Register Of Historic Places
Continuation Sheet

Section Number 7 Page 67

MID TOWN HISTORIC DISTRICT
Mobile
Mobile County, AL

- 531 2158 EMOGENE ST c. 1925. Bungalow, one story, gable roof front, frame, recessed porch covers facade, three bay facade, square brick porch columns, 6/1 windows flank Craftsman door, knee braces, exposed rafters. 31 1006 C
- 532 2159 EMOGENE ST c. 1940. Minimal Traditional, one story, cross gable, frame, attached hip roof porch at one end with ornamental iron supports, 3/1 windows, purlins, exposed rafters. 32 1006 C
- 533 3 FIELDER PL c. 1945. Minimal Traditional, one story, gable roof sides, frame, four bay facade, offcenter entrance with six panel door, gable engaged above, paired 8/8 windows. 1 1037 C
- 534 100 FLORENCE PL c. 1945. Minimal Traditional, one story, hip roof, brick, four bay facade, offcenter entrance with attached hip roof porch with square posts, six panel door, 12/12 windows, interior chimney, box cornice. 3 1040 C
- 535 101 FLORENCE PL c. 1930. English Cottage Revival, one story, cross gable, brick, three bay facade, round top entrance with attached arched gable porch, casement windows, inset porch south end, exposed rafters, end chimney. 4 1040 C
- 536 102 FLORENCE PL c. 1930. English Cottage Revival, one story, cross gable, brick, three bay facade, staggered gables center, lower one attached with battered brick supports, wood door, tripled multi-light window north side, inset porch with arched opening south side, infilled by glass, round top louvered vent main front gable, box cornice closed return, end chimney. 2 1040 C
- 537 103 FLORENCE PL c. 1925. Mission Revival, NR 1991, one story, flat roof, stucco, three bay facade, attached shed roof porch covers facade, ceramic tile roof, arched openings in stucco, square one story tower north side with ceramic tile roof, exterior chimney south end, pipe vents around side elevations, parapeted with coping. 1 1040 C
- 538 104 FLORENCE PL c. 1925. Mission Revival, NR 1991, one story, flat roof, stucco, attached shed roof porch with ceramic tiles, arched openings, square one story south adjacent with paired 6/1 windows, hip ceramic tile roof, pipe vents side elevations, chimney north end, parapeted with coping. 5 1040 C
- 539 105 FLORENCE PL c. 1940. Colonial Revival, one story, gable sides, brick, four bay facade, offcenter entrance, six panel door, attached pedimented gable with dentil work over entrance with box columns with capitals, flanking 12/12 windows with ornamental iron burglar bars, frame bay south end with 9/9 window, dentil course around eaves, interior chimney. 6 1040 C

United States Department of the Interior
National Park Service

National Register Of Historic Places
Continuation Sheet

Section Number 7 Page 68

MID TOWN HISTORIC DISTRICT
Mobile
Mobile County, AL

- 540 106 FLORENCE PL c. 1935. Minimal Traditional, one story, gable roof sides, frame, three bay facade, attached gable at entrance with battered brick supports, round top door, pair 6/1 windows adjacent north, tripled 6/1 windows adjacent south, exposed rafters, end chimney. 35 1039 C
- 541 107 FLORENCE PL c. 1925. Mission Revival, NR 1991, one story, gable roof sides, stucco, three bay facade, attached arched porch with flat parapeted roof, multi-light door with sidelights, casement windows adjacent with stuccoed arched transoms, ornamental railing to either side of porch, end chimney. 7 1040 C
- 542 108 FLORENCE PL c. 1940. Minimal Traditional, one story, gable roof sides, frame, four bay facade, offcenter entrance with attached gable on square posts, flanking paired 6/6 windows, screened, inset porch south bay, exposed rafters, end chimney. 34 1039 C
- 543 109 FLORENCE PL c. 1940. Bungalow, one story, gable front, aluminum sided, four bay facade, duplex, pair six panel doors each end with rounded roofs on wall brackets over steps, two pairs of 3/1 windows between with shutters, round top louvered vent, interior chimney. 8 1040 C
- 544 110 FLORENCE PL c. 1925. Cottage Revival, one story, gable roof sides, frame, three bay facade, side entrance with six panel door, chimney adjacent, tripled Tudor pane windows and tripled 3/1 windows south bay. 33 1039 C
- 545 111 FLORENCE PL c. 1940. Bungalow, two story, gable roof front, asbestos sided, inset two story porch with square posts and balustrade at second story, entrances in side off porch, tripled 6/6 windows first and second story adjacent porch, louvered vent, exposed rafters, two interior chimneys. 9 1049 C
- 546 112 FLORENCE PL c. 1930. Minimal Traditional, one story, cross gable, ell plan, frame, recessed screened porch with square posts in front gable, round top 3/1 light in gable, smaller entrance gable adjacent with round top door, chimney front of facade with flanking round top 3/1 windows, exposed rafters. 32 1039 C
- 547 113 FLORENCE PL c. 1940. Minimal Traditional, one story, gable roof sides, two bay facade, attached offcenter gable porch with Palladian opening and ornamental ironwork, multi-light windows, box cornice closed return, louvered vent, end chimney. 10 1040 C
- 548 114 FLORENCE PL c. 1930. Cottage Revival, one story, cross gable, brick, two bay facade, side entrance with six panel door and sidelights, bubble awning, paired 6/6 windows in front gable, louvered vents. 31 1039 C

ob 8 nr 1
no

United States Department of the Interior
National Park Service

National Register Of Historic Places
Continuation Sheet

Section Number 7 Page 69

MID TOWN HISTORIC DISTRICT
Mobile
Mobile County, AL

- 549 115 FLORENCE PL c. 1925. Tudor Revival, one story, cross gable, brick, three bay facade gable front with recessed gable ell, attached gable over entrance with wall brackets, round top door, flanking paired 6/6 windows, half-timbered gable with stucco, ell features terrace with balustrade, round top entrance with rounded covering on wall brackets, paired 6/6 windows. 11 1040 C
- 550 116 FLORENCE PL c. 1945. Two story, gable roof sides, stucco, three bay facade, inset two story porch covers two bays, iron supports, perma-stone applied to facade at first story porch, six panel door, 8/8 windows. 30 1039 C
- 551 117 FLORENCE PL c. 1940. Minimal Traditional, one and a half story, gable roof sides, three bay facade with attached side gable porch, screened, offcenter entrance, six panel door, attached gable over entrance with ornamental iron supports, 9/9 windows with shutters, pair dormers with 6/6 windows, French doors lead onto porch. 12 1040 C
- 552 118 FLORENCE PL c. 1925. Mission Revival, NR 1991, two story, hip roof, stucco, two story three bay block with offset one story flat roof wing, wing features attached shed roof porch with square posts, first floor windows 3/1, second floor casement windows with middle one featuring a lunette transom. 29 1039 C
- 553 119 FLORENCE PL c. 1925. Mission Revival, NR 1991, one story, flat roof, parapeted with coping, stucco, two bay facade, octagonal one story tower at north front corner with casement windows and canvas awning, pipe vents, pitched roof with ceramic tiles, entrance in side of tower features sloping roof on wall brackets over steps, bank of casement windows in facade with fan transom, wing wall with arched opening and urn, two story garage rear with three automobile bays, hip roof, paired 6/6 windows, frame. 13 1040 C
- 554 120 FLORENCE PL c. 1945. Colonial Revival, one story, gable roof sides, vinyl sided, three bay facade, six panel center entrance with small metal awning and small gable above, dentil course, 8/8 windows. 28 1039 C
- 555 121 FLORENCE PL c. 1940. Minimal Traditional, one story, gable roof sides, brick, three bay facade, double wooden doors, flanking banks of casement windows, box cornice. 14 1040 C
- 556 122 FLORENCE PL c. 1940. Minimal Traditional, one story, gable roof sides, asbestos shingles, three bay facade, six panel door with gable above on wall brackets, flanking 6/6 windows with shutters. 27 1039 C
- 557 123 FLORENCE PL c. 1930. English Cottage Revival, one and a half story, cross gable, asbestos sided, two bay facade, offcenter gable with round top door with diamond lights, attached gable on wall brackets over steps, 3/1 window in gable above, louvered vent, tripled 3/1 windows adjacent, shed roof dormer with tripled 3/1 windows, end chimney. 15 1040 C

United States Department of the Interior
National Park Service

National Register Of Historic Places
Continuation Sheet

Section Number 7 Page 70

MID TOWN HISTORIC DISTRICT
Mobile
Mobile County, AL

- 558 124 FLORENCE PL c. 1925. Minimal Traditional, one and a half story, cross gable, frame, inset porch north bay, clapboarded knee wall and screened, attached gable with brick columns at entrance, paired 6/6 windows south side, gable above with louvered vent. 26 1039 C
- 559 125 FLORENCE PL c. 1940. Minimal Traditional, one story, gable roof front, frame, three bay facade, offcenter entrance with six panel door with classical surround, attached gable over steps on wall brackets of ornamental iron, bay window with hip roof center, three 6/6 windows, bank of windows with awning south end, round louvered vent, side chimney. 16 1040 C
- 560 126 FLORENCE PL c. 1925. Mission Revival, one story, flat, parapeted roof with coping, stucco, three bay facade, entrance has louvered screen door, attached flat roof porch with ceramic tile roof covers entrance, stucco knee wall across rest of facade, tripled Craftsman windows with ceramic tile awning either side entrance, attached porte-cochere south end, pipe vents, side chimney. 25 1039 C
- 561 127 FLORENCE PL c. 1930. English Cottage Revival, one story, cross gable, ell plan, stucco, three bay facade, central entrance with six panel door and bubble awning, center gable, wide chimney north adjacent with brick upper shaft, tripled 6/1 windows in dominant gable, narrow louvered vent. 17 1040 C
- 562 128 FLORENCE PL c. 1930. Bungalow, one story, cross gable, frame, three bay facade, central gable porch with brick columns, bubble canvas awning, wood door with diamond lights, round light in gable, paired 6/1 windows north adjacent, picture window south adjacent, round top louvered vent in dominant gable. 24 1039 C
- 563 129 FLORENCE PL c. 1925. Mission Revival, NR 1991, two story, flat roof, stucco, three bay facade, attached one story flat roof porch covers facade, arched openings, wood door with sidelights and transom, flanked by paired 9/1 windows, two story square tower center of facade behind porch with casement windows, pyramidal ceramic tile roof, parapeted flat roof around house with coping, side chimney, pipe vents. 18 1040 C
- 564 130 FLORENCE PL c. 1945. Minimal Traditional, one and a half story, cross gable, frame, five bay facade, central entrance, six panel door, 6/6 windows, dentil course, lunette vent in gable, gable dormer with 6/6 window, interior chimney. 23 1039 C
- 565 131 FLORENCE PL c. 1930. English Cottage Revival, one story, cross gable, ell plan, stucco, three bay facade, dominant gable features bank of 6/6 windows with arched transom, multi-light door south adjacent with sloping shed roof porch off main gable, stucco column and arched openings, round top casement windows on south side of entrance, wing walls south and north ends, louvered vent, end chimney. 19 1040 C
- 566 132 FLORENCE PL c. 1925. Mission Revival, two story, hip roof, stucco, two story hip roof block with three bays, one story three bay wing south side, entrance in one story wing, six panel door with lunette transom, flanking casement windows, shed roof supported on wall brackets over entrance, one story hip roof bay window with three 6/6 windows attached to two story block, casement windows above, exposed rafters. 22 1039 C

United States Department of the Interior
National Park Service

National Register Of Historic Places
Continuation Sheet

Section Number 7 Page 71

MID TOWN HISTORIC DISTRICT
Mobile
Mobile County, AL

- 567 133 FLORENCE PL c. 1940. English Cottage Revival, one and a half story, cross gable, brick, three bay facade, round top center entrance with sloping covering off of dominant gable, ornamental iron supports, tripled 6/6 windows in dominant gable, small 6/6 window with shutters above, side gables half-timbered, end chimney with corbeled cap. 20 1040 C
- 568 134 FLORENCE PL c. 1925. Bungalow, one story, cross gable, frame, three bay facade, metal awning over entrance, tripled 3/1 windows north adjacent, inset screened porch south with square posts, exposed rafters, louvered vent in gable. 21 1039 C
- 569 135 FLORENCE PL c. 1940. Minimal Traditional, one story, cross gables, three bay facade, asbestos sided, centered entrance with attached gable on wall brackets over steps, louvered vents in large gables, paired and tripled 3/1 windows, open eaves but no exposed rafters. 21 1040 C
- 570 136 FLORENCE PL c. 1940. Minimal Traditional, one story, gable roof front, frame, three bay facade, offcenter gable with extended slope over entrance, square post, tripled 3/1 windows in front gable, six panel door, 3/1 window north adjacent, louvered vents in gables, interior chimney. 20 1039 C
- 571 137 FLORENCE PL c. 1925. Mission Revival, one story, gable roof front with gable wing, stucco, three bay facade, centered entrance with round top door, gable surround, flanking 6/6 windows, pipe vents in gable, interior chimney. 22 1040 C
- 572 138 FLORENCE PL c. 1940. Minimal Traditional, one story, cross gable, aluminum sided, three bay facade, wood door with gable above on metal wall brackets, paired 6/6 windows north adjacent, inset porch in front gable with square post, x pattern railing, louvered vent. 19 1039 C
- 573 139 FLORENCE PL c. 1925. Mission Revival, one story, pair gable roofs front, stucco, three bay facade, attached one story shed roof porch abutts gable bay and covers rest of facade, arched openings, round top door, paired 3/1 windows, round top louvered vent in smaller gable, lunette light in larger, end chimney. 23 1040 C
- 574 140 FLORENCE PL c. 1925. Mission Revival, one story, gable roofs front are later additions, original roof was flat, stucco, attached shed roof porch covers most of facade, stucco columns with arched openings, porte-cochere, multi-light door, casement windows. 18 1039 C
- 575 141 FLORENCE PL c. 1930. Tudor Revival, one story, cross gable, stucco, four bay facade, centered gabled entrance with round top door, arched opening south side with bank of casement windows and transom, pair 6/6 windows north side flank chimney on facade, half-timbering in gables, box cornice. 24 1040 C

United States Department of the Interior
National Park Service

National Register Of Historic Places
Continuation Sheet

Section Number 7 Page 72

MID TOWN HISTORIC DISTRICT
Mobile
Mobile County, AL

- 576 142 FLORENCE PL c. 1950. Minimal Traditional, one story, gable roof front, brick, three bay facade, round top wood door with canvas awning and gable, flanking 6/6 windows, set back wing with paired 6/6 windows north elevation, box cornice. 17 1039 C
- 577 143 FLORENCE PL c. 1925. Mission Revival, NR 1991, one story, flat, parapeted roof with coping, three bay facade, stucco, attached shed roof porch with ceramic tile roof covers facade, arched openings, wood door flanked by casement windows, side chimney. 25 1040 C
- 578 144 FLORENCE PL c. 1925. Mission Revival, one and a half story, cross gables, stucco, four bay facade, centered gable at entrance with stucco arch, pair arched openings north adjacent, porte-cochere with flat, parapeted roof, casement windows in dominant gable, round top window in half story, exposed rafters. 16 1039 C
- 579 145 FLORENCE PL c. 1925. Mission Revival, one story, cross gable, stucco, ell plan with attached flat roof porte cochere with arched side opening, picture window in front gable with arched top and three transom windows, round top door in south side of ell, shed roof covering over entrance and attaches two ells, round vents. 26 1040 C
- 580 146 FLORENCE PL c. 1930. Bungalow, one story, gable roof front, stucco, three bay facade, attached hip roof porch covers facade, square stucco pillars, screened, louvered vent, exposed rafters. Windows and door not visible through screens. 15 1039 C
- 581 147 FLORENCE PL c. 1925. Mission Revival, one story, hip roof, stucco, hip roof bay front with picture window with sidelights and brick sill and lintel, attached hip roof porte cochere south side with square stucco columns with accented brick capitals, arches, pipe vents, box cornice. 27 1040 C
- 582 148 FLORENCE PL c. 1925. Mission Revival, one story, gable roof sides, stucco, three bay facade, kick off shed roof porch with square stucco columns, broad arches, porch wraps north elevation, ceramic tile roof, end chimney. 14 1039 C
- 583 104 FRAZER CT c. 1990. Executive Mansion, two story, gable roof sides, brick, four bay facade, offcenter entrance with attached one story gable porch with Tuscan columns, six panel door, lunette transom, 6/6 windows, end chimney. 8 1039 N
- 584 108 FRAZER CT c. 1985. Executive Mansion, two story, hip roof, brick, five bay facade, attached one story gable porch with paired posts, 9/9 windows, entrance on south elevation matches facade. 9 1039 N

cb 6 NR 1
Also =

United States Department of the Interior
National Park Service

National Register Of Historic Places
Continuation Sheet

Section Number 7 Page 73

MID TOWN HISTORIC DISTRICT
Mobile
Mobile County, AL

- 585 112 FRAZER CT c. 1980. Executive Mansion, two story, hip roof, five bay facade, brick, 9/9 windows, entrance slightly inset, six panel door with sidelights and transom, Palladian window above. 10 1039 N
- 586 117 FRAZER CT c. 1985. Neo-Georgian, two story, H plan, five bay facade, hip roof with end gables, attached one story flat roof porch with box columns, Palladian window above, 6/6 windows, round vents in gables. 13 1039 N
- 587 121 FRAZER CT c. 1985. Executive Mansion, two and a half story, gable roof sides, brick, five bay facade, centered gable with arched entryway, six panel door with sidelights and transom, 9/9 windows, pair dormers, widow's walk, box cornice closed return. 12 1039 N
- 588 125 FRAZER CT c. 1990. Executive Mansion, two story, gable roof sides, brick, five bay facade with centered gable, attached one story gable porch with square posts, 6/6 windows, end chimney. 11 1039 N
- 589 3 N FULTON ST c. 1935. Bungalow, one story, gable sides, frame, duplex, four bay facade, pair front doors with paired 3/1 windows to sides, recessed porch with dormer over steps, square stucco columns, post at center of steps, interior chimney. 17 1022 C
- 590 6 N FULTON ST c. 1930. Bungalow, twin house to 8 North Fulton, one story, gable roof front, two bay facade, inset porch, screened, box columns, paired 6/6 windows with awning, louvered vent, knee braces, exposed rafters. 22 1022 C
- 591 7 N FULTON ST c. 1940. Minimal Traditional, one story, cross gable, frame, ell plan, entrance in ell with shed roof porch on iron supports, 4/1 windows, exposed rafters. 18 1022 C
- 592 8 N FULTON ST c. 1930. Bungalow, one story,, gable roof front, frame, two bay facade, inset porch with entrance in side, paired 6/6 windows with shutters, louvered vent, knee braces, exposed rafters. 21 1022 C
- 593 8 S FULTON ST c. 1925. Bungalow, one story, gable roof sides, frame, three bay facade, recessed porch covers facade, round posts, door with sidelights, paired 3/1 windows flank entrance, gable over steps, purlins, exposed rafters. 23 1022 C

cb 5
12022

United States Department of the Interior
National Park Service

National Register Of Historic Places
Continuation Sheet

Section Number 7 Page 74

MID TOWN HISTORIC DISTRICT
Mobile
Mobile County, AL

- 594 9 N FULTON ST c. 1925. Bungalow, one story, hip roof, stucco, recessed porch covers facade, square stucco pillars, screened, windows and doors not visible, exposed rafters, side chimney with corbeled cap. 19 1022 C
- 595 11 N FULTON ST c. 1955. Ranch Style, one story, gable sides, brick, attached gable over entrance with ornamental iron supports, tripled 3/1 windows south side, multi-light window north adjacent. 20 1022 N
- 596 50 S FULTON ST c. 1945. Minimal Traditional, one story, gable roof sides, brick, duplex, pair front doors with 8/8 windows in between, interior chimney. 24 1022 C
- 597 51 S FULTON ST c. 1945. Minimal Traditional, one story, gable roof sides, inset offcenter porch with attached gable on square posts, paired 6/6 windows, exposed rafters, interior chimney. 35 1024 C
- 598 52 1/2 S FULTON ST c. 1990. Two story, gable roof sides, inverted board and batten, three bay facade, door with sidelights, paired 6/6 aluminum windows. 25 1022 N
- 599 53 S FULTON ST c. 1945. Minimal Traditional, one story, cross gable, aluminum sided, three bay facade, attached gable over entrance on square post, six panel door, flanked by paired 6/6 windows with burglar bars south, 8/8 window with burglar bars north, box cornice closed return, end chimney. 34 1024 C
- 600 55 S FULTON ST c. 1945. Minimal Traditional, one story, gable sides, frame, three bay facade, inset porch with attached gable on square posts and balustraded, 6/6 windows, entrance in side of porch, box cornice closed return. 33 1024 C
- 601 56 S FULTON ST c. 1930. Bungalow, one story, gable sides, frame, attached offcenter gable porch, screened, with square brick pillars, purlins, exposed rafters. 26 1022 C
- 602 57 S FULTON ST c. 1945. Minimal Traditional, one story, cross gable, frame, four bay facade, recessed porch covers front gable, square posts and balustraded, secondary gable on square posts over steps, 8/8 windows, exposed rafters, end chimney. 32 1024 C

United States Department of the Interior
National Park Service

National Register Of Historic Places
Continuation Sheet

Section Number 7 Page 75

MID TOWN HISTORIC DISTRICT
Mobile
Mobile County, AL

- 603 58 S FULTON ST c. 1930. Bungalow, one story, hip roof, frame, five bay facade, recessed porch covers facade, ornamental iron posts on brick plinths, 6/6 windows, wood door, exposed rafters. 27 1022 C
- 604 59 S FULTON ST c. 1945. Minimal Traditional, one story, gable sides, asbestos sided, three bay facade, six panel door with attached gable on battered brick supports, paired 3/1 windows north adjacent, paired 2/2 horizontal pane south adjacent, round top louvered vents in gables, box cornice. 31 1024 C
- 605 60 S FULTON ST c. 1940. Minimal Traditional, one story, cross gable roof, stucco, duplex, pair attached hip roof porch with square posts, balustrade, paired 3/1 windows, two interior chimneys. 28 1022 C
- 606 61 S FULTON ST c. 1940. Minimal Traditional, one story, cross gable, frame, six panel door and chimney flanked by 2/2 windows in front gable, recessed porch adjacent south with square posts, balustraded and screened, exposed rafters. 30 1024 C
- 607 62 S FULTON ST c. 1940. Minimal Traditional, one story, cross gable, inset porch, screened, 6/6 windows, interior chimney. 29 1022 C
- 608 63 S FULTON ST c. 1940. Minimal Traditional, one story, gable roof side, frame, three bay facade, attached gable on square posts at entrance, flanking 6/6 windows, end chimney, exposed rafters. 29 1024 C
- 609 64 S FULTON ST c. 1940. Minimal Traditional, one story, cross gable, six panel door with stoop, 8/8 windows, lunette louvered vent. 30 1022 C
- 610 65 S FULTON ST c. 1945. Minimal Traditional, one story, cross gable, wood door center of three bay facade, asbestos sided, paired 6/6 windows, recessed porch in cross gable, square posts, balustraded and screened, exposed rafters. 28 1024 C
- 611 66 S FULTON ST c. 1925. Bungalow, one story, hip roof, brick, attached hip roof porch covers facade, brick pillars on brick knee wall, screened, flat roof porte-cochere north side, hip roof dormer with louvered vent, exposed rafters, side chimney. 31 1022 C
- eb*

United States Department of the Interior
National Park Service

National Register Of Historic Places
Continuation Sheet

Section Number 7 Page 76

MID TOWN HISTORIC DISTRICT
Mobile
Mobile County, AL

-
- 612 67 S FULTON ST c. 1945. Minimal Traditional, one story, gable roof sides, asbestos sided, five bay facade, six panel door with shed roof on ornamental posts, 6/6 and 8/8 windows with burglar bars, end chimney. 27 1024 C
- 613 68 S FULTON ST c. 1945. Minimal Traditional, two story, gable roof sides, frame, three bay facade, attached one story gable porch with square columns with capitals, 8/8 windows, end chimney, box cornice closed return. 32 1022 C
- 614 69 S FULTON ST c. 1945. Minimal Traditional, one story, cross gable, asbestos sided, three bay facade, center entrance with six panel door and sidelights, canvas awning, paired 6/6 windows south adjacent, paired 9/6 windows north adjacent, interior chimney. 26 1024 C
- 615 71 S FULTON ST c. 1930. Bungalow, one story, gable roof front, asbestos sided, two bay facade, side entrance with sidelights, gable over door with wall brackets, three aluminum windows with awning, extensive alterations. 25 1024 N
- 616 75 S FULTON ST c. 1940. Minimal Traditional, one story, gable roof sides, asbestos sided, three bay facade, inset porch covers 2/3 facade, screened, square posts and balustraded, gable over entrance, paired 6/6 windows, exposed rafters. 24 1024 C
- 617 100 S FULTON ST c. 1925. Bungalow, one story, gable roof front, frame, three bay facade, attached offcenter gable porch with square posts, balustrade and screened, centered entrance with multi-light door, attached gable on wall brackets, paired 6/1 windows, louvered vent in gable, exposed rafters. 33 1022 C
- 618 102 S FULTON ST c. 1925. Bungalow, one story, gable front, asbestos sided, attached offcenter gable porch with square posts on brick plinths, balustrade and screened, paired 3/1 windows, exposed rafters, side chimney. 34 1022 C
- 619 103 S FULTON ST c. 1940. Minimal Traditional, one story, gable roof front, asbestos sided, two bay facade, six panel door with sidelights, inset screened porch north adjacent, louvered vent, exposed rafters. 23 1024 C
- 620 104 S FULTON ST c. 1930. Bungalow, one story, jerkin head gable front, four bay facade, entrance with sidelights, 3/1 windows, louvered vent in gable, purlins, exposed rafters. 35 1022 C
- 46 5

United States Department of the Interior
National Park Service

National Register Of Historic Places
Continuation Sheet

Section Number 7 Page 77

MID TOWN HISTORIC DISTRICT
Mobile
Mobile County, AL

- 621 105 S FULTON ST c. 1945. Bungalow, one story, gable roof front, asbestos sided, attached, offcenter gable roof porch, ornamental iron supports, three bay facade, multi-light window south adjacent entrance, paired 6/6 windows north adjacent with awning, louvered vent in gable, exposed rafters. 22 1024 C
- 622 106 S FULTON ST c. 1935. Bungalow, one story, gable roof front, frame, attached offcenter gable porch with box columns on brick plinths, x balustrade and screened, triangular vents in gables, paired 6/6 windows, exposed rafters. 1 1023 C
- 623 107 S FULTON ST c. 1945. Minimal Traditional, one story, gable roof sides, asbestos sided, three bay facade, inset porch covers 2/3 of facade, screened with square post and balustrade, paired 6/6 windows, gable over steps, exposed rafters. 21 1024 C
- 624 108 S FULTON ST c. 1945. Minimal Traditional, one story, gable roof sides, asbestos sided, three bay facade, six panel door with gable above, pair 6/6 windows north adjacent, board and batten with 6/6 window south adjacent, exposed rafters. 2 1023 C
- 625 109 S FULTON ST c. 1940. Minimal Traditional, one story, cross gable, frame, ell plan, six panel door, 6/6 windows, louvered vent in gable, end chimney, box cornice. 20 1024 C
- 626 110 S FULTON ST c. 1930. Bungalow, one story, gable roof sides, frame, three bay facade, inset porch with battered box columns on stucco plinths, balustraded, pair staggered gables over steps, paired 6/6 windows flank multi-light door, exposed rafters. 3 1023 C
- 627 111 S FULTON ST c. 1940. Minimal Traditional, one and a half story, gable roof sides, frame, three bay facade with gable one bay wing south end, six panel door, attached gable porch with square posts, flanking 12/12 windows, pair gable dormers with 6/6 windows, interior chimney, louvered vents, box cornice. 19 1024 C
- 628 112 S FULTON ST c. 1940. Minimal Traditional, one story, cross gable, frame, three bay facade, inset porch in front gable, square posts and balustraded, six panel door and 1/1 window, paired 3/1 windows north adjacent, louvered vent, exposed rafters. 4 1023 C
- 629 114 S FULTON ST c. 1940. Minimal Traditional, one story, gable roof sides, three bay facade, six panel door with gable above, canvas awning, tripled 6/6 windows either side, end chimney, box cornice. 5 1023 C

26 3

100

United States Department of the Interior
National Park Service

National Register Of Historic Places
Continuation Sheet

Section Number 7 Page 78

MID TOWN HISTORIC DISTRICT
Mobile
Mobile County, AL

- 630 115 S FULTON ST c. 1945. Minimal Traditional, one story, cross gable, vinyl sided, four bay facade, offcenter entrance with six panel door, 8/8 windows, inset porch north end, square posts, balustraded and screened, interior chimney, triangular louvered vent in front gable. 18 1024 C
- 631 116 S FULTON ST c. 1945. Minimal Traditional, one story, cross gable, frame, attached brick gable at entrance, round top wooden door, bank horizontal light windows south adjacent, box cornice. 6 1023 C
- 632 117 S FULTON ST c. 1940. Minimal Traditional, one story, gable roof sides, frame, three bay facade with attached gable wing north end, screened porch here, six panel door with attached gable porch on Tuscan columns, flanking 16/16 windows, end chimney. 17 1024 C
- 633 118 S FULTON ST c. 1945. Minimal Traditional, one story, gable roof sides, frame, attached gable portico covers center three bays of five bay house, paired box columns with capitals, balustraded, louvered vent, 6/6 windows, box cornice closed return, end chimney. 7 1023 C
- 634 119 S FULTON ST c. 1945. Minimal Traditional, one story, cross gable, asbestos sided, three bay facade, paired 6/6 windows with shutters in center gable bay, lunette louver above, inset porch north end, square posts and balustrade, box cornice. 16 1024 C
- 635 120 S FULTON ST c. 1925. Bungalow, one and a half story,, gable roof sides, recessed porch covers facade, square brick pillars, paired 3/1 windows, six panel door, gable dormer with three windows, all 3 pane, purlins, exposed rafters, louvered vents in end gables, end chimney. 8 1023 C
- 636 150 S FULTON ST c. 1945. Neo-Classical Revival, two story apartments, gable roof sides, asbestos sided, five bay facade, centered portico with full height box columns with capitals, six panel door with classical surround, 8/8 windows, end bays inset porches with square posts and balustraded first and second stories, box cornice. 9 1023 C
- 637 151 S FULTON ST c. 1940. Minimal Traditional, one story, gable roof sides, brick, three bay facade, six panel door with stucco gable above on wall purlins, paired 3/1 windows flank entrance, box cornice. 15 1024 C
- 638 152 S FULTON ST c. 1940. Minimal Traditional, one story, gable roof sides, stucco, two bay facade, attached offcenter gable porch with square brick pillars, six panel door with sidelights, window with canvas awning, narrow louvered vent, end chimney. 10 1023 C

26 9

United States Department of the Interior
National Park Service

National Register Of Historic Places
Continuation Sheet

Section Number 7 Page 79

MID TOWN HISTORIC DISTRICT
Mobile
Mobile County, AL

- 639 153 S FULTON ST c. 1945. Minimal Traditional, two story, gable roof sides, asbestos sided, three bay facade, attached one story gable at entrance, ornamental iron supports, 8/8 windows, end chimney, box cornice. 14 1024 C
- 640 155 S FULTON ST c. 1940. Minimal Traditional, one story, gable roof sides, frame, four bay facade, six panel door with gable above, paired 6/1 windows south adjacent, chimney flanked by 6/1 windows north adjacent, exposed rafters. 13 1024 C
- 641 156 S FULTON ST c. 1950. Minimal Traditional, one story, gable roof sides, brick, three bay facade, attached gable porch at entrance on ornamental iron supports, multi-light window north adjacent, tripled tinted windows south adjacent with awning. 11 1023 C
- 642 157 S FULTON ST c. 1940. Minimal Traditional, one story, gable roof sides, frame, inset porch covers 2/3 of facade, screened, square post and balustraded, paired 6/6 windows, gable over entrance steps, pair gable dormers with louvered vents, exposed rafters, end chimney. 12 1024 C
- 643 158 S FULTON ST c. 1930. Mission Revival, one story, gable roof front is a later addition to original flat roof, stucco, porte-cochere north side, pair arches in attached porch with gable over entrance, ceramic tile roof, casement window south adjacent with fan transom, interior chimney. 12 1023 C
- 644 159 S FULTON ST c. 1940. Minimal Traditional, one story, cross gable, frame, three bay facade, multi-light door, inset porch north side, balustraded and screened, chimney adjacent entrance south, 6/6 window, exposed rafters. 11 1024 C
- 645 160 S FULTON ST c. 1960. One story, gable roof front, inset porch with square posts and awning, paired 6/6 aluminum windows, aluminum sided. 13 1023 N
- 646 161 S FULTON ST c. 1930. Bungalow, one story, gable roof front, frame,, attached, offcenter gable roof porch, square posts and balustraded, screened, six panel door, paired 6/6 windows, triangular louvered vent in main gable, side chimney, exposed rafters. 10 1024 C
- 647 162 S FULTON ST c. 1930. Mission Revival, one story, hip roof, stucco, three bay facade, inset porch south side with stucco pillar and arched opening, 3/1 windows flank chimney, pipe vents, exposed rafters. 14 1023 C

26 8
mb 1

United States Department of the Interior
National Park Service

National Register Of Historic Places
Continuation Sheet

Section Number 7 Page 80

MID TOWN HISTORIC DISTRICT
Mobile
Mobile County, AL

- 648 163 S FULTON ST c. 1925. Bungalow, one story, jerkin head gable front, attached jerkin head gable porch covers most of facade, slightly offcenter, square posts, balustraded, screened, metal awnings, vinyl sided, louvered vent. 9 1024 C
- 649 164 S FULTON ST c. 1925. Mission Revival, one story, flat parapeted roof with coping, stucco, three bay facade, attached shed roof porch with ceramic tile roof extends to north side as porte-cochere, arched stucco openings, six panel door, 4/1 window flanked by narrow lights, pipe vents. 15 1023 C
- 650 165 S FULTON ST c. 1940. Minimal Traditional, one story,, gable roof sides, four bay facade, six panel door, gable over entrance with two 6/6 windows to north, original inset porch to south infilled with casement windows and ornamental ironwork, chimney at facade, exposed rafters. 8 1024 C
- 651 166 S FULTON ST c. 1945. Minimal Traditional, two story, cross gable, ell plan, three bay facade, six panel door with attached shed roof porch on ornamental iron supports, 8/8 windows in ell, paired 6/6 with shutters in front gable, exposed rafters, end chimney, louvered vent. 16 1023 C
- 652 167 S FULTON ST c. 1940. Minimal Traditional, one story, cross gable, frame, four bay facade, six panel door with surround, chimney adjacent, paired 3/1 windows, inset, screened porch with square posts and balustrade north end, louvered vent in gable. 7 1024 C
- 653 169 S FULTON ST c. 1940. Minimal Traditional, one story, gable roof sides, asbestos siding, three bay facade, six panel door, gable above, paired 3/1 windows flank entrance, louvered vents in gables, end chimney. 6 1024 C
- 654 170 S FULTON ST c. 1920. Bungalow, one story, gable roof front, frame, attached offcenter gable porch with paneled box columns now filled with multi-lights, paired 2/2 windows in main gable, louvered vent, exposed rafters. 17 1023 C
- 655 200 S FULTON ST c. 1955. Ranch Style, one story, gable on hip sides, brick, three bay facade, attached gable on ornamental iron supports over entrance, six panel door flanked by multi-light casement metal windows, box cornice. 18 1023 N
- 656 201 S FULTON ST c. 1925. Bungalow, one story,, gable roof front, recessed porch covers facade,, battered, boxed columns on brick plinths, three bay facade, wood door with flanking 6/6 windows, pair louvered vents in gable, knee braces, exposed rafters. 5 1024 C

26 8

1120

United States Department of the Interior
National Park Service

National Register Of Historic Places
Continuation Sheet

Section Number 7 Page 81

MID TOWN HISTORIC DISTRICT
Mobile
Mobile County, AL

- 657 202 S FULTON ST c. 1955. Ranch Style, one story gable roof sides, brick, three bay facade, attached gable porch with ornamental iron supports at entrance, six panel door, picture window south adjacent and casement metal windows north adjacent, box cornice. 19 1023 N
- 658 203 S FULTON ST c. 1930. Bungalow, one story, gable on hip, frame, inset entrance and porch with open picture window sized openings, Craftsman door, paired 3/1 windows, louvered vent, exposed rafters. 4 1024 C
- 659 204 S FULTON ST c. 1925. Bungalow, one story, gable roof front, vinyl sided, recessed porch covers facade, six panel door, aluminum windows, battered, boxed columns on brick plinths, exposed rafters, interior chimney. 20 1023 C
- 660 205 S FULTON ST c. 1925. Bungalow, one and a half story, gable roof sides, frame, three bay facade, inset porch with paired square columns on brick plinths, balustrade, large pane windows with transom, Craftsman door, shed roof dormer with multi-light windows, exposed rafters, interior chimney, end chimney. 3 1024 C
- 661 206 S FULTON ST c. 1925. Bungalow, one story, gable roof front, frame, three bay facade, attached offcenter porch with stucco pillars, screened, multi-light door, paired 3/1 windows in main gable, knee braces, exposed rafters, side chimney. 21 1023 C
- 662 207 S FULTON ST c. 1930. Bungalow, one story,, gable roof front, attached, offcenter gable roof porch, Tuscan columns on block plinths, three bay facade, 2/2 windows flank door, knee braces, louvered vent, exposed rafters, interior chimney. 2 1024 C
- 663 208 S FULTON ST c. 1945. Minimal Traditional, one story, cross gable, vinyl sided, three bay facade, six panel door, chimney flanked by 8/8 windows, louvered vent, box cornice. 22 1023 C
- 664 209 S FULTON ST c. 1930. Bungalow, one story, gable roof front, attached offcenter gable porch with Tuscan columns on brick plinths, canvas awnings obscure windows and door, louvered vent, exposed rafters, interior chimney. 1 1024 C
- 665 210 S FULTON ST c. 1920. Vernacular, one story, hip roof, frame, recessed porch covers facade, square posts, six panel door flanked by paired 2/2 windows with board shutters, scalloped eave board. 23 1023 C

United States Department of the Interior
National Park Service

National Register Of Historic Places
Continuation Sheet

Section Number 7 Page 82

MID TOWN HISTORIC DISTRICT
Mobile
Mobile County, AL

- 666 211 S FULTON ST c. 1940. Bungalow, one story, gable roof sides, three bay facade, asbestos sided, attached offcenter gable porch with paired box columns on brick plinths, Craftsman door, 1/1 windows, light in gable, exposed rafters, end chimney. 35 1023 C
- 667 212 S FULTON ST c. 1915. Vernacular, one story, high hip roof, two bay facade, frame, recessed porch covers facade, box columns with capitals, door with sidelights and transom, large single pane window with transom, exposed rafters. 24 1023 C
- 668 213 S FULTON ST c. 1925. Bungalow, one story, gable roof front, attached gable porch covers facade, box columns and balustraded, duplex with pair front doors, flanked by 2/2 windows, exposed rafters. 34 1023 C
- 669 214 S FULTON ST c. 1945. Minimal Traditional, two story, cross gable, ell plan, vinyl sided, recessed porch in ell with square post, shed roof dormer above with casement windows, paired 6/6 windows in front gable. 25 1023 C
- 670 215 S FULTON ST c. 1940. Minimal Traditional, one story, cross gable, asbestos sided, inset porch, screened with awning obscuring all detail, awning at windows in front gable, exposed rafters. 33 1023 C
- 671 251 S FULTON ST c. 1940. Minimal Traditional, one story, hip roof, asbestos sided, offcenter attached gable porch, paired Tuscan columns, wood door, 6/6 windows. 30 1023 C
- 672 253 S FULTON ST c. 1925. Bungalow, one story, gable roof front, attached, offcenter gable roof porch, battered, boxed columns on brick plinths, 1/1 windows, wood door, knee braces, exposed rafters. 32 1023 C
- 673 255 S FULTON ST c. 1925. Bungalow, one story, gable roof front, three bay facade, frame, attached offcenter gable porch with box columns on brick plinths, frame infill between plinths, multi-light front door, 2/2 windows, knee braces, louvered vent, exposed rafters. 31 1023 C
- 674 256 S FULTON ST c. 1910. Vernacular, one story, hip roof, frame, recessed porch covers facade and wraps south side, box columns with capitals, screened, windows and doors not visible, hip roof dormer, interior chimney, box cornice. 26 1023 C

United States Department of the Interior
National Park Service

National Register Of Historic Places
Continuation Sheet

Section Number 7 Page 83

MID TOWN HISTORIC DISTRICT
Mobile
Mobile County, AL

- 675 259 S FULTON ST c. 1945. Shotgun House, one story, gable roof front, attached gable porch with Tuscan columns, paired 6/6 windows, exposed rafters, interior chimney. 29 1023 C
- 676 261 S FULTON ST c. 1945. Minimal Traditional, one story, gable roof front, asbestos sided, shed roof bay window with three pairs of casement windows, side entrance, exposed rafters. 28 1023 C
- 677 263 S FULTON ST c. 1945. Minimal Traditional, one story, gable roof front, frame, four bay facade, paired multi-light windows, flanked by 6/6 windows, entrance around south elevation and not visible, side chimney, exposed rafters. 27 1023 C
- 678 50 GLENWOOD ST c. 1925. Bungalow, one story, gable roof sides, frame, inset porch south end, square brick pillar, paired 6/1 windows, knee braces, exposed rafters. 1 1027 C
- 679 51 GLENWOOD ST c. 1925. Bungalow, one story, gable roof front, frame, three bays, attached offcenter gable porch with square brick pillars, multi-light door, flanked by 3/1 windows, purlins, louvered vent, box cornice, side chimney. 1 1025 C
- 680 52 GLENWOOD ST c. 1945. Cottage Revival, one story, cross gable, frame, pair gables at facade with chimney between, entrance in north gable, small gable with round top door, 6/1 windows, louvered vents, box cornice, closed return. 35 1026 C
- 681 53 GLENWOOD ST c. 1925. Bungalow, one story, gable roof sides, inset porch south end, with box corner post with capital, entrance in side of porch, Craftsman windows flank wide stucco chimney at facade, exposed rafters. 2 1025 C
- 682 54 GLENWOOD ST c. 1945. Cottage Revival, one story, cross gable, frame, front gable sweeps to south, round top door with small light south adjacent, inset porch infilled with frame and two large single pane windows, louvered vent. 34 1026 C
- 683 55 GLENWOOD ST c. 1925. Bungalow, one story, jerkin head gable front, frame, three bay facade, recessed porch covers facade, paneled, boxed columns on stucco plinths, door obscured by screen, paired 3/1 windows flank entrance, louvered vent, purlins, exposed rafters, porte-cochere south side. 3 1025 C

26 7
1025

United States Department of the Interior
National Park Service

National Register Of Historic Places
Continuation Sheet

Section Number 7 Page 84

MID TOWN HISTORIC DISTRICT
Mobile
Mobile County, AL

- 684 56 GLENWOOD ST c. 1945. Minimal Traditional, one story, cross gable, frame, three bay facade, steep gable over entrance, attached metal awning on metal supports, large stepped chimney north adjacent, paired 6/1 windows south adjacent and framed in porch, exposed rafters. 33 1026 C
- 685 57 GLENWOOD ST c. 1945. Minimal Traditional, one story, cross gable, asbestos sided, three bay facade, inset porch south end, screened with ornamental iron balustrade, wide chimney flanked by 6/1 windows, louvered vents, box cornice. 4 1025 C
- 686 58 GLENWOOD ST c. 1925. Bungalow, one story, gable roof front, frame, three bay facade, Craftsman door with transom, flanked by grouped Craftsman windows,, recessed porch covers facade, square brick pillars, louvered vent, knee braces, exposed rafters. 32 1026 C
- 687 60 GLENWOOD ST c. 1925. Bungalow, one story, gable on hip roof front, frame, recessed porch covers facade, square brick pillars, gable at south end, screened, Craftsman windows, exposed rafters. 31 1026 C
- 688 61 GLENWOOD ST c. 1950. Minimal Traditional, one story, gable roof sides, brick, attached offcenter gable porch with square brick pillars, metal awnings, entrance and windows too dark to see, interior chimney, box cornice. 5 1025 C
- 689 62 GLENWOOD ST c. 1945. Minimal Traditional, one story, gable roof sides, asbestos sided, four bay facade, six panel door with attached shed roof porch on ornamental iron supports, 8/8 windows, louvered vents end gables. 30 1026 C
- 690 63 GLENWOOD ST c. 1925. Bungalow, one story, gable roof sides, stucco, inset porch, screened with metal awnings, paired 6/1 windows, knee braces, exposed rafters, interior chimney. 6 1025 C
- 691 64 GLENWOOD ST c. 1945. Minimal Traditional, one story, gable sides, asbestos sided, three bay facade, attached gable at entrance with square posts, tripled 6/6 windows north adjacent, single 6/6 window south adjacent, interior chimney. 29 1026 C
- 692 65 GLENWOOD ST c. 1925. Cottage Revival, one and a half story, cross gable, shingled, five bay facade, centered gable with chimney up front, flanked by small casement windows, roofline sweeps down to south over round top slightly inset entrance, casement windows south adjacent, pair shed roof dormers in front gable. 7 1025 C

United States Department of the Interior
National Park Service

National Register Of Historic Places
Continuation Sheet

Section Number 7 Page 85

MID TOWN HISTORIC DISTRICT
Mobile
Mobile County, AL

- 693 66 GLENWOOD ST c. 1925. Mission Revival, one story, gable roof front a later addition onto flat parapeted original roof, stucco, square entrance block with wing wall and opening, bank French doors south adjacent with twisted columns between each set of doors, awning above, pipe vents. 28 1026 C
- 694 67 GLENWOOD ST c. 1945. Minimal Traditional, one story, cross gable, asbestos sided, three bay facade, wood door with wood shed roof awning above, paired 6/1 windows flank entrance, lunette louvered vent, box cornice closed return, end chimney. 8 1025 C
- 695 68 GLENWOOD ST c. 1940. Minimal Traditional, one story, cross gable, frame, three bay facade, front gable roof line extends over centered entrance, round top opening and door, bay window south adjacent, chimney north adjacent, louvered vent. 27 1026 C
- 696 69 GLENWOOD ST c. 1940. Bungalow, one story, gable roof sides, frame, three bay facade, six panel door with fabric awning, paired 1/1 windows south adjacent, chimney and 3/1 window north adjacent, exposed rafters. 9 1025 C
- 697 70 GLENWOOD ST c. 1940. Minimal Traditional, one story, gable sides, frame, attached offcenter gable porch with box columns and balustraded, six panel door, tripled 6/6 windows south adjacent, paired north adjacent, louvered lunette in gable, box cornice. 26 1026 C
- 698 71 GLENWOOD ST c. 1940. Neoclassical Revival, one story, gable roof front, recessed porch covers facade, square columns with capitals, balustraded, screened, dentil course, louvered vent, box cornice, side chimney. 10 1025 C
- 699 72 GLENWOOD ST c. 1940. Minimal Traditional, one and a half story, gable roof sides, asbestos sided, three bay facade, awning over entrance, flanking aluminum windows, pair gable dormers with 6/6 windows, triangular louvered vents in end gables. 25 1026 C
- 700 100 GLENWOOD ST c. 1940. Minimal Traditional, one story, cross gable, frame, original porch infilled with frame and aluminum windows, louvered vent, box cornice. 24 1026 C
- 701 101 GLENWOOD ST c. 1925. Bungalow, two story, gable roof front, frame, two bay facade, attached one story hip roof porch covers facade, pierced brick pillars and balustrade, 1/1 windows, fabric awnings at second story, louvered vent, exposed rafters, interior chimney. 11 1025 C

ca 9
ncb

United States Department of the Interior
National Park Service

National Register Of Historic Places
Continuation Sheet

Section Number 7 Page 86

MID TOWN HISTORIC DISTRICT
Mobile
Mobile County, AL

- 702 102 GLENWOOD ST c. 1945. Minimal Traditional, one story, gable roof sides, frame, three bay facade, inset porch south bay, square posts, balustraded, attached rain porch with brackets off posts, pair of 6/1 windows flank broad chimney at facade, box cornice closed return. 23 1026 C
- 703 103 GLENWOOD ST c. 1940. Minimal Traditional, one story, gable roof sides, frame, three bay facade, inset porch north end with gable above, square brick pillars, chimney at facade flanked by windows with canvas awnings obscuring top sash, louvered vent, box cornice, closed return. 12 1025 C
- 704 104 GLENWOOD ST c. 1945. Colonial Revival, one and a half story, gable roof sides, frame, three bay facade, attached hip roof porch covers facade, Tuscan columns, six panel door with sidelights, flanking paired 6/1 windows, three gable dormers with 9 pane lights. 22 1026 C
- 705 105 GLENWOOD ST c. 1970. Ranch Style, one story, gable roof sides, brick and board and batten, diamond pane lights, box cornice. 13 1025 N
- 706 106 GLENWOOD ST c. 1925. Bungalow, one story, gable on hip roof front, frame, three bay facade, recessed porch covers facade with gable over steps, paneled box columns on brick plinths, brick balustrade, two front doors, multi-light, 3/1 windows, knee braces, exposed rafters. 21 1026 C
- 707 107 GLENWOOD ST c. 1930. Bungalow, one story, hip roof, stucco, offcenter hip roof block with entrance and paired 6/1 windows. Entrance sheltered by bubble awning, exposed rafters, side chimney. 14 1025 C
- 708 108 GLENWOOD ST c. 1925. Bungalow, one story, gable roof front, frame, three bay facade, attached offcenter gable porch with square brick pillars, brick balustrade, six panel door flanked by paired 3/1 windows, knee braces, louvered vent, exposed rafters, side chimney. 20 1026 C
- 709 109 GLENWOOD ST c. 1945. Minimal Traditional, one and a half story, gable roof sides, asbestos sided, three bay facade, six panel door, attached hip roof porch with ornamental iron posts covers entrance only, flanked by paired aluminum windows, shed roof dormer center above with paired aluminum windows, box cornice. 15 1025 C
- 710 110 GLENWOOD ST c. 1925. Bungalow, one story, gable roof front, frame, attached gable porch covers facade, paneled, boxed columns on brick plinths, wood door with flanking 1/1 windows, louvered vent, purlins, exposed rafters. 19 1026 C

cb
2007

United States Department of the Interior
National Park Service

National Register Of Historic Places
Continuation Sheet

Section Number 7 Page 87

MID TOWN HISTORIC DISTRICT
Mobile
Mobile County, AL

- 711 111 GLENWOOD ST c. 1940. Minimal Traditional, one story, gable roof sides, frame, inset porch south end with square brick pillars, gable over porch, tripled 3/1 windows north adjacent, louvered vent, box cornice. 16 1025 C
- 712 112 GLENWOOD ST c. 1930. Cottage Revival, one story, gable roof sides, centered entrance, Craftsman door in A-frame gable, shingled, tripled 6/1 windows north adjacent, inset, screened porch south adjacent, exposed rafters. 18 1026 C
- 713 113 GLENWOOD ST c. 1925. Bungalow, one story, gable roof front, vinyl sided, attached offcenter gable porch, square brick pillars, six panel door, 3/1 windows, knee braces, louvered vent, exposed rafters, side chimney. 17 1025 C
- 714 114 GLENWOOD ST c. 1925. Bungalow, one story, jerkin head gable front, frame, attached staggered gable bay with Craftsman door and gable covering on wall brackets, tripled 6/1 windows, inset porch south adjacent wraps south elevation, pierced brick columns, knee braces. 17 1026 C
- 715 115 GLENWOOD ST c. 1925. Bungalow, one story, cross gable, frame, recessed porch covers facade, square brick pillars, six panel door, 3/1 windows, louvered vent, exposed rafters, side chimney, purlins. 18 1025 C
- 716 116 GLENWOOD ST c. 1930. Cottage Revival, one story, cross gable, frame, centered entrance with shingled gable, louvered vent, paired 6/1 windows north adjacent, inset porch south adjacent with tripled square corner post, end chimney, box cornice. 16 1026 C
- 717 117 GLENWOOD ST c. 1925. Bungalow, gable roof front, vinyl sided, three bay facade, attached gable porch covers facade, square brick pillars, Craftsman door flanked by paired 4/1 windows, louvered vent, side chimney. 19 1025 C
- 718 118 GLENWOOD ST c. 1940. Bungalow, one story, gable roof sides, frame, three bay facade, 8/8 windows, multi-light door with transom, attached shed roof porch at entrance with slightly battered columns, exposed rafters. 15 1026 C
- 719 119 GLENWOOD ST c. 1940. Minimal Traditional, one story, cross gable, frame, inset porch south end with square posts, gable over steps, 8/8 windows, exposed rafters, louvered vent, end chimney. 20 1025 C

cb 9

United States Department of the Interior
National Park Service

National Register Of Historic Places
Continuation Sheet

Section Number 7 Page 88

MID TOWN HISTORIC DISTRICT
Mobile
Mobile County, AL

-
- 720 121 GLENWOOD ST c. 1925. Bungalow, one story, gable roof front, frame, three bay facade, attached offcenter gable porch with square brick pillars, porte-cochere south side, six panel door flanked by tripled 3/1 windows, louvered vent in main gable, exposed rafters. 21 1025 C
- 721 122 GLENWOOD ST c. 1915. Bungalow, one and a half story, gable roof sides, frame, attached shed roof porch covers facade, shingled columns on brick plinths, multi-light door, paired 9/1 windows, gable dormer above with pair 6/1 windows, louvered vent, box cornice, closed return. 14 1026 C
- 722 150 GLENWOOD ST c. 1945. Minimal Traditional, one story, gable roof sides, asbestos sided, four bay facade, multi-light door with attached gable porch on square posts, 3/1 windows, some paired, exposed rafters. 13 1026 C
- 723 151 GLENWOOD ST c. 1925. Bungalow, one story, cross gable, vinyl sided, original recessed porch infilled with aluminum windows, six panel door with lunette window, porte-cochere infilled with wood and door, louvered vent, box cornice. 22 1025 N
- 724 152 GLENWOOD ST c. 1945. Minimal Traditional, one story, gable roof sides, asbestos sided, three bay facade, panel door with six lights, attached gable porch with square posts and balustrade, 8/8 windows, exposed rafters. 12 1026 C
- 725 153 GLENWOOD ST c. 1945. Minimal Traditional, one story, gable roof sides, frame, four bay facade, six panel door slightly inset with gabled surround, 12/12 windows, inset porch south end with square posts and balustraded, box cornice. 23 1025 C
- 726 154 GLENWOOD ST c. 1925. Bungalow, one story, gable on hip roof, brick, three bay facade, attached offcenter hip porch with arched openings and brick columns, Craftsman door flanked by paired 3/1 windows, box cornice. 11 1026 C
- 727 155 GLENWOOD ST c. 1955. Minimal Traditional, one story, gable roof sides, vinyl sided, windows shielded by canvas awnings, slightly inset entrance with canvas awning, end chimney. 24 1025 N
- 728 156 GLENWOOD ST c. 1945. Minimal Traditional, one story, gable roof sides, frame, five bay facade, attached centered gable porch with box columns and ornamental iron brackets, six panel door with flanking 9/9 windows, other windows 6/6, box cornice. 10 1026 C

United States Department of the Interior
National Park Service

National Register Of Historic Places
Continuation Sheet

Section Number 7 Page 89

MID TOWN HISTORIC DISTRICT
Mobile
Mobile County, AL

- 729 159 GLENWOOD ST c. 1925. Creole Cottage, one story, gable roof sides, frame, five bay facade,, recessed porch covers facade, box columns with capitals, six panel door, 6/6 windows with shutters, end chimney, exposed rafters. 25 1025 C
- 730 160 GLENWOOD ST c. 1930. Bungalow, one story, gable roof front, frame, three bay facade, attached, centered, gable porch with paired square posts, stained glass light in gable, louvered vent in main gable, wood door flanked by paired windows, exposed rafters, side chimney. 9 1026 C
- 731 161 GLENWOOD ST c. 1925. Bungalow, one story, gable on hip roof, stucco with brick water table, recessed porch offcenter with square stucco pillars, porte-cochere off north side, door with window, sidelights and transom, paired 6/1 windows. 26 1025 C
- 732 162 GLENWOOD ST c. 1940. Minimal Traditional, one story, gable roof front, frame, three bay facade, attached gable bay with paired 6/6 windows and shed roof side porch over multi-light entrance, square post, louvered vent, box cornice. 8 1026 C
- 733 163 GLENWOOD ST c. 1930. Bungalow, one story, gable roof front, brick, pair gable bays each end, each with paired 6/1 windows, shed roof porch between with paneled box columns and screened, paired 6/1 windows in gable above, exposed rafters. 27 1025 C
- 734 165 GLENWOOD ST c. 1945. Minimal Traditional, two story, gable roof sides with gable wings each end, frame, three bay facade, side entrance, six panel door with sidelights, covering over steps, 8/8 window first floor, 6/6 second floor, interior chimney, metal awnings over windows in gable wings. 28 1025 C
- 735 166 GLENWOOD ST c. 1940. Minimal Traditional, one story, cross gable, vinyl sided, eave of front gable extends down over round top entrance, awning, 8/8 windows, louvered vent, chimney at facade, box cornice. 7 1026 C
- 736 167 GLENWOOD ST c. 1945. Minimal Traditional, one story, hip roof, gable bays form H plan, frame, no entrance visible from street, attached shed roof porch connects the gable wings, square posts, pair 6/6 windows under porch, each gable bay features 12/12 window, shutters missing. Triangular vents in gables, box cornice closed return, end chimney. 29 1025 C
- 737 170 GLENWOOD ST c. 1940. Minimal Traditional, one story, cross gable, vinyl sided, three bay facade, multi-light door, original windows replaced with single pane lights, gable over entrance, no support, wall chimney at facade. 6 1026 C

United States Department of the Interior
National Park Service

National Register Of Historic Places
Continuation Sheet

Section Number 7 Page 90

MID TOWN HISTORIC DISTRICT
Mobile
Mobile County, AL

- 738 200 GLENWOOD ST c. 1945. Colonial Revival, two story, gable roof sides, brick, four bay facade, full height flat roof porch with box columns with capitals covers three bays, six panel door with swan's neck pediment and classical surround, 6/6 windows with shutters, end chimney. 5 1026 C
- 739 201 GLENWOOD ST c. 1945. Minimal Traditional, one and a half story, gable roof sides, frame, offcenter entrance, six panel door with fabric awning in small gable, 8/8 window north adjacent, pair frame dormers with 6/6 windows, interior chimney. 30 1025 C
- 740 203 GLENWOOD ST c. 1960. Two story, gable roof sides, asbestos sided, attached one story gabled garage offcenter facade, attached one story shed roof porch with ornamental iron support south adjacent, 6/6 windows, circular light second floor middle bay, louvered vent in garage and metal door. 31 1025 N
- 741 206 GLENWOOD ST c. 1945. Minimal Traditional, one story, cross gable, asbestos sided, ell plan, 6/6 window in front gable with shutters and lintal, attached shed roof porch with square posts and balustraded, end chimney. 4 1026 C
- 742 207 GLENWOOD ST c. 1955. One and a half story, brick, cross gable, gable garage south end with metal roll door, centered entrance with shed roof and ornamental iron supports, pair gable dormers, metal casement windows, slate roof. 32 1025 N
- 743 208 GLENWOOD ST c. 1980. Modern, one story, gable front, frame, rear section features broken gable with clerestory windows, paired single pane window, front gable section has no windows or doors facing street. 3 1026 N
- 744 210 GLENWOOD ST c. 1945. Minimal Traditional, one story, cross gable, ell plan, asbestos sided, front gable features paired 6/6 windows with inset, screened porch, ornamental iron supports, balustrade, louvered vent, picture window in ell with flanking 9/9 windows, exposed rafters. 2 1026 C
- 745 211 GLENWOOD ST c. 1925. Bungalow, one story, cross gable, frame, gable front with recessed porch covering facade, square brick pillars and screened, Craftsman door flanked by paired 3/1 windows, triangular louvered vent in gable, exposed rafters, interior chimney. 33 1025 C
- 746 213 GLENWOOD ST c. 1945. Minimal Traditional, one story, gable roof sides, asbestos sided, three bay facade, attached gable over entrance with ornamental iron supports, four panel door with fanlight, 8/8 windows with shutters. 34 1025 C

MS
1026 C

United States Department of the Interior
National Park Service

National Register Of Historic Places
Continuation Sheet

Section Number 7 Page 91

MID TOWN HISTORIC DISTRICT
Mobile
Mobile County, AL

- 747 214 GLENWOOD ST c. 1975. Ranch Style, one story, gable roof front, brick, attached gable porch with Tuscan columns, iron railing, three bay facade, wood door with flanking aluminum windows, box cornice. 1 1026 C
- 748 2250 GOVERNMENT ST c. 1925. Bungalow, one story, gable roof front, frame, three bay facade,, recessed porch covers facade, square brick pillars, six panel door, tripled 3/1 windows east bay, doubled 3/1 windows west bay, gable porte-cochere east side, knee braces, louvered vent, exposed rafters. 26 1002 C
- 749 8 HOMER ST c. 1925. Bungalow, one story, gable roof front,, attached, offcenter gable roof porch, square brick pillars, metal awnings across and around porch and over other windows, Craftsman door and windows, louvered vent in gable, bargeboard in gable, exposed rafters. 5 1037 C
- 750 10 HOMER ST c. 1955. Minimal Traditional, one story, gable roof sides, brick, three bay facade, attached gabled porch covers center bay, ornamental iron supports, triangular vent in gable, metal casement windows south adjacent, paired 6/6 windows north adjacent, box cornice closed return. 6 1037 N
- 751 12 HOMER ST c. 1950. Minimal Traditional, one story, gable roof sides, asbestos sided, three bay facade, six panel door with attached gable over steps on ornamental iron supports, paired windows either side with metal awnings, box cornice. 7 1037 C
- 752 16 HOMER ST c. 1925. Bungalow, one and a half story, cross gable, frame, front gable roofline sweeps across porch, battered box columns on brick plinths, multi-light door in side under porch, tripled windows in facade obscured by metal awning, 6/6 window in gable, exposed rafters. 8 1037 C
- 753 18 HOMER ST c. 1910. Vernacular, one story on piers, high hip roof, frame, three bay facade, inset porch covers two bays, square posts, wood door with window, transom, 2/2 windows, exposed rafters, interior chimney. 9 1037 C
- 754 20 HOMER ST c. 1960. Ranch Style, one story, gable roof front, brick, three bay facade, wood door with multi-light window, flanked by metal windows, patterned board and batten gable with triangular louvered vent, flat roof carport south side, box cornice. 10 1037 N
- 755 2156 HOMEWOOD ST c. 1945. Minimal Traditional, one story, cross gable, frame, pair staggered gables at facade, smaller one contains six panel door, larger one has single shouldered chimney with 3/1 light north adjacent and pair 3/1 windows south of entrance bay, exposed rafters. 6 1007 C

United States Department of the Interior
National Park Service

National Register Of Historic Places
Continuation Sheet

Section Number 7 Page 92

MID TOWN HISTORIC DISTRICT
Mobile
Mobile County, AL

- 756 2157 HOMEWOOD ST c. 1945. Creole Cottage, one and a half story, gable roof sides, frame, three bay facade, door with six light window, flanking 8/8 windows, shed roof porch with square posts, pair gable dormers with 6/6 windows, exposed rafters. 7 1007 C
- 757 2158 HOMEWOOD ST c. 1925. Bungalow, one story, gable roof front, frame, three bay facade, six panel door, 3/1 windows, attached offcenter gable porch with paneled box columns on brick plinths, louvered vents, exposed rafters. 5 1007 C
- 758 2159 HOMEWOOD ST c. 1930. Bungalow, one story, gable roof sides, frame, three bay facade, attached, offcenter gable roof porch, box columns with capitals, six panel door, paired 1/1 windows flank entrance, porte-cochere off north side, stucco pillars, end chimney, exposed rafters, small louvered vent in gable. 8 1007 C
- 759 2160 HOMEWOOD ST c. 1925. Bungalow, one story, gable roof front, frame, attached offcenter gable porch with attached porte-cochere to north side, square brick pillars, six panel door with sidelights and transom, exposed rafters. 4 1007 C
- 760 2161 HOMEWOOD ST c. 1940. Cottage Revival, one story, cross gable, asbestos sided, four bay facade, centered gable with sweeping roofline to north, chimney at facade flanked by 3/1 windows, small gable north adjacent, inset porch with brick arch, paired 3/1 windows, louvered vent, exposed rafters. 9 1007 C
- 761 2200 HOMEWOOD ST c. 1940. Minimal Traditional, one story, gable roof sides, frame, three bay facade, inset porch north end with square posts and balustrade, entrance not visible from street, as it is in north side of porch, chimney at facade flanked by 1/1 windows, box cornice. 3 1007 C
- 762 2204 HOMEWOOD ST c. 1945. Minimal Traditional, one story, gable sides, vinyl sided, three bay facade, wood door with window in three vertical lights in A-frame gable, flanking paired 6/1 windows, box cornice, end chimney. 1 1007 C
- 763 2204 HOMEWOOD ST c. 1925. Bungalow, one story, gable roof front, frame, three bay facade, attached offcenter gable on hip porch with porte-cochere north side, square brick pillars, six panel door with sidelights and transom, 3/1 windows, exposed rafters, side chimney. 2 1007 C
- 764 2206 HOMEWOOD ST c. 1930. Bungalow, one story, cross gable on jerkin head gable, vinyl sided, attached gable on ornamental iron supports at entrance, 3/1 windows. 35 1006 C

26 3
1-3

United States Department of the Interior
National Park Service

National Register Of Historic Places
Continuation Sheet

Section Number 7 Page 93

MID TOWN HISTORIC DISTRICT
Mobile
Mobile County, AL

- 765 2207 HOMEWOOD ST c. 1925. Bungalow, one story, gable roof sides, frame, three bay facade, attached shed roof porch covers facade, square posts, lattice panels, paired windows either side entrance, 3/1 south adjacent, one 6/1 and one 3/1 paired north adjacent, end chimney. 10 1007 C
- 766 2208 HOMEWOOD ST c. 1950. One story, brick, hip roof, attached offcenter gable porch with square brick columns, picture window, jalousied windows and paired 3/1 windows at facade, Craftsman door, boxed cornice. 34 1006 C
- 767 2209 HOMEWOOD ST c. 1925. Cottage Revival, one story, cross gable, brick, two bay facade, dominate gable features set three full height casement windows, lunette louver vent above, secondary gable south adjacent set back with round top door, six pane light south adjacent, chimney up south side of dominant gable. 11 1007 C
- 768 1804 HUNTER AVE c. 1925. Bungalow, two story, hip roof, frame, three bay facade, attached one story shed roof porch, paneled boxed columns on brick plinths, low balustrade, six panel door, 3/1 windows, bay window second floor with support brackets, box cornice. 1 1004 C
- 769 1806 HUNTER AVE c. 1900. Victorian cottage, one story, hip roof, frame, in process of being dismantled, inset porch east end with turned posts and balustrades, 2/2 windows, box cornice, door removed and much of siding at facade. 2 1004 C
- 770 1808 HUNTER AVE c. 1930. Bungalow, one story, jerkin head gable front, brick, three bay facade, inset porch, screened, 3/1 windows, concrete belt course around house at window sill level, pair lights in gable with stone sill, exposed rafters. 3 1004 C
- 771 1810 HUNTER AVE c. 1910. American Foursquare, two story, hip roof, frame, three bay facade, attached offcenter hip roof porch with square columns with capitals, four panel door with sidelights and transom, 1/1 windows, exposed rafters. 4 1004 C
- 772 1813 HUNTER AVE c. 1945. Minimal Traditional, one story, gable roof sides, brick, duplex, centered attached gable porch with pair brick arched openings, pair doors with six lights each, pair 6/1 windows east and west adjacent, louvered vent, box cornice, closed return. 7 1004 C
- 773 1814 HUNTER AVE c. 1920. Neoclassical Revival, one and a half story, gable roof sides, attached gable roof porch covers facade, box columns with capitals, four panel door with sidelights and transom, flanked by tripled 1/1 windows, set three 1/1 windows in gable, interior chimney. 5 1004 C

United States Department of the Interior
National Park Service

National Register Of Historic Places
Continuation Sheet

Section Number 7 Page 94

MID TOWN HISTORIC DISTRICT
Mobile
Mobile County, AL

- 774 1815 HUNTER AVE c. 1920. Bungalow, one story, cross gable, ell plan, frame, three bay facade, attached shed roof porch covers two bays and abutts front gable, door features six lights, 6/1 windows, paired in front gable, knee braces, exposed rafters, interior chimney. 6 1004 C
- 775 1853 HUNTER AVE c. 1945. Minimal Traditional, one story, frame, cross gable, ell plan, four bay facade, six panel door in front gable, attached gable over steps with ornamental iron supports, 8/8 windows, exposed rafters, interior chimney. 14 1005 C
- 776 1854 HUNTER AVE c. 1925. Bungalow, one story, gable roof sides, vinyl sided, three bay facade, attached offcenter hip roof porch with paneled boxed columns on brick plinths, side entrance a wood door with six lights, sidelights, paired 3/1 windows adjacent, box cornice, interior chimney. 12 1004 C
- 777 1855 HUNTER AVE c. 1940. Colonial Revival, two and a half story, brick, three bay facade, attached one story broken gable porch with paired square posts, six panel door with fan transom and sidelights, 8/8 windows to either side, paired 6/6 windows over porch, three gable dormers with 6/6 windows, end chimney, attached one story gable porch west elevation, screened. 13 1005 C
- 778 1856 HUNTER AVE c. 1940. Colonial Revival, one and a half story, gable roof sides, three bay facade, frame, six panel door, sidelights and fan transom, flanking 8/8 windows with sutters, recessed porch covers facade, Tuscan columns, pair gable dormers with 8/8 windows, end chimney. 13 1004 C
- 779 1857 HUNTER AVE c. 1935. Cottage Revival, two and a half story, gable roof sides, brick first floor up to sill level on second, stucco above, five bay facade, 6/6 windows, entrance east end, six panel door with fabric awning, pair gable dormers with casement windows, interior chimney, exposed rafters. 12 1005 C
- 780 1859 HUNTER AVE c. 1930. Bungalow, one story, gable roof sides, vinyl sided, three bay facade, attached offcenter gable porch with paired square posts with capitals, wood door with window, sidelights, 6/6 windows, oval louvered vent, box cornice. 11 1005 C
- 781 1861 HUNTER AVE c. 1925. Bungalow, two story, gable on hip roof, frame, three bay facade, center two story gable bay with paired 6/6 windows first and second story, louvered vent, entrance east end, inset with brick pillar, peaked openings, west end features inset sleeping porch at second story, screened, paired 6/6 windows first story, exposed rafters. 10 1005 C
- 782 1863 HUNTER AVE c. 1925. Bungalow, two story, gable on hip, first story brick second shingled, side entrance with attached gable porch, Tuscan columns, bank casement windows with transoms center bay first story, paired 6/1 windows west end, second story features small casement window over porch, then two large 1/1 windows, then paired 1/1 windows at west end, interior chimney, exposed rafters. 9 1005 C

United States Department of the Interior
National Park Service

National Register Of Historic Places
Continuation Sheet

Section Number 7 Page 95

MID TOWN HISTORIC DISTRICT
Mobile
Mobile County, AL

- 783 1865 HUNTER AVE c. 1925. Mission/Classical Revival, two story, hip roof, stucco, two story offcenter hip roof bay projects, arched openings in first story, square stucco pillars with columns on second, screened, entrance at first story under porch features wood door with transom, chimney up front, 6/1 windows either side, main entrance west end, wood door with full classical surround, engaged columns and broken pediment with closed returns, box cornice. 8 1005 C
- 784 1901 HUNTER AVE c. 1960. Minimal Traditional, one story, gable roof front, brick, three bay facade, gable with wall braces over stoop, door with nine lights, 6/6 windows, vinyl in gable, louvered vent, box cornice. 7 1005 N
- 785 1903 HUNTER AVE c. 1925. Bungalow, one story, gable roof front, frame, three bay facade,, recessed porch covers facade, square brick pillars, six panel door with sidelights and transom, Craftsman windows, louvered vent, knee braces, exposed rafters. 6 1005 C
- 786 1905 HUNTER AVE c. 1930. Bungalow, one story, gable roof front, frame, three bay facade, attached offcenter gable porch with box columns on brick plinths, screened, entrance not visible, paired 3/1 windows, knee braces, exposed rafters, metal awning over steps. 5 1005 C
- 787 1906 HUNTER AVE c. 1940. Minimal Traditional, one story, hip roof with gable brick bay, frame main body of house, irregular mass, gable bay features bay window with metal roof, casement windows, awnings over other windows, box cornice, louvered vent. 14 1004 C
- 788 1907 HUNTER AVE c. 1945. Minimal Traditional, one story, gable roof sides, frame, three bay facade, six panel door, 6/1 windows, attached gable over entrance with ogee arch, paired square posts, knee braces in side gables, exposed rafters, interior chimney. 4 1005 C
- 789 1908 HUNTER AVE c. 1940. Colonial Revival, C. L. Hutchisson, Jr., architect, FHA house, one and a half story, frame, gable roof sides with gable wings each end to form H plan, attached one story flat roof porch between wings, Tuscan columns with balustrade on roof, six panel door with sidelights and fan transom, flanked by French doors, pair gable dormers above with 6/6 windows, wings each feature pair 6/6 windows with shutters, box cornice closed return round louvered vents in gables, interior chimney. 15 1004 C
- 790 1909 HUNTER AVE c. 1935. Bungalow, one story, hip roof with gable bay, frame, two bay facade, stoop with lattice rail, wood door with window, flanking 1/1 windows, paired 1/1 windows in bay with lattice shutters, louvered vent, exposed rafters, side chimney. 3 1005 C
- 791 1910 HUNTER AVE c. 1950. Minimal Traditional, one story, gable roof sides, brick, four bay facade, six panel door with awning, 6/6 windows with shutters, box cornice. 16 1004 C

United States Department of the Interior
National Park Service

National Register Of Historic Places
Continuation Sheet

Section Number 7 Page 96

MID TOWN HISTORIC DISTRICT
Mobile
Mobile County, AL

- 792 1911 HUNTER AVE c. 1925. Bungalow, one story, gable roof front, frame, four bay facade, attached offcenter gable porch with square brick pillars, Craftsman door flanked by Craftsman windows, tripled Craftsman windows in dominant gable, knee braces, lattice vents, exposed rafters, side chimney. 2 1005 C
- 793 1912 HUNTER AVE c. 1940. Minimal Traditional, one and a half story, brick, cross gable, ell plan, three bay gable front with side entrance, six panel door, 8/8 windows with shutters, 6/6 window with shutters in gable, box cornice closed return, interior chimney, shed roof infilled porch adjacent gable. 17 1004 C
- 794 1913 HUNTER AVE c. 1935. Bungalow, one story, cross gable, frame, three bay facade, recessed porch covers two bays, turned post and balustrade, six panel door, 3/1 windows, paired in gable front, louvered vent, knee braces, exposed rafters. 1 1005 C
- 795 1914 HUNTER AVE c. 1940. Colonial Revival, one and a half story, gable roof sides, frame, five bay facade, attached shed roof porch covers three bays, box columns with capitals, six panel door with classical surround, 6/6 windows with shutters, three gable dormers with metal casement windows, box cornice. 8 1004 C
- 796 1915 HUNTER AVE c. 1945. Minimal Traditional, one story, gable roof sides, vinyl sided, three bay facade, six panel door, attached gable porch with paired square posts, 6/6 windows with shutters, interior chimney, box cornice, closed return. 35 1004 C
- 797 1916 HUNTER AVE c. 1940. Minimal Traditional, one story, cross gable, stucco, staggered gables at facade, round top door in secondary, smaller one, casement windows, casement window in larger gable, interior chimney. 19 1004 C
- 798 1917 HUNTER AVE c. 1945. Minimal Traditional, two story, hip roof, vinyl sided, three bay facade, six panel door, attached gable on paired posts over entrance, 8/8 windows, side chimney, interior chimney. 34 1004 C
- 799 1920 HUNTER AVE c. 1945. Minimal Traditional, one and a half story, gable roof sides, vinyl sided, three bay facade, attached flat roof porch with ornamental iron supports covers most of facade, six panel door, paired 6/6 windows either side entrance, pair gable dormers with 6/6 windows, end chimney, box cornice. 20 1004 C
- 800 1921 HUNTER AVE c. 1960. Ranch Style, one story, hip roof, brick, four bay facade, paired aluminum windows, six panel door, interior chimney. 33 1004 N

United States Department of the Interior
National Park Service

National Register Of Historic Places
Continuation Sheet

Section Number 7 Page 97

MID TOWN HISTORIC DISTRICT
Mobile
Mobile County, AL

- 801 1922 HUNTER AVE 1938. Colonial Revival, C. L. Hutchisson, Jr., architect, FHA house, one and a half story, frame, gable roof sides, three bay facade, six panel door with fan transom and classical surround, 8/8 windows with shutters, pair gable dormers with 6/6 windows, end chimney. 21 1004 C
- 802 1950 HUNTER AVE c. 1950. Colonial Revival, one and a half story, gable roof sides, brick, five bay facade, six panel door with attached porch, box columns with capitals, 6/6 windows, dentil course, four segmental arch roofed dormers, 6/6 windows, attached flat roof porch west end, square posts, ornamental railing, screened, interior chimney. 22 1004 C
- 803 1951 HUNTER AVE c. 1960. Ranch Style, one story, hip roof, brick and board and batten, paired 6/6 aluminum windows, entrance around side, box cornice. 32 1004 N
- 804 1953 HUNTER AVE c. 1950. Minimal Traditional, one story, hip roof, brick, two bay facade, inset porch with ornamental iron supports, board and batten under porch to window sill level, brick below, paired 8/8 windows, wide, boxed eaves. 31 1004 C
- 805 1955 HUNTER AVE c. 1990. Ranch Style, one story, gable roof front, brick veneer, three bay facade with garage, six panel door, paired 6/6 windows, attached offcenter gable porch with slender turned posts and balustrade, board and batten gable treatment, triangular louvered vent. 30 1004 N
- 806 1956 HUNTER AVE c. 1925. Bungalow, one story, gable roof front, frame, three bay facade, attached offcenter gable porch covers one bay, porte-cochere east side extends as shed roof porch across other two bays, square brick pillars, unusual sheaf of wheat balustrade, six panel door, paired 4/1 windows, exposed rafters, purlins. 23 1004 C
- 807 1957 HUNTER AVE c. 1940. Minimal Traditional, one story, gable roof sides, frame, three bay facade, inset porch east half of house, square post and balustraded, gable over entrance, paired 6/6 windows under porch, 8/8 window in west bay, six panel door, exposed rafters, end chimney. 29 1004 C
- 808 1958 HUNTER AVE c. 1925. Bungalow, gable roofs front, vinyl sided, three bay facade, pair gable front wings, eastern one open underneath as porte-cochere, square brick pillars, inset porch between wings, wood door with window, 4/1 windows, louvered vents, purlins, exposed rafters. 24 1004 C
- 809 1959 HUNTER AVE c. 1925. Bungalow, two story, jerkin head gable sides, stucco, three bay facade, attached jerkin head gable bay, one story center with entrance, six panel door with sidelights, knee braces, metal casement windows first story, tripled 3/1 windows second story, porte-cochere east side, exposed rafters, two interior chimneys. 28 1004 C

United States Department of the Interior
National Park Service

National Register Of Historic Places
Continuation Sheet

Section Number 7 Page 98

MID TOWN HISTORIC DISTRICT
Mobile
Mobile County, AL

-
- 810 1960 HUNTER AVE c. 1920. Bungalow, one story, gable roof front, frame, three bay facade,, recessed porch covers facade, Tuscan columns on brick plinths, side entrance, wood door with window, transom, 9/1 windows, window in gable flanked by louvered vents, exposed rafters. 25 1004 C
- 811 1961 HUNTER AVE c. 1950. Minimal Traditional, one and a half story, gable roof sides, vinyl sided, three bay facade, six panel door, attached gable porch with ornamental iron supports, 8/8 windows with shutters, pair gable dormers with 6/6 windows, box cornice. 27 1004 C
- 812 1963 HUNTER AVE c. 1950. Minimal Traditional, one story, gable roof sides, asbestos sided, four bay facade, attached gable porch with ornamental iron supports covers center two bays, wood door, 6/6 windows, louvered vent. 26 1004 C
- 813 1 JAPONICA AVE c. 1950. Minimal Traditional, one story, gable roof sides, brick, five bay facade, six panel door with fabric awning over stoop, 8/8 windows, chimney at facade, box cornice. 18 1034 C
- 814 2 JAPONICA AVE c. 1945. Minimal Traditional, one and a half story, gable roof sides, frame, five bay facade, six panel door with attached gable over stoop, square posts, 6/6 windows with ornamental cast iron panels below, pair gable dormers with casement windows, dentil course across facade, box cornice. 17 1034 C
- 815 4 JAPONICA AVE c. 1945. Minimal Traditional, two story, gable roof sides, frame, three bay facade with attached two story wing north end, slightly recessed, six panel door, attached one story gable over stoop with ornamental iron supports, paired 6/6 windows with shutters, chimney between house and north wing, box cornice. 16 1034 C
- 816 6 JAPONICA AVE c. 1945. Minimal Traditional, one and a half story, gable roof sides, frame, five bay facade with attached flat roof sun porch north end, six panel door, attached flat roof porch with balustrade on top over stoop, iron supports, 6/6 windows with shutters, sun porch features 12 light windows in frame infill, balustraded roof, three gable dormers with casement windows. 15 1034 C
- 817 7 JAPONICA AVE c. 1945. Minimal Traditional, two story, gable roof sides, frame, three bay facade, six panel door, attached one story gable porch with box columns with capitals, 12/12 windows with shutters, one story porch attached south end, glassed in, box cornice. 19 1034 C
- 818 8 JAPONICA AVE c. 1945. Minimal Traditional, one and a half story, gable roof sides, brick, three bay facade with attached gable wings north and south, slightly recessed from the plane of the facade, central entrance with six panel door, sidelights, attached gable porch over stoop with paired box columns with capitals, wing to south has infilled porch, pair gable dormers with 6/6 windows, interior chimney. 14 1034 C

United States Department of the Interior
National Park Service

National Register Of Historic Places
Continuation Sheet

Section Number 7 Page 99

MID TOWN HISTORIC DISTRICT
Mobile
Mobile County, AL

-
- 819 9 JAPONICA AVE c. 1945. Minimal Traditional, one story, gable roof sides, frame, four bay facade with attached gable wing north end, six panel door with gabled, classical surround, 12/12 windows with fabric awnings, dentil course, box cornice. 20 1034 C
- 820 10 JAPONICA AVE c. 1945. Minimal Traditional, one and a half story, gable roof sides, brick, five bay facade, central entrance, louvered screen door, attached gable over stoop with ornamental iron supports, 6/6 windows with shutters, pair gable dormers with 6/6 windows, end chimney, one story flat roofed porch attached north end, screened. 13 1034 C
- 821 11 JAPONICA AVE c. 1965. Ranch Style, one story, hip roofs, garage north end with single auto bay, shed roof over stoop with iron supports, metal hurricane shutters conceal windows, box cornice. 21 1034 N
- 822 14 JAPONICA AVE c. 1945. Minimal Traditional, one story, cross gable, ell plan, frame, four bay facade, recessed porch covers three bays, square posts and broad arches, six panel door, 6/6 windows with shutters, lunette louvered vent, end chimney. 12 1034 C
- 823 15 JAPONICA AVE c. 1945. Minimal Traditional, one story, cross gable, brick, prominent gable bay at center of facade with bay window with picture windows, probably a later addition with shingled roof, entrance to south with awning, paired 6/6 windows. 22 1034 C
- 824 16 JAPONICA AVE c. 1945. Minimal Traditional, one story, gable roof sides, frame, five bay facade, six panel door, attached gable over stoop with square posts, 8/8 windows with shutters, louvered vents in end gables, interior chimney, dentil course across facade, box cornice, closed return. 11 1034 C
- 825 17 JAPONICA AVE c. 1940. Minimal Traditional, one story, gable roof sides, brick, three bay facade, center entrance with six panel door and bubble awning, pair 8/8 windows north adjacent, inset porch south adjacent with arched infill, end chimney, two story garage apartment in rear, gable on hip roof sides, frame, three wooden auto bay doors, 3/1 windows above, shed roof balcony with square posts and balustrade, six panel door, exposed rafters. 23 1034 C
- 826 18 JAPONICA AVE c. 1945. Minimal Traditional, one story, gable roof sides, vinyl sided, four bay facade, six panel door, attached gable over stoop with square posts, 8/8 windows with shutters, south bay features a sun room with a bank of metal casement windows. 10 1034 C
- 827 19 JAPONICA AVE c. 1945. Minimal Traditional, one story, gable roof sides, frame, three bay facade, six panel door, attached gable over stoop with ornamental iron supports, 12/12 full height windows with shutters, pair gable dormers with 6/6 windows, interior chimney, one story flat roof wing south end. 25 1034 C

United States Department of the Interior
National Park Service

National Register Of Historic Places
Continuation Sheet

Section Number 7 Page 100

MID TOWN HISTORIC DISTRICT
Mobile
Mobile County, AL

- 828 20 JAPONICA AVE c. 1945. Minimal Traditional, one story, gable roof sides, frame, three bay facade with attached gable wing south end, six panel door with attached gable over stoop with square posts, flanking 12/12 windows with shutters, interior chimney, minimal eave. 9 1034 C
- 829 21 JAPONICA AVE c. 1945. Minimal Traditional, two story, gable roof sides, frame, three bay facade, six panel door, 8/8 windows with shutters, end chimney, attached two story wing north end rear with garage and 6/6 windows. 26 1034 C
- 830 22 JAPONICA AVE c. 1945. Cottage Revival, one and a half story, gable roof sides, brick, three bay facade, gable wings north and south, slightly recessed, north wing features inset porch, six panel door, 12/12 windows, pair gable dormers with 6/6 windows. 8 1034 C
- 831 25 JAPONICA AVE c. 1945. Minimal Traditional, one story, cross gable, ell plan, frame, inset entrance bay, metal casement windows, end chimney, box cornice. 27 1034 C
- 832 26 JAPONICA AVE c. 1945. Minimal Traditional, one story, gable roof sides, frame, five bay facade, entrance slightly inset, wood door with diamond lights, 12/12 windows, box cornice, no return. 7 1034 C
- 833 150 KEENAN AVE c. 1925. Bungalow, one story, gable front, frame, attached offcenter gable porch with square brick pillars, three bay facade, multi-light door, paired 3/1 windows, louvered vents, exposed rafters. 21 1016 C
- 834 152 KEENAN AVE c. 1920. Bungalow, heavily altered, one story, gable roof front, brick, attached offcenter gable porch with square brick pillars, paired aluminum windows, vinyl in gable and on eaves. 20 1016 N
- 835 154 KEENAN AVE c. 1945. Minimal Traditional, one story, cross gable, vinyl sided, three bay facade, entrance shaded by attached gable with square posts, 8/8 windows with ornamental iron panels below sash. 19 1016 C
- 836 155 KEENAN AVE c. 1975. Modern apartment complex, two story, brick, mansard roof, five bay facade, aluminum windows, segmental arch roofed dormers all around. 22 1016 N

United States Department of the Interior
National Park Service

National Register Of Historic Places
Continuation Sheet

Section Number 7 Page 101

MID TOWN HISTORIC DISTRICT
Mobile
Mobile County, AL

- 837 157 KEENAN AVE c. 1890. Neoclassical Revival, moved from downtown circa 1965, one story, hip roof, frame, three bay facade, recessed porch covers facade, paneled, box columns, full height 2/2/2 windows with shutters, side hall plan, wood door with window, transom, box cornice, side chimney. 23 1016 C The architectural style of the house is compatible with those in the district; therefore, it should be considered a contributing building.
- 838 158 KEENAN AVE c. 1925. Bungalow, one and a half story, frame, three bay facade, recessed porch covers facade,, battered, boxed columns on brick plinths, central entrance with Craftsman door, paired 3/1 windows flank, gable dormer with tripled 3/1 windows, knee braces, end chimney and one interior chimney, exposed rafters. 18 1016 C
- 839 159 KEENAN AVE c. 1925. Bungalow, one story, gable roof front, vinyl sided, three bay facade, multi-light door, 1/1 windows,, recessed porch covers facade,, paneled, boxed columns on brick plinths, knee braces, box cornice. 24 1016 C
- 840 161 KEENAN AVE c. 1925. Bungalow, one and a half story, frame, hip roof, four bay facade,, recessed porch covers facade, box columns, balustraded, with lattice panels placed over balustrade on front, six panel door with sidelights offcenter, paired 3/1 windows, hip roof dormer with pair single light windows, box cornice. 25 1016 C
- 841 162 KEENAN AVE c. 1925. Bungalow, one and a half story, gable roof sides, frame, recessed porch covers facade, box columns, modern wood door flanked by paired 6/6 windows with shutters, gable dormer above with horizontal window, end chimney. 17 1016 C
- 842 163 KEENAN AVE c. 1960. One story, hip roof, brick, attached hip roof porch offcenter with ornamental iron supports and railing, metal awning across porch and over other windows, box cornice. 26 1016 N
- 843 164 KEENAN AVE c. 1960. Minimal Traditional, one story, gable roof sides, brick, three bay facade, eight panel door, shed roof porch with ornamental iron supports, metal casement windows north adjacent, large picture window south adjacent, end chimney with corbeled cap. 16 1016 N
- 844 166 KEENAN AVE c. 1925. Bungalow, one and a half story, cross gable, frame, four bay facade, recessed porch covers three bays, box columns on brick plinths, side entrance, multi-light door, paired 3/1 windows in gable on south bay, large gable dormer above with paired 3/1 windows, knee braces, exposed rafters, one story gable wing north end rear with metal awnings over windows. 15 1016 C
- 845 200 KEENAN AVE c. 1945. Minimal Traditional, one story, gable roof sides, brick, three bay facade, centered entrance with gable and bubble awning, bank casement windows north adjacent, paired 6/1 windows south adjacent, box cornice closed return, louvered vent, end chimney. 14 1016 C

United States Department of the Interior
National Park Service

National Register Of Historic Places
Continuation Sheet

Section Number 7 Page 102

MID TOWN HISTORIC DISTRICT
Mobile
Mobile County, AL

-
- 846 201 KEENAN AVE c. 1925. Bungalow, one story, hip roof, frame, attached offcenter gable porch with square posts, screened, paired 3/1 windows, large louvered vent in gable, interior chimney, exposed rafters. 27 1016 C
- 847 202 KEENAN AVE c. 1945. Minimal Traditional, one story, gable roof sides, vinyl sided, central entrance, six panel door, attached gable porch at entrance with battered brick support, round top entryway, paired 6/6 windows either side, end chimney. 13 1016 C
- 848 203 KEENAN AVE c. 1925. Bungalow, one and a half story, hip roof, vinyl sided, two bay facade, inset porch, battered box column on brick plinth, screened, tripled 1/1 windows, hip roof dormer with paired aluminum windows, box cornice. 28 1016 C
- 849 204 KEENAN AVE c. 1945. Minimal Traditional, one story, cross gable, asbestos sided, inset porch with turned post on brick plinth, aluminum windows, louvered vent, minimal eaves with crown molding. 12 1016 C
- 850 205 KEENAN AVE c. 1925. Bungalow, one story, gable roof front, vinyl sided, three bay facade, attached offcenter gable porch, box columns on brick plinths, screened, wood door with window, tripled 3/1 windows, box cornice. 29 1016 C
- 851 206 KEENAN AVE c. 1945. Minimal Traditional, one story, cross gable, asbestos sided, three bay facade, centered multi-light door with attached gable overhead on wall braces, secondary gable staggered to south, chimney with single shoulder at facade, picture windows, box cornice. 11 1016 C
- 852 208 KEENAN AVE c. 1945. Minimal Traditional, two story, gable roof sides, asbestos sided, apartment building, five bay facade, central entrance a door with multi-light windows, attached gable over stoop with square posts, paired 8/8 windows either side, end bays feature attached two story hip roofed porches with square posts and balustrades, box cornice. 10 1016 C
- 853 106 MARGARET ST c. 1925. Bungalow, one story, gable front, vinyl sided, three bay facade, attached offcenter gable over inset porch, square posts, balustraded, door obscured behind screen, paired 6/1 windows, small window in main gable, box cornice. 30 1040 C
- 854 108 MARGARET ST c. 1940. Minimal Traditional, extensively altered, one and a half story, vinyl sided facade, asbestos sided side elevations, five bay facade, six panel door with ornamental iron burglar door, 6/6 windows, pair gable dormers with single outside windows, gingerbread in dormer gables. 31 1040 N

United States Department of the Interior
National Park Service

National Register Of Historic Places
Continuation Sheet

Section Number 7 Page 103

MID TOWN HISTORIC DISTRICT
Mobile
Mobile County, AL

- 855 110 MARGARET ST c. 1945. Minimal Traditional, one story, cross gable, asbestos sided, front gable features two sets of tripled 6/6 windows each end, with metal awnings, entrance around south side with metal awning over stoop. 32 1040 C
- 856 112 MARGARET ST c. 1950. Minimal Traditional, cross gable, asbestos sided, gable bay projects at facade with metal awnings over windows, porch on south side, metal shed roof with ornamental iron supports, paired 6/6 windows, main roofline is a half gable up to ridgecrest, then runs to rear as a flat roof. 33 1040 C
- 857 114 MARGARET ST c. 1925. Bungalow, one story, gable roof front, frame, recessed porch covers facade, three bay facade, square stucco pillars, paired 3/1 windows, six panel door, knee braces, louvered vent, exposed rafters. 34 1040 C
- 858 116 MARGARET ST c. 1960. Minimal Traditional, one story, cross gable, brick, ell plan, attached metal shed roof porch on slender iron supports, metal awning over window, vinyl in gable. 35 1040 N
- 859 118 MARGARET ST c. 1925. Bungalow, one story, gable roof front, frame, three bay facade, inset porch south two bays, square posts, screened, ornamental iron railing, paired Craftsman windows, louvered vent, knee braces, exposed rafters, interior chimney. 1 1041 C
- 860 120 MARGARET ST c. 1945. Minimal Traditional, one and a half story, frame, three bay facade with gable wings north and south slightly set back, six panel door, 12/12 windows with ornamental iron burglar panels, three gable dormers with 6/6 windows. 2 1041 C
- 861 123 MARGARET ST c. 1930. Bungalow, one story, hip roof, stucco, one bay facade, bank three 3/1 windows, attached flat roof porte-cochere, exposed rafters, entrance around north side, not visible from street. 17 1041 C
- 862 124 MARGARET ST c. 1950. Minimal Traditional, one story, cross gable, frame, side entrance with inset porch with square posts, 6/6 windows with shutters, interior chimney. 3 1041 C
- 863 125 MARGARET ST c. 1945. Minimal Traditional, one story, gable roof sides, frame, three bay facade, inset porch south end, screened, entrance not visible, double shouldered chimney at facade flanked by 3/1 windows, exposed rafters. 16 1041 C

CB F
12-2-1

United States Department of the Interior
National Park Service

National Register Of Historic Places
Continuation Sheet

Section Number 7 Page 104

MID TOWN HISTORIC DISTRICT
Mobile
Mobile County, AL

- 864 126 MARGARET ST c. 1940. Minimal Traditional, two story, gable roof sides, asbestos sided, recessed porch covers facade, infilled with casement windows, 6/6 windows side elevation, exposed rafters. 4 1041 C
- 865 127 MARGARET ST c. 1925. Bungalow, one story, gable roof front, stucco, attached offcenter gable bay with tripled 3/1 windows, attached shed roof porch adjacent with square stucco pillar and knee wall, pipe vents, side chimney, frame gables, exposed rafters. 15 1041 C
- 866 128 MARGARET ST c. 1945. Minimal Traditional, one story, gable roof sides, asbestos sided, four bay facade, wood door, 8/8 windows, south bay features tripled 6/6 windows. 5 1041 C
- 867 129 MARGARET ST c. 1925. Bungalow, one story, gable front, vinyl sided, three bay facade, attached offcenter gable porch, square brick pillars, ornamental iron drop frieze, door obscured behind screen, paired 3/1 windows, metal casement windows in main gable. 14 1041 C
- 868 130 MARGARET ST c. 1945. Minimal Traditional, one story, cross gable, asbestos sided, four bay facade, entrance in small gable south end, six panel door with lunette transom, chimney with round top niche north adjacent, centered gable with pair 8/8 windows with shutters, round top louvered vent, infilled porch north bay, arched openings in brick filled with metal casement iwndows. 6 1041 C
- 869 131 MARGARET ST c. 1925. Bungalow, one story, hip roof, H plan, three bay facade, stucco, attached shed roof porch with square stucco pillars at entrance between hip roofed bays, tripled 3/1 windows, exposed rafters, pipe vents. 13 1041 C
- 870 133 MARGARET ST c. 1945. Minimal Traditional, one story, gable roof sides, brick, attached offcenter gable porch with paired square posts, ornamental iron railing, x-pattern drop freize and screened, ornamental iron panels in lower sash of 6/6 iwndows, box cornice, frame gable. 12 1041 C
- 871 134 MARGARET ST c. 1910. Queen Anne/Free Classic, one and a half story, hip roof, frame, six bay facade, two bay gable north end, 1/1 windows, pent, modified Palladian window in gable, wood door with window, transom, attached hip roof porch abutts gable and covers rest of facade, Tuscan columns, balustraded, hip roof dormer with paired windows, box cornice, interior chimney with corbeled cap. 7 1041 C
- 872 135 MARGARET ST c. 1925. Bungalow, one story, frame, three bay facade, attached offcenter gable porch, battered, boxed columns on brick plinths, multi-light door, paired 3/1 windows, knee braces, exposed rafters. 11 1041 C

United States Department of the Interior
National Park Service

National Register Of Historic Places
Continuation Sheet

Section Number 7 Page 105

MID TOWN HISTORIC DISTRICT
Mobile
Mobile County, AL

- 873 137 MARGARET ST c. 1930. Bungalow, one story, frame, four bay facade, side entrance, Craftsman door, attached offcenter hip roof porch with square posts, 6/6 windows with shutters, box cornice. 10 1041 C
- 874 139 MARGARET ST c. 1970. Ranch Style, one story, gable roof sides, brick, most of house obscured by vegetation. 9 1041 N
- 875 142 MARGARET ST c. 1980. Minimal Traditional, two story, gable roof sides, brick, side entrance, attached one story gable porch with square posts over stoop, 8/8 windows with shutters not fitted to close. 8 1041 N
- 876 1 MOHAWK ST c. 1945. Two story garage apartment, gable roof sides, frame, auto bay south end with attached one story lean-to with another auto bay, both feature double wooden doors, second story entrance with flight of wooden steps, wood door with diamond light, 3/1 windows with shutters flank, exposed rafters. 13 1028 C
- 877 2 MOHAWK ST c. 1915. Working Man's Foursquare, one and a half story, hip roof, frame, three bay facade, recessed porch originally covered facade, paneled box columns, now north and south bays infilled c. 1920 with casement windows, entrance now inset, four panel door with sidelights and transom, hip roof dormer with horizontal light, exposed rafters, interior chimney. 11 1028 C
- 878 3 MOHAWK ST c. 1915. Working Man's Foursquare, one and a half story, frame, three bay facade, inset porch covers two bays, square posts, wood door with window, sidelights and leaded glass transom single pane windows with leaded glass transoms, hip roof dormer with horizontal light, exposed rafters. 14 1028 C
- 879 5 MOHAWK ST c. 1925. Bungalow, one story, hip roof, frame, three bay facade, multi-light door, 6/1 windows, recessed porch covers facade, square columns with capitals, gable dormer with purlins, louvered vent, exposed rafters. 15 1028 C
- 880 6 MOHAWK ST c. 1990. One story, gable roof sides, frame, three bay facade, wood door, paired 6/6 windows with shutters, recessed porch covers facade, square posts. 12 1028 N
- 881 7 MOHAWK ST c. 1945. Minimal Traditional, one story, gable roof sides, three bay facade, attached gable porch south bay with tripled square posts on stuccoed kneewall, Gothic window in gable, pair multi-light doors, smaller attached gable over entrance stoop north adjacent, wall brackets, multi-light door, Gothic louvered vent, chimney north adjacent, 6/1 window north bay, exposed rafters. 16 1028 C

United States Department of the Interior
National Park Service

National Register Of Historic Places
Continuation Sheet

Section Number 7 Page 106

MID TOWN HISTORIC DISTRICT
Mobile
Mobile County, AL

- 882 8 MOHAWK ST c. 1940. Minimal Traditional, one story, cross gable, asbestos sided, three bay facade, centered entrance, six panel door, attached gable over stoop with square posts, paired 3/1 windows in gable north adjacent, picture window south adjacent, louvered vent, exposed rafters, end chimney. 10 1028 C
- 883 9 MOHAWK ST c. 1940. Bungalow, one story, gable roof front, frame, two bay facade, inset porch south bay, square post, balustraded and screened, paired 3/1 windows, metal awning wraps porch, exposed rafters. 17 1028 C
- 884 10 MOHAWK ST c. 1945. Minimal Traditional, one story, gable roof sides, frame, slightly set back gabled wing north end, three bay facade, centered entrance, six panel door, attached gable over stoop with ornamental iron supports, 6/6 windows with shutters, exposed rafters. 9 1028 C
- 885 11 MOHAWK ST c. 1945. Minimal Traditional, one story, gable roof sides, frame, three bay facade with gable wing attached north end, wood door with three lights, attached gable at stoop with Tuscan columns, paired 3/1 windows, wing is stuccoed and has paired aluminum windows, interior chimney, exposed rafters. 18 1028 C
- 886 12 MOHAWK ST c. 1940. Minimal Traditional, one story, gable roof sides, asbestos sided, four bay facade, duplex, attached gable over stoop, iron supports, pair multi-light front doors, large louvered vent in gable, paired 6/6 windows, box cornice, two story garage rear. 8 1028 C
- 887 13 MOHAWK ST c. 1935. Tudor Cottage, one story, cross gable, frame, four bay facade, inset porch south bay, square posts with curved brackets, entrance not visible, pair gables flank battered stucco chimney at facade, each dormer features frame half-timbering, 6/1 window, exposed rafters. 19 1028 C
- 888 14 MOHAWK ST c. 1950. Minimal Traditional, one story, cross gable, asbestos sided, three bay facade, wood door with small windows, attached gable over stoop with ornamental iron supports and plain iron railing, paired 6/6 windows with shutters. 7 1028 C
- 889 15 MOHAWK ST c. 1930. Minimal Traditional, one and a half story, gable roof sides, frame, recessed porch covers facade, square posts, fabric awning, 6/6 windows, gable dormer with paired 6/6 windows, fabric awning, attached two story porte-cochere south end, second story board and batten with 6/6 windows and fabric awnings, louvered vents, exposed rafters, interior chimney. 20 1028 C
- 890 16 MOHAWK ST c. 1980. One and a half story, gable roof front, brick, attached offcenter gable with two 6/6 windows, inset porch covers half of main facade, square posts with stick brackets, six panel door, shuttered window in vinyl gable, side chimney. 6 1028 N

United States Department of the Interior
National Park Service

National Register Of Historic Places
Continuation Sheet

Section Number 7 Page 107

MID TOWN HISTORIC DISTRICT
Mobile
Mobile County, AL

- 891 18 MOHAWK ST c. 1945. Minimal Traditional, one story, cross gable, ell plan, frame, three bay facade, central entrance with wood door, attached gable over porch with ornamental iron supports, windows obscured by shrubs, end chimney, box cornice. 5 1028 C
- 892 50 MOHAWK ST c. 1915. Working Man's Foursquare, one and a half story, hip roof, frame, three bay facade, wood door with window, sidelights and transom, 1/1 windows, recessed porch covers facade, square box columns, hip roof dormer with boarded windows, exposed rafters. 4 1028 C
- 893 51 MOHAWK ST c. 1940. Minimal Traditional, one story, cross gable, ell plan, frame, three bay facade, gabled entrance with round top opening, inset door, wood with glass, paired 6/1 windows, north adjacent, round top louvered vent in main gable, batten strips in gable over clapboarding, exposed rafters. 21 1028 C
- 894 52 MOHAWK ST c. 1930. Bungalow, one story, gable roof front, asbestos sided, four bay facade, pair attached gable porches north and south, square posts, balustraded and screened, six panel doors, 6/6 windows, triangular louvered vent, exposed rafters. 3 1028 C
- 895 53 MOHAWK ST c. 1925. Cottage Revival, one story, cross jerkin head gable roof, ell plan, stucco, three bay facade, centered gable with entrance, round top opening, six panel door inside, paired 6/6 windows north and south adjacent, chimney north adjacent entrance, louvered vent. 22 1028 C
- 896 54 MOHAWK ST c. 1945. Minimal Traditional, one story, gable roof front, asbestos sided, three bay facade, attached offcenter gable porch with square posts and balustraded, screened, six panel door, tripled 6/6 windows, triangular louvered vents in gables, exposed rafters. 2 1028 C
- 897 55 MOHAWK ST c. 1940. Bungalow/Early Ranch Style, one story, cross gable, brick, low slung, five bays, entrance in south end, gable with stoop, arched top door, paired 4/1 windows, gable bay north end, slight eyebrow in eave over middle bay, exposed rafters. 23 1028 C
- 898 56 MOHAWK ST c. 1925. Bungalow, one story, gable roof front, frame, three bay facade, attached slightly offcenter gable porch with square stucco pillars, six panel door, flanked by one set paired 3/1 windows and one set tripled 3/1 windows, purlins, louvered vent, exposed rafters, porte-cochere north side. 1 1028 C
- 899 57 MOHAWK ST c. 1925. Bungalow, one story, gable roof sides, frame, three bay facade, centered entrance, six panel door with gable on wall brackets over stoop, paired 3/1 windows north adjacent, inset porch south adjacent, screened with metal awning, exposed rafters. 24 1028 C

United States Department of the Interior
National Park Service

National Register Of Historic Places
Continuation Sheet

Section Number 7 Page 108

MID TOWN HISTORIC DISTRICT
Mobile
Mobile County, AL

- 900 58 MOHAWK ST c. 1925. Bungalow, one story, gable roof front, frame, three bay facade, attached shed roof porch covers facade, square brick pillars, gable over stoop with arched brick opening, portecochere north side, six panel door, 3/1 windows, exposed rafters, side chimney. 35 1027 C
- 901 59 MOHAWK ST c. 1945. Minimal Traditional, one story, gable roof sides, frame, three bay facade, centered entrance with six panel door, attached gable over stoop with slender turned posts, tripled 4/4 windows north adjacent, 6/6 window south bay, exposed rafters. 25 1028 C
- 902 61 MOHAWK ST c. 1945. Minimal Traditional, one story, cross gable, ell plan, frame, board and batten facade, clapboarded sides and rear, paired 8/8 windows in front gable, recessed porch south adjacent covers rest of facade, six panel door in south bay, interior chimney. 26 1028 C
- 903 62 MOHAWK ST c. 1940. Minimal Traditional, one story, cross gable, ell plan, stucco, recessed porch covers front gable, brick knee wall and open arch, attached brick entrance north adjacent with square brick pillars with caps, arched opening, paired 3/1 windows, louvered vent. 34 1037 C
- 904 100 MOHAWK ST c. 1945. Minimal Traditional, one story, gable roof sides, board and batten, five bay facade, six panel door with attached shed roof over stoop, square posts, 6/6 windows, shed roof addition north side. 33 1027 C
- 905 101 MOHAWK ST c. 1945. Minimal Traditional, one story, gable roof sides, frame, four bay facade, six panel entrance slightly inset with extended eave over stoop, 6/6 windows with shutters, scalloped fascia. 27 1028 C
- 906 103 MOHAWK ST c. 1945. Minimal Traditional, one story, gable roof sides, brick, three bay facade, centered entrance, six panel door, attached gable over stoop supported on slender Tuscan columns, iron cheek railings, entrance flanked by 8/8 windows with shutters and paneled section below sash, end chimney, box cornice. 28 1028 C
- 907 104 MOHAWK ST c. 1925. Bungalow, one and a half story, hip roof, frame, four bay facade, recessed porch covers three bays, box columns and balustraded, six panel door with transom, casement windows with transoms in north bay, hip roof dormer with two sets paired lights, box cornice. 32 1027 C
- 908 105 MOHAWK ST c. 1945. Minimal Traditional, one story, gable roof sides, frame, three bay facade, wood door with round light, wall gable above, double shouldered chimney north adjacent, end bays feature multi-light windows with shutters, exposed rafters. 29 1028 C

United States Department of the Interior
National Park Service

National Register Of Historic Places
Continuation Sheet

Section Number 7 Page 109

MID TOWN HISTORIC DISTRICT
Mobile
Mobile County, AL

- 909 107 MOHAWK ST c. 1925. Bungalow, one and a half story, hip roof, frame, three bay facade, recessed porch covers facade, battered, boxed columns on brick plinths, balustraded, slightly offcenter entrance, six panel door with side panels, lights only at top, 4/1 windows with shutters, hip dormer above with four light light, flanking louvered vents, two side chimneys, exposed rafters. 30 1028 C
- 910 108 MOHAWK ST c. 1970. One story, wide gable roof front, brick, attached gable porch covers center of facade, four elongated square columns, large front door, no windows in facade, box cornice. 31 1027 N
- 911 109 MOHAWK ST c. 1955. Minimal Traditional, one story, gable sides, asbestos sided, three bay facade, central entrance, six panel door, flanked by curved bay windows with multi-lights, gable wing attached north end with attached hip entrance bay north end. 31 1028 N
- 912 110 MOHAWK ST c. 1945. Minimal Traditional, one story, cross gable, ell plan, frame, four bay facade, offcenter entrance, six panel door, attached gable over stoop, ornamental iron supports, flanked by 6/6 windows, paired 6/6 windows with shutters in gable, box cornice, no return. 30 1027 C
- 913 111 MOHAWK ST c. 1980. Ranch Style, one story, low hip roof, brick, 6/6 aluminum windows with shutters, burglar screen over entrance, box cornice. 32 1028 N
- 914 112 MOHAWK ST c. 1945. Minimal Traditional, one story, gable roof sides, frame, three bay facade, centered entrance, six panel door, attached gable over stoop with battered brick supports, tripled 6/6 windows north adjacent, box cornice, no return. 29 1027 C
- 915 113 MOHAWK ST c. 1940. Minimal Traditional, one story, cross gable, frame, three bay facade, central entrance, six panel door with attached gable over stoop, inset porch north bay, screened and clapboarded knee wall, paired 3/1 windows south bay, triangular louvered vent, end chimney. 33 1028 C
- 916 114 MOHAWK ST c. 1925. Bungalow, one and a half story, brick, hip roof, three bay facade, inset porch with square brick pillar, multi-light front door, banks four 3/1 windows, jerkin head roof dormer with three sets Craftsman three light windows, box cornice. 28 1027 C
- 917 115 MOHAWK ST c. 1940. Minimal Traditional, one story, cross gable, ell plan, frame, three bay facade, front gable features sweeping roofline to north which encompasses round top entrance, double wood doors with glass, inset porch north bay now glassed in, awning strip, louvered vent, double shouldered brick chimney north adjacent entrance, 3/1 window north bay, exposed rafters. 34 1028 C

United States Department of the Interior
National Park Service

National Register Of Historic Places
Continuation Sheet

Section Number 7 Page 110

MID TOWN HISTORIC DISTRICT
Mobile
Mobile County, AL

- 918 116 MOHAWK ST c. 1945. Minimal Traditional, one story, gable roof sides, frame, three bay facade, attached gable over stoop with square posts, door obscured by screen, windows by vegetation. 27 1027 C
- 919 117 MOHAWK ST c. 1940. Cottage Revival, one story, cross gable, ell plan, frame, cross gable in north bay, round top entrance with diamond lights, round top louvered vent in gable, single shoulder brick chimney with round top niche south adjacent, tripled Tudor window, inset porch south bay with brick pillars, infilled with metal casement windows and metal awning. 35 1028 C
- 920 118 MOHAWK ST c. 1925/1980. Bungalow, one and a half story, hip roof, vinyl sided, recessed porch which covered facade has been infilled with vinyl sided and aluminum windows, drastically altering the original integrity, hip roof dormer. 26 1027 N
- 921 119 MOHAWK ST c. 1945. Minimal Traditional, one story, cross gable, ell plan, frame, four bay facade, two bay gable front with double shouldered brick chimney flanked by 6/6 windows, recessed porch down north side, turned posts and balustraded, six panel door, louvered vent in front gable. 1 1029 C
- 922 120 MOHAWK ST c. 1940. Minimal Traditional, one story, cross gable, ell plan, frame, three bay facade, wood door with lights, lunette transom, attached gable over stoop with Tuscan columns, arched opening, banks 6/1 windows north and south adjacent, louvered vent in dominant gable, exposed rafters. 25 1027 C
- 923 121 MOHAWK ST c. 1945. Minimal Traditional, one and a half story, gable sides, frame, five bay facade, attached flat roof porch covers facade, ornamental iron supports and railing on roof, six panel door, 6/6 windows, three dormers with 6/6 windows, end chimney. 2 1029 C
- 924 122 MOHAWK ST c. 1975. Ranch Style, one story, gable roof sides, brick with frame gables, aluminum windows with shutters, box cornice. 24 1027 N
- 925 123 MOHAWK ST c. 1925. Bungalow, one and a half story, gable sides, frame, three bay facade, recessed porch covers facade, box columns with capitals, balustraded, wood door with window, sidelights, flanking windows with transoms, shed roof dormer with multi-light windows, exposed rafters. 3 1029 C
- 926 150 MOHAWK ST c. 1945. Minimal Traditional, one and a half story, gable roof sides, frame, three bay facade, six panel door, attached gable over stoop with square posts, multi-light windows, end chimney, box cornice, no return. 23 1027 C

110
1027 C

United States Department of the Interior
National Park Service

National Register Of Historic Places
Continuation Sheet

Section Number 7 Page 111

MID TOWN HISTORIC DISTRICT
Mobile
Mobile County, AL

- 927 151 MOHAWK ST c. 1925. Bungalow, one and a half story, gable roof sides, frame, recessed porch covers facade, grouped battered posts on brick plinths, three french doors in facade, gable dormer above with three single pane lights, exposed rafters. 4 1029 C
- 928 152 MOHAWK ST c. 1945. Minimal Traditional, one story, gable roof sides, frame, four bay facade, six panel door, attached gable over stoop with square posts, 8/8 windows with shutters, box cornice. 22 1027 C
- 929 153 MOHAWK ST c. 1930. Bungalow, one story, gable roof sides, frame, three bay facade, centered entrance, multi-light door with attached gable over stoop on Tuscan columns, flanking French doors, pair steeply pitched gable dormers with louvered vents, exposed rafters. 5 1029 C
- 930 154 MOHAWK ST c. 1945. Minimal Traditional, one story, cross gable, ell plan, frame, recessed porch abutts front gable, square brick pillar and knee wall, fabric awning strip, pair 8/8 windows with shutters in gable, box cornice. 21 1027 C
- 931 155 MOHAWK ST c. 1930. Cottage Revival, one story, cross gable, ell plan, shingled, front gable features double shouldered stucco chimney with rusticated accents up center, flanked by small round top casement windows, roof line sweeps south covering an inset porch that is now filled in with frame and tinted glass. 6 1029 C
- 932 156 MOHAWK ST c. 1925. Bungalow, one story, gable roof sides, frame, three bay facade,, recessed porch covers facade, square brick pillars, wood door with window, sidelights, flanked by paired Craftsman windows, gable dormer with lattice vents, exposed rafters. 20 1027 C
- 933 157 MOHAWK ST c. 1940. Minimal Traditional, one story, cross gable, frame, three bay facade, inset porch covers two bays, chamfered posts, awning hangs down between posts, set 3/3 windows in south bay, six panel door, louvered vent, end chimney, exposed rafters. 7 1029 C
- 934 158 MOHAWK ST c. 1920. Bungalow, one story, hip roof, frame, two bay facade, recessed porch covers facade, paired slightly battered posts on clapboarded plinths, six panel door with transom, main window one pane of glass with transom and sidelights, exposed rafters. 19 1027 C
- 935 159 MOHAWK ST c. 1945. Two story garage apartment, gable roof sides, asbestos sided, first story features two auto bays at each end bay with pair casement windows between, second storry features two 8/8 windows and a band of four casement windows in south bay, entrance to sides or rear. 8 1029 C

United States Department of the Interior
National Park Service

National Register Of Historic Places
Continuation Sheet

Section Number 7 Page 112

MID TOWN HISTORIC DISTRICT
Mobile
Mobile County, AL

- 936 160 MOHAWK ST c. 1950. Minimal Traditional, two story, cross gable, ell plan, brick, three bay facade, centered entrance in attached gable with round top entrance, six panel door, garage in first story of front gable, wood door with set four square windows, metal casement windows above with shutters, triangular louvered vent, box cornice, no return. 18 1027 C
- 937 161 MOHAWK ST c. 1930. Cottage Revival, one story, cross gable, ell plan, brick, inset porch in front gable, arched openings north and south sides, screened, metal awning across front, 6/1 windows, door not visible, louvered vent, one side chimney, one interior chimney, box cornice. 9 1029 C
- 938 162 MOHAWK ST c. 1945. Minimal Traditional, one story, cross gable, ell plan, frame, four bay facade, recessed, screened porch covers three bays, tripled 3/1 windows with shutters in front gable, end chimney, box cornice, no return. 17 1027 C
- 939 163 MOHAWK ST c. 1925. Bungalow, one story, gable on hip roof front, stucco, three bay facade, recessed gable porch covers facade, battered stucco pillars and balustrade, six panel door flanked by paired 1/1 windows, louvered vent, knee braces, port-cochere north side, exposed rafters. 10 1029 C
- 940 164 MOHAWK ST c. 1950. One story, cross gable, asbestos sided, six panel front door. 16 1027 C
- 941 165 MOHAWK ST c. 1980. Ranch Style, one story, gable roof sides, brick, three bay facade, kick off shed roof porch covers two bays, ornamental iron supports, wood door, paired 6/6 aluminum windows north adjacent, single 6/6 window south adjacent, box cornice. 11 1029 N
- 942 166 MOHAWK ST c. 1945. Minimal Traditional, one story, jerkin head gable sides, asbestos sided, three bay facade, wood door with window and flanking paired 1/1 windows, louvered vents in gables. 15 1027 C
- 943 167 MOHAWK ST c. 1925. Vernacular, two story, gable on hip front, vinyl sided, three bay facade, main body of house is gable on hip with an attached offcenter hip roof block and an attached offcenter two story gable porch with paired square columns, balustraded and screened, six panel front door south adjacent attached porch, French doors in second floor of porch, other windows mixed 6/6 and casement, louvered vent, box cornice closed return. 12 1029 C
- 944 168 MOHAWK ST c. 1945. Minimal Traditional, one story, cross gable, ell plan, asbestos sided, three bay facade, centered six panel entrance door with bay window in front gable, 6/6 windows. 14 1027 C

168 3
1

United States Department of the Interior
National Park Service

National Register Of Historic Places
Continuation Sheet

Section Number 7 Page 113

MID TOWN HISTORIC DISTRICT
Mobile
Mobile County, AL

- 945 169 MOHAWK ST c. 1945. Minimal Traditional, one story, gable roof sides, asbestos sided, three bay facade, inset porch covers two bays, six panel door, paired 6/6 windows, porch has balustrade and is screened, gable centered above stoop with planter box and louvered vent, exposed rafters. 13 1029 C
- 946 170 MOHAWK ST c. 1925. Bungalow, one story, jerkin head gable front, frame, attached one story flat roof porch covers facade, box battered columns on high brick plinths, porch eave features series of exposed brackets, side chimney, exposed rafters. 13 1027 C
- 947 171 MOHAWK ST c. 1940. Minimal Traditional, one story, asbestos sided, gable roof front, duplex, four bay facade, two front doors, each six panel, attached shed roof porch over stoop with square posts, 8/8 windows, louvered vent, exposed rafters. 14 1029 C
- 948 200 MOHAWK ST c. 1925. Bungalow, one story, gable roof front, frame, three bay facade, attached, offcenter gable roof porch, square brick pillars, Craftsman door flanked by paired 3/1 windows, knee braces, exposed rafters. 12 1027 C
- 949 201 MOHAWK ST c. 1945. Minimal Traditional, one story, cross gable, asbestos sided, three bay facade, entrance north adjacent front gable, six panel door with fabric awning, bay window in gable with three 6/6 windows, round louvered vent, paired 6/6 windows south adjacent, box cornice, closed return. 15 1029 C
- 950 203 MOHAWK ST c. 1945. Minimal Traditional, two and a half story, gable roof sides, first story stucco, second asbestos sided, three bay facade, six panel front door center facade, attached one story gable over stoop with square posts, flanked by paired 6/6 windows, paired 6/6 windows in second story, gable dormer center above with paired 6/6 windows, exterior stairway to upper story around south end, two story gable roof sides garage apartments rear, inverted board and batten, paired 6/6 windows. 16 1029 C
- 951 204 MOHAWK ST c. 1945. Minimal Traditional, one and a half story, gable roof sides, frame, three bay facade, recessed porch covers facade, house abandoned and in disrepair, ornamental iron railing still in place, gable dormers with four light windows, slate roof. 11 1027 C
- 952 205 MOHAWK ST c. 1950. Minimal Traditional, one story, cross gable, ell plan, asbestos sided, three bay facade, inset porch north side front gable, ornamental iron support on corner, six panel door, paired 6/6 windows, exposed rafters. 18 1029 C
- 953 206 MOHAWK ST c. 1925. Bungalow, jerkin head gable front, vinyl sided, three bay facade, attached jerkin head gable porch covers most of facade, ornamental iron supports and railing, six panel door flanked by paired 3/1 windows, box cornice no return. 10 1027 C

United States Department of the Interior
National Park Service

National Register Of Historic Places
Continuation Sheet

Section Number 7 Page 114

MID TOWN HISTORIC DISTRICT
Mobile
Mobile County, AL

- 954 207 MOHAWK ST c. 1925. Bungalow, one story, gable roof sides, aluminum siding, attached gable porch centered, paneled battered box columns on stucco knee wall, six panel door, 6/6 aluminum windows. 19 1029 C
- 955 208 MOHAWK ST c. 1925. Bungalow, one story, gable roof front, asbestos sided, recessed porch covers facade, box slightly battered columns, Craftsman door, 3/1 windows, Craftsman window in gable, exposed rafters. 9 1027 C
- 956 209 MOHAWK ST c. 1945. Minimal Traditional, one story, gable sides, asbestos sided, three bay facade, centered front door, six panel, attached gable over stoop with ornamental iron supports, multi-light windows with fabric awnings, box cornice. 20 1029 C
- 957 210 MOHAWK ST c. 1945. Minimal Traditional, one and a half story, gable roof sides, frame, four bay facade, offcenter entrance in gable, six panel door, awning over stoop, 1/1 windows, two gable dormers with 6/6 windows, louvered vent, box cornice. 8 1027 C
- 958 211 MOHAWK ST c. 1950. Minimal Traditional, one story, gable roof sides, asbestos sided, three bay facade, inset porch south bay with square posts and balustraded, six panel door, center bay a picture window with flanking multi-light casement, north bay 8/8 window, fabric awnings, wall gable over north bay, triangular louvered vent, box cornice. 21 1029 C
- 959 253 MOHAWK ST c. 1925. Bungalow, one story, jerkin head gable front, frame, three bay facade, inset porch south two bays,, battered, boxed columns on brick plinths, 3/1 windows, metal awnings around porch and over windows, six panel door, knee braces, small light and flanking triangular louvers in gable, exposed rafters. 22 1029 C
- 960 255 MOHAWK ST c. 1930. Bungalow, one story, gable roof sides, vinyl sided, three bay facade, inset porch south bay, Tuscan column, metal awning wraps around porch and covers paired Craftsman windows center of facade, single shoulder brick chimney with contrasting color brick with Craftsman window north adjacent, jerkin head gable in roof line. 23 1029 C
- 961 256 MOHAWK ST c. 1930. Bungalow, one story, gable roof front, frame, recessed porch covers facade, paired square posts on brick plinths, six panel door flanked by paired 3/1 windows, exposed rafters. 7 1027 C
- 962 257 MOHAWK ST c. 1925. Bungalow, one story, gable roof front, three bay facade, vinyl sided, attached offcenter gable porch covers two bays,, battered, boxed columns on brick plinths, wood door, paired 3/1 windows, louvered vents, side chimney, cornice inclosed by vinyl. 24 1029 C

United States Department of the Interior
National Park Service

National Register Of Historic Places
Continuation Sheet

Section Number 7 Page 115

MID TOWN HISTORIC DISTRICT
Mobile
Mobile County, AL

- 963 259 MOHAWK ST c. 1950. Minimal Traditional, one story, cross gable, asbestos sided, four bay facade, door north adjacent front gable, burglar door, metal awnings over door and windows, 8/8 window north adjacent and in gable, bank casement windows in north bay, interior chimney. 25 1029 C
- 964 260 MOHAWK ST c. 1925. Bungalow, one story, gable roof front, vinyl sided, three bay facade, attached offcenter gable porch with ornamental iron supports on brick plinths, paired 6/1 windows, knee braces, round louvered vent, box cornice. 6 1027 C
- 965 261 MOHAWK ST c. 1950. Minimal Traditional, one story, gable roof sides, brick, four bay facade, six panel door, eave extends over stoop, ornamental iron support at corner, 3/1 window north adjacent, paired 3/1 windows south adjacent, triangular vents in gable. 26 1029 C
- 966 262 MOHAWK ST c. 1930. Bungalow, one story, gable roof front, vinyl sided, attached offcenter porch with square posts on brick plinths, wood door with window, paired 1/1 windows. 5 1027 C
- 967 263 MOHAWK ST c. 1945. Minimal Traditional, one story, gable roof sides, vinyl sided, four bay facade, offcenter entrance, wood door with multi-lights, attached gable over stoop on wall brackets, flanking paired windows with metal awnings, inset porch south bay, screened and balustraded, metal awning. 27 1029 C
- 968 264 MOHAWK ST c. 1955. One story, gable on hip front, stucco, inset porch covers half facade, ornamental iron supports and railing, multi-light window north adjacent. 4 1027 N
- 969 265 MOHAWK ST c. 1945. Minimal Traditional, one story, gable roof sides, vinyl sided, three bay facade, attached offcenter gable porch, square brick pillars and metal awning at facade, six panel door, 6/1 windows, side chimney. 28 1029 C
- 970 266 MOHAWK ST c. 1945. Minimal Traditional, one story, cross gable, vinyl sided, four bay facade, six panel door with attached gable over porch with ornamental iron supports and frieze, 6/6 windows, chimney at facade, louvered vent, box cornice. 3 1027 C
- 971 268 MOHAWK ST c. 1945. Minimal Traditional, one story, gable roof sides, frame, five bay facade, offcenter entrance with gable on wall brackets over stoop, metal awning over door, 1/1 windows with shutters, end chimney, louvered vents, box cornice. 2 1027 C

United States Department of the Interior
National Park Service

National Register Of Historic Places
Continuation Sheet

Section Number 7 Page 116

MID TOWN HISTORIC DISTRICT
Mobile
Mobile County, AL

- 972 1814 MURRAY ST c. 1925. Bungalow, one and a half story, gable roof sides, frame, three bay facade, recessed porch covers two bays, square brick pillar on brick plinth, Craftsman door, paired 1/1 windows south adjacent, bank 1/1 windows in south bay, shed roof dormer with Craftsman light and flanking louvers, exposed rafters. 14 1006 C
- 973 1816 MURRAY ST c. 1925. Bungalow, one story, gable roof front, frame, three bay facade, attached offcenter gable porch with square brick pillars, Craftsman door, paired 4/1 windows flank entrance, exposed purlins, louvered vent in main gable, horizontal light in porch gable, exposed rafters. 15 1006 C
- 974 1900 MYRTLE AVE c. 1930. Bungalow, one story, gable roof sides, frame, three bay facade, wood door with window, attached gable porch with paired square columns, 3/1 windows with shutters flank porch, knee braces, box cornice, closed return. 23 1000 C
- 975 1902 MYRTLE AVE c. 1925. Bungalow, one story, gable roof sides, frame, three bay facade, centered entrance with gable, six panel door with round top filled transom, flanking round top niches, casement windows with transoms in south bay, original inset porch in north bay with square brick pillar infilled with glass, knee braces, exposed rafters, end chimney. 24 1000 C
- 976 1903 MYRTLE AVE c. 1940. Minimal Traditional, one story, gable on hip roof front, frame, three bay facade, six panel entrance with attached gable over stoop on wall brackets, paired 3/1 windows flank entrance with shutters, inset screened porch north end, lunette louvered vent in gable. 17 1001 C
- 977 1904 MYRTLE AVE c. 1925. Bungalow, two story, hip roof, frame, three bay facade, attached one story shed roof porch covers facade, square brick pillars at corners, paired wooden columns on brick plinths with capitals adjacent steps, paired 6/6 windows flank multi-light door, exposed rafters, interior chimney. 25 1000 C
- 978 1905 MYRTLE AVE c. 1925. Bungalow, gable roof front, frame, two bay facade, attached, offcenter gable roof porch, paneled boxed columns, screened, Craftsman door, paired 6/6 windows with shutters, board and batten treatment in gable, triangular louvered vent, exposed rafters. 16 1001 C
- 979 1906 MYRTLE AVE c. 1930. Bungalow, one story, gable roof front, brick, three bay facade, offcenter entrance, six panel door with screen, casement windows with shutters flank entrance, attached one story gable over stoop with ornamental iron supports, knee braces, louvered vent in main gable, exposed rafters. 26 1000 C
- 980 1907 MYRTLE AVE c. 1930. Bungalow, one story, gable roof sides, frame, three bay facade, attached flat roof porch, box columns on brick knee wall, screened, wood door with window, flanked by doubled French doors, knee braces, end chimney, exposed rafters. 15 1001 C

United States Department of the Interior
National Park Service

National Register Of Historic Places
Continuation Sheet

Section Number 7 Page 117

MID TOWN HISTORIC DISTRICT
Mobile
Mobile County, AL

- 981 1908 MYRTLE AVE c. 1945. Minimal Traditional, one story, gable roof sides, vinyl sided, four bay facade, inset porch with gable above, square posts and screened, six panel door, 6/6 windows with ornamental iron panels below sash, triangular louvered vent in gable, exposed rafters, large interior chimney. 27 1000 C
- 982 1910 MYRTLE AVE c. 1940. Minimal Traditional, two story, cross gable roof, asbestos sided, duplex, entrance in north bay multi-light door in gable surround, entrance in south bay inset porch, screened, with ornamental iron railing, tripled 6/6 windows first and second story between entrances, small gable dormer with louvered panel, exposed rafters. 28 1000 C
- 983 1911 MYRTLE AVE c. 1945. Minimal Traditional, one and a half story, gable roof sides, frame, three bay facade, inset porch north bay, attached gable with square brick pillars, bubble awning, six panel door, chimney at facade flanked by 12/12 windows with shutters, flat roof carport north side attached, exposed rafters. 14 1001 C
- 984 1912 MYRTLE AVE c. 1980. Ranch Style, one story, brick, hip roof, inset entrance with wood door with lunette window, flanking sidelights south side entrance, square post corner porch, bank aluminum windows, box cornice. 29 1000 N
- 985 1914 MYRTLE AVE c. 1925. Bungalow, one story, cross jerkin head gable roof, frame, three bay facade, offcenter entrance in cross gable, six panel door with sidelights and fan transom, attached gable over stoop with Tuscan columns and arched opening in gable, bank 1/1 windows with transom south adjacent, original inset porch in north bay has been infilled and bumped out one bay to north, large glass panels and flat roof over bump out, end chimney, exposed rafters. 30 1000 C
- 986 1915 MYRTLE AVE c. 1945. Minimal Traditional, one and a half story, gable roof sides, frame, three bay facade with attached one story gable wing north, six panel door with sidelights and fan transom, attached gable over stoop with tripled square posts with capitals, casement windows with shutters, chimney south side, exposed rafters. 13 1001 C
- 987 1916 MYRTLE AVE c. 1930. Bungalow, one story, jerkin head gable roof sides, frame, three bay facade, offcenter entrance, six panel door, flanking 6/6 windows, paired 1/1 windows in north bay, attached shed roof porch covers two bays, tripled square posts with capitals, louvered vent, exterior end chimney. 31 1000 C
- 988 1917 MYRTLE AVE c. 1945. Minimal Traditional, two story, gable roof sides, asbestos upper story, brick first story, three bay facade, side entrance, six panel door, attached one story porch with square brick pillars, 8/8 windows, box cornice, closed return, louvered vents in gables. 12 1001 C
- 989 1918 MYRTLE AVE c. 1925. Bungalow, one story, cross jerkin head gable roof, five bay facade, centered entrance, six panel door, attached gable over stoop with square posts with capitals, 6/6 windows, chimney each end, exposed rafters. 23 1000 C

United States Department of the Interior
National Park Service

National Register Of Historic Places
Continuation Sheet

Section Number 7 Page 118

MID TOWN HISTORIC DISTRICT
Mobile
Mobile County, AL

- 990 1920 MYRTLE AVE c. 1945. Cape Cod Cottage Revival, one and a half story, frame, three bay facade, centered entrance, six panel door, 6/6 windows, three gable dormers with 6/6 sash, triangular louvered vent in gables, no eaves. 33 1000 C
- 991 1950 MYRTLE AVE c. 1925. Bungalow, one story, hip roof, frame, three bay facade, attached gable porch covers most of facade, paired columns on brick knee wall, now all infilled with clapboards and glass, six panel door with sidelights, 3/1 windows, Palladian light and louvers in gable, box cornice, closed return. 34 1000 C
- 992 1951 MYRTLE AVE c. 1925. Bungalow, one story, hip roof, frame, recessed porch covers facade, tripled columns with capitals on stucco knee wall, tinted glass infill obscures windows and door, gable over steps, paired knee braces, louvered vent, exposed rafters. 11 1001 C
- 993 1952 MYRTLE AVE c. 1925. Bungalow, one story, jerkin head gable roof sides, three bay facade, attached jerkin head gable porch center of facade, pierced brick columns with arched opening, screened, inset porch south bay, screened with ornamental iron railing, porte-cochere off south end, bank casement windows north bay with square brick pillar at corner, end chimney, exposed rafters. 35 1000 C
- 994 1953 MYRTLE AVE c. 1940. Minimal Traditional, one story, gable roof sides, asbestos sided, three bay facade, bay window with three 6/6 windows, attached gable porch north adjacent with square brick pillars, six panel door, paired 6/6 windows north adjacent, louvered vent in gable, box cornice, closed return. 10 1001 C
- 995 1954 MYRTLE AVE c. 1940. Creole Cottage, one and a half story, gable roof sides, asbestos sided, recessed porch covers facade, box columns and screened, multi-light door, 9/9 windows, pair gable dormers with 6/6 windows, box cornice, no return. 1 1001 C
- 996 1955 MYRTLE AVE c. 1940. Minimal Traditional, one story, gable roof sides, frame, three bay facade, centered entrance, six panel door, attached gable over stoop with brick columns leading to round top opening, paired 3/1 windows flank entrance with shutters, end chimney, box cornice. 9 1001 C
- 997 1956 MYRTLE AVE c. 1960. One story, hip roof, brick, four bay facade, wood door, attached shed roof over stoop with delicate ornamental iron supports, horizontal 2/2 windows with shutters, box cornice. 2 1001 N
- 998 1957 MYRTLE AVE c. 1940. Minimal Traditional, one story, jerkin head gable sides, frame, three bay facade with attached one story hip roof sun room attached south side, wood door with lights, attached gable porch over stoop, square columns with capitals and rounded opening in gable, casement windows flank entrance, interior chimney, exposed rafters. 8 1001 C

United States Department of the Interior
National Park Service

National Register Of Historic Places
Continuation Sheet

Section Number 7 Page 119

MID TOWN HISTORIC DISTRICT
Mobile
Mobile County, AL

- 999 1958 MYRTLE AVE c. 1925. Bungalow, one story, gable roof sides, brick, original facade much altered, attached offcenter gable porch has been infilled with brick and aluminum multi-light windows with shutters, entrance north adjacent was originally a recessed porch, now infilled with brick and a six panel door, knee braces and half-timbering in gable, louvered vent, exposed rafters, carport south side, interior chimney. 3 1001 N
- 1000 1959 MYRTLE AVE c. 1930. Bungalow, one story, gable roof sides, frame, two bay facade, attached offcenter gable porch with pierced brick pillars, six panel door with sidelights, casement windows in north bay, attached porte-cochere south side porch, knee braces, louvered vent, purlins, end chimney, exposed rafters. 7 1001 C
- 1001 1960 MYRTLE AVE c. 1965. Ranch Style, one story, gable roof sides, brick, four bay facade, door obscured by burglar door, metal casement windows, north bay with ornamental iron accenting sides and bottom, interior chimney, carport north side, set back somewhat. 4 1001 N
- 1002 1961 MYRTLE AVE c. 1930. Bungalow, one story, cross gable, ell plan, perma-stone, four bay facade, attached shed roof porch covers three bays, box columns on perma-stone plinths, balustraded, Craftsman door and windows, horizontal light in front gable, knee braces, two interior chimneys, exposed rafters. 6 1001 C
- 1003 1964 MYRTLE AVE c. 1965. One story, gable off hip, brick, two bay facade, side entrance, six panel door with flanking metal casement windows, picture window north bay with casement sidelight, box cornice. 5 1001 N
- 1004 1800 OLD GOVERNMENT ST 1918. Memorial Park, World War I Memorial, George Rogers, architect, landscaped wedge of property bounded by Old Government Street to the north and Government Street to the south, graveled paths approach and circle a pool and fountain, a colonnade stands at the western end of the park, consists of four columns between wide end sections, which feature bronze memorial plaques, full entablature, flag pole in front. 1 1000 C
- 1005 1806 OLD GOVERNMENT ST 1926. Mission Revival, George Rogers, architect, NR 1991, two story, hip ceramic tile roof with centered Mission parapet, stucco, inset entrance an arched opening, wood door, casement windows first and second stories, cantilevered wrought iron balcony over entrance, three arch topped casement windows, eave brackets, two interior chimneys, one story porches attached east and west elevations, glass infill, interior retains fixtures, bath and toilet, Mission Style garage rear of property. 2 1000 C
- 1006 1810 OLD GOVERNMENT ST 1907. Colonial Revival, two story, hip roof, frame, four bay facade, attached one story flat roof porch covers three bays, paired Tuscan columns, roof balustraded, wood door with window, sidelights and transom, full height slide-by windows under porch, bay window first floor west bay, tripled sash, other windows 6/6, box cornice. 3 1000 C
- 1007 1820 OLD GOVERNMENT ST 1928. Spanish Revival Style, Azalea Court Apartments, J. Platt Roberts, architect, NR 1988, three story, U plan, brick with stone quoins, building wraps around an iron fenced courtyard, Mission parapet center of hyphen, and each wing, facing courtyard, round top windows, paired 6/1 windows with stucco round tops, estucheons at facades of two wings between

United States Department of the Interior
National Park Service

National Register Of Historic Places
Continuation Sheet

Section Number 7 Page 120

MID TOWN HISTORIC DISTRICT
Mobile
Mobile County, AL

- 1007 second and third stories, belt course, ceramic tile roof. 4 1000 C
- 1008 1852 OLD GOVERNMENT ST c. 1945. Minimal Traditional, two story, gable roof sides, asbestos sided, apartment building, five bay facade, central entrance, six panel door with attached one story shed roof over stoop, square posts, flanked by paired 8/8 windows first and second story, each end bay features two story attached/recessed hip roof porches, square posts and balustraded, box cornice. 18 1001 C
- 1009 1854 OLD GOVERNMENT ST c. 1945. Minimal Traditional, two story, gable roof sides, asbestos sided, five bay facade, apartment building, central entrance, six panel door with attached one story shed roof over stoop, square posts, paired 8/8 windows flank entrance first and second stories, each end by features two story hip roof gallery, square posts and balustraded first and second stories, box cornice. 19 1001 C
- 1010 1856 OLD GOVERNMENT ST c. 1920. Bungalow, one and a half story, gable roof front, frame, two bay facade, inset porch covers half of facade, square brick pillar, six panel door with Craftsman sidelights and transom, grouped Craftsman windows west bay, paired set in gable above, knee braces, exposed rafters. 20 1001 C
- 1011 1858 OLD GOVERNMENT ST c. 1900. Colonial Revival, two story, hip roof, five bay facade, vinyl sided, attached one story hip roof porch covers three bays, Tuscan columns, double wood doors with windows, transom, 2/2 windows, six windows second story, middle two a hip roof bay, hip roof dormer above with no window or vent, box cornice. 21 1001 C
- 1012 1860 OLD GOVERNMENT ST c. 1925. Cottage Revival, two story, cross gable, stucco, three bay facade, two story gable bay center of facade, multi-light door with sidelights, engaged open pilasters flank entrance and are one story in height, 6/6 window above, paired 6/6 windows, no cornice. 22 1001 C
- 1013 1864 OLD GOVERNMENT ST c. 1900. Colonial Revival, one and a half story, hip roof, frame, three bay facade, recessed porch covers facade and wraps partially around east elevation, Tuscan columns on stucco plinths, balustraded, wood door with window, sidelights and transom, 1/1 windows, exposed rafters, hip roof dormer with 6/6 window with flanking narrow 1/1 lights, exposed rafters, interior chimney and exterior chimney. 23 1001 C
- 1014 1865 OLD GOVERNMENT ST c. 1930. Tudor Revival, one and a half story, gable roof sides, brick, four bay facade, attached offcenter gable porch covers three bays, pierced brick columns, half timbered gable with casement windows with window planter box, wood door with window center of facade, pair French doors east adjacent, paired 6/1 windows west adjacent, shed roof porte-cochere east side. 33 1003 C
- 1015 1866 OLD GOVERNMENT ST c. 1945. Minimal Traditional, one story, gable roof front, frame, three bay facade, attached offcenter porch with ornamental iron supports and railing, multi-light door, paired 6/6 windows east adjacent, one 6/6 window in west bay, box cornice, triangular louvered vents in gables. 24 1001 C

United States Department of the Interior
National Park Service

National Register Of Historic Places
Continuation Sheet

Section Number 7 Page 121

MID TOWN HISTORIC DISTRICT
Mobile
Mobile County, AL

- 1016 1867 OLD GOVERNMENT ST c. 1910. American Foursquare, two story, hip roof, two bay facade, frame, recessed two story porch covers facade and wraps around east elevation, box columns with capitals first story and second, west bay second story infilled with four 4/1 windows, balustraded at second floor, screened, dentil course first and second stories, two front doors, 1/1 windows. 32 1003 C
- 1017 1868 OLD GOVERNMENT ST c. 1905. American Foursquare, two story, hip roof, frame, three bay facade, attached one story porch covers facade, entrance inset, wood door with window, transom, Tuscan columns, balustraded, second story porch inset in one bay over entrance, Tuscan column and balustraded, 2/2 windows, exposed rafters, interior chimney. 25 1001 C
- 1018 1869 OLD GOVERNMENT ST c. 1925. Bungalow, one story, gable roof front, frame, three bay facade, recessed porch covers facade, tripled box columns with capitals at corners, paired center, all on stucco plinths, six panel door, paired 6/1 windows, exposed timbers in square pattern in stucco gable, louvered vent, knee braces, exposed rafters, side chimney, gable bays east and west elevations. 31 1003 C
- 1019 1900 OLD GOVERNMENT ST c. 1900. Colonial Revival, two story, hip roof, frame, five bay facade, recessed two story porch covers facade, tripled Tuscan columns each corner, paired beside steps, second level balustraded, double wood doors with windows, transom, 1/1 windows, box cornice, later widow's walk on roof, interior chimney. 26 1001 C
- 1020 1901 OLD GOVERNMENT ST c. 1930. Cottage Revival, one story, cross gable, brick, four bay facade, centered entrance in gable, round top wooden door, round top arch in gabled entrance, staggered larger gable east behind entrance, both gables half timbered, chimney west adjacent flanked by 3/1 windows, inset porch east end, arched opening covered with plastic, box cornice. 30 1003 C
- 1021 1902 OLD GOVERNMENT ST c. 1900. Victorian, two story, hip roof, five bay facade, inset two story porch covers three bays, ornamental iron supports and railing at second story, turned posts and balustraded at first story, wood door with window, sidelights and transom, 1/1 windows except first floor west bay, which is a later 12/12 sash, box cornice. 27 1001 C
- 1022 1903 OLD GOVERNMENT ST c. 1945. Minimal Traditional, one story, gable roof sides, frame, three bay facade with inset porch at east end, slender square posts and screened, six panel door, attached flat roof porch over stoop, square posts, 8/8 windows flank entrance, interior chimney. 29 1003 C
- 1023 1904 OLD GOVERNMENT ST c. 1930. Bungalow, one story, gable roof front, frame, three bay facade, jalousied windows and door, attached gable over stoop, ornamental iron supports, knee braces, exposed rafters. 28 1001 C
- 1024 1905 OLD GOVERNMENT ST c. 1910. Colonial Revival, two story, hip roof, frame, house in ell plan with one bay wing east front, side entrance, four panel door with sidelights and transom, attached hip roof porch covers facade and wraps around wing, large 1/1 windows, box cornice. 28 1003 C

United States Department of the Interior
National Park Service

National Register Of Historic Places
Continuation Sheet

Section Number 7 Page 122

MID TOWN HISTORIC DISTRICT
Mobile
Mobile County, AL

- 1025 1906 OLD GOVERNMENT ST c. 1900. Victorian, two story, hip roof, frame, four bay facade, inset two story porch covers two bays, turned posts, balustraded, four panel front door, sidelights and transom, 1/1 windows with shutters, box cornice, side chimney. 29 1001 C
- 1026 1907 OLD GOVERNMENT ST c. 1910. American Foursquare, two story, hip roof, two bay facade, frame, recessed two story porch covers facade, Tuscan columns first and second story, second story balustraded, side hall plan, wood door with sidelights and transom, tripled 1/1 windows with shutters first story, paired 1/1 windows with shutters second story west bay, French doors east bay, box cornice, side chimney. 27 1003 C
- 1027 1908 OLD GOVERNMENT ST c. 1930. Cottage Revival, one story, cross gable, ell plan, stucco, three bay facade, entrance in gable, round top door with diamond lights, cast concrete frames round top inset opening, louvered vent above, inset porch covers two bays, infilled with jalousied windows. 30 1001 C
- 1028 1909 OLD GOVERNMENT ST c. 1945. Minimal Traditional, one and a half story, gable roof sides, brick, three bay facade with attached two bay wing east side, easternmost bay a carport, centered entrance, flanked by picture window east adjacent and horizontal paired awning windows west adjacent with shutters, pair gable dormers with horizontal awning windows, box cornice, chimney between house and wing. 26 1003 C
- 1029 1910 OLD GOVERNMENT ST c. 1925. Bungalow, one story, gable roof front, two bay facade, aluminum sided, offcenter attached gable porch with battered box columns on brick plinths, wood door with lunette light, side lights filled, transom open, paired 9/1 windows, box cornice. 31 1001 C
- 1030 1911 OLD GOVERNMENT ST c. 1925. Bungalow, two story, hip roof, vinyl sided, four bay facade, attached slightly offcenter one story hip roof porch covers most of facade, box columns with capitals, east bay filled with casement windows with transoms, six panel door with sidelights and transom, 6/1 windows, center of second story features attached hip roof porch with square posts and clapboarded wall, box cornice, side chimney. 25 1003 C
- 1031 1912 OLD GOVERNMENT ST c. 1925. Bungalow, one story, gables off hip roof, frame, three bay facade, inset porch covers two bays, square brick pillars with arched openings at facade and east elevation, bubble awning over steps, half timbering in stucco gable, multi-light door, tripled 3/1 windows west adjacent, exposed rafters. 32 1001 C
- 1032 1913 OLD GOVERNMENT ST c. 1925. Bungalow, one story, gable roof front, frame, three bay facade, recessed porch covers facade, square brick pillars, Craftsman door with transom, tripled 6/1 windows flank entrance, purlins in gable, three pane light with flanking louvers, exposed rafters. 24 1003 C
- 1033 1914 OLD GOVERNMENT ST c. 1910. Colonial Revival, one story, hip roof, frame, five bay facade, wood door with window, transom, 2/2 windows with shutters, recessed porch covers facade, Tuscan columns, ornamental iron railing, exposed rafters, side chimney. 33 1001 C

United States Department of the Interior
National Park Service

National Register Of Historic Places
Continuation Sheet

Section Number 7 Page 123

MID TOWN HISTORIC DISTRICT
Mobile
Mobile County, AL

- 1034 1915 OLD GOVERNMENT ST c. 1925. Bungalow, one story, staggered gables front, frame, three bay facade, side entrance, six panel door with fabric awning, 8/8 window with 4/4 sidelights, shutters, tripled 4/4 windows in main gable, knee braces, exposed rafters. 23 1003 C
- 1035 1916 OLD GOVERNMENT ST c. 1910. Colonial Revival, one story, hip roof, frame, five bay facade, double wood doors with windows, transom, 2/2 windows, recessed porch covers facade, exposed rafters, side chimney. 34 1001 C
- 1036 1917 OLD GOVERNMENT ST c. 1925. Tudor Revival, one story, hip roof, brick, two bay facade, attached offcenter gable with squared posts, half-timbered gable, wood door flanked by small Tudor windows, paired 6/6 windows west adjacent, attached gable porch west elevation, paired square posts, half timbered, two interior chimneys. 22 1003 C
- 1037 1918 OLD GOVERNMENT ST c. 1910. Colonial Revival, one story, hip roof, frame, five bay facade, recessed porch covers facade, Tuscan columns, heavy ornamental iron burglar door conceals entrance, sidelights and transom, 2/2 windows with shutters, end chimneys, box cornice. 35 1001 C
- 1038 1919 OLD GOVERNMENT ST c. 1920. Bungalow, one story, gable roof sides, frame, three bay facade, Craftsman door, paired Craftsman windows flank entrance, recessed porch covers facade, box columns with capitals, gable with arched ceiling over stoop, pair small gable dormers with louvered vents, exposed rafters. 21 1003 C
- 1039 1920 OLD GOVERNMENT ST c. 1970. Ranch Style, one story, hip roof, brick, seven bay facade, door obscured by heavy ornamental iron burglar screen, 9/9 aluminum windows, box cornice. 1 1002 N
- 1040 1921 OLD GOVERNMENT ST c. 1940. Minimal Traditional, one story, gable roof sides, frame, three bay facade, round top wood door, attached gable with brick round top arch, slightly battered sides, paired 3/1 windows west adjacent with shutters, inset porch east bay, glassed in, louvered vent, end chimney, exposed rafters. 20 1003 C
- 1041 1923 OLD GOVERNMENT ST c. 1925. Bungalow, two story, gable on hip front, frame, three bay facade, inset one story porch east front corner, square brick pillar, pointed arch, six panel door, paired 6/6 windows, second story, west bay jalousied windows, louvered vent, exposed rafters. 19 1003 C
- 1042 1948 OLD GOVERNMENT ST c. 1930. Cottage Revival, one story, cross gable, three bay facade, stucco, centered entrance a six panel door in gable with curving wing walls, red brick headers trim around door, bubble awning over door, paired 6/6 windows west bay with fan transom and brick header trim, shutters, three modern infill single pane windows east bay with fan transom, brick headers across arch in two rows, box cornice, closed return. 2 1002 C

United States Department of the Interior
National Park Service

National Register Of Historic Places
Continuation Sheet

Section Number 7 Page 124

MID TOWN HISTORIC DISTRICT
Mobile
Mobile County, AL

- 1043 1951 OLD GOVERNMENT ST c. 1925. Bungalow, one story, cross gable, frame, attached offcenter gable porch, square brick pillars, screened, east adjacent is picture window with casement window sidelights and a transom, shutters, end chimney, louvered vent, exposed rafters, attached shed roof carport west side. 18 1003 C
- 1044 1952 OLD GOVERNMENT ST c. 1930. Cottage Revival, one story, cross gable, three bay facade, stucco, centered entrance in gable, six panel door with white brick surround, tripled 6/6 windows in east bay with white brick surround, inset porch north bay, arched window infill, end chimney, box cornice, closed return. 3 1002 C
- 1045 1954 OLD GOVERNMENT ST c. 1945. Minimal Traditional, one story, gable roof sides, asbestos sided, three bay facade, centered entrance, six panel door, attached gable with square posts, dentil course runs below cornice of house, 12/12 windows with shutters flank entrance, box cornice closed return. 4 1002 C
- 1046 1955 OLD GOVERNMENT ST c. 1940. Colonial Revival, one and a half story, gable roof sides, frame, three bay facade, centered entrance, six panel door, attached segmental roof over stoop with paired square posts, flanking 9/9 windows with shutters, three gable dormers, 6/6 windows, interior chimney, gable wing east rear. 17 1003 C
- 1047 1956 OLD GOVERNMENT ST c. 1945. Minimal Traditional, one story, cross gable, frame, four bay facade, inset porch covers two bays, square posts and screened, metal awning, chimney up center of front gable, flanked by 6/6 windows with shutters, triangular louvered vent, open eaves but no rafters. 5 1002 C
- 1048 1957 OLD GOVERNMENT ST c. 1945. Colonial Revival, one and a half story, gable roof sides, frame, three bay facade, centered entrance, six panel door, attached roof over stoop, ornamental iron supports, flanking 12/12 windows with shutters, three gable dormers, 6/6 windows, interior chimney, dentil course, attached gable wing east rear with metal awning over east side. 16 1003 C
- 1049 1958 OLD GOVERNMENT ST c. 1940. Cottage Revival, one story, gable roof sides, brick, three bay facade, centered entrance, six panel door, attached gable with arched opening, round top louvered vent, paired 6/6 windows east adjacent, inset porch west adjacent, pair arched openings, screened, end chimney. 6 1002 C
- 1050 1960 OLD GOVERNMENT ST c. 1940. Cottage Revival, one and a half story, cross gable, brick, four bay facade, round top wood door with attached gable with arched opening, pair 12/12 windows east adjacent with shutters and ornamental iron burglar bars over lower sash, casement windows west adjacent with ornamental iron burglar bars, fabric awning, pair gable dormers with six pane sash and louvered panel below, end chimney, box cornice, no return. 7 1002 C
- 1051 2007 OLD GOVERNMENT ST c. 1945. Minimal Traditional, one story, gable roof sides, asbestos sided, three bay facade, six panel door, attached gable over stoop, Tuscan columns, flanking 8/8 windows with shutters, end chimney, gable wing east rear with metal awning wrapping around. 15 1003 C

United States Department of the Interior
National Park Service

National Register Of Historic Places
Continuation Sheet

Section Number 7 Page 125

MID TOWN HISTORIC DISTRICT
Mobile
Mobile County, AL

- 1052 2008 OLD GOVERNMENT ST c. 1925. Bungalow, one story, gable roof front, three bay facade, vinyl sided, recessed porch covers facade, box battered columns on brick plinths, balustraded and screened, four panel door with lunette light, paired 3/1 windows, knee braces, enclosed cornice, side chimney, 8 1002 C
- 1053 2009 OLD GOVERNMENT ST c. 1960. Ranch Style, one story, gable roof sides, brick, four bay facade, offcenter entrance with burglar door, attached gable over stoop, ornamental iron supports, metal casement windows, box cornice, no return. 14 1003 N
- 1054 2010 OLD GOVERNMENT ST c. 1925. Bungalow, one story, gable roof front, frame, four bay facade, duplex, recessed porch covers facade, square brick pillars with capitals, framing in place to screen but not screened, two front doors, wood with windows, flanked by paired 2/2 windows, exposed rafters. 9 1002 C
- 1055 2050 OLD GOVERNMENT ST c. 1925. Bungalow, one and a half story, gable roof sides, frame, three bay facade, recessed porch covers facade, battered, boxed columns on brick plinths, Craftsman door with sidelights, paired 6/1 windows flank entrance, shed roof dormer with bank of casement windows, knee braces, exposed rafters, end chimney. 10 1002 C
- 1056 2051 OLD GOVERNMENT ST c. 1930. Cottage Revival, one and a half story, cross gable, ell plan, brick, three bay facade, round top inset entrance, arched picture window east adjacent, paired 4/1 windows west adjacent, small 1/1 window in gable, end chimney, box cornice, no return. 13 1003 C
- 1057 2053 OLD GOVERNMENT ST c. 1925. Bungalow, one story, gable roof front, frame, attached gable porch covers most of facade, pierced brick pillars, brick knee wall, three bay facade, Craftsman doors and windows, knee braces, exposed rafters. 12 1003 C
- 1058 2054 OLD GOVERNMENT ST c. 1925. Bungalow, one story, gable roof front, vinyl sided, recessed porch covers facade, ornamental iron supports with brackets on brick plinths, door obscured by louvered screen, flanked by paired 6/1 windows, horizontal light in gable, knee braces, eaves covered. 11 1002 C
- 1059 2055 OLD GOVERNMENT ST c. 1945. Minimal Traditional, one story, cross gable, frame, four bay facade, centered gable with entrance, six panel door with bubble awning, louvered vent in gable, brick chimney east adjacent, paired 3/1 windows west adjacent, east end a recessed porch with square posts, balustraded and screened, box cornice. 11 1003 C
- 1060 2056 OLD GOVERNMENT ST c. 1930. Bungalow, one story, gable roof front, asbestos sided, three bay facade, attached hip roof porch covers facade, square brick pillars on knee wall, side entrance, multi-light door, 1/1 windows, lattice vent in gable, exposed rafters. 12 1002 C

United States Department of the Interior
National Park Service

National Register Of Historic Places
Continuation Sheet

Section Number 7 Page 126

MID TOWN HISTORIC DISTRICT
Mobile
Mobile County, AL

- 1061 2057 OLD GOVERNMENT ST c. 1925. Bungalow, one story, staggered gables front, frame, four bay facade, attached shed roof porch covers three bays, square posts with braces on brick plinths, wood door with window, 1/1 windows, paired 1/1 windows in front gable, knee braces, louvered vent in larger gable, exposed rafters. 10 1003 C
- 1062 2058 OLD GOVERNMENT ST c. 1925. Bungalow, one story, gable roof sides, frame, three bay facade, attached offcenter gable porch with square brick pillars, door obscured by screen, French doors in west bay, bank four 3/1 windows east bay, chimney at facade, stuccoed, knee braces, exposed rafters. 13 1002 C
- 1063 2059 OLD GOVERNMENT ST c. 1925. Bungalow, one story, gable roof front, frame, attached, offcenter gable roof porch, battered brick pillars, brick knee wall, three bay facade, gable porte-cochere west side with battered brick pillars, Craftsman door, paired Craftsman windows east adjacent, tripled Craftsman windows west adjacent, knee braces, triangular lattice vents in gables, exposed rafters. 9 1003 C
- 1064 2104 OLD GOVERNMENT ST c. 1930. Minimal Traditional, one story gable roof sides, brick, three bay facade, offcenter attached gable porch with arched brick opening, infilled with aluminum awning windows and screen door, tripled 3/1 windows middle bay, paired 3/1 windows west bay, interior chimney. 14 1002 C
- 1065 2106 OLD GOVERNMENT ST c. 1940. Minimal Traditional, one story, cross gable, aluminum sided, three bay facade, inset porch east bay, square brick corner pillar, gables south and east, louvered vent, chimney at facade flanked by windows, box cornice, no return. 15 1002 C
- 1066 2108 OLD GOVERNMENT ST c. 1930. Bungalow, one story, hip roof, stucco up to window sill level, frame above, three bay facade, door obscured by screen, attached hip roof porch over stoop with Tuscan columns, 3/1 windows with shutters, box cornice. 16 1002 C
- 1067 2150 OLD GOVERNMENT ST c. 1960. Commercial office, one story, frame, tin mansard roof, aluminum awning windows, six panel door, no porch. 17 1002 N
- 1068 2151 OLD GOVERNMENT ST c. 1945. Minimal Traditional, one story, gable roof sides, frame, three bay facade, attached gable with slender iron supports over stoop, six panel door, paired 6/6 windows west adjacent, large multi-light window east adjacent, exposed rafters. 8 1003 C
- 1069 2153 OLD GOVERNMENT ST c. 1940. Minimal Traditional, one story, gable roof sides, frame, three bay facade, offset inset porch with attached gable, square posts, six panel door, paired 1/1 windows with shutters, louvered vent, exposed rafters. 7 1003 C

United States Department of the Interior
National Park Service

National Register Of Historic Places
Continuation Sheet

Section Number 7 Page 127

MID TOWN HISTORIC DISTRICT
Mobile
Mobile County, AL

- 1070 2154 OLD GOVERNMENT ST c. 1945. Minimal Traditional, one story, gable roof sides, asbestos sided, four bay facade, wood door with small window, screen, attached gable porch covers two bays, ornamental iron supports and railing, paired 6/6 windows, box cornice, closed return, interior chimney. 18 1002 C
- 1071 2155 OLD GOVERNMENT ST c. 1940. Minimal Traditional, one story, gable roof sides, frame, three bay facade, attached centered gable entrance, brick battered arched support, inset porch west adjacent with paneled box column infilled with glass, 3/1 windows, end chimney, exposed rafters, louvered vent. 6 1003 C
- 1072 2156 OLD GOVERNMENT ST c. 1930. Bungalow, one and a half story, gable roof front, stucco, three bay facade, attached hip roof porch covers facade, square brick pillars, ornamental iron supports on brick plinths flank steps, six panel door, 1/1 windows, 1/1 window in gable with lattice panel over lower sash, staggered secondary gable one bay back and offcenter one bay, round louvered vent, pair large shed roof dormers east and west elevations with 1/1 windows, exposed rafters, side chimney. 19 1002 C
- 1073 2157 OLD GOVERNMENT ST c. 1925. Bungalow, one story, hip roof, frame, three bay facade, attached gable porch covers center of facade, paneled battered box columns on brick plinths, screened, Craftsman door, windows obscured by screens, knee braces, louvered vent, box cornice, no return. 5 1003 C
- 1074 2158 OLD GOVERNMENT ST c. 1945. Colonial Revival, one and a half story, gable roof sides, brick, five bay facade, attached flat roof porch covers three bays, paired square columns with capitals, balustraded roof, six panel front door with flanking pilasters and fan transom, 6/6 windows, pair gable dormers with 6/6 windows, end chimney. 20 1002 C
- 1075 2159 OLD GOVERNMENT ST c. 1925. Bungalow, one story, gable roof sides, frame, three bay facade, attached gable porch covers facade, paneled, boxed columns on brick plinths, six panel door, paired 6/1 windows flank entrance, dentil course along front gable, knee braces, louvered vent, exposed rafters, side chimney. 4 1003 C
- 1076 2200 OLD GOVERNMENT ST c. 1950. Minimal Traditional, one story, hip roof, frame, four bay facade, door obscured by screen, no porch, stoop, 6/6 windows with board shutters, air condition window units in two windows, exposed rafters. 21 1002 C
- 1077 2201 OLD GOVERNMENT ST c. 1925. Bungalow, one story, gable roof front, frame, three bay facade, attached offcenter gable porch, box battered columns on brick plinths, screened, fabric drop frieze, louvered vent, knee braces, exposed rafters, windows and doors obscured by screens and burglar bars. 3 1003 C
- 1078 2202 OLD GOVERNMENT ST c. 1925. Bungalow, one story, gable roof front, asbestos sided, three bay facade, attached offcenter gable porch with battered boxed columns on brick plinths, three entrances, centered original door a multi-light door with transom, flanked by later multi-light doors, western one with a fabric awning, louvered vent, purlins, exposed rafters, interior chimney. 22 1002 C

United States Department of the Interior
National Park Service

National Register Of Historic Places
Continuation Sheet

Section Number 7 Page 128

MID TOWN HISTORIC DISTRICT
Mobile
Mobile County, AL

- 1079 2203 OLD GOVERNMENT ST c. 1960. Colonial Revival, one story, gable roof front, brick, three bay facade, attached gable porch covers most of facade, Tuscan columns and balustraded, six panel door, multi-light metal windows, round louvered vent and dentil course at porch gable, box cornice, no return. 2 1003 N
- 1080 2204 OLD GOVERNMENT ST c. 1925. Bungalow, one story, gable roof front, frame, three bay facade, six panel door with transom, flanking 3/1 windows, paired west, tripled east, recessed porch covers facade, square brick pillars, knee braces, lunette light in gable, gable porte-cochere east elevation, side chimney, exposed rafters. 23 1002 C
- 1081 2205 OLD GOVERNMENT ST c. 1955. Minimal Traditional, one story, cross gable, vinyl sided, three bay facade, side entrance, inset porch with ornamental iron support and railing, metal casement windows in central gabled bay, box cornice, no return. 1 1003 N
- 1082 2206 OLD GOVERNMENT ST c. 1950. Minimal Traditional, one story, gable roof sides, brick, three bay facade, carport inset west bay, attached offcenter gable porch covers two bays, square posts with capitals, balustraded, six panel door, paired 6/6 windows, box cornice, board and batten gable. C
- 1083 2207 OLD GOVERNMENT ST c. 1945. Minimal Traditional, one story, cross gable, asbestos sided, three bay facade, centered entrance in attached gable with square posts, decorative metal drop frieze, wood door with glass, 8/8 windows with shutters, purlins, exposed rafters. 35 1002 C
- 1084 2208 OLD GOVERNMENT ST c. 1970. Ranch Style, one story, gable roof sides, brick, three bay facade, centered entrance, wood door, tripled 6/6 windows west bay, one 6/6 window with shutters east bay, box cornice. 25 1002 N
- 1085 2209 OLD GOVERNMENT ST c. 1950. Minimal Traditional, one story, gable roof sides, frame, three bay facade, attached gable with entrance, board and batten, center bay, paired 3/1 windows east adjacent, one 3/1 window west adjacent, exposed rafters. 34 1002 C
- 1086 2252 OLD GOVERNMENT ST c. 1970. Ranch Style, one story, gable roof sides, recessed porch covers facade, square posts, inset carport east bay, brick, side entrance, picture window with square surrounding lights, box cornice. 27 1002 N
- 1087 2254 OLD GOVERNMENT ST c. 1940. Minimal Traditional, one story, gable roof sides, brick and frame, three bay facade, inset entrance, six panel door, west bay frame with paired 6/1 windows, east bay tripled 6/6 windows with shutters, end chimney. 28 1002 C

06 5
06 6

United States Department of the Interior
National Park Service

National Register Of Historic Places
Continuation Sheet

Section Number 7 Page 129

MID TOWN HISTORIC DISTRICT
Mobile
Mobile County, AL

- 1088 2255 OLD GOVERNMENT ST c. 1925. Bungalow, one story, gable roof front, frame, three bay facade, recessed porch covers facade, square brick pillars, six panel door, paired 3/1 windows with shutters flank entrance, gable porte-cochere east side, knee braces, louvered vent, exposed rafters, side chimney. 33 1002 C
- 1089 2256 OLD GOVERNMENT ST c. 1925. Bungalow, one story, gable roof sides, frame, attached offcenter gable porch with square brick pillars, aluminum awning window infill, metal awning across above windows, purlins, louvered vent, exposed rafters, side chimney, original windows obscured by dark screens. 29 1002 C
- 1090 2257 OLD GOVERNMENT ST c. 1925. Bungalow, one and a half story, jerkin head gable roof front, frame, three bay facade, inset porch east bay, ornamental iron support and brackets, door in side, six panel, paired 3/1 windows center bay, double shouldered chimney west adjacent, smaller 3/1 window in west bay, paired 6/1 windows in gable, knee braces, exposed rafters, interior chimney. 32 1002 C
- 1091 2258 OLD GOVERNMENT ST c. 1925. Bungalow, one story, cross jerkin head gable roof, frame, four bay facade, inset porch covers half facade, square brick pillar, screened, chimney at facade flanked by 3/1 window, louvered vent, exposed rafters. 30 1002 C
- 1092 VOID
- 1093 1801 OLD SHELL RD c. 1935. Nixon Drugs, Standard Commercial, C. L. Hutchisson, Sr. architect, one story, brick, flat roof with peaked parapet with concrete coping, offcenter entrance, aluminum door with transom, set three plate glass windows, one frame infilled window, attached flat roof awning covers sidewalk, series transoms over awning, stucco infilled with signs, corner sign hangs over sidewalk. 26 1010 C
- 1094 1803 OLD SHELL RD c. 1935. Standard Commercial, one story, flat roof, brick, series four store fronts, multi-light doors, plate glass windows, easternmost one shuttered with louvered shutters, flat roof metal canopy covers sidewalk. 27 1010 C
- 1095 1805 OLD SHELL RD c. 1970. Commercial, one story, flat roof, brick, vertical windows east and west ends of facade. 28 1010 N
- 1096 1807 OLD SHELL RD c. 1970. Commercial, one story, flat roof, brick and cinder block, corner entrance, aluminum door with iron pole corner support, series four plate glass windows. 29 1010 N

United States Department of the Interior
National Park Service

National Register Of Historic Places
Continuation Sheet

Section Number 7 Page 130

MID TOWN HISTORIC DISTRICT
Mobile
Mobile County, AL

- 1097 1809 OLD SHELL RD c. 1935. Bungalow, one story, gable roof front, frame, three bay facade, six panel door, 3/1 windows, attached fabric awning covers two bays, slender metal supports on brick plinths, knee braces, louvered vent, exposed rafters, side chimney. 30 1010 C
- 1098 1811 OLD SHELL RD c. 1920. Vernacular, one and a half story, gable roof front, board and batten, brick up to window sill level, three bay facade, one story gable bay offcenter east, attached shed roof porch covers other two bays, ornamental iron support on brick plinth, six panel door, aluminum 6/6 windows, louvered vent over window in gable, box cornice. 13 1010 N
- 1099 1813 OLD SHELL RD c. 1910. Vernacular, one story, cross gable, ell plan, aluminum sided, attached hip roof porch has been infilled with siding, aluminum windows, gable bay, 2/2 windows, light in gable, louver in secondary gable. 32 1010 N
- 1100 1815 OLD SHELL RD c. 1925. Bungalow, one story, gable roof front, frame, three bay facade, attached shed roof porch with gables either end covers facade, west gable covers a porte-cochere, square brick pillars, Craftsman door, flanking paired Craftsman windows, purlins, exposed rafters. 33 1010 C
- 1101 1817 OLD SHELL RD c. 1925. Bungalow, one story, gable roof front, frame, three bay facade, attached gable porch covers facade, battered, boxed columns on brick plinths, wood door with window, 3/1 windows, knee braces, louvered vent in porch gable, exposed rafters, two interior chimneys. 34 1010 C
- 1102 1819 OLD SHELL RD c. 1920. Two story, gable roof sides with pair small gables at facade, frame, six bay facade, attached offcenter one story hip roof porch with square brick pillars, ornamental iron railing, screened, 2/2 windows, door obscured by screen, louvered vents in gables. 35 1010 C
- 1103 1823 OLD SHELL RD c. 1870. Greek Revival, one story, hip roof with gable wing east, attached offcenter gable porch with box columns with capitals, balustraded, 6/6 windows with shutters under porch, louvered vent, bay window east adjacent with full height 2/4 windows, probably a later Victorian addition, two interior chimneys with corbeled caps, box cornice, dentil course. 1 1011 C
- 1104 1824 OLD SHELL RD c. 1945. Apartment building, one and two story, flat roof, brick, series of four auto bays in first story at east end, second story features a frame bay window supported on brackets, 3/1 windows, one story portion of building to west, inset entrance, 6/6 windows, brick coping. 23 1012 C
- 1105 1825 OLD SHELL RD c. 1920. Bungalow, two story, hip roof, three bay facade, frame, six panel central entrance, attached one story gable over stoop with ornamental iron supports, paired 6/6 windows with shutters, one story hip roof wing east side, hip porte-cochere west side, exposed rafters. 2 1011 C

United States Department of the Interior
National Park Service

National Register Of Historic Places
Continuation Sheet

Section Number 7 Page 131

MID TOWN HISTORIC DISTRICT
Mobile
Mobile County, AL

- 1106 1829 OLD SHELL RD c. 1925. Bungalow, two story, cross gable, ell plan, frame, three bay facade, entrance in west bay, six panel door, attached gable on wall brackets over stoop, tripled 3/1 windows with fabric awning center bay first story, inset porch under facing gable, square brick pillars, stepped knee wall, tripled 3/1 windows in two upstairs bays, sunburst in front gable, box cornice, no return. 3 1011 C
- 1107 1831 OLD SHELL RD c. 1925. Bungalow, heavily altered and added to, gable roof sides, asbestos sided, shed roof additions at facade, some windows boarded up, others metal casement, in main house original portion windows are 2/2, entrance at facade and at east elevation, ornamental iron railings on stoops, fabric awnings across portion of facade, exposed rafters, knee braces, interior chimney with corbeled cap. 4 1011 N
- 1108 1835 OLD SHELL RD c. 1900/1980. Queen Anne, one and a half story, cross gables, vinyl sided, house faces a side street but has an Old Shell Road address, major two story additions to rear and north elevation, original windows have been largely replaced by single pane lights with vertical blinds, hexagonal turret at facade with roof, bracketed eaves, triangular louvered vents in gables, box cornice, no return. 5 1011 N
- 1109 1838 OLD SHELL RD c. 1950. Garage apartments, two story, gable roof sides, asbestos sided, three auto bays in first story with double wooden doors, entrance west side, six panel door with attached gable on wall brackets, 6/6 windows with shutters on second story, box cornice. 22 1012 C
- 1110 1840 OLD SHELL RD c. 1925. Bungalow, one story, gable roof front, frame, three bay facade, recessed porch covers facade, modern wood door with square window, flanked by paired 6/1 windows, square brick pillars, ornamental iron supports on brick plinths flank steps, knee braces, horizontal light in gable, exposed rafters. 21 1012 C
- 1111 1842 OLD SHELL RD c. 1925. Bungalow, one story, gable roof front, frame, three bay facade, attached offcenter gable porch, battered, boxed columns on brick plinths, screened, door not visible, windows obscured by metal awnings which also wrap around porch, louvered vents, knee braces, exposed rafters. 20 1012 C
- 1112 1844 OLD SHELL RD c. 1920. Bungalow, one story, hip roof, frame, two bay facade, inset porch covers half facade, battered box column on brick plinth, entrance is side wall of porch, Craftsman door, paired 3/1 windows, box cornice, interior chimney. 19 1012 C
- 1113 1850 OLD SHELL RD c. 1925. Bungalow, gable roof front, frame, three bay facade, recessed porch covers facade, high brick plinths with tripled brick supports and frame cross pieces, six panel door, multi-light top sash over one pane flanks entrance, tripled light in gable, purlins, box cornice, no return. 18 1012 C
- 1114 1851 OLD SHELL RD c. 1920. Beaux Arts Style, two story, hip roof, green ceramic tile roof, brick, three bay facade, one story hip roof wing east, two story wing west, centered entrance, six panel door with sidelights and transom, attached gable over stoop, paired Tuscan columns, arched opening in gable, casement windows in arched openings with transoms flank entrance, second floor windows 6/1, interior chimney, exposed rafters. 6 1011 C

United States Department of the Interior
National Park Service

National Register Of Historic Places
Continuation Sheet

Section Number 7 Page 132

MID TOWN HISTORIC DISTRICT
Mobile
Mobile County, AL

- 1115 1852 OLD SHELL RD c. 1950. Minimal Traditional, duplex, one story, gable roof sides, asbestos sided, four bay facade, attached gable porch with paired square posts covers center two bays, two front doors, wood with multi-light windows, paired 6/6 windows flank entrances, louvered vent in gable, box cornice, no return. 17 1012 C
- 1116 1854 OLD SHELL RD c. 1920. Bungalow, one and a half story, hip roof, frame, three bay facade, recessed porch covers facade, battered, boxed columns on brick plinths, centered wood door with window, flanking paired 3/1 windows, hip roof pop up with 3/1 windows and chimney at front, exposed rafters. 16 1012 C
- 1117 1856 OLD SHELL RD c. 1910. Vernacular, one story, hip roof, frame, two bay facade, recessed porch covers facade, paneled boxed columns, later wood balustrade, wood door with multi-lights, transom, paired 6/1 windows with shutters, exposed rafters. 15 1012 C
- 1118 1857 OLD SHELL RD c. 1925. Colonial Revival, two story, gable roof sides, frame, three bay facade, central entrance, six panel door with sidelights and fan transom, attached gable over stoop, Tuscan columns, arched opening in gable, paired 6/6 windows flank entrance, end chimney, box cornice. 7 1011 C
- 1119 1858 OLD SHELL RD c. 1930. Bungalow, one story, gable roof front, stucco, three bay facade, attached offcenter gable porch with arched opening with exposed brick headers in arch, square stucco pillars with exposed brick capitals, Craftsman door, tripled 3/1 windows in east bay, 6/6 windows under porch, louvered vent in main gable, purlins, exposed rafters. 14 1012 C
- 1120 1861 OLD SHELL RD c. 1925. Bungalow, one and a half story, cross gables, frame, three bay facade, recessed porch covers facade, battered box columns with capitals on clapboarded plinths, Craftsman door, 6/6 sash, dentil course across front gable, knee braces, window in gable slightly bumped out, exposed rafters. 8 1011 C
- 1121 1900 OLD SHELL RD 1874/moved c. 1970. Classical Revival, one story, hip roof, frame, five bay facade, attached flat roof porch covers three bays, ornamental cast iron supports and railing, wood door with sidelights and transom in classical surround, 6/6 windows with shutters, box cornice, house originally stood on Broad Street downtown and was moved. 13 1012 C The house fits within the architectural context of the district and should be considered contributing.
- 1122 1901 OLD SHELL RD 1922. Dutch Colonial Revival, C. L. Hutchisson, Sr. architect, one and a half story, gambrel roof sides, frame, three bay facade with one story hip roof wing west elevation, six panel entrance with sidelights, slightly recessed with Doric pilasters and large round topped arch above, tripled double hung sash flank entrance, center window 6/6 with 4/4 flanking, large shed roof dormer above, 6/6 windows east and west with shutters, group three six light windows center bay, stone end chimney. 9 1011 C
- 1123 1903 OLD SHELL RD c. 1930. Bungalow, one story, gable roof front, stucco, two bay facade, attached offcenter gable porch with slender paired posts, louvered vents in both gables, multi-light tripled verticle window in east bay with lunette transoms, knee braces, exposed rafters, ridge chimney. 10 1011 C

United States Department of the Interior
National Park Service

National Register Of Historic Places
Continuation Sheet

Section Number 7 Page 133

MID TOWN HISTORIC DISTRICT
Mobile
Mobile County, AL

- 1124 1905 OLD SHELL RD c. 1925. Minimal Traditional, two story, cross gable, ell plan, brick, five bay facade, entrance in front gable, six panel door with transom, classical door surround with gable above, 8/8 windows with shutters, three wall gables in ell over second story windows, louvered vent, one story flat roof porte-cochere east side, end chimney, box cornice, no return. 11 1011 C
- 1125 1907 OLD SHELL RD c. 1925. Colonial Revival, two story, gable roof sides with one story gable wings each end, three bay facade, central entrance, six panel door with Palladian surround, 12/12 windows with shutters, 6/6 windows with shutters second floor, two end chimneys, casement windows in wings, box cornice. 12 1011 C
- 1126 1911 OLD SHELL RD c. 1925. Colonial Revival, two story, gable roof sides, brick, two story gable wing west end, three bay facade, wing has two bays, central entrance, six panel door with sidelights and fan transom, attached one story gable porch over stoop, Tuscan columns, arch in gable, flanked by 6/6 windows with shutters, pair wall gables in wing, three chimneys, box cornice. 13 1011 C
- 1127 1915 OLD SHELL RD c. 1930. Colonial Revival, one and a half story, gable roof sides, frame, three bay facade, central entrance, six panel door with sidelights and fan transom, flanking 12/12 windows with shutters, three gable dormers with 6/6 windows, end chimney, box cornice. 14 1011 C
- 1128 2000 OLD SHELL RD c. 1920. Bungalow, one and a half story, cross gable, brick, attached one story hip porch covers facade, west half infilled with brick and casement windows, east half features square brick pillars and screened, entrance not visible, staggered pair of gables at facade, louvered vent in offset one, window in main one, exposed rafters. 12 1012 C
- 1129 2001 OLD SHELL RD c. 1940. Colonial Revival, two story, cross gable, brick, three bay facade with one story gable wing west end, centered entrance, six panel door with sidelights and transom, attached one story gable porch with tripled Tuscan columns, dentil work around eaves and gables, casement windows with shutters, box cornice, end chimney. 15 1011 C
- 1130 2005 OLD SHELL RD c. 1940. Colonial Revival, two story, gable roof sides, brick, five bay facade, central entrance, six panel door, classical surround with gable, 9/9 windows with ornamental iron burglar bars over lower sash, soldiered lintels, end chimney, box cornice. 16 1011 C
- 1131 2006 OLD SHELL RD c. 1925. Bungalow, one story, gable roof front, frame,, recessed porch covers facade, square brick pillars, modern wooden balustrade, six panel door with sidelights, 1/1 windows, louvered vent in gable, knee braces, exposed rafters. 11 1012 C
- 1132 2008 OLD SHELL RD c. 1930. Bungalow, one story, gable roof front, frame, two bay facade, attached offcenter gable porch with tripled box columns on brick plinths, wood door, paired 3/1 windows with planter box, louvered vents, knee braces, exposed rafters, interior chimney. 10 1012 C

26 5
100

United States Department of the Interior
National Park Service

National Register Of Historic Places
Continuation Sheet

Section Number 7 Page 134

MID TOWN HISTORIC DISTRICT
Mobile
Mobile County, AL

- 1133 2009 OLD SHELL RD c. 1850. Gulf Coast Cottage, one and a half story, gable roof sides, frame, recessed porch covers facade, square posts with capitals, balustraded, center hall plan, four panel door with sidelights and transom, 6/6 windows with shutters, three gable dormers, most probably added ca. 1940, 6/6 windows in dormers, two interior chimneys, box cornice. 17 1011 C
- 1134 2010 OLD SHELL RD c. 1930. Bungalow, one story, gable roof front, vinyl sided,, recessed porch covers facade, battered stucco pillars, wood door, 6/1 windows, horizontal Craftsman light in gable, knee braces, enclosed rafters. 9 1012 C
- 1135 2015 OLD SHELL RD c. 1910. Vernacular, two story, hip roof, frame, two bay facade, side hall plan, four panel door with sidelights and transom, 1/1 windows, attached hip roof porch covers facade and wraps around east elevation, Tuscan columns, interior chimney, exterior chimney, box cornice. 18 1011 C
- 1136 2019 OLD SHELL RD c. 1925. Bungalow, gable on hip roof, stucco, four bay facade, attached offcenter gable porch with stucco pillars and broad arched opening, round top door with screen, casement windows with transoms, open deck east adjacent with balustrade, casement windows and arched transom, knee braces, lattice vent in gables, exposed rafters, side chimney. 19 1011 C
- 1137 2025 OLD SHELL RD c. 1930. Bungalow, one story, gable roof front, asbestos sided, three bay facade, attached offcenter gable porch with box battered columns on brick plinths, wood door, paired and tripled 3/1 windows, knee braces, louvered vent in main gable, two interior chimneys. 20 1011 C
- 1138 2051 OLD SHELL RD c. 1900. Victorian Cottage, one story, high hip roof, frame, ell plan with hip roofs, facade is two bays, side hall plan with wood door with window, sidelights and transom, attached shed roof porch with Tuscan columns, 1/1 windows, seperate entrance in main block of house, east end, wood door with window, transom, attached shed roof porch with square post, balustraded, box cornice, two interior chimneys with corbeled caps. 21 1011 C
- 1139 2053 OLD SHELL RD c. 1900. Victorian Cottage, one story, cross gable, frame, three bay facade, center hall plan, wood door with window, sidelights and transom, attached hip roof porch covers facade, Tuscan columns, paired 1/1 windows, louvered vent, interior chimney with corbeled cap, box cornice. 22 1011 C
- 1140 2055 OLD SHELL RD c. 1900. Queen Anne Cottage, one and a half story, hip roof, frame, four bay facade, gabled bay west end, 2/2 windows, pent, louvered vent, bargeboard, center hall plan, wood door with window, transom, recessed porch covers three bays, turned posts, balustraded, brackets, drop frieze, slide-by windows, hip roof dormer with small light, interior chimney with corbeled cap, box cornice, picket fence. 23 1011 C
- 1141 2058 OLD SHELL RD c. 1975. Apartment building, two and a half story, gambrel roof front, brick first story, vinyl upper story, inset porch second floor west side, square posts and large x pattern railing, aluminum 6/6 windows, wood door in center of brick first story. 8 1012 N

United States Department of the Interior
National Park Service

National Register Of Historic Places
Continuation Sheet

Section Number 7 Page 135

MID TOWN HISTORIC DISTRICT
Mobile
Mobile County, AL

- 1142 2062 OLD SHELL RD c. 1960. Standard Commercial, one story, flat roof with gable over centered entrance, brick, double wood doors with attached awning on slender iron supports, bumped out shop windows flank entrance, brick dentil course, gable has wood block dentil course, widely spaced. 7 1012 N
- 1143 2064 OLD SHELL RD 1948/1985. Standard Commercial, two story, flat roof, brick and stucco scored to simulate ashlar, inset entrance, aluminum door, paired 1/1 windows flank entrance, 1/1 windows second story with shutters, slight overhang at first story with dentil course and dentil course at top of building, one story flat roof rear section. 6 1012 N
- 1144 2065 OLD SHELL RD c. 1990. Commercial, one story, flat roof, brick and stucco, very long building, tinted windows, aluminum doors, parking lot with landscaping in front. 24 1011 N
- 1145 2068 OLD SHELL RD c. 1930. Standard Commercial, one story, flat roof with parapets, brick, centered entrance, double aluminum doors with plate glass windows flanking, facade features engaged brick buttresses, center pair flank entrance and extend slightly above the peaked parapet, side elevations feature large brick blinds, attached flat roof metal awning wraps building, transom blinds above awning. 5 1012 C
- 1146 2150 OLD SHELL RD c. 1850. Greek Revival, one story, gable roof sides with wings set back, five bay facade, frame, flush boards on facade, recessed porch covers facade and wings, tapered box columns and balustraded, double wood doors with round top panes, transom, French doors with shutters, lattice underpinning, box cornice. Outstanding example of a country Greek Revival residence. 3 1012 C
- 1147 2150 OLD SHELL RD c. 1990. Chevron Filling Station, gas pumps out front under metal flat roofed canopy, convenience store in building, one story, flat roof. 4 1012 N
- 1148 2151 OLD SHELL RD c. 1925. Standard Commercial, one story, flat roof, brick, corner building with series plate glass windows and aluminum entrances, attached flat metal awning covers sidewalk north and east elevations, business signs affixed to wall above awning. 25 1011 C
- 1149 2155 OLD SHELL RD c. 1965. Standard Commercial, two story, brick, flat roof, five bay facade, double wood doors with lunette transom, multi-light windows with shutters on first story, stuccoed arched blinds second story with soldiered borders, multi-light window center second floor, shutters, concrete water table, cornice, raised end walls. 26 1011 N
- 1150 VOID

United States Department of the Interior
National Park Service

National Register Of Historic Places
Continuation Sheet

Section Number 7 Page 136

MID TOWN HISTORIC DISTRICT
Mobile
Mobile County, AL

-
- 1151 2166 OLD SHELL RD c. 1940. Neo-Classical Revival, two story, gable roof sides, brick with frame wing west end, five bay facade, central hall plan, full height two story attached flat roof porch with balustraded roof, Doric columns, ornamental iron work, six panel door with sidelights and fan transom, French doors with transoms and shutters, casement windows at second story with ornamental iron panels in lower half, attached balcony over middle second story bay with ornamental ironwork, box cornice. 2 1012 C
- 1152 2167 OLD SHELL RD c. 1940. Cottage Revival, one story, cross gable, frame, four bay facade, six panel door with bubble awning, casement windows with transoms, louvered vent, stucco chimney with single pot at juncture of wings. 28 1011 C
- 1153 2169 OLD SHELL RD c. 1930. Bungalow, one story, gable roof front, frame, three bay facade, attached, offcenter gable roof porch, paired paneled box columns on brick plinths, Craftsman door, 1/1 windows, knee braces, light in porch gable, louvered vent in main gable, box cornice. 29 1011 C
- 1154 2170 OLD SHELL RD c. 1930. Bungalow, one and a half story, gable roof sides, frame, three bay facade with attached gable wing slightly set back west side, inset porch covers two bays, paneled, boxed columns on brick plinths, screened, casement windows, three dormers with 6/6 windows, exposed rafters. 1 1012 C
- 1155 2175 OLD SHELL RD c. 1940. Minimal Traditional, one story, hip roof, frame, board and batten, four bay facade, inset porch in east bay, square post and balustraded, six panel door in side wall, 9/9 windows with shutters, gable front west bay, center chimney, box cornice, no return. 30 1011 C
- 1156 2179 OLD SHELL RD c. 1945. Minimal Traditional, one story, cross gable, asbestos sided, three bay facade, centered entrance, attached shed roof over stoop with ornamental iron work and drop frieze, chimney west adjacent with corbeled cap, 8/8 windows, box cornice, no return. 31 1011 C
- 1157 2181 OLD SHELL RD c. 1935. Bungalow, one story, cross gable, frame, attached offcenter gable porch, square columns with capitals, balustraded, wood door with window, classical surround, casement windows with shutters over lower half, louvered vents, exposed rafters, attached flat roof carport west side. 32 1011 C
- 1158 2315 OLD SHELL RD c. 1925. Bungalow, one and a half story, gable roof sides, frame, three bay facade with attached one story porches east and west ends, Craftsman door center with sidelights, attached one story gable porch with square posts with capitals, paired 4/1 windows, shed roof dormer with casement windows, exposed rafters, interior chimney. 33 1011 C
- 1159 2317 OLD SHELL RD c. 1925. Bungalow, one story, gable roof front, frame, recessed porch covers facade, paneled, boxed columns on brick plinths, Craftsman door flanked by 6/1 windows, paired 6/1 windows in west bay, knee braces, tripled 4/4 lights in gable, exposed rafters, interior chimney. 34 1011 C

United States Department of the Interior
National Park Service

National Register Of Historic Places
Continuation Sheet

Section Number 7 Page 137

MID TOWN HISTORIC DISTRICT
Mobile
Mobile County, AL

- 1160 2321 OLD SHELL RD c. 1930. Bungalow, originally gas station, one story, gable roof front, brick and stucco, open area infilled for use as an art gallery, plate glass windows and entrance on west side, double wood doors with windows, knee braces, pair louvered vents in gable, exposed rafters. 35 1011 C
- 1161 7 RICKARBY ST c. 1930. Bungalow, one story, gambrel roof front, frame, three bay facade, attached hip roof porch covers facade, box columns and balustraded, six panel door, flanking paired 3/1 windows, louvered vent in gable, exposed rafters. 31 1019 C
- 1162 8 RICKARBY ST c. 1900. Queen Anne, two story, gable roof front, frame, one story gable bay south side facade, shingled gable with louvered vent, 1/1 window with shutters, attached hip roof porch covers rest of facade, turned posts and balustraded, central hall plan, wood door with window, transom, pair 2/2 windows in main gable, louvered vent above, shed roof dormers north and south elevation, box cornice, interior chimney with corbeled cap. 30 1019 C
- 1163 9 RICKARBY ST c. 1900. Victorian Cottage, one and a half story, gable roof front, frame, two bay facade, attached one story hip roof porch covers facade, square brick pillars, probably a later porch, c. 1920, side hall plan, six panel door with sidelights, 1/1 windows with shutters, paired 1/1 windows in gable with shutters, louvered vent, gable roof dormers north and south elevation, box cornice, no return. 32 1019 C
- 1164 10 RICKARBY ST c. 1925. Bungalow, one story, gable roof front, frame, three bay facade, attached, offcenter gable roof porch, box columns with capitals, six panel door, 3/1 windows, purlins, louvered vent in porch gable only, exposed rafters, interior chimney. 29 1019 C
- 1165 11 RICKARBY ST c. 1900. Queen Anne, two story, gambrel roof front, frame, two bay facade, inset porch with bay window south adjacent, tripled Tuscan columns at corner, four panel door with sidelights and transom, 1/1 windows, shingled upper story with tripled 1/1 windows in gable, square light above, box cornice, closed return above windows, shingled upper story flares slightly over first story. 33 1019 C
- 1166 12 RICKARBY ST c. 1920. Vernacular, one and a half story, gable on hip front, frame, three bay facade, inset porch covers two bays, square posts, metal awnings wrap around porch and cover all windows, six panel door with sidelights and transom, paired 1/1 windows, paired 1/1 windows in gable, louvered vent, large shed roof dormers north and south elevations, exposed rafters. 28 1019 C
- 1167 13 RICKARBY ST c. 1930. Bungalow, one story, gable roof front, frame, three bay facade, recessed porch covers facade, box columns and balustraded, central entrance, wood door, 2/2 windows, knee braces, lattice vent in gable, box cornice, no return, two interior chimneys. 34 1019 C
- 1168 14 RICKARBY ST c. 1930. Bungalow, one story, gable roof front, frame, three bay facade, attached, offcenter gable roof porch, battered, boxed columns on brick plinths, six panel door, paired 1/1 windows, louvered vents in gable, exposed rafters, side chimney. 27 1019 C

United States Department of the Interior
National Park Service

National Register Of Historic Places
Continuation Sheet

Section Number 7 Page 138

MID TOWN HISTORIC DISTRICT
Mobile
Mobile County, AL

- 1169 15 RICKARBY ST c. 1950. Minimal Traditional, one story, frame, gable roof sides, two bay facade, attached offcenter gable porch with square posts, six panel door with shutters, 6/6 window, board and batten in gable with louvered vent, box cornice, no return. 35 1019 C
- 1170 16 RICKARBY ST c. 1945. Minimal Traditional, one story, cross gable, ell plan, frame, four bay facade, paired 1/1 windows with shutters in gable, louvered vent, shed roof porch covers three bays, square posts with ornamental iron brackets, balustraded, wood door with window, 1/1 windows, exposed rafters. 26 1019 C
- 1171 18 RICKARBY ST c. 1920. Bungalow, one story, cross gable on hip roof, frame, four bay facade, gable bay front south half facade, 9/1 window with shutters, pent, recessed porch adjacent covers three bays, box columns, balustraded, double Craftsman doors with transom, 9/1 windows with burglar bars, box cornice with slatted soffit for ventilation, end chimney. 25 1019 C
- 1172 19 RICKARBY ST c. 1920. Bungalow, one story, gable roof front, frame, three bay facade, inset porch covers two bays, Craftsman door, paired 9/1 windows, box columns on brick piers, pair six pane lights in gable, knee braces, exposed rafters. 1 1020 C
- 1173 20 RICKARBY ST c. 1940. Vernacular, one story, gable roof sides, frame, recessed porch covers facade, box columns and balustraded, six panel door, multi-light windows, box cornice. 24 1019 C
- 1174 21 RICKARBY ST c. 1910. Working Man's Foursquare, one story, hip roof, frame, three bay facade, inset porch covers two bays, paneled box columns with capitals, balustraded, four panel door with sidelights and transom, paired 1/1 windows, hip roof dormer with horizontal light, box cornice. 2 1020 C
- 1175 22 RICKARBY ST c. 1910/1925. Vernacular/Bungalow, appears to be two houses joined, north building a one story, frame, gable roof front, two bay Bungalow with recessed porch, box battered columns on brick plinths and balustraded, six panel door with transom, 2/2 window, exposed rafters, south building which abutts is one story, frame, gable roof front, two bays, pair 2/2 windows with shutters, box cornice, closed return, no entrance. 23 1019 C
- 1176 51 RICKARBY ST c. 1940. Colonial Revival, two story, hip roof, brick, three bay facade, slightly offcenter entrance, six panel door within slightly battered classical surround, paired 6/6 windows north adjacent, 6/6 windows with shutters above, lunette louvered vent in roof above, box cornice, one story hip wing south side. 3 1020 C
- 1177 52 RICKARBY ST c. 1940. Minimal Traditional, two story, hip roof, frame, three bay facade, centered entrance, six panel door with transom, attached one story hip roof porch with square posts with capitals, flanked by 8/8 windows with shutters, large central chimney on roof crest, second story windows 6/6 with shutters, hip two story wing north end. 22 1019 C

20 8
1020

United States Department of the Interior
National Park Service

National Register Of Historic Places
Continuation Sheet

Section Number 7 Page 139

MID TOWN HISTORIC DISTRICT
Mobile
Mobile County, AL

- 1178 54 RICKARBY ST 1843. Carlen House, NR 1981, Museum, Gulf Coast Cottage, one and a half story, gable roof sides, frame, five bay facade, recessed porch covers facade, box columns with capitals, balustraded, four panel door with sidelights and transom, central hall plan with reverse stairway, 6/6 windows, box cornice, closed return, single gable dormer at rear. This house was originally the seat of a twenty acre farm owned by Michael Carlen. One of the earliest houses in the district. 21 1019 C
- 1179 253 SEMINOLE ST c. 1950. Minimal Traditional, one story, gable roof sides, brick, three bay facade, centered entrance, attached gable porch at center bay, ornamental iron supports, metal casement windows, louvered vent, box cornice, no return. 6 1034 C
- 1180 255 SEMINOLE ST c. 1955. Minimal Traditional, one story, gable roof sides, vinyl sided, four bay facade, attached gable with ornamental iron supports over stoop, paired 3/1 windows, box cornice, no return. 5 1034 N
- 1181 257 SEMINOLE ST c. 1945. Minimal Traditional, one story, cross gable, frame, three bay facade, centered entrance in gable, six panel door with attached gable on paired wall brackets, chimney with single rounded shoulder north adjacent, paired 6/1 windows, box cornice, no return. 4 1034 C
- 1182 259 SEMINOLE ST c. 1945. Minimal Traditional, one story, frame, cross gable, three bay facade, centered entrance, attached gable on wall brackets over stoop, engaged pilasters, door obscured by burglar door, paired 3/1 windows, south bay an infilled porch with glass and ornamental iron railing, clapboarded corner pillar, round top vent in main gable, exposed rafters, end chimney. 3 1034 C
- 1183 261 SEMINOLE ST c. 1940. Cottage Revival, one story, cross gable, brick and frame, three bay facade, centered entrance, six panel door, attached gable on wide brick supports over stoop, arched opening, chimney north adjacent, paired 6/6 windows, south bay an infilled porch with clapboards and aluminum windows, corner brick pillar, exposed rafters. 2 1034 C
- 1184 263 SEMINOLE ST c. 1940. Minimal Traditional, one and a half story, gable roof sides, vinyl sided, three bay facade, centered entrance, wood door with attached gable over stoop, brick with arched opening, tripled horizontal windows south adjacent, casement windows north adjacent with metal awning, large gable dormer above with bank of windows obscured by metal awning, louvered vent, box cornice, no return. 1 1034 C
- 1185 265 SEMINOLE ST c. 1930. Bungalow, two story, frame, cross gable, ell plan, three bay facade, inset porch first story cross gable, brick pillars, screened, entrance in north bay, wood door with three stepped lights, attached gable with wall brackets over stoop, metal awnings obscure windows, louvered vent, box cornice, no return. 35 1033 C
- 1186 51 SILVERWOOD c. 1940. Minimal Traditional, two story, cross gable, asbestos sided, four bay facade, two story gable at facade with inset porches first and second floors, square posts, x railing second story, screened first and second story, entrance six panel door adjacent porch with metal awning, lunette louvered vent in gable, paired 6/6 windows, box cornice, no return, end chimney. 6 1043 C

United States Department of the Interior
National Park Service

National Register Of Historic Places
Continuation Sheet

Section Number 7 Page 140

MID TOWN HISTORIC DISTRICT
Mobile
Mobile County, AL

- 1187 52 SILVERWOOD c. 1945. Minimal Traditional, one story, hip roof, brick, two bay facade, offset hip porch with round columns, six panel door, picture window with flanking 6/6 windows, box cornice, hip offset wing north front with paired 6/1 windows. 7 1043 C
- 1188 53 SILVERWOOD c. 1925. Bungalow, one story, gable on hip front, frame, three bay facade, recessed porch covers facade, square brick pillars on brick plinths, gable over steps, porte-cochere north side, six panel door, flanking multi-light windows with transoms, louvered vent, purlins, exposed rafters. 5 1043 C
- 1189 54 SILVERWOOD c. 1930. English Cottage Revival, one story, cross gable, brick, four bay facade, Tudor style door in small brick gable with round top and transom, casement windows, round top vent in main gable, box cornice, closed return. 8 1043 C
- 1190 55 SILVERWOOD c. 1940. Minimal Traditional, one story, cross gable, frame, three bay facade, centered entrance, six panel door, attached gable with brick arched opening at entrance, small gable over south bay with a round top light, south bay features paired multi-light windows with shutters, north bay brick with arched top casement windows, box cornice, no return. 4 1043 C
- 1191 56 SILVERWOOD c. 1935. Cottage Revival, one story, cross gable, brick, three bay facade, ell plan, front gable has battered sides and slightly flared eaves, wood door with burglar door and bubble fabric awning, arch top window north adjacent, battered chimney at juncture with facade, paired 3/1 windows, exposed rafters. 9 1043 C
- 1192 57 SILVERWOOD c. 1925. Bungalow, one story, gable roof front, frame, three bay facade, attached offcenter gable porch with square brick pillars and screened, paired 3/1 windows with shutters, knee braces, paired small windows in porch gable, exposed rafters, side chimney in side gable. 3 1043 C
- 1193 58 SILVERWOOD c. 1925. Bungalow, one story, cross gable, frame, three bay facade, attached offcenter gable porch with pierced brick columns, six panel door, 3/1 windows, porte-cochere north side, louvered vent, end chimney, exposed rafters. 10 1043 C
- 1194 59 SILVERWOOD c. 1925. Bungalow, one story, gable on hip, frame, three bay facade, front gable offset and two bays, wood door with small window, bubble fabric awning, paired Craftsman windows with shutters, louvered vent, exposed rafters, interior chimney. 2 1043 C
- 1195 60 SILVERWOOD c. 1930. Bungalow, one story, gable roof front, aluminum sided, attached offcenter gable porch with square brick pillars, door obscured by screen door, paired 3/1 windows with shutters, knee braces, exposed rafters. 11 1043 C

cb 9

220

United States Department of the Interior
National Park Service

National Register Of Historic Places
Continuation Sheet

Section Number 7 Page 141

MID TOWN HISTORIC DISTRICT
Mobile
Mobile County, AL

- 1196 61 SILVERWOOD c. 1930. Minimal Traditional, one story, cross gable, frame, ell plan, four bay facade, chimney at front gable, stucco with double shoulders accented by red brick, peaked cap accented by red brick, round top casement windows flank chimney, six panel door, attached gable over stoop with square posts with braces, gables have slightly flared sides, casement windows in north bay, box cornice, no return. 1 1043 C
- 1197 62 SILVERWOOD c. 1925. English Cottage Revival, one story, cross gable, brick, staggered gables at facade, secondary one larger with sweeping roofline to south, entrance in smaller gable, round top wood door, arch brick corbels surround, metal casement windows north adjacent, tripled sash south adjacent, box cornice no return. 12 1043 C
- 1198 63 SILVERWOOD c. 1925. Bungalow, one and a half story, gable roof sides, frame, three bay facade, kick-off shed roof porch covers facade, paired massive battered columns at corners on brick plinths, six panel door, windows are tripled, 6/1 in center with flanking 4/1, large gable dormer with tripled 6/6 windows, knee braces, exposed rafters, side chimney. 35 1042 C
- 1199 64 SILVERWOOD c. 1925. Bungalow, one story, gable roof sides, frame, three bay facade,, recessed porch covers facade, square brick pillars, pair gables at porch eave line, each over an arched brick opening, six panel door flanked by tripled Craftsman windows, wide fascia obscures exposed rafters. 13 1043 C
- 1200 65 SILVERWOOD c. 1950. Minimal Traditional, one story, gable on hip front, brick, three bay facade, centered entrance, attached gable over stoop, ornamental iron work, picture window south adjacent, ornamental iron rail over lower half of window, louvered vent in main gable, box cornice, no return, side chimney. 34 1042 C
- 1201 66 SILVERWOOD c. 1925. Bungalow, one story, gable roof sides, stucco, three bay facade, recessed porch covers facade, gable over steps, niche either side of steps, accented red brick in arched opening and along wing wall south adjacent and string course across facade, porch north of gable screened, paired 3/1 windows, knee braces, exposed rafters, end chimney. 14 1043 C
- 1202 67 SILVERWOOD c. 1925. Bungalow, one story, hip roof, brick, three bay facade, attached offcenter hip roof porch with gable over steps, square brick pillars, six panel door with flanking paired 3/1 windows, knee braces, exposed rafters, side chimney. 33 1042 C
- 1203 68 SILVERWOOD c. 1925. Minimal Traditional, one story, cross gables, ell plan, three bay facade, frame, staggered gables at facade, entrance at juncture with facade, six panel door with metal awning above, tripled 6/1 windows in gable, paired north adjacent, triangular louvered dormer above, no eave. 15 1043 C
- 1204 69 SILVERWOOD c. 1925. Bungalow, one story, cross gable, frame, three bay facade,, recessed porch covers facade, battered brick supports on brick plinths, six panel door with flanking 3/1 windows, gable over steps, purlins, exposed rafters, end chimney. 32 1042 C

United States Department of the Interior
National Park Service

National Register Of Historic Places
Continuation Sheet

Section Number 7 Page 142

MID TOWN HISTORIC DISTRICT
Mobile
Mobile County, AL

- 1205 71 SILVERWOOD c. 1945. Minimal Traditional, one story, cross gable, frame, three bay facade, centered entrance, attached gable over stoop with brick surround and arched opening, paired 6/1 windows south adjacent, infilled porch north adjacent, aluminum windows, round top louvered vent, box cornice, no return. 31 1042 C
- 1206 120 SILVERWOOD c. 1930. Bungalow, one story, gable on hip roof, vinyl sided, three bay facade, recessed porch covers facade, square stucco pillars, gable over steps, bubble awning, porch infilled with clapboards and glass, purlins, exposed rafters. 16 1043 C
- 1207 122 SILVERWOOD c. 1930. Bungalow, one story, hip roof, vinyl sided, five bay facade, attached hip roof porch covers three bays, square posts, screened, 3/1 windows, door not visible, fascia obscures rafters. 17 1043 C
- 1208 123 SILVERWOOD c. 1930. Bungalow, one story, cross gable, frame, ell plan, three bay facade, six panel door with gable on square posts over stoop, tripled 3/1 windows, exposed rafters. 30 1042 C
- 1209 124 SILVERWOOD c. 1940. Minimal Traditional, one story, gable roof sides, frame, three bay facade, central entrance, six panel door slightly inset, gable above, tripled multi-light windows either side, box cornice, end chimney. 18 1043 C
- 1210 125 SILVERWOOD c. 1940. Bungalow, one story, gable roof sides, frame, three bay facade, inset porch covers two bays, paired square posts with unifying capitals, six panel entrance south bay, paired 6/6 windows, exposed rafters. 29 1042 C
- 1211 126 SILVERWOOD c. 1940. Minimal Traditional, one and a half story, gable roof sides, frame, three bay facade, centered entrance, six panel door, attached gable over stoop with square posts, paired 6/6 windows north adjacent, tripled multi-pane sash south adjacent, pair gable dormers with six light windows, box cornice, no return. 19 1043 C
- 1212 127 SILVERWOOD c. 1925. English Cottage Revival, one story, cross gable, ell plan, frame, four bay facade, double shoulder stucco chimney with arched motif on face at facade, flanked by round topped casement windows, gable roof sweeps north over entrance, supported by ornamental iron work, six panel door, box cornice, no return. 28 1042 C
- 1213 128 SILVERWOOD c. 1940. Minimal Traditional, one story, gable roof sides, frame, three bay facade, centered entrance, six panel door with attached hip roof over stoop on open wood columns with x patterns, flanked by tripled multi-light windows with fabric awnings, end chimney, box cornice, no return. 20 1043 C

United States Department of the Interior
National Park Service

National Register Of Historic Places
Continuation Sheet

Section Number 7 Page 143

MID TOWN HISTORIC DISTRICT
Mobile
Mobile County, AL

- 1214 129 SILVERWOOD c. 1925. Bungalow, one and a half story, gable roof sides, frame, three bay facade, recessed porch covers facade, corners supported by massive stucco pillars with accented capitals, slender battered columns each side of steps, door with nine lights, flanked by paired 3/1 windows, gable dormer with horizontal light, knee braces, exposed rafters. 27 1042 C
- 1215 130 SILVERWOOD c. 1925. Colonial Revival, one story, hip roof, brick, five bay facade, attached gable porch covers three bays, slender Ionic columns, six panel door with transom with diamond muntin pattern, flanked by 6/1 windows with transom with diamond muntin patterns, end bays feature paired 6/1 windows with transoms with diamond muntin patterns, dentil course around house and gable, lunette louvered vent, clapboarded gable, gable ell rear. 21 1043 C
- 1216 131 SILVERWOOD c. 1925. Bungalow, one story, gable roof front, frame, three bay facade, recessed porch covers facade, pierced brick columns, Craftsman door with sidelights, flanked by paired 3/1 windows, louvered vents, exposed rafters, side chimney and interior chimney. 26 1042 C
- 1217 132 SILVERWOOD c. 1930. Minimal Traditional, one story, gable roof sides, frame, three bay facade, centered entrance, six panel door, attached gable over stoop with slender square paired posts, paired 6/1 windows with shutters flank entrance, end chimney, exposed rafters. 22 1043 C
- 1218 133 SILVERWOOD c. 1925. Bungalow, one story, staggered gables front, frame, three bay facade, attached shed roof porch abutts staggered gable, square brick pillars, balustrades added later, chimney at front gable has double shoulders high up the stack, flanked by tripled 4/1 windows, north set have shed roof across the tops, flanking louvered vents in gable, knee braces, exposed rafters, door obscured by screen. 25 1042 C
- 1219 134 SILVERWOOD c. 1925. English Cottage Revival, one and a half story, frame, cross gable, ell plan, recessed porch covers two of three bays, square brick pillar, screened, round top wooden door set in gable frame with round top brick surround, tripled Tudor windows in gable south adjacent, gable dormer with extended roof, round top casement window with diamond muntins, exposed rafters. 23 1043 C
- 1220 135 SILVERWOOD c. 1925. Bungalow, one and a half story, gable roof sides, frame, three bay facade, recessed porch covers facade, Tuscan columns, six panel door flanked by paired 3/1 windows, gable dormer with tripled Craftsman windows, knee braces, exposed rafters, end chimney. 24 1042 C
- 1221 136 SILVERWOOD c. 1940. Minimal Traditional, one and a half story, gable roof sides, frame, three bay facade, attached offcenter gable with entrance, round top door with bubble awning, brick face surround, paired 3/1 windows with shutters either side, exposed rafters. 24 1043 C
- 1222 137 SILVERWOOD c. 1925. Bungalow, one story, gable roof sides, frame, attached offcenter hip roof porch with gable over steps, square brick pillars, infilled to north with aluminum windows, six panel door with sidelights and transom, tripled multi-light lights in south bay, exposed rafters, end chimney. 23 1042 C

United States Department of the Interior
National Park Service

National Register Of Historic Places
Continuation Sheet

Section Number 7 Page 144

MID TOWN HISTORIC DISTRICT
Mobile
Mobile County, AL

- 1223 VOID
- 1224 139 SILVERWOOD c. 1925. English Cottage Revival, one story, cross gable, brick, four bay facade, centered gable with round top wooden door, flat roof above with ornamental iron supports and cresting, round top niche north adjacent, chimney at rear of this gable up front wall, round top casement windows north bay, casement windows south bay, box cornice, no return. 22 1042 C
- 1225 140 SILVERWOOD c. 1945. Minimal Traditional, one story, gable roof sides, aluminum sided, four bay facade, six panel door, attached gable over stoop, ornamental iron supports, tripled multi-light windows flank entrance, north bay obscured by metal awnings at facade and north elevation, interior ridge chimney. 26 1043 C
- 1226 141 SILVERWOOD c. 1940. English Cottage Revival, one story, cross gable, three bay facade, brick, centered entrance in gable, round top door with bubble awning, chimney south adjacent, 6/6 window with shutters in south bay, arched top window north bay with shutters, round top louvered vent in gable, box cornice, no return. 21 1042 C
- 1227 143 SILVERWOOD c. 1940. English Cottage Revival, one story, cross gable, frame, three bay facade, attached offcenter gable with two bays, round top wooden door with accented trim, inset porch with arched opening, round top louvered vent, paired 6/6 windows, chimney at facade where gable joins wall, exposed rafters, fascia ends cut in simple pattern. 20 1042 C
- 1228 145 SILVERWOOD c. 1945. Minimal Traditional, one story, gable roof sides, brick, five bay facade with gable wings north and south of one bay each, wood door with three lights across top, ornamental iron screen, set in classical surround within a brick gable, 6/6 windows with shutters, interior chimney, box cornice, no return. 19 1042 C
- 1229 10 SOUTH ST c. 1940. Minimal Traditional, one story, gable roof sides, brick, three bay facade, six panel door, tripled 6/6 windows in north bay, arched window south bay, attached brick porch with gable at stoop, end chimney, box cornice, no return. 8 1019 C
- 1230 11 SOUTH ST c. 1925. Bungalow, one story, hip roof, brick, three bay facade, centered entrance, multi-light door with sidelights and fan transom, flanking tripled 1/1 windows, attached gable over stoop with Tuscan columns, large triangular louvered vent, exposed rafters. 19 1019 C
- 1231 12 SOUTH ST c. 1940. Minimal Traditional, one story, cross gable, ell plan, brick, four bay facade, six panel door, 6/6 windows with shutters, louvered vent, box cornice, closed return, interior chimney. 7 1019 C

United States Department of the Interior
National Park Service

National Register Of Historic Places
Continuation Sheet

Section Number 7 Page 145

MID TOWN HISTORIC DISTRICT
Mobile
Mobile County, AL

- 1232 13 SOUTH ST c. 1925. Bungalow, one story, hip roof, frame, three bay facade, attached gable porch covers most of facade, battered box columns on brick plinths, balustraded, centered entrance, six panel door with sidelights and transom, flanking 1/1 windows, louvered vent in gable with shutters added, knee braces, exposed rafters, pair side chimneys. 10 1019 C
- 1233 14 SOUTH ST c. 1920. Bungalow, one story, gambrel roof front, frame, three bay facade, attached offcenter gambrel porch with pierced brick columns, Craftsman door with flanking paired 3/1 windows, louvered vent, knee braces, exposed rafters, interior chimney. 6 1019 C
- 1234 15 SOUTH ST c. 1925. Bungalow, one story, gable roof sides, frame, four bay facade, attached offcenter gable porch covers three bays,, battered, boxed columns on brick plinths, balustraded, six panel door, 4/1 windows, casement windows in south bay, shingled gable, knee braces, exposed rafters, side chimney with pot. 11 1019 C
- 1235 16 SOUTH ST c. 1920. Bungalow, one story, gable roof front, frame, three bay facade, recessed porch covers facade, paired square posts on brick plinths, Craftsman door with flanking paired 6/1 windows, dentil course, louvered vent, knee braces, exposed ornamental truss in gable, exposed rafters, side chimney. 5 1019 C
- 1236 17 SOUTH ST c. 1925. Bungalow, one story, gable roof front, vinyl sided, three bay facade, recessed porch covers facade, battered, boxed columns on brick plinths, Craftsman door, casement windows, louvered vent in gable, knee braces, chimney north side. 12 1019 C
- 1237 18 SOUTH ST 1916. Bungalow, one and a half story, gable roof sides, frame, three bay facade, centered entrance, Craftsman door with multi-light sidelights and transom, French doors with transom north bay, recessed porch covers facade, south bay infilled with casement windows with transoms, square brick pillars, shed roof dormer with four 6/1 windows, interior chimney, exposed rafters. 4 1019 C
- 1238 19 SOUTH ST c. 1925. Bungalow, one and a half story, gable roof front, vinyl sided, three bay facade, attached one story hip roof porch covers facade, paired square posts on brick plinths, balustraded, Craftsman door, paired 1/1 windows, knee braces, paired aluminum windows in gable, shed roof dormers north and south elevations. 13 1019 C
- 1239 20 SOUTH ST c. 1925. Bungalow, one and a half story, hip roof, frame, two bay facade, recessed porch covers facade, square brick pillars, Craftsman door with sidelights, paired 3/1 windows, hip roof clerestory with casement windows, exposed rafters. 3 1019 C
- 1240 21 SOUTH ST c. 1925. Bungalow, one story, gable roof front, frame, three bay facade, offcenter gable bay with bank casement windows, attached hip roof porch adjacent with paneled box column on brick plinth, Craftsman entrance, paired 1/1 windows north adjacent, louvered vents in both gables, knee braces, exposed rafters, one interior chimney, two exterior chimneys. 14 1019 C

United States Department of the Interior
National Park Service

National Register Of Historic Places
Continuation Sheet

Section Number 7 Page 146

MID TOWN HISTORIC DISTRICT
Mobile
Mobile County, AL

- 1241 23 SOUTH ST c. 1925. Bungalow, one and a half story, hip roof, frame,, recessed porch covers facade, infilled with board and batten, door at north end, square brick pillars, paired 3/1 windows on side elevations, hip roof dormer with Craftsman window, exposed rafters. 15 1019 C
- 1242 24 SOUTH ST c. 1925. Bungalow, one story, gable roof sides, frame, three bay facade, recessed porch covers facade, paired square posts on stucco plinths, six panel door with Craftsman sidelights, flanked by paired 1/1 windows, exposed rafters. 2 1019 C
- 1243 25 SOUTH ST c. 1925. Bungalow, one story, gable roof front, frame, three bay facade, recessed porch covers facade, box columns on brick plinths, six panel door flanked by paired Craftsman windows, vertical six pane light in gable with flanking louveres, exposed rafters. 16 1019 C
- 1244 26 SOUTH ST c. 1925. Bungalow, one story, gable roof front, frame, two bay facade, recessed porch covers facade, ornamental concrete block corner pillars and foundation, six panel door with Craftsman sidelights, paired Craftsman windows, dentil course, louvered vent, knee braces, exposed rafters. 1 1019 C
- 1245 28 SOUTH ST c. 1925. Bungalow, one story, gable roof front, frame, recessed porch covers facade, square posts on brick plinths, six panel door, tripled 3/1 windows north adjacent, modified Palladian window/vent in gable, knee braces, exposed rafters. 35 1018 C
- 1246 30 SOUTH ST c. 1960. Minimal Traditional, two and a half story, brick, hip roof, three bay facade, centered entrance, six panel door, attached hip one story porch with ornamental iron supports, 6/6 aluminum windows with shutters, box cornice. 34 1018 N
- 1247 32 SOUTH ST c. 1970. Ranch Style, one story, gable roof sides, brick, three bay facade, centered entrance, six panel door, aluminum 6/6 windows, board and batten gables, box cornice. 33 1018 N
- 1248 34 SOUTH ST c. 1965. Ranch Style, hip roof, brick, two bay facade, inset side porch with attached gable over stoop, ornamental iron supports, triangular louvered vent, metal casement windows, box cornice. 32 1018 N
- 1249 36 SOUTH ST c. 1970. Ranch Style, one story, hip roof, brick, three bay facade, centered entrance, six panel door, attached gable over stoop on ornamental iron supports, aluminum windows, box cornice. 31 1018 N

06 5
100

United States Department of the Interior
National Park Service

National Register Of Historic Places
Continuation Sheet

Section Number 7 Page 147

MID TOWN HISTORIC DISTRICT
Mobile
Mobile County, AL

- 1250 108 SOUTH ST c. 1925. Bungalow, one story, gable off hip roof front, frame, three bay facade, attached offcenter gable porch with square brick pillars, ornamental iron supports flank brick supports, ornamental iron railing, round top door with fan light, paired 6/1 windows south adjacent door, casement windows in south bay, porte-cochere north elevation, knee braces, triangular louvered vents, exposed rafters. 30 1018 C
- 1251 110 SOUTH ST c. 1960. Minimal Traditional, one story, gable roof sides, vinyl sided, three bay facade, centered entrance, six panel door, attached gable over stoop with ornamental iron supports, paired 6/6 aluminum windows with shutters, box cornice, no return. 29 1018 N
- 1252 112 SOUTH ST c. 1940. Minimal Traditional, one story, cross gable, aluminum sided, four bay facade, entrance in north bay, round top door set in two bay front facing gable, round top multi-light window center of gable, single shoulder chimney south adjacent, inset porch south bay, screened with iron railing, fabric awning, gable dormer with paired 6/6 windows, box cornice, no return. 28 1018 C
- 1253 114 SOUTH ST c. 1940. Minimal Traditional, one story, cross gable, vinyl sided, three bay facade, centered entrance, wood door in brick surround, paired 6/6 windows south bay have infilled the inset porch, square brick pillars, chimney with sloping sides at facade, box cornice, no return. 27 1018 C
- 1254 118 SOUTH ST c. 1940. Minimal Traditional, one story, cross gable, ell plan, frame, three bay facade, gable offcenter porch infilled with board and batten and aluminum windows, corner brick pillars, paired 3/1 windows with shutters, end chimney, exposed rafters, large triangular vent in front gable. 26 1018 C
- 1255 122 SOUTH ST c. 1940. Minimal Traditional, one story, gable roof sides, vinyl sided, three bay facade, centered round top door, attached gable with brick arched opening, arch accented by double row of headers, flanking picture windows with shutters, end chimney, box cornice, closed return. 25 1018 C
- 1256 124 SOUTH ST c. 1950. Minimal Traditional, one story, cross gable, brick, three bay facade, centered entrance inset, ornamental iron posts, six panel door, paired 8/8 windows with shutters in north bay, board and batten gable with scalloped lower border, triangular louvered vent, end chimney, box cornice, no return. 24 1018 C
- 1257 128 SOUTH ST 1938. FHA House, C. L. Hutchisson, Jr. architect, Colonial Revival, two story, hip roof, brick, three bays, side entrance, wood door with sidelights and small metal awning over stoop, small wrought iron ornamental balcony above, 6/6 windows with shutters and jibbed lower panels, second story features unusual 6/6 windows with arched tops which punch through the eave line, side chimney with corbeled cap, box cornice. 23 1018 C
- 1258 150 SOUTH ST c. 1930. Minimal Traditional, one story, gable roof front, brick, three bay facade, centered entrance, nonhistoric wood door with three lights, flat roof boxed roof over stoop, paired 6/1 windows north adjacent, inset porch in south bay, arched openings facade and south elevation, screened, triangular louvered vent, no cornice. 22 1018 C

United States Department of the Interior
National Park Service

National Register Of Historic Places
Continuation Sheet

Section Number 7 Page 148

MID TOWN HISTORIC DISTRICT
Mobile
Mobile County, AL

- 1259 152 SOUTH ST c. 1930. Dutch Colonial Revival, one and a half story, gambrel roof sides, frame, three bay facade, centered entrance, wood door in classical surround, flanking 8/8 windows with shutters, large three bay shed roof dormer above with 8/8 windows with shutters, attached one story hip roof porch south elevation, Tuscan columns, balustraded, end chimney, box cornice, no return. 21 1018 C
- 1260 156 SOUTH ST c. 1940. Colonial Revival, two story, gable roof sides, brick, three bay facade, centered entrance, six panel door with classical surround, attached gable over stoop with Tuscan columns, 8/8 windows with shutters, 6/6 window with shutters center bay second story, box cornice, no return. 20 1018 C
- 1261 160 SOUTH ST c. 1940. Gulf Coast Cottage, one and a half story, gable roof sides, frame, three bay facade, recessed porch covers facade, Tuscan columns, x pattern railing, six panel door with sidelights, 8/8 windows with shutters, three gable dormers with 6/6 windows, end chimney, box cornice, no return. 19 1018 C
- 1262 162 SOUTH ST c. 1940. Minimal Traditional, one story, gable roof sides, asbestos sided, four bay facade, attached gable over stoop, paired square posts, six panel door, 8/8 windows with shutters, end chimney, no cornice. 18 1018 C
- 1263 164 SOUTH ST c. 1945. Minimal Traditional, one story, cross gable, ell plan, frame, four bay facade, double shoulder brick chimney center of front gable, flanked by 6/6 windows with shutters, door obscured by ornamental burglar door, ornamental iron support and cresting on flat roof over stoop, box cornice, no return. 17 1018 C
- 1264 166 SOUTH ST c. 1940. Colonial Revival, one and a half story, gable roof sides, frame, five bay facade, centered entrance, six panel door with classical surround and small gable with dentil work above, 6/6 windows with shutters, ornamental iron panels below sash, pair gable dormers with 6/6 windows, attached one story flat roof sun porch south end, metal casement windows, balustrade around roofline, chimney between sun porch and main house, dentil course runs facade, box cornice, no return. 16 1018 C
- 1265 168 SOUTH ST c. 1940. Minimal Traditional, one story, gable sides, frame, five bay facade, gable offcenter south, attached flat roof over stoop, square posts, six panel door, paired 6/6 windows with shutters, round top light in gable, interior chimney, box cornice, no return. 15 1018 C
- 1266 180 SOUTH ST c. 1940. English Cottage Revival, one story, cross gable, H form, brick, five bay facade, Tudor bay with diamond lights in south gable, small 3/1 window above, two sets paired 6/1 windows center of facade, entrance in north gable, round top wooden door, separate entrance in gable at south elevation, side chimney, no cornice. 14 1018 C
- 1267 181 SOUTH ST c. 1940. Minimal Traditional, one and a half story, gable roof sides, brick, four bay facade, six panel door, attached frame gable with ornamental iron supports, 6/6 windows with shutters, ornamental iron burglar bars at lower half of sash, pair gable dormers with 6/6 windows, exposed rafters. 17 1019 C

United States Department of the Interior
National Park Service

National Register Of Historic Places
Continuation Sheet

Section Number 7 Page 149

MID TOWN HISTORIC DISTRICT
Mobile
Mobile County, AL

- 1268 182 SOUTH ST c. 1940. Minimal Traditional, one story, gable roof sides, frame, three bay facade, centered entrance, door with three lights, screen, attached gable over stoop with ornamental iron supports, paired 6/6 windows north bay with metal awning, inset porch south bay with paired square posts, screened, ornamental iron railing, metal awning which wraps around to south elevation, box cornice, no return, end chimney. 13 1018 C
- 1269 183 SOUTH ST c. 1930. English Cottage Revival, one and a half story, cross gable, ell plan, brick, three bay facade, centered entrance, wood door with diamond window, bubble awning, tripled 6/1 windows north adjacent, round topped window in gable, inset porch south bay, arched openings are screened, arches accented with headers, box cornice, no return. 18 1019 C
- 1270 185 SOUTH ST c. 1940. Minimal Traditional, one story, gable roof sides, vinyl sided, three bay facade, centered entrance, six panel door with attached gable surround, paired 8/8 windows north bay, bank four single pane windows south bay, box cornice, no return, end chimney. 19 1019 C
- 1271 186 SOUTH ST c. 1940. English Cottage Revival, one story, gable roof sides, brick, three bay facade, centered entrance, round top wooden door, attached gable with arched openings in three sides, arches accented by double row of headers, soldier course above, chimney north adjacent, casement window in north bay, arched openings infilled with tinted glass south bay and south elevation, arches accented with double row of headers, round top louvered vents in gable, hip roof garage at rear, no cornice. 12 1018 C
- 1272 188 SOUTH ST 1938. FHA House, C. L. Hutchisson, Jr. architect, English Cottage Revival, one story, cross gable, frame, three bay facade, entrance in offcenter gable with single shoulder chimney adjacent, round top door with screen, small window in gable with diamond muntins, tripled Tudor windows center bay, gable dormer with window with diamond muntins, no cornice. 11 1018 C
- 1273 191 SOUTH ST c. 1940. Minimal Traditional, one story, frame, gable sides, four bay facade, six panel door with sidelights and fan transom, attached gable over stoop with fluted Doric columns, paired 6/1 windows flank entrance, south bay an inset, screened porch with ornamental iron railing, box cornice, no return. 20 1019 C
- 1274 1805 SPRINGHILL AVE c. 1920. Bungalow, one story, cross gable on hip, ceramic tile roof, stucco, two bay facade, attached offcenter porch with arched opening accented by coping, wood door with window, sidelights and fan transom, unroofed patio east adjacent with stone balustrade, casement windows, attached gable porch east elevation, modified Palladian light in gable, knee braces, exposed rafters, interior chimney. 24 1012 C
- 1275 1809 SPRINGHILL AVE c. 1910. Bungalow, two and a half story, hip roof, vinyl sided, five bay facade, central entrance, wood door with sidelights and transom, 6/1 windows, attached one story hip roof porch covers three bays, box columns on stucco plinths, hip roof dormer with six pane light, box cornice, two interior chimneys. 25 1012 C
- 1276 1811 SPRINGHILL AVE c. 1920. Bungalow, one story, hip roof, brick, three bay facade, attached offcenter gable porch with arched openings accented by white stucco pillars and coping along arches, Craftsman door in center bay with sidelights and transom, flanked by casement windows with arched transoms, purlins, lunette light in gable, exposed rafters. 26 1012 C

United States Department of the Interior
National Park Service

National Register Of Historic Places
Continuation Sheet

Section Number 7 Page 150

MID TOWN HISTORIC DISTRICT
Mobile
Mobile County, AL

1277 VOID

- 1278 1851 SPRINGHILL AVE c. 1925. Spanish Colonial Revival, two story, hip roof of ceramic clay tile, three bay facade with one story porte-cochere east side and two story set back wing west side, stucco, three bay facade, round top wood door, attached one story gable over stoop on Tuscan columns on ornamental concrete block plinths, arched top, paired 6/6 windows, balustrade over porte-cochere, exposed rafters, one story garage rear of property with stucco walls and ceramic tile hip roof, wooden doors in auto bay. 28 1012 C
- 1279 1855 SPRINGHILL AVE c. 1980. Colonial Revival, two story hip roof, brick central section of four bays with attached one story hip wings of two bays each, each end, 6/6 windows with shutters, entrance in west end, box cornice. 29 1012 N
- 1280 1901 SPRINGHILL AVE c. 1985. Modern Commercial, one and a half story, gable roof sides, brick, bank plate glass windows along street, shed roof dormer offcenter in roofline runs about half the length of building. 30 1012 N
- 1281 1903 SPRINGHILL AVE c. 1920. Bungalow, one and a half story, cross gable on hip, frame, attached shed roof porch abutts gable front and becomes a porte-cochere on east side, square brick pillars, infilled with glass and wood door with sidelights, 2/2 windows, paired four pane lights in gable, box cornice, closed return, interior chimney. 31 1012 C
- 1282 1951 SPRINGHILL AVE 1897. Touart House, Neo-Classical Revival, one story, hip roof, three bay facade with attached wings east and west rear, recessed porch covers facade, paneled boxed columns and balustraded, wings feature recessed porches with same details, double front doors, multi-light with fan transom, 6/6 windows with shutters, interior chimney with corbeled cap, box cornice, original estate covered entire block between Springhill Ave. and Old Shell, Margaret Street named for original owner's wife. 32 1012 C
- 1283 1955 SPRINGHILL AVE c. 1910. Neo-Classical Revival, two story, hip roof, frame, three bay facade, recessed porch covers facade, full height paneled box columns, wood door with window, sidelights and transom, balcony above at center bay on brackets, ornamental ironwork, 1/1 windows, box cornice, interior chimney. 33 1012 C
- 1284 1957 SPRINGHILL AVE c. 1950. Minimal Traditional, one story, gable roof front, brick, two bay facade, inset corner porch with arched opening, door around side, paired 3/1 windows with burglar bars, louvered vent, box cornice, closed return. 34 1012 C
- 1285 1959 SPRINGHILL AVE c. 1925. Bungalow, one story, gable roof front, frame, three bay facade, recessed porch covers facade, tripled square posts each corner on brick knee wall, Craftsman door with sidelights, casement window east bay and Craftsman window in west bay, pair Craftsman lights in gable, knee braces, exposed rafters. 35 1012 C

United States Department of the Interior
National Park Service

National Register Of Historic Places
Continuation Sheet

Section Number 7 Page 151

MID TOWN HISTORIC DISTRICT
Mobile
Mobile County, AL

- 1286 2059 SPRINGHILL AVE 1937. Summerville Court Apartments, part of 22 building complex, two story, cross hip roof, H plan, brick, seven bays, centered entrance, wood door with six lights, classical surround, 8/8 windows and 6/6 windows in cross bays, lunette louvered vents in roof, inset two story porch rear elevation in center bay, box cornice. 28 1038 C
- 1287 160 STONEWALL PL c. 1965. Modern apartments, one of four identical buildings, two story, gable roof sides, brick, corners feature narrow, elongated, brick quoins, five bay facade, central entrance, wooden door with horizontal lights, sidelights, banks tripled aluminum windows each side, single aluminum windows in end bays. 8 1004 N
- 1288 161 STONEWALL PL c. 1965. Modern apartments, one of four identical buildings, two story, gable roof side, brick, corners feature narrow, elongated, brick quoins, five bay facade, central entrance, wood door with horizontal lights, sidelights, banks tripled aluminum windows each side, single aluminum windows in end bays. 10 1004 N
- 1289 162 STONEWALL PL c. 1965. Modern apartments, one of four identical buildings, two story, gable roof sides, brick, corners feature narrow, elongated brick quoins, five bay facade, central entrance, wood door with horizontal lights, sidelights, banks tripled windows each side, single aluminum windows in end bays. 9 1004 N
- 1290 163 STONEWALL PL c. 1965. Modern apartments, one of four identical buildings, two story, gable roof side, brick, corners feature narrow, elongated brick quoins, five bay facade, central entrance, wood door with horizontal lights, sidelights, banks tripled aluminum windows each side, single aluminum windows in end bays. 11 1004 N
- 1291 200 SUMMERVILLE CT 1937. Summerville Court Apartments, Colonial Revival, part of 22 building complex, two story, hip roof, brick, seven bay facade, recessed porch covers center five bays, two story box columns with capitals, second story balustraded, French doors lead onto balcony, six panel entrance with fan light and sidelights, 8/8 windows with shutters, 6/6 windows in end bays, box cornice. 27 1038 C
- 1292 201 SUMMERVILLE CT 1937. Summerville Court Apartments, Office, part of 22 building complex, one story, hip roof, brick, five bay facade, centered entrance with attached hip roof porch on ornamental iron supports, paired 6/6 windows with shutters flank entrance, lunette louvered vents in roof, box cornice. 22 1038 C
- 1293 204 SUMMERVILLE CT 1937. Summerville Court Apartments, Colonial Revival, part of a 22 building complex, two story, cross hip roof, H plan, brick, seven bay facade, centered entrance, wood door with windows, attached one story hip roof porch with box columns with capitals, wrought iron balcony above at second story center window, 8/8 windows with shutters, 6/6 windows in cross bays, lunette louvers in roof, box cornice, inset rear porch. 29 1038 C
- 1294 205 SUMMERVILLE CT 1937. Summerville Court Apartments, Colonial Revival, part of a 22 building complex, two story, cross hip roof, H plan, brick, seven bay facade, centered entrance, wood door with windows, attached one story hip roof porch on square posts with capitals over stoop, 8/8 windows with shutters, 6/6 windows in cross bays, lunette louvered vents in roof, box cornice. 21 1038 C

United States Department of the Interior
National Park Service

National Register Of Historic Places
Continuation Sheet

Section Number 7 Page 152

MID TOWN HISTORIC DISTRICT
Mobile
Mobile County, AL

- 1295 206 SUMMERVILLE CT 1937. Summerville Court Apartments, Colonial Revival, part of a 22 building complex, two story, hip roof, brick, seven bay facade, recessed porch covers five bays, two story box columns with capitals, second story balustraded, centered entrance wood door with infilled fan transom, sidelights, 8/8 windows with shutters first floor, French doors second story onto balcony, 8/8 with shutters in end bays, three lunette lights in roof, box cornice, inset rear porch. 17 1038 C
- 1296 209 SUMMERVILLE CT 1937. Summerville Court Apartments, Pool House, part of 22 building complex, one story, hip roof, brick, five bay facade, recessed porch covers facade, box columns with capitals, French doors in center bay, 4/4 windows with shutters, box cornice, pool in front with fence. 20 1038 C
- 1297 210 SUMMERVILLE CT 1937. Summerville Court Apartments, Colonial Revival, part of 22 building complex, two story, cross hip roof, H plan, brick, seven bay facade, centered entrance, wood door with windows, classical surround with broken swan's neck pediment, 8/8 windows with shutters, 6/6 windows in cross bays, pair lunette lights in roof, box cornice, attached one story covered walkway to north. 32 1038 C
- 1298 212 SUMMERVILLE CT 1937. Summerville Court Apartments, Colonial Revival, part of 22 building complex, two story, hip roof, brick, seven bay facade, recessed porch covers five bays, two story box columns with capitals, second story balustraded, centered entrance, wood door with infilled fan transom, sidelights, 8/8 windows with shutters first floor, French doors second floor, 6/6 windows with shutters end bays, three lunette lights in roof, box cornice. 31 1038 C
- 1299 214 SUMMERVILLE CT 1937. Summerville Court Apartments, Colonial Revival, part of 22 building complex, two story, cross hip roof, brick, seven bay facade, centered entrance, wood door with windows, classical surround, broken swan's neck pediment, 8/8 windows with shutters, 6/6 windows in cross bays, dentil course, box cornice, pair of lunette lights in roof. 30 1038 C
- 1300 215 SUMMERVILLE CT 1937. Summerville Court Apartments, Colonial Revival, part of 22 building complex, hip roof, brick, seven bay facade, inset porch covers five bays, two story box columns with capitals, second story balustraded, centered entrance, six panel door with infilled fan transom, sidelights, 8/8 windows with shutters first story, French doors second story, 6/6 windows with shutters in cross bays, dentil course, three lunette lights in roof, box cornice. 19 1038 C
- 1301 217 SUMMERVILLE CT 1937. Summerville Court Apartments, Colonial Revival, part of 22 building complex, two story, cross hip roof, brick, seven bay facade, centered entrance, wood door with window, classical surround, segmental arch above door, 8/8 windows with shutters, 6/6 windows with shutters in end bays, dentil course, louvered lunettes in roof, box cornice. 18 1038 C
- 1302 218 SUMMERVILLE CT 1937. Summerville Court Apartments, Colonial Revival, part of 22 building complex, two story, cross hip roof, H plan, brick, seven bay facade, centered entrance, wood door with nine lights, classical surround, wrought iron balcony above with French doors center bay only, 8/8 windows with shutters, 6/6 windows with shutters end bays, dentil course, louvered lunette and lunette light in roof, box cornice, inset rear porch center bay, interior chimney. 33 1038 C

United States Department of the Interior
National Park Service

National Register Of Historic Places
Continuation Sheet

Section Number 7 Page 153

MID TOWN HISTORIC DISTRICT
Mobile
Mobile County, AL

-
- 1303 2058 SUMMERVILLE CT 1937. Summerville Court Apartments, Colonial Revival, part of 22 building complex, two story, cross hip roof, H plan, brick, seven bay facade, centered entrance, wood door with nine lights, classical surround, wrought iron balcony above at center bay only, 8/8 windows with shutters, 6/6 windows with shutters in end bays, dentil course, lunette louvered vents in roof, box cornice. 26 1038 C
- 1304 2059 SUMMERVILLE CT 1937. Summerville Court Apartments, Colonial Revival, part of 22 building complex, two story, hip roof, brick, seven bays, inset two story porch covers five bays, two story box columns with capitals, balustraded balcony, centered entrance, six panel door with infilled fan transom, sidelights, 8/8 windows with shutters, 6/6 windows with shutters in end bays, French doors exit onto balcony, dentil course, three lunette lights in roof, inset two story porch rear center bay. 34 1038 C
- 1305 2063 SUMMERVILLE CT 1937. Summerville Court Apartments, Colonial Revival, part of 22 building complex, two story, hip roof, brick, seven bay facade, recessed porch covers five bays, two story box columns with capitals, balustraded balcony, centered entrance, six panel door with infilled fan transom, sidelights, 8/8 windows with shutters, 6/6 windows with shutters in end bays, French doors exit onto balcony, three lunette lights, box cornice. 25 1038 C
- 1306 2066 SUMMERVILLE CT 1937. Summerville Court Apartments, Colonial Revival, part of 22 building complex, two story, cross hip roof, H plan, brick, seven bay facade, centered entrance, wood door with nine lights, classical surround, 8/8 windows with shutters, 6/6 windows with shutters in end bays, pair lunette louvers on roof, dentil course, box cornice. 23 1038 C
- 1307 2067 SUMMERVILLE CT 1937. Summerville Court Apartments, Colonial Revival, part of 22 building complex, two story, cross hip roof, H plan, brick, seven bay facade, centered entrance, wood door with nine lights, classical surround, segmental arch above, 8/8 windows with shutters, 6/6 windows with shutters in end bays, dentil course, pair lunette lights in roof, box cornice. 24 1038 C
- 1308 2056 TERRACE ST c. 1960. Minimal Traditional, two story, hip roof, asbestos sided, three bay facade with attached one story wing north side, six panel door in projecting one story hip roof bay, paired aluminum windows, box cornice. 14 1007 N
- 1309 2058 TERRACE ST c. 1920. Bungalow, one story, frame, hip roof, three bay facade, inset porch covers two bays, brick pillars, screened, Craftsman door with sidelights, paired 3/1 windows, exposed rafters. 13 1007 C
- 1310 2060 TERRACE ST c. 1950. Two story garage apartment, gable roof front, asbestos sided, two bay facade, wood stair, 4/1 windows, triangular louvered vent. 12 1007 C
- 1311 150 TUSCALOOSA ST c. 1925. Bungalow, one story, jerkin head gable roof front, frame, two bay facade, attached offcenter jerkin head gable porch, tripled posts on brick plinths, four panel door with row of small lights across top, sidelights and transom, 6/6 window with shutters, board and batten gable, louvered vent, exposed rafters. 28 1040 C

United States Department of the Interior
National Park Service

National Register Of Historic Places
Continuation Sheet

Section Number 7 Page 154

MID TOWN HISTORIC DISTRICT
Mobile
Mobile County, AL

-
- 1312 152 TUSCALOOSA ST c. 1925. Bungalow, one story, hip roof, frame, three bay facade, attached offcenter gable porch, tripled box columns with capitals on brick plinths, wood door center of facade, flanked bay paired 3/1 windows, purlins, louvered vents, exposed rafters, side chimney. 29 1040 C
- 1313 9 UPHAM ST c. 1930. Bungalow, one story, gable roof front, frame, two bay facade, attached offcenter gable porch with jalousied window infill, paired 3/1 windows with shutters, louvered vents in gables, exposed rafters. 18 1037 C
- 1314 10 UPHAM ST c. 1935. Bungalow, one story, gable roof front, asbestos sided, two bay facade, attached offcenter gable porch, brick pillars, infilled with square lights, paired 6/6 windows, lattice vents in gables, exposed rafters, two story gabled garage rear, two auto bays with wood doors, apartment entrance between, Craftsman door with fabric awning, 3/1 windows, louvered vent. 21 1037 C
- 1315 11 UPHAM ST c. 1980. One story, gable roof sides, probably a converted garage, almost entire facade infilled with cinder blocks and two large, multi-light windows. 19 1037 N
- 1316 13 UPHAM ST c. 1960. Standard Commercial, one story, cinderblock, flat roof, four bay facade, entrance slightly inset with fabric awning over stoop, windows shuttered, crimped tin along roofline. 20 1037 N
- 1317 66 UPHAM ST c. 1900. Victorian Cottage, one story, gable roof sides, asbestos sided, three bay facade, recessed porch covers facade, chamfered posts with brackets, balustraded, wood door with window, transom, 1/1 windows with shutters, gable above with square light, box cornice. 24 1037 C
- 1318 107 UPHAM ST c. 1960. Standard Commercial, one story, flat roof, brick, banks of aluminum display windows, metal awning runs length of building. 23 1037 N
- 1319 119 UPHAM ST c. 1960. Ranch Style, one story, cross gable, ell plan, brick, aluminum windows, wood door with sidelights, interior chimney. 25 1037 N
- 1320 122 UPHAM PL c. 1955. Minimal Traditional, one and a half story, gable roof front, board and batten first story, vinyl in gable, pair inset porches each corner, ornamental iron corner supports, 9/9 windows between, pair 6/6 windows in gable, box cornice, no return. 1 1039 N

United States Department of the Interior
National Park Service

National Register Of Historic Places
Continuation Sheet

Section Number 7 Page 155

MID TOWN HISTORIC DISTRICT
Mobile
Mobile County, AL

- 1321 213 UPHAM ST c. 1965. Ranch Style, one story, gable roof sides, brick, aluminum windows, box cornice. 26 1037 N
- 1322 204 UPHAM ST 1937. Summerville Court Apartments, Colonial Revival, part of 22 building complex, two story, cross hip roof, H plan, brick, seven bay facade, centered entrance, wood door with nine lights, classical surround with broken swan's neck pediment, 8/8 windows with shutters, water table, dentil course, three lunette lights in roof, box cornice. 13 1038 C
- 1323 208 UPHAM ST 1937. Summerville Court Apartments, Colonial Revival, part of 22 building complex, two story, hip roof, brick, seven bay facade, recessed porch covers five bays, two story box columns with capitals, balustraded second story, four panel door with infilled fan transom, sidelights, 8/8 windows with shutters, French doors onto balcony, lunette lights in roof, dentil course, box cornice. 14 1038 C
- 1324 214 UPHAM ST 1937. Summerville Court Apartments, Colonial Revival, part of 22 building complex, two story, hip roof, brick, seven bay facade, recessed porch covers five bays, two story box columns with capitals, second story balustraded, four panel door with infilled fan transom, sidelights, 8/8 windows with shutters, French doors at second story, three lunette lights in roof, dentil course, box cornice. 15 1038 C
- 1325 218 UPHAM ST 1937. Summerville Court Apartments, Colonial Revival, part of 22 building complex, two story, cross hip roof, brick, seven bay facade, central entrance, wood door with nine lights, classical surround, 8/8 windows with shutters, three lunette lights in roof, dentil course, box cornice. 16 1038 C
- 1326 2101 UPHAM PL c. 1970. Ranch Style, one story, hip roof, gable roof sides, ell plan, brick, metal casement windows, box cornice. 5 1039 N
- 1327 2103 UPHAM PL c. 1970. Ranch Style, one story, hip roof, brick, four bay facade, metal casement windows, slightly inset entrance with ornamental iron support, wood door, box cornice. 4 1039 N
- 1328 2105 UPHAM PL c. 1970. Ranch Style, one story, brick, gable roof sides, three bay facade, side entrance, six panel door slightly inset with vinyl surround, tripled 6/6 aluminum windows in center bay, box cornice. 3 1039 N
- 1329 2106 UPHAM PL c. 1955. Minimal Traditional, one and a half story, gable roof sides, aluminum sided, one story gable wing south side, shed roof dormer, 1/1 windows, much obscured by vegetation. 6 1039 N

cb
1039 N

United States Department of the Interior
National Park Service

National Register Of Historic Places
Continuation Sheet

Section Number 7 Page 156

MID TOWN HISTORIC DISTRICT
Mobile
Mobile County, AL

- 1330 2107 UPHAM PL c. 1970. Ranch Style, one story, gable roof sides, brick, three sections, four bay section one end, two bay section other, two bay center section with recessed porch on square posts, paired multi-light windows, six panel door, interior chimney. 2 1039 N
- 1331 2108 UPHAM ST c. 1970. Ranch Style, one story, gable roof sides, brick, attached gable porch with ornamental iron supports, banks of aluminum windows, box cornice, no return. 7 1039 N
- 1332 7 VAN HEUVAL ST c. 1920. Vernacular, one story, gable roof sides, frame, three bay facade, centered entrance, six panel door, attached gable porch covers center bay, Tuscan columns, balustraded, 6/6 windows, lunette louver in gable, box cornice. 13 1020 C
- 1333 9 VAN HEUVAL ST c. 1940. Minimal Traditional, one story, gable roof sides, stucco, three bay facade, wood door in stuccoed center gable with entrance slightly inset, quoin surround, roofline sweeps down south adjacent, partially covering large chimney with sloping sides, 6/6 windows, box cornice. 12 1020 C
- 1334 11 VAN HEUVAL ST c. 1925. Bungalow, one and a half story, frame lower story, board and batten in gable,, recessed porch covers facade, box columns with capitals, north bay infilled with clapboards and 2/2 window, porch screened, door not visible, pair louvered vents each side gable, tripled windows with metal awning, knee braces, exposed rafters, shed roof dormers north and south elevations. 11 1020 C
- 1335 13 AND 15 VAN HEUVAL ST c. 1925. Bungalow, one story, gable roof front, frame, three bay facade, pair attached gable porches each end bay, paneled box columns with attached trelliswork for roses, Craftsman doors, 3/1 windows, six pane light in gable, knee braces, louvered vent, exposed rafters, interior chimney. 10 1020 C
- 1336 14 VAN HEUVAL ST c. 1940. Two story garage apartment, frame, gable roof sides, board and batten lower story, frame upper story, 3/1 windows with shutters, exposed rafters. 14 1020 C
- 1337 17 VAN HEUVAL ST c. 1925. Bungalow, one story, gable roof sides, frame, three bay facade,, recessed porch covers facade, square posts, screened, wood door, flanked by paired 2/2 windows, knee braces, louvered vents in gables, exposed rafters. 9 1020 C
- 1338 19 VAN HEUVAL ST c. 1925. Bungalow, one story, jerkin head gable roof front, frame, two bay facade,, recessed porch covers facade, box columns, wood door, 6/6 windows, later 2x4 balustrade, box cornice, no return. 8 1020 C

26 F
1020 C

United States Department of the Interior
National Park Service

National Register Of Historic Places
Continuation Sheet

Section Number 7 Page 157

MID TOWN HISTORIC DISTRICT
Mobile
Mobile County, AL

- 1339 20 VAN HEUVAL ST c. 1940. Minimal Traditional, two story, gable roof front, frame, two bay facade, wood door with window and burglar gate, 6/6 windows, tar paper in gable, louvered vent, exposed rafters. 15 1020 C
- 1340 21 VAN HEUVAL ST c. 1925. Bungalow, jerkin head gable roof sides, frame, two bays, attached offcenter jerkin head gable porch with paneled box columns with capitals, six panel door, 6/6 window with shutters, board and batten gable, louvered vent, box cornice, no return. 7 1020 C
- 1341 23 VAN HEUVAL ST c. 1925. Bungalow, one story, jerkin head gable roof front, frame, two bay facade, recessed porch covers facade, box columns with capitals, later 2x4 balustrade, nonhistoric wood door with oval window, sidelights, sunburst molding over door, probably added, board and batten gable, oval design of later vintage applied, purlins, exposed rafters. 6 1020 C
- 1342 25 VAN HEUVAL ST c. 1925. Bungalow, one story, gable roof front, frame, three bay facade, attached offcenter gable porch, square brick pillars, six panel door, flanked by paired 3/1 windows, stuccoed gables, purlins, louvered vents, exposed rafters. 5 1020 C
- 1343 29 VAN HEUVAL ST c. 1960. Two story brick apartment building, hip roof, seven bay facade with parking in front, two story gable bay center with attached one story flat roof porch, ornamental iron supports and cresting, four panel door with fan light, sidelights and transom, metal casement windows, awnings over interior bays, exposed rafters. 4 1020 N
- 1344 1 WESTWOOD ST c. 1960. Minimal Traditional, one story, cross gable, vinyl sided, three bay facade, side entrance with attached gable over stoop on square posts, fabric awnings over multi-light aluminum windows, box cornice, no return. 15 1033 N
- 1345 2 WESTWOOD ST c. 1940. Minimal Traditional, one story, gable roof sides, frame, three bay facade with attached carport north end with exaggerated eave, attached hip roof porch at center bay with ornamental iron supports, six panel door, flanking paired 3/1 windows, interior chimney between house and carport, box cornice, no return. 14 1033 C
- 1346 3 WESTWOOD ST c. 1940. Neo-Creole, one and a half story, gable roof sides, aluminum sided,, recessed porch covers facade, box columns with capitals, six panel door, 8/8 windows with shutters and jib doors, pair gable dormers with 6/6 windows, box cornice, no return. 16 1033 C
- 1347 5 WESTWOOD ST c. 1940. Minimal Traditional, one story, gable roof sides, frame, four bay facade, attached gable over stoop with square posts with braces, louvered vent, tripled 6/6 windows north adjacent, exposed rafters, interior chimney, rear ell. 17 1033 C

CB 7
ncc 2

United States Department of the Interior
National Park Service

National Register Of Historic Places
Continuation Sheet

Section Number 7 Page 158

MID TOWN HISTORIC DISTRICT
Mobile
Mobile County, AL

- 1348 7 WESTWOOD ST c. 1940. Colonial Revival, one and a half story, frame, five bay facade, centered entrance, six panel door in classical surround, 6/6 windows, pair gable dormers with 6/6 windows, end chimney, no cornice. 18 1033 C
- 1349 9 WESTWOOD ST c. 1960. Two story apartment, gable roof sides, vinyl sided, three bay facade, second story slightly overhangs along facade, first story board and batten, six panel door, 6/6 windows, pair gable wall dormers above, box cornice, no return. 19 1033 N
- 1350 12 WESTWOOD ST c. 1960. Minimal Traditional, one story, gable roof sides, vinyl sided, four bay facade, attached offcenter gable over stoop with paired square posts, six panel door, 12/12 windows with shutters, interior chimney. 13 1033 N
- 1351 14 WESTWOOD ST c. 1960. Minimal Traditional, one story, gable roof sides, aluminum sided, four bay facade, attached offcenter gable porch with ornamental iron supports, six panel door, aluminum windows, box cornice, no return, interior chimney. 12 1033 N
- 1352 16 WESTWOOD ST c. 1940. Minimal Traditional, one story, cross gable, ell plan, four bay facade, inset porch south bay in cross gable, infilled with 1/1 windows, ornamental iron railing, wood door, chimney at facade, 6/6 windows, box cornice, closed return. 11 1033 C
- 1353 18 WESTWOOD ST c. 1925. Bungalow, one story, gable roof front, frame, three bay facade, attached offcenter gable porch, square posts on brick pillars, wood door flanked by paired 3/1 windows, purlins, exposed rafters, interior chimney. 10 1033 C
- 1354 20 WESTWOOD ST c. 1940. Minimal Traditional, one and a half story, gable roof sides, frame, three bay facade, attached gable at center bay, square psots with capitals, wood door, 6/6 windows with shutters, end chimney, exposed rafters, 3/1 window in side gable, two story garage apartment rear, gable roof front, frame, two bays, attached offcenter one story shed roof porch, 6/6 windows. 8 1033 C
- 1355 21 WESTWOOD ST c. 1945. Two story garage apartment, gable roof sides, frame, three bay facade, two auto bays with double wooden doors, staircase with attached shed roof porch on square posts upstairs, Craftsman door, paired 3/1 windows. 20 1033 C
- 1356 22 WESTWOOD ST c. 1940. Minimal Traditional, one story, cross gable, aluminum sided, three bay facade, entrance north bay with steeply pitched gable above, bubble awning, single shoulder chimney south adjacent, triangular louvered vent in center gable, box cornice, no return. 7 1033 C

CL 6
me 3

United States Department of the Interior
National Park Service

National Register Of Historic Places
Continuation Sheet

Section Number 7 Page 159

MID TOWN HISTORIC DISTRICT
Mobile
Mobile County, AL

- 1357 24 WESTWOOD ST c. 1940. Minimal Traditional, one story, cross gable, frame, three bay facade, inset porch south end, brick pillars, 1/1 window infill, attached brick gable at entrance, wood door, paired 6/6 windows north adjacent, end chimney, box cornice, closed return. 6 1033 C
- 1358 26 WESTWOOD ST c. 1940. Minimal Traditional, one story, gable sides with rear ell, three bay facade, inset porch north end, brick supports, 3/1 windows, chimney at facade with high single shoulder, round louvered vents in gables. 5 1033 C
- 1359 50 WESTWOOD ST c. 1925. Bungalow, one story, gable roof sides, frame, five bay facade,, recessed porch covers facade, square brick pillars, Craftsman door, Craftsman windows, louvered vent in gables, exposed rafters. 4 1033 C
- 1360 52 WESTWOOD ST c. 1930. English Cottage Revival, one story, gable roof sides, frame, three bay facade, attached offcenter gable porch with paired square posts with braces, gothic light with shutters in gable, chimney at facade, six panel door, 6/6 windows, exposed rafters. 3 1033 C
- 1361 56 WESTWOOD ST c. 1940. Minimal Traditional, one story, gable roof sides, frame, four bay facade, attached gable porch with square posts, 12/12 windows with shutters, box cornice, no return, interior chimney. 2 1033 C
- 1362 57 WESTWOOD ST c. 1925. Bungalow, one story, gable roof front, frame, three bay facade, attached offcenter gable porch with square brick pillars, gable porte-cochere south side, Craftsman door, 3/1 windows, louvered vent, box cornice, closed return. 21 1033 C
- 1363 58 WESTWOOD ST c. 1940. Minimal Traditional, one story, gable roof sides, frame, three bay facade, attached gable at entrance with battered brick face, six panel door, paired 6/6 windows, exposed rafters, louvered vent in front gable. 1 1033 C
- 1364 59 WESTWOOD ST c. 1925. Bungalow, one story, gable roof front, frame, three bay facade,, recessed porch covers facade,, battered, boxed columns on brick plinths, porte-cochere south side, Craftsman door and windows, knee braces, light with flanking louvered vents in gable, exposed rafters. 22 1033 C
- 1365 60 WESTWOOD ST c. 1930. Bungalow, one story, gable roof sides, frame, attached offcenter flat roof porch, square posts, balustraded, screened, metal awnings, front door obscured, 3/1 windows, interior chimney exposed rafters. 35 1032 C

1033
C

United States Department of the Interior
National Park Service

National Register Of Historic Places
Continuation Sheet

Section Number 7 Page 160

MID TOWN HISTORIC DISTRICT
Mobile
Mobile County, AL

- 1366 61 WESTWOOD ST c. 1940. Minimal Traditional, one story, gable roof sides, frame, three bay facade, centered gable with stucco face and quoins around entrance, wood door with lights, roofline sweeps almost to ground north side, fronts chimney with sloping shoulders, 3/1 windows with shutters, exposed rafters. 23 1033 C
- 1367 62 WESTWOOD ST c. 1960. Minimal Traditional, one story, gable roof sides, aluminum sided, attached gable porch covers most of facade, perma-stone base which continues across facade below window sill level, porch supported on box columns resting on the stone wall, screened, door obscured, triangular louvered vent. 34 1032 N
- 1368 63 WESTWOOD ST c. 1940. English Cottage Revival, one story, cross gable, ell plan, frame, two bay facade, attached shed roof porch with arched stucco openings adjacent gable bay, tripled 6/1 windows in gable, gothic louvered vent, side chimney, exposed rafters. 24 1033 C
- 1369 70 WESTWOOD ST c. 1930. Bungalow, one story, hip roof, frame, three bay facade, attached offcenter gable porch, square brick pillars, screened, multi-light door, 3/1 windows, round top louvered vent, exposed rafters, side chimney. 33 1032 C
- 1370 100 WESTWOOD ST c. 1940. Minimal Traditional, one story, gable roof sides, frame, three bay facade, attached gable porch covers center of facade, paired Tuscan columns, six panel door, paired 3/1 windows, end chimney, exposed rafters, gable peak in roofline. 32 1032 C
- 1371 101 WESTWOOD ST c. 1940. Minimal Traditional, one story, gable roof sides, frame, three bay facade, attached gable porch covers center bay, square posts, 3/1 windows, end chimney, exposed rafters. 25 1033 C
- 1372 102 WESTWOOD ST c. 1925. Spanish Revival, one story, flat, parapeted roof with coping, two bay facade, inset porch with stucco pillar, porte-cochere under main roofline north side, paired 3/1 windows, Craftsman door, pipe vents around wall. 31 1032 C
- 1373 103 WESTWOOD ST c. 1945. Minimal Traditional, one story, gable roof sides, frame, four bay facade, attached gable porch with ornamental iron supports, six panel door, 12/12 window north adjacent, 8/8 window with shutters south adjacent, end chimney, exposed rafters. 26 1033 C
- 1374 105 WESTWOOD ST c. 1945. Minimal Traditional, one story, frame, gable roof sides, attached gable bay center, board and batten, six panel door, 3/1 windows with shutters, exposed rafters. 27 1033 C

United States Department of the Interior
National Park Service

National Register Of Historic Places
Continuation Sheet

Section Number 7 Page 161

MID TOWN HISTORIC DISTRICT
Mobile
Mobile County, AL

-
- 1375 107 WESTWOOD ST c. 1945. Minimal Traditional, one story, gable roof sides, frame, three bay facade, attached gable at entrance with battered brick face, six panel door, 12/12 windows with shutters, exposed rafters. 28 1033 C
- 1376 110 WESTWOOD ST c. 1940. Minimal Traditional, one story, hip roof, frame, three bay facade, attached gable over stoop, infilled with large arched windows, the one at the front breaks the pediment, accomodated by a closed return, engaged pilasters, shuttered windows, end chimney. 30 1032 C
- 1377 111 WESTWOOD ST c. 1925. Bungalow, one story, cross gable, frame, three bay facade, recessed porch covers facade, box columns on brick wall, multi-light entrance, paired 3/1 windows, knee braces, end chimney, exposed rafters. 29 1033 C
- 1378 113 WESTWOOD ST c. 1970. Ranch Style, one story, hip roof with gable bay, brick, metal casement windows with shutters, board and batten and triangular louvered vent in gable, box cornice, closed return. 30 1033 N
- 1379 114 WESTWOOD ST c. 1940. Minimal Traditional, one story, gable roof sides, frame, three bay facade, offcenter entrance, six panel door with sidelights, attached gable with Tuscan columns, knee braces, 4/1 windows, exposed rafters, interior chimney. 29 1032 C
- 1380 115 WESTWOOD ST c. 1945. Minimal Traditional, one story, gable roof sides, asbestos sided, four bay facade, attached gable with wall brackets over door, paired 3/1 windows, interior chimney, box cornice, no return. 31 1033 C
- 1381 116 WESTWOOD ST c. 1930. Bungalow, one story, gable roof front, frame, recessed porch covers facade, box columns on clapboarded kneewall, screened, metal awning, door and windows obscured, louvered vent, knee braces, porte-cochere north side, exposed rafters. 28 1032 C
- 1382 117 WESTWOOD ST c. 1940. English Cottage Revival, one story, cross gable, brick, three bay facade, chimney with high single shoulder at facade, gable over steps with gothic vent, square brick pillars on inset porch, porte-cochere north side, exposed rafters. 32 1033 C
- 1383 118 WESTWOOD ST c. 1925. Bungalow, one story, gable roof front, frame, three bay facade, recessed porch covers facade, square brick pillars, screened with ornamental iron railing and frieze work, louvered vent, knee braces, porte-cochere north side, side chimney, exposed rafters. 27 1032 C

United States Department of the Interior
National Park Service

National Register Of Historic Places
Continuation Sheet

Section Number 7 Page 162

MID TOWN HISTORIC DISTRICT
Mobile
Mobile County, AL

- 1384 120 WESTWOOD ST c. 1930. Bungalow, one story, gable on hip roof sides, vinyl sided, three bay facade, inset porch with square brick pillars, paired 6/6 window, Craftsman door, box cornice. 26 1032 C
- 1385 121 WESTWOOD ST c. 1935. Bungalow, one story, gable roof sides, frame, two bay facade, inset porch with ornamental iron supports and railing, Craftsman door, tripled 3/1 windows with shutters, jerkin head gable in roof, end chimney, exposed rafters. 33 1033 C
- 1386 122 WESTWOOD ST c. 1930. Bungalow, one story, hip roof, brick, two bay facade, attached offcenter hip roof porch, battered box columns on brick plinths, porch screened, obscures door, tripled 3/1 windows south adjacent. 25 1032 C
- 1387 123 WESTWOOD ST c. 1940. Minimal Traditional, one story, cross gable, aluminum sided, four bay facade, round top wood door, single shoulder chimney north adjacent, flanked by small verticle lights, paired aluminum windows south adjacent entrance. 34 1033 C
- 1388 150 WESTWOOD ST c. 1925. Spanish Revival, one story, hip roof, stucco, two bay facade, attached offcenter shed roof porch with arched stucco openings forms gable porte-cochere north side with arched auto access, Craftsman window in south bay, a hip roof projection, exposed rafters, interior chimney. 24 1032 C
- 1389 152 WESTWOOD ST c. 1925. Bungalow, one story, hip roof, brick, two bay facade, inset porch with hip roof projection, square brick pillars, Craftsman door, tripled windows, exposed rafters, side chimney, interior chimney. 23 1032 C
- 1390 154 WESTWOOD ST c. 1925. Bungalow, one story, gable roof front, frame, three bay facade, attached gable porch covers most of facade, square brick pillars with square posts either side steps, Craftsman door, flanked by paired 3/1 windows, louvered vent, knee braces, porte-cochere north side, exposed rafters, side chimney. 22 1032 C
- 1391 156 WESTWOOD ST c. 1930. Bungalow, one story, gable roof front, frame, three bay facade, attached offcenter gable porch, cross-pieced columns, screens obscure windows and doors, louvered vent, purlins, exposed rafters. 21 1032 C
- 1392 158 WESTWOOD ST c. 1930. Vernacular, one story, hip roof, three bay facade, frame, inset porch covers two bays, square posts, wood door, paired 6/1 windows, exposed rafters. 20 1032 C

cb 9
200

United States Department of the Interior
National Park Service

National Register Of Historic Places
Continuation Sheet

Section Number 7 Page 163

MID TOWN HISTORIC DISTRICT
Mobile
Mobile County, AL

- 1393 209 WESTWOOD ST c. 1955. Minimal Traditional, one story, gable roof sides, asbestos sided, four bay facade, attached gable over stoop, paired square posts and balustraded, 6/6 windows with slatted awnings, exposed rafters. 1 1032 N
- 1394 211 WESTWOOD ST c. 1945. Minimal Traditional, one story, gable on hip sides, cross gable, frame, drop sided, five bay facade, six panel door in center of cross gable at south end, attached gable above on wall braces, 3/1 windows, smaller and paired in north bay, box cornice, no return. 10 1032 C
- 1395 213 WESTWOOD ST c. 1955. Minimal Traditional, one story, gable on hip front, offcenter gable over inset porch, square posts and balustraded, wood door, paired 3/1 windows, box cornice, no return. 9 1032 N
- 1396 250 WESTWOOD ST c. 1945. Minimal Traditional, one story, cross gable, frame, four bay facade, six panel door with stoop, 6/6 windows, bay window in cross gable, 6/6 windows, box cornice, no return, triangular louvered vent. 11 1032 C
- 1397 254 WESTWOOD ST c. 1940. Minimal Traditional, one and a half story, frame, four bay facade, centered entrance, six panel door, attached gable porch with Tuscan columns, flanked by 6/6 windows with shutters, pair gables in roof with 8 pane lights, centered ridge chimney. 12 1032 C
- 1398 255 WESTWOOD ST c. 1930. English Cottage Revival, one and a half story, cross gables, ell plan, brick, three bay facade, round top door in secondary wall gable, four pane light south adjacent, chimney north adjacent at juncture with one and a half story cross gable, casement windows in half story, louvered lunette vent, box cornice, no return. 8 1032 C
- 1399 256 WESTWOOD ST c. 1920. Bungalow, one story, hip roof, frame, three bay facade, attached hip roof porch covers most of facade, gable over steps, brick pillars, wood door with window, flanked by paired 3/1 windows, exposed rafters. 13 1032 C
- 1400 257 WESTWOOD ST c. 1955. Minimal Traditional, one story, gable roof front, vinyl sided, three bay facade, side entrance with fabric awning, bay window center with three windows, center one 6/1 and side ones 4/1, inset porch south bay, jalousied windows, round louvered vent. 7 1032 N
- 1401 258 WESTWOOD ST c. 1945. Minimal Traditional, one story, gable roof sides, vinyl sided, three bay facade, attached gable porch with square posts, screened, at entrance, 3/1 windows with shutters, box cornice, no return, interior chimney. 14 1032 C

cb 6
1032 C

United States Department of the Interior
National Park Service

National Register Of Historic Places
Continuation Sheet

Section Number 7 Page 164

MID TOWN HISTORIC DISTRICT
Mobile
Mobile County, AL

- 1402 259 WESTWOOD ST c. 1930. English Cottage Revival, one story, cross gables, brick, three bay facade, centered entrance with arched openings in corner of dominant gable, casement windows south adjacent, tripled 6/1 windows south adjacent in secondary gable, louvered lunettes, end chimney. 6 1032 C
- 1403 260 WESTWOOD ST c. 1945. Minimal Traditional, one story, gable roof sides, asbestos sided, three bay facade, centered entrance, attached gable over stoop with ornamental iron supports, 6/6 windows with shutters, box cornice, no return. 15 1032 C
- 1404 261 WESTWOOD ST c. 1930. Bungalow, one story, hip roof, brick, four bay facade, attached gable porch at entrance, brick pillars with arched openings, canvas awnings obscure door and windows, louvered lunette in gable, box cornice, no return. 5 1032 C
- 1405 262 WESTWOOD ST c. 1930. Bungalow, one story, hip roof, brick, three bay facade, attached offcenter gable porch, ornamental iron supports on brick knee wall, screened, louvered vent in gable, box cornice, no return. 16 1032 C
- 1406 263 WESTWOOD ST c. 1930. Bungalow, one story, gable roof front, brick, three bay facade, attached gable porch covers most of facade, brick pillars with arched openings, multi-light door, flanked by paired 3/1 windows, louvered vent in stucco gable, exposed rafters, interior chimney. 4 1032 C
- 1407 264 WESTWOOD ST c. 1930. Bungalow, one story, gable roof sides, frame, two bay facade, attached offcenter gable porch, paneled box columns with capitals, multi-light door, 6/1 windows, louvered vent in stuccoed gable, exposed rafters. 17 1032 C
- 1408 265 WESTWOOD ST c. 1940. Minimal Traditional, one story, cross gable, ell plan, stucco, three bay facade, attached gable porch north end with square posts with capitals, wood door with diamond light, chimney with high single shoulder north adjacent gable ell, metal awning over paired 3/1 windows in gable, louvered lunette, box cornice, closed return. 3 1032 C
- 1409 266 WESTWOOD ST c. 1925. Bungalow, one story, gable roof sides, three bay facade, attached, offcenter shed roof porch covers two bays, box columns on brick plinths, flat board balustrade, Craftsman door and windows, end chimney, interior chimney, louvered vents in gables, exposed rafters. 18 1032 C
- 1410 267 WESTWOOD ST c. 1930. Bungalow, one story, gable roof front, brick, three bay facade, attached offcenter gable porch with square brick pillars, screened, Craftsman door, paired Craftsman windows, stuccoed gables with half-timbering, louvered vents, gabled porte-cochere north side, exposed rafters. 2 1032 C

cb →
ncb

United States Department of the Interior
National Park Service

National Register Of Historic Places
Continuation Sheet

Section Number 7 Page 165

MID TOWN HISTORIC DISTRICT
Mobile
Mobile County, AL

- 1411 268 WESTWOOD ST c. 1940. Minimal Traditional, two story, gable roof front, frame, two bay facade, attached two story shed roof porch covers center of facade, square posts and balustraded, staircase with wide board balusters traverses the facade, 6/6 windows, louvered vent, exposed rafters. 19 1032 C
- 1412 50 WILLIAMS ST c. 1940. Minimal Traditional, one story, cross gable, four bay facade, centered two bay gable with chimney up center, six panel door with fabric awning, paired 6/6 windows, clapboarded gables. 16 1022 C
- 1413 51 WILLIAMS ST c. 1940. Minimal Traditional, one and a half story, frame, four bay facade, cross gable, centered gable with 8/8 window with shutters, louvered vent, entrance north adjacent, six panel door, four gable dormers with 6/6 windows, two interior chimneys, box cornice, closed return. 16 1020 C
- 1414 52 WILLIAMS ST c. 1940. Minimal Traditional, one story, cross gable, ell plan, frame, three bay facade, inset porch south bay, square posts, entrance in side of porch, tripled 9/9 windows in middle bay, inset, screened porch in north cross gable, paired square posts with capitals, exposed rafters. 15 1022 C
- 1415 54 WILLIAMS ST c. 1940. Colonial Revival, two story, gable roof sides, frame, three bay facade, centered entrance, six panel door in classical surround with broken pediment, 12/12 windows with shutters, end chimney, box cornice, no return. 14 1022 C
- 1416 57 WILLIAMS ST c. 1940. Neo-Creole, one story, gable roof sides, frame, three bay facade, recessed porch covers facade, paired square posts with capitals, balustraded, centered six panel door, 12/12 windows with shutters, interior chimney, box cornice, no return. 17 1020 C
- 1417 59 WILLIAMS ST c. 1940. Colonial Revival, two story, gable roof sides, brick, three bay facade, centered entrance, six panel door with sidelights, fan transom, soldiered surround, tripled 6/6 windows with shutters flank entrance, paired second story, center bay a casement window, box cornice, closed return. 18 1020 C
- 1418 60 WILLIAMS ST c. 1940. Minimal Traditional, one and a half story, gable roof sides, frame, five bay facade with attached gable wing north side, centered entrance, six panel door, stoop, 9/9 windows with shutters, pair gable dormers with 6/6 windows, interior chimney, box cornice. 13 1022 C
- 1419 61 WILLIAMS ST c. 1940. Colonial Revival, two story, gable roof sides, brick, three bay facade, centered entrance, wood door with small round top lights at top, classical surround, attached one story gable porch with paired Tuscan columns, arched opening in pediment, 15/15 windows with shutters first story, 12/12 second, end chimney, box cornice, no return. 19 1020 C

United States Department of the Interior
National Park Service

National Register Of Historic Places
Continuation Sheet

Section Number 7 Page 166

MID TOWN HISTORIC DISTRICT
Mobile
Mobile County, AL

- 1420 62 WILLIAMS ST c. 1940. Minimal Traditional, one and a half story, gable roof sides, brick, five bay facade, attached flat roof, clapboarded wing south side, recessed porch covers two bays, ornamental iron work supports, six panel door with flanking shutters, multi-light windows, pair gable dormers with 6/6 windows, cross gable bay with 6/6 window, interior chimney. 12 1022 C
- 1421 63 WILLIAMS ST c. 1940. Minimal Traditional, one story, gable roof sides, brick, three bay facade, centered entrance, six panel door with sidelights, attached shed roof porch covers entrance, ornamental iron supports, 12/12 windows with shutters, box cornice, no return. 20 1020 C
- 1422 64 WILLIAMS ST c. 1945. Minimal Traditional, one story, gable roof sides, vinyl sided, three bay facade, centered entrance, wood door, attached gable over stoop with ornamental iron work, paired 6/6 windows north adjacent, paired 1/1 windows south adjacent, end chimney, box cornice, no return. 11 1022 C
- 1423 65 WILLIAMS ST c. 1940. Minimal Traditional, one story, gable on hip sides, brick, five bays, 8/8 windows with shutters, attached hip roof porch with ornamental iron supports, interior chimney, box cornice. 21 1020 C
- 1424 101 WILLIAMS ST c. 1940. Minimal Traditional, one story, gable roof sides, brick, five bay facade, six panel door, attached flat roof porch over stoop with square posts with capitals, 6/6 windows, brick quoins at corners, box cornice, no return. 22 1020 C
- 1425 103 WILLIAMS ST c. 1940. Minimal Traditional, two story, gable roof sides, frame, three bay facade, centered entrance, six panel door with sidelights, attached one story gable porch with square posts, 12/12 windows with shutters, box cornice, no return. 23 1020 C
- 1426 105 WILLIAMS ST c. 1940. Minimal Traditional, one and a half story, frame, gable roof sides, three bay facade with attached gable wing south end, centered door with six panels, 15/15 windows with wide shutters, pair gable dormers with 6/6 windows, interior chimney, box cornice, no return. 24 1020 C
- 1427 106 WILLIAMS ST c. 1945. Minimal Traditional, one and a half story, gable roof sides, frame, three bay facade with gable wing south side, inset entrance covered in black plastic, under renovation, paired 6/6 windows flank, pair gable dormers with 6/6 windows, round top louvered vent, interior chimney, dentil course, box cornice, no return. 10 1022 C
- 1428 108 WILLIAMS ST c. 1950. Minimal Traditional, two story, gable roof sides, brick, three bay facade, centered entrance, six panel door with sidelights and transom, attached one story porch at entrance, ornamental ironwork supports, 12/12 windows with shutters, end chimney, box cornice, no return. 9 1022 C

United States Department of the Interior
National Park Service

National Register Of Historic Places
Continuation Sheet

Section Number 7 Page 167

MID TOWN HISTORIC DISTRICT
Mobile
Mobile County, AL

- 1429 110 WILLIAMS ST c. 1960. Minimal Traditional, one story, gable roof sides, frame, three bay facade, centered entrance, attached gable over stoop with ornamental iron supports, picture window north adjacent with sidelights, jalousied windows south adjacent, box cornice, no return. 8 1022 N
- 1430 111 WILLIAMS ST c. 1940. Minimal Traditional, gable roof sides, frame, five bay facade, centered entrance, six panel door, sidelights, attached one story gable porch at stoop with square posts with capitals, 6/6 windows with shutters, box cornice, no return. 25 1020 C
- 1431 112 WILLIAMS ST c. 1945. Minimal Traditional, one story, gables, vinyl sided, three bay facade, attached gable at entrance, battered brick face, round top door with diamond light, louvered vent in gable, paired 3/1 windows with fabric awnings, end chimney, box cornice, no return. 7 1022 C
- 1432 113 WILLIAMS ST c. 1940. Minimal Traditional, one story, cross gable, frame, four bay facade, six panel door with fabric awning, 6/6 windows with shutters, staggered gables center of facade, triangular louvered vent in larger gable, box cornice, no return. 26 1020 C
- 1433 114 WILLIAMS ST c. 1960. Minimal Traditional, one story, gable roof sides, vinyl sided, four bay facade, inset porch at entrance, square post, wood door, aluminum windows, box cornice, no return. 6 1022 C
- 1434 115 WILLIAMS ST c. 1940. Minimal Traditional, one and a half story, brick, three bay facade, gable roof front, side entrance, six panel door, attached gable over stoop with ornamental iron supports, tripled 6/6 windows in south bay, paired 6/6 windows in gable, all windows feature burglar bars, side chimney. 27 1020 C
- 1435 116 WILLIAMS ST c. 1945. Minimal Traditional, one and a half story, gable roof sides, brick, five bay facade, wood door with sidelights, fabric awning over stoop, 6/6 windows with ornamental iron panels below, three board and batten gabled dormers with louvers, interior chimney, dentil course. 5 1022 C
- 1436 117 WILLIAMS ST c. 1940. Minimal Traditional, one and a half story, gable roof sides, frame, three bay facade, six panel door in classical surround with flanking 8/8 windows with shutters, pair gable dormers with 8/8 windows, box cornice, closed return. 28 1020 C
- 1437 120 WILLIAMS ST c. 1930. Bungalow, one and a half story, cross gable, brick, ell plan, three bay facade, pair tripled casement windows in front gable, fan transoms, 3/1 window in gable above, paired 3/1 windows in south bay, entrance in south side of cross gable, box cornice, no return. 4 1022 C

26 8
110

United States Department of the Interior
National Park Service

National Register Of Historic Places
Continuation Sheet

Section Number 7 Page 168

MID TOWN HISTORIC DISTRICT
Mobile
Mobile County, AL

- 1438 121 WILLIAMS ST c. 1940. Colonial Revival, one and a half story, gable roof sides, frame, five bay facade, attached gable porch covers three bays, Tuscan columns, dentil course, diamond light in gable, six panel front door, full height 9/9 windows with shutters, box cornice, no return. 29 1020 C
- 1439 122 WILLIAMS ST c. 1930. English Cottage Revival, one story, cross gable, ell plan, brick, three bay facade, recessed porch in cross gable, arched brick openings for entrance and south adjacent, paired 6/1 windows, gable roofline sweeps north across entrance, gothic louvered vent in gable, end chimney, exposed rafters. 3 1022 C
- 1440 123 WILLIAMS ST c. 1940. English Cottage Revival, one story, cross gable, brick, four bay facade, centered cross gable with double shouldered chimney up center, flanked by casement windows, half lunette louvered vents flank chimney in gable, inset porch north bay, fabric awning, screening obscures door, 9/1 window in south bay, exposed rafters. 30 1020 C
- 1441 124 WILLIAMS ST c. 1945. Minimal Traditional, two story, gable roof sides, aluminum sided, three bay facade, six panel door with fabric awning over stoop, bay window north adjacent, paired 6/6 windows with shutters south adjacent, wall dormer center bay with 6/6 window, box cornice, no return. 2 1022 C
- 1442 125 WILLIAMS ST c. 1940. Minimal Traditional, one and a half story, gable roof sides, brick and frame, four bay facade, recessed porch covers half of facade, square brick pillars, six panel door, paired 6/1 windows with shutters, offcenter shed roof dormer with two pairs 6/1 windows with shutters, interior chimney. 31 1020 C
- 1443 128 WILLIAMS ST c. 1950. Minimal Traditional, one and a half story, gable roof sides, brick, three bay facade with attached one bay gable wings east and west, paired 6/6 windows, attached gable over stoop, wood door, three gable dormers with 6/6 windows. 1 1022 C
- 1444 129 WILLIAMS ST c. 1960. Minimal Traditional, one story, gable roof sides, brick, five bays, recessed porch with fluted iron supports, six panel door, 12/12 windows with shutters, box cornice, no return. 32 1020 N
- 1445 151 WILLIAMS ST c. 1945. Minimal Traditional, one and a half story, cross gable, brick, clapboarded gables, modern wood door, sidelights and transom, attached offcenter gable porch, pierced brick columns, 6/6 windows, box cornice, no return, one story guest house rear, gable roof sides, brick. 33 1020 C
- 1446 152 WILLIAMS ST c. 1940. Classical Revival, one story, gable roof sides, frame, five bay facade, attached gable portico with Tuscan columns covers three bays, six panel door, flanked by 12/12 windows, louvered lunette in gable, box cornice. 35 1021 C

cb
1022

United States Department of the Interior
National Park Service

National Register Of Historic Places
Continuation Sheet

Section Number 7 Page 169

MID TOWN HISTORIC DISTRICT
Mobile
Mobile County, AL

- 1447 154 WILLIAMS ST c. 1945. Minimal Traditional, one story, gable roof sides, frame, four bay facade, six panel door, 12/12 windows with shutters, offcenter gable with ornamental iron supports over stoop, interior chimney, box cornice. 34 1021 C
- 1448 155 WILLIAMS ST c. 1955. Minimal Traditional, one story, gable roof sides, four bays, brick, two bays frame section south attached, recessed porch in frame section, paired square posts with decorative infill, metal casement windows, scalloped pattern below eave, box cornice, no return. 34 1020 N
- 1449 156 WILLIAMS ST c. 1945. Minimal Traditional, one story, cross gable, ell plan, frame, five bay facade, entrance in cross gable, inset with ornamental iron supports, six panel door, 6/6 windows with shutters in gable, picture window in center bay with flanking 12/12 windows, aluminum awning windows in north bay, interior chimney. 33 1021 C
- 1450 157 WILLIAMS ST c. 1940. Minimal Traditional, one story, cross gables, frame, three bay facade, attached offcenter gable porch with square posts, six panel door, paired 3/1 windows, roofline of porch sweeps wouth, smaller gable over south bay, fabric awning over south window, end chimney, exposed rafters. 1 1021 C
- 1451 159 WILLIAMS ST c. 1945. Minimal Traditional, one story, gable roof sides, brick, two bay facade, wood door with lunette light, attached gable over stoop with ornamental ironwork, gable open, tripled 6/6 windows. 2 1021 C
- 1452 160 WILLIAMS ST c. 1940. Minimal Traditional, one and a half story, cross gable, frame, four bay facade with south bay open as a porte-cochere, six panel door, attached gable over stoop with Tuscan columns, louvered vent, 3/1 windows, chimney north adjacent entrance, two gable dormers with 3/1 windows, exposed rafters. 32 1021 C
- 1453 161 WILLIAMS ST c. 1925. Bungalow, one story, hip roof, frame, three bay facade, attached offcenter gable porch with paired square posts on brick plinths with pierced brick balustrade, screened, Craftsman door, paired 3/1 windows, lunette louver in gable, box cornice, interior chimney. 3 1021 C
- 1454 162 WILLIAMS ST c. 1930. Bungalow, one story, gable roof front, vinyl sided, attached offcenter gable porch with shed roof extension over rest of facade, squat box battered columns on high brick plinths, three bays, wood door, flanked by paired Craftsman windows, interior chimney. 31 1021 C
- 1455 163 WILLIAMS ST c. 1930. Bungalow, one story, cross gable on hip, ell plan, frame, four bay facade, attached shed roof porch with square posts on brick plinths, Craftsman door, 3/1 windows with burglar bars, gable peak over porch at eaveline, end chimney, box cornice, closed return. 4 1021 C

cb 3
1021

United States Department of the Interior
National Park Service

National Register Of Historic Places
Continuation Sheet

Section Number 7 Page 170

MID TOWN HISTORIC DISTRICT
Mobile
Mobile County, AL

- 1456 164 WILLIAMS ST c. 1930. Bungalow, one story, gable roof front, aluminum sided, brick up to window sills at facade, three bay facade, attached offcenter gable porch with box columns on brick plinths, metal awning, Craftsman door flanked by paired 1/1 windows, light with flanking louvered vents in gable, knee braces, box cornice, closed return. 30 1021 C
- 1457 165 WILLIAMS ST c. 1930. Bungalow, one story, gable on hip front, three bay facade, brick, centered door obscured by burlar door, curved bay window north adjacent, paired 6/1 windows south adjacent with metal awning, side chimney, box cornice. 5 1021 C
- 1458 166 WILLIAMS ST c. 1940. Minimal Traditional, one story, cross gables on hip, aluminum sided, three bay facade, round top entrance, round top window south adjacent, chimney center of facade with two pots, tripled 6/1 windows in front gable, round top louvered vent, box cornice, no return. 29 1021 C
- 1459 167 WILLIAMS ST c. 1940. Minimal Traditional, one story, frame, cross gable, ell plan, four bay facade, centered entrance, round top door, cross gable features paired 9/1 windows, louvered vent, roofline sweeps south over entrance, double shouldered chimney to south flanked by round top windows, exposed rafters, interior chimney. 6 1021 C
- 1460 168 WILLIAMS ST c. 1930. Bungalow, one story, jerkin head gable sides, frame, three bay facade, centered entrance, attached gable porch with box columns with capitals, wood doors, flanked by tripled and paired Craftsman windows, end chimney, box cornice, no return. 28 1021 C
- 1461 169 WILLIAMS ST c. 1940. Minimal Traditional, one story, gable roof sides, frame, three bay facade, centered entrance, round top door, attached gable over stoop with battered brick face, tripled 6/1 windows north adjacent, doubled 6/1 windows south adjacent, fabric awnings, end chimney, box cornice. 7 1021 C
- 1462 170 WILLIAMS ST c. 1930. Bungalow, one story, hip roof, frame, attached offset hip roof porch with square brick pillars has been infilled with frame and picture windows, canvas awnings over windows, exposed rafters, side chimney. 27 1021 C
- 1463 171 WILLIAMS ST c. 1930. English Cottage Revival, one story, cross gable, three bay facade, brick, wood door with three lights, attached gable over stoop with battered brick face, arched opening, chimney north adjacent with stepped single shoulders, casement windows, louvered vent in cross gable, box cornice, no return. 8 1021 C
- 1464 180 WILLIAMS ST c. 1925. Bungalow, one story, hip roof, frame, three bay facade, attached offcenter hip roof porch with square, pierced brick pillars, single wood post at center of porch, wood door, paired 6/1 windows, box cornice, side chimney. 26 1021 C

United States Department of the Interior
National Park Service

National Register Of Historic Places
Continuation Sheet

Section Number 7 Page 171

MID TOWN HISTORIC DISTRICT
Mobile
Mobile County, AL

- 1465 182 WILLIAMS ST c. 1925. Bungalow, one story, gable roof front, frame, three bay facade, recessed porch covers facade, battered, boxed columns on brick plinths, balustraded, metal awning across facade, louvered vents in gable, porte-cochere south side. 25 1021 C
- 1466 184 WILLIAMS ST c. 1925. Bungalow, one and half story, gable roof sides, frame, three bay facade,, recessed porch covers facade, paired Tuscan columns on brick plinths, multi-light door with sidelights and transom, paired 3/1 windows, shed roof dormer with tripled 3/1 windows, end chimney. 24 1021 C
- 1467 186 WILLIAMS ST c. 1925. Bungalow, one and a half story, frame, three bay facade, recessed porch covers facade, Tuscan columns with iron railing, six panel door flanked by paired aluminum windows, hip roof dormer with 6/6 window with shutters, exposed rafters. 23 1021 C
- 1468 200 WILLIAMS ST c. 1925. Bungalow, duplex, one and a half story, hip roof, brick, three bay facade, recessed porch covers facade, arched openings with arches accented by contrasting red on tan brick, two front doors with burglar doors, flanked by 2/2 windows, gable dormer with stained glass window, purlins, box cornice. 22 1021 C
- 1469 204 WILLIAMS ST c. 1930. Minimal Traditional, one story, gable roof sides, frame, three bay facade, inset porch covers two bays, gable over steps, square posts with capitals, 2x4 balustrade, metal casement windows, ornamental burglar bars on windows under porch, box cornice, no return. 21 1021 C
- 1470 206 WILLIAMS ST c. 1925. Bungalow, duplex, one story, gable roof sides, frame, four bay facade, attached gable porch with tripled box columns with capitals on brick plinths, screened, two Craftsman front doors, 6/1 windows, louvered lunette in gable, box cornice, closed return. 20 1021 C
- 1471 208 WILLIAMS ST c. 1930. Bungalow, one story, gable roof sides, frame, three bay facade, six panel door, attached gable porch over stoop, tripled square columns with capitals, casement windows, interior chimney, exposed rafters. 19 1021 C
- 1472 250 WILLIAMS ST c. 1920. Bungalow, one story, gable roof front, frame, three bay facade, recessed porch covers facade, battered, boxed columns on brick plinths, Craftsman door, 3/1 windows, louvered vent, exposed rafters. 18 1021 C
- 1473 252 WILLIAMS ST c. 1950. Minimal Traditional, one story, gable on hip roof, asbestos sided, four bay facade, centered two bay gable, six panel door with fabric awning over stoop, horizontal light windows, lunette louvered vent, box cornice, no return. 17 1021 C

26 3
1021 C

United States Department of the Interior
National Park Service

National Register Of Historic Places
Continuation Sheet

Section Number 7 Page 172

MID TOWN HISTORIC DISTRICT
Mobile
Mobile County, AL

- 1474 254 WILLIAMS ST c. 1900. Victorian Cottage, one story, gable on hip, frame, three bay facade, offcenter gabled bay with full height 1/1/1 windows, recessed porch covers two bays, Tuscan columns on paneled plinths, modern wood door, two interior stuccoed chimneys, box cornice, closed return. 16 1021 C
- 1475 256 WILLIAMS ST c. 1925. Bungalow, one and a half story, jerkin head gable roof sides, frame, three bay facade, recessed porch covers facade, box columns, infilled with clapboarded knee wall and glass, fabric awning across facade, 6/1 windows, door not visible, shed roof dormer with three horizontal multi-light windows, en chimney, exposed rafters. 15 1021 C
- 1476 258 WILLIAMS ST c. 1925. Bungalow, one story, gable roof sides, frame, three bay facade, recessed porch covers facade, square posts on brick plinths with cross piece capitals, gable over steps, Craftsman door, flanked by paired 3/1 windows, end chimney, exposed rafters. 14 1021 C
- 1477 260 WILLIAMS ST c. 1960. Minimal Traditional, one story, gable roof front, two bay facade, asbestos sided, brick veneer up to window sill level, 1/1 windows, triangular louvered vent in gable, box cornice, no return. 13 1021 N
- 1478 262 WILLIAMS ST c. 1925. Bungalow, one story, gable roof front, frame, two bay facade, recessed porch covers facade, battered box columns at corners, square box columns on plinths flank steps, balustraded, six panel door with sidelights, 6/1 windows, louvered vents, knee braces, exposed rafters. 12 1021 C
- 1479 300 WILLIAMS ST c. 1920. Vernacular, one story, gable roof sides, frame, two bay facade, wood door with window, paired 6/6 windows, kick-off shed roof porch with square posts and balustraded, box cornice, no return. 11 1021 C
- 1480 304 WILLIAMS ST c. 1965. One story, flat roof, picture windows along street, aluminum door, metal building. 10 1021 N
- 1481 307- 11 WILLIAMS ST c. 1950. Art Deco, theatre, one story along sidewalk with aluminum windows and doors, raised superstructure with flat tops and curves. 9 1021 C
- 1482 5 WISTERIA AVE c. 1940. English Cottage Revival, one story, cross gable, ell plan, vinyl sided, attached gable porch south end with ornamental iron supports, entrance north adjacent with gable over stoop, paired 6/1 windows, single shouldered chimney at north side entrance, Gothic light in main gable, box cornice, no return. 15 1037 C

26 =
206 =

United States Department of the Interior
National Park Service

National Register Of Historic Places
Continuation Sheet

Section Number 7 Page 173

MID TOWN HISTORIC DISTRICT
Mobile
Mobile County, AL

- 1483 7 WISTERIA AVE c. 1940. Minimal Traditional, one and a half story, cross gable, ell plan, aluminum sided, four bay facade, inset porch adjacent two bay gable, Tuscan columns, ornamental iron railing, six panel door with sidelights, paired 6/1 windows south adjacent, pair 6/1 windows in front gable, single gable dormer with 6/6 light, box cornice, no return. 16 1037 C
- 1484 8 WISTERIA AVE c. 1940. Minimal Traditional, one story, gable roof sides, frame, three bay facade, centered entrance, six panel door, attached gable over stoop with paired slender columns, arch in gable, door flanked by 12/12 window north side and paired 6/6 windows with shutters south side, end chimney, exposed rafters. 14 1037 C
- 1485 9 WISTERIA AVE c. 1940. English Cottage Revival, one and a half story, cross gable, ell plan, frame, four bay facade, entrance north adjacent cross gable, six panel door, attached gable porch over stoop with square brick pillar, bank three 6/6 windows in gable, smaller 6/6 window in half story, exposed rafters, interior chimney. 17 1037 C
- 1486 10 WISTERIA AVE c. 1940. English Cottage Revival, one story, gable roof sides, vinyl sided, three bay facade, centered attached gable with battered brick face, inset porch south side with square posts with brackets, screened, Gothic louvered vent in side gables, exposed rafters, end chimney. 13 1037 C
- 1487 12 WISTERIA AVE c. 1940. Minimal Traditional, duplex, one story, gable roof sides, frame, four bays, attached shed roof porch with square posts covers two entrances, wood doors, flanking 12/12 windows with shutters, exposed rafters. 12 1037 C
- 1488 14 WISTERIA AVE c. 1940. Minimal Traditional, one story, cross gable, ell plan, frame, four bay facade, front gable features sweeping roofline to south over porch, wood door, 6/6 windows, interior chimney, lunette louvered vent in gable. 11 1037 C
- 1489 200 WOODLANDS AVE c. 1940. Colonial Revival, two story, gable roof sides, stucco, three bay facade, centered entrance, six panel door with sidelights and fan sunburst motif, attached one story gable porch over stoop with box columns, paired 6/6 windows with decorative keystone, quoins at corners, one story gable roof wing south side, box cornice, no return. 12 1038 C
- 1490 202 WOODLANDS AVE c. 1940. Colonial Revival, one and a half story, gable roof sides, frame, three bay facade, centered entrance, six panel door in classical surround, attached one story hip roof porch with square posts with capitals and balustraded, 8/8 windows with shutters flank entrance, three wall dormers with 6/6 windows, half story overhangs slightly with drop pendent at corners, end chimney, box cornice, no return. 11 1038 C
- 1491 203 WOODLANDS AVE c. 1945. Minimal Traditional, one story, cross gable, ell plan, frame, five bay facade, attached shed roof porch covers three bays and abutts cross gable, box columns with ornamental iron railing and screened, metal awning wraps porch, pair 9/9 windows with shutters in cross gable, box cornice, no return, triangular vent in gables. 33 1037 C

United States Department of the Interior
National Park Service

National Register Of Historic Places
Continuation Sheet

Section Number 7 Page 174

MID TOWN HISTORIC DISTRICT
Mobile
Mobile County, AL

-
- 1492 204 WOODLANDS AVE c. 1940. Bungalow, one story, hip roof, stucco, three bay facade, water table with belt course, attached offcenter hip roof porch with stucco pillars with capitals, six panel door, paired 3/1 windows, side chimney, box cornice, gabled louvered vent south elevation. 10 1038 C
- 1493 205 WOODLANDS AVE 1928. Bungalow, N. H. Holmes, Sr. architect, N. H. Holmes, III architect of wing (c. 1985), one and a half story, gable roof sides, brick with frame gables, attached gable porch covers center of facade, square brick pillars, casement windows, Craftsman door, wing to north side, rear, slate roof. 2 1038 C
- 1494 206 WOODLANDS AVE c. 1930. Spanish Revival, one story, ceramic tile hip roof, stucco, attached hip roof wings offcenter facade and north elevation behind plane of facade, center projecting gable bay center of facade, round top 3/1 window with planter box, paired 3/1 windows with sills and eared lintels, interior chimney, box cornice. 9 1038 C
- 1495 207 WOODLANDS AVE c. 1940. English Cottage Revival, one and a half story, gable roof sides, stucco, four bay facade, wood door with leaded window, shutters, casement windows with shutters, three gable dormers with casement windows, box cornice, closed return, interior chimney. 3 1038 C
- 1496 208 WOODLANDS AVE c. 1940. Colonial Revival, two story, gable roof sides, frame, three bay facade, centered entrance, six panel door with sidelights and fan transom, attached one story gable porch over stoop, paired Tuscan columns, arch in gable, paired 6/6 windows with shutters, end chimney, attached two story gable wing south end. 8 1038 C
- 1497 210 WOODLANDS AVE c. 1930. Tudor Revival, one and a half story, brick and stucco, cross gables, round top entrance in stucco gable with accented random rusticated bricks and rusticated brick surround around door frame, casement windows, half timbering in gables, louvered vents, wall dormer south adjacent entrance with paired multi-light windows, gable wing rear north elevation with pair gable dormers with casement windows. 7 1038 C
- 1498 211 WOODLANDS AVE c. 1930. Tudor Revival, one and a half story, cross gables, brick, stucco, pair staggered gables north end facade, northernmost one brick with bay window, larger gable half-timbered with round top wood door, rusticated brick accenting around door, casement windows, end chimney. 4 1038 C
- 1499 213 WOODLANDS AVE c. 1930. Colonial Revival, two story, cross gable, brick, six bay facade, centered entrance, six panel door with sidelights and round top transom, soldiered surround, 8/8 windows with shutters, two bay gable cross gable south adjacent, round louvered vent, box cornice, closed return, interior chimney with corbeled cap, attached one story carport north end. 5 1038 C
- 1500 215 WOODLANDS AVE c. 1930. English Cottage Revival, one and a half story, cross gable, ell plan, brick, three bay facade, large bay window in cross gable, 6/6 windows, six panel door in side of cross gable, chimney at south bay of facade, no cornice. 6 1038 C

United States Department of the Interior
National Park Service

National Register of Historic Places
Continuation Sheet

MID TOWN HISTORIC DISTRICT
Mobile
Mobile County, AL

Section number 8 Page 1

8. Statement of Significance

Community Planning (Criterion A)

The Midtown Historic District is significant as an early 20th century suburban expansion of Mobile to the west. This area is typical of Mobile's predominantly middle class housing boom west of downtown between 1900 and 1950. Several distinctive suburban developments representing the architectural styles of their periods are located within the Midtown District, including Bienville and Demouy Avenues (1920), Florence Place (1926), Silverwood (1927), Williams Court (1930), Japonica Avenue (1939), Audubon Place (1940), Benedict Place (1941), and Elizabeth Place (1941). Some of these developments feature open entrance gates with the name of the street (Florence Place, Silverwood, Williams Court) as well as period street lights. Florence Place originally featured a fountain in the center of the development but this was filled in during the 1950s and is now a landscaped oval. The Midtown Historic District is further significant for Memorial Park (1918, # 1004) at its southeast corner. This landscaped park was designed by Mobile architect George Rogers as a World War I memorial and includes a free standing colonnade, fountain and azaleas and live oak trees. The Midtown Historic District is also significant for several other landscape elements besides the park, namely fully intact live oak canopys most notably over Bienville Avenue (1920) and Florence Place (1926). These elements demonstrate the importance of an attractively designed and maintained environment to the early residents of the Midtown District. The mature tree canopys and well-maintained Memorial Park give the district a sylvan quality and coolness during the hot summer months. The Midtown District is further significant for its variety of trees and plants placed along the streets, including live oak trees, water oak trees, several varieties of palm trees, as well as crepe myrtles, azaleas and camellias. Many of these trees and plants were planted as early as the turn of the century and have achieved full, mature growth, giving the district a shady, wooded character.

United States Department of the Interior
National Park Service

National Register of Historic Places
Continuation Sheet

MID TOWN HISTORIC DISTRICT
Mobile
Mobile County, AL

Section number 8 Page 2

Architecture (Criterion C)

The Midtown Historic District is significant for its concentration of early to mid-twentieth century middle class housing reflecting national stylistic trends. Among the intact architectural styles represented in this district are the Queen Anne, Colonial Revival, American Foursquare, Dutch Colonial Revival, English Cottage Revival, Tudor Revival, Spanish Colonial Revival, Bungalow and Minimal Traditional. The district is further significant for a number of mid-19th century Gulf Coast Cottages which were among the first houses constructed in the area. These include 4 Audubon Place (1840, # 23) and 2009 Old Shell Road (c. 1850, # 1133). The district is also significant for its strong thematic streets like Florence Place (1926, Mission Revival), Bienville and Demouy Avenues (1920, Bungalow) and Japonica Avenue (1939, Minimal Traditional). The Midtown District is also significant for the number of local architects who worked in the area, including George Rogers, C. L. Hutchisson, Sr., C. L. Hutchisson, Jr. and Nicholas Holmes, Sr.

Historical Summary

During Mobile's first one hundred years (1711-1811) the area encompassed by the Midtown Historic District was undeveloped forest. During the periods of French (1711-1763) and British (1763-1780) control little occurred in the area. During the Spanish period (1780-1813) however, the first attempts were made to settle the woods to the west of the town. The area was carved into two Spanish Land Grants. The Dubroca Tract, which covers much of the eastern half of the district, was granted to Benjamin Dubroca by the Spanish government on February 26, 1803. Immediately to the west, the Murrell Tract covers much of the western half of the district, and was granted to John Murrell on May 7, 1804. Both of these grants were quite large at 800 arpens each (Hamilton, 500). Dubroca and Murrell were determined to settle their land, and each built a house and began farming. Dubroca had several acres under cultivation and Murrell brought in cattle and hogs (Hamilton, 500).

United States Department of the Interior
National Park ServiceNational Register of Historic Places
Continuation SheetSection number 8 Page 3MID TOWN HISTORIC DISTRICT
Mobile
Mobile County, AL

Mobile did not prosper under any of its colonial governments, in large part due to the royal monopolies on trade, and during the War of 1812 came peaceably under American control (McLaurin, 35). The owners of the Spanish Land Grants in the area subsequently applied to the United States government for new titles. As American settlers filtered down to the Gulf Coast from the eastern seaboard, the old Spanish tracts were sold or leased by their original owners. Portions of the Dubroca Tract were sold to William Kennedy in 1816. Kennedy did little with the property, and his brother Joshua took title in 1825. In 1842 Joshua Kennedy leased about thirty acres south of Dauphin Street to Michael Carlen (Scruggs, 1). Carlen moved onto the property and built a one and a half story Gulf Coast Cottage for his family. The Carlen House (# 1178) still stands and is operated today by the Museum of the City of Mobile. The building is a typical example of a mid-19th century Gulf Coast Cottage, with its recessed porch, box columns and five bay facade. There was originally a separate kitchen (now destroyed). Carlen planted cabbages on his property, and also ran a small grocery on Dauphin Street downtown.

During the mid-19th century a number of small farms spread into the area. Dauphin Street (called Dauphin Way) and Old Shell Road (called Spring Hill Shell Road) were dirt tracks leading from downtown Mobile out to the resort community of Spring Hill, a few miles west, and these roads allowed some penetration of the area by settlers. At the same time Michael Carlen was establishing his farm, a Colonel Deas built a large Gulf Coast Cottage a little further west. Colonel Deas' house (#23) is a sophisticated blending of Greek Revival and vernacular elements. It is a one and a half story structure with boxed columns, four panel entrance door with sidelights and transom and three dormers in the roof. Deas imported a number of cattle and operated a dairy on the site for many years. In 1939 the house was moved off of Dauphin Street to front Audubon Place, then just being developed. On the north side of Dauphin Street a woman named Margaret Greene erected a small one and a half story cottage in 1851. Like Carlen nearby, she planted cabbages on her property, and her house served as a stop for carriages making the day-long journey out to Spring Hill (Smith, 10). Over the next fifty years Greene's small house was

United States Department of the Interior
National Park Service

National Register of Historic Places
Continuation Sheet

MID TOWN HISTORIC DISTRICT
Mobile
Mobile County, AL

Section number 8 Page 4

enlarged and improved, eventually becoming a Victorian mansion (#368).

On the eve of the Civil War, Mobile's western city limit was at Catherine Street, about a mile east of Carlen's property. A smattering of cabbage farms, a dairy and a small sawmill were about all that existed along the city's western reaches. With the coming of the war, Mobile was heavily fortified by a series of earthworks running completely around the city. The small farms west of the city were unprotected, and little new growth occurred there until after the war. Mobile surrendered without a shot being fired in the spring of 1865, long after the city's strategic significance had been nullified with the Union capture of Forts Morgan and Gaines at the mouth of the bay in the summer of 1864 (McLaurin, 68).

Mobile struggled during the postwar years. The city's population nearly stagnated, growing from 30,000 souls in 1865 to only 39,000 by 1900 (McLaurin, 95). Even so, transportation improved, and the city began to push west with an electric streetcar line running out both Government and Dauphin Streets. By 1907 the Government Street line ran out to just west of Houston Street, and made a turn. The site was locally know as the Loop, and became a small commercial hub. The Dauphin Street line ran all the way out to Spring Hill as early as the 1870s (Sparks, 12). A number of people purchased land in the area for small farms, among them George Rickarby, a former blockade runner (Smith, 8). Rickarby bought some ten acres on Dauphin Street near the Carlen farm and built a two story house. His modest estate was known as Rickarby Place. His son, Elliot Rickarby, recalled in 1923 what the nearby Carlen farm (then owned by a descendent of Michael Carlen) was like, "When I first knew the property Mr. Carlen was a truck gardener, raising cabbages, potatoes, hay, etc., and as a boy, I frequently went on the property and shot birds with a sling shot, and at harvest time when they were cutting hay, having frequently gathered with the boys of the neighborhood to catch rabbit, etc." (Scruggs, 1). Though the Rickarby house subsequently burned, Rickarby Street (north of Murphy High School) preserves the name in the neighborhood today.

**United States Department of the Interior
National Park Service****National Register of Historic Places
Continuation Sheet****MID TOWN HISTORIC DISTRICT
Mobile
Mobile County, AL**Section number 8 Page 5

By the turn of the century then, the area was easily accessible from downtown, and lightly developed with a handful of 10 to 40 acre farms. The first significant subdivision came in 1901 with the surveying and platting by local real estate agents of Dauphin Heights, a narrow strip of land just west of Fulton Street running north from Dauphin Street to Spring Hill Avenue (see plat map). Other subdivisions and new streets followed, Rickarby Street in 1902, Old Government in 1904 and Carlen Street in 1906. With the completion of the street car line at the Loop in 1907, growth accelerated.

Mobile's fortunes were improving, and during the first decade of the 20th century the city shook off the torpor of the postwar years. The railyards and docks expanded, attracting hundreds of workers, and new housing was desperately needed (McLaurin, 79). A number of houses were constructed along these newly platted streets. Those along the principal thoroughfares of Dauphin and Old Government were typically substantial two story frame buildings, of Victorian or Neo-Classical Revival styles (#s 344, 368, 1006, 1025). The residents of these new houses could easily catch the streetcars into town for work or shopping.

The next two decades witnessed full throttle development of this section of Mobile. By 1915 most of the area was within the city limits, and transportation continued to be improved with faster street car service, new street construction and paving. Two of the Midtown Historic District's defining landmarks were constructed during this time, Memorial Park (# 1004) and Murphy High School (# 162).

Like the residents of most American cities, Mobilians enthusiastically supported their troops during the First World War. After the Armistice, a local group, the Mother's Army and Navy League, began to raise funds for a monument to the local men killed in the conflict. A site was donated to them near the Loop, and local architect George Rogers designed the monument and accompanying landscaping. Rogers came to Mobile in 1901, claiming to be a Columbia educated architect, though the school has no record of his ever having attended. Nevertheless, he was a gifted designer, and is locally noted for his man buildings including the Van Antwerp Building (1906) Mobile's first skyscraper and the

**United States Department of the Interior
National Park Service**

**National Register of Historic Places
Continuation Sheet**

**MID TOWN HISTORIC DISTRICT
Mobile
Mobile County, AL**

Section number 8 Page 6

Bellingrath Gardens and Home. Rogers took a personal interest in the World War I memorial project, and managed to get marble donated by the Sylacauga (Alabama) Marble Works (Mobile Press Register, 11/12/94). His design features a freestanding marble colonnade and fountain. Members of the American Legion planted oak trees in the park. The park was dedicated in 1926.

Murphy High School was built at the same time. In 1923 the Carlen family heirs sold nearly 30 acres to the Mobile County School Board as the site for a new high school. Ground was broken the following year, and the school opened in 1926 (Smith, 4). George Rogers was the architect and designed the complex in the Mission Revival style. The school consisted of some 700 students during its early days, and ball games played on its athletic fields were an attraction for the entire neighborhood.

During the 1920s, several neighborhoods opened up (see plat map). These included Bienville and Demouy Avenues in 1920, Florence Place in 1926, Carlen Heights, opposite the High School, in 1927, Silverwood and a portion of South Street, also in 1927. All of these streets quickly filled with houses built by Mobile's growing middle class. During 1922, for example, the city issued 265 building permits (Bond). In 1927, a fine Spanish Revival apartment building (# 1007) was constructed. By 1930 Mobile's population was over 50,000, and the port and railyards were prospering. A number of these streets quickly became distinguished by their architectural styles; Bienville and Demouy Avenues as Bungalow streets and Florence Place as a Mission Revival/Spanish Revival Street. Florence Place and Silverwood also featured entrance gates and period street lighting. Such neighborhoods were locally promoted in the press and proved popular.

In 1930, Williams Court was opened and three brick houses constructed. Then came the Depression and building ground to a halt. In Florence Place, sales slowed, then stopped. When things improved and sales finally did resume, buyers balked at constructing their homes in the Mission Style, and the developers backed off their early attempt to create a themed street (Interview, Paul Scruggs).

**United States Department of the Interior
National Park Service**

**National Register of Historic Places
Continuation Sheet**

**MID TOWN HISTORIC DISTRICT
Mobile
Mobile County, AL**

Section number 8 Page 7

During the 1930s and 1940s, the city limits pushed further to the west, and new streets were opened off of Dauphin Street (see plat map). These included Japonica Avenue in 1939, Audubon Place in 1940, and Benedict Place and Elizabeth Place in 1941. To the west and south of Murphy High School, new houses began to be constructed on streets like South Street, Glenwood Street and Clearmont Street. Back to the east, towards Bienville and Demouy Avenues, what few vacant lots there were quickly sold and had houses placed on them (Interview, Paul Scruggs). Houses built during these decades were typical of those being erected by the middle class all over the country. Regional variations like tall windows and doors, wide halls, and slatted porch ceilings disappeared. Most of the streets in the area were finally paved, alleviating the clouds of choking dust and muddy pools that were common before. The Loop matured as a commercial hub, with a drug store (# 1), theatre (# 1481), grocery and other small businesses.

By 1950, the area known as the Midtown Historic District was well within the city limits, mostly built out, and very popular with the middle class. Since 1990, many of the older families have sold their houses to younger couples with small children, and the Midtown area is enjoying something of a renaissance. With fully grown oak canopies over many of its streets and charming historic houses, the Midtown Historic District is one of Mobile's most popular residential locations.

United States Department of the Interior
National Park Service

National Register of Historic Places
Continuation Sheet

MID TOWN HISTORIC DISTRICT
Mobile
Mobile County, AL

Section number 9 Page 1

9. Major Bibliographical References

Bond, Amy Bryant. "Midtown Historic District." Around Downtown,
October 1999.

McLaurin, Melton and Michael Thomason. Mobile: The Life and Times
of a Great Southern City. Woodland Hills, California: Windsor
Publications, 1981.

Gould, Elizabeth B. From Fort to Port: An Architectural History
of Mobile, 1711-1918. Tuscaloosa: University of Alabama
Press, 1987.

----- . From Builders to Architects: The Hobart
Hutuchisson Six. Montgomery: Black Belt Press, 1997.

Hamilton, Peter J. Colonial Mobile. 1897, Reprint University of
Alabama Press, 1976.

Interview, Paul Scruggs, Real Estate Developer, 10/15/94.

Mobile City Directories, 1900-1950. Mobile Municipal Archives.

Mobile Register, 1900-1994, various articles and trade editions.
Local History Branch, Mobile Public Library.

Scruggs, Nancy. "Historic Murphy District Association, 1990."
Unpublished manuscript. Mobile Historic Development
Commission.

Smith, Mary. "Historic Murphy District Association, Inc., 1992-
93." Unpublished manuscript. Mobile Historic Development
Commission.

Sparks, Asa. "Mobile, Birthplace of 4-Wheel Brakes," Traction and
Models Magazine. July 1967.

Tax Records, City of Mobile, 1850-1950. Microfilm at Mobile
Municipal Archives.

**United States Department of the Interior
National Park Service**

**National Register of Historic Places
Continuation Sheet**

**MID TOWN HISTORIC DISTRICT
Mobile
Mobile County, AL**

Section number 10 Page 1

10. Verbal Boundary Description

The boundary of the Midtown Historic District is shown as the solid line on the accompanying map, entitled "Midtown Historic District," scaled 1:2400.

Boundary Justification

The boundaries of the Midtown Historic District were drawn to include the greatest concentration of 1900-1950 contributing historic buildings in the area. The northwestern corner of the district is abutted by the existing Ashland Place Historic District and the eastern boundary by the existing Old Dauphin Way Historic District.

United States Department of the Interior
National Park ServiceNational Register of Historic Places
Continuation SheetMID TOWN HISTORIC DISTRICT
Mobile
Mobile County, ALSection number photos Page 1Photographic KeyMidtown Historic District
Mobile, Mobile County, Alabama
John Sledge, photographer
February 1997-November 1998
MHDC Negative File--MB #1000-1043

Photo #	Description (Roll/Frame #)
1.	Streetscape, Spring Hill Avenue, camera facing west from Silverwood (1043/30).
2.	Streetscape, Silverwood gates from Spring Hill Avenue, camera facing south (1043/29).
3.	Streetscape, Silverwood, camera facing south (1043/28).
4.	Detail, Silverwood streetlight (1043/27).
5.	Streetscape, Florence Place, camera facing north from Old Shell Road (1043/32).
6.	Streetscape, Old Government Street, camera facing west (1003/35).
7.	4 Audubon Place, camera facing northwest (1035/4).
8.	2009 Old Shell Road, camera facing north (1011/17).
9.	1864 Old Government Street, camera facing north (1001/23).
10.	1916 Old Government Street, camera facing north (1002/34).
11.	1901 Old Shell Road, camera facing south (1011/9).
12.	1832 Dauphin Street, camera facing north (1007/25).
13.	2019 Old Shell Road, camera facing north (1011/19).
14.	123 Bienville Avenue, camera facing east (1013/31).
15.	122 Bienville Avenue, camera facing northwest (1013/35).
16.	119 Florence Place, camera facing west (1040/13).
17.	115 Florence Place, camera facing west (1040/11).
18.	101 Bienville Avenue, camera facing east (1013/20).
19.	114 South Street, camera facing west (1018/27).
20.	17 Japonica Ave., camera facing east (1034/23).
21.	123 Florence Place, camera facing west (1040/15).
22.	115 Mohawk Street, camera facing east (1028/34).
23.	116 Glenwood Street, camera facing west (1026/16).
24.	Garage, 17 Japonica Avenue, camera facing east (1034/24).

**United States Department of the Interior
National Park Service**


**National Register of Historic Places
Continuation Sheet**








**MID TOWN HISTORIC DISTRICT
Mobile
Mobile County, AL**

Section number photos Page 2

Photograph Key continued

- 25. 2063 Summerville Ct., camera facing southwest (1038/25).
- 26. 2058 Summerville Ct., camera facing northeast (1038/26).
- 27. 1850 Airport Blvd., camera facing west (1000/5).
- 28. 307-11 Williams Street, camera facing east (1001/22).
- 29. 11 Japonica Avenue, camera facing east (1034/21).
- 30. 110 South Street, camera facing northwest (1018/29).
- 31. 214 Glenwood Street, camera facing west (1026/1).
- 32. 208 Glenwood Street, camera facing west (1026/3).
- 33. 124 South Street, camera facing west (1018/24).
- 34. 111 Mohawk Street, camera facing east (1028/32).



-  Contributing Building
-  Non-Contributing Building
-  Midtown Historic District Boundary
-  Property Lines
-  Schools
-  RR Track
-  Edge of Pavement

**City of Mobile
Midtown Historic District**

600 0 600 Feet

1" = 600'



City of Mobile GIS
01/31/2000

S.Kearney \giserver\gisdata\histdev\
project\midtowndist.apr