

STATE:
New York


COUNTY:
Nassau

FOR NPS USE ONLY

ENTRY DATE

**NATIONAL REGISTER OF HISTORIC PLACES
INVENTORY - NOMINATION FORM
FOR FEDERAL PROPERTIES**

(Type all entries - complete applicable sections)



1. NAME

COMMON:
* * Sagamore Hill National Historic Site

AND/OR HISTORIC:
Sagamore Hill

2. LOCATION

STREET AND NUMBER:
Sagamore Hill Road

CITY OR TOWN:
Oyster Bay

CONGRESSIONAL DISTRICT:
11

STATE:
New York

CODE:
36

COUNTY:
Nassau
New York

CODE:
059

3. CLASSIFICATION

CATEGORY (Check One)	OWNERSHIP	STATUS	ACCESSIBLE TO THE PUBLIC
<input type="checkbox"/> District <input checked="" type="checkbox"/> Site <input type="checkbox"/> Object <input checked="" type="checkbox"/> Building <input type="checkbox"/> Structure <input type="checkbox"/> Public Acquisition: <input type="checkbox"/> In Process <input type="checkbox"/> Being Considered	<input checked="" type="checkbox"/> Public <input type="checkbox"/> Private <input type="checkbox"/> Both	<input checked="" type="checkbox"/> Occupied <input type="checkbox"/> Unoccupied <input type="checkbox"/> Preservation work in progress	Yes: <input checked="" type="checkbox"/> Restricted <input type="checkbox"/> Unrestricted <input type="checkbox"/> No

PRESENT USE (Check One or More as Appropriate)

<input type="checkbox"/> Agricultural	<input type="checkbox"/> Government	<input checked="" type="checkbox"/> Park	<input type="checkbox"/> Transportation	<input type="checkbox"/> Comments
<input type="checkbox"/> Commercial	<input type="checkbox"/> Industrial	<input type="checkbox"/> Private Residence	<input type="checkbox"/> Other (Specify)	
<input checked="" type="checkbox"/> Educational	<input type="checkbox"/> Military	<input type="checkbox"/> Religious		
<input type="checkbox"/> Entertainment	<input checked="" type="checkbox"/> Museum	<input type="checkbox"/> Scientific		

4. AGENCY

National Park Service

REGIONAL HEADQUARTERS: (If applicable)
North Atlantic Region

STREET AND NUMBER:
150 Causeway Street

CITY OR TOWN:
Boston, Massachusetts

STATE:
Massachusetts

CODE:
25

5. LOCATION OF LEGAL DESCRIPTION

COURTHOUSE, REGISTRY OF DEEDS, ETC.:
County Clerk's Office

STREET AND NUMBER:
240 Old Country Road

CITY OR TOWN:
Mineola

STATE:
New York

CODE:
36

6. REPRESENTATION IN EXISTING SURVEYS

TITLE OF SURVEY:
Area Investigation Report

DATE OF SURVEY: July 5-7, 1961 Federal State County Local

DEPOSITORY FOR SURVEY RECORDS:
Branch of History, National Park Service

STREET AND NUMBER:
Interior Building 19th and C Street N.W.

CITY OR TOWN:
Washington

STATE:
D.C.

CODE:
11

SEE INSTRUCTIONS

STATE: Massachusetts

COUNTY: Nassau

ENTRY NUMBER

DATE

FOR NPS USE ONLY

7. DESCRIPTION

CONDITION

(Check One)

Excellent Good Fair Deteriorated Ruins Unexposed

(Check One)

Altered Unaltered

(Check One)

Moved Original Site

DESCRIBE THE PRESENT AND ORIGINAL (if known) PHYSICAL APPEARANCE

Built during 1884-85, Sagamore Hill is a solidly built Queen Anne styled structure of frame and brick, the wood siding a mustard color, the bricks red and the trim green. It is a rambling structure consisting of twenty three rooms. On the first floor are a large center hall, the library which served as Theodore Roosevelt's private office, the dining room, the kitchen, and the spacious North Room, added in 1904. On the second floor are the family bedrooms, the nursery, guest rooms and the original bath room. On the top floor is the Gun Room (T.R.'s retreat), Theodore Jr.'s room, the school room, the linen room, the sewing room and the servant's room. Furnishings throughout the house are original Roosevelt pieces. On the south and west side of the house is a spacious porch.

The house is surrounded by landscaped lawn. There are thirty two acres of large, second-growth timber of which oaks are most prominent.

Until the North Room was added in 1904, the house as designed by Rich and Lamb was not changed. After the house was purchased in the early 1950's by the Theodore Roosevelt Association a number of repairs and alterations were required to provide tour circulation for the public and protection to the place and its contents. The present condition is good.

Significance - 1st Order

	lat.		long.
Latitude and Longitude: NW	40° 53' 16"	x	73° 30' 16"
NE	40° 53' 16"	x	73° 29' 24"
SE	40° 53' 01"	x	73° 29' 24"
SW	40° 53' 01"	x	73° 30' 16"

Acreage: 85 acres

Treatment Recommended: Exterior preservation, some interior restoration of 2nd and 3rd floor room finishes.

Preliminary cost estimate for above: \$75,000

Photograph enclosed

SEE INSTRUCTIONS

NATIONAL REGISTER OF HISTORIC PLACES
INVENTORY - NOMINATION FORM

(Continuation Sheet)

STATE New York	
COUNTY Nassau	
FOR NPS USE ONLY	
ENTRY NUMBER	DATE

(Number all entries)

7. Description (continued for Sagamore Hill National Historic Site)

There are other frame-structures on the grounds dating from the Presidential years:

1. Grey Cottage (1910), 26' x 2" long and 20'x4" wide, used as a residence by Roosevelt's valet and coachman. The house has undergone a number of mainly interior alterations during the mid 1960's. It is used by the park as a residence. It has been well maintained and, except for the rear (south) side, the exterior appearance (wood clapboard) has been only slightly changed from the original.

Significance : 2nd Order

Treatment recommended: preservation

Preliminary cost estimate for above \$2,000/yr.

Photograph enclosed

2. Ice House, an eight sided building of brick and shingles with five feet high brick walls, six inches wide, and asbestos roof shingles. Altered between 1949 - 1953 to accommodate public toilet rooms. It is in good condition

Significance: 2nd Order

Treatment recommended: Restoration

Preliminary cost estimate for above: \$1,000

Photograph enclosed

3. New Barn (1907), converted to park residence. Westerly half of building is now used as living quarters, easterly half as garage. Structure has wood sidings and the roof is made of cedarwood shingles. Building contains five rooms, including kitchen and one bath; has also a small screened-in porch and a storage attic. Condition of the building is good.

Significance: 2nd Order

Treatment recommended: preservation

Preliminary cost estimate for above: \$1,000/yr.

Photograph enclosed.

4. Carriage House and Tool Shed, wood construction, adjacent structures. Their condition is good.

Significance: 2nd Order

Treatment recommended: preservation

Preliminary cost estimate for above: \$1,000/yr.

Photograph enclosed

NATIONAL REGISTER OF HISTORIC PLACES
INVENTORY - NOMINATION FORM

(Continuation Sheet)

STATE New York	
COUNTY Nassau	
FOR NPS USE ONLY	
ENTRY NUMBER	DATE

(Number all entries)

7. Description (continued for Sagamore Hill National Historic Site)

(2nd continuation sheet)

5. Gardner's Shed. Its condition is good.

Significance: 2nd Order

Treatment recommended: preservation

Preliminary cost estimate for above: \$200/yr.

Photograph enclosed

6. Chicken House, part of building used as tool shed exhibit area, and another as storage for souvenir shop and canteen. Construction is clapboard siding, asphalt shingle roof.

Significance: 2nd Order

Treatment recommended: Restoration

Preliminary cost estimate for above: \$30,000

Photograph enclosed.

7. Old Orchard, home of Theodore Roosevelt, Jr. built in 1930-1938. A two story brick structure in excellent condition. Built on a four acre tract, once part of Sagamore Hill; used now as park headquarters. Condition of building is good.

Significance: 2nd Order

Recommended treatment: preservation

Preliminary Cost estimates for above: \$3,000/yr.

Photograph enclosed

8. Windmill, ca. 1905, pumped water for Sagamore Hill. Reconstructed in 1971; it has steel wheel on top of a frame of wood about 65' high. Its condition is fairly good.

Significance: 2nd Order

Recommended Treatment: preservation

Preliminary cost estimate for above: \$500/yr.

8. SIGNIFICANCE

PERIOD (Check One or More as Appropriate)

- | | | | |
|--|---------------------------------------|--|--|
| <input type="checkbox"/> Pre-Columbian | <input type="checkbox"/> 16th Century | <input type="checkbox"/> 18th Century | <input checked="" type="checkbox"/> 20th Century |
| <input type="checkbox"/> 15th Century | <input type="checkbox"/> 17th Century | <input checked="" type="checkbox"/> 19th Century | |

SPECIFIC DATE(S) (If Applicable and Known)

AREAS OF SIGNIFICANCE (Check One or More as Appropriate)

- | | | | |
|--|---|---|--|
| <input type="checkbox"/> Aboriginal | <input checked="" type="checkbox"/> Education | <input checked="" type="checkbox"/> Political | <input type="checkbox"/> Urban Planning |
| <input type="checkbox"/> Prehistoric | <input type="checkbox"/> Engineering | <input type="checkbox"/> Religion/Philosophy | <input type="checkbox"/> Other (Specify) _____ |
| <input type="checkbox"/> Historic | <input type="checkbox"/> Industry | <input checked="" type="checkbox"/> Science | _____ |
| <input type="checkbox"/> Agriculture | <input type="checkbox"/> Invention | <input type="checkbox"/> Sculpture | _____ |
| <input checked="" type="checkbox"/> Architecture | <input type="checkbox"/> Landscape Architecture | <input checked="" type="checkbox"/> Social/Humanitarian | _____ |
| <input checked="" type="checkbox"/> Art | <input checked="" type="checkbox"/> Literature | <input type="checkbox"/> Theater | _____ |
| <input type="checkbox"/> Commerce | <input type="checkbox"/> Military | <input type="checkbox"/> Transportation | _____ |
| <input type="checkbox"/> Communications | <input type="checkbox"/> Music | | |
| <input checked="" type="checkbox"/> Conservation | | | |

STATEMENT OF SIGNIFICANCE

The significance of this site is that it was the home of Theodore Roosevelt from 1885 until his death in 1919.

It was on the wide porch of Sagamore Hill that Roosevelt was formally notified of his nominations as Governor of New York in 1898, as Vice-President in 1900, and as President in 1904.

During the Presidential years Sagamore Hill was the summer White House. Roosevelt met the envoys of Japan and Russia separately in the library and then brought them face to face to inaugurate the Conference that ended in the Treaty of Portsmouth, New Hampshire on Sept. 5, 1905.

SEE INSTRUCTIONS

9. MAJOR BIBLIOGRAPHICAL REFERENCES

- Francis Wilshin, Historic Resource Study, Sagamore Hill (Denver Service Center, 1972)
- Norman M. Souder, Historic Structures Report, Part II, Architectural Data Section, Sagamore Hill (National Park Service, 1964)

10. GEOGRAPHICAL DATA

LATITUDE AND LONGITUDE COORDINATES DEFINING A RECTANGLE LOCATING THE PROPERTY			O R	LATITUDE AND LONGITUDE COORDINATES DEFINING THE CENTER POINT OF A PROPERTY OF LESS THAN TEN ACRES		
CORNER	LATITUDE	LONGITUDE		LATITUDE	LONGITUDE	
	Degrees Minutes Seconds	Degrees Minutes Seconds		Degrees Minutes Seconds	Degrees Minutes Seconds	
NW	40° 53' 19"	73° 30' 16"	U T M on map	° ' "	° ' "	
NE	40° 53' 19"	73° 29' 19"				
SE	40° 53' 01"	73° 29' 19"				
SW	40° 53' 01"	73° 30' 16"				
APPROXIMATE ACREAGE OF NOMINATED PROPERTY:			85 acres			
LIST ALL STATES AND COUNTIES FOR PROPERTIES OVERLAPPING STATE OR COUNTY BOUNDARIES						
STATE:	CODE	COUNTY:	CODE			
STATE:	CODE	COUNTY:	CODE			
STATE:	CODE	COUNTY:	CODE			
STATE:	CODE	COUNTY:	CODE			

11. FORM PREPARED BY

NAME AND TITLE: <u>Ricardo Torres-Reyes, Historian</u>		DATE: <u>4/75</u>
BUSINESS ADDRESS: <u>North Atlantic Region</u>		
STREET AND NUMBER: <u>150 Causeway Street</u>		PHONE:
CITY OR TOWN: <u>Boston</u>	STATE: <u>Massachusetts</u>	CODE: <u>25</u>

12. CERTIFICATION OF NOMINATION

State Liaison Officer recommendation:

Yes
 No
 None

State Liaison Officer Signature

In compliance with Executive Order 11593, I hereby nominate this property to the National Register, certifying that the State Liaison Officer has been allowed 90 days in which to present the nomination to the State Review Board and to evaluate its significance. The recommended level of significance is National State Local

[Signature]
Federal Representative Signature

Date

Title

NATIONAL REGISTER VERIFICATION

I hereby certify that this property is included in the National Register.

NHS
Director, Office of Archeology and Historic Preservation

Date _____

ATTEST:

NHS [Signature]
Keeper of The National Register


Date 10/20/74

SEE INSTRUCTIONS



zone 18
D - 4526-680 N
626-000 E
C - 4527-220
626-000

Mapped by the Army Map Service
Edited and published by the Geological Survey
Revised by the Geological Survey in cooperation with New York
Department of Transportation
Control by USGS, USCGS and Nassau County
Planimetry by photogrammetric methods from aerial photographs
taken 1941. Topography by planetable surveys 1943. Revised 1967
and 224 (1966). This information is not intended for navigational purposes
Selected hydrographic data compiled from US&GS Charts 222 (1963)
and 224 (1966). This information is not intended for navigational purposes
Polyconic projection. 1927 North American datum
10,000-foot grids based on New York coordinate system, Long Island zone
and Connecticut coordinate system
1000-meter Universal Transverse Mercator grid ticks, zone 18,
shown in blue
Red tint indicates areas in which only landmark buildings are shown



ROAD CLASSIFICATION

Heavy-duty	Light-duty
Medium-duty	Unimproved dirt

RECEIVED
AUG 11 1975
NATIONAL
REGISTER

BAYVILLE, N.Y.—CONN
NE/4 OYSTER BAY 15' QUADRANGLE
N4052.5—W7330/7.5
1967
AMS 6265 I NE—SERIES V821





RECEIVED

AUG 11 1975

NATIONAL
REGISTER



Mapped by the Army Map Service
Edited and published by the Geological Survey
Revised by the Geological Survey in cooperation with New York
Department of Transportation
Control by USGS, USC&GS and USCE
Topography by planetable surveys 1931-1932.
Revised from aerial photographs taken 1966. Field checked 1967
Selected hydrographic data compiled from USC&GS Charts 221
and 224 (1967). This information is not intended for navigational purposes
Polyconic projection. 1927 North American datum
10,000-foot grids based on New York coordinate system, Long Island zone,
and Connecticut coordinate system
1000-meter Universal Transverse Mercator grid ticks, zone 18,
shown in blue
Red tint indicates areas in which only landmark buildings are shown



CONTOUR INTERVAL 20 FEET
DATUM IS MEAN SEA LEVEL
DEPTH CURVES AND SOUNDINGS IN FEET—DATUM IS MEAN LOW WATER
SHORELINE SHOWN REPRESENTS THE APPROXIMATE LINE OF MEAN HIGH WATER
THE MEAN RANGE OF TIDE IS APPROXIMATELY 7.4 FEET

THIS MAP COMPLIES WITH NATIONAL MAP ACCURACY STANDARDS
FOR SALE BY U.S. GEOLOGICAL SURVEY, WASHINGTON, D.C. 20242
A FOLDER DESCRIBING TOPOGRAPHIC MAPS AND SYMBOLS IS AVAILABLE ON REQUEST



ROAD CLASSIFICATION
Heavy-duty — Light-duty
Medium-duty — Unimproved dirt
State Route

LLOYD HARBOR, N. Y.—CONN.
NW/4 NORTHPORT 15' QUADRANGLE
N4052.5—W7322.5/7.5
1967
AMS 6365 IV NW—SERIES V821





NATIONAL REGISTER OF HISTORIC PLACES
PROPERTY MAP FORM

(Type all entries - attach to or enclose with map)

STATE New York	
COUNTY Nassau	
FOR NPS USE ONLY	
ENTRY NUMBER	DATE

SEE INSTRUCTIONS

1. NAME

COMMON: Sagamore Hill National Historic Site
AND/OR HISTORIC: Sagamore Hill

2. LOCATION

STREET AND NUMBER:
Sagamore Hill Road

CITY OR TOWN:
Oyster Bay

STATE:
New York

CODE
36

COUNTY:
New York

CODE
059

3. MAP REFERENCE

SOURCE: U.S. Geological Survey: 7.5 minute Series
(1) Bayville Quadrangle (2) Lloyd Harbor Quadrangle


SCALE: 1: 24000

DATE: (1) 1967 (2) 1967

4. REQUIREMENTS

TO BE INCLUDED ON ALL MAPS

1. Property boundaries where required.
2. North arrow.
3. Latitude and longitude reference.



UNITED STATES DEPARTMENT OF THE INTERIOR
NATIONAL PARK SERVICE

**NATIONAL REGISTER OF HISTORIC PLACES
INVENTORY -- NOMINATION FORM**

FOR FEDERAL PROPERTIES

FOR NPS USE ONLY

RECEIVED MAY 7 1979

DATE ENTERED

approved
1/31/80

SEE INSTRUCTIONS IN *HOW TO COMPLETE NATIONAL REGISTER FORMS*
TYPE ALL ENTRIES -- COMPLETE APPLICABLE SECTIONS

1 NAME

HISTORIC
Sagamore Hill National Historic Site

AND/OR COMMON
Sagamore Hill

2 LOCATION

STREET & NUMBER
Sagamore Hill Road

CITY, TOWN

Oyster Bay

STATE
New York

VICINITY OF
CODE

NOT FOR PUBLICATION
CONGRESSIONAL DISTRICT

COUNTY
Nassau

CODE

3 CLASSIFICATION

CATEGORY	OWNERSHIP	STATUS	PRESENT USE
<input type="checkbox"/> DISTRICT	<input checked="" type="checkbox"/> PUBLIC	<input checked="" type="checkbox"/> OCCUPIED	<input type="checkbox"/> AGRICULTURE
<input checked="" type="checkbox"/> BUILDING(S)	<input type="checkbox"/> PRIVATE	<input type="checkbox"/> UNOCCUPIED	<input checked="" type="checkbox"/> MUSEUM
<input type="checkbox"/> STRUCTURE	<input type="checkbox"/> BOTH	<input type="checkbox"/> WORK IN PROGRESS	<input checked="" type="checkbox"/> PARK
<input checked="" type="checkbox"/> SITE	<input type="checkbox"/> PUBLIC ACQUISITION	<input type="checkbox"/> ACCESSIBLE	<input type="checkbox"/> PRIVATE RESIDENCE
<input type="checkbox"/> OBJECT	<input type="checkbox"/> IN PROCESS	<input type="checkbox"/> YES: RESTRICTED	<input type="checkbox"/> RELIGIOUS
	<input type="checkbox"/> BEING CONSIDERED	<input checked="" type="checkbox"/> YES: UNRESTRICTED	<input type="checkbox"/> SCIENTIFIC
		<input type="checkbox"/> NO	<input type="checkbox"/> TRANSPORTATION
			<input type="checkbox"/> MILITARY
			<input type="checkbox"/> OTHER:

4 AGENCY

REGIONAL HEADQUARTERS: (If applicable)
National Park Service, NARO

STREET & NUMBER

15 State Street

CITY, TOWN

Boston

VICINITY OF

STATE

Mass.

5 LOCATION OF LEGAL DESCRIPTION

COURTHOUSE,
REGISTRY OF DEEDS, ETC. County Clerk's Office

STREET & NUMBER

240 Old Country Road

CITY, TOWN

Mineola

STATE

New York

6 REPRESENTATION IN EXISTING SURVEYS

TITLE
Area Investigation Report

DATE

July 5-7, 1961

FEDERAL STATE COUNTY LOCAL

DEPOSITORY FOR
SURVEY RECORDS Branch of History, National Park Service, Interior Building

CITY, TOWN

Washington

STATE

DC

7 DESCRIPTION

CONDITION		CHECK ONE	CHECK ONE
<input type="checkbox"/> EXCELLENT	<input type="checkbox"/> DETERIORATED	<input type="checkbox"/> UNALTERED	<input checked="" type="checkbox"/> ORIGINAL SITE
<input checked="" type="checkbox"/> GOOD	<input type="checkbox"/> RUINS	<input checked="" type="checkbox"/> ALTERED	<input type="checkbox"/> MOVED DATE _____
<input type="checkbox"/> FAIR	<input type="checkbox"/> UNEXPOSED		

DESCRIBE THE PRESENT AND ORIGINAL (IF KNOWN) PHYSICAL APPEARANCE

Sagamore Hill National Historic Site, the "Summer White House" of President Theodore Roosevelt, is located in Oyster Bay, New York, on the northwestern shore of Long Island. The 85 acre site of farm and woodland on the Falmouth Moraine commands the highest elevation in the Cove Neck area and has 890 feet of frontage on Cold Spring Harbor. The property, basically L-shaped, is set in a terrain dominated by the coves, necks, spits and bays of the Long Island Sound.

The area surrounding the Site is primarily estate land of the village of Cove Neck. Though it is no longer as isolated as during the Roosevelts' residency, the surroundings are still moderately wooded with many small stands of old growth deciduous forest. At Oyster Bay, 2.8 miles west, are large sand and gravel quarries. Some land east of the Falmouth Moraine is still farmed. The eastern portion of the property (consisting of approximately 32 acres) has old second growth cover, chiefly oak and tulips, with a shallow freshwater pond, a salt marsh and creek, and about 900 feet of beach fronting on Cold Spring Harbor. A variety of birds, water fowl, and small mammals can be found within the area. This eastern portion of the park is being used, since 1968, as a National Environmental Study area.

The nearest urban centers are Hicksville (pop. 51,000), located ten miles south, and Huntington (pop. 12,000), in adjoining Suffolk County about seven miles to the east. New York City is 29 miles to the west.

Roosevelt began the construction of Sagamore Hill in 1884 on land purchased the year before from Thomas Youngs of Oyster Bay for \$10,000 cash, a mortgage for \$20,000 and the right "to remove the growing crops, and the crops stored in the farm barn," then the only building on the property.

A rough sketch map drawn by Roosevelt shortly after the estate purchase identifies main features such as roads, fields, woodlands, an orchard, fences, crops growing there, ponds and a spring. It indicates that the farm was in operation at the time and that the land was well suited to growing fruits and vegetables. In addition to a barn and orchard, the map shows a cornfield, a field of buckwheat and an asparagus bed. The northeast section of the property is identified as "cedar hill." This is located directly east of the orchard which is, in turn, east of the cornfield. The southeast and a major part of the southern portion of the property is identified as woodland. In addition to the cornfield, two other fields are shown--one some distance south of the barn, the other in the southwest section of the property. A road is shown running through the approximate center of the property. This is bisected by a road that passes just west of the barn to connect with a road that skirts the field of buckwheat on the north. Two ponds are identified, one in the north central part of the property, later named the "woodpile pond," and the other in the southeast corner, later called the "lower lake." A frog spring is shown in the north central section of "cedar hill." (Sagamore Hill NHS files)

The house that Theodore Roosevelt built in 1884-85 is quite free from later alterations with the exception of an addition, the North Room, made by the Roosevelts in 1905. The house is sited on the crest of a hill that, in Roosevelt's day, provided

UNITED STATES DEPARTMENT OF THE INTERIOR
NATIONAL PARK SERVICE

**NATIONAL REGISTER OF HISTORIC PLACES
INVENTORY -- NOMINATION FORM**

FOR NPS USE ONLY	
RECEIVED	MAY 7 1979
DATE ENTERED	approved 1/31/80

CONTINUATION SHEET

ITEM NUMBER 7

PAGE two

a commanding view in every direction, sweeping west to Oyster Bay and north to Long Island Sound. Some of this view is still visible from the third floor. The house is surrounded by extensive landscaped lawns beyond which, in all directions, are acres of large second-growth timber, primarily oak. The belts of woodland, interspersed with fields, separate the house and its ancillary buildings from all others.

The greater portion of the Sagamore Hill estate was woodland during Roosevelt's lifetime with the areas under cultivation varying with the seasons and good farming practices. There were at times, however, as many as forty acres of the full ninety-five being farmed.

The Sagamore Hill property was acquired by the Theodore Roosevelt Association in 1950, together with the furnishings and belongings accumulated by the Roosevelt family throughout the years.

The Association opened the house to the public in 1953. In July 1963 the Theodore Roosevelt Association donated the property to the United States government. It thereby became Sagamore Hill National Historic Site. The house and its contents, as well as the grounds, continue to be carefully preserved in like manner to when Theodore Roosevelt and his family lived there.

The most significant historic structures of the Site are as follows:

1. Sagamore Hill (No. NS1) (Constructed in 1885)

Theodore Roosevelt had Sagamore Hill built in 1884-85 at a cost of \$16,975.00. He commissioned the New York architects, Lamb and Rich, to design his new house in Oyster Bay, but a great many of his own ideas were incorporated into the design. Roosevelt wrote:

... I did not know enough to be sure what I wished in outside matters. But I had perfectly definite views what I wished in inside matters, what I desired to live in and with; I arranged all this so as to get what I desired insofar as my money permitted; and then Rich put on the outside cover with but little help from me. I wished a big piazza, very broad at the N.W. corner where we could sit in rocking chairs and look at the sunset; a library with a shallow bay window opening south; the parlor or drawing room occupying all the western end of the lower floor; as broad a hall as our space would permit; big fireplaces for logs; on the top floor the gun room occupying the western end so that north and west it looks over the sound and bay. I had to live inside and not outside the house; and while I should have liked to "express" myself in both, as I had to choose, I chose the former. (Letter by Theodore Roosevelt to Henry H. Saylor editor of Country Life in America dated 3 October 1915).

UNITED STATES DEPARTMENT OF THE INTERIOR
NATIONAL PARK SERVICE

**NATIONAL REGISTER OF HISTORIC PLACES
INVENTORY -- NOMINATION FORM**

FOR NPS USE ONLY	
RECEIVED	MAY 7 1978
DATE ENTERED	<i>approved</i> 1/31/80

CONTINUATION SHEET

ITEM NUMBER 7

PAGE three

The result is a solidly constructed frame and red brick structure which is in both plan and detail, a typical of the then popular Queen Anne architectural expressions that were contemporary and entirely appropriate to its location, architects and occupants.

The house is a large-scaled, rambling two-and-one-half stories with an attic and full basement, although from the interior there is a full third story. The foundations are twenty inches thick with joists, rafters and roof-boards that match the same massive proportions. The foundations and the raised basement are of local stone, mica schist, which is laid in squared rubble fashion.

The house features prominent gables, dormers, verandahs and a porte-cochere. The asymmetrical massing of the house is, in the context of latter nineteenth century architecture, turning toward a more horizontal and yet picturesque expression. The house has big open volumes, crowned by wide gable ends and dormers that reach outward expensively and not upwards, as in earlier Victorian styles. The shingles of the upper stories form a continuous skin that ties the varied planes and decorative shingle work into a smoothly flowing whole. This house's high voluminous roof and multi-directional massing characterize the change to the horizontal in design.

The house has many Queen Anne details on the exterior. The common bond red brick skin that covers the first floor and the mustard-colored and dark green-trimmed second and top floors provide fashionable latter nineteenth century color contrasts. There are terra-cotta sunflower medallion window decorations, sawn-wood ornament, a shaped verandah, imitation half-timbering in several dormer gables, all of which are expressions of the Queen Anne style. The gable and dormer ends are covered with a combination of clapboards and shingles that are wave and curved-end cut.

The verandah extends from the porte-cochere on the south facade around the west side where it widens to 18'6" and forms an outdoor sitting room, shaded by a large awning. There is a sawn-wood balustrade at the outer edge which continues with the verandah for a short distance along the west side of the north wing. A lattice-sided service porch with an openwork top is off the staff's kitchen and another porch is on the east side of the house. A small shingled porch and two decks open off the President's bedroom, bathroom and a Guest Room, respectively.

Window styles are varied, ranging from large single light sash to leaded, stained glass sash. Many upper sash are divided into small paned patterns. Two-over-two light sash are used in the service areas. Most of the windows on the first and second floors are fitted with exterior blinds. The ones on the third floor have been removed since 1953.

The house and porch roofs on Sagamore Hill were originally covered with wood shingles which were later covered over with asbestos shingles in 1950-52.

UNITED STATES DEPARTMENT OF THE INTERIOR
NATIONAL PARK SERVICE

**NATIONAL REGISTER OF HISTORIC PLACES
INVENTORY -- NOMINATION FORM**

FOR NPS USE ONLY

RECEIVED MAY 7 1979

DATE ENTERED

approved 1/31/80

CONTINUATION SHEET

ITEM NUMBER 7 PAGE four

The three massive chimneys on the main part of the house are decorated with elaborate checkered brick panels, achieved by recessing alternate bricks of a header-laid pattern, and each has lancet-like slots set below the raised and corbelled band course. The North Room chimney has the same scale and mass without the decorative treatment.

Sagamore Hill consists of twenty-three rooms. On the first floor are a large oak paneled and beamed entrance and stair hall, the library which served as Theodore Roosevelt's private office, the dining room, drawing room, kitchen (behind which was a laundry room), a pantry, and the spacious North Room added in 1905. On the second floor are the family and guest bedrooms, the nursery, an original bathroom and three later ones. The stair hall is centrally located and is lighted by a stained glass skylight. The rear (service) stair extends from the basement to the third floor. On the top floor is the Gun Room, Theodore Jr.'s room, the schoolroom, linen room, sewing room, and the cook's room and two maids' rooms. The unfinished attic was reached by a ship's ladder stair in a third floor closet.

The interior finish of the house is typical of the period. Most of the interior woodwork in the form of heavy oak paneling, wainscoting and elaborate mantels, is stained and varnished and most of the walls are covered with reproduction wallpaper of the general period.

The North Room (40' x 30'), designed by architect C. Grant LaFarge, was added to the house in 1905 in response to the President's need for a large, dignified room to receive the groups of delegates and distinguished visitors who visited Sagamore Hill. The exterior of the North Room blends well with the remainder of the house in that the walls are red brick and the shingled gable is similar to the gables on the house. A plaster or composition eagle and wreath decoration, by Gutzon Borglum, is set on a wood panel on the gable.

Joining the room to the north side of the house meant taking away a prominent entrance there and placing it from the west side of the hall to the porch. The room was built with two steps down from the entrance hall to a landing and with two more steps down to the room from each end of the landing. Built entirely of American and Philippine wood, the room with a high ceiling is a monochrome of luminous soft red-brown. The mantelpiece is of carmagon wood from the Philippines, the ceiling of American swamp cypress and hazel. The black walnut Ionic columns, set in pairs against all four walls, heighten the dignity of the room. The North Room also has a bold textured wallpaper of red and gold which is the only original wallpaper remaining in the house.

Until the North Room was added, the house as designed by Lamb and Rich was unchanged. After the property was purchased by the Theodore Roosevelt Association in 1950, a number of alterations were made in various parts of the house to provide for circulation of visitors and for the protection of the house and its contents.

UNITED STATES DEPARTMENT OF THE INTERIOR
NATIONAL PARK SERVICE

**NATIONAL REGISTER OF HISTORIC PLACES
INVENTORY -- NOMINATION FORM**

FOR NPS USE ONLY

RECEIVED

MAY 7 1979

DATE ENTERED

approved
1/3/80

CONTINUATION SHEET

ITEM NUMBER 7 PAGE five

The narrow hall that leads to the kitchen was straightened; the dumbwaiter and the stairs to the cellar from the kitchen were remodeled in conjunction with this alteration. In this same area the stairway from outside the kitchen door to this hall was changed from a narrow curved stairway to a stairway with two landings to accommodate the curve.

The room on the east of the kitchen, formerly the laundry, is an office for the Park Technician. The small service porch off the kitchen on the north was enclosed and made into a staff kitchen; steps from this to the outside face east.

There were changes also in the room on the second floor known as Alice's room and in the adjoining hall during the Association's restoration.

Because of using the third floor rooms as exhibit areas, one entirely new stairway, needed for better traffic circulation, was built from the second to the third floor on the northwest side of the house. The stairway from the second to the third floor on the southeast side of the house was widened. Metal louvres were added on the north and south sides of the attic when a large fan was installed.

The original wood shingled roof was covered with asbestos shingles while the interior alterations were being carried out.

Since 1963, the NPS has restored the top floor rooms as closely as possible to their appearance when the Roosevelts lived at Sagamore Hill. The restorations have included that of the original linen room, removal of false partitions, refinishing of varnished woodwork which had been painted, papering of rooms from which wallpaper had been removed, etc.

2. Gray Cottage (No. HS 2) (Constructed in 1910)

The Gray Cottage is a small wood frame clapboarded building which was built in 1910 to house the Roosevelts' coachman and valet and their families. It was divided into two apartments, one on each side of the house. It has been well maintained and except for the rear south side, the exterior is only slightly altered from its original appearance. In 1953 the house underwent a restoration, and a number of interior alterations were made during the 1960's for an adaptive reuse of the structure as a Park Service residence.

The Gray Cottage is a rectangular block 26'2" x 20', and is two-and-one-half stories with a medium pitch gable roof. The center of the front facade has a small enclosed storm porch with a shed roof. While the porch may not have been enclosed originally, there is evidence that it was done at a very early stage in the history of the house. There was, in addition, a rear porch which has since been removed. The house is modestly detailed with wooden corner boards and eaves returns.

UNITED STATES DEPARTMENT OF THE INTERIOR
NATIONAL PARK SERVICE

**NATIONAL REGISTER OF HISTORIC PLACES
INVENTORY -- NOMINATION FORM**

FOR NPS USE ONLY	
RECEIVED	MAY 7 1979
DATE ENTERED	<i>approved</i> 1/31/80

CONTINUATION SHEET

ITEM NUMBER 7 PAGE six

It has a full basement with poured concrete walls which are presumably reinforced, given that there is no evidence of cracking or unequal settlement. There is also an attic which is accessible by means of a staircase placed above the flight of stairs to the second story.

There are four symmetrically placed sash windows in each facade with wooden shutters and each gable end has a smaller window to light the attic. The roof now has a covering of wood shingles, which was probably the original roofing material.

3. Ice House (No. HS 3) (Constructed in 1885)

The Ice House is an octagonal building of red brick, walled to a height of five feet and capped by a very steep, pointed, asbestos shingled roof (Probably wooden originally). The building had a wooden floor originally and has since been adapted into use as public washrooms.

4. New Barn (No. HS 4) (Constructed in 1907)

When Roosevelt first bought the Sagamore Hill estate, the only standing structure was the Old Barn, which later was used not only for farming and carriage horses but as an adventure playground by the President, his children and the numerous cousins from nearby. When this building, estimated to be nearly a century old, collapsed in 1904, the New Barn was eventually built to replace it in 1907. The foundation stones of the Old Barn still remain. The New Barn is a wooden frame structure with asphalt shingled gambrel roof and with a partial basement. It had a large central opening, sliding doors and a cupola atop to provide ventilation.

It has been altered inside to serve as a park residence and garage. It now has five rooms, including a kitchen and one bath, and, also has a small screened porch and storage attic.

5. Carriage House and Tool Shed (Nos. HS 5 and 6) (Construction date unknown)

The Carriage House and Tool Shed are adjacent wooden frame structures, clapboarded and with shingled gable roofs. Both are one and one half stories, have overhanging eaves and wooden corner boards.

The Carriage House is oriented to the gable end and has two large flushboard doors with crossbracing and metal hinges.

6. Gardener's Shed (No. HS 7) (Construction date unknown)

The Gardener's Shed is a simple frame building with wooden board-and-batten siding, a shingled gable roof with a diamond shaped window in each gable end.

UNITED STATES DEPARTMENT OF THE INTERIOR
NATIONAL PARK SERVICE

**NATIONAL REGISTER OF HISTORIC PLACES
INVENTORY -- NOMINATION FORM**

FOR NPS USE ONLY

RECEIVED

MAY 7 1979

DATE ENTERED

approved 4/31/80

CONTINUATION SHEET

ITEM NUMBER

7

PAGE seven

7. Chicken House (No. HS 8) (Construction date unknown)

The Chicken House is of frame construction with clapboard siding and an asphalt shingle roof. Part of the building is now used as a tool shed exhibit area and part is a storage area for the souvenir shop and snack bar.

8. Windmill (No. HS 9) (Construction in ca. 1884-86; reconstructed in 1971)

The original windmill, constructed ca. 1884-86, pumped water for the Sagamore Hill estate. The present windmill is a 1971 reconstruction built to replace what was an essential part of the estate when Theodore Roosevelt lived there. It has a steel propeller on top of a wooden structure about 65' high.

There are other minor historic features on the Site related to the historic period (1884-1919). The Stable and Lodge, built prior to 1884, burned in 1947, and the stone foundations were covered with earth. The foundation is believed to be intact except for two large stones that were removed to accommodate a water line. The wood post-and-rail fences generally follow the historic fence line. The fence around the formal garden does not conform to the historic location because of the existence of the modern entrance road and parking area.

There are four original "TR" landmarks: a carved entrance stone, a carved pet cemetery stone, and two gate stones along with two stone and masonry retaining walls at the original entrance. Quentin Roosevelt's grave marker (brought from his grave in France) is also located near the house.

A Development Subzone contains several structures not related to the Roosevelt period:

1. Concession facility--constructed in 1951--this structure houses a gift shop and snack bar.
2. Kiosk--a summer and weekend information station built in 1968.
3. Maintenance building--built in 1938--this structure includes garages and work areas for the park maintenance staff and a two-bedroom apartment.
4. Foreman's Cottage--also built in 1938--this building is now used as a residence.

Another structure not associated with the life of Roosevelt is Old Orchard. This two-story Georgian home with brick veneer and slate shingle roof was built in 1938 by Theodore Roosevelt, Jr. The interior has been adapted to accommodate administrative offices, museum exhibits and residential quarters. The exterior retains its original appearance.

8 SIGNIFICANCE

PERIOD	AREAS OF SIGNIFICANCE -- CHECK AND JUSTIFY BELOW			
<input type="checkbox"/> PREHISTORIC	<input type="checkbox"/> ARCHEOLOGY-PREHISTORIC	<input type="checkbox"/> COMMUNITY PLANNING	<input type="checkbox"/> LANDSCAPE ARCHITECTURE	<input type="checkbox"/> RELIGION
<input type="checkbox"/> 1400-1499	<input type="checkbox"/> ARCHEOLOGY-HISTORIC	<input checked="" type="checkbox"/> CONSERVATION	<input type="checkbox"/> LAW	<input type="checkbox"/> SCIENCE
<input type="checkbox"/> 1500-1599	<input type="checkbox"/> AGRICULTURE	<input type="checkbox"/> ECONOMICS	<input type="checkbox"/> LITERATURE	<input type="checkbox"/> SCULPTURE
<input type="checkbox"/> 1600-1699	<input checked="" type="checkbox"/> ARCHITECTURE	<input type="checkbox"/> EDUCATION	<input type="checkbox"/> MILITARY	<input type="checkbox"/> SOCIAL/HUMANITARIAN
<input type="checkbox"/> 1700-1799	<input type="checkbox"/> ART	<input type="checkbox"/> ENGINEERING	<input type="checkbox"/> MUSIC	<input type="checkbox"/> THEATER
<input checked="" type="checkbox"/> 1800-1899	<input type="checkbox"/> COMMERCE	<input type="checkbox"/> EXPLORATION/SETTLEMENT	<input type="checkbox"/> PHILOSOPHY	<input type="checkbox"/> TRANSPORTATION
<input checked="" type="checkbox"/> 1900-	<input type="checkbox"/> COMMUNICATIONS	<input type="checkbox"/> INDUSTRY	<input checked="" type="checkbox"/> POLITICS/GOVERNMENT	<input type="checkbox"/> OTHER (SPECIFY)
		<input type="checkbox"/> INVENTION		

SPECIFIC DATES 1884

BUILDER/ARCHITECT Lamb & Rich

STATEMENT OF SIGNIFICANCE

Sagamore Hill is historically significant as the estate of Theodore Roosevelt, 26th President of the United States, who lived in this house from 1884 until his death in January, 1919. On the wide, shaded porch of Sagamore Hill, Roosevelt was formally notified of his nominations as Governor of New York in 1898, as Vice President in 1900, and as President in 1904. While Roosevelt served in the Presidency from 1901-1909, Sagamore Hill became the "Summer White House." A notable event in diplomatic history occurred during the summer of 1905 at Sagamore Hill when Roosevelt met envoys of Russia and Japan separately in the library for conferences that preceded negotiations at Portsmouth, New Hampshire, that resulted in the Treaty of Portsmouth on September 5, 1905, ending the Russo-Japanese War.

As well as its significant historical associations, Sagamore Hill is a distinguished architectural work, representing a transitional period in American architectural development. The Queen Anne details, strongly influenced by prevailing European tastes, were lavishly superimposed on an emerging and distinctly American articulation of mass. The voluminous massing and horizontality of the design, further enhanced by the sensitive LaFarge addition, are certainly of an exemplary nature.

The house's setting, astride a hill surrounded by lawns and deciduous forests, reflects Roosevelt's great love of nature and outdoor activity. A contemporary journalist observed, "One reason why Sagamore Hill has such great charm for [the President]... is that to use his own expression, 'he doesn't live in his neighbor's pocket.'" (Maurice Low, Saturday Evening Post, October 11, 1902) The grounds and the forests were the setting for the rambles and outdoor activities that Roosevelt is famous for and which his children, nephews and nieces delighted in, particularly when he would drop the affairs of state at their urging to join them. Three of his children were born there and all six grew up in the idyllic setting.

Within the park is a collection of momentos, gifts, hunting trophies, furniture, furnishings and other memorabilia that lend Sagamore Hill its distinctive character and are inextricably associated with the historic structure and the personality of Theodore Roosevelt. These objects give a fascinating and intimate insight into the various aspects of a truly singular life, and are as much a part of the historic scene as the joists, rafters and roof-boards of the Theodore Roosevelt home itself.

Mrs. Roosevelt lived at the house until her death in 1948. The careful preservation of Sagamore Hill and its collection assures, in accordance with the family's wishes, that a visitor feels the Roosevelts have stepped out for a moment and will return shortly. Sagamore Hill National Historic Site preserves a comfortably informal and intimate visit into the life of a great man.

9 MAJOR BIBLIOGRAPHICAL REFERENCES

Souder, Norman "Historic Structures Report Part II Architectural Data Section: Sagamore Hill" National Park Service, 1964

Wilshin, Francis "Historic Resource Study, Sagamore Hill" (Denver Service Center, 1972)

10 GEOGRAPHICAL DATA

ACREAGE OF NOMINATED PROPERTY 85

UTM REFERENCES

A	1,8	6,2,6	2,0,0	4,5	2,7	1,8,0	B	1,8	6,2,7	2,0,0	4,5	2,7	0,4,0
	ZONE	EASTING	NORTHING		ZONE	EASTING		ZONE	EASTING	NORTHING		ZONE	EASTING
C	1,8	6,2,7	2,0,0	4,5	2,6	8,0,0	D	1,8	6,2,6	0,0,0	4,5	2,6	6,8,0
	ZONE	EASTING	NORTHING		ZONE	EASTING		ZONE	EASTING	NORTHING		ZONE	EASTING

VERBAL BOUNDARY DESCRIPTION

LIST ALL STATES AND COUNTIES FOR PROPERTIES OVERLAPPING STATE OR COUNTY BOUNDARIES

STATE	CODE	COUNTY	CODE
STATE	CODE	COUNTY	CODE

11 FORM PREPARED BY

NAME / TITLE

Bronwyn Krog, Preservation Historian

ORGANIZATION

NARO

DATE

10/2/78

STREET & NUMBER

15 State Street

TELEPHONE

223-3778

CITY OR TOWN

Boston,

STATE

Mass.

12 CERTIFICATION OF NOMINATION

STATE HISTORIC PRESERVATION OFFICER RECOMMENDATION

YES ___ NO ___ NONE ___

STATE HISTORIC PRESERVATION OFFICER SIGNATURE

In compliance with Executive Order 11593, I hereby nominate this property to the National Register, certifying that the State Historic Preservation Officer has been allowed 90 days in which to present the nomination to the State Review Board and to evaluate its significance. The evaluated level of significance is National ___ State ___ Local.

FEDERAL REPRESENTATIVE SIGNATURE

TITLE

Bronwyn Krog Acting Ass't Dir Cultural Resources

DATE

1/24/79

FOR NPS USE ONLY

I HEREBY CERTIFY THAT THIS PROPERTY IS INCLUDED IN THE NATIONAL REGISTER

Carol D. Stull

DATE

1-31-80

DIRECTOR, OFFICE OF ARCHEOLOGY AND HISTORIC PRESERVATION

KEEPER OF THE NATIONAL REGISTER


ATTEST:

Lynn N. Kober

DATE

Jan. 30, 1980

KEEPER OF THE NATIONAL REGISTER



WILSONS MILL ROAD

COLD SPRING HARBOR

GARAGE & MAINTENANCE AREA

CARETAKER'S RESIDENCE

OLD CELLAR

HOUSE

TRAIL

CONCESSIONS

CARETAKER'S RESIDENCE

ROOSEVELT HOUSE

COTTAGE RESIDENCE

TRAIL

RECEIVED

MAY 7 1979

NATIONAL REGISTER


----- National Historic Site Boundary



National Environmental Study Area



Development Sub-zone



200 0 200 400 feet
60.96 0 60.96 121.92 meters



Westside of Sagamore Hill

#1

PROPERTY OF THE NATIONAL REGISTER

NPS Number 201566

Title:

Sagamore Hill Elevation West Side
Massau Co. N.Y.

Loc.

West Side of
Sagamore Hill


~~12/1~~

NATIONAL REGISTER OF HISTORIC PLACES
PROPERTY PHOTOGRAPH FORM*(Type all entries - attach to or enclose with photograph)*

STATE New York	
COUNTY Nassau	
FOR NPS USE ONLY	
ENTRY NUMBER	DATE

SEE INSTRUCTIONS

1. NAME			
COMMON: Sagamore Hill National Historic Site			
AND/OR HISTORIC: Sagamore Hill			
2. LOCATION			
STREET AND NUMBER: Sagamore Hill Road			
CITY OR TOWN: Oyster Bay			
STATE: New York	CODE 36	COUNTY: Nassau	CODE 059
3. PHOTO REFERENCE			
PHOTO CREDIT: National Park Service, Sagamore Hill			
DATE OF PHOTO: 1972			
NEGATIVE FILED AT: Sagamore Hill National Historic Site			
4. IDENTIFICATION			
DESCRIBE VIEW, DIRECTION, ETC. West Side of Sagamore Hill (Photo No. 1)			





**REST
ROOMS**

LADIES

Sagamore Hill National Historic
Site

Oyster Bay, New York

Nassau Co.

Photograph taken by Park Staff
November 1978. Negative at Park.

10/10

Ice House

(1885)

MAY 7 1979



Sagamore Hill National Historic
Site
Oyster Bay, New York
Photograph taken by Park staff
November, 1978

missed

20710

Gray Cottage
(1910)

MAY 7 1979



M

Sagamore Hill National Historic Site
Oyster Bay, New York

Chicken House MAY 7 1979

Grassm Co
The first window on the left be-
longs to the tool shed, the next
three belong to the Chicken House 3 of 10



Sagamore Hill National Historic Site
Oyster Bay , New York *Nassau Co*

Windmill

MAY 7 1979

A reconstruction of the 1905
windmill built by the National Park
Service in 1971.

4 of 10



Sagamore Hill National Historic
Site
Oyster Bay, New York.

Photograph taken by Park Staff
November, 1978. Negative
at Park

Masson C. S-0210

Carriage House and Tool Shed
MAY 7 1979

Double door - Carriage House
Single door- Tool Shed
Rear portion is Chicken House



Sagamore Hill National Historic
Site

Oyster Bay, New York

Photograph taken by Park Staff
November, 1978. Negative at
Park.

Nassau Co

6 of 10

Gardener's Shed

MAY 7 1979



Sagamore Hill National Historic Site
Oyster Bay, New York

MAY 7 1979

Barn (1907) MAY 7 1979

Wasson C

Photograph taken November, 1978,
Negative at Park

7/20



Sagamore Hill National Historic Site
Oyster Bay, New York

MAY 7 1979

Theodore Roosevelt Home (1884-1885)
(1905 North room addition on left)

Masson W

Photograph taken November, 1978 *8070*



Sagamore Hill National Historic
Site
Oyster Bay, New York

Photograph taken by Park staff,
November, 1978. Negative at
Park.

13

Theodore Roosevelt Home (1884-1885)

MAY 7 1979

Wasson C

7 of 10



11

MAY 7 1979

Theodore Roosevelt Home

(1884-1885)


missoula

1047 10



Sagamore Hill NHS
Cove Neck, NY
UTM References
Bayville N.Y. Quadrangle
A 18 626 200 45 27 180
D 18 626 000 45 26 680
Lloyd Harbor Quadrangle
B 18 627 200 45 27 060
C 18 627 200 45 26 800

Mapped by the Army Map Service
Edited and published by the Geological Survey
Revised by the Geological Survey in cooperation with New York
Department of Transportation
Control by USGS, USC&GS and USCE
Topography by planetable surveys 1931-1932.
Revised from aerial photographs taken 1966. Field checked 1967
Selected hydrographic data compiled from USC&GS Charts 221
and 224 (1967). This information is not intended for navigational purposes
Polyconic projection. 1927 North American datum
10,000-foot grids based on New York coordinate system, Long Island zone,
and Connecticut coordinate system
1000-meter Universal Transverse Mercator grid ticks, zone 18,
shown in blue
Red tint indicates areas in which only landmark buildings are shown



SCALE 1:24000
CONTOUR INTERVAL 20 FEET
DATUM IS MEAN SEA LEVEL
DEPTH CURVES AND SOUNDINGS IN FEET—DATUM IS MEAN LOW WATER
SHORELINE SHOWN REPRESENTS THE APPROXIMATE LINE OF MEAN HIGH WATER
THE MEAN RANGE OF TIDE IS APPROXIMATELY 7.4 FEET
THIS MAP COMPLIES WITH NATIONAL MAP ACCURACY STANDARDS
FOR SALE BY U.S. GEOLOGICAL SURVEY, WASHINGTON, D. C. 20542
A FOLDER DESCRIBING TOPOGRAPHIC MAPS AND SYMBOLS IS AVAILABLE ON REQUEST



ROAD CLASSIFICATION
Heavy-duty ——— Light-duty ———
Medium-duty ——— Unimproved dirt ———
State Route ○
LLOYD HARBOR, N. Y.—CONN.
NW/4 NORTHPORT 15' QUADRANGLE
N4052.5—W7322.5/7.5
1967
AMS 6365 IV NW—SERIES V821





Sagamore Hill, N.Y.
Cove Neck, N.Y.
UTM References
Bayville N.Y. Quadrangle
A 18 626 200 45 27 180
D 18 626 000 45 26 680
Lloyd Harbor Quadrangle
B 18 627 200 45 27 040
C 18 627 000 45 26 800

Mapped by the Army Map Service
Edited and published by the Geological Survey
Revised by the Geological Survey in cooperation with New York
Department of Transportation
Control by USGS, USC&GS and Nassau County
Planimetry by photogrammetric methods from aerial photographs
taken 1941. Topography by planetable surveys 1943. Revised 1967
Selected hydrographic data compiled from USC&GS Charts 222 (1963)
and 224 (1966). This information is not intended for navigational purposes
Polyconic projection. 1927 North American datum
10,000-foot grids based on New York coordinate system, Long Island zone
and Connecticut coordinate system
1000-metre Universal Transverse Mercator grid ticks, zone 18,
shown in blue
Red tint indicates areas in which only landmark buildings are shown



ROAD CLASSIFICATION

Heavy-duty	Light-duty
Medium-duty	Unimproved dirt

BAYVILLE, N.Y.-CONN.
N4052.5-W7330/7.5
1967
AMS 6265 I NE-SERIES V821

RECEIVED
MAY 7 1968
NATIONAL REGISTER

Property Sagamore Hill National Historic Site

66000096

State N.Y.

Working Number 5.7.79

Already on NR

TECHNICAL

CONTROL

Photos 10
Maps 2

pl
OK 5.21.79

home of T.R., 26th Pres of U.S., from 1884 to his death in 1919. The house served as a summer white house (1901-1909) and was the scene of the conference that led to the treaty ending the Russo-Japanese war. The house is also noteworthy for its architecture - it is a massive, 2 1/2 story, frame and brick Queen Anne style building. The 85 acre site includes outbuildings original to the estate and several modern Park Service buildings.

HISTORIAN

accept
Patrick Andrews
1/3/80

ARCHITECTURAL HISTORIAN

ARCHEOLOGIST

OTHER

HAER

Inventory _____

Review _____

The 85 acres are apparently the tract of land purchased in 1950 ~~from~~ by the Roosevelt Association + later given to the NPS. (It is only 10 acres short of T.R.'s original tract). Acreage is justified in part 8. State map has been provided with this resubmission.

REVIEW UNIT CHIEF

Accept
L. Babe 1/30/80

BRANCH CHIEF

KEEPER

National Register Write-up _____

Send-back _____

Entered _____

Federal Register Entry _____

Re-submit _____

INT:2106-74

Handwritten signatures and dates:
Approved
1/31/80
1/24/80

ROUTING AND REVIEW SLIP

1st Ord Sig

~~Form Not Signed by~~

THE ENCLOSED NOMINATIONS ARE ROUTED TO YOU FOR YOUR PROFESSIONAL REVIEW AND COMMENT ON THE CORRECTNESS AND ADEQUACY OF THE STATEMENTS AND EVALUATIONS CONTAINED THEREIN, SUPPLYING ADDITIONAL OR CORRECTIVE INFORMATION AS APPROPRIATE. REVIEWER WILL SIGN HIS NAME HEREON FOR LATER REFERENCE IF NECESSARY. USE ADDITIONAL SHEET FOR COMMENT IF NEEDED AND ATTACH HERETO.

NOMINATED PROPERTY: SAGAMORE HILL NHS: including

FROM AREA OF: 8 additional structures 2d Ord Sig

1 PA

CHIEF ARCHEOLOGIST:

I concur. This complex would qualify on at least three bases: J.R.'s home, signing of the Treaty of Portsmouth, and architectural.

SIGNED: Jackson W. Moore, Jr.

2 PD

CHIEF HISTORIAN:

OK

SIGNED: Harry W. Offord

3 PC

CHIEF HISTORICAL ARCHITECT:

OK

SIGNED: H. A. Judd

4 PC

REGISTRAR, LCS

PR KEEPER OF THE NATIONAL REGISTER:

C. O. Meek
Registrar, LCS
Tel. 343 2532

RECOMMENDED FOR THE NATIONAL REGISTER
 ENTERED ON THE LCS 03-21 1975

INT: 4937-1 REGISTRAR LCS

PLEASE RETURN TO REGISTRAR, LCS BY

MAR 31 1975

NAME OF PROPERTY Sagamore Hill NHS STATE N.Y.

The attached National Register Inventory-Nomination form is being returned to your office for clarification of the information indicated below. PLEASE RETURN THIS FORM WHEN THE NOMINATION IS RESUBMITTED.

7 Description: _____

8 Statement of Significance: May we assume that all of this N.H.S. is considered nationally significant and is administered as class 6 land? Yes

9 Bibliography: _____

10 Geographical Data -- Acreage: _____
UTM Reference(s): _____
Verbal Boundary Description: _____

12 Certification: _____

Photographic Coverage: _____

Map Coverage: a sketchmap would be helpful.

Other: _____

Questions concerning this nomination may be directed to _____
on the National Register staff, telephone _____

Thank you for your attention to the above items.

Charles [Signature]
Chief, Branch of Registration

Date: 1.9.76

INT:2105-74

Property

Sagamore Hill NHS

Already on NR
7-25-1962

State

New York

Working Number

8.11.75. ~~104~~

TECHNICAL

Photos 8
Maps 3

#12 needs date
needs SHPO sign.
UTM coordinates missing

CONTROL

pl
8.13.75

Should have included discussion of
TR Jr. + his house.

HISTORIAN

Livengood
10-4-76

ALREADY ON REGISTER.

ARCHITECTURAL HISTORIAN

SUPPLEMENTARY DESCRIPTION

LEBORNEY
8-26-75

PHOTOS TOO SMALL . 1930'S GEORGIAN REVIVAL INCLUDED

ARCHEOLOGIST

OTHER

HAER

Inventory _____
Review _____

REVIEW UNIT CHIEF

OK ~~OK to be~~
Cole 10-15-76 ~~filed~~
Cole 11-6-75

BRANCH CHIEF

[Signature]
10.15.76

KEEPER

[Signature]
10/25/76

National Register Write-up _____
Federal Register Entry _____

Send-back _____
Re-submit 7.22.76

Entered _____

INT:2106-74



United States Department of the Interior

NATIONAL PARK SERVICE
WASHINGTON, D.C. 20240

IN REPLY REFER TO:
H34-PC

AUG 6 1975



Memorandum

To: Director, Office of Archeology and Historic Preservation

Through: Federal Representative to the National Register
Department of the Interior

From: Federal Representative, National Park Service

Subject: Nominations to the National Register of Historic Places

The enclosed nominations from the North Atlantic Region of the National Park Service are submitted in support of their inclusion in the National Register of Historic Places. They are:

1. Hamilton Grange National Memorial
2. Federal Hall National Memorial
3. General Grant National Memorial
4. Sagamore Hill National Historic Site
5. John F. Kennedy National Historic Site
6. Theodore Roosevelt Birthplace National Historic Site
7. Status of Liberty National Monument

for Robert M. Utley

Enclosures





United States Department of the Interior

NATIONAL PARK SERVICE
WASHINGTON, D.C. 20240

IN REPLY REFER TO:
H34-PC

AUG 6 1975

Memorandum

To: Director, Office of Archeology and Historic Preservation

Through: Federal Representative to the National Register
Department of the Interior

From: Federal Representative, National Park Service

Subject: Nominations to the National Register of Historic Places

The enclosed nominations from the North Atlantic Region of the National Park Service are submitted in support of their inclusion in the National Register of Historic Places. They are:

1. Hamilton Grange National Memorial
2. Federal Hall National Memorial
3. General Grant National Memorial
4. Sagamore Hill National Historic Site
5. John F. Kennedy National Historic Site
6. Theodore Roosevelt Birthplace National Historic Site
7. Status of Liberty National Monument

/s/ Harry W. Pfanz

Robert M. Utley

Enclosures





IN REPLY REFER TO:
H30 NAR (PH)

United States Department of the Interior

NATIONAL PARK SERVICE

NORTH ATLANTIC REGION

150 CAUSEWAY STREET

BOSTON, MA. 02114

May 6, 1976

PC -
Mr Meek

Memorandum

To: Assistant Director, Park Historic Preservation, WASO

From: Associate Regional Director, Planning and Resource Preservation, North Atlantic Region

Subject: National Register Forms

We enclose the following National Register Inventory-Nomination forms with the additional information requested by the National Register Office. In some cases it was necessary to prepare a new form, but using the same 1972 forms, as previously arranged with the National Register Staff.

1. Grant's Tomb NM
2. Sub-Treasury Building NM
3. Hamilton Grange NM
4. Theodore Roosevelt Birthplace NHS
5. John F. Kennedy NHS
6. Atwood-Higgins House, Cape Cod NS
7. Highland Golf Course, Cape Cod NHS
8. Statue of Liberty NM
9. Sagamore Hill NHS

F. Ross Holland, Jr.

F. Ross Holland, Jr.



Enclosures



United States Department of the Interior

NATIONAL PARK SERVICE

NORTH ATLANTIC REGION

15 STATE STREET

BOSTON, MASSACHUSETTS 02109

April 9, 1979



APR 12 8 10 AM '79

RECEIVED
NATIONAL PARK SERVICE
WASHINGTON OFFICE

IN REPLY REFER TO:

H30-NAR(PH)

Memorandum


To: Assistant Manager, Cultural Resources Management
Division, Washington

From: Associate Director, Planning and Resource Preservation,
North Atlantic Region


Subject: National Register Nominations

Enclosed are the following nominations submitted by the North Atlantic Region for confirmation of inclusion in the National Register of Historic Places:

1. Morristown National Historical Park,
2. Home of Franklin D. Roosevelt National Historic Site,
3. ~~Val-Kill Historic District; Eleanor Roosevelt National Historic Site,~~
4. Saint-Gaudens National Historic Site,
5. Sagamore Hill National Historic Site.


Charles P. Clapper

Enclosures (5)



In 1950, 2 years after the death of Mrs. Roosevelt, Sagamore Hill, its contents, and 83 acres of land were purchased by the Theodore Roosevelt Association, a non-profit corporation founded in 1919 to recall "to the American people Mr. Roosevelt's personality and achievements, and the ideals of individual and national life that he preached and practiced." In 1963 the association presented Sagamore Hill (along with Theodore Roosevelt Birthplace in New York City, the Old Orchard Museum, and a \$500,000 endowment) to the American people as a gift to be administered by the National Park Service, U.S. Department of the Interior.

ABOUT YOUR VISIT: Sagamore Hill National Historic Site is at the end of the Cove Neck Road, Oyster Bay, Long Island, N.Y., and can be reached by the Long Island Railroad from New York City's Pennsylvania Station at Seventh Avenue and 33d Street. Taxis meet all trains. By car, the easiest route is over the Long Island Expressway to Exit 41 (N.Y. 106 North). This road leads directly to Oyster Bay; upon arriving, turn right at the third traffic light and follow the signs to Sagamore Hill. Normal driving time from New York City is 90 minutes.

Please check with the park staff for days and hours of operation.

ADMINISTRATION: Sagamore Hill National Historic Site is administered by the National Park Service, U.S. Department of the Interior, with the cooperation of the Theodore Roosevelt Association. A superintendent, whose address is 26 Wall Street, New York, NY 10003, is in charge of the site.

As the Nation's principal conservation agency, the Department of the Interior has basic responsibilities for water, fish, wildlife, mineral, land, and recreational resources. Indian and Territorial affairs are other major concerns of America's "Department of Natural Resources." The Department works to assure the wisest choice in managing all our resources so each will make its full contribution to a better United States—now and in the future.

U.S. DEPARTMENT of the INTERIOR
NATIONAL PARK SERVICE

☆ U.S. GOVERNMENT PRINTING OFFICE: 1970-392-726/43

nps new york

Sagamore Hill

National Historic Site

Assar Co.

There could be no healthier and pleasanter place in which to bring up children than in that nook of old-time America around Sagamore Hill. Certainly I never knew small people to have a better time or a better training for their work in afterlife than . . . at Sagamore Hill.

Sagamore Hill was built by Theodore Roosevelt during 1884 and 1885 and remained his permanent home the rest of his life. After its completion, the young Roosevelt moved in with his sister, Anna, and his daughter, Alice. His first wife, Alice Lee, had died only hours after their daughter was born. In December 1886 Roosevelt married Edith Kermit Carow, a childhood friend. The following spring they arrived at Sagamore Hill, and here, except for absences imposed by his public career, the Roosevelts spent the rest of their lives. Here were born three of their five children: Theodore, Jr., Kermit, and Ethel. Here to the "Summer White House" came national and international figures from every walk of life. Here on January 6, 1919, Theodore Roosevelt died peacefully in his sleep at the age of 60; and here Edith Roosevelt lived until her death in 1948 at the age of 87.

At Sagamore Hill we loved a great many things—birds and trees, and books, and all things beautiful, and horses and rifles, and children and hard work and the joy of life.

THE HOUSE ON COVE NECK: When Theodore Roosevelt was 15, his father established the family's summer residence at Oyster Bay, and the boy spent his vacations exploring the fields and woodlands on Cove Neck. Six months after graduating from Harvard, young Roosevelt bought the hill on Cove Neck where his home now stands. A barn was the only building on the tree-barren hill. For this property he paid \$10,000 in cash and assumed a 20-year mortgage for the \$20,000 balance. Two other purchases brought the total area to 155 acres, of which he kept 95, selling the rest to an aunt and his older sister.

The New York architectural firm of Lamb and Rich drew up the plans for the home, but before the final agreement for its construction was signed, Theodore's wife and mother died—in the same house and on the same day. Determined to have a suitable home for his infant daughter, Roosevelt contracted with John A. Wood & Son of Lawrence, Long Island, to build for \$16,975 the house that was to become known as Sagamore Hill.

Roosevelt had originally planned to name the property "Leeholm," for his first wife. But within 2 years he had begun seeing Edith Kermit Carow. He soon called the estate "Sagamore Hill . . . from the old Sagamore Mohannis, who as Chief of his little tribe, signed away his rights to the land."

After all, fond as I am of the White House and much though I have appreciated these years in it, there isn't any place in the world like home—like Sagamore Hill, where things are our own, with our own associations. . . .

HOME OF A GREAT AMERICAN: In 1889, after a short 2 years of writing and playing host to scores of visitors attracted to the young squire of Sagamore Hill, Roosevelt was named a member of the U.S. Civil Service Commission, the first major step in a life of distinguished public service. Through his career—as President of the Police Commission of the City of New York, Assistant Secretary of the Navy, lieutenant colonel of the famed Rough Riders, Governor of New York, Vice President, and Chief Executive—Sagamore Hill was the house to which he always returned. It was on the wide piazza of Sagamore Hill that Roosevelt was formally notified of his nomination as Governor of New York in 1898, as Vice President in 1900, and as President in 1904.

Not only was Sagamore Hill the center of the day-to-day administration of the country's affairs during the summers from 1901 to 1909, but it had an abundance of dramatic events of national and international importance. One occurred on the August day in 1905 when Roosevelt separately met the envoys of warring Russia and Japan in the library at Sagamore Hill, and then brought them face-to-face to inaugurate the conference that resulted in the Treaty of Portsmouth, N.H., on September 5, 1905, ending the conflict.

Speaking from the somewhat detached point of view of the masculine parent, I should say there was just the proper mixture of freedom and control in the management of the children. They were never allowed to be disobedient or to shirk lessons or work; and they were encouraged to have all the fun possible. They often went barefoot, especially during the many hours passed in various enthralling pursuits along and in the waters of the bay. They swam, they tramped, they boated, they coasted and skated in winter, they were intimate friends with the cows, chickens, pigs, and other livestock. . . .

HOME OF A GREAT AMERICAN FAMILY: For more than 30 years Sagamore Hill was one of the most conspicuous homes in America, talked about in crossroad stores and lonely farm kitchens, at church socials and family dinners, on city street corners, and by roundup fires on far-flung Western ranches. People talked about a man never too busy being President to be a devoted father to his four boys and two girls, and a boon companion to countless friends.

The doings of the Roosevelts and their kin filled reams of copy filed by correspondents who maintained a vigil at the "Summer White House." The President himself was an ardent advocate of the "strenuous life," and he could frequently be seen joining the children in their games and taking the boys for a hike or swim, chopping wood, riding horseback, or striding across the fields and through the woods he loved. Occasionally there would be a mournful procession of children, led by President and Mrs. Roosevelt, to the small animal cemetery to lay away a family pet.



Sagamore Hill is a rambling, solidly built, 22-room Victorian structure of frame and brick. Today it is little changed from the time, a half-century ago, when it was the home of a distinguished American and his family.

I had perfectly definite views what I wished in inside matters, what I desired to live in and with; I arranged all this, so as to get what I desired in so far as my money permitted; [the architects] put on the outside cover with but little help from me. I wished a big piazza . . . where we could sit in rocking chairs and look at the sunset; a library with a shallow bay window looking south, the parlor or drawing room occupying all the western end of the lower floor . . . big fireplaces for logs. . . . I had to live inside and not outside the house, and while I should have liked to "express myself" in both, as I had to choose, I chose the former.

THE HOUSE AND ITS FURNISHINGS: On the first floor are a large center hall, the library that served as T.R.'s private office, the dining room, Mrs. Roosevelt's drawing room, the kitchen, and the spacious north room, added in 1905. This room was designed by Roosevelt's friend, C. Grant LaFarge, son of the artist John LaFarge. The 30- by 40-foot room is built of Philippine and American woods: mahogany, black walnut, swamp cypress, and hazel. Crammed with hunting trophies, books, paintings, flags, and furniture, the Trophy Room vividly reflects the spirit of Theodore Roosevelt.

The second floor contains the family bedrooms, the nursery, guest rooms, and the room with the great porcelain bathtub. Theodore Roosevelt, Jr., once recalled that the tub's wastepipe made "the most astonishing series of gurgles" when the water ran out. "We were told by our Irish nurse that these were the outcries of the 'faucet lady' and we watched with care to see if we could catch a glimpse of her head in the pipe."

The Gun Room, housing Roosevelt's large collection of hunting arms, is on the top floor. Here, too, he sometimes went to write or to entertain his friends, away from the bustle of the household. Other rooms include quarters for maids and a cook, a sewing room, a school-room where some of the children were tutored, and Theodore Roosevelt, Jr.'s, bedroom as it was in his pre-college days.

Furnishings throughout the house are original Roosevelt pieces. In every room are items used and loved by the family. On every hand are crowded bookshelves, the contents revealing the wide range of Roosevelt's interests. Indeed, many were from his own hand.

On the south and west sides of the house is the spacious piazza from which Roosevelt looked out over Oyster Bay Harbor and Long Island Sound. On the grounds are landscaped gardens and, nearby, the Old Orchard Museum, formerly Gen. Theodore Roosevelt, Jr.'s, home, containing displays relating to the "Conservation President" and his family.