

United States Department of the Interior
National Park Service

National Register of Historic Places Continuation Sheet

Name of Property

County and State

Section number **SUPPLEMENTARY LISTING RECORD** Page _____

Name of multiple property listing (if applicable)

NRIS Reference Number: 13000305

Property Name: Buffalo Zoo Entrance Court

County: Erie State: New York

Multiple Name:

This property is listed in the National Register of Historic Places in accordance with the attached nomination documentation subject to the following exceptions, exclusions, or amendments, notwithstanding the National Park Service certification included in the nomination documentation.

Alexis Abernathy
Signature of the Keeper

6/6/13
Date of Action

Amended Items in Nomination:

In Section 8 of the National Register of Historic Places nomination area of significance has been changed from landscape architecture to architecture and ethnic heritage should be written as ethnic heritage/black.

While John Brent spent most of his career as a landscape architect, there remains almost no landscape left, two trees, at the Buffalo Zoo to document Brent's contributions. With just an acre to work with an only a wall left of his work. It is only the Entrance Court left to document Brent's work, an architectural element. Therefore the change to the area of significance architecture.

The National Register guidelines also require, when documenting ethnic heritage, that ethnic heritage needs to be specific.

Alexis Abernathy
National Register Reviewer
202-354-2236

United States Department of the Interior
National Park Service



305

National Register of Historic Places Registration Form

This form is for use in nominating or requesting determinations for individual properties and districts. See instructions in *How to Complete the National Register of Historic Places Registration Form* (National Register Bulletin 16A). Complete each item by marking "x" in the appropriate box or by entering the information requested. If an item does not apply to the property being documented, enter "N/A" for "not applicable." For functions, architectural classification, materials, and areas of significance, enter only categories and subcategories from the instructions. Place additional entries and narrative items on continuation sheets (NPS Form 10-900a). Use a typewriter, word processor, or computer to complete all items.

1. Name of Property

historic name Buffalo Zoo Entrance Court

other names/site number _____

2. Location

street & number Parkside Avenue & Amherst Street [] not for publication

city or town Buffalo [] vicinity

state New York code NY county Erie code 029 zip code 14214

3. State/Federal Agency Certification

As the designated authority under the National Historic Preservation Act, as amended, I hereby certify that this nomination [] request for determination of eligibility meets the documentation standards for registering properties in the National Register of Historic Places and meets the procedural and professional requirements as set forth in 36 CFR Part 60. In my opinion, the property meets [] does not meet the National Register criteria. I recommend that this property be considered significant [] nationally [] statewide locally. ([] see continuation sheet for additional comments.)

Rudolph A. Puopert DSHPO
Signature of certifying official/Title

3/29/13
Date

New York State Office of Parks, Recreation & Historic Preservation
State or Federal agency and bureau

In my opinion, the property [] meets [] does not meet the National Register criteria. ([] see continuation sheet for additional comments.)

Signature of certifying official/Title

Date

State or Federal agency and bureau

4. National Park Service Certification

I hereby certify that the property is:

- entered in the National Register
[] see continuation sheet
- [] determined eligible for the National Register
[] see continuation sheet
- [] determined not eligible for the National Register
- [] removed from the National Register
- [] other (explain) _____

[Signature]
Signature of the Keeper

date of action 5-22-13

Buffalo Zoo Entrance Court

Erie County, New York

Name of Property

County and State

8. Statement of Significance

Applicable National Register Criteria

(Mark "x" in one or more boxes for the criteria qualifying the property for National Register listing.)

A Property associated with events that have made a significant contribution to the broad patterns of our history.

B Property is associated with the lives of persons significant in our past.

C Property embodies the distinctive characteristics of a type, period, or method of construction or that represents the work of a master, or possesses high artistic values, or represents a significant and distinguishable entity whose components lack individual distinction.

D Property has yielded, or is likely to yield, information important in prehistory or history.

Criteria Considerations

(Mark "x" in all boxes that apply.)

A owned by a religious institution or used for religious purposes.

B removed from its original location

C a birthplace or grave

D a cemetery

E a reconstructed building, object, or structure

F a commemorative property

G less than 50 years of age or achieved significance within the past 50 years

Areas of Significance:

(Enter categories from instructions)

Landscape Architecture

Ethnic Heritage

Period of Significance:

1935 - 1938

Significant Dates:

1935, 1938

Significant Person:

N/A

Cultural Affiliation:

N/A

Architect/Builder:

John Edmonston Brent

Narrative Statement of Significance

(Explain the significance of the property on one or more continuation sheets.)

Buffalo Zoo Entrance Court

Erie County, New York

Name of Property

County and State

city or town San Antonio

state TX zip code 78209

Additional Documentation

Submit the following items with the completed form:

Continuation Sheets

Maps

A **USGS map** (7.5 or 15 minute series) indicating the property's location

A **Sketch map** for historic districts and properties having large acreage or numerous resources.

Photographs

Representative **black and white photographs** of the property.

Additional items

(Check with SHPO or FPO for any additional items)

Property Owner (Complete this item at the request of the SHPO or FPO)

name City of Buffalo (Buffalo Zoo)

street & number 300 Parkside Avenue

telephone _____

city or town Buffalo

state NY zip code 14214

Paperwork Reduction Act Statement: This information is being collected for applications to the National Register of Historic Places to nominate properties for listing or determine eligibility for listing, to list properties, and to amend existing listings. Response to this request is required to obtain a benefit in accordance with the National Historic Preservation Act, as amended (16 U.S.C. 470 *et seq.*)

Estimated Burden Statement: public reporting burden for this form is estimated to average 18.1 hours per response including time for reviewing instructions, gathering and maintaining data, and completing and reviewing the form. Direct comments regarding this burden estimate or any aspect of this form to the Chief, Administrative Services Division, National Park Service, P.O. Box 37127, Washington, D.C. 20503

United States Department of the Interior
National Park Service

National Register of Historic Places
Continuation Sheet

Buffalo Zoo Entrance Court
Name of Property
Erie County , New York
County and State

Section 7 Page 1

The Buffalo Zoo Entrance Court is located at the intersection of Parkside Avenue and Amherst Street in the northeast corner of Delaware Park in Buffalo, Erie County. Delaware Park, including the zoo and entrance court, was listed on the National Register as a contributing feature in the Delaware Park-Front Park System, a component of the Olmsted Parks and Parkways Thematic Resources (1982). That nomination documented and listed the extant features from Frederic Law Olmsted's significant citywide parks and parkways system. While successful in that regard, the nomination did not capture all of the diverse historic aspects of each of its components, some of which had extensive histories independent of the system. In researching African American architect John Edmonston Brent, it was discovered Brent had made significant contributions to the redesign of the zoo between 1935 and 1938. Most of the Brent-designed components have been lost, and the Buffalo Zoo Entrance Court is the single Brent component that survives with a high degree of integrity. In addition to Brent's landscape design, the entrance court also includes important local examples of WPA era sculpture. Neither of these significant themes is covered in the original documentation and the features are not enumerated in the thematic nomination. This nomination supports individual listing for the 1935-1938 entrance court as a rare and significant example of the work of John Edmonston Brent. The nomination includes the two approaches to the entrance from Amherst Street and Parkside Avenue, two small landscaped islands between the approaches, the grassy circle, the stone and wrought iron fence behind it, which includes gates 3 and 4, and the identical fence that encloses the south side of the entrance court and extends around the west side of Parkside Avenue, where it incorporates a stone bus shelter. The entire composition encompasses one acre and includes two contributing features, the entrance court itself and the structure including the fence, gates, and shelter.

Brent's 1935 design replaced an earlier (c1924) entrance at this site that was much simpler and less elaborate. His drawings stipulate major changes to the alignment, the creation of the circle (replacing a simple half circle), three circulation features where there had only been one, two islands, two gates, the fencing, addition of the streetcar shelter, and changes to vegetation. The new entrance filled the entire corner between Amherst and Parkside. Brent took a modest access drive and transformed it into a formal composition within the zoo's overall City Beautiful plan.

United States Department of the Interior
National Park Service

National Register of Historic Places
Continuation Sheet

Buffalo Zoo Entrance Court
Name of Property
Erie County , New York
County and State

Section 7 Page 2

The primary circulation feature is the 600-foot-long, paved, curvilinear drive, 32 feet wide, that arcs southwest from Parkside Avenue and circumscribes the circle. A second, straight, drive (Crandall Rd) approaches the circle from Amherst Street, to the north, and a third roadway extends southeast between the two islands, connecting the other two drives. The latter two roadways are each 29 feet wide. The roadways lining the park and the circle are outlined with small rectangular cobblestone curbs of native New York red Medina (Grimsby) sandstone. The two islands are enclosed with thin slabs of Medina sandstone.

In composition and style, the fencing and gates follow a simple pattern with regular geometry and repeating elements. In general, the fence can be described as a low stone wall with concrete coping, broken by evenly spaced piers of similar construction. Between and atop the piers, the fence is composed of narrow wrought-iron vertical pickets. The gate footings and structural core are cast in place concrete. The caps of the piers and flanking walls are precast concrete. The stone veneer is ashlar masonry of native New York Onondaga limestone, which was quarried within two miles of the zoo site. Textural face variation was created by chiseling some of the stone and "tumbling" some pieces and placing them in regular squared courses. The gate and fence are wrought iron. The entire length of the walls, with fence and gates, measures three hundred and fifteen feet.

There are two major sections of fencing: A long section of fence wraps around the southeast corner of Parkside Avenue and the entrance court, incorporating a stone shelter into the fencing along Parkside. The shelter is an open, rectangular stone structure, five bays wide. The Parkside Avenue elevation is defined by tall piers defining openings into the shelter. Brent's sketches show plans for another small portion of identical fencing framing the northeast corner of the entrance court and Parkside Avenue; however, this was never built. Entrance piers on either side of the entrance court roadway were also not built.

The second, and larger, section of fencing encloses the southwest side of the circle, flaring out at each of its edges, and incorporating the two sets of gates. Each gateway occupies a fifteen-foot-wide opening. Each opening includes two decorative wrought-iron gate segments composed of vertical pickets and long scrolled crosspieces (7'-6" W x 8' - 6" H). The iron gates swing by ground mounted pivots and two hinges anchored in

United States Department of the Interior
National Park Service

National Register of Historic Places
Continuation Sheet

Buffalo Zoo Entrance Court
Name of Property
Erie County , New York
County and State

Section 7 Page 3

the adjacent main piers. Each gateway is flanked by a large pier with a tripartite composition (2'-6" W x 5'-0" L x 9'-9" H) flanked by sections of low wall and wrought-iron, and then by piers enclosing sections of full-height stone walls with decorative openings in the stonework. Although Brent's plans called for a wood latticed parapet atop each of these sections of wall, there is no evidence that they were ever installed. Each gatepost originally featured a stylized light fixture, almost Art Deco in style, about 5'-6" above grade; however, these have been removed (the recesses and metal mounting fixtures survive behind the current signs). Also removed were wooden seats installed between the piers around the circle. The front of each gatepost features a low plinth, upon which sits a sculpture. There are four different grouping of animals: a pair of beavers and a pair of badgers at gate 3, and a single baby elephant and a pair of baby bears at gate 4.

VEGETATION

The planting plan was not elaborate and generally served to retain the grassy park-like landscape informally dotted with trees that was already in place. Brent's plan specified the removal of a number of trees, mostly those that impeded construction of the new features. He also removed an existing bridle path along Parkside Avenue. Several trees were identified to be retained, including an oak and an elm in the circle; both survive. In addition, Brent specified the addition of elm trees spaced evenly along the front of the fence behind the circle. These do not survive. Bushes currently in front of the fence that partially obscure it were added later.

MATERIALS

Limestone veneer

The stone veneer is ashlar masonry of native New York Onondaga limestone. Chunks of black flint embedded in the rock contribute to its natural gray color (very light to very dark) and variation of hardness. The inconsistent hardness makes it especially difficult to work ("dress"/trim) with hand tools. These compounds also contribute to the stone's tendency to decompose into small fragments and result in limited structural strength. In the nineteenth century, Onondaga limestone received limited use in buildings. It was used more often for foundation walls in outbuildings, fencing, and landscape paving. City of Buffalo records verify that all, or a major portion, of the gate and wall limestone came from the Manhattan Quarry which was within two miles of the zoo site.

United States Department of the Interior
National Park Service

National Register of Historic Places
Continuation Sheet

Buffalo Zoo Entrance Court
Name of Property
Erie County , New York
County and State

Section 7 Page 4

Medina sandstone

The roadways lining the park and the circle are outlined with small rectangular cobblestone curbs of native New York red Medina (Grimsby) sandstone, while The two islands are enclosed with thin slabs of the sandstone.

Precast concrete

Precast concrete was used for pier and wall caps in the gate and fence. A light sandblast (abrasive blast) finish was used on all sides of the caps. The precast caps are natural concrete color.

Cast Stone (dry-tamped)

Cast stone was used to produce the animal sculptures. A natural light gray color was created by proportioning the amount of cement and aggregate. Cast stone is an almost-dry cement, lime and aggregate mixture which is dry-tamped, or packed with a tool, into a mold to produce a dense stone-like unit. The dry-tamp fabrication method was used to produce an outer surface resembling a stone surface.

Wrought Iron

The gate and fence is created from decorative wrought iron. Rod iron was used for vertical pickets. Bar iron was used for circular and scroll ornament.

Stainless steel

Detail notes for the gate lights specify the frames to be "stainless steel." This material was frequently used in architectural details influenced by the Art Deco style (1920s-1940s). This material is known for its durability and resistance to corrosion.

Tapestry glass

Detail notes for the gate lights specify the lenses to be "tapestry glass." This variation of plate glass was manufactured by the Pittsburgh Plate Glass company from the 1920s through the 1940s. The surface of the glass was finished with various designs or textures to diffuse light while obstructing clear vision through the material. The glass was produced in thicknesses of either 3/16" or 5/16."

**United States Department of the Interior
National Park Service**

**National Register of Historic Places
Continuation Sheet**

Section 7 Page 5

 Buffalo Zoo Entrance Court
Name of Property
 Erie County , New York
County and State

INTEGRITY

The Buffalo Zoo Entrance Court retains substantial integrity to the period of significance. Nearly all of the design features specified by Brent were constructed, with only one small section of fencing, entrance posts, and a decorative lattice top remaining incomplete. A comparison with Brent's plans and drawings reveal that the roadways retain their original size, width, alignment and, materials. Original curbs survive. The fence and shelter composition are intact and in their original location. The only known alterations are the removal of the electrical accent lights from the gates, the wood benches from the seat walls, and the loss of the elm trees.

United States Department of the Interior
National Park Service

National Register of Historic Places
Continuation Sheet

Section 8 Page 1

Buffalo Zoo Entrance Court

Name of Property

Erie County, New York

County and State

Summary

The Buffalo Zoo Entrance Court is significant in the areas of landscape architecture and ethnic heritage as an important and extremely rare surviving design by early twentieth century African American landscape architect John Edmonston Brent (1889-1962). Brent, one of a small group of African Americans to work as both a landscape architect and an architect in the 1930s, completed the design for the entrance court in two stages between 1935 and 1938 as part of an overall expansion and redesign of the zoo. The Buffalo Zoo, the third oldest (1875) zoo in America, originated as part of Fredrick Law Olmsted's design for a municipal park system. In Olmsted's plan, the area that is now the zoo was a deer park in the northeast corner of Delaware Park. Spurred on by local donations of animals, the deer park developed rapidly into a zoo between 1875 and 1930, attracting great community interest and precipitating the founding of the Zoological Society of Buffalo in 1931. A basic conceptual outline for the zoo was developed in 1924 by Buffalo city architect Harold L. Beck; however, the details and construction of the plan were not implemented until WPA funds were secured in 1935 after Beck's retirement. The person most responsible for implementing and developing the plan was architect and landscape architect John Edmonston Brent, who, as an employee of the Buffalo Parks Department, worked on design, planning, and implementation of more than sixteen facilities and exhibits at the zoo from 1935 until his retirement in 1957. Brent played a major role in transforming the layout of the zoo from an outline into an elaborately detailed neoclassical garden influenced by the City Beautiful movement. Of Brent's sixteen documented projects, the majority have been demolished or substantially altered. The nominated property, intended to serve as a major entrance to the zoo at the northeast corner, represented Brent's substantial enlargement and elaboration of what had been a simple entrance road in this location. Brent dignified the corner with a fully developed neoclassical composition, including two entrance drives with cobblestone curbs leading to a formal traffic circle and two entrance gates. The composition was framed by a monumental stone-faced and wrought-iron fence; another section of fencing incorporated an open shelter along the edge of Parkside Avenue. The entrance court fencing was constructed of a variety of materials, including cast concrete, cast stone, limestone, sandstone and wrought iron. Although the composition was classical in form and composition, the materials were used to create a eclectic design embodying rusticated, arts and crafts and even Art Deco elements.

John E. Brent is significant as one of the earliest group of recognized African American landscape architects in

United States Department of the Interior
National Park Service

National Register of Historic Places
Continuation Sheet

Section 8 Page 2

Buffalo Zoo Entrance Court

Name of Property

Erie County, New York

County and State

the United States with a substantial body of work. Brent was one of fewer than one hundred licensed African American architects in the United States at the time. He was also one of the first, and fewer than six, African Americans to be formally recognized and simultaneously practice as both an architect and a landscape architect in America.¹ His 1926 design for Buffalo's Michigan Street YMCA (demolished) was the second "Colored Y" designed by an African American architect in the United States. He was one of thirteen African American architects to be invited from across the country to a juried exhibition of work at Howard University (Washington, D.C.) in 1931. His work for the Buffalo parks department made him one of only three African American architects known to undertaken such important work for a municipality in the United States prior to federal civil rights legislation. His work for the zoo was one of his most important commissions.

Although the entrance court is the only surviving intact component of Brent's large body of work at the Buffalo Zoo, it is a distinctive and complete composition that illustrates typical federal Works Progress Administration (WPA) era park design and is representative of the aesthetic that Brent used for all his work at the zoo. Because African American landscape architects were greatly underrepresented in American society historically, because Brent was a recognized and prominent member of this profession, and because this is an extremely rare surviving example of his work, the Buffalo Zoo Entrance Court is worthy of nomination in the areas of landscape architecture and ethnic heritage.

The entrance court is also significant for its precast concrete animal sculptures created between 1938 and 1939 by WPA artists. There are two sculptures at each gate, each with different animals.

LANDSCAPE ARCHITECT/ARCHITECT JOHN EDMONSTON BRENT

John Edmonston Brent was born in 1889 and raised in Washington, DC. His father, Calvin T.S. Brent (1854 - 1899), was the first African American architect in Washington, DC after the Civil War. After John E. Brent completed his primary school (grades 1-8) studies he attended Tuskegee Institute in Tuskegee, Alabama, from 1904-1907, studying carpentry and architecture. William S. Pittman, architect for the first "Colored YMCA" in America, was an instructor in the architectural department during Brent's first two years. Pioneer African

¹ Landscape architects were not licensed in this period

**United States Department of the Interior
National Park Service**

**National Register of Historic Places
Continuation Sheet**

Buffalo Zoo Entrance Court

Name of Property

Erie County, New York

County and State

Section 8 Page 3

American landscape architect David Williston was also a Tuskegee professor during Brent's first two years, teaching horticulture and landscape gardening. The professional works of Williston and Brent were later included in a juried exhibit at Howard University in 1931.

Brent returned to Washington and worked for the District of Columbia Parks Department for two years. He attended Drexel Institute in Philadelphia (1909-1912), where he studied architecture and took a course in landscape design. After graduating with a degree in architecture, he immediately moved to Buffalo and worked one to three year periods for a number of local architects until 1926. Brent took the New York State architect's examination in 1926 and received his license (#2977) in March, 1926. During the late nineteenth and early twentieth century the African American population of Buffalo had grown significantly and Black Buffalonians had become leaders in the national civil rights movement. Brent is credited as one of the founders of the Buffalo chapter of the National Association for the Advancement of Colored People (NAACP).

At that time, public accommodations in the United States were segregated, even down to amusements, restaurants, drinking fountains and YMCA's. Under a challenge grant by the philanthropist Julius Rosenwald, twenty-one segregated YMCA's were built across the country to provide services for the African American community similar to those that the white population enjoyed. Rosenwald was the CEO of Sears & Roebuck and one of the wealthiest men in the country. He was initially interested in helping to fund YMCA's because he believed in the organization's mission and was unwilling to tolerate racial inequality. He put up 25 percent of the cost of a building, which was roughly \$125,000, if the local community could raise the remaining amount. Buffalo was the second city to accept the challenge, and Brent was selected to design and supervise the construction of the Michigan Street Y.M.C.A. Brent became the second African American architect to design a "Colored Y.M.C.A." in America. Rosenwald personally attended the opening dedication of the Michigan Street Y and commended Brent for his architectural design and construction supervision work.

Rosenwald was also instrumental in financing the Washington, DC segregated Y, once it had lost its funding from other sources. That Y, known as the 12th Street Y.M.C.A., is still standing and was the first "Colored Y.M.C.A." designed by an African American architect (W. Sidney Pittman, also a Tuskegee graduate). It was

**United States Department of the Interior
National Park Service**

**National Register of Historic Places
Continuation Sheet**

Buffalo Zoo Entrance Court

Name of Property

Erie County, New York

County and State

Section 8 Page 4

through Rosenwald's work with the Y's that he met Dr. Booker T. Washington and became a board member of Tuskegee. Together, Rosenwald and Washington began a school building program that provided more than 5,000 school houses across the south. A number of these so-called "Rosenwald Schools" have been listed on the National Register.

In Buffalo, local philanthropist George Matthews started a trust fund with a \$100,000 donation for the completion and maintenance of the YMCA. Known as the "Booker T. Washington Foundation," it was the largest donation ever made for the Y work among African Americans in the United States.² (Overall the Matthews family donated more than \$500,000 for the building and maintenance of the Michigan Avenue YMCA.) Brent served on the board of directors of the Michigan Street Y for more than thirty years, and he developed a landscape plan for a YMCA camp. Neither the Michigan Avenue Y nor the camp survives.

Following completion of the Michigan Avenue Y, Brent practiced architecture in Buffalo under his own name until 1930. In 1931 he was hired to work in the architect's office of the U.S. Department of the Interior in Washington D.C. In this position, Brent assisted Howard University campus architect Albert I. Cassell in preparing plans for dormitories and a classroom building at the historically Black college. Prior to Cassell's 1929 master plan, all of the buildings and grounds had been planned and designed by white architects and engineers with oversight from the interior department. Howard Mackey Sr., an African American architect who had been appointed to develop an academic architecture program at Howard, began to advocate for African American architects and engineers to plan and design buildings at Howard. In order to publicize their talent, Mackey organized a juried exhibit in May 1931 that included works by African American architects from all parts of the United States. Brent was one of thirteen African American architects selected to participate.

Brent's work for the U.S. Department of the Interior was completed in 1933 and he returned to Buffalo, where he was hired as a draftsman in the Buffalo Parks Department in 1935. Given his training and experience, Brent

²Lillian S Williams, "To Elevate the Race: The Michigan Avenue YMCA and the Advancement of Blacks in Buffalo, New York, 1922-1940," in *New Perspectives on Black Educational History*, ed. Vincent P. Franklin and James D. Anderson (Boston: G.K. Hall, circa 1978), 132.

United States Department of the Interior
National Park Service

National Register of Historic Places
Continuation Sheet

Section 8 Page 5

Buffalo Zoo Entrance Court

Name of Property

Erie County, New York

County and State

was vastly overqualified to work as a draftsman, and it is unclear whether his underemployment can be attributed to the effects of the Depression or to racism. However, his experience with the interior department gave the city of Buffalo an advantage when it applied for WPA funding. Communities that did not have locally qualified architects and engineers required an outside professional assigned to prepare construction documents and supervise construction. With Brent on staff, Buffalo was exempt from this requirement. Research strongly suggests that Brent's work for the Buffalo Zoo was as a professional designer (see below). In 1936 Brent was promoted to the position of "junior landscape architect." Brent worked at the Buffalo Zoo until he retired, due to ill health, in 1957. He died in 1962 and is buried in Forest Lawn Cemetery

SOCIAL/CULTURAL CONTEXT

John Edmonston Brent worked at the Buffalo Zoo in a professional capacity as both a landscape architect and an architect. He worked on the design, planning, and implementation of more than a sixteen facilities and exhibits at the Buffalo Zoo from 1935-1937. His documented work includes the Bear Pit, Pheasant Building, Goat Island Shelter, Elephant House Fence and Manure Box, Russell Street Entrance, Monkey Island Moat Wall, and Seal Pool Drainage Plan. Evidence suggests that Brent was the person most responsible for implementing the details of the zoo's classical layout as it was developed during the 1930s. The proposed plan for the zoo published in 1924 shows the basic outline of a formal plan, including major east-west and northeast-southwest axes, a large semi-circular feature on the eastern edge and several smaller circulation features. Spaces were identified for animal exhibits. It also stipulated seven entrances into the zoo. This plan was signed by Buffalo city architect Harold L. Beck. Beck's work can be seen in several of the city's public schools and his 1913 Flemish Revival firehouse at 395 Amherst Street in Buffalo is one of his more highly styled examples extant. Major development of this plan did not commence until the zoo secured WPA funding in the early 1930s. As the zoo developed over the next decade, this plan was filled in with the more complex geometric components of a detailed circulation system, including additional axial and cross-axial roads and paths. Within and around this system, numerous smaller spaces were identified and developed as landscaped park areas, complex animal exhibit spaces, and less formal grounds for larger animals.

A great deal of research in the Buffalo Zoo's archives was undertaken before attributing the fully developed zoo landscape to John Brent. The head landscape architect for the Buffalo parks between 1934 and c1960 was

**United States Department of the Interior
National Park Service**

**National Register of Historic Places
Continuation Sheet**

Buffalo Zoo Entrance Court

Name of Property

Erie County, New York

County and State

Section 8 Page 6

Roeder J. Kinkel. Kinkel, who later ran a landscaping business with his two brothers, is believed to have acted in an administrative capacity, working primarily from his office in downtown Buffalo on overall management of the city's park system. Nevertheless, he is listed as the landscape architect on the zoo drawings, all of which he also signed and approved. J.B. Brent is noted as having drawn the plans, usually the job of a draftsman (though it can also be that of the designer). However, despite Brent's title, he was more than qualified to undertake the actual design work, and, unlike Kinkel, he had offices both downtown, at the park office, and at the zoo itself. Brent's descendants have attested that he went out to the zoo every afternoon. The more than forty original drawings initialed by Brent relating to exhibits and furnishings at the zoo from 1935 to 1957 do not account for every single feature that was constructed. However, a thorough search of the Buffalo city architect's office and other local archives turned up almost no other drawings for zoo features, suggesting that Brent worked out many of the details on site. Certainly the variety of projects documented by his drawings suggests that he had a hand in the overall development of the zoo. Only three names are found on all existing drawings found for the zoo: Roeder's, Brent's and those of H.M. Evarts, a civil engineer. While Roeder's name appears on all of them, Brent's and Evarts's names are found only on those projects that most logically require their particular expertise and skills. This distinction would not have been necessary were the two only acting as draftsmen.

The large number of drawings by Brent both authenticate his zoo work and record the evolution and change of exhibits at the Buffalo Zoo. They may also be one of the largest collections of drawings by an African American architect working on a civic/municipal project in the United States at the time, as only three other African American architects did such prominent work for a municipality in the United States prior to World War II and before federal civil rights legislation. Of them, Brent was the only one practicing both as a landscape architect and an architect. They others are:

Clarence Wesley "Cap" Wigington (1883-1967), worked as senior design architect for the City of St. Paul, Minnesota for 32 years (1917-1949). Sixty of his buildings still stand in St. Paul, with several listed on the National Register of Historic Places.

United States Department of the Interior
National Park Service

National Register of Historic Places
Continuation Sheet

Section 8 Page 7

Buffalo Zoo Entrance Court

Name of Property

Erie County, New York

County and State

John Louis Wilson, Jr. (1898-1989), employed as architect by the New York City Parks Department from the 1930s to the 1960s. He was commissioned to work with a team of architects to design the Harlem River Houses (National Register listed) and other public housing in New York City.

Louis Arnett Stuart Bellinger (1891-1946) practiced architecture in Pittsburgh, Pennsylvania. Bellinger's single "landscape" commission, "Central Park," home field of the African American Pittsburgh Keystones baseball team (1920), has been demolished. From 1923-1926 Bellinger worked as an assistant architect in the Pittsburgh City Architect's office. The balance of his work was in private practice.

Brent was one of fewer than sixty licensed African American architects in the United States at the time. He was also one of the first, and one of fewer than six, African Americans to be recognized and simultaneously practice as both a landscape architect and a professional architect in America. Racial segregation and discrimination prevented African Americans from entering accredited design schools to study engineering, city planning, landscape architecture, or architecture. It was virtually impossible to acquire professional registration without the necessary academic credentials and apprenticeship opportunities. Brent became the fifth African American in history to join the American Institute of Architects in 1944, and he maintained his membership until 1959. The Buffalo Zoo Entrance Court is his largest and most complete surviving work.

DEVELOPMENT OF THE BUFFALO ZOO

The Buffalo Zoo is located in north central Buffalo, in the northeast corner of Delaware Park, and covers twenty three acres. The zoo is bounded by Amherst Street on the north, Parkside Avenue on the east, a park loop road on the south, and a park loop road on the west. The original 17.6 acre tract of 1870, which was set aside for the deer park and eventual zoo, was not fenced. Wrought-iron fences began to be erected c.1875, and the main visitor entrance was from the park drive on the south side of the zoo. A 1909 zoo master plan proposed the addition of visitor entrances from the west off Colvin Boulevard and from the north, approximately two hundred and fifty feet west of the intersection of Parkside Avenue and Amherst Street. After 1916, the International Railway Company (IRC) extended electric streetcar Route #9/Zoo/Kenmore north beyond the zoo along Parkside Avenue, making entrances from Parkside Avenue a necessity. In 1924, a new master plan was

United States Department of the Interior
National Park Service

National Register of Historic Places
Continuation Sheet

Buffalo Zoo Entrance Court

Name of Property

Erie County, New York

County and State

Section 8 Page 8

developed by Harold L. Beck, Buffalo city architect from c1912 to 1926. Beck's master plan provided the outline for a neoclassical layout and identified seven entrances to the grounds. Most of the entrances were oriented toward the south and east sides of the property. The entrance indicated near the corner of Amherst and Parkside was the only entrance in the northeast quadrant. It featured a single roadway leading to a semicircular island aligned on axis and covered with flowers

Brent's larger and more formal entrance court was planned and designed in two phases. The first section was designed in 1935 as the first phase of the new entrance composition. Detailed construction plans for gate #3 and #4 were designed and approved in October and November of 1935. The ensemble was composed of a landscaped circle, incorporating existing trees and a paved drive around its circumference (diameter from the center of the circle to the edge of the drive was 22 feet); around this was a larger circle including a fence with two gates, which extended another 22 feet from center. The fence was a low (2'-3", H x 550') curvilinear wall with native limestone veneer, intermediate piers, and wrought-iron fence infill; five seat walls (8'-6" H); cast stone sculptures on precast concrete bases mounted on masonry veneer plinths; two entrance pathways with flanking piers; and two wrought-iron gates (8'-6", H; 14'-6", W). These were originally identified as gates 7 and 1; however, they are now known as gates 3 and 4, respectively. The composition also included landscaped beds; and street trees.

The fence and streetcar shelter along Parkside Avenue was the second phase, planned and designed in 1937. This composition begins with a formal pier at the southwest corner of the Amherst Street and Parkside Avenue intersection and connects to a semicircular wrought-iron fence mounted on a low masonry wall. The semicircular wall connects to the northwest corner wall of a pavilion type streetcar shelter (15' W x 40' - 0" L x 10' - 6" H). The sidewalk width in front of the shelter tapers from 20' (W) to 16' (W). The fence resumes at the south end of the streetcar shelter and proceeds south for approximately sixty-two feet, where it abuts a chain link fence. The plans also called for formal piers on either side of the road and another section of fencing on the northeast corner. The entrance piers and the second section of fence were not constructed.

The layout of gates number 3 and 4 evolved between the 1924 and 1938 zoo master plans. The 1938 plan shows the two gates located immediately adjacent to one another. Gate 3 is oriented on a northeast-southwest

**United States Department of the Interior
National Park Service**

**National Register of Historic Places
Continuation Sheet**

Buffalo Zoo Entrance Court

Name of Property

Erie County, New York

County and State

Section 8 Page 9

axis from the 1924 master plan. Gate 4 is oriented approximately parallel to the north-south axis of the nineteenth-century south gate and the 1909-1924 master plans. The existing pedestrian paths are still aligned to these historic axes. The 1938 "Approved General Layout Plan" included a total of seven major visitor entrances. Although Brent did not design them all, his design established a prototype that was used, with some variation, at other entrances.

Brent's design for the entrance court is a formal composition that reflects the same City Beautiful aesthetic seen in the 1938 plan as a whole. Yet, the fence itself, with its combination of rusticated stone face, scrolled ironwork and intended lattice parapet, is a more eclectic feature that combines a variety of aesthetics common in park architecture in the period, in particular some of the national parks designed by the Civilian Conservation Corps. Together, these influences make the Buffalo Zoo Entrance Court a distinguished and attractive feature. It is also one of the last remnants of the zoo's important 1930s era of development.

WPA

The Public Works Administration (PWA) was established in 1933 as part of the federal New Deal Program to build large scale public infrastructure projects such as electrical utilities, airports, highways, dams, bridges, hospitals and schools. The Works Progress Administration (WPA) was established in 1935 to focus on relatively small projects and hire unemployed and unskilled workers. In 1939, after the WPA was abolished, the Federal Works Agency (FWA) took charge of both the PWA and the WPA. The FWA functioned until 1949, when the General Services Administration and U.S. Department of the Interior absorbed its responsibilities. During the 1930s, the Works Progress Administration funded construction of a number of zoos across America. The Buffalo Zoo benefited by receiving nearly \$2.8 million from the federal program between 1935 and 1944. These funds allowed the zoo to carry out its ambitious development scheme, and by 1947 it was considered one of the top six zoos in the United States based on the layout and character of its exhibits.

FEDERAL ART PROGRAM

The Federal Art Project (FAP) operated in forty eight states from 1934-1943 under the WPA. Its main mission was to provide employment for out-of-work artists and provide art for non-federal government buildings. FAP

**United States Department of the Interior
National Park Service**

**National Register of Historic Places
Continuation Sheet**

Section 8 Page 10

Buffalo Zoo Entrance Court

Name of Property

Erie County, New York

County and State

artists created murals, paintings and sculpture for facilities such as libraries, hospitals, schools and multi-family housing. From 1938 to 1939 Robert Cronbach (1908-2001) was in charge of the Buffalo unit of the FAP, tasked with creating the sculpture at Buffalo's Willert Park public housing project (National Register eligible), which was implemented by the United States Housing Authority through the WPA. William Ernst Erich, an important artist of architectural sculpture and an instructor at the Art Institute of Buffalo, was appointed to supervise the large group of artists (sculptors and painters) that produced murals and sculpture for various projects at the Buffalo Zoo. However, due to limited administrative budgets, the artists themselves were essentially "self-supervised" and they remain anonymous. Among their most memorable projects for the zoo were the cast stone animals at the zoo entrance gates. These include four different compositions: a pair of beavers and a pair of badgers at gate 3 and a single baby elephant and a pair of baby bears at gate 4.

United States Department of the Interior
National Park Service

National Register of Historic Places
Continuation Sheet

Buffalo Zoo Entrance Court
Name of Property
Erie County, New York
County and State

Section 9 Page 1

BIBLIOGRAPHY

“Brent, John Edmonston,” (ahd1004979). *The AIA Historical Directory of American Architects*, s.v.
“<http://www.aia.org/about/history/aiab082017>”

Donahue, Jesse C., and Erik K. Trump. *American Zoos During the Depression: A New Deal for Animals*.
Jefferson, NC: McFarland, 2012

Middleton, G.A.T. *Modern Buildings, Their Planning, Construction And Equipment*. Vol. 1. London: Claxton
Publishing Company, 1921.

Pittsburgh Plate Glass Company. *A Catalogue of Tapestry Glass*. Pittsburgh Plate Glass Company. Pittsburg:
1924;1930.

Underwood, Lucien Marcus. *Thesis: The geological formations crossed by the Syracuse and Chenango Valley
R.R.: together with a sketch of the hydrography and valley formations of Madison and Onondaga counties*.
Meminnville, TN: Standard Publishing Company, 1879.

Williams, Lillian Serece, Ph.D. *Strangers in the Land of Paradise: Creation of an African American
Community in Buffalo, New York, 1900-1940*. Bloomington, IN: Indiana University Press, 2000.

Wilson, Dreck Spurlock. *African American Architects: A Biographical Dictionary 1865-1945*. New York:
Taylor & Francis, 2007.

PERIODICALS & REPORTS

Fly, Everett L. “The Hidden Heritage of Black Sites: Black Settlements In America (Urban Enclaves; Alley
Dwellings; African American Resorts & Recreation; African American Architects; Negro Exhibits;
Tuskegee Institute and African American Environmental Education).” *Place*, 1981.

ARTICLES

Dozier, Richard K. “A Historical Survey: Black Architects and Craftsmen.” *Black World/Negro Digest* 23(7)
May, 1974, 4-15.

Martin, Nancy Ehrich and Roger W. Ehrich. William Ernst Ehrich Biography.
<http://ehrich.us/biography.html>

Van Ness, Cynthia *Afro-Americans in New York Life and History*. (January 1, 2012).
<http://readperiodicals.com201201/2599645571.html#b#ixzz1qTPxZFAG>

United States Department of the Interior
National Park Service

National Register of Historic Places
Continuation Sheet

Section 9 Page 2

Buffalo Zoo Entrance Court
Name of Property
Erie County, New York
County and State

Web Guide. Colorado Historical Society, Office of Archaeology and Historic Preservation.
http://oahp.historycolorado.org/guides/architecture/rustic_wpa.htm

SPECIAL COLLECTIONS AND RECORDS

Buffalo, NY. State University of New York at Buffalo Archives. Michigan Avenue Y.M.C.A. Records, circa 1920-1970.

_____ Buffalo City Architect's Office. Public Projects Archives.

_____ City Clerk. Vital Records and Archives.

_____ Erie County Clerk. Land Records and Archives..

_____ Buffalo Zoo. Rare Documents and Scrapbook Collection.

Application of John E. Brent to the Municipal Civil Service Commission of the City of Buffalo, September 28, 1936.

Washington, D.C. National Archives. Record Group 66, Records of the Commission of Fine Arts/1893-1990),

_____ Record Group 69, Works Projects Administration Administrative History; Predecessor Agencies (Works Progress Administration/1935-1939).

_____ Record Group 135, Public Works Administration Administrative History.

ORAL INTERVIEWS

Miller, Jean and Jennifer Fields. Interview, April 17, 2012; May 8, 2012. Buffalo, New York.

McGriff, Jennifer, Janessa Robinson, and Brent Rollins. Interview by ???? July 11, 2012; August 20, 2012; October 23, 2012. Buffalo, New York/Washington, D.C..

**United States Department of the Interior
National Park Service**

**National Register of Historic Places
Continuation Sheet**

Section 10 Page 1

Buffalo Zoo Entrance Court

Name of Property

Erie County, New York

County and State

Verbal Boundary Description

The boundary is indicated by a heavy line on the enclosed map with scale.

Boundary Justification

The boundary was drawn to include the full extent of the Buffalo Zoo Entrance Court as designed by John E. Brent between 1935 and 1938. The entrance court is defined as the two access roads from Amherst Street and Parkside Avenue, the two small islands and one connecting roadway between them, the traffic circle, both sections of stone and wrought iron fence, including the streetcar shelter and both gates, and all vegetation within this area.

United States Department of the Interior
National Park Service

National Register of Historic Places
Continuation Sheet

Buffalo Zoo Entrance Court

Name of Property

Erie County , New York

County and State

Section 11 Page 1

JOHN EDMONSTON BRENT ZOO PROJECTS INVENTORY

<u>DRAWING NO.</u>	<u>DATE</u>	<u>DESCRIPTION</u>	<u>STATUS</u>
C - 4 - 2	10-28-35	Working Drawing Entrance Court & Gateways, Gates 1 & 7	Extant
C - _ - _	03-23-36	Working Drawing Eagle, Hawk, Vulture, Owl Cage, Project 42424	Demolished
C - 4 - 9	05-01-36	Working Drawing Bear Pits (32" x 41 1/2")	Demolished
C - 4 - 12	05-01-36	Working Drawings Construction Details Bear Pits (20 1/4" x 42 1/4")	Demolished
C - 4 - 7	06-25-36	Details for Entrance Piers Revised 6-25-36/J.E.B.	Extant as part of gates #1 & #7
C - 4 - 15	06-11-36	Steps In Walks & Fence Around Moats	Altered
C - 4 - 17	06-15-36	Alternate Plan	Not Built

United States Department of the Interior
National Park Service

National Register of Historic Places
Continuation Sheet

Buffalo Zoo Entrance Court

Name of Property

Erie County , New York

County and State

Section 11 Page 2

of Roof Construction
Pergolas in Entrance Court

C - 4 - 31	01-20-37	Working Drawing Amherst Street Entrance (25 3/4" x 44 1/4")	Altered
C - 4 - 37	03-20-37	Working Drawing Exhibit Poster Labels (19 3/4" x 24")	Demolished
<u>DRAWING NO.</u>	<u>DATE</u>	<u>DESCRIPTION</u>	<u>STATUS</u>
C - 4 - 39	03-22-37	Working Drawing Russell Avenue Entrance Court (14" x 25")	Extant
C - 4 - 41	04-29-37	Section Thru Bear Dens (17 3/4" x 25")	Demolished
C - 4 - 18	07-10-38	Working Drawing Beaver Exhibit	Demolished
C - 4 - 86	01-2-36	Working Drawing	Altered & parts

United States Department of the Interior
National Park Service

National Register of Historic Places
Continuation Sheet

Buffalo Zoo Entrance Court

Name of Property

Erie County, New York

County and State

Section 11 Page 3

		American Swamp, North American Plain & Goat Hill	demolished
C - 4 - 21	08-27-36	Detail of Moat of Wall at Monkey Island	Demolished
C - 4 - 22	08-31-36	Water and Drainage Lines About Bear Pits (26" x 38 1/2")	Demolished
C - 4 - 24	09-15-36	Working Drawing Pheasantry	Altered
C - 4 - 26	10-01-36	Detail of Skylight on Pheasantry	Altered
C - 4 - 27	10-23-36	Details Goat Hill (31 3/4" x 41 1/2")	Demolished
C - 4 - 33	02-22-37	Working Drawing Barnyard Exhibit (24 1/4" x 36")	Altered
<u>DRAWING NO.</u>	<u>DATE</u>	<u>DESCRIPTION</u>	<u>STATUS</u>
C - 4 - 47	09-21-37	Rock & Earth	Demolished

United States Department of the Interior
National Park Service

National Register of Historic Places
Continuation Sheet

Buffalo Zoo Entrance Court

Name of Property

Erie County, New York

County and State

Section 11 Page 4

		Hills in Goat Exhibit (23 1/2" x 42")	
C - 4 - 55	08-26-38	Working Drawing Plastered Moat Walls - Bear Pits (18" x 42 1/8")	Demolished
C - 4 - 60	03-21-39	New Gates in Fence Around Elephant Yard (18 1/4" x 30")	Demolished
C - 4 - 66	04-25-39	New Manure Box (18 5/8" x 30")	Demolished
C - 4 - 82	04-06-40	Poster Label Frames	Demolished
C - 4 - 99	05-08-40	New Entrance Gateways Colvin-Amherst & Jewett-Parkside Delaware Park	Not built
C - 4 - 84	06-12-40	Metal Plant Containers at Window Shelves in Mammals - Bldg. & Lion & Tigers Bldg.	Demolished

United States Department of the Interior
National Park Service

National Register of Historic Places
Continuation Sheet

Buffalo Zoo Entrance Court

Name of Property

Erie County, New York

County and State

Section 11 Page 5

Zoological Gardens

C - 4 - 10 09-03-40 Details Barn Extant, Altered
(19 3/4" x 36 1/4")

C - 4 - 71 01-18-41 Fence Around Barnyard Demolished
Barnyard
(18 3/8" x 24 1/2")

C - 4 - 74 03-31-41 Grain Bins New Barn Demolished
(18 3/8" x 35 1/2")

DRAWING NO. DATE DESCRIPTION STATUS

C - 4 - 80 06-02-41 New Light Demolished
Standards -
Zoological Gardens
(17 3/8" x 36")

C - 4 - 102 06-04-41 Grading Plan Altered
Parking Area
(24 3/4" x 24 1/2")

C - 4 - 108 02-14-51 New Enclosing Altered
Fences at
Pheasantries
(18 1/2" x 27 3/8")

C - 4 - 109 02-19-52 New Fences Altered
(20 1/4" x 36 1/4")

United States Department of the Interior
National Park Service

National Register of Historic Places
Continuation Sheet

Buffalo Zoo Entrance Court

Name of Property

Erie County, New York

County and State

Section 11 Page 6

C - 4 - 111	08-18-52	Resurfacing Present Demolished Walks at Old Bear Pits (12 3/8" x 30")	
C - 4 - 112	12-30-52	New Fences (16 3/4" x 24 1/2")	Altered
C - 4 - 89	04-07-52	Plan of Island Eleven Reptile Cage Doors New Manholes in Present Sewer (24 1/4" x 35 1/4")	Altered
C - 4 - 122	08-26-57	Proposed Giraffe, Ostrich, Kangaroo Exhibit (17 7/8" x 18")	Not built
L - 370	12-27-51	Conversion of Present Comfort Station to Picnic Shelter at Front Park (16 1/2" x 25")	Altered

<u>DRAWING NO.</u>	<u>DATE</u>	<u>DESCRIPTION</u>	<u>STATUS</u>
L - 412	06-26-53	Remodeling of Comfort Station for Picnic Shelter	Altered

United States Department of the Interior
National Park Service

National Register of Historic Places
Continuation Sheet

Buffalo Zoo Entrance Court

Name of Property

Erie County, New York

County and State

Section 11 Page 7

at Front Park
(18" x 30")

L - 413	07-03-53	Remodeling of Comfort Station for Picnic Shelter at Front Park (18" x 24 1/4")	Altered
---------	----------	--	---------

JOHN EDMONSTON BRENT PRIVATE PROJECTS INVENTORY

<u>NAME</u>	<u>ADDRESS</u>	<u>CITY, STATE</u>	<u>YEAR</u>	<u>COMMENTS</u>
McGuire Medical Office	482 Jefferson Avenue	Buffalo, NY		Demolished
Michigan Avenue YMCA	585 Michigan Avenue	Buffalo, NY	1926	Demolished
Miles, Mitchell	400 Genesee Street	Cheektowaga, NY	c.1935	Demolished
Michigan Avenue YMCA Camp		Wales Hollow, NY	c.1936	Demolished
Payne, Clara		Eden, NY		Summer Cottage

JOHN EDMONSTON BRENT HOWARD UNIVERSITY INVENTORY (MR. BRENT ASSISTED IN PREPARATION OF ARCHITECTURAL PLANS BETWEEN 1931 AND 1933; HE WAS NOT

United States Department of the Interior
National Park Service

National Register of Historic Places
Continuation Sheet

Buffalo Zoo Entrance Court

Name of Property

Erie County , New York

County and State

Section 11 Page 8

ARCHITECT OF RECORD)

<u>NAME</u>	<u>DATE</u>	<u>DESCRIPTION</u>	<u>STATUS</u>
Frazier Hall	1931	Women's Dormitory	Altered
Crandall Hall	1931	Women's Dormitory	Altered
Truth Hall	1931	Women's Dormitory	Altered
Chemistry	c.1940	Classroom	Altered

United States Department of the Interior
National Park Service

National Register of Historic Places
Continuation Sheet

Section 11 Page 9

Buffalo Zoo Entrance Court

Name of Property

Erie County, New York

County and State



John Edmonston Brent, date unknown

United States Department of the Interior
National Park Service

National Register of Historic Places
Continuation Sheet


Section 11 Page 11

Buffalo Zoo Entrance Court

Name of Property

Erie County, New York

County and State



1938 Buffalo Zoo Plan

NOTE
PRESENT BRIDGE PATH TO
BE REMOVED AS DIRECTED

NOTE
FOR ROAD GRADES ETC. SEE LATER
DRAWING. CURB GRAPES ARE TO BE AS
INDICATED HEREIN. FOR LOCATION OF
REMOVING SEE LATER DRAWING.


NOTE
THIS GATEWAY DETAILS TYPICAL
FOR GATEWAYS # 2, 3, 4, & 5 EXCEPT
THAT GATES & PIERS ARE NOT
ON A CURVE.

SCALE ELEVATION GATEWAYS #1 & 7
ALL JOINTING IN GATES TO BE WELDED
ALL MATERIAL FOR GATES & FENCE TOPS SOLID WROUGHT IRON.

SCALE ELEVATION OF SEATS ETC. AT A

WORKING DRAWING
ENTRANCE COURT & GATEWAYS
NEW ZOOLOGICAL GARDENS
DELAWARE PARK BUFFALO, N.Y.
PREPARED BY THE DEPARTMENT OF PARKS
FRANK A. COON COMMISSIONER
ROEDER J. KINKEL LANDSCAPE ARCHITECT
WILLIAM L. O'DAY ENGINEER





REVISED - 11-1-35
DRAWING # L-14
DRAWN BY J.E.D.
DATE - 10-28-35
APPROVED













TO COLVIN AVE

FROM AMHERST ST.
ONE-WAY TRAFFIC

SCALE 1/8" = 1 FT.



C-4-2




DETAILS FOR ENTRANCE PIERS
NEW ZOOLOGICAL GARDENS, BUFFALO, N. Y.

PREPARED BY DEPARTMENT OF PARKS
FRANK A. COON
COMMISSIONER


ROBERT J. KUNDEL
LANDSCAPE ARCHITECT

SCALES - 1/2" = 1', 3" = 1' AND FULL SIZE


DRAWN 1/27/36
BY E.A.S.
APPROVED [Signature]
REVISED 2/5/36
REVISED 6-25-36 J.E.B.




ELEVATION (Looking West)
SCALE 1/8" = 1 FT.



CROSS SECTION SHELTER HOUSE AT 'A-A'
SCALE 1/4" = 1 FT.



PLAN.
SCALE 1/8" = 1 FT.




SCALE ELEV. W.I. GATES AT BRIDLE PATH.

APPROVED	COMM. OF PARKS	
	COMM. OF PUBLIC WORKS	<i>[Signature]</i> 1/24/37
	DIR. OF BUILDINGS	<i>[Signature]</i> 1/24/37
	ARCHITECTURAL BUREAU	<i>[Signature]</i> 1/24/37
REVISIONS		

WORKING DRAWING
AMHERST STREET ENTRANCE
NEW ZOOLOGICAL GARDENS.
DELAWARE PARK BUFFALO, N.Y.
PREPARED BY THE DEPARTMENT OF PARKS
FRANK A. COON COMMISSIONER
ROEDER J. KINKEL LANDSCAPE ARCHITECT.

APPROVED -
F.A. Coon 1/24/37
COMM. OF PARKS

DRAWN BY - J.E. B.
DATE - 1-20-37
APPROVED -
C-4-31



Buffalo NE, NY
Quadrangle

Zoo Entrance Court

1:24,000
1 in = 2,000 ft

Copyright: © 2010 National Geographic Society

Coordinate System: NAD 1983 UTM Zone 18N
Projection: Transverse Mercator
Datum: North American 1983
Units: Meter



 Zoo Entrance Court

Tax Parcel Data:
Erie Co. RPS
<http://gis1.erie.gov/GC>







4761000

4761000



1:4,000
1 in = 333 ft



Coordinate System: NAD 1983 UTM Zone 18N
Projection: Transverse Mercator
Datum: North American 1983
Units: Meter

 Zoo Entrance Court

186000
Tax Parcel Data:
Erie Co. RPS
<http://gis1.erie.gov/GC>







ENTRANCE



ENTRANCE
←



DO NOT
BLOCK DRIVEWAY





GATE 4

GATE 4

NO PARKING
DO NOT
BLOCK GATE

GATE 4













National Register of Historic Places
Memo to File

Correspondence

The Correspondence consists of communications from (and possibly to) the nominating authority, notes from the staff of the National Register of Historic Places, and/or other material the National Register of Historic Places received associated with the property.

Correspondence may also include information from other sources, drafts of the nomination, letters of support or objection, memorandums, and ephemera which document the efforts to recognize the property.

UNITED STATES DEPARTMENT OF THE INTERIOR
NATIONAL PARK SERVICE

NATIONAL REGISTER OF HISTORIC PLACES
EVALUATION/RETURN SHEET

REQUESTED ACTION: NOMINATION

PROPERTY NAME: Buffalo Zoo Entrance Court

MULTIPLE NAME:

STATE & COUNTY: NEW YORK, Erie

DATE RECEIVED: 4/05/13 DATE OF PENDING LIST: 4/26/13
DATE OF 16TH DAY: 5/13/13 DATE OF 45TH DAY: 5/22/13
DATE OF WEEKLY LIST:

REFERENCE NUMBER: 13000305

REASONS FOR REVIEW:

APPEAL: N DATA PROBLEM: N LANDSCAPE: N LESS THAN 50 YEARS: N
OTHER: N PDIL: N PERIOD: N PROGRAM UNAPPROVED: N
REQUEST: N SAMPLE: N SLR DRAFT: N NATIONAL: N

COMMENT WAIVER: N

ACCEPT RETURN REJECT 5-22-13 DATE

ABSTRACT/SUMMARY COMMENTS:

**Entered in
The National Register
of
Historic Places**

RECOM./CRITERIA _____

REVIEWER _____ DISCIPLINE _____

TELEPHONE _____ DATE _____

DOCUMENTATION see attached comments Y/N see attached SLR Y/N

If a nomination is returned to the nominating authority, the nomination is no longer under consideration by the NPS.



THE ASSEMBLY
STATE OF NEW YORK
ALBANY

CHAIR
Subcommittee on
Oversight of Minority and
Women-Owned Business Enterprises

COMMITTEES
Alcoholism and Drug Abuse
Environmental Conservation
Governmental Operations
Health
Higher Education
Insurance

CRYSTAL D. PEOPLES-STOKES
141ST Assembly District
Erie County

December 10, 2012

Mr. Daniel McEneny
New York State Division for Historic Preservation
Peebles Island State Park
P.O. Box 189
Waterford, NY 12188-0189

RE: Nomination of "John E. Brent Landscape Gates and Streetcar Shelter at Buffalo Zoo" to the National Register of Historic Places

Dear Mr. McEneny,

I enthusiastically support the nomination of "John E. Brent Landscape Gates and Streetcar Shelter at Buffalo Zoo" to the National Register of Historic Places. These seventy-seven year old gates are extremely rare and important local and national historic resources. They represent the heritage and image of the city of Buffalo and one of its important institutions, the Buffalo Zoo.

In addition, National Register designation of the gates would be invaluable in our efforts to bolster heritage tourism. This listing would help our state and nation recognize historic contributions of African American landscape architects and architects who are currently under-represented. Mr. John E. Brent was a tireless community and civic leader in Buffalo. He was a role model for all Buffalonians, regardless of race, class or religion. The Buffalo Zoo is already exploring ways to incorporate Mr. Brent's work into its "Ecosystems Architects" public school science module.

I urge the State Board of Historic Preservation to consider all aspects of American culture that the gates and Mr. Brent represent. The gates are the only remaining landscape composition by Mr. Brent in the United States. The citizens of Buffalo and America cannot afford to lose these important landmark structures.

Please do not hesitate to call upon me if I may be of assistance with this very important project.

Sincerely,

Hon. Crystal D. Peoples-Stokes
New York State Assembly-141st District

RESOLUTION

By: Michael LoCurto Delaware District Council Member

RE: Preservation of Buffalo Zoo Gates

WHEREAS: The Buffalo Zoo is the third oldest zoo in the United States and a rare public asset to the City of Buffalo and the United States; and

WHEREAS: Gates number three and number four have provided a significant part of the physical public image and character of the Buffalo Zoo for more than 75 years; and

WHEREAS: Original architectural documents in the possession of the City of Buffalo have authenticated the work of African American architect John Edmonston Brent on many aspects of the Buffalo Zoo from 1935 to 1957, including gates number three and number four; and

WHEREAS: The professional legacy of John Edmonston Brent as an African American early twentieth century pioneer in architecture is of national significance; and

WHEREAS: John Edmonston Brent was the first African American architect in the City of Buffalo, and made many important and historic contributions to our community, including as the architect who designed the former Michigan Street YMCA (the second "Colored YMCA" designed by an African American in the United States); the first president, of the NAACP Buffalo Branch; and an architect in the City Parks Department for many years; and


WHEREAS: The Zoo gates number three and number four represent two of the last remaining, and complete, works of John Edmonston Brent in America.

NOW, THEREFORE, BE IT RESOLVED:

RESOLVED: That Buffalo Common Council supports and endorses the preservation of Zoo gate, number three and number four; and be it further

RESOLVED: That the Buffalo Zoo be authorized to have formal nominations prepared and submitted for Zoo gate number three (3) and number four (4) to the National Register of Historic Places (NRHP) in time for January, 2013 review by the New York State Historic Preservation Office; and be it finally

RESOLVED: That the Buffalo Zoo shall hereby be authorized to work with nationally recognized consultants Everett L. Fly and Ellen P. Hunt to conduct the necessary historical research and documentation and prepare the nominations meeting the requirements of the National Register of Historic Places. No fees for the research and application production will be charged to the City of Buffalo.



Michael LoCurto
Delaware District Council Member

17 December 2012

New York State Division for Historic Preservation
New York State Office of Parks, Recreation & Historic Preservation
Peebles Island State Park
P.O. Box 189
Waterford, NY 12188-0189
Attn: Mr. Daniel McEneny

RE: Nomination of "John E. Brent Landscape Gates and Streetcar Shelter at Buffalo Zoo" to the National Register of Historic Places

Mr. McEneny:

The descendants of John Edmonston Brent enthusiastically support the listing of the "John E. Brent Landscape Gates and Streetcar Shelter at Buffalo Zoo" to the National Register of Historic Places.

Mr. Brent was our father and great uncle. We remember him taking us to the Buffalo Zoo on many occasions. Each weekday morning he left his home and went to work downtown at Buffalo City Hall. He returned home at noon for lunch, and then left again to work at the Zoo. But, Uncle John never told us what he did at the Zoo or pointed out any of the exhibits he planned and designed. We were amazed and delighted to learn more of his professional accomplishments earlier this year. We are only aware of Uncle John's work at the Buffalo Zoo that remains from his career. To us he was simply "Uncle John", and a man who always worked to help his community.

We understand that only a tiny handful of African Americans worked on significant places as the Buffalo Zoo in Uncle John's day. We would be honored if Uncle John's efforts could be memorialized and his story could be used as inspiration for young people in America.

Please contact us if we can do more to recognize the work of Mr. John E. Brent.

Sincerely,

Brent J Rollins
Phone # (716) 886-3622

CC: Dr. Donna Fernandes, President and CEO Buffalo Zoo
300 Parkside Avenue
Buffalo, New York 14214

RECEIVED
DEC 24 2012

HISTORIC PRESERVATION
FIELD SERVICES BUREAU

17 December 2012

New York State Division for Historic Preservation
New York State Office of Parks, Recreation & Historic Preservation
Peebles Island State Park
P.O. Box 189
Waterford, NY 12188-0189
Attn: Mr. Daniel McEneny

RE: Nomination of "John E. Brent Landscape Gates and Streetcar Shelter at Buffalo Zoo" to the National Register of Historic Places

Mr. McEneny:

The descendants of John Edmonston Brent enthusiastically support the listing of the "John E. Brent Landscape Gates and Streetcar Shelter at Buffalo Zoo" to the National Register of Historic Places.

Mr. Brent was our father and great uncle. We remember him taking us to the Buffalo Zoo on many occasions. Each weekday morning he left his home and went to work downtown at Buffalo City Hall. He returned home at noon for lunch, and then left again to work at the Zoo. But, Uncle John never told us what he did at the Zoo or pointed out any of the exhibits he planned and designed. We were amazed and delighted to learn more of his professional accomplishments earlier this year. We are only aware of Uncle John's work at the Buffalo Zoo that remains from his career. To us he was simply "Uncle John", and a man who always worked to help his community.

We understand that only a tiny handful of African Americans worked on significant places as the Buffalo Zoo in Uncle John's day. We would be honored if Uncle John's efforts could be memorialized and his story could be used as inspiration for young people in America.

Please contact us if we can do more to recognize the work of Mr. John E. Brent.

Sincerely,

Jennifer McEneny
Phone # (716) 881-5808

CC: Dr. Donna Fernandes, President and CEO Buffalo Zoo
300 Parkside Avenue
Buffalo, New York 14214

17 December 2012

New York State Division for Historic Preservation
New York State Office of Parks, Recreation & Historic Preservation
Peebles Island State Park
P.O. Box 189
Waterford, NY 12188-0189
Attn: Mr. Daniel McEneny

RE: Nomination of "John E. Brent Landscape Gates and Streetcar Shelter at Buffalo Zoo" to the National Register of Historic Places

Mr. McEneny:

Placing the "John E. Brent Landscape Gates and Streetcar Shelter at Buffalo Zoo" on the National Register of Historic Places is very important in many ways. Few African Americans have ever had the opportunity to work on such an important place as the Buffalo Zoo. In Mr. Brent's day the number of trained African Americans given the responsibility of creating places that all people could use and enjoy was even smaller.

So many achievements by African Americans have been ignored or destroyed over time. Too often the physical products of early twentieth century African Americans are merely considered as insignificant parts of American culture and places. Mr. Brent's work at the Buffalo Zoo stands clearly on its own in the foreground. The gates by Mr. Brent gives us an opportunity to protect quality work by at least one African American.

Though Mr. John E. Brent was a humble man, he was a very special and honorable member of the Buffalo community. If his story could be told and celebrated it would be a role model for everyone in the United States, especially young people in today's cities.

It would be tragic to ignore Mr. Brent and his work. Please contact me if I can do anything more to help recognize the work of this great American, Mr. John E. Brent.

Sincerely,

Karin Voorhis

Karin Voorhis

CC: Dr. Donna Fernandes, President and CEO Buffalo Zoo
300 Parkside Avenue
Buffalo, New York 14214



17 December 2012

New York State Division for Historic Preservation
New York State Office of Parks, Recreation & Historic Preservation
Peebles Island State Park
P.O. Box 189
Waterford, NY 12188-0189
Attn: Mr. Daniel McEneny



RE: Nomination of "John E. Brent Landscape Gates and Streetcar Shelter at Buffalo Zoo" to the National Register of Historic Places

Mr. McEneny:

Placing the "John E. Brent Landscape Gates and Streetcar Shelter at Buffalo Zoo" on the National Register of Historic Places is very important in many ways. Few African Americans have ever had the opportunity to work on such an important place as the Buffalo Zoo. In Mr. Brent's day the number of trained African Americans given the responsibility of creating places that all people could use and enjoy was even smaller.

So many achievements by African Americans have been ignored or destroyed over time. Too often the physical products of early twentieth century African Americans are merely considered as insignificant parts of American culture and places. Mr. Brent's work at the Buffalo Zoo stands clearly on its own in the foreground. The gates by Mr. Brent gives us an opportunity to protect quality work by at least one African American.

Though Mr. John E. Brent was a humble man, he was a very special and honorable member of the Buffalo community. If his story could be told and celebrated it would be a role model for everyone in the United States, especially young people in today's cities.

It would be tragic to ignore Mr. Brent and his work. Please contact me if I can do anything more to help recognize the work of this great American, Mr. John E. Brent.

Sincerely,

Sherry White

CC: Dr. Donna Fernandes, President and CEO Buffalo Zoo
300 Parkside Avenue
Buffalo, New York 14214

17 December 2012

New York State Division for Historic Preservation
New York State Office of Parks, Recreation & Historic Preservation
Peebles Island State Park
P.O. Box 189
Waterford, NY 12188-0189
Attn: Mr. Daniel McEneny

RE: Nomination of "John E. Brent Landscape Gates and Streetcar Shelter at Buffalo Zoo" to the National Register of Historic Places

Mr. McEneny:

The descendants of John Edmonston Brent enthusiastically support the listing of the "John E. Brent Landscape Gates and Streetcar Shelter at Buffalo Zoo" to the National Register of Historic Places.

Mr. Brent was our father and great uncle. We remember him taking us to the Buffalo Zoo on many occasions. Each weekday morning he left his home and went to work downtown at Buffalo City Hall. He returned home at noon for lunch, and then left again to work at the Zoo. But, Uncle John never told us what he did at the Zoo or pointed out any of the exhibits he planned and designed. We were amazed and delighted to learn more of his professional accomplishments earlier this year. We are only aware of Uncle John's work at the Buffalo Zoo that remains from his career. To us he was simply "Uncle John", and a man who always worked to help his community.

We understand that only a tiny handful of African Americans worked on significant places as the Buffalo Zoo in Uncle John's day. We would be honored if Uncle John's efforts could be memorialized and his story could be used as inspiration for young people in America.

Please contact us if we can do more to recognize the work of Mr. John E. Brent.

Sincerely,

A handwritten signature in blue ink, appearing to read "James H. Saberski", is written over the word "Sincerely,".

CC: Dr. Donna Fernandes, President and CEO Buffalo Zoo
300 Parkside Avenue
Buffalo, New York 14214

17 December 2012

New York State Division for Historic Preservation
New York State Office of Parks, Recreation & Historic Preservation
Peebles Island State Park
P.O. Box 189
Waterford, NY 12188-0189
Attn: Mr. Daniel McEneny

RE: Nomination of "John E. Brent Landscape Gates and Streetcar Shelter at Buffalo Zoo" to the National Register of Historic Places

Mr. McEneny:


Placing the "John E. Brent Landscape Gates and Streetcar Shelter at Buffalo Zoo" on the National Register of Historic Places is very important in many ways. Few African Americans have ever had the opportunity to work on such an important place as the Buffalo Zoo. In Mr. Brent's day the number of trained African Americans given the responsibility of creating places that all people could use and enjoy was even smaller.

So many achievements by African Americans have been ignored or destroyed over time. Too often the physical products of early twentieth century African Americans are merely considered as insignificant parts of American culture and places. Mr. Brent's work at the Buffalo Zoo stands clearly on its own in the foreground. The gates by Mr. Brent gives us an opportunity to protect quality work by at least one African American.

Though Mr. John E. Brent was a humble man, he was a very special and honorable member of the Buffalo community. If his story could be told and celebrated it would be a role model for everyone in the United States, especially young people in today's cities.

It would be tragic to ignore Mr. Brent and his work. Please contact me if I can do anything more to help recognize the work of this great American, Mr. John E. Brent.

Sincerely,

A handwritten signature in cursive script that reads "Sandra B. Mayo". The signature is written in black ink and includes a long, sweeping horizontal line at the end.

CC: Dr. Donna Fernandes, President and CEO Buffalo Zoo
300 Parkside Avenue
Buffalo, New York 14214

17 December 2012

New York State Division for Historic Preservation
New York State Office of Parks, Recreation & Historic Preservation
Peebles Island State Park
P.O. Box 189
Waterford, NY 12188-0189
Attn: Mr. Daniel McEneny

RE: Nomination of "John E. Brent Landscape Gates and Streetcar Shelter at Buffalo Zoo" to the National Register of Historic Places

Mr. McEneny:


Placing the "John E. Brent Landscape Gates and Streetcar Shelter at Buffalo Zoo" on the National Register of Historic Places is very important in many ways. Few African Americans have ever had the opportunity to work on such an important place as the Buffalo Zoo. In Mr. Brent's day the number of trained African Americans given the responsibility of creating places that all people could use and enjoy was even smaller.

So many achievements by African Americans have been ignored or destroyed over time. Too often the physical products of early twentieth century African Americans are merely considered as insignificant parts of American culture and places. Mr. Brent's work at the Buffalo Zoo stands clearly on its own in the foreground. The gates by Mr. Brent gives us an opportunity to protect quality work by at least one African American.

Though Mr. John E. Brent was a humble man, he was a very special and honorable member of the Buffalo community. If his story could be told and celebrated it would be a role model for everyone in the United States, especially young people in today's cities.

It would be tragic to ignore Mr. Brent and his work. Please contact me if I can do anything more to help recognize the work of this great American, Mr. John E. Brent.

Sincerely,

A handwritten signature in blue ink that reads "James W. Maye". The signature is written in a cursive style with a large, looped initial "J".

CC: Dr. Donna Fernandes, President and CEO Buffalo Zoo
300 Parkside Avenue
Buffalo, New York 14214

17 December 2012

New York State Division for Historic Preservation
New York State Office of Parks, Recreation & Historic Preservation
Peebles Island State Park
P.O. Box 189
Waterford, NY 12188-0189
Attn: Mr. Daniel McEneny

RE: Nomination of "John E. Brent Landscape Gates and Streetcar Shelter at Buffalo Zoo" to the National Register of Historic Places

Mr. McEneny:


Placing the "John E. Brent Landscape Gates and Streetcar Shelter at Buffalo Zoo" on the National Register of Historic Places is very important in many ways. Few African Americans have ever had the opportunity to work on such an important place as the Buffalo Zoo. In Mr. Brent's day the number of trained African Americans given the responsibility of creating places that all people could use and enjoy was even smaller.

So many achievements by African Americans have been ignored or destroyed over time. Too often the physical products of early twentieth century African Americans are merely considered as insignificant parts of American culture and places. Mr. Brent's work at the Buffalo Zoo stands clearly on its own in the foreground. The gates by Mr. Brent gives us an opportunity to protect quality work by at least one African American.

Though Mr. John E. Brent was a humble man, he was a very special and honorable member of the Buffalo community. If his story could be told and celebrated it would be a role model for everyone in the United States, especially young people in today's cities.

It would be tragic to ignore Mr. Brent and his work. Please contact me if I can do anything more to help recognize the work of this great American, Mr. John E. Brent.

Sincerely,

A handwritten signature in black ink, appearing to read "Palmer W. Jacobson". The signature is fluid and cursive, with a large, stylized initial 'P'.

CC: Dr. Donna Fernandes, President and CEO Buffalo Zoo
300 Parkside Avenue
Buffalo, New York 14214

17 December 2012

New York State Division for Historic Preservation
New York State Office of Parks, Recreation & Historic Preservation
Peebles Island State Park
P.O. Box 189
Waterford, NY 12188-0189
Attn: Mr. Daniel McEneny

RE: Nomination of "John E. Brent Landscape Gates and Streetcar Shelter at Buffalo Zoo" to the National Register of Historic Places

Mr. McEneny:

Placing the "John E. Brent Landscape Gates and Streetcar Shelter at Buffalo Zoo" on the National Register of Historic Places is very important in many ways. Few African Americans have ever had the opportunity to work on such an important place as the Buffalo Zoo. In Mr. Brent's day the number of trained African Americans given the responsibility of creating places that all people could use and enjoy was even smaller.

So many achievements by African Americans have been ignored or destroyed over time. Too often the physical products of early twentieth century African Americans are merely considered as insignificant parts of American culture and places. Mr. Brent's work at the Buffalo Zoo stands clearly on its own in the foreground. The gates by Mr. Brent gives us an opportunity to protect quality work by at least one African American.

Though Mr. John E. Brent was a humble man, he was a very special and honorable member of the Buffalo community. If his story could be told and celebrated it would be a role model for everyone in the United States, especially young people in today's cities.

It would be tragic to ignore Mr. Brent and his work. Please contact me if I can do anything more to help recognize the work of this great American, Mr. John E. Brent.

Sincerely,

A handwritten signature in cursive script that reads "Alan Schagger" followed by a stylized flourish.

CC: Dr. Donna Fernandes, President and CEO Buffalo Zoo
300 Parkside Avenue
Buffalo, New York 14214

17 December 2012

New York State Division for Historic Preservation
New York State Office of Parks, Recreation & Historic Preservation
Peebles Island State Park
P.O. Box 189
Waterford, NY 12188-0189
Attn: Mr. Daniel McEneny

RE: Nomination of "John E. Brent Landscape Gates and Streetcar Shelter at Buffalo Zoo" to the National Register of Historic Places

Mr. McEneny:

Placing the "John E. Brent Landscape Gates and Streetcar Shelter at Buffalo Zoo" on the National Register of Historic Places is very important in many ways. Few African Americans have ever had the opportunity to work on such an important place as the Buffalo Zoo. In Mr. Brent's day the number of trained African Americans given the responsibility of creating places that all people could use and enjoy was even smaller.

So many achievements by African Americans have been ignored or destroyed over time. Too often the physical products of early twentieth century African Americans are merely considered as insignificant parts of American culture and places. Mr. Brent's work at the Buffalo Zoo stands clearly on its own in the foreground. The gates by Mr. Brent gives us an opportunity to protect quality work by at least one African American.

Though Mr. John E. Brent was a humble man, he was a very special and honorable member of the Buffalo community. If his story could be told and celebrated it would be a role model for everyone in the United States, especially young people in today's cities.

It would be tragic to ignore Mr. Brent and his work. Please contact me if I can do anything more to help recognize the work of this great American, Mr. John E. Brent.

Sincerely,

Ann L. Schragger
Annapolis, Md.

CC: Dr. Donna Fernandes, President and CEO Buffalo Zoo
300 Parkside Avenue
Buffalo, New York 14214

17 December 2012

New York State Division for Historic Preservation
New York State Office of Parks, Recreation & Historic Preservation
Peebles Island State Park
P.O. Box 189
Waterford, NY 12188-0189
Attn: Mr. Daniel McEneny

RE: Nomination of "John E. Brent Landscape Gates and Streetcar Shelter at Buffalo Zoo" to the National Register of Historic Places

Mr. McEneny:

Placing the "John E. Brent Landscape Gates and Streetcar Shelter at Buffalo Zoo" on the National Register of Historic Places is very important in many ways. Few African Americans have ever had the opportunity to work on such an important place as the Buffalo Zoo. In Mr. Brent's day the number of trained African Americans given the responsibility of creating places that all people could use and enjoy was even smaller.

So many achievements by African Americans have been ignored or destroyed over time. Too often the physical products of early twentieth century African Americans are merely considered as insignificant parts of American culture and places. Mr. Brent's work at the Buffalo Zoo stands clearly on its own in the foreground. The gates by Mr. Brent gives us an opportunity to protect quality work by at least one African American.

Though Mr. John E. Brent was a humble man, he was a very special and honorable member of the Buffalo community. If his story could be told and celebrated it would be a role model for everyone in the United States, especially young people in today's cities.

It would be tragic to ignore Mr. Brent and his work. Please contact me if I can do anything more to help recognize the work of this great American, Mr. John E. Brent.

Sincerely,

Dr. William A. Burrell Ph.D.

CC: Dr. Donna Fernandes, President and CEO Buffalo Zoo
300 Parkside Avenue
Buffalo, New York 14214

17 December 2012

New York State Division for Historic Preservation
New York State Office of Parks, Recreation & Historic Preservation
Peebles Island State Park
P.O. Box 189
Waterford, NY 12188-0189
Attn: Mr. Daniel McEneny

RE: Nomination of "John E. Brent Landscape Gates and Streetcar Shelter at Buffalo Zoo" to the National Register of Historic Places

Mr. McEneny:


Placing the "John E. Brent Landscape Gates and Streetcar Shelter at Buffalo Zoo" on the National Register of Historic Places is very important in many ways. Few African Americans have ever had the opportunity to work on such an important place as the Buffalo Zoo. In Mr. Brent's day the number of trained African Americans given the responsibility of creating places that all people could use and enjoy was even smaller.

So many achievements by African Americans have been ignored or destroyed over time. Too often the physical products of early twentieth century African Americans are merely considered as insignificant parts of American culture and places. Mr. Brent's work at the Buffalo Zoo stands clearly on its own in the foreground. The gates by Mr. Brent gives us an opportunity to protect quality work by at least one African American.

Though Mr. John E. Brent was a humble man, he was a very special and honorable member of the Buffalo community. If his story could be told and celebrated it would be a role model for everyone in the United States, especially young people in today's cities.

It would be tragic to ignore Mr. Brent and his work. Please contact me if I can do anything more to help recognize the work of this great American, Mr. John E. Brent.

Sincerely,


Yvonne J. Burrell

CC: Dr. Donna Fernandes, President and CEO Buffalo Zoo
300 Parkside Avenue
Buffalo, New York 14214

17 December 2012

New York State Division for Historic Preservation
New York State Office of Parks, Recreation & Historic Preservation
Peebles Island State Park
P.O. Box 189
Waterford, NY 12188-0189
Attn: Mr. Daniel McEneny

RE: Nomination of "John E. Brent Landscape Gates and Streetcar Shelter at Buffalo Zoo" to the National Register of Historic Places

Mr. McEneny:

Placing the "John E. Brent Landscape Gates and Streetcar Shelter at Buffalo Zoo" on the National Register of Historic Places is very important in many ways. Few African Americans have ever had the opportunity to work on such an important place as the Buffalo Zoo. In Mr. Brent's day the number of trained African Americans given the responsibility of creating places that all people could use and enjoy was even smaller.

So many achievements by African Americans have been ignored or destroyed over time. Too often the physical products of early twentieth century African Americans are merely considered as insignificant parts of American culture and places. Mr. Brent's work at the Buffalo Zoo stands clearly on its own in the foreground. The gates by Mr. Brent gives us an opportunity to protect quality work by at least one African American.

Though Mr. John E. Brent was a humble man, he was a very special and honorable member of the Buffalo community. If his story could be told and celebrated it would be a role model for everyone in the United States, especially young people in today's cities.

It would be tragic to ignore Mr. Brent and his work. Please contact me if I can do anything more to help recognize the work of this great American, Mr. John E. Brent.

Sincerely,

A handwritten signature in cursive script that reads "Dana D. Jackson". The signature is written in black ink and is positioned above the contact information for Dr. Donna Fernandes.

CC: Dr. Donna Fernandes, President and CEO Buffalo Zoo
300 Parkside Avenue
Buffalo, New York 14214

17 December 2012

New York State Division for Historic Preservation
New York State Office of Parks, Recreation & Historic Preservation
Peebles Island State Park
P.O. Box 189
Waterford, NY 12188-0189
Attn: Mr. Daniel McEneny

RE: Nomination of "John E. Brent Landscape Gates and Streetcar Shelter at Buffalo Zoo" to the National Register of Historic Places

Mr. McEneny:

Placing the "John E. Brent Landscape Gates and Streetcar Shelter at Buffalo Zoo" on the National Register of Historic Places is very important in many ways. Few African Americans have ever had the opportunity to work on such an important place as the Buffalo Zoo. In Mr. Brent's day the number of trained African Americans given the responsibility of creating places that all people could use and enjoy was even smaller.

So many achievements by African Americans have been ignored or destroyed over time. Too often the physical products of early twentieth century African Americans are merely considered as insignificant parts of American culture and places. Mr. Brent's work at the Buffalo Zoo stands clearly on its own in the foreground. The gates by Mr. Brent gives us an opportunity to protect quality work by at least one African American.

Though Mr. John E. Brent was a humble man, he was a very special and honorable member of the Buffalo community. If his story could be told and celebrated it would be a role model for everyone in the United States, especially young people in today's cities.

It would be tragic to ignore Mr. Brent and his work. Please contact me if I can do anything more to help recognize the work of this great American, Mr. John E. Brent.

Sincerely,

Pamela J. Robinson - Wash. D.C.
Arnold + Crispin - Wash DC

CC: Dr. Donna Fernandes, President and CEO Buffalo Zoo
300 Parkside Avenue
Buffalo, New York 14214

17 December 2012

New York State Division for Historic Preservation
New York State Office of Parks, Recreation & Historic Preservation
Peebles Island State Park
P.O. Box 189
Waterford, NY 12188-0189
Attn: Mr. Daniel McEneny

RE: Nomination of "John E. Brent Landscape Gates and Streetcar Shelter at Buffalo Zoo" to the National Register of Historic Places

Mr. McEneny:

Placing the "John E. Brent Landscape Gates and Streetcar Shelter at Buffalo Zoo" on the National Register of Historic Places is very important in many ways. Few African Americans have ever had the opportunity to work on such an important place as the Buffalo Zoo. In Mr. Brent's day the number of trained African Americans given the responsibility of creating places that all people could use and enjoy was even smaller.

So many achievements by African Americans have been ignored or destroyed over time. Too often the physical products of early twentieth century African Americans are merely considered as insignificant parts of American culture and places. Mr. Brent's work at the Buffalo Zoo stands clearly on its own in the foreground. The gates by Mr. Brent gives us an opportunity to protect quality work by at least one African American.

Though Mr. John E. Brent was a humble man, he was a very special and honorable member of the Buffalo community. If his story could be told and celebrated it would be a role model for everyone in the United States, especially young people in today's cities.

It would be tragic to ignore Mr. Brent and his work. Please contact me if I can do anything more to help recognize the work of this great American, Mr. John E. Brent.

Sincerely,

A handwritten signature in blue ink that reads "Andrew Robinson, D.D.S." The signature is written in a cursive style.

CC: Dr. Donna Fernandes, President and CEO Buffalo Zoo
300 Parkside Avenue
Buffalo, New York 14214



Andrew M. Cuomo
Governor

Rose Harvey
Commissioner

New York State Office of Parks, Recreation and Historic Preservation

Historic Preservation Field Services Bureau • Peebles Island, PO Box 189, Waterford, New York 12188-0189

518-237-8643

www.nysparks.com

29 March 2013

Alexis Abernathy
National Park Service
National Register of Historic Places
1201 Eye St. NW, 8th Floor
Washington, D.C. 20005

Re: National Register Nominations

Dear Ms. Abernathy:

I am pleased to enclose the following five National Register nominations to be considered for listing by the Keeper of the National Register:

Fire Hook and Ladder Company No. 14, New York County
E.M. Hager & Sons Co. Building, Erie County
Hurricane Stock Farm, Montgomery County
Buffalo Zoo Entrance Court, Erie County
South Wedge Historic District, Monroe County

Please note that we are submitting each nomination on disc. For each nomination, I have enclosed two discs, one containing the nomination and maps and the other containing the digital images. I have also enclosed a cover sheet signed by Ruth Pierpont for each. Please feel free to call me at 518.237.8643 x 3261 if you have any questions.

Sincerely:

Kathleen LaFrank
National Register Coordinator
New York State Historic Preservation Office