


1769

United States Department of the Interior
National Park Service

National Register of Historic Places
Registration Form



This form is for use in nominating or requesting determinations for individual properties and districts. See instructions in *How to Complete the National Register of Historic Places registration Form* (National Register Bulletin 16A). Complete each item by marking "x" in the appropriate box or by entering the information requested. If an item does not apply to the property being documented, enter "N/A" for "not applicable." For functions, architectural classification, materials, and areas of significance, enter only categories and subcategories from the instructions. Place additional entries and narrative items on continuation sheets (NPS Form 10-900a). Use a typewriter, word processor, or computer, to complete all items.

1. Name of Property

historic name Galloway-Speedway Historic District

other names/site number NA

2. Location

street & number N. Parkway, Faxon, Greenlaw, Galloway, and Forrest Avenues

NA not for publication

city or town Memphis

vicinity N/A

state Tennessee

code TN

county Shelby

code 157

zip code _____

3. State/Federal Agency Certification

As the designated authority under the National Historic Preservation Act, as amended, I hereby certify that this nomination request for determination of eligibility meets the documentation standards for registering properties in the National Register of Historic Places and meets the procedural and professional requirements set for in 36 CFR Part 60. In my opinion, the property meets does not meet the National Register criteria. I recommend that this property be considered significant nationally statewide locally. (See continuation sheet for additional comments.)

Herbert L. Hayden
Signature of certifying official/Title

6/9/04
Date

Deputy State Historic Preservation Officer, Tennessee Historical Commission

State or Federal agency and bureau

In my opinion, the property meets does not meet the National Register criteria. (See Continuation sheet for additional comments.)

Signature of certifying official/Title

Date

State or Federal agency and bureau

4. National Park Service Certification

I hereby certify that the property is:

entered in the National Register.

See continuation sheet

determined eligible for the National Register.

See continuation sheet

determined not eligible for the National Register

removed from the National Register.

other,

(explain):

Signature of the Keeper

Date of Action

Edson H. Beall

7/28/04

5. Classification

Ownership of Property
(Check as many boxes as apply)

Category of Property
(Check only one box)

Number of Resources within Property
(Do not include previously listed resources in count)

- private
- public-local
- public-State
- public-Federal
- building(s)
- district
- site
- structure
- object

Contributing	Noncontributing	
381	68	buildings
		sites
5		structures
		objects
386	68	Total

Name of related multiple property listing
(Enter "N/A" if property is not part of a multiple property listing.)

Number of Contributing resources previously listed in the National Register

Historic Residential Resources of Memphis, Shelby County, TN

1

6. Function or Use

Historic Functions

(Enter categories from instructions)

- DOMESTIC: Single Dwelling
- DOMESTIC: Multiple Dwelling
- RELIGION: Religious Facility
- GOVERNMENT: Public Works
- GOVERNMENT: Fire Station
- TRANSPORTATION: Road-Related
- DOMESTIC: Secondary structure

Current Functions

(Enter categories from instructions)

- DOMESTIC: Single Dwelling
- DOMESTIC: Multiple Dwelling
- RELIGION: Religious Facility
- GOVERNMENT: Public Works
- SOCIAL: Clubhouse
- TRANSPORTATION: Road-Related
- DOMESTIC: Secondary structure

7. Description

Architectural Classification

(Enter categories from instructions)

- Bungalow/Craftsman
- Colonial Revival
- Tudor Revival
- Spanish Colonial Revival
- OTHER: American Foursquare; Minimal Traditional; Folk Victorian

Materials

(Enter categories from instructions)

- foundation CONCRETE, BRICK, STONE
- walls WOOD, vinyl, aluminum, STUCCO, BRICK STONE
- roof ASPHALT, METAL
- other WOOD, STONE

Narrative Description

(Describe the historic and current condition of the property on one or more continuation sheets.)

8. Statement of Significance

Applicable National Register Criteria

(Mark "x" in one or more boxes for the criteria qualifying the property for National Register listing.)

- A** Property is associated with events that have made a significant contribution to the broad patterns of our history.
- B** Property is associated with the lives of persons significant in our past.
- C** Property embodies the distinctive characteristics of a type, period, or method of construction or represents the work of a master, or possesses high artistic values, or represents a significant and distinguishable entity whose components lack individual distinction.
- D** Property has yielded, or is likely to yield, information important in prehistory or history.

Criteria Considerations

(Mark "x" in all boxes that apply.)

Property is:

- A** owned by a religious institution or used for religious purposes.
- B** removed from its original location.
- C** moved from its original location.
- D** a cemetery.
- E** a reconstructed building, object, or structure.
- F** a commemorative property
- G** less than 50 years of age or achieved significance within the past 50 years.

Areas of Significance

(Enter categories from instructions)

ARCHITECTURE
COMMUNITY PLANNING AND DEVELOPMENT

Period of Significance

Ca. 1900 – ca. 1953

Significant Dates

N/A

Significant Person

(complete if Criterion B is marked)

N/A

Cultural Affiliation

N/A

Architect/Builder

Regan and Weller
Various, unknown

Narrative Statement of Significance

(Explain the significance of the property on one or more continuation sheets.)

9. Major Bibliographical References

Bibliography

(Cite the books, articles, and other sources used in preparing this form on one or more continuation sheets.)

Previous documentation on file (NPS):

- preliminary determination of individual listing (36 CFR 67) has been requested
- previously listed in the National Register (1 property)
- Previously determined eligible by the National Register
- designated a National Historic Landmark
- recorded by Historic American Buildings Survey # _____
- recorded by Historic American Engineering Record # _____

Primary location of additional data:

- State Historic Preservation Office
 - Other State Agency
 - Federal Agency
 - Local Government
 - University
 - Other
- Name of repository: Tennessee Historical Commission

10. Geographical Data

Acreage of Property Approximately 84 acres Northwest Memphis 404 NE

UTM References

(place additional UTM references on a continuation sheet.)

1	<u>15</u>	<u>770345</u>	<u>3894532</u>	3	<u>15</u>	<u>771275</u>	<u>3894049</u>
	Zone	Easting	Northing		Zone	Easting	Northing
2	<u>15</u>	<u>771341</u>	<u>3894516</u>	4	<u>15</u>	<u>770340</u>	<u>3894069</u>

See continuation sheet

Verbal Boundary Description

(Describe the boundaries of the property on a continuation sheet.)

Boundary Justification

(Explain why the boundaries were selected on a continuation sheet.)

11. Form Prepared By

name/title Teresa Douglass, Historic Preservation Specialist
organization Thomason & Associates date November 2003
street & number PO Box 121225 telephone 615/385-4960
city or town Nashville state TN zip code 37212

Additional Documentation

submit the following items with the completed form:

Continuation Sheets

Maps

A **USGS map** (7.5 Or 15 minute series) indicating the property's location

A **Sketch map** for historic districts and properties having large acreage or numerous resources.

Photographs

Representative **black and white photographs** of the property.

Additional items

(Check with the SHPO) or FPO for any additional items

Property Owner

(Complete this item at the request of SHPO or FPO.)

name Multiple, more than fifty, legal notice
street & number _____ telephone _____
city or town _____ state _____ zip code _____

Paperwork Reduction Act Statement: This information is being collected for applications to the National Register of Historic Places to nominate properties for listing or determine eligibility for listing, to list properties, and to amend existing listing. Response to this request is required to obtain a benefit in accordance with the National Historic Preservation Act, as amended (16 U.S.C. 470 *et seq.*)

Estimated Burden Statement: Public reporting burden for this form is estimated to average 18.1 hours per response including time for reviewing instructions, gathering and maintaining data, and completing and reviewing the form. Direct comments regarding this burden estimate or any aspect of this form to the Chief, Administrative Services Division, National Park Service, P. O. Box 37127, Washington, DC 20013-7127; and the Office of Management and Budget, Paperwork Reductions Projects (1024-0018), Washington, DC 20303.

United States Department of the Interior
National Park Service

National Register of Historic Places Continuation Sheet

Section number 7 Page 1

Galloway-Speedway Historic District
Memphis, Shelby County, Tennessee

DESCRIPTION

The Galloway-Speedway Historic District is located along portions of Galloway, Greenlaw, Faxon, and Forrest Avenues, and North Parkway within the city limits of Memphis, Tennessee. The district is residential in character and primarily contains dwellings constructed from ca. 1910 to ca. 1950. The vast majority of dwellings within the district are Craftsman/Bungalow designs, including numerous examples of "Airplane" Bungalows. Other architectural styles represented include Folk Victorian, American Foursquare, Tudor Revival, Colonial Revival, and Minimal Traditional. A few examples of vernacular house forms, such as, pyramid square, and gabled ell designs, also appear in the district. In addition to dwellings, the Galloway-Speedway Historic District contains one fire station, two churches, and four pump stations/wellhouses. The district contains a total of 331 primary buildings and structures, of which 309 or 94% are considered to be contributing to the character of the district. In addition to the primary buildings there are an additional 77 contributing outbuildings and 46 non-contributing outbuildings. The district retains a high degree of architectural integrity with minimal modern in-fill or vacant lots. The Galloway-Speedway Historic District meets the registration requirements for the property type "Residential Historic Districts" set forth in the Multiple Property Documentation Form "Residential Development in Memphis, Shelby County, Tennessee" and "Residential Development in Memphis, Shelby County, Tennessee (additional documentation)."

The Galloway-Speedway neighborhood developed in the early twentieth century as Memphis experienced substantial growth. From 1880 to 1900, the city's population had more than tripled, rising from around 34,000 to over 102,000. To accommodate this growth, the city annexed a large area surrounding the city core in 1899, and subsequently a number of subdivisions were established. The Galloway-Speedway Historic District includes portions of what were the Galloway Park and Speedway Terrace subdivisions in the newly annexed area. The neighborhood developed rapidly in the following decades as Memphis' population continued to climb reaching over 162,000 by 1920 and exceeding 253,000 by 1930.

The Galloway-Speedway Historic District is centered around North Parkway, the northern segment of the Memphis Parkway System, which was developed ca. 1909-1913 as a scenic thoroughfare. Inspired by the City Beautiful Movement, the Parkway was intended to be a linear park that connected large city parks. The four-lane North Parkway serves as the primary east-west corridor in the district and has a wide, landscaped median. This segment of North Parkway is a contributing element of the National Register-listed Memphis Parkway System (NR 07/03/89). Streets are arranged in a grid pattern and lots in the district are rectangular in form and typically measure between 125' to 150' deep and 50' to 70' in width. Interstate 240, constructed in the mid-1960s, serves as the district's eastern boundary. The northern and southern boundaries are drawn to exclude commercial development, and the western boundary is marked by the end of North Parkway's large median.

The neighborhood tended to develop north to south, although dwellings appeared on each of its five streets during the 1910s. The quickest to develop was Faxon Avenue, primarily due to its proximity to a streetcar line. The district's oldest remaining building was built at 842 North Parkway ca. 1902. This two-story, brick dwelling retains much of its original design including a two-story porch with square brick columns, and two entrances on the main façade.

Some of the earliest dwellings constructed in the district were built with Folk Victorian characteristics. The most common of these is the pyramid square house form. This design is characterized by a square, or nearly square, house plan with a hipped or pyramidal roof. These dwellings were often built with decorative porches on the main façade and with dormers at the roofline. The district contains several examples of the pyramid square design, many of which are located on Faxon Avenue. A representative example is the dwelling at 985 Faxon Avenue. Built ca. 1912, this

United States Department of the Interior
National Park Service

National Register of Historic Places Continuation Sheet

Section number 7 Page 2

Galloway-Speedway Historic District
Memphis, Shelby County, Tennessee

frame, one-and one-half story dwelling features a hipped roof with a hipped roof dormer on the main façade, a brick foundation, and an incised wraparound porch.

Another Folk Victorian house found in the district is the gabled ell form, which features a projecting gabled bay on the main façade, decorative porches, and one or more primary entrances. The district contains only a few moderate examples of this house form. The most representative example is the frame dwelling located at 950 Faxon Avenue. This dwelling was built ca. 1905 with a weatherboard exterior and a wraparound porch. Decorative detailing includes fishscale shingles in the gable field. The dwelling at 841 Faxon Avenue has influences of both the pyramid square and gabled ell designs. The house was built ca. 1910 with a hipped roof and a projecting gabled bay on the main façade. This bay has chamfered corners and contains the main entrance. The dwelling also has a partial-width porch with milled brackets.

Several dwellings built in the district during the 1910s and early 1920s are American Foursquare designs. This house form is a hipped roof, two-story dwelling with four primary rooms on each floor. This type of dwelling often features influences of the Colonial Revival style and typically features at least one dormer, a full-width or wraparound porch, and an accentuated main entrance. A representative example is the dwelling at 1077 North Parkway. Built ca. 1910, this two-story, brick dwelling has a hipped roof with a hipped dormer at the roofline of the main façade, a full-width porch with square brick columns and a closed brick railing, and paired one-over-one wood sash windows. The dwelling at 1032 Greenlaw Avenue was also built in the American Foursquare design ca. 1913. This frame example has a hipped roof porch with Doric columns on brick piers. A variant of the American Foursquare is the dwelling at 961 North Parkway was built with influences of the Colonial Revival style ca. 1925. This two-story dwelling has a red brick exterior and features decorative brick detailing in contrasting yellow brick. The house has a flat roof with a decorative brick patterned cornice, a one-story flat roof porch with square brick columns, and yellow brick quoins.

The Tudor Revival style, which was also popular during the early twentieth century, is very limited in the Galloway-Speedway Historic District. The dwelling at 945 Forrest Avenue was designed in the late 1920s with influences of the Tudor Revival style with stone detailing and an arched entrance with brick detailing and keystones. The dwelling at 1005 North Parkway was constructed ca. 1927 and reflects both American Foursquare and Tudor Revival influences. This two-story dwelling features a two-story projecting bay on the main façade, in the center of which is a large brick and stone chimney. The stonework on the chimney extends into an arch that connects to the dwelling's stone porch columns. The arch has a central stone keystone and voussoirs.

The overwhelming architectural style found in the neighborhood, however, is the Craftsman/Bungalow design. This style largely defines the district and gives it its overall character. The Craftsman/Bungalow style was one of the most popular residential architectural styles throughout the country in the early twentieth century at the time the Galloway-Speedway neighborhood was being established, and homeowners in the district quickly made it the preferred style of the subdivision. This style of dwelling was widely built throughout the district from ca. 1910 through the 1920s and into the 1930s. Common features of this style include a horizontal form with wide eaves, exposed roof rafters, and large porches with tapered columns and column piers or pedestals. Windows in these dwelling often have decorative upper sashes, frequently in various geometric designs. The historic district contains numerous examples of this style, including both gable and hipped roof examples, and both brick and frame construction, with varying degrees of elaboration. The dwelling at 1004 Forrest Avenue is a brick veneer Bungalow built ca. 1930. It has a jerkinhead roof with exposed roof rafters, knee brace brackets, and a shed roof dormer. The porch has a hipped roof with modillion blocks and square brick columns. The ca. 1922 Bungalow at 975 Galloway Avenue has a stucco exterior, battered brick porch piers, and an original multi-light glass and wood door with an eight-light transom and ten-light sidelights.

United States Department of the Interior
National Park Service

National Register of Historic Places Continuation Sheet

Section number 7 Page 3

Galloway-Speedway Historic District
Memphis, Shelby County, Tennessee

Many of the Craftsman style dwellings within the district were built in the "Airplane" Bungalow design. This sub-type is characterized by multiple gable roof planes, often with flared eaves, and a second story gabled monitor roof section with bands of multiple windows. These sections typically housed a sleeping room and were common in warm climate areas. Examples of this version of the Bungalow include the dwelling at 981 North Parkway, which was constructed ca. 1927. The dwelling has multiple gable rooflines with paired brackets, Craftsman style upper sash windows, and a multi-light glass and wood door with original sidelights and transom. One of the most representative examples of this design is the ca. 1922 dwelling at 1023 North Parkway. This dwelling has a brick exterior with large brackets and decorative wood detailing in the gable field and porch columns. Many of the Craftsman style dwellings within the district, including the previous two examples, feature porte-cocheres. These drive-thru bays are typically extensions of the main façade porch and extend over a driveway of poured concrete or concrete ribbons.

In addition to single-family dwellings, the district also contains a few apartment buildings that date to the early twentieth century. At 1099 North Parkway is a two-story, brick veneer apartment building constructed ca. 1925. The building has a gable roof with modillion blocks at the eaves, original three-over-one vertical light windows, and a two-story hipped roof, partial-width porch with square brick columns. The porch columns display decorative diamond concrete panels. At 1081 Greenlaw Avenue is a ca. 1917 two-story apartment building. This building has a flat roof, one-over-one sash windows, and a hipped roof, two-story partial-width porch with square brick columns with woodcut diamond panels.

The Galloway-Speedway Historic District also contains two churches and one fire station. Fire Station No. 15 was constructed at 1010 Faxon Avenue ca. 1920. The one-story, brick veneer building reflects the Bungalow design common to the neighborhood. Its jerkinhead roof has large knee brace brackets, and the main façade has two projecting hipped roof bays with tri-part one-over-one windows. Battered brick columns flank each bay, and entrances set within the bays are surrounded by structural glass block walls. The original central garage has been enclosed with concrete blocks and ca. 1990 paired steel doors; however, it retains a large arched transom and flanking pilasters with concrete caps. Concrete panels set within the exterior walls of the building list local city officials of the period. A panel also lists the firm of Regan and Weller, Architects, which designed the station, and J.E. Wright as the contractor.

The Parkway Seventh Day Adventist Church was constructed at 833 North Parkway ca. 1920. The church is a modest Classical Revival style building with a central full-height portico featuring Ionic capitals on the columns. The church retains some rectangular stained glass windows, which have concrete sills and lintels. A large two-story brick wing was added to the rear of the church building ca. 1930.

The Epworth United Methodist Church was constructed at 1120 Faxon Avenue 1914-1924. This large two-story church reflects influences of the Spanish Colonial Revival style. The building features a Spanish Mission style parapet that pierces the main roofline and large Palladian style stained glass windows. Two main entrances on the main façade are accentuated by large surrounds with concrete pilasters with Corinthian capitals and a large decorative concrete cornice.

Throughout the Galloway-Speedway neighborhood along North Parkway are four pumping stations. These stations were constructed ca. 1920 as the city provided public utilities to the area. These are small square brick structures having flat roofs with concrete coping, doors of chain link and either original, one-over-one double hung wood sash windows or open pattern brick infill in the window openings. The interior houses the square concrete well and the pump mechanism is positioned a few feet in front of the building.

United States Department of the Interior
National Park Service

National Register of Historic Places Continuation Sheet

Section number 7 Page 4

Galloway-Speedway Historic District
Memphis, Shelby County, Tennessee

Today, the Galloway-Speedway Historic District retains much of its early twentieth century appearance. Most properties continue to remain owner occupied and the majority retains their original form and plan. Demolition in the district had been minimal, and rehabilitation of dwellings in the district has increased in recent years. Dwellings in the district possess a strong degree of architectural integrity, and the district conveys a strong sense of time and place.

INDIVIDUAL PROPERTY DESCRIPTIONS

Properties in the inventory are organized by street and numerically by address. Entries list the address of the property, approximate date of construction, and associated secondary resources.

Key:

CB = Contributing Building

NCB = Non-contributing Building

CS = Contributing Structure

ca. = Circa

FAXON AVENUE

1. 841 Faxon Avenue ca. 1910 SY-5173 CB

This is a frame, one-story, pyramid square plan dwelling built ca. 1910. The dwelling has a brick foundation, an exterior of asbestos shingle siding, a hipped roof of asphalt shingles with a projecting front gable and two interior central stone chimneys. The partial –width shed roof porch has a milled frieze, milled brackets and ca. 1960 wrought iron columns and railing. The projecting gable bay on the main façade has chamfered corners and contains the main entrance. The main entrance has an original single-light glass and wood paneled door. Windows are original one-over-one double hung wood sash.

2. 844 Faxon Avenue ca. 1930 SY-5155 NCB

The property at 844 Faxon Avenue is a frame, gable front church built ca. 1930 and extensively altered with an added brick veneer exterior that has covered the main entrance. The church is now used as a dwelling and retains its original windows.

3. 848 Faxon Avenue ca. 1935 SY-5174 CB

At this location is a frame, one-story, front gable plan dwelling built ca. 1935. The dwelling has a continuous concrete foundation, an exterior of aluminum siding, a jerkinhead roof of asphalt shingles and metal flues. The full-width, hipped roof porch has wrought iron columns and a concrete floor. The main entrance has a ca. 1980 flush wood door. Windows are ca. 1950, two-over-two double hung horizontal sash.

4. 849 Faxon Avenue ca. 1920 SY-5175 CB

One- and one-half story, frame, Airplane Bungalow with a raised gabled monitor roof section built ca. 1920. The dwelling has an exterior of brick veneer, a hipped roof of asphalt shingles with a large projecting front gable one-story section and an exterior end chimney. The full-width, incised porch has square brick columns and a closed brick railing. The main entrance is not visible due to a metal security door but it still retains its original rectangular, single-light transom. Windows are original one-over-one double hung wood sash with concrete sills. In the gable field on the

United States Department of the Interior
National Park Service

National Register of Historic Places Continuation Sheet

Section number 7 Page 5

Galloway-Speedway Historic District
Memphis, Shelby County, Tennessee

main façade is a single-light fixed window and vinyl siding. The gabled monitor roof section has an exterior of vinyl siding.

5. 853 Faxon Avenue ca. 1970 SY-5176 NCB

At this location is a two-story, ten unit, brick veneer Apartment Building built ca. 1970. The building has a full-width, incised porch/walkway with metal posts and a metal railing.

6. 856 Faxon Avenue ca. 1925 SY-5177 CB

The property at 856 Faxon Avenue is a frame, one-story Bungalow built ca. 1925. The dwelling has a continuous concrete foundation, a side gable roof with two front gables each with diamond shaped wood attic vents, an exterior of brick veneer and one exterior end brick chimney. The partial-width, incised porch has brick columns and a closed brick railing with a concrete top rail. The main entrance has a ca. 1980, flush wood door. Windows are original, Craftsman style, one-over-one double hung wood sash with a Craftsman style picture window on the main façade. Paired, nine-over-one double hung wood sash attic windows and asbestos shingle siding are located in the side gable fields.

7. 859 Faxon Avenue ca. 1920 SY-5178 CB

One- and one-half story, frame, pyramid square plan dwelling built ca. 1920. The dwelling has an exterior of stucco, a hipped roof of asphalt shingles with exposed roof rafters and a large interior stone chimney. The full-width, incised porch has stone columns and a closed railing. Two entrances are located on the main façade. One entrance has is not visible but retains its original transom while the other has a ca. 1980, single-light glass and wood door. Windows are original twelve-over-one double hung wood sash.

(Garage, ca. 1970, NCB) Located to the rear of the dwelling is a non-contributing, ca. 1970, frame shed/garage. A hipped roof dormer with two, twelve-light fixed windows is located on the main façade.

8. 862 Faxon Avenue ca. 1913 SY-5179 CB

At this location is a frame, one- and one-half story Bungalow built ca. 1913. The dwelling has a an exterior of asbestos shingle siding, a jerkinhead roof of asphalt shingles with exposed roof rafters and two interior central brick chimneys with arched caps. The full-width, hipped roof porch has exposed roof rafters and Corinthian columns on paneled concrete piers. The main entrance has a ca. 1990, flush wood door with an original rectangular, single-light transom and original single-light glass and wood sidelights. Two, one-over-one double hung wood sash windows are located in the gable field of the main façade.

9. 863 Faxon Avenue ca. 1920 SY-5180 CB

This is a frame, one- and one-half story pyramid square plan dwelling with Bungalow influences built ca. 1920. The dwelling has a continuous stucco covered foundation, an exterior of stucco, a hipped roof of asphalt shingles and one interior central stone chimney. The full-width, incised porch has square stone columns and a closed stone and stucco railing with a concrete top rail. The main entrance has an original six-light and three wood panel door with an original single-light transom and metal security door. Windows are original one-over-one double hung wood sash with wood surrounds. A hipped roof dormer with two window openings and exposed roof rafters is located on the main façade. A ca. 1970 addition has been added to the rear façade with an exterior of aluminum siding.

United States Department of the Interior
National Park Service

National Register of Historic Places Continuation Sheet

Section number 7 Page 6

Galloway-Speedway Historic District
Memphis, Shelby County, Tennessee

10. 866 Faxon Avenue ca. 1923 SY-5181 CB

The property at this location is a frame, one- and one-half story, Folk Vernacular style, gabled ell plan dwelling with Tudor Revival style influences built ca. 1923. The dwelling has a continuous concrete block foundation, an exterior of aluminum siding, a gable and hipped roof of asphalt shingles with a steep gable on the main façade, two interior central brick chimneys, one exterior end brick flues and one exterior end brick chimney. The partial-width, shed roof porch is supported by wrought iron posts. The main entrance has a ca. 1970, single-light glass and wood door with a metal security door. A secondary entrance on the west façade has a solid wood door with a metal security door. Windows are original one-over-one double hung wood sash with metal awnings. On the rear façade is a shed roof addition with an exterior of aluminum siding and a metal awning. A wood wheelchair ramp has been attached to the west entrance.

(Shed, ca. 1980, NCB) Located to the rear of the dwelling is a non-contributing, ca. 1980, metal shed.

11. 870 Faxon Avenue ca. 1996 SY-5182 NCB

The original house at this address has been razed and replaced with a ca. 1996, one-story, manufactured home. The dwelling has a front gable roof, an exterior of aluminum siding, four-over-four double hung vinyl sash windows and a gable roof entry porch with wrought iron posts.

12. 873 Faxon Avenue ca. 1920 SY-5183 CB

This is a frame, one- and one-half story Bungalow built ca. 1920. The dwelling has a continuous stucco covered foundation, a jerkinhead roof of asphalt shingles, an exterior of brick veneer and an interior end brick chimney with a corbelled brick cap. The full-width, hipped roof porch has square brick columns and a closed brick railing with a concrete top rail and half moon brick drains. The main entrance has a original, wide-width ten-light and three wood panel door with an original ten-light transom and original four-light and single wood panel sidelights. Windows are one-over-one double hung wood sash with concrete sills. A soldier brick beltcourse and a wood cornice surround the dwelling. Aluminum siding and two, single-light fixed windows flanked by a single-light metal sliding glass windows are located in the gable field on the main façade.

13. 876 Faxon Avenue ca. 1923 SY-5184 CB

At 876 Faxon Avenue stands a frame, one- and one-half story pyramid square plan dwelling with Bungalow influences built ca. 1923. The dwelling has a hipped roof of asphalt shingles, an exterior of weatherboard siding and brick veneer and an exterior end brick chimney with a corbelled and brick patterned cap. The full-width, incised porch has double, square wood columns and a concrete floor. The main entrance has a ca. 1950, two panel wood door with an original single-light transom and original, opaque single-light and single wood panel sidelights. Windows are original one-over-one double hung wood sash with wood sills and surrounds. Diamond wood security bars have been placed on the main façade windows with one of the paired sets of windows on the main façade slightly protruding giving the house a slightly Bavarian sense. A sailor brick water table surrounds the dwelling. Located on the main façade is a hipped roof dormer with two, single-light fixed windows. A protruding gable roof window box with gable returns and a double set of windows is located on a side façade. A brick pier and round double wood railing fence separates the front lawn from the sidewalk.

United States Department of the Interior
National Park Service

National Register of Historic Places Continuation Sheet

Section number 7 Page 7

Galloway-Speedway Historic District
Memphis, Shelby County, Tennessee

14. 879 Faxon Avenue ca. 1920 SY-5185 CB

This is a frame, one- and one- half story Bungalow built ca. 1920. The dwelling has a unique pressed board with a raised brick pattern siding painted yellow which gives the appearance of brick veneer, a continuous concrete block foundation, a jerkinhead roof of asphalt shingles and one interior central concrete chimney. The full-width, hipped roof porch has battered stone columns and a closed stone railing with a stone top rail. The main entrance has a fifteen-light glass and wood door with an original three-section, single-light transom, original ten-light and wood panel sidelights and a metal security door. Windows are original Craftsman style, one-over-one double hung wood sash. A wood water table surrounds the dwelling. A protruding, jerkinhead roof bay with triple set of Craftsman style windows and knee brace brackets is located on east façade. Two, large single-light fixed windows and the pressed board brick pattern siding has been installed in the gable field on the main façade.

15. 880 Faxon Avenue ca. 1917 SY-5186 CB

At this location is a frame, one-story, pyramid square plan dwelling built ca. 1917. The dwelling has a continuous brick foundation, an exterior of aluminum siding (installed vertically on the main façade and horizontally on the remaining facades), a hipped roof of asphalt shingles and one interior central stucco covered chimney. A second opening for a chimney is still on the roofline but the chimney has been removed. The full-width, incised porch has wrought iron posts, brackets and railings and a concrete floor. The main entrance has a ca. 1970, six wood panel door with an original transom, currently boarded, original two-light and single wood panel sidelights and a storm door. Windows are original one-over-one double hung wood sash. A gable roof dormer with a pediment and the window openings that have been boarded is located on the main façade. Portions of an original two-track concrete block driveway extend down the side of the dwelling to the backyard.

16. 883 Faxon Avenue ca. 1910 SY-5187 CB

One- and one-half story Bungalow built ca. 1910. The dwelling has an exterior of thin strip weatherboard siding, some vertical board siding on the main façade a continuous stucco covered foundation, a hipped roof of asphalt shingles and two interior central stucco covered chimneys. The wraparound incised porch has exposed roof rafters, tapered wood columns on concrete piers and a closed stuccoed railing. The main entrance has an original nine-light glass and wood panel door with a metal security door. A secondary entrance has an original single-light glass and wood door. Windows are replacement one-over-one double hung metal sash with all the openings having been downsized and filled in. A wood water table surrounds the dwelling. An ca. 1940 addition was added to the rear façade with wide strip weatherboard siding and original windows. Two shed roof dormers are located on the roofline. One is located on the east façade and has three windows-a twelve-light fixed window flanked by six-light fixed windows. The dormer located on the north façade has two, original, nine-light fixed windows, an exterior of weatherboard siding and exposed roof rafters. On the east façade is a protruding, gable roof bay with a double set of windows and one, original, fixed nine-light window in the gable field.

17. 889 Faxon Avenue ca. 1910 SY-5188 CB

This is a frame, one- and one-half story Bungalow built ca. 1910 The dwelling has a continuous ashlar-faced concrete block foundation, an exterior of stucco with wood cornering, a jerkinhead roof of asphalt shingles with exposed roof rafters, one exterior end brick chimney and two interior stucco covered chimneys. The full-width, hipped roof porch has exposed milled roof rafters, Corinthian columns, a closed concrete block railing with a concrete top rail. The porch extends off the east façade with a patio extension that extends to a protruding jerkinhead roof bay with a side entrance and double set of windows. The main entrance has an original single-light glass and wood door with a single-light transom (boarded) and original single-light and single wood panel sidelights. The secondary entrance on the east

United States Department of the Interior
National Park ServiceNational Register of Historic Places
Continuation SheetSection number 7 Page 8Galloway-Speedway Historic District
Memphis, Shelby County, Tennessee

façade in the bay has a ca. 1980, six wood panel door with an original single-light transom that has been screened. Windows are original one-over-one double hung wood sash with wood surrounds. A wood water table surrounds the dwelling. Two, one-over-one double hung wood sash windows, knee brace brackets and stucco are located in the gable fields.

(Carport, ca. 1970) NCB Located to the rear of the dwelling is a non-contributing, ca. 1970, open bay carport with a gable roof.

18. 890 Faxon Avenue ca. 1925 SY-5189 CB

At 890 Faxon Avenue stands a frame, one- and one-half story pyramid square plan dwelling built ca. 1925. The dwelling has an exterior of stucco, a hipped roof of asphalt shingles and exposed roof rafters and a metal flue. The full-width, incised porch has tapered wood columns on brick piers and an open brick railing. The main entrance is not visible but it does retain its original seven-light transom and original, six-light and single wood panel sidelights. Windows are replacement, six-over-six double hung vinyl sash with a sixteen-light fixed picture window on the main façade with vinyl fake muntin bars.

(Garage, ca. 1930, CB) Located to the rear of the dwelling is a ca. 1930, frame, garage with an asphalt shingled hipped roof, an exterior of stucco and paired wood hinged doors.

19. 895 Faxon Avenue ca. 1930 SY-5190 CB

Located at 895 Faxon Avenue is a frame, one- and one-half story Airplane Bungalow with an original, raised monitor roof section built ca. 1930. The dwelling has a front gable roof of asphalt shingles with an offset small projecting gable and exposed roof rafters, an exterior of brick veneer and one interior central brick chimney. The full-width, hipped roof porch has exposed roof rafters, square brick columns and an enclosed brick railing. The main entrance has a ca. 1980, flush wood door. The main façade has a large vertical board panel enclosing what could possibly have been the original main entrance doorway. Windows are one-over-one double hung wood sash with concrete sills. The original, raised hipped monitor roof section has an exterior of vertical board siding.

20. 896 Faxon Avenue ca. 1925 SY-5191 CB

This is a frame, one- and one-half Bungalow built ca. 1925. The dwelling has a continuous concrete block foundation, an exterior of stucco, a jerkinhead roof of asphalt shingles with exposed roof rafters and an interior concrete covered brick chimney. The full-width, incised porch has square brick columns and a concrete floor. The main entrance has a replacement three-light glass and three wood paneled door with an original three-section, single-light transom and original six-light sidelights. Windows are original one-over-one double hung wood sash. Knee brace brackets and rectangular, paired, four-light fixed windows are located in the main facades gable field.

21. 898 Faxon Avenue ca. 1925 SY-5192 CB

At this location is a frame, one- and one-half story Bungalow built ca. 1925. The dwelling has an exterior of brick veneer, a front gable roof of asphalt shingles and an interior end brick chimney. The full-width, hipped roof porch is supported by brick columns. The main entrance is not visible but it does retain its original four-light transom. Windows are original one-over-one double hung wood sash windows with the side facades have metal shed roof awnings. Two, single-light attic windows are located in the gable field on the main façade.

United States Department of the Interior
National Park Service

National Register of Historic Places Continuation Sheet

Section number 7 Page 9

Galloway-Speedway Historic District
Memphis, Shelby County, Tennessee

(Garage, ca. 1940, CB) A ca. 1940, frame garage with an asphalt shingled gable roof and vertical board hinged doors is located to the rear of the dwelling.

22. 899 Faxon Avenue ca. 1920 SY-5193 CB

This is a one-story, frame front gable plan Bungalow built ca. 1920. The dwelling has an asphalt shingled gable roof with exposed roof rafters, an interior brick chimney and an exterior of weatherboard except for the main façade that has wide width horizontal wood panels. The full-width, shed roof porch with a gable has replaced brick columns, a concrete floor and an open concrete railing. The main entrance has a ca. 1990, fanlight and aluminum door. The original sidelights and transom have covered over with exterior paneling. Windows are original one-over-one double hung wood sash. Two, single-light attic windows are located in the gable field on the main façade.

23. 900 Faxon Avenue ca. 1925 SY-5194 CB

Standing at 900 Faxon Avenue is a frame, one-story Bungalow built ca. 1925. The dwelling has a continuous concrete foundation, a jerkinhead roof with asphalt shingles and exposed roof rafters, an exterior of brick veneer and one interior end chimney with a corbelled cap. The full-width, gable and hipped roof porch has exposed roof rafters, square brick columns with patterned brick detailing, a closed brick railing with a concrete top rail and stucco in the gable field. The main entrance is not visible but it does have a metal security door. Windows are original one-over-one double hung wood sash with concrete sills and some have metal awnings. A sailor brick beltcourse and a soldier course water table surround the dwelling. Modillion brackets, stucco and two are located in the gable field on the main facades roofline. One of the two window openings contains an attic vent while the other contains a single-light glass and wood window.

(Shed, ca. 1970, NCB) Located to the rear of the dwelling is a non-contributing, ca. 1970, metal shed.

24. 904 Faxon Avenue ca. 1925 SY-5196 CB

This is a frame, one- and one-half story Bungalow built ca. 1925. The dwelling has an exterior of brick veneer, a continuous concrete foundation, a front gable roof of asphalt shingles with exposed roof rafters and one interior end brick chimney. The full-width, hipped roof porch has a wood cornice, exposed roof rafters, stone piers, a closed stone railing with swags and a concrete floor. The main entrance has a ca. 1970, solid wood door with an original single-light transom and metal security door. Windows are original one-over-one double hung wood sash with concrete sills. A wood cornice and header course beltcourse surrounds the dwelling. Located in the gable field on the main façade are exposed roof rafters and two, single-light fixed windows and rolled asphalt shingle siding.

25. 912 Faxon Avenue ca. 1925 SY-5197 CB

This is a frame, one- and one-half story Bungalow built ca. 1925. The dwelling has a continuous brick foundation, an exterior of weatherboard siding, a multi-gable and hipped roof of asphalt shingles and three interior central brick chimneys. The full-width, hipped roof porch has weatherboard sided square column and a closed weatherboard railing with a wood top rail. The door to the main entrance is not visible but it does retain its original, three-section transom with a sunburst design, original single-light and wood panel sidelights also with a sunburst pattern and a metal security door. Windows are original nine-over-one double hung wood sash. A wood water table surrounds the dwelling. On the east and west facades are protruding, gable roof bays with two windows. In the gable field on the main façade is stick work, stucco, milled roof rafter brackets and two, vertical light rectangular fixed windows with one of the openings having been boarded.

United States Department of the Interior
National Park ServiceNational Register of Historic Places
Continuation SheetSection number 7 Page 10Galloway-Speedway Historic District
Memphis, Shelby County, Tennessee

(Garage, ca. 1950, NCB) Located to the rear of the dwelling is a non-contributing, ca. 1950, gable roof garage with corrugated metal siding.

26. 920 Faxon Avenue ca. 1915 SY-5199 CB

At 920 Faxon Avenue is a frame, one- and one-half story Bungalow built ca. 1915. The dwelling has a continuous stucco covered foundation, an exterior of stucco, a jerkinhead roof of asphalt shingles and exposed roof rafters and an interior central and an interior end stucco covered chimney. The full-width, hipped roof porch has milled exposed roof rafters, a wood cornice, Corinthian columns on paneled concrete piers, a concrete floor and a metal awning on the west façade. The main entrance has an original single-light glass and wood door with an original, large single-light transom, original single-light and single wood panel sidelights and a metal security door. Windows are original Craftsman style windows. A wood water table surrounds the dwelling. On the west and east facades are protruding bays with a double set of windows. Added to the rear of the dwelling is a ca. 1970 addition with aluminum siding. In the gable field on the main façade are knee brace brackets, stucco and a Craftsman style, one-over-one double hung wood sash window.

(Shed, ca. 1915, CB) Located to the rear of the dwelling is a ca. 1915, frame shed with an exterior of board and batten siding, a gable roof and board and batten hinged double doors.

27. 921 Faxon Avenue ca. 1920 SY-5200 CB

This is a frame, one- and one-half story Bungalow built ca. 1920. The dwelling has a continuous concrete foundation, an exterior of brick veneer, a jerkinhead roof of asphalt shingles and one exterior end concrete and brick chimney. The full-width, hipped roof porch has square brick columns, an open wood railing with added two by fours and a concrete floor. The main entrance has a ca. 1980, six panel wood door with a metal security door. Windows are original nine-over-one double hung wood sash with metal security bars. A wood cornice and a concrete water table surround the dwelling. A protruding jerkinhead roof bay with a triple set of windows is located on a side façade. In the gable field on the main façade are knee brace brackets, stucco and two nine-light fixed windows.

28. 925 Faxon Avenue ca. 1920 SY-5201 CB

This is a frame, one- and one-half story Bungalow built ca. 1920. The dwelling has a continuous concrete foundation, an exterior of wired brick veneer, a jerkinhead roof of asphalt shingles with milled brackets and an interior end brick chimney with a corbelled cap. The full-width, hipped roof porch has square brick columns with concrete plinths, a closed brick railing with a concrete top rail and milled brackets. The door to the main entrance is unknown but it does retain its original eight-light transom and original single-light and wood panel sidelights. Windows are original one-over-one double hung wood sash. A soldier course brick beltcourse and a wood cornice surround the dwelling. Located in the gable field on the main façade are three window openings boarded over and milled brackets.

29. 926 Faxon Avenue ca. 1920 SY-5202 CB

Located at 926 Faxon Avenue is a frame, one- and one-half story Bungalow built ca. 1920. The dwelling has a continuous stucco covered foundation, an exterior of stucco, a jerkinhead roof of asphalt shingles and an interior central brick and stucco chimney with metal caps. The full-width, hipped roof porch has double and triple square wood columns with wood plinths on stuccoed piers and a deteriorated square wood baluster railing. The main entrance has a ca. 1970, diamond light and solid wood door with a metal security door. Windows are original one-over-one double hung wood sash with metal security bars. A thin, wood water table surrounds the dwelling. On the east façade is a

United States Department of the Interior
National Park ServiceNational Register of Historic Places
Continuation SheetSection number 7 Page 11Galloway-Speedway Historic District
Memphis, Shelby County, Tennessee

protruding jerkinhead roof bay with a double set of windows. On the west façade is another protruding jerkinhead roof bay with only two windows.

30. 930 Faxon Avenue ca. 1925 SY-5203 CB

This is a frame, one- and one-half story Bungalow built ca. 1925. The dwelling has a continuous stucco covered foundation, an exterior of stucco, a jerkinhead bay of asphalt shingles and two exterior end brick chimneys. The full-width, gable and hipped roof porch has a wood cornice, battered brick columns with concrete plinths, a brick floor and stucco in the gable field. The main entrance has a ca. 1970, solid wood door. Windows are original one-over-one double hung wood sash with wood surrounds and metal security bars. Detailing includes a wood cornering and a wood water table that surrounds the dwelling. A ca. 1970, addition has been added to the rear façade with weatherboard siding. In the gable field on the main façade is stucco and two square attic vents.

(Garage, ca. 1940, CB) Located to the rear of the dwelling is a ca. 1940, frame, one-bay garage with weatherboard siding, a gable roof and no doors.

31. 931 Faxon Avenue ca. 1920 SY-5204 CB

This is a frame, one- and one-half story Bungalow built ca. 1920. The dwelling has a continuous concrete block foundation, an exterior of weatherboard siding and stucco, a jerkinhead roof of asphalt shingles with exposed roof rafters and one interior brick chimney with a concrete cap. The full-width, hipped roof porch has exposed roof rafters, battered stone columns, an open wood railing and one stone pier with a stone plinth. Two entrances are located on the main façade. The main entrance has a Craftsman style, single-light glass and wood door with an original three-section (three light-four-light-three-light) transom, original Craftsman style single-light and wood panel sidelights and a storm door. The secondary entrance is half boarded and not it use but does have a ca. 1970, diamond light and wood door with an original single-light transom with the glass missing and an original screen door. Windows are original one-over-one double hung wood sash. A wood water table surrounds the dwelling. On the west façade is a protruding bay with a triple set of windows. In the gable field on the main façade are weatherboard siding, exposed roof rafters and one screened opening.

(Garage, ca. 1970, NCB) Located to the rear of the dwelling is a non-contributing, ca. 1970, concrete block and plywood garage with a gable roof.

32. 934 Faxon Avenue ca. 1920 SY-5205 CB

Located at 934 Faxon Avenue is a frame, one-story pyramid square plan dwelling built ca. 1920. The dwelling has an exterior of stucco, a hipped roof of asphalt shingles, an interior concrete chimney and an interior brick chimney. The full-width, incised porch has exposed roof rafters and Tuscan columns on rusticated concrete block piers. The main entrance has a multi-glass and wood door with an original seven-light transom and original six-light sidelights. Windows are original one-over-one double hung wood sash and ca. 1960, two-over-two horizontal-light wood sash. A hipped roof dormer with two openings and exposed roof rafters is located on the roofline of the main façade.

33. 937 Faxon Avenue ca. 1918 SY-5206 CB

This is a frame, one- and one-half story Bungalow built ca. 1918. The dwelling has a continuous concrete foundation, an exterior of asbestos shingle siding, a jerkinhead roof of asphalt shingles with exposed roof rafters and interior metal flues. The full-width, hipped roof porch has square brick columns, a closed brick railing and a concrete floor. The main entrance door is not visible but it does retain its original rectangular transom covered with a wood panel.

United States Department of the Interior
National Park ServiceNational Register of Historic Places
Continuation SheetSection number 7 Page 12Galloway-Speedway Historic District
Memphis, Shelby County, Tennessee

Windows are original Craftsman style one-over-one double hung wood sash. A small jerkinhead roof projecting window bay is located on the west façade. In the gable field on the main façade are knee brace brackets, exposed roof rafters and two window openings—one is covered and the other has a twelve-light fixed attic window.

34. 940 Faxon Avenue ca. 1925 SY-5207 CB

At 940 Faxon Avenue stands a frame, two-story American Foursquare style dwelling built ca. 1925. The dwelling has an exterior of brick veneer, a hipped roof of asphalt shingles and two interior brick chimneys. The full-width, hipped roof porch has exposed roof rafters, square brick columns and an open brick railing. Two entrances are located on the main façade. One entrance has a ca. 1990, fanlight and aluminum door while the other has a ca. 1990, nine-light glass and metal door. Windows are original nine-over-one and six-over-one double hung wood sash with some ca. 1980 one-over-one double hung vinyl sash replacements. All windows have concrete sills on the first floor. On the rear façade of the dwelling is an original, large one-story wing with a gable roof. Located on the second floor is an incised bay and a central projecting bay. In the gable field on the main façade is a hipped roof dormer with two, four-light windows and exposed roof rafters.

35. 941 Faxon Avenue ca. 1920 SY-5208 CB

This is a frame, one- and one-half story pyramid square plan dwelling built with Bungalow influences ca. 1920. The dwelling has a continuous concrete foundation, an exterior of stucco, a hipped roof of asphalt shingles and an interior concrete chimney. The full-width, incised porch has stuccoed square columns and a closed stuccoed railing. The main entrance has a ca. 1980, flush wood door with an original three-light transom, original single-light and wood panel sidelights and a storm door. Windows are original nine-over-one double hung wood sash. On the roofline of the main façade is a hipped roof dormer with three, single-light fixed windows.

36. 945 Faxon Avenue ca. 1918 SY-5209 CB

This is a frame, one- and one-half story Bungalow built ca. 1918. The dwelling has a continuous concrete foundation, an exterior of brick veneer, a jerkinhead roof of asphalt shingles with exposed roof rafters, one interior brick and interior end brick chimneys. The full-width, hipped roof porch extends out to a porte-cochere with exposed roof rafters, battered brick columns and an open brick railing. The main entrance has an original sixteen-light glass and wood door with a storm door. Windows are original four-over-one vertical light double hung wood sash with concrete sills. Located in the gable field on the main facade are three, single-light fixed attic windows.

37. 946 Faxon Avenue ca. 2002 SY-5210 NCB

The original dwelling at this location has been removed and in its place is a ca. 2002, one-story Bungalow with an exterior of brick veneer and a hipped roof with a projecting gable roof porch

38. 950 Faxon Avenue ca. 1905 SY-5211 CB

One-and one-half story, gabled ell plan, Queen Anne style dwelling built ca. 1905. The dwelling has a brick pier foundation with concrete infill, an exterior of weatherboard siding and an asphalt shingled gable roof. The wraparound, shed roof porch has tapered wood posts and a brick foundation. The main entrance has an original single-light glass and wood panel door with an original rectangular single-light transom and a storm door. Windows are original one-over-one double hung wood sash. On the east façade is a small projecting gable wing. An original shed roof wing is located on the rear façade. In the gable field on the main façade are fishscale shingles and an attic vent.

United States Department of the Interior
National Park ServiceNational Register of Historic Places
Continuation SheetSection number 7 Page 13Galloway-Speedway Historic District
Memphis, Shelby County, Tennessee**39. 951 Faxon Avenue ca. 1989 SY-5212 NCB**

This is a frame, one-story rectangular plan dwelling built ca. 1989. The dwelling has an exterior of brick veneer with corner corbelling, a gable roof with milled porch posts, a front gable roof of asphalt shingles, one-over-one double hung metal sash windows and a ca. 1990, six wood panel door.

40. 957 Faxon Avenue ca. 1918 SY-5214 CB

The property at 957 Faxon Avenue is a frame, one- and one-half story Bungalow built ca. 1918. The dwelling has a continuous concrete foundation, an exterior of stucco, a side gable roof of asphalt shingles and one interior end brick chimney covered with concrete. The partial-width, gable roof porch extends out to an uncovered patio section and has knee brace brackets, square brick columns and a closed brick railing. The main entrance has an original six-light glass and wood door with an original three-light transom and a metal security door. Windows are original Craftsman style one-over-one double hung wood sash. In the gable fields are two, attic windows covered with wood panels. An original large, gable roof wing with an exterior of weatherboard siding and exposed roof rafters is located on the rear façade.

41. 960 Faxon Avenue ca. 2001 SY-5215 NCB

The original dwelling at this location has been razed and replaced with a ca. 2001, one-story brick veneer dwelling.

42. 964 Faxon Avenue ca. 1920 SY-5216 CB

This is a frame, one- and one-half story Bungalow built ca. 1920 and slightly renovated. The dwelling has a continuous concrete foundation, an exterior of stucco, one exterior end concrete covered chimney and a side gable roof of asphalt shingles. The full-width, incised porch has replacement square wood posts. The main entrance has a ca. 2000, metal panel door with an original rectangular, single-light transom with a storm door. Windows are replacement one-over-one double hung with most of them being covered with wood panels. On the roofline of the main façade is a shed roof dormer with two, single-light fixed windows. The dwelling is currently vacant.

43. 965 Faxon Avenue ca. 1920 SY-5217 CB

This is a frame, one- and one-half story Bungalow built ca. 1920. The dwelling has a continuous concrete foundation, an exterior of brick veneer, a side gable roof of asphalt shingles and one interior end brick chimney. The shed roof porch has square wood columns, a closed brick railing and has been partially enclosed with screen panels. Two entrances are located on the main façade. The main entrance has a single-light glass and wood door with an original eight-light transom and original single-light sidelights. The secondary entrance on the main façade has a fifteen-light glass and wood door with an original rectangular single-light transom. Windows are mostly original one-over-one double hung wood sash with some one-over-one vinyl sash replacements. Concrete sills are located under the windows. On the side elevations are projecting gable roof windows bays. An original frame, shed roof wing has been built off the rear façade. On the roofline of the main façade is a shed roof dormer with knee brace brackets and original attic windows currently covered with vinyl siding.

44. 970 Faxon Avenue ca. 1920 SY-5218 CB

At 970 Faxon Avenue stands a frame, one-story Colonial Revival influenced Bungalow built ca. 1920. The dwelling has an exterior of pressed wood with a faux raised brick pattern, a hipped roof of asphalt shingles with exposed roof rafters, one interior central and one interior brick chimneys. The rebuilt, gable roof entry porch is supported by square wood columns and the sides of the porch have been enclosed with vertical wood panels with arched openings. The main entrance door is not visible but the entrance does retain its original four-light fanlight transom, original five-light

United States Department of the Interior
National Park ServiceNational Register of Historic Places
Continuation SheetSection number 7 Page 14Galloway-Speedway Historic District
Memphis, Shelby County, Tennessee

sidelights (four-lights fixed over a single fixed light) and a storm door. Windows are original one-over-one double hung wood sash with triple sets flanking the entrance. A wood beltcourse surrounds the dwelling beneath the windows.

45. 971 Faxon Avenue ca. 1923 SY-5219 CB

This is a frame, one-story, front gable plan Bungalow built ca. 1923. The dwelling has a jerkinhead roof of asphalt shingles, a continuous concrete block foundation, an exterior of brick veneer and an interior end brick chimney. The full-width, hipped roof porch has square brick columns and a closed brick railing. The main entrance has an original multi-light glass and wood door with an original eight-light transom, original multi-light sidelights and a metal security door. Windows are ca. 1990, nine-over-nine double hung vinyl sash windows with fake muntin bars and metal security bars. In the gable field are knee brace brackets and three, single-light attic windows.

46. 974 Faxon Avenue ca. 1920 SY-5220 CB

Located at 974 Faxon Avenue is a frame, one-and one-half story Bungalow built ca. 1920. The dwelling has an exterior of permastone, a side gable roof of asphalt shingles and one exterior end permastone chimney. The full-width, incised porch has exposed roof rafters, wrought iron posts and a concrete floor. The main entrance has a ca. 1990, fanlight and aluminum panel door with a storm door. Windows are original one-over-one double hung wood sash with shed roof metal awning on some of the side facades. Located in the gable fields are knee brace brackets.

47. 975 Faxon Avenue ca. 1920 SY-5221 CB

This is a frame, one- and one-half story Airplane Bungalow built ca. 1920 is currently in a state of disrepair. The dwelling has a continuous concrete foundation, an exterior of aluminum siding, a side gable roof of asphalt shingles and two interior brick chimneys. The full-width, shed roof porch extends out to a carport and has exposed roof rafters, Tuscan columns, one replacement square wood column and has been partially enclosed with screen panels on the west façade. The main entrance has an original, wide width, six panel wood door with a metal security door. A secondary entrance to the patio area has original multi-light French double doors with screen doors. Windows are original nine-over-one double hung wood sash with metal security bars. The windows on the main façade have been replaced with one sliding metal track window. An upper wood beltcourse surrounds the dwelling.

48. 980 Faxon Avenue ca. 1925 SY-5222 CB

At 980 Faxon Avenue is a frame, one-story Colonial Revival influenced dwelling built ca. 1925. The dwelling has a continuous concrete block foundation, an exterior of pressed wood with a raised faux brick pattern siding, a hipped roof of asphalt shingles and two interior brick chimneys. The gable roof entry porch has square wood columns, a wide wood cornice, a full pediment and knee brace brackets, stucco and one, single-light fixed window in the gable field. The main entrance has an original five-light glass and wood door with a metal security door and original five-light and wood panel sidelights with metal security bars. Windows are original one-over-one double hung wood sash with two, triple sets of windows flanking the entrance. Two wood water tables surround the dwelling. An original wing with original pressed wood with raised faux brick pattern siding is located on the rear façade.

(Shed, Ca. 1935, CB) To the rear of the dwelling is a ca. 1935, frame shed with a gable roof.

United States Department of the Interior
National Park Service

National Register of Historic Places Continuation Sheet

Section number 7 Page 15

Galloway-Speedway Historic District
Memphis, Shelby County, Tennessee

49. 981 Faxon Avenue ca. 1920 SY-5223 CB

One and one-half story Bungalow built ca. 1920. The dwelling has a continuous concrete foundation, an exterior of brick veneer, a jerkinhead roof of asphalt shingles with exposed roof rafters, metal flues and an interior end brick chimney. The full-width, hipped roof porch has a wood cornice, battered stone columns, a closed brick railing with a concrete top rail and half-moon brick drains and two, replacement wrought iron posts. The main entrance has an original wide width, fifteen-light glass and wood door with an original ten-light transom, original five-light glass and wood sidelights and a metal security door. Windows are original, Craftsman-style, one-over-one double hung wood ash windows with concrete sills. A soldier course water table and beltcourse surround the dwelling. In the gable field on the main façade are three, Craftsman style fixed windows and stucco. A window or door opening on the main façade has been enclosed.

50. 984 Faxon Avenue ca. 1920 SY-5224 CB

This is a frame, one- and one-half story Bungalow built ca. 1920 and remodeled with Colonial Revival influences. The dwelling has an exterior of brick veneer and permastone, a continuous brick foundation, a side gable roof of asphalt shingles and an interior brick chimney. The gable roof entry porch extends into a patio on the east façade. The porch has wrought iron columns on brick piers. The patio has brick piers with tile plinths. Both the porch and patio have tile floors. The main entrance has a replacement four wood panel door with a metal security door and a permastone lintel with a keystone. Windows are replacement two-over-two horizontal light double hung wood sash and a triple set of four-over-four double hung metal sash windows flanking six-over-six double hung metal sash windows on the main façade along with two, six-over-six double hung metal sash windows flanking the entrance. Enclosed knee brace brackets are located in the gable fields and stick work has been placed in the gable field of the porch.

51. 985 Faxon Avenue ca. 1912 SY-5225 CB

The property at this location is a frame, one-story pyramid square plan dwelling built ca. 1912. The dwelling has a continuous brick foundation, an exterior of vinyl siding, a hipped roof of asphalt shingles with exposed roof rafters and two interior brick chimneys both with clay caps. The wraparound, incised porch has exposed roof rafters and square wood columns on concrete piers. The door to the main entrance is not visible but it does retain its original five-light transom and original single-light sidelights with metal security bars and a metal security door. A secondary entrance on the main façade has an original eight-light glass and wood panel door with original six-light glass and wood sidelights. Windows are original one-over-one double hung wood sash with metal security bars. On the main façade is a hipped roof dormer with exposed roof rafters and two, square louvered wood attic vents.

52. 990 Faxon Avenue ca. 1920 SY-5226 CB

This is a frame, one- and one-half story front gable Bungalow built ca. 1920. The dwelling has a continuous concrete block foundation, an exterior of stucco, a jerkinhead roof of asphalt shingles with exposed roof rafters and one interior and one exterior stucco covered chimneys. The full-width, hipped roof porch has square brick columns and railing. Two entrances are located on the main façade. The main entrance has a ca. 1990, flush wood door with its original rectangular single-light transom while the other entrance has been covered with a plywood panel. Windows are one-over-one double hung wood sash with some having metal security bars. In the gable field on the main façade are knee brace brackets and an attic window covered with a wood panel. On the west façade is a projecting jerkinhead roof window bay.

(Garage, ca. 1920, CB) Located to the rear of the dwelling is an original garage with an exterior of shiplap siding and an asphalt shingle roof.

United States Department of the Interior
National Park Service

National Register of Historic Places Continuation Sheet

Section number 7 Page 16

Galloway-Speedway Historic District
Memphis, Shelby County, Tennessee

53. 991 Faxon Avenue ca. 1913 SY-5227 CB

One- and one-half story, frame, central passage plan, front gable dwelling built ca. 1913 and is currently vacant. The dwelling has a brick foundation, an exterior of weatherboard siding, an asphalt shingled gable roof and three interior central brick chimneys with clay caps. The full-width, hipped roof porch is supported by square wood posts. The door and window openings have been covered with plywood panels. A square attic window is located in the gable field on the main façade. Projecting gable bays on both the east and west facades. On the west façade is a small, shed roof side porch.

54. 994 Faxon Avenue ca. 1920 SY-5228 CB

This is a frame, one- and one-half story Bungalow built ca. 1920. The dwelling has an exterior of stucco, a combination gable and hipped roof of asphalt shingles and one interior brick chimney. The full-width, incised porch is supported by brick columns. The main entrance has an original eight-light and four wood panel door with an original three-section (two-light-three-light-two-light) transom and original three-light and single wood panel sidelights. Windows are original, Craftsman style, one-over-one double hung wood sash. A wood beltcourse surrounds the dwelling. Located in the gable field on the main façade are three attic windows, one five-vertical light fixed window flanked by four-vertical light fixed sash.

55. 995 Faxon Avenue ca. 1918 SY-5229 CB

At 955 Faxon stands a frame, one-story, Bungalow built ca. 1918. The dwelling has a continuous brick foundation, an exterior of vinyl siding, a gable roof of asphalt shingles with exposed roof rafters and an interior central brick chimney. The side gable roof porch extends out into a porte-cochere with exposed roof rafters, short square wood posts on large brick piers. The main entrance has a ca. 1990, single-light glass and wood door with a metal security door. The windows have mostly been replaced and most of those on the main façade have been covered over, however, some original one-over-one double hung wood sash remain. Knee brace brackets are located in the gable fields.

56. 999-1001 Faxon Avenue ca. 1941 SY-5230 CB

One- and one-half story, frame, Minimal Traditional style duplex built ca. 1941. The dwelling has a continuous concrete foundation, an exterior of brick veneer and a side gable roof of asphalt shingles. The two gable roof entry canopies over the two main entrances are supported with heavy knee brace brackets and have a full-width concrete floor. The two main entrances on the main façade both have original Craftsman-style, six-light and wood panel door with metal security doors. The two side entrances to the duplex have a ca. 1970, diamond light glass and wood door and the other has an original nine-light glass and wood door. Shed roof canopies supported by knee brace brackets cover both side entrances. Windows are original eight-over-eight double hung wood sash with original shutters. A brick header course water table surrounds the dwelling. Weatherboard and a six-light fixed window are located in the gable field on the main façade. An original shed roof wing is attached to the rear façade.

(Garage, ca. 1941, CB) Located to the rear of the dwelling is an original, two-bay garage with wide width weatherboard siding and no doors.

United States Department of the Interior
National Park Service

National Register of Historic Places Continuation Sheet

Section number 7 Page 17

Galloway-Speedway Historic District
Memphis, Shelby County, Tennessee

57. 1000 Faxon Avenue ca. 1920 SY-5234 CB

This is a frame, one- and one-half story Bungalow built ca. 1920 and is currently vacant and under renovation. The dwelling has a continuous concrete block foundation, an exterior of stucco, a jerkinhead roof of asphalt shingles, one interior end brick chimney and one interior concrete and brick chimney. The full-width, hipped roof porch has square brick columns and brick piers with concrete plinths. The main entrance has an original Craftsman-style, eight-light and three wood panel door with an original single-light transom. Windows have all been covered with wood panels. A wood water table and cornice surround the dwelling. A protruding jerkinhead roof bay with a triple set of windows is located on a side façade. Stucco, knee brace brackets and two window openings-one screened and one boarded are located in the gable field.

(Shed, ca. 1940, CB) Located to the rear of the dwelling is a ca. 1940, frame shed with a shed roof.

58. 1004 Faxon Avenue ca. 1920 SY-5232 CB

The property at this location is a frame, one- and one-half story Bungalow built ca. 1920 and currently is vacant and in a severe state of disrepair. The dwelling has a continuous brick foundation, an exterior of asbestos shingle siding (some of siding panels are broken or torn), an asphalt shingled jerkinhead roof with exposed roof rafters and one interior brick chimney with a concrete cap. The full-width, hipped roof porch has exposed roof rafters, tapered wood columns on brick piers with concrete plinths. The door to the main entrance has covered over with a wood and vinyl siding panels and not visible, however, the entrance does retain its original four-light and single wood panel sidelights. All of the windows have been boarded over with wood and vinyl siding panels. Asbestos shingle siding and three boarded window openings are located in the gable field.

59. 1005-07 Faxon Avenue ca. 1940 SY-5233 CB

Located at 1005-07 Faxon Avenue is a frame, one- and one-half story Minimal Traditional style dwelling built ca. 1940 and is currently vacant. The dwelling has a continuous concrete block foundation, an exterior of brick veneer, a gable roof of asphalt shingles and an interior brick chimney with a corbelled cap. The shed roof canopy over the main entrance is supported by large, heavy brackets. The main entrance has been boarded so the doorway is not visible. All the windows on the first floor have been boarded over with wood panels. Windows on the second forlorn are original six-over-six double hung wood sash. A sailor brick beltcourse surrounds the dwelling. A circular louvered attic vent is located in the gable fields.

60. 1010 Faxon Avenue ca. 1920 SY-5234 CB

The one-story, Bungalow influenced Fire Station No. 15 was built ca. 1920 by the architectural firm of Regan and Weller. The station was discontinued in the late 20th century and is currently being used as a senior citizens center. The building has a continuous concrete foundation, jerkinhead roof of asphalt shingles with exposed roof rafters and large knee brace brackets, an interior brick chimney and an exterior of brick veneer. Windows are replacement, one-over-one double hung wood sash. Side façade windows have concrete sills and some window openings have been filled in with brick. On the main (S) facade are two projecting hipped roof bays with a tri-part one-over-one double hung wood sash windows set within battered brick columns. On the inside of these bays are entrances set within structural glass block walls. Entrances have ca. 1990 flush steel doors. These bays flank the original central garage bay entrance that has been enclosed with concrete blocks and ca. 1990, paired steel doors. The original segmental arched transom remains extant and has four sections each with three or four vertical lights. A soldier course of brick frames the garage entrance with concrete corner stones. Flanking the entrance are three pilasters of varying height with concrete caps. Above the entrance is a concrete panel with inscription "Fire Station No. 15" and a relief of a

United States Department of the Interior
National Park Service

National Register of Historic Places Continuation Sheet

Section number 7 Page 18

Galloway-Speedway Historic District
Memphis, Shelby County, Tennessee

fireman's hat, axe and fire hose nozzle above the inscription. On either side of the entrance is a concrete panel. The west panel has the following inscription: "F.L. Monteverde, Mayor, Commissioner of Public Affairs and Health; Charles B. Quinn, Commissioner of Fire and Police; C.W. Miller, Commissioner of Accounts, Finances & Revenues; A.D. Mason, Commissioner of Streets Bridges and Sewers; Leo Goodman, Commissioner of Public Utilities Grounds and Buildings." On the east panel is the following inscription: C.C. Pashby, City Clerk; M.J. Fitzmorris, Chief of Fire Department; J.M. Dolan, Secretary of Fire Department; Regan and Weller, Architects; J.E. Wright, Contractor.

The rear façade is similar in design to the main façade with an original garage bay filled with concrete blocks and steel doors, however, the original segmented arched transom has been covered with plywood panels and the garage bay is covered by a projecting jerkinhead roof bay. A double row of header course brick frames the rear entrance. At the base of both the main and rear façade garage entrances are pyramidal concrete cones.

61. 1011 Faxon Avenue ca. 1923 SY-5235 CB

This is a frame, two-story, front gable plan Bungalow built ca. 1923. The dwelling has an exterior of weatherboard siding with wood cornering, a gable roof of asphalt shingles with exposed roof rafters and one interior end stepped brick chimney. The full-width, incised porch has a wood cornice and square brick columns with concrete plinths. The main entrance has an original nine-light glass and wood panel door with its original three-light transom. A side entrance on the west façade has an original five wood panel door with a shed roof canopy supported by knee brace brackets. Windows are original nine-over-one double hung wood sash with some on the west façade boarded with wood panels. On the west and east façades are shed roof wall dormers with exposed roof rafters and each having two windows. A protruding shed roof bay on the east facade has exposed roof rafters and a triple set of windows. Square louvered attic vents and knee brace brackets are located in the gable fields. An original one-story wing with asbestos shingle siding and a gable roof is located on the rear façade.

62. 1023 Faxon Avenue ca. 1912 SY-5237 CB

At 1023 Faxon Avenue is a frame, one- and one-half story, gabled ell plan dwelling with Queen Anne style influences built ca. 1912. The dwelling has an exterior of vinyl siding, a brick pier foundation with brick infill and some stucco, a hipped roof of asphalt shingles and three, interior concrete chimneys. The wraparound, hipped roof porch has replacement wrought iron posts and two, single-light fixed windows in the gable field. The main entrance has an original six-light and wood panel door with original three-section transom, original single-light and wood panel sidelights and a metal security door. A secondary entrance has a ca. 1970, diamond-light and wood door. Windows are original one-over-one double hung wood sash. A wood wheelchair ramp extends from the porch on the main façade. On the west façade is a protruding gable roof bay with three windows. The dwelling is currently in a state of disrepair.

63. 1026 Faxon Avenue ca. 1970 SY-5239 NCB

This is a frame, ca. 1970 Bungalow with a stucco-covered foundation, an exterior of vinyl siding and a side gable roof of asphalt shingles. The gable roof entry porch is supported by square wood columns on an open wood railing. Of the two entrances on the main façade, one has been covered with vinyl siding while the other has a ca. 1980, six-panel metal door with original sidelights that have been covered with wood panels and a metal security door. Windows are six-over-six double hung metal sash.

United States Department of the Interior
National Park ServiceNational Register of Historic Places
Continuation SheetSection number 7 Page 19Galloway-Speedway Historic District
Memphis, Shelby County, Tennessee**64. 1027 Faxon Avenue ca. 1912 SY-5238 CB**

At 1027 Faxon Avenue stands a frame, two-story American Foursquare style dwelling built ca. 1912. The dwelling has a continuous stucco covered foundation, an exterior of stucco, an asphalt shingled hipped roof and one interior end stucco covered chimney. The full-width, hipped roof porch extends out to a carport and has stucco covered tapered columns on stucco-covered piers with concrete plinths and a closed stucco railing. The main entrance has a ca. 1980, solid wood door but retains its original single-light transom and original single-light and wood panel sidelights. Windows are original, one-over-one and six-over-one double hung wood sash with wood surrounds. A wood beltcourse and cornice surround the dwelling. On the main façade is a hipped roof dormer with three, single-light fixed windows. On the east façade is a protruding, hipped roof bay with three windows. An original one-story addition is located on the rear façade. Attached to this rear wing is a ca. 1970, shed roof addition with an exterior of vinyl siding. The dwelling is currently in a state of disrepair.

65. 1032 Faxon Avenue ca. 1928 SY-5240 CB

This is a frame, one- and one-half story Bungalow built ca. 1928. The dwelling has a continuous concrete foundation, an exterior of brick veneer, a jerkinhead roof of asphalt shingles with milled brackets and one interior end and one interior brick chimneys with corbelled caps. The full-width, hipped roof porch extends out to a porte-cochere and has a wrought iron frieze, wrought iron brackets, a wood cornice, battered brick columns, a closed brick railing, modillion blocks and half-moon concrete drains. The main entrance has an original nine-light glass and wood panel door with an original seven-light transom, original six-light and wood panel sidelights with metal security bars and a metal security door. Windows are original Craftsman-style, one-over-one double hung wood sash with concrete sills. A solid course brick water table and beltcourse surround the dwelling. Stucco, modillion blocks, knee brace brackets and two, single-light fixed attic windows are located in the gable field on the main façade. A ca. 1970, shed roof addition with an exterior of vinyl siding has been added to the rear façade.

(Garage, ca. 1950, CB) Located to the rear of the dwelling is a ca. 1950, one-bay garage with an exterior of shiplap siding and a gable roof of asphalt shingles.

66. 1037 Faxon Avenue ca. 1912 SY-5242 CB

The property at 1037 Faxon Avenue is a frame, two-story, asymmetrical plan Bungalow built ca. 1912. The dwelling has a continuous stucco covered foundation, an exterior of stucco and brick veneer, a jerkinhead roof of asphalt shingles, one exterior end brick and stucco covered chimney and one interior end stucco covered chimney. The full-width, shed roof porch has exposed roof rafters, knee brace brackets, a large wood cornice, battered stone columns, square wood columns on stone piers and a closed stone railing with a concrete top rail. The main entrance has a ca. 1980, fifteen-light glass and wood door with its original single-light transom with metal security bars. A secondary entrance on the east façade has a solid wood door. Windows are original, Craftsman-style one-over-one double hung wood sash with some replacement one-over-one double hung sash. Two wood beltcourses surround the dwelling. On the roofline of the main façade are two, gable roof dormers with pentagonal shaped window opening covered with wood panels, small gable returns and exposed roof rafters. Located in the gable fields are knee brace brackets and a triple set of single-light fixed windows.

United States Department of the Interior
National Park ServiceNational Register of Historic Places
Continuation SheetSection number 7 Page 20Galloway-Speedway Historic District
Memphis, Shelby County, Tennessee**67. 1036 Faxon Avenue ca. 1913 SY-5241 CB**

This is a frame, one- and one-half story pyramid square plan dwelling built ca. 1913. The dwelling has a continuous stucco covered foundation, an exterior of stucco, a hipped roof of asphalt shingles and an interior brick chimney. The full-width, incised porch has square, stucco covered columns and an enclosed stuccoed railing. The porch has been partially enclosed with aluminum siding and windows on the east façade. The main entrance has an original single light glass and wood door with an original single-light transom and original single-light and wood panel sidelights. Windows are some original one-over-one double hung wood sash with many replacement two-over-two horizontal light double hung metal sash. Located on the roofline of the south and west façades are hipped roof dormers with exposed roof rafters, an exterior of asphalt shingles and attic vent openings which have been downsized and covered wood panels. On the west façade is a protruding bay with a four-set of windows.

(Garage, ca. 1970, NCB) A ca. 1970 addition has been added to the rear façade with an exterior of vinyl siding.

68. 1039 Faxon Avenue ca. 1927 SY-5243 CB

One- and one-half story Bungalow built ca. 1927. The dwelling has a continuous stucco covered foundation, an exterior of brick veneer, a jerkinhead roof of asphalt shingles and one exterior end and one interior brick chimneys. The full-width, gable and hipped roof porch has square brick columns on brick piers with concrete plinths, an open brick railing with a concrete top rail and vinyl siding in the gable field. The main entrance has a fifteen-light glass and wood door with an original single-light transom and a metal security door. Windows are original, three-over-one vertical light double hung wood sash with concrete sills and metal security bars. A soldier course beltcourse and water table surround the dwelling. Vinyl siding and two window openings-one with no glass and the other with a four-light fixed window with a screen.

(Garage ca. 1970, NCB) Located to the rear of the dwelling is a non-contributing, ca. 1970, one-bay garage with an exterior of vinyl siding, a gable roof and no door. The garage extends into a wrought iron post supported carport.

69. 1040 Faxon Avenue ca. 1913 SY-5244 CB

This is a frame, one- and one-half story Bungalow built ca. 1913. The dwelling has a continuous concrete foundation, an exterior of vinyl siding, a hipped roof of asphalt shingles with exposed roof rafters and an interior concrete chimney with three clay chimney caps. The full-width, incised porch has square wood paneled columns and a closed vinyl sided railing. The door to the main entrance is not visible but the entrance does retain its original three-section transom and original single-light sidelights. Windows are original one-over-one double hung wood sash. Located on roofline of the main (S) façade is a hipped roof dormer with exposed roof rafters and two, single-light fixed windows. A small projecting window bay with four, one-over-one double hung wood sash windows is located on the west façade.

70. 1043 Faxon Avenue ca. 1911 SY-5245 CB

At this location is a frame, two-story American Foursquare style dwelling built ca. 1911. The dwelling has an exterior of vinyl siding, a hipped roof of asphalt shingles and an interior end concrete chimney. The wraparound, hipped roof porch has wrought iron columns and a wrought iron railing. The main entrance has a ca. 1980, single-light glass and wood door with an original single-light transom and original single-light sidelights covered with metal security bars. Windows are original one-over-one double hung wood sash and replacement two-over-two double hung metal sash, both having metal security bars. A small projecting one-story bay window is located on the west façade. On the roofline of the main (N) façade is a hipped roof dormer with an opening covered with aluminum siding.

United States Department of the Interior
National Park Service

National Register of Historic Places Continuation Sheet

Section number 7 Page 21

Galloway-Speedway Historic District
Memphis, Shelby County, Tennessee

71. 1046 Faxon Avenue ca. 1923 SY-5246 CB

This is a frame, one- and one-half story Bungalow built ca. 1923. The dwelling has a continuous poured concrete foundation, an exterior of brick veneer, a jerkinhead roof of asphalt shingles and one interior brick chimney. The full-width, hipped roof porch has battered brick columns and closed brick railing. Two entrances are located on the main façade both have a ca. 1990, paneled aluminum door with one entrance retaining its original single-light rectangular transom covered with a wood panel. Windows are original one-over-one double hung wood sash with metal security bars. In the gable field on the main façade are two attic windows with wood lattice. A small, projecting gable bay window is located on the east and west facades.

72. 1047 Faxon Avenue ca. 1913 SY-5247 CB

This is a frame, one-story, pyramid square plan dwelling built 1913. The dwelling has a continuous concrete foundation, an exterior of vinyl siding, an interior stone chimney and an asphalt shingled hipped roof. The full-width, incised porch has double and triple square wood columns, a closed stone railing and a concrete floor. The main entrance retains its original eight-light glass and wood panel door with an original three-light transom and a metal security door. Located in the gable field on the main (S) façade are exposed roof rafters and at the roofline is a hipped roof dormer with roof rafters, an exterior of vinyl siding and three, single-light fixed windows.

(Shed, ca. 1980, NCB) Situated to the rear of the dwelling is a non-contributing, ca. 1980, small metal storage shed.

73. 1052 Faxon Avenue ca. 1923 SY-5248 CB

Located at 1052 Faxon Avenue is a frame, one- and one-half story Bungalow built ca. 1923. The dwelling has a continuous poured concrete foundation, an exterior of wired brick veneer, a gable front roof of asphalt singles with exposed roof rafters and a side gable window and an interior brick chimney. The full-width, hipped roof porch has a gable over the entrance and extends out to a porte-cochere. The porch is supported by square brick columns and an open brick railing. The main entrance has an original fifteen-light glass and wood door with original ten-light sidelights with metal security bars and a metal security door. Windows are original one-over-one double hung wood sash with metal security bars. Located in the gable field on the main façade are two, single-light fixed attic windows.

74. 1053 Faxon Avenue ca. 1912 SY-5249 CB

This is a frame, one- and one-half story Bungalow built ca. 1912. The dwelling has a continuous poured concrete foundation, an exterior of vinyl siding, an exterior end stone chimney and a side gable roof of asphalt shingles. The full-width, shed roof porch has exposed roof rafters under the flare, tapered wood columns on stone piers, an open wood railing and a poured concrete floor. The main entrance has an original six-light glass and wood door with an original rectangular, single-light transom and a storm door. Windows are original nine-over-one double hung wood sash with paired, nine-light casement windows with three-light transoms on the side facades. On the main façade roofline is a shed roof dormer with three, eight-light fixed windows and knee brace brackets in the gable field. The interior of the dwelling has original built-in bookcases, china cabinets with leaded glass and large ceiling beams.

75. 1056 Faxon Avenue ca. 1913 SY-5250 NCB

This is a frame, two-story, American Foursquare style dwelling built ca. 1913. The dwelling has a continuous brick and poured concrete foundation, an exterior of vinyl siding, an asphalt shingled hipped roof with a flare and one interior end brick chimney. The full-width, hipped roof porch has square brick columns on brick piers and a concrete floor. The remodeled main entrance has been covered with aluminum siding and the door is not visible. Windows are one-over-one double hung wood sash.

United States Department of the Interior
National Park Service

National Register of Historic Places Continuation Sheet

Section number 7 Page 22

Galloway-Speedway Historic District
Memphis, Shelby County, Tennessee

76. 1057 Faxon Avenue ca. 1926 SY-5251 NCB

This is a frame, one-story Bungalow built ca. 1926 and moved to this located within the past twenty years and drastically remodeled. The dwelling has an exterior of vertical panels and a multi-gable roof of asphalt shingles with exposed roof rafters. The porch has been altered with one section totally enclosed. The remainder of the porch has a gable roof with exposed roof rafters and a single remaining wood post. The main entrance door is not visible but does have a metal security door. Windows are mostly replacement, six-over-one double hung wood sash with the majority being covered over with wood boards.

77. 1063 Faxon Avenue ca. 1920 SY-5252 CB

At 1063 Faxon Avenue stands a frame, one- and one-half story Minimal Traditional style dwelling with Colonial Revival style influences built ca. 1920. The dwelling has a continuous poured concrete foundation, an exterior of brick veneer, a side gable roof of asphalt shingles and an interior brick chimney. The gable roof entry porch extends out to a patio section has square brick columns, an open concrete railing and vinyl siding in the gable field. The main entrance has a ca. 1980, flush wood door. Windows are ca. 1980, one-over-one double hung vinyl clad windows with concrete sills and metal security bars. A soldier course brick water table surrounds the dwelling. A small, frame, shed roof wing is located on the rear façade.

78. 1069 Faxon Avenue ca. 1920 SY-5254 CB

One- and one-half story Airplane Bungalow with a raised monitor roof section built ca. 1920. The dwelling has a continuous concrete block and stucco covered foundation, an exterior of stucco, a multi-gabled roof of asphalt shingles and two stucco covered exterior end chimneys. The full-width hipped roof porch has a segmented aluminum sided frieze and cornice, battered stone columns and a closed stone railing with a concrete top rail. The main entrance has an original eight-light glass and wood panel door with original sidelights that have been partially covered with aluminum siding and a metal security door. Windows are original one-over-one double hung wood sash with wood surrounds and metal security bars. A wood beltcourse and two, wood water tables surround the dwelling. On the west façade is a protruding bay with a double set of windows. Located in the gable field on the main façade is stucco and two, single-light fixed windows. The full-width raised gabled monitor roof section has an exterior of aluminum siding. Also attached to the side façade is a metal shed roof carport with an attached shed with an exterior of aluminum siding. A ca. 1970, addition has been attached to the rear façade with an exterior of aluminum siding.

(Garage, ca. 1920, CB) Located to the rear of the dwelling is an original two-bay frame garage with an asphalt shingled hipped roof, weatherboard siding and two sets of double diagonal-cut wood hinged doors.

79. 1071 Faxon Avenue ca. 1920 SY-5255 CB

This is a frame, one- and one-half story Airplane Bungalow with a full-width, raised monitor roof section built ca. 1920. The dwelling has a continuous concrete and stucco covered foundation, an exterior of asbestos shingle siding, a hipped roof of asphalt shingles with exposed roof rafters and one interior brick chimney with two clay chimney caps. The full-width, incised porch has a large wood cornice and frieze, banded Tuscan columns on a closed concrete block railing with a concrete top rail. Half of the porch has been enclosed with screening and a metal awning has been placed on the west façade. The main entrance has an original single-light glass and wood door with an original single-light transom and original single-light and wood panel sidelights. Windows are original one-over-one double hung wood sash with wood surrounds. On the west façade is a protruding bay with a triple set of windows. On the east façade is another protruding bay but this bay has only two windows. A ca. 1970, gable roof addition has been added

United States Department of the Interior
National Park Service

National Register of Historic Places Continuation Sheet

Section number 7 Page 23

Galloway-Speedway Historic District
Memphis, Shelby County, Tennessee

to the rear façade. The raised gabled monitor roof section has exposed roof rafters and asbestos shingle siding. On the main façade is a hipped roof dormer with exposed roof rafters.

(Garage/Shed, ca. 1940, NCB) Located to the rear of the dwelling is a ca. 1940, renovated, frame garage/shed with a hipped roof of asphalt shingles, an exterior of vinyl siding and replaced doors and windows.

80. 1074 Faxon Avenue ca. 1922 SY-5256 CB

The property at this location is a frame, one- and one-half story Bungalow built ca. 1922. The dwelling has a continuous stucco covered foundation, an exterior of painted pressed board wood shingle siding, a gable and hipped roof of asphalt shingles and a concrete a brick interior chimney with two clay caps. The full-width, incised roof has square stuccoed columns with concrete plinths and a single concrete dentil detail and a closed stuccoed railing with a concrete top rail. The main entrance has an original single-light glass and wood door with an original single-light transom, original single-light and wood panel sidelights and a screen door. Windows are original one-over-one double hung wood sash. Located on the roofline of the main façade is a large, gable roof dormer with three window openings—two missing glass and one with a single-light fixed window. In the gable field on the main façade are gable returns and a single-light fixed window. A wood water table surrounds the dwelling. On the west façade is a protruding gable roof bay with a double set of windows. On the east façade is another protruding bay but with a triple set of windows.

81. 1078 Faxon Avenue ca. 1921 SY-5257 CB

This is a frame, one- and one-half story Bungalow built ca. 1921. The dwelling has a continuous poured concrete foundation, an exterior of brick veneer, a multi-gable roof of asphalt shingles and two, interior end brick chimneys. The full-width, gable roof porch has square brick columns with corbelled capitals, a closed stucco covered and a concrete railing with a concrete top rail. The gable field of the porch has stick work, stucco and three, two-light metal jalousie windows. The main façade has two entrances both having ca. 1980, fifteen-light glass and wood doors and wrought iron security doors. Windows are original three-over-one vertical light and six-over-one double hung wood sash with concrete sills. A concrete water table and a large wood cornice surround the dwelling. A ca. 1970, addition has been attached to the rear façade with a gable roof and an exterior of aluminum siding. Stucco and a double set of original three-over-one vertical light double hung wood sash windows are in the gable fields.

(Garage, ca. 1921, CB) Located to the rear of the dwelling is a ca. 1921, frame garage/shed with a steep pitched gable roof.

82. 1079 Faxon Avenue ca. 1912 SY-5258 CB

Located at 1079 Faxon Avenue is a frame, one- and one-half story Bungalow built ca. 1912 and remodeled ca. 1960 with a rear two-story addition. The dwelling has a continuous poured concrete foundation, an exterior of stucco, a jerkinhead roof of asphalt shingles with exposed roof rafters and one exterior end brick and stucco-covered chimney. The full-width, hipped roof porch has battered stone columns and an open wood railing. The main entrance has an original Craftsman-style, single-light and single wood panel door with original three-section (three-light-four-light-three-light) transom, original Craftsman style single-light and wood panel sidelights with metal security bars and a metal security door. Windows are original one-over-one double hung wood sash with wood surrounds. A wood beltcourse and water table surround the dwelling. The 2nd story addition has a gable front roof of asphalt shingles and an exterior of asbestos shingle siding. On the west façade is a protruding, jerkinhead roof bay with a triple set of windows. Stucco, knee brace brackets and two, one-over-one double hung wood sash windows are located in the gable fields.

United States Department of the Interior
National Park ServiceNational Register of Historic Places
Continuation SheetSection number 7 Page 24Galloway-Speedway Historic District
Memphis, Shelby County, Tennessee

(Shed, ca. 1980, NCB)

83. 1084 Faxon Avenue ca. 1917 SY-5259 CB

This is a frame, one- and one-half story Bungalow built ca. 1917. The dwelling has a continuous stucco-covered foundation, an exterior of stucco, a gable and hipped roof of asphalt shingles with exposed roof rafters, one exterior end brick and stucco-covered chimney and one interior end brick and concrete chimney. The full-width, shed roof porch has battered brick columns, square wood columns on brick piers and a closed stuccoed railing with a concrete top rail. The door to the main entrance is not visible but it does retain the original transom that has been covered with a wood panel. Windows are original twelve-over-one double hung wood sash with security bars. A wood water table surrounds the dwelling. On the east façade is a protruding bay with a triple set of windows. A ca. 1970 addition has been added to the rear façade with an exterior of aluminum siding. At the roofline on the main façade is a gable roof dormer with three, small six-light fixed offset windows.

84. 1085 Faxon Avenue ca. 1930 SY-5260 CB

One- and one-half story Airplane Bungalow with a raised monitor roof section built ca. 1930. The dwelling has a continuous concrete foundation, an exterior of wired brick veneer, a gable and hipped roof of asphalt shingles with exposed roof rafters and one exterior end and one interior end brick chimneys. The full-width, gable and hipped roof porch extends out to a porte-cochere and has exposed roof rafters, a wood cornice, square brick columns with swags and corbelled capitals, an open brick railing with a concrete top rail and stucco in the gable field. The door to the main entrance is not visible but the entrance does retain its original single-light and single wood panel sidelights, a metal security door and a header course lintel over the doorway. Windows are original one-over-one double hung wood sash with concrete sills. A soldier course brick beltcourse surrounds the dwelling. The raised hipped monitor roof section has exposed roof rafters and an exterior of weatherboard siding. Stucco and two, single-light fixed windows are located in the gable fields.

(Garage, ca. 1920, CB) Located to the rear of the dwelling is a ca. 1920, one-bay garage with a gable roof of asphalt shingles, an exterior of weatherboard siding and vertical board double doors.

85. 1088 Faxon Avenue ca. 1920 SY-5261 CB

This is a frame, one- and one-half story Bungalow built ca. 1920. The dwelling has a continuous poured concrete and stucco-covered foundation, an exterior of stucco, a jerkinhead and gable roof of asphalt shingles with exposed roof rafters and one interior end concrete chimney. The full-width, hipped roof porch has battered stone columns with concrete plinths, a closed stone railing with a concrete top rail and wrought iron brackets. The west side of the porch has been enclosed with vertical board and windows. Two entrances are located on the main façade. The main entrance has an original, Craftsman-style, eight-light glass and wood panel door with an original six-light transom (painted-in) and original sidelights covered with wood panels. The secondary entrance on the main façade has a ca. 1970, solid wood door. Both entrances have metal security doors. Windows are original, Craftsman style one-over-one double hung wood sash. A sailor course beltcourse and a soldier course water table surround the dwelling. On the east façade is a protruding gable roof bay with a triple set of windows and stucco and one, two-light fixed window in the gable field. In the jerkinhead field are two, two-light fixed rectangular windows and stucco. In the gable roof's gable field are stucco and a twelve-light fixed window.

United States Department of the Interior
National Park ServiceNational Register of Historic Places
Continuation SheetSection number 7 Page 25Galloway-Speedway Historic District
Memphis, Shelby County, Tennessee**86. 1089 Faxon Avenue ca. 1915 SY-5262 CB**

This is a frame, one- and one-half story Airplane Bungalow with a full two-story raised monitor roof section built ca. 1915. The dwelling has a continuous stucco-covered foundation, an exterior of stucco with wood cornering, an asphalt shingled jerkinhead roof with exposed roof rafters and one interior end stucco-covered chimney with a concrete chimney cap. The full-width, hipped roof porch has exposed roof rafters, a stuccoed swaged cornice/frieze, stuccoed battered stone columns and an open concrete railing. The main entrance has a Colonial Revival style influenced entry with a pedimented entablature with ridged pilasters and a metal security door. The door itself is not visible. Windows are original, nine-over-one double hung wood sash and ten-light fixed casement windows with the top two-light fixed. On the main (N) façade is a picture window with a large single-light fixed window flanked by five-light fixed windows with a casement segment. On the east façade are large, twenty-light fixed windows flanked by two, four-light casement windows. A wood water table and beltcourse surround the dwelling. An entrance on a side façade has a shed roof canopy supported by brackets. A wood wheelchair ramp has been installed off the west side of the porch. In the gable field on the main façade are stucco, knee brace brackets and a triple set of four-light fixed windows. On the east façade is a protruding bay with a hipped roof with exposed roof rafters, an exterior of brick veneer, builders glass blocks and two windows. On the west façade is a jerkinhead roof bay with a triple set of windows of nine-over-one double hung wood sash windows. In the gable field of both facades protruding bays are stucco, knee brace brackets and a small, square attic vent. The raised hipped monitor roof section has exposed roof rafters, asphalt shingles and wood cornering.

(Garage, ca. 1920, CB) Located to the rear of the dwelling is a ca. 1920, frame, one-bay garage with an exterior of weatherboard, a gable roof of asphalt shingles and vertical board hinged double doors.

87. 1094 Faxon Avenue ca. 1920 SY-5263 CB

At 1094 Faxon Avenue stands a frame, one- and one-half story Bungalow built ca. 1920. The dwelling has a continuous poured concrete foundation, an exterior of brick veneer, a front gable roof of asphalt shingles, one interior end and one interior brick chimneys. The full-width, hipped and gable roof has exposed roof rafters, a wood cornice, battered stone columns with concrete plinths, a closed stone railing with a concrete top rail and stucco in the gable field. Two entrances are located on the main façade. One entrance has an original, Craftsman style, single-light glass and wood panel door with an original eight-light transom and original four-light and wood panel sidelights. The second entrance on the main façade has a ca. 1990, solid wood door but still retains its original eight-light transom and original four-light sidelights. Windows are original Craftsman-style, one-over-one double hung wood sash with concrete sill. A soldier course beltcourse and wood cornice surrounds the dwelling. Stucco and two, single-light fixed windows are located in the gable field on the main façade.

88. 1095 Faxon Avenue ca. 1915 SY-5264 CB

This is a frame, one- and one-half story Bungalow built ca. 1915. The dwelling has an exterior of stucco and half-timbering, a front gable roof of asphalt shingles and two stucco covered interior chimneys. The gable roof entry porch extends out to a patio and has battered stone columns, an open concrete railing, a concrete floor and stucco and half-timbering in the gable field. The main entrance has an original, Craftsman style eight-light glass and wood panel door with an original twelve-light transom and original ten-light and wood panel sidelights. Windows are original, Craftsman style, one-over-one double hung wood sash with metal security bars and metal shed roof awnings on the side facades. On the east elevation is a small, projecting gable roof window bay with three, one-over-one double hung wood sash windows. Vinyl soffits have been installed in the eaves.

United States Department of the Interior
National Park ServiceNational Register of Historic Places
Continuation SheetSection number 7 Page 26Galloway-Speedway Historic District
Memphis, Shelby County, Tennessee

(Garage, ca. 1915, CB) Located to the rear of the dwelling is a ca. 1915, one-bay frame garage with an exterior of synthetic siding, a hipped roof of asphalt shingles with exposed roof rafters, a ca. 1970, overhead metal track door and an adjacent pedestrian entrance with an original four-light and four wood panel door. Marked in the sidewalk in front of the dwelling are the words "M.C. Turney & Sons 1948 Memphis".

89. 1100 Faxon Avenue ca. 1940 SY-5265 CB

Located at this address is a frame, one- and one-half story Bungalow built ca. 1940. The dwelling has an exterior of brick veneer, a clipped side gable roof of asphalt shingles and an interior brick chimney. The full-width, jerkinhead roof porch has square brick columns, wrought iron columns and a closed brick railing. The main entrance has a ca. 1990 paneled wood door with a metal security door. Windows are original, six-over-one double hung wood sash with concrete sills and metal security bars. In the gable field of the porch are knee brace brackets and two, four-light attic windows. Knee brace brackets are also located in the remaining gable fields. An original door or window opening on the main façade has been enclosed with brick.

90. 1101 Faxon Avenue ca. 1920 SY-5266 CB

This is a frame, one- and one-half story Airplane Bungalow with a rear raised monitor roof section built ca. 1920. The dwelling has an exterior of brick veneer, two interior brick chimneys and a clipped side gable roof of asphalt shingles. The full-width, gable and shed roof porch has battered stone columns, a tongue and groove ceiling and an open concrete railing. The door to the main entrance is not visible but the entrance does retain its original four-light transom. An entrance on the east façade has a ca. 1990, solid wood door with an original single-light transom and original single-light sidelights. Windows are original six-over-one double hung wood sash with metal security bars and concrete sills. A soldier course water table surrounds the dwelling. An original, small shed roof wing with an exterior of stucco is located on the rear façade. In the gable field on the main façade are two, single-light fixed attic windows. Stucco is located in all the gable fields. The raised gabled monitor roof has an exterior of stucco and exposed roof rafters.

(Shed, ca. 1940, CB) Located to the rear of the dwelling is a ca. 1940, small, frame shed with an exterior of horizontal board, a shed roof with exposed roof rafters and a flush wood door.

91. 1111 Faxon Avenue ca. 1915 SY-5267 CB

At this location is a frame, two-story American Foursquare style dwelling built ca. 1915. The dwelling has an exterior of Masonite shingle siding, a hipped roof of asphalt shingles and an interior end brick chimney. The rebuilt, full-width shed roof porch has ca. 1990, square wood columns and a square wood lattice railing. The main entrance has a ca. 1990, paneled aluminum door with an original transom currently covered with a wood panel and original sidelights that have been either totally removed or covered over. Windows are ca. 1990, six-over-six vinyl clad double hung sash with fake muntin bars.

92. 1117 Faxon Avenue ca. 1915 SY-5268 CB

This is a frame, one- and one-half story Bungalow built ca. 1915 and currently is seriously deteriorated and poor condition. The dwelling has an exterior of weatherboard siding, a continuous brick foundation covered with stucco, a side gable roof and an interior end stucco covered chimney with a clay chimney cap. The full-width, shed roof porch has square stuccoed columns, two Tuscan columns on stuccoed piers and a closed stuccoed railing with an arched frieze. The main entrance has a ca. 1980, flush wood door but retains its original single-light transom, original single-light sidelights and a metal security door. A small projecting shed roof window bay with exposed roof rafters is

United States Department of the Interior
National Park ServiceNational Register of Historic Places
Continuation SheetSection number 7 Page 27Galloway-Speedway Historic District
Memphis, Shelby County, Tennessee

located on the west façade. In the gable field on the main façade are two, gable roof dormers with exposed roof rafters and each having a single-fixed light window. Knee brace brackets and stucco are located in the gable fields.

93. 1120 Faxon Avenue ca. 1914-1924 SY-5269-70 CB

Located at 1120 Faxon Avenue is a two-story, Spanish Colonial Revival influenced church built from 1914 to 1924 with an attached manse and ca. 1960 rear addition. The church originally went by the name of the Epworth M.E. Church but has since had a name change to the Good Samaritan United Methodist Church. The church has an exterior of brick veneer, a hipped roof of asphalt shingles with wide eaves and paired oversized brackets. On the main (S), east and west facades, the church has a large central concrete panel with a Spanish Mission style parapet that pierces the main roofline. The parapets have scroll and leaf designs of concrete. Set within each of these concrete panels is a large Palladian style influenced tri-part window. The central portion of the window has a large circular pane with a cross design in the stained glass. Beneath this are eight large rectangular stained glass windows. The entire window design is set within a concrete frame divided by fluted pilasters with Ionic capitals and an arched band with a circle motif and large keystone with a globe shaped top. Flanking the windows are original metal/iron light fixtures with round globes.

On the main façade are two identical entrances on either side of the large central concrete panel. The entrances have ca. 1985, paired steel door with original rectangular stained glass transoms. The frames and surrounds of entrances remain original. These are large concrete pilasters with Corinthian capitals and a large concrete cornice that continues into a concrete surround of 2nd story windows above the entrances. These windows are one-over-one double hung wood sash of stained glass. The concrete surrounds have a scroll and urn design above the windows and below the windows are large concrete panels with a central shield and vine design. Flanking this panels (directly above the cornice of the entrance) are decorative pear-shaped urns. Leading to each entrance are concrete steps that are parallel to the building and enclosed with a concrete wall. An added handicap ramp (ca. 1975-80) leads to the eastern entrance of the main façade. Basement windows are original four-light glass and wood design. On the west façade is a concrete panel that reads "Epworth M.E. Church South 1914-1924".

On the west façade is a basement entrance with an original four-light glass and wood door with an original three-light transom. Basement windows on the west façade are four-over-four and eight-over-eight double hung wood sash. A second basement entrance has a ca. 1990 steel door.

The rear portion of the church has an exterior of brick veneer, eight-over-eight double hung wood sash windows and two windows with a single large diamond upper sash over a four-vertical light lower sash. The rear façade has a large polygonal bay.

On the side facades, the stained glass of the upper portions of the large central windows has been replaced with textured glass. Rear façade has original six-light casement windows and two-light transoms. At the basement level at the rear corners of the church are concrete pier braces with large concrete scroll designed caps.

Adjacent to the church to the east is a contributing, ca. 1920, two-story, frame, American Foursquare style dwelling (SY-5270-CB). The dwelling has a hipped roof of asphalt shingles, two interior brick chimneys and an exterior of brick veneer. The main entrance has a single-light glass and wood door with an original single-light transom and original single-light sidelights. Windows are six-over-one double hung wood sash. On the main façade roofline is a hipped roof dormer with three, square wood vents. On the west façade of the dwelling is an exterior metal staircase that leads to a second floor entrance.

United States Department of the Interior
National Park Service

National Register of Historic Places Continuation Sheet

Section number 7 Page 28

Galloway-Speedway Historic District
Memphis, Shelby County, Tennessee

The church and the American Foursquare dwelling are attached at the rear via a two-story wing that appears to date to ca. 1960. The wing has an exterior of brick veneer, three-light metal hopper windows with brick sills and soldier course brick lintels and an interior brick chimney. On the south façade of the wing is an entrance with paired ca. 1990, steel doors. The entrance leads to a landing and stairs down to ground level and is covered by a large flat roof supported by a brick wall and a wrought iron post. The roof has a large aluminum sided cornice with a wrought iron frieze and brackets.

FORREST AVENUE

94. 918-20 Forrest Avenue ca. 1940 SY-5274 NCB

At this location stands a frame, one- and one-half story Minimal Traditional style dwelling built ca. 1940 and extensively remodeled. The dwelling has an exterior of brick veneer, a continuous concrete foundation, a multi-gable roof of asphalt shingles and one interior central brick flue with a corbelled brick cap and a clay chimney cap. The shed roof entry porch has only one-brick column. The main façade has two entrances. Both entrances have metal security doors but only one is visible with a ca. 1980, fanlight and panel aluminum door. Windows are original six-over-six double hung wood sash with metal security bars and brick sills. A soldier brick beltcourse surrounds the dwelling. Yellow vinyl siding is located in the gable fields.

(Shed, ca. 1940, CB) Located to the rear of the dwelling is a contributing, ca. 1940, frame shed with a gable roof and vertical board hinged double doors.

95. 921 Forrest Avenue ca. 1928 SY-5275 CB

This is a frame, one-story Bungalow built ca. 1928. The dwelling has an exterior of brick veneer with stucco on the main façade, a jerkinhead roof of asphalt shingles, two metal flues, one interior and one interior central stucco and brick chimneys. The full-width, hipped roof porch has double square wood columns on stuccoed piers, and a closed brick railing. The main entrance has an original multi-light glass and wood door with an original four-light transom and a metal security door. Windows are original one-over-one double hung wood sash with brick sills on the side facades. A soldier brick beltcourse surrounds the dwelling. Two, single-light fixed windows are located in the gable field on the main façade.

(Garage, ca. 1928, CB) Located to the rear of the dwelling is an original, frame, garage with an exterior of synthetic siding, a gable roof and hinged, double wood doors.

96. 924 Forrest Avenue ca. 1929 SY-5276 CB

One- and one-half story Airplane Bungalow with a raised monitor roof section built ca. 1929. The dwelling has an exterior of brick veneer, a multi-gabled roof of asphalt shingles, one interior end and one exterior end brick chimneys. The full-width, hipped and gable roof porch extends out to a porte-cochere and has tapered stone columns, a closed brick railing and a square metal vent in the gable field. Both entrances on the main façade have fifteen-light glass and wood doors with one retaining its original four-light sidelights. Windows are original three-over-one vertical light double hung wood sash. The raised monitor roof section has an exterior of asbestos shingle siding, exposed roof rafters, two-over-two double hung horizontal light double hung metal sash windows and paired two-over-two horizontal light double hung wood sash windows in the gable field.

United States Department of the Interior
National Park Service

National Register of Historic Places Continuation Sheet

Section number 7 Page 29

Galloway-Speedway Historic District
Memphis, Shelby County, Tennessee

97. 925 Forrest Avenue ca. 1928 SY-5277 CB

This is one-story, frame Bungalow built ca. 1928. The dwelling has a continuous concrete foundation, an exterior of brick veneer, a jerkinhead roof of asphalt shingles and a metal flue. The full-width, hipped roof porch has tapered brick columns, an open brick railing and a concrete top rail. The main entrance has a ca. 1970, diamond-light glass and wood door with a metal security door and an enclosed transom. Windows are original one-over-one double hung wood sash with metal security bars. Two, square, single-light fixed windows are in the gable field on the main façade.

(Shed, ca. 1980, NCB) Located to the rear of the dwelling is a non-contributing, ca. 1980, small metal storage shed.

98. 930-32 Forrest Avenue ca. 1967 SY-5278 NCB

This is a frame, one-story Bungalow and was totally remodeled ca. 1967. The dwelling has an exterior of brick veneer, a metal flue and an asphalt shingled gable and hipped roof with the hipped section originally a porch that has been enclosed. The small, incised entry porch has one, wrought iron post. The main entrance is unknown but it does retain a metal security door. Windows are six-over-six double hung windows with security bars.

(Shed, ca. 1980, NCB)

99. 931 Forrest Avenue ca. 1928 SY-5279 CB

The property at this address is a frame, one-story Bungalow built ca. 1928. The dwelling has an exterior of stucco, an asphalt shingled jerkinhead roof and one exterior end stucco covered chimney. The full-width, hipped roof porch has exposed roof rafters, stone and concrete columns and a shed roof awning. The main entrance has a multi-vertical light glass and wood door with an original three section rectangular transom and original vertical light sidelights. Windows are original four-over-one vertical-light double hung wood sash windows. Flanking the chimney are multi-light rectangular, fixed light Craftsman windows.

(Shed, ca. 1980, NCB) Located to the rear of the dwelling is a non-contributing, ca. 1980, metal storage shed. Paired, single-light windows are located in the main facades gable field.

100. 934 Forrest Avenue ca. 1927 SY-5280 CB

This is a frame, one-story Bungalow built ca. 1927. The dwelling has an exterior of brick veneer, a multi-gabled roof of asphalt shingles with exposed roof rafters and a large exterior end brick chimney on the main façade with patterned brick detailing. The full-width, gable roof porch extends out to a porte-cochere with exposed roof rafters, brick columns, one wrought iron column and a closed brick railing. The main entrance has an original, Craftsman style, single-light glass and wood door with original single-light sidelights and a metal security door. Windows are original, Craftsman style, one-over-one double hung wood sash with metal, shed roof awnings. Paired, square Craftsman style attic windows are located in the gable field on the main façade.

(Shed, ca. 1980, NCB) Located to the rear of the dwelling is a non-contributing, ca. 1980, frame shed.

101. 935 Forrest Avenue ca. 1930 SY-5281 CB

One- and one-half story Airplane Bungalow with a raised monitor roof section built ca. 1930. The dwelling has a multi-gabled roof of asphalt shingles with exposed roof rafters, an exterior of brick veneer, one interior brick chimney with a soldier course brick and wood design detail and one large, tapered, exterior end brick chimney with decorative brick and wood design detailing. The gable roof porch extends out to a porte-cochere with exposed roof rafters, brick

United States Department of the Interior
National Park Service

National Register of Historic Places Continuation Sheet

Section number 7 Page 30

Galloway-Speedway Historic District
Memphis, Shelby County, Tennessee

columns, a closed brick railing, concrete floor and a tongue and groove ceiling. Two entrances are located on the main façade. The main entrance has an original three-light glass and wood door with original four-light and single wood panel sidelights. The secondary entrance on the main façade has double, fifteen-light glass and wood doors. Windows are Craftsman style, one-over-one double hung wood sash. Brackets are located in the gable fields. Under the windows flanking the chimney are projecting wood and stone flowerbox holders. The raised monitor roof section has a weatherboard and stucco exterior.

102. 940 Forrest Avenue ca. 1920 SY-5282 CB

This is a frame, one-story Bungalow built ca. 1920. The dwelling has an exterior of stucco, a continuous concrete block foundation, a jerkinhead roof of asphalt shingles and exposed scroll design roof rafters, one concrete block interior end and one interior brick chimneys. The hipped roof porch has exposed roof rafters, stuccoed columns with capitals and a closed stucco railing. The main entrance has an original single-light glass and wood door with an original, large single-light transom. Windows are original one-over-one double hung wood sash. Knee brace brackets and paired, Craftsman style one-over-one double hung wood sash attic windows are located in the gable field.

(Garage, ca. 1930, CB) Located to the rear of the dwelling is a ca. 1930, one-open bay, frame garage with an asphalt shingled roof and an exterior of aluminum siding.

103. 941 Forrest Avenue ca. 1924 SY-5283 CB

This is a frame, one-story Bungalow built ca. 1924. The dwelling has an exterior of brick veneer, a front gable roof of asphalt shingles with exposed roof rafters, one interior brick and one exterior end brick chimneys. The gable roof porch extends out to a porte-cochere and has exposed roof rafters, battered brick columns and a closed brick railing. A six-light fixed window is located in the gable field. The main entrance has an original, double, six-light glass and wood doors. Windows are original Craftsman style, one-over-one double hung wood sash.

(Garage, ca. 1940, CB) Located to the rear of the dwelling is a ca. 1940, frame, single-bay garage with an asphalt shingled hipped roof, an exterior of weatherboard and plywood doors.

104. 944 Forrest Avenue ca. 1918 SY-5284 CB

Standing at 944 Forrest Avenue is a frame, one-story Bungalow built ca. 1918. The dwelling has a continuous stucco covered foundation, an exterior of brick veneer, one interior central brick chimney and a jerkinhead roof of asphalt shingles with exposed scroll design roof rafters. The hipped roof porch has exposed roof rafters, square brick columns and a closed brick railing. The main entrance has an original single-light glass and wood door. Windows are original Craftsman style, one-over-one double hung wood sash. Knee brace brackets and paired, two-over-two horizontal sash windows are located in the gable fields.

(Garage, ca. 1960, NCB) Located to the rear of the dwelling is a non-contributing, ca. 1960, concrete block garage.

105. 945 Forrest Avenue ca. 1927 SY-5285 CB

One- and one-half story, frame, Tudor Revival style influenced dwelling built ca. 1927. The dwelling has an asphalt-shingled gable roof, an exterior of brick veneer and two exterior end brick chimneys. The full-width, incised porch has a large gable over the entry, rough course stone columns, a closed stone railing and metal shed roof awnings. A fixed six-light glass and wood attic window is located in the porch's gable field. The main entrance retains its original arched, single-light glass and wood paneled door with a soldier brick arched surround with keystones. Windows are

United States Department of the Interior
National Park ServiceNational Register of Historic Places
Continuation SheetSection number 7 Page 31Galloway-Speedway Historic District
Memphis, Shelby County, Tennessee

original, Craftsman style, multi-diamond light, one-over-double hung wood sash windows with aluminum awnings on the side facades.

(Garage, ca. 1927, CB) Located to the rear of the dwelling is an original, frame garage with an exterior of brick veneer, an asphalt shingle gable roof, weatherboard in the gable fields and a four-light and twelve wood panel overhead track door. Attached to the garage is a side carport with a shed roof supported by square wood posts

106. 950 Forrest Avenue ca. 1918 SY-5286 CB

This is a frame, one- and one-half story Bungalow built ca. 1918. The dwelling has a continuous concrete foundation, an exterior of brick veneer (skirt wall) and stucco and a jerkinhead roof of asphalt shingles. The full-width, hipped roof porch extends out to a porte-cochere and has square, rusticated concrete columns, a closed brick railing, a shed roof aluminum awning and a set of paired nine-light glass and wood attic windows in the gable field. The main entrance has a ca. 1990 flush wood door with its original, large, eight-light transom, six-light and single wood panel sidelights and a metal security door. Windows are original one-over-one double hung wood sash. The main façade has two sets of paired, ten-light glass and wood casement windows. The east façade has three sets of paired, ten-light glass and wood casement windows. Knee brace brackets are located in the main rooflines gable fields. The interior of the dwelling retains some of the original wood floors and original rusticated concrete block mantles to match the porch columns.

107. 953 Forrest Avenue ca. 1930 SY-5287 CB

This is a frame, one-story Bungalow built ca. 1930. The dwelling has a continuous stucco covered foundation, an asphalt shingled hipped roof, an exterior of stucco and one interior stucco covered chimney. The full-width hipped and gable roof porch has tapered wood columns with a wood dentil design and plinths on stuccoed piers, a closed stuccoed railing and two, fixed single-light windows in the gable field. The main entrance has a ca. 1980, solid wood door with an original three-section, single-light transom, original single-light and single wood panel sidelights and a metal security door. Windows are replacement one-over-one and two-over-two double hung metal sash. A wood water table surrounds the dwelling. Located on the main façade roofline is a hipped roof dormer with two window openings with no glass. On the east façade is a protruding shed roof bay with one window.

108. 954 Forrest Avenue ca. 1925 SY-5288 CB

At this location is a frame, one- and one-half story Bungalow built ca. 1925 and drastically remodeled. The dwelling has an exterior of permastone siding, one interior concrete chimney and an asphalt shingle hipped roof. The full-width, incised side porch has wrought iron posts, wrought iron brackets and a concrete floor. Two entrances on the main façade have ca. 1970, diamond-light glass and wood doors with metal security doors and an aluminum awning over the entrance not within the incised porch. Windows are original eight-over-eight and six-over-six double hung wood sash with permastone sills and lintels with keystones. Located at the roofline are two, shed roof dormers with permastone siding, exposed roof rafters and window openings.

109. 957 Forrest Avenue ca. 1920 SY-5289 CB

This is a frame, one-story Bungalow built ca. 1920. The dwelling has a continuous concrete block foundation, an asphalt shingled jerkinhead roof, an exterior of stucco, one interior brick chimney, one concrete chimney with a metal cap and one interior end brick and concrete flue. The full-width, hipped roof porch has a patio extension, exposed roof rafters, square stuccoed columns with capitals and a closed stuccoed railing. The main entrance has an original Craftsman style single-light glass and wood panel door with an original three-section, single-light transom, original

United States Department of the Interior
National Park ServiceNational Register of Historic Places
Continuation SheetSection number 7 Page 32Galloway-Speedway Historic District
Memphis, Shelby County, Tennessee

sidelights (boarded) and a metal security door. Windows are currently boarded over. A wood water table surrounds the house. On the east façade is a protruding, shed roof bay with three boarded up windows. The dwelling is currently vacant and for sale.

110. 958 Forrest Avenue ca. 1920 SY-5290 CB

The property at this location is a frame, one- and one-half story Bungalow built ca. 1920 and has undergone some modifications. The dwelling has a continuous concrete foundation, an exterior of stucco, a front gable (modified from a jerkinhead) roof of asphalt shingle and one interior brick chimney. The full-width, gable roof porch has an enclosed shed roof section (west end), one remaining square brick veneer column, an open brick railing and one attic vent in the gable field. The main entrance is not visible but it does retain a metal security door. Windows are mostly original, one-over-one double hung wood sash with some replacements and metal security bars. Located on the enclosed section of the porch is a picture window with four-over-four double hung wood sash windows flanking a sixteen-light fixed glass and wood window. A wood water table surrounds the dwelling and two, fixed single-light attic windows are located in the main façades gable field.

(Shed, ca. 1970, NCB)

111. 964 Forrest Avenue ca. 1920 SY-5291 CB

This is a one- and one-half story Bungalow built ca. 1920. The dwelling has a continuous stucco covered foundation, a jerkinhead roof of asphalt shingles, an exterior of stucco and one exterior end stucco chimney with a clay chimney cap. The full-width, gable and hipped roof porch has square stuccoed columns and a stuccoed stone closed railing. A diamond-shaped wood attic vent, stick work and stucco are located in the gable field of the porch. The main entrance has a ca. 1980, solid wood door. Windows are mostly original, six-over-six double hung wood sash with some replacement two-over-two horizontal light sash. Two wood beltcourses surround the dwelling. Two window openings, stick work and stucco are located in the gable on the main façade.

112. 965 Forrest Avenue ca. 1920 SY-5292 CB

At 965 Forrest Avenue stands a frame, one- and one-half story pyramid square plan dwelling with Bungalow influences built ca. 1920. The dwelling has a continuous brick foundation, an asphalt shingle hipped roof with exposed roof rafters, an exterior of stucco, two interior end stuccoed chimneys and one interior chimney with stucco and slightly protruding "arms". The full-width, incised porch has square, stuccoed columns with a dentil design on brick piers and large dentils in the frieze. The main entrance is not visible but it does retain an original three-section, single-light transom, original single-light and single wood panel sidelights which have been boarded over and a metal security door. Windows are original nine-over-one double hung wood sash with metal security bars. A wood water table surrounds the dwelling. Located at the roofline are two, hipped roof dormers with two, nine-light fixed glass and wood windows and exposed roof rafters.

113. 967 Forrest Avenue ca. 1920 SY-5293 CB

This is a frame, one-story Bungalow built ca. 1920. The dwelling has a continuous brick foundation, a jerkinhead roof of asphalt shingles with exposed milled roof rafters, one interior brick chimney and an exterior of blue stucco. The full-width, hipped roof porch has exposed milled roof rafters, battered brick columns and a closed brick railing. The door to the main entrance is not visible but it does retain a metal security door and an original five-light transom that has been painted in. Windows are original, nine-over-nine double hung wood sash with two, triple sets on the main

United States Department of the Interior
National Park ServiceNational Register of Historic Places
Continuation SheetSection number 7 Page 33Galloway-Speedway Historic District
Memphis, Shelby County, Tennessee

façade. A wood water table surrounds the dwelling. A protruding bay is sited on the east façade. Stucco, knee brace brackets and two, fixed, nine-light glass and wood windows are located in the main facades gable field.

114. 970 Forrest Avenue ca. 1922 SY-5294 CB

This is a one- and one-half story Bungalow built ca. 1922. The dwelling has a wired brick veneer exterior, an asphalt shingle side gable roof and one exterior end brick chimney. The full-width, shed roof porch is supported by battered brick columns and an open brick railing. The porch extends out to a porte-cochere that is supported by replacement square wood posts. The main entrance retains its original glass and wood door with a metal security door. Windows are original three-over-one-vertical light double hung wood sash with concrete sills. A soldier brick beltcourse and water table surround the dwelling. On the main facades roofline is a large gable roof dormer with knee brace brackets and three, original three-over-one vertical light double hung wood sash windows. A protruding shed roof bay extends out of the west façade with a triple set of windows.

115. 971 Forrest Avenue ca. 1920 SY-5295 CB

One- and one-half story, frame Bungalow built ca. 1920. The dwelling has an exterior of stucco above and brick veneer below the wood water table, a continuous concrete block foundation, an asphalt shingled hipped roof, one interior end and one interior concrete chimney. The full-width, hipped roof porch is supported by battered stone columns. The main entrance has an original nine-light and single wood panel door with an original three-section (two-light-three-light-two-light) transom and original six-light and single wood panel sidelights. Windows are mostly one-over-one double hung wood sash with some replacements on the east façade. The main and west façade have slender, four-over-one casement windows. A wood beltcourse surrounds the dwelling. Located at the roofline is a hipped roof dormer with two, three-light fixed windows and an exterior of rolled asphalt siding.

116. 974 Forrest Avenue ca. 1930 SY-5296 CB

This is a frame, one- and one-half story Bungalow built ca. 1930. The dwelling has a jerkinhead roof of asphalt shingles, an exterior of wired brick veneer and a continuous concrete foundation. The full-width, jerkinhead roof porch has a metal awning, square brick columns and a closed wired brick railing. Milled gable returns and stucco are located in the gable field of the porch. The main entrance is not visible but it does retain a metal security door. Windows are original three-over-one vertical light double hung wood sash with concrete lintels and sills and metal security bars. A soldier brick beltcourse and a protruding brick water table surround the dwelling. Located at the roofline are two eyebrow dormers with four-light fixed windows.

(Garage, ca. 1930, CB) Sited to the rear of the dwelling is a ca. 1930, frame garage with a jerkinhead roof of asphalt shingles, weatherboard siding, exposed roof rafters and two, vertical board sliding track doors.

117. 975 Forrest Avenue ca. 1920 SY-5297 CB

This is a frame, one- and one-half story Bungalow built ca. 1920. The dwelling has a continuous stucco covered foundation, an exterior of stucco and shiplap siding, a jerkinhead roof of asphalt shingles with exposed roof rafters and an interior brick chimney. The full-width, hipped roof porch has tapered wood columns on battered brick piers and an open brick railing. The main entrance has an original eight-light and wood panel door with a metal security door. Windows are original one-over-one double hung wood sash. A gable roof addition with shiplap siding has been added to the rear façade.

United States Department of the Interior
National Park ServiceNational Register of Historic Places
Continuation SheetSection number 7 Page 34Galloway-Speedway Historic District
Memphis, Shelby County, Tennessee**118. 980 Forrest Avenue ca. 1914 SY-5298 CB**

At 980 is a frame, one- and one-half story Bungalow built ca. 1914. The dwelling has an exterior of stone veneer, a side gable roof of asphalt shingles and one interior stone veneer chimney. The full-width shed roof porch has square stone columns and rounded concrete columns with decorative capitals and formed detailing on stone veneer piers with concrete plinths. The main entrance has a multi-light glass and wood door with an original single-light transom. Windows are original nine-over one double hung wood sash. A protruding hipped roof bay extends off a side facade with milled roof rafters and a triple set of windows. Located at the roofline is a shed a roof dormer with an exterior of stucco, exposed milled roof rafters and three, six-light fixed windows. Enclosed knee brace brackets are located in the gable fields.

119. 981 Forrest Avenue ca. 1920 SY-5299 CB

This is a frame, one- and one-half story Bungalow built ca. 1920. The dwelling has a continuous concrete block foundation, an exterior of stucco, a front gable roof of asphalt shingles and one interior concrete chimney. The full-width, incised porch is supported by double and triple wood columns. The main entrance has a replacement solid wood door but retains its original three-section (two-light-boarded-two-light) transom, original eight-light and single wood panel sidelights and a metal security door. Windows are original nine-over-one double hung wood sash. A wood water table surrounds the dwelling. On the west façade is a protruding bay with two windows. Stick work, stucco and two, fixed nine-light windows are located in the gable field of the main façade.

120. 984 Forrest Avenue ca. 1922 SY-5300 NCB

Located at 984 Forrest Avenue is a frame, one-story pyramid square plan dwelling built ca. 1922 and remodeled with Bungalow influences. The dwelling has a continuous stucco covered foundation, an exterior of aluminum and weatherboard siding, an interior brick chimney and an asphalt shingled hipped roof. The door in the main entrance is not visible it does retain an original three-section transom, original single-light and single wood panel sidelights and a metal security door. Windows are original six-over-one double hung wood sash. Located at the roofline are two shed roof dormers with exposed roof rafters, milled brackets and one, three-light fixed window. The east façade dormer has only one, single-light fixed window. Milled brackets are located in the gable fields.

(Shed, ca. 1920, CB)

121. 985 Forrest Avenue ca. 1940 SY-5301 CB

This is a frame, one- and one-half story Airplane Bungalow with two, raised monitor roof sections built ca. 1940. The dwelling has a continuous concrete block foundation, a jerkinhead roof of asphalt shingles, an exterior of brick veneer and stucco and one interior stucco covered chimney with two clay chimney caps. The full-width, hipped roof porch has a tile floor, a metal awning and has been enclosed with screening. A porte-cochere extends off the porch with an added carport extension. The main entrance has an original eight-light and three-wood panel door. Windows are original one-over-one double hung wood sash with metal security bars. A soldier brick beltcourse surrounds the dwelling. The two raised monitor roof sections have an exterior of stucco.

(Shed, ca. 1940, CB) Located to the rear of the dwelling is a ca. 1940, frame shed with an exterior of vinyl siding, a hipped roof, two-over-two horizontal light metal windows and a ca. 1970, diamond-light and wood door.

United States Department of the Interior
National Park Service

National Register of Historic Places Continuation Sheet

Section number 7 Page 35

Galloway-Speedway Historic District
Memphis, Shelby County, Tennessee

122. 990 Forrest Avenue ca. 1928 SY-5302 CB

This is a frame, one- and one-half story Bungalow built ca. 1928. The dwelling has an exterior of brick veneer, a cross gable roof of asphalt shingles and one exterior end brick chimney. The full-width, hipped roof porch has been enclosed with one-over-one double hung metal sash windows and solid brick railing. The main entrance has an original nine-light glass and wood door with a metal security door. Windows are original nine-over-one double hung wood sash. Synthetic siding and knee brace brackets are located in the gable fields along with paired, nine-light windows.

123. 991 Forrest Avenue ca. 1920 SY-5303 CB

One- and one-half story Bungalow built ca. 1920. The dwelling has a continuous concrete block foundation, an exterior of stucco, a cross gable roof of asphalt shingles with exposed roof rafters and one exterior end stucco covered chimney. The full-width, hipped roof porch has exposed roof rafters, stuccoed square columns and a closed stuccoed railing. The main entrance has a ca. 1990, wood panel door. Windows are original, Craftsman style, multi-light-over-one double hung wood sash. Located in the gable field of the main facades is a single-light attic window.

124. 994 Forrest Avenue ca. 1930 SY-5304 CB

This is a frame, one- and one-half story Airplane Bungalow with a rear hipped roof sleeper dormer built ca. 1930. The dwelling has an exterior of brick veneer, an asphalt shingled hipped roof with a front facing gable section and exposed roof rafters and one exterior end and one interior brick chimneys. The full-width, hipped roof porch has exposed roof rafters, square brick columns and a closed brick railing. The main entrance has an original, Craftsman style, nine-light glass and wood door with original, Craftsman style sidelights and an original three-vertical light transom, currently boarded. Windows are original, Craftsman style double hung sash. Located within the front facing gable section of the roof is a lunette attic window.

125. 995 Forrest Avenue ca. 1930 SY-5305 CB

This is a frame, one- and one-half story Airplane Bungalow with a raised hipped monitor roof section built ca. 1930. The dwelling has an exterior of rusticated stone veneer, a gable roof of asphalt shingle with exposed roof rafters, one interior stucco covered chimney and one interior rusticated stone veneer chimney. The full-width, hipped roof porch has exposed roof rafters, rusticated stone veneer battered columns and an open rusticated stone veneer railing. The main entrance has a ca. 1980, solid wood panel door with an original three-section, Craftsman style transom and original, Craftsman style, nine-light and wood panel sidelights.

(Garage, ca. 1930, CB) Located to the rear of the dwelling is a ca. 1930, frame garage with an asphalt shingled hipped roof, an exterior of weatherboard siding, exposed roof rafters and a pedestrian entrance. One of the garage bays has been enclosed with siding.

126. 1000 Forrest Avenue ca. 1967 SY-5306 NCB

This is a ca. 1967, brick veneer, Ranch style duplex. The duplex has a front gable roof of asphalt shingles and metal flues. Windows are two-over-two horizontal light double hung metal sash. The hipped roof porch is supported by metal posts.

United States Department of the Interior
National Park Service

National Register of Historic Places Continuation Sheet

Section number 7 Page 36

Galloway-Speedway Historic District
Memphis, Shelby County, Tennessee

127. 1001 Forrest Avenue ca. 1971 SY-5307 NCB

This is a frame, one-story Bungalow built ca. 1971. The dwelling has an exterior of asbestos shingle siding, a gable roof of asphalt shingles and a metal flue. The full-width, hipped roof porch is supported by square wood posts on stuccoed piers. The main entrance is not visible but it does retain a metal security door. Windows are ca. 1970, two-over-two horizontal light double hung metal sash. A wood vent is located in the gable field on the main facade.

128. 1004 Forrest Avenue ca. 1930 SY-5308 CB

This is a frame, one- and one-half story Bungalow built ca. 1930. The dwelling has an exterior of brick veneer, a jerkinhead roof of asphalt shingles and an interior brick chimney. The full-width, hipped roof porch has square brick columns, a closed brick railing and modillion blocks. The main entrance has an original single-light glass and wood door with an original ten-light transom, original single-light sidelights and a metal security door. Windows are original one-over-one double hung wood sash. Knee brace brackets and paired one-over-one double hung wood sash windows are located in the gable field on the main facade. Located at the roofline on the side façade is a shed roof dormer with exposed roof rafters.

129. 1005 Forrest Avenue ca. 1920 SY-5309 CB

The property at 1005 Forrest Avenue is a frame, one- and one-half story Airplane Bungalow with a raised gabled monitor roof sleeper section built ca. 1920. The dwelling has a side gable roof of asphalt shingles with exposed roof rafters, an interior brick chimney and an exterior of stucco. The full-width, incised porch has battered stone columns and closed stone railing. The main entrance has a single-light glass and wood door with an original three-light transom and original eight-light sidelights. Windows are Craftsman style, multi-light-over-one and one-over-one double hung wood sash. On the main facades roofline is an asphalt shingled gable roof dormer with three, single-light glass and wood windows. Knee brace brackets are located in the gable fields. On the rear façade is an original projecting gable roof wing on which the raised monitor roof section was built.

130. 1010 Forrest Avenue ca. 1928 SY-5310 CB

This is a frame, one-story Bungalow built ca. 1928. The dwelling has an exterior of brick veneer, an asphalt shingled gable roof, an interior and an exterior end brick chimney. The full-width, incised porch has square brick columns and an open brick railing. A gable roof section extends out to a porte-cochere supported by wrought iron posts. The main entrance has an original, Craftsman style, multi-light glass and wood door with an original three-light transom, original four-light sidelights and a metal security door. Windows are original six-over-one and one-over-one double hung wood sash. In the gable field of the porch are three, single-light fixed attic windows.

131. 1011 Forrest Avenue ca. 1913 SY-5311 CB

This is a frame, one-story Bungalow built ca. 1913. The dwelling has an exterior of wood shingles and a jerkinhead roof of asphalt shingles with exposed roof rafters. The wraparound porch has tapered wood columns on tapered stuccoed piers, a tongue and groove ceiling, a concrete floor and extends out into a patio on the east façade. The main entrance has an original three-vertical light glass and wood door with a tapered wood surround. The glass in the door has an upward arrow design. A secondary entrance on the east façade exiting onto the patio has a double nine-light glass and wood doors with an original six-light transom. Flanking the secondary entrance are Craftsman style windows and original metal and glass lamps with an etched glass circular globe. The rear entrance has an original nine-light glass and wood door. Windows are original Craftsman style, one-over-one double hung wood sash with tapered wood surrounds. Also located on the east façade is an original stained glass rectangular window. Located on

United States Department of the Interior
National Park Service

National Register of Historic Places Continuation Sheet

Section number 7 Page 37

Galloway-Speedway Historic District
Memphis, Shelby County, Tennessee

the main façade is a projecting jerkinhead bay with a seven-light rectangular attic window. Located in the gable field are paired, attic windows which house AC units. On the rear elevation is a large wall dormer.

(Garage, ca. 1930, CB) Sited to the rear of the dwelling is a ca. 1930, frame garage with an exterior of asbestos shingle siding, an asphalt shingled gable roof, paired hinged, vertical board wood doors, two-over-two horizontal light double hung metal sash windows and a ca. 1980, flush wood pedestrian entrance door.

132. 1022 Forrest Avenue ca. 1920 SY-5312 CB

This is a frame, one- and one-half story Bungalow built ca. 1920. The dwelling has an exterior of brick veneer, a continuous concrete foundation, a multi-gabled roof of asphalt shingles with large eaves and one exterior end brick chimney with a corbelled cap. The full-width, hipped roof porch has stone columns and a closed wired brick railing. The main entrance has an original glass and wood door with original eight-light and wood panel sidelights with metal security bars and a metal security door. Windows are original six-over-one double hung wood sash with metal security gratings. A header course brick beltcourse surrounds the dwelling. Stick work, stucco and two, six-light fixed windows and one window opening with no glass is located in the gable field on the main facade. On the west façade is a protruding bay with a triple set of windows and on the east façade is another protruding bay with four-over-one double hung wood sash with metal security bars.

133. 1023 Forrest Avenue ca. 1920 SY-5313 CB

One- and one-half Bungalow built ca. 1920. The dwelling has a continuous stucco covered foundation, an exterior brick veneer, a jerkinhead roof of asphalt shingles, one exterior end and one interior end brick chimneys. The full-width, jerkinhead and hipped roof porch has battered brick columns and a square wood railing for added support. The main entrance door is not visible but it does retain a metal security door. A secondary entrance has been resized and a window installed in its place. Windows are original one-over-one double hung wood sash. Stucco and three window openings-two, fixed single-light glass and wood and one, fixed six-light glass and wood are located in the gable fields. An original hipped roof wing has been added to the rear façade.

(Carport, ca. 1970, NCB)

134. 1026 Forrest Avenue ca. 1914 SY-5314 CB

This is a frame, one- and one-half story Bungalow built ca. 1914. The dwelling has a continuous brick foundation, an exterior of stucco and brick veneer, a hipped and gable roof of asphalt shingles and an interior concrete chimney. The full-width, hipped roof has two square brick columns and a closed brick railing. Half of the porch has been totally enclosed with vertical board siding and windows. The main entrance door is not visible but it does retain its original transom that is currently boarded, its original sidelights that have been shuttered and a metal security door. A secondary entrance has a two wood panel door with a metal security door. Windows are one-over-one double hung wood sash with metal security bars. A wood water table surrounds the dwelling. On the east façade is a small protruding bay with two windows. On the west façade is a protruding, gable roof bay with gable returns and two, one-over-one double hung wood sash windows and rectangular stained glass windows.

(Shed, ca. 1930, CB) Located to the rear of the dwelling is a frame shed with a gable roof, weatherboard siding, exposed roof rafters and a solid wood door.

United States Department of the Interior
National Park Service

National Register of Historic Places Continuation Sheet

Section number 7 Page 38

Galloway-Speedway Historic District
Memphis, Shelby County, Tennessee

135. 1027 Forrest Avenue ca. 1915 SY-5315 CB

At this location is a frame, one- and one-half story Bungalow built ca. 1915 and currently under restoration. The dwelling has a continuous stucco covered foundation, an exterior of wired brick veneer, a hipped and gable roof of asphalt shingles with exposed roof rafters, one exterior end concrete chimney and one interior end stucco covered chimney. The full-width, shed roof porch has exposed roof rafters, a concrete floor, rectangular stone columns and knee brace brackets at the eaves. The main entrance has a ca. 1990, solid wood door but it still retains its original transom and original six-light and single wood panel sidelights. Windows are Craftsman style, one-over-one double hung wood sash with multiple muntin bars. A patterned (three vertical, three horizontal) brick water table and soldier course brick beltcourse surround the dwelling. Knee brace brackets are located in the gable fields. On the west façade is a small protruding bay with a triple set of windows. Located on the roofline of the main façade is a gable roof dormer with exposed roof rafters and three, single-light double hung wood sash windows.

136. 1032 Forrest Avenue ca. 1916 SY-5316 CB

This is a frame, one- and one-half story Bungalow built ca. 1916. The dwelling has an exterior of stucco, an asphalt shingled jerkinhead roof with exposed roof rafters and a side gable bay, and one interior stucco covered chimney. The full-width, hipped roof porch has wrought iron posts on a closed stucco railing and exposed roof rafters. The main entrance door is not visible but it does retain its original transom and screen door. Windows are one-over-one double hung wood sash. Paired, six-light fixed attic windows are located in the gable field on the main facade.

(Garage/Shed, ca. 1930, CB) Located to the rear of the dwelling is a ca. 1930, frame, garage/shed with an asphalt shingled gable roof and weatherboard siding. The car bay of the garage has been enclosed and a four-light glass and wood door pedestrian entrance and a one-over-one double hung wood sash window have been added.

137. 1033 Forrest Avenue ca. 1916 SY-5317 CB

One- and one-half story Bungalow built ca. 1916. The dwelling has an exterior of stucco and weatherboard siding, a jerkinhead roof of asphalt shingles, one interior concrete chimney and one exterior end, stucco covered, cut-off chimney. The full-width, hipped roof porch is supported by square wood posts with capitals on brick piers. The main entrance has a single-light glass and wood door with a metal security door. Windows are one-over-one double hung wood sash with some replacements. On the west façade is a protruding, jerkinhead roof bay with two windows. A shed roof addition has been added to the rear façade. A wood water table surrounds the dwelling. Located in the gable field on the main façade are two, single-light fixed attic windows.

138. 1036 Forrest Avenue ca. 1916 SY-5318 CB

This is a frame, one- and one-half story Bungalow built ca. 1916. The dwelling has an exterior of stucco, a side gable roof of asphalt shingles and an interior central stucco covered chimney. The full-width, shed roof porch is supported by stucco covered battered columns. The main entrance has an original six-light glass and wood door with an original three-light transom and original nine-light sidelights. Windows are original one-over one double hung wood sash windows with some having metal shed roof awnings. Located at the roofline is a shed roof dormer with three, single-light windows. A rear façade porch has been enclosed with screen panels.

(Shed, ca. 1930, CB) Located to the rear of the dwelling is a ca. 1930, frame, two-open bay garage with a shed roof.

United States Department of the Interior
National Park Service

National Register of Historic Places Continuation Sheet

Section number 7 Page 39

Galloway-Speedway Historic District
Memphis, Shelby County, Tennessee

139. 1037 Forrest Avenue ca. 1922 SY-5319 CB

This is a frame, one-story Bungalow built ca. 1922. The dwelling has an exterior of altered stucco, a hipped roof of asphalt shingles with large eaves and a projecting gable on the side façade, one exterior end and one interior brick chimneys. The full-width, hipped roof porch is supported by square, tapered brick columns. The main entrance has a ca. 1990, panel wood door. Windows are some original one-over-one double hung wood sash and some replacement one-over-one double hung vinyl sash.

140. 1041 Forrest Avenue ca. 1920 SY-5320 CB

This is a frame, one- and one-half story Bungalow built ca. 1920. The dwelling has an exterior of brick veneer, a jerkinhead roof of asphalt shingles, a metal flue and an interior brick chimney. The partial-width, jerkinhead roof porch has a large frieze of aluminum siding, square brick columns and a closed brick railing. The main entrance has an eight-light glass and wood door with a metal security door. Windows are original six-over-one double hung wood sash. A six-light attic window is located in the gable field of the main façade and of the porch. A canvas awning carport supported by metal posts is situated off the side façade of the dwelling.

141. 1042 Forrest Avenue ca. 1922 SY-5321 CB

This is a frame, one- and one-half story Bungalow built ca. 1922. The dwelling has an exterior of brick veneer, a jerkinhead roof of asphalt shingles with wide eaves of tongue and groove and an interior brick chimney. The full-width, hipped roof porch is supported by battered rusticated stone columns. The main entrance has an original nine-light glass and wood door with an original four-light transom. Windows are original six-over-one double hung wood sash with rough cut concrete sills. In the gable field on the main facade are paired, three-over-one vertical light double hung wood sash windows.

142. 1046 Forrest Avenue ca. 1918 SY-5322 CB

Standing at 1046 Forrest Avenue is a frame, one- and one-half story Bungalow built ca. 1918. The dwelling has an exterior of stucco and weatherboard skirting, a hipped and gable roof of asphalt shingles with a projecting gable over the porch and one interior brick chimney. The full-width, incised porch has square brick columns, a closed brick railing and a metal awning. Two entrances are located on the main façade, both having ca. 1990, flush wood doors. Windows are one-over-one double hung wood sash with metal, shed roof awnings. Three, single-light windows are located in the gable field on the main façade. A gable bay is a located on the side façade.

(Shed, ca. 1960, NCB) Located to the rear of the dwelling is a non-contributing, ca. 1960, frame shed with a gable roof.

143. 1047 Forrest Avenue ca. 1916 SY-5323 CB

This is a frame, one- and one-half story Bungalow built ca. 1916. The dwelling has a continuous stucco covered foundation, a jerkinhead roof of asphalt shingles with exposed roof rafters, one interior concrete flue and one interior end brick chimney. The full-width, hipped roof porch has exposed roof rafters, battered brick columns and an open brick railing. The main entrance has a ca. 1970, single-light glass and wood door with an original seven-light transom, original ten-light sidelights and a metal security door. Windows are original one-over-one double hung wood sash with brick lintels and concrete sills. A header course brick beltcourse surrounds the dwelling. In the gable field on the main façade are wood shingles and three window openings, one of which has no glass and the other two have six-light fixed windows. A shed roof addition has been added to the rear façade with an exterior of aluminum siding.

United States Department of the Interior
National Park ServiceNational Register of Historic Places
Continuation SheetSection number 7 Page 40Galloway-Speedway Historic District
Memphis, Shelby County, Tennessee**144. 1052 Forrest Avenue ca. 1920 SY-5324 CB**

One- and one-half story Bungalow built ca. 1920. The dwelling has a continuous stucco covered foundation, a jerkinhead roof of asphalt shingles and one interior brick chimney with a metal cap. The full-width, shed roof porch has exposed roof rafters, square brick columns with an inserted concrete square design detail, a closed brick railing and a metal awning on the east façade. Two entrances are located on the main façade. One entrance has an original, multi-light glass and wood door and the other entrance has an original wide, single-light and wood panel door. Both entrances retain their original single-light transoms and metal security doors. Windows are original one-over-one double hung wood sash with concrete sills. A soldier brick beltcourse surrounds the dwelling. Fishscale shingles and two, three-over-three double hung wood sash windows are located in the gable fields.

(Shed, ca. 1990, NCB) Located to the rear of the dwelling is a non-contributing, ca. 1990, metal shed.

145. 1053 Forrest Avenue ca. 1916 SY-5325 CB

This is a frame, one- and one-half story Bungalow built ca. 1916. The dwelling has a continuous stucco covered foundation, a front gable roof of asphalt shingles, an exterior of brick veneer and one interior brick chimney. The full-width, hipped roof porch has battered columns with an open wood lattice railing. The main entrance has an original eight-light glass and wood door. Windows are original six-over-one double hung wood sash with concrete sills. A soldier course brick beltcourse surrounds the dwelling. Vinyl siding and one, replacement six-over-six double hung metal sash window is located in the main facades gable field.

(Garage, ca. 1930, CB) Located to the rear of the dwelling is a small, ca. 1930, two-bay, concrete block garage with a gable roof and an exterior of vinyl siding.

146. 1056 Forrest Avenue ca. 1920 SY-5326 CB

This is a frame, one- and one-half story Bungalow built ca. 1920. The dwelling has an exterior of brick veneer, two interior brick chimneys and a gable and hipped roof of asphalt shingles with milled brackets. The gable roof entry porch has modillion blocks, battered brick columns and closed brick railing. Asphalt shingle siding and five, single-light fixed windows are located in the porch's gable field. The main entrance has an original multi-light glass and wood door with an original four-light transom and a metal security door. Windows are original six-over-one double hung wood sash with concrete sills and some soldier brick surrounds. A soldier brick beltcourse and a concrete water table surround the dwelling. A shed roof addition is located on the rear façade with weatherboard siding. On the west façade roofline is a hipped roof dormer with three, four-light fixed windows and modillion blocks.

147. 1057 Forrest Avenue ca. 1914 SY-5327 CB

Located at 1057 Forrest Avenue is a frame, one-story Bungalow built ca. 1914. The dwelling has a continuous stucco covered foundation, an exterior of brick veneer, an asphalt shingled, gable and hipped roof with exposed milled roof rafters and two interior concrete chimneys. The gable roof porch has exposed milled roof rafters and square brick columns. The main entrance has an original eight-light glass and wood panel door with a metal security door. A soldier course brick beltcourse surrounds the dwelling. Located in both the gable field of the porch and the main façade are asphalt shingles and a triangular, wood lattice attic vents.

United States Department of the Interior
National Park ServiceNational Register of Historic Places
Continuation SheetSection number 7 Page 41Galloway-Speedway Historic District
Memphis, Shelby County, Tennessee**148. 1060 Forrest Avenue ca. 1918 SY-5328 CB**

This is a frame, one-story Bungalow built ca. 1918. The dwelling has an exterior of weatherboard siding, a jerkinhead roof of asphalt shingles with exposed scalloped design roof rafters and two interior stucco covered chimneys. The partial-width, hipped roof porch has exposed roof rafters and Tuscan columns on rough-cut, concrete block piers. The main entrance has a six-light glass and wood door with an original three-light transom and a storm door. Windows are original one-over-one double hung wood sash with metal security bars. Located in the main facades gable field are paired, four-light attic windows.

149. 1063 Forrest Avenue ca. 1922 SY-5329 CB

This is a frame, one-story Bungalow built ca. 1922. The dwelling has a clipped cross gable roof of asphalt shingles and one interior and one interior end brick chimneys. The full-width, hipped and gable roof has knee brace brackets, rusticated stone battered columns, an open wood railing and a rectangular, four-light fixed window in the gable field. Two entrances are located on the main façade. One entrance has an original, eight-light glass and wood door and the other entrance has an original four-vertical light door with a metal security door. Windows are original six-over-one double hung wood sash. Paired, single-light attic windows are located in the gable field on the main façade.

150. 1064 Forrest Avenue ca. 1918 SY-5330 CB

This is a frame, one-story Bungalow built ca. 1918. The dwelling has an exterior of weatherboard siding, an asphalt shingled hipped roof with modillion blocks and two interior concrete chimneys. The partial-width, shed roof porch has paired modillion blocks and Doric fluted columns on small, short, concrete piers. The main entrance has an original eight-light glass and wood door with an original three-light transom and a storm door. Windows are original one-over-one double hung wood sash with metal security bars. Located on the main facades roofline is a hipped roof dormer with modillion blocks and two, four-light fixed windows.

(Garage, ca. 1930, CB) Located to the rear of the dwelling is a ca. 1930, frame, one-bay garage with a gable roof of asphalt shingles, an exterior of shiplap siding and a ca. 1990, metal panel overhead track door.

151. 1067 Forrest Avenue ca. 1922 SY-5331 CB

The property at this location is a frame, one-story Bungalow built ca. 1922. The dwelling has an exterior of brick veneer, a cross gable roof of asphalt shingles with some exposed milled roof rafters and one interior end and one interior brick chimneys. The full-width, hipped and gable roof porch has some exposed milled roof rafters, knee brace brackets, rusticated concrete battered columns, an open wood railing and a small, rectangular, four-light fixed window in the gable field. Two entrances are located on the main façade. One entrance has a six-light glass and wood door and the other has an eight-light glass and wood door. Windows are original six-over-one double hung wood sash. Knee brace brackets are located in the gable fields along with paired square attic vents.

152. 1068 Forrest Avenue ca. 1922 SY-5332 CB

This is a frame, one- and one-half story Bungalow built ca. 1922. The dwelling has an exterior of brick veneer, a hipped roof of asphalt shingles and two interior brick chimneys. The gable roof porch has brackets in the eaves, battered brick columns and paired, six-light fixed attic windows in the gable field. The porch has been enclosed with vertical wood panels and jalousie windows. The main entrance has an original eight-light glass and wood panel door with a metal shed roof awning. Windows are original, six-over-one double hung wood sash. Located on the side facades are hipped roof dormers with two, single-light windows.

United States Department of the Interior
National Park Service

National Register of Historic Places Continuation Sheet

Section number 7 Page 42

Galloway-Speedway Historic District
Memphis, Shelby County, Tennessee

153. 1073 Forrest Avenue ca. 1922 SY-5333 CB

This is a frame, one- and one-half story Airplane Bungalow with a raised gabled monitor roof section built ca. 1922. The dwelling has an exterior of brick veneer, an exterior end brick chimney and a hipped roof of asphalt shingles. The full-width, hipped and gable roof porch has square brick columns, a closed brick railing and paired, three-vertical light attic windows in the gable field. The porch has been enclosed with screen panels. Two entrances are located on the main façade. One entrance has double, fifteen-light glass and wood doors and the other entrance has a single, fifteen-light glass and wood door. Windows are original three-over-one double hung wood sash. On the main façade is a gable roof dormer with a round, stenciled wood attic vent and three, three-vertical light fixed windows. An eyebrow dormer with a vent is located in the roofline of the raised gabled monitor roof section.

154. 1074 Forrest Avenue ca. 1922 SY-5334 CB

At 1074 Forrest Avenue is a frame, one- and one-half story Bungalow built ca. 1922. The dwelling has an exterior of brick veneer, a hipped roof of asphalt shingles with wide eaves of tongue and groove and an interior brick chimney. The partial-width, gable roof porch has square brick columns, a closed brick railing and paired, single-light attic windows in the gable field. Both entrances on the main façade have original nine-light glass and wood doors with original three-light transoms and storm doors. Windows are original one-over-one double hung wood sash with metal security bars and concrete sills. On the main façade roofline is a hipped roof dormer with two, single-light windows.

(Garage, ca. 1930, CB) Located to the rear of the dwelling is an original, open-bay, frame garage with a gable roof of asphalt shingles and weatherboard siding.

155. 1077 Forrest Avenue ca. 1922 SY-5335 CB

This is a frame, one-story, Airplane Bungalow built ca. 1922. The dwelling has an exterior of brick veneer, a jerkinhead roof of asphalt shingles and an exterior end brick chimney. The full-width, jerkinhead and hipped roof extends out to a porte-cochere and is supported by square brick columns and an open brick railing. A three-vertical light fixed attic window is located in the gable field of the porch. The main entrance has a ca. 1990 flush wood door and a metal security door. A side entrance retains its original three-vertical light glass and wood door with an original arched wood canopy over the entrance. Windows are original three-over vertical light double hung wood sash with metal security bars and metal awnings.

156. 1078 Forrest Avenue ca. 1922 SY-5336 CB

This is a frame, one-story Bungalow built ca. 1922. The dwelling has an exterior of brick veneer, an asphalt shingled jerkinhead roof and an interior brick chimney. The partial-width, gable roof porch is supported by rusticated concrete battered columns and have paired, six-light fixed attic windows in the gable field. Two entrances are located on the main façade. One entrance has an original eight-light glass and wood door and the other has a six-light glass and wood door. Both entrances retain their original single-light transoms but they have been blocked in. Windows are original one-over-one double hung wood sash with concrete sills and metal security bars. Vinyl siding and vinyl soffits are located in the gable fields and in the eaves.

(Shed, ca. 1980, NCB) Located to the rear of the dwelling is a non-contributing, ca. 1980, frame shed with a hipped roof.

United States Department of the Interior
National Park Service

National Register of Historic Places Continuation Sheet

Section number 7 Page 43

Galloway-Speedway Historic District
Memphis, Shelby County, Tennessee

157. 1084 Forrest Avenue ca. 1922 SY-5337 CB

At 1084 Forrest Avenue stands a frame, one-story Bungalow built ca. 1922. The dwelling has an exterior of brick veneer, a jerkinhead roof of asphalt shingles and an interior end brick chimney. The full-width, jerkinhead roof porch has a jerkinhead bay on the main façade and extends out to a porte-cochere. The porch has exposed roof rafters, rusticated concrete battered columns, an open railing and a single-light fixed attic window in the gable field. The main entrance has an original eight-light glass and wood panel door with original four-light and single wood panel sidelights. Windows are original one-over one-double hung wood sash. Two attic window openings, which have been covered with vinyl, are located in the gable field on the main façade.

(Garage/Shed, ca. 1960, NCB) Located to the rear of the dwelling is a non-contributing, ca. 1960, concrete block garage/shed.

158. 1085 Forrest Avenue ca. 1922 SY-5338 CB

This is a frame, one-story Bungalow built ca. 1922. The dwelling has an exterior of brick veneer, a gable and hipped roof of asphalt shingles and exposed roof ratters and an interior brick chimney with a metal cap. The full-width, hipped and gable roof porch has exposed roof rafters, square brick columns, a closed brick railing and a four-light attic window in the gable field. The main entrance retains its original eight-light glass and wood door with a storm door. Windows are original one-over-one double hung wood sash with metal security bars. A fixed, four-light attic window is located in the gable field on the main façade. An original shed roof wing, possibly an enclosed porch, is located on the rear façade and has an exterior of shiplap siding and a nine-light fixed windows. Vinyl siding has been installed over the eaves.

159. 1088 Forrest Avenue ca. 1922 SY-5339 CB

This is a frame, one- and one-half story Bungalow built ca. 1922. The dwelling has an exterior of brick veneer, a jerkinhead roof of asphalt shingles, an interior brick chimney and a metal flue. The full-width, hipped roof porch has a vinyl-sided frieze, square brick columns and closed brick railing. Both entrances on the main façade have double, fifteen-light glass and wood doors with original six-light transoms. Windows are original six-over-one double hung wood sash with concrete sills. Paired, six-light attic windows are located in the gable field on the main façade.

(Garage, ca. 1940, CB) Located to the rear of the dwelling is a ca. 1940, frame garage with an asphalt shingled gable roof, an exterior of shiplap siding, double hinged shiplap doors and a shiplap pedestrian door.

160. 1089 Forrest Avenue ca. 1922 SY-5340 CB

One- and one-half story Bungalow built ca. 1922. The dwelling has a continuous stucco covered foundation, a jerkinhead roof of asphalt shingles, an exterior of brick veneer, two metal flues and an interior end brick chimney. The full-width, hipped and gable roof porch has knee brace brackets, exposed milled roof rafters, square brick columns and stucco and a four-light fixed rectangular attic window in the gable field. The main entrance has a ca. 1970, three-rectangular light, diagonally spaced glass and wood door with a storm door. Windows are original six-over-one double hung wood sash with concrete sills and metal awnings on the west façade. A soldier brick water table surrounds the dwelling. Two, four-light fixed windows, vertical board siding and knee brace brackets are located in the gable field on the main façade.

United States Department of the Interior
National Park Service

National Register of Historic Places Continuation Sheet

Section number 7 Page 44

Galloway-Speedway Historic District
Memphis, Shelby County, Tennessee

161. 1094 Forrest Avenue ca. 1922 SY-5341 CB

Located on the property at 1094 Forrest Avenue is a frame, one- and one-half story Bungalow built ca. 1922. The dwelling has a continuous stucco covered foundation, an exterior of multi-colored, wired brick veneer, a jerkinhead roof of asphalt shingles and an interior end brick chimney. The full-width, hipped roof porch extends out to a porte-cochere with some swags on the east and west facades. The porch has square brick columns and has been enclosed with two sets of four, fifteen light fixed glass and wood windows on the main (S) façade and an open brick railing which has been enclosed with glass panels. The main entrance has an original wide, nine-light glass and wood door with and original four-light transom. The porch door is a single-light glass and vertical board Dutch door with flanking fixed windows. Windows are original six-over-one double hung wood sash with metal security bars. A soldier course beltcourse and a header course brick water table surround the house. Two, single-light fixed windows, stucco and attic vents are located in the gable fields.

(Garage, ca. 1920, CB) Located to the rear of the dwelling is a ca. 1920, frame, one-bay garage with a gable roof, rolled asphalt faux brick siding and double hinged vertical board doors.

162. 1095 Forrest Avenue ca. 1922 SY-5342 CB

This is a frame, one- and one-half story Bungalow built ca. 1922. The dwelling has an exterior of brick veneer, a continuous stucco covered foundation, a gable roof of asphalt shingles and an interior brick chimney. The full-width, hipped roof porch extends out to a porte-cochere with square brick columns, square brick piers with concrete plinths and a closed brick railing. The main entrance retains its original eight-light glass and wood panel door with its original four-light glass and wood panel sidelights. Windows are original one-over-one double hung wood sash with concrete sills and metal security bars. A soldier course beltcourse and water table surround the dwelling. Green asphalt shingle siding and a single-light fixed window are located in the main facades gable field. An original wing was attached to the rear façade with vertical board siding.

163. 1098 Forrest Avenue ca. 1926 SY-5343 CB

One- and one-half story Airplane Bungalow with a full two-story rear section built ca. 1926. The dwelling has an exterior of wired brick veneer, a concrete block foundation with diamond pattern concrete foundation vents, a multi-gabled roof of asphalt shingles and two exterior end chimney with the one located on the west façade having a battered brick and concrete design. The full-width, double gable roof porch extends out to a porte-cochere with exposed roof rafters, battered stone columns, a closed stone railing and a tile floor. A three-light fixed rectangular window is located in the gable field of each porch gable. The main entrance has been totally boarded so no entrance detail is visible. Windows are probably three-over-one vertical light double hung wood sash with concrete sills but most on the 1st floor have been boarded. A wired brick soldier course beltcourse and concrete water table surround the dwelling. Wood slats and a triangular attic vent are located in the gable field. An original, two-story sleeper section with three-over-one vertical light windows is located on the rear façade. Attached to the rear façade of the two-story section is an original one-story rear wing. The dwelling is currently vacant and for sale.

164. 1099 Forrest Avenue ca. 1920 SY-5344 CB

This is a frame, one- and one-half story Bungalow built ca. 1920. The dwelling has a continuous stucco covered foundation, an exterior of brick veneer, a jerkinhead roof of asphalt shingles, one interior end and one interior brick chimney. The full-width, hipped roof porch has square brick columns and a closed brick railing with arched brick and concrete design drains. The main entrance has original double ten-light glass and wood doors with an original five-light transom. A secondary entrance on the east façade has a double gable roof porch with square brick columns, a

United States Department of the Interior
National Park Service

National Register of Historic Places Continuation Sheet

Section number 7 Page 45

Galloway-Speedway Historic District
Memphis, Shelby County, Tennessee

closed brick railing and double ca. 1980, six panel wood doors with an original five-light transom. Windows are original, Craftsman style, six-over-one double hung wood sash with concrete sills and metal security bars. A soldier course brick water table and beltcourse surrounds the dwelling. Knee brace brackets are located in the gable fields.

165. 1111-13 Forrest Avenue ca. 1928 SY-5346 CB

Located at 1111-13 is a frame, one- and one-half story Airplane Bungalow style duplex with a raised hipped monitor roof section built ca. 1928. The dwelling has an exterior of brick veneer, a gable and hipped roof of asphalt shingles and an interior brick chimney. The two gable entry porches have battered brick columns, an open brick railing and stucco in the gable field. A diamond light attic vent was originally in the gable fields but has been filled in with stucco. Both entrances have ca. 1980, solid wood doors and original screen doors. Windows are original one-over-one double hung wood sash. A soldier course water table and beltcourse surrounds the dwelling. The raised hipped monitor roof section has one-over-one double hung metal sash windows. On both the east and west facades are protruding hipped roof bays with a triple set of one-over-one double hung wood sash windows. A small addition has been added to the rear façade with an exterior of aluminum siding. Stucco and two, single-light fixed are located in the gable fields of the main roofline.

166. 1112 Forrest Avenue ca. 1915 SY-5345 CB

At 112 Forrest Avenue stands a frame, two-story American Foursquare style dwelling built ca. 1915 and currently used as the St. Jude Christian Spiritual Church Mission House. The dwelling has an exterior of weatherboard siding, a hipped roof of asphalt shingles, two exterior end brick chimneys and metal flues. The wraparound, flat roof porch is supported by rusticated Tuscan columns detailed with three rusticated pronounced rings on rusticated concrete block piers. The original main entrance on the south façade has been boarded up but it still retains its original three-section transom (painted in) and original sidelights (boarded). A side entrance on the west façade has a ca. 1970, three-rectangular light diagonally- spaced glass and wood door with a metal awning. Another secondary entrance on the main façade has a ca. 1980, solid wood door. The entrance on the east façade has a single light glass and wood door with the glass portion and the original sidelights boarded over. Windows are original one-over-one double hung wood sash with some replacement two-over-two horizontal light double hung metal sash and one large single-light fixed window added on the main (S) facade. Two shed roof dormers each with two attic vents are located at the roofline. A two-story wing was added to the rear façade along with a two-story wrought iron porch and exterior staircase.

167. 1116 Forrest Avenue ca. 1920 SY-5347 CB

Located directly adjacent and to the rear of 1112 Forrest Avenue is a rectangular plan, small, Traditional style dwelling built ca. 1920 and now used at the St Jude Christian Spiritual Church. The building has an exterior of weatherboard, a stone foundation, an exterior end brick chimney and a side gable roof of asphalt shingles and exposed roof rafters. The main entrance has a gabled canopy supported by knee brace brackets and a solid wood door. Windows are a conglomeration of two-over-one, one-over-one double hung wood sash, four-light fixed glass and wood windows and windows that have been resized to rectangular slats.

United States Department of the Interior
National Park Service

National Register of Historic Places Continuation Sheet

Section number 7 Page 46

Galloway-Speedway Historic District
Memphis, Shelby County, Tennessee

GALLOWAY AVENUE

168. 914 Galloway Avenue ca. 1921 SY-5348 CB

Located at 914 Galloway Avenue is a frame, one and one-half story Bungalow built ca. 1921. The dwelling has an asphalt shingle, gable roof, an exterior of stucco with a wood beltcourse and an interior end, brick chimney. The full-width, shed roof porch has wrought iron columns on replacement concrete piers. The main entrance has a ca. 1960, three-light, glass and wood door. Windows are one-over-one double hung wood sash with several being boarded over. Flanking the chimney are twelve-light glass and wood Craftsman windows. Located on the main façade is a shed roof dormer with paired three-light windows. Knee brace brackets are located at the eaves.

169. 915 Galloway Avenue ca. 1921 SY-5349 CB

This is a frame, one and one-half story Bungalow built ca. 1921. The dwelling has a continuous brick foundation, weatherboard siding, an asphalt shingle hipped roof and a central brick chimney. The full-width, jerkinhead roof porch has wrought iron columns and railing and paired, single-light windows in the gable field. The entrance and windows have been boarded. Exposed roof rafters are located at the eaves and knee brace brackets are located in the gable fields.

170. 920 Galloway Avenue ca. 1925 SY-5350 CB

This is a frame, one-story, Bungalow built ca. 1925. The dwelling has a continuous concrete foundation, brick veneer siding, an asphalt shingle front gable roof and an interior brick chimney. The gable roof entry porch has brick columns with a triple vertical diamond tile or concrete design and a closed brick railing. The main entrance has a replacement multi-light glass and wood door and a security door. Windows are original one-over-one double hung wood sash with concrete sills and metal security bars. Stucco and two vent openings are located in the gable fields. A later addition has been added to the rear façade of the house and has board and batten siding.

(Shed, ca. 1960, NCB) Located to the rear of the building is a ca. 1960 non-contributing shed.

171. 921 Galloway Avenue ca. 1921 SY-5351 CB

The property at 921 Galloway Avenue is a frame, one-story, Bungalow built ca. 1921. The dwelling has a continuous concrete foundation, an exterior of vinyl siding, an asphalt shingle jerkinhead roof and one exterior end brick chimney and one interior concrete chimney, both with chimney caps. The full-width, jerkinhead and hipped roof porch has replacement wrought iron columns and a concrete floor. Gable returns are located in the gable fields. The main entrance has an original Craftsman style, three-light glass and wood door. Windows are original one-over-one double hung wood sash with metal security bars. A fixed, single light window is located in the front gable field. A small, later addition has been added to the rear façade.

(Shed, ca. 1920, CB) Located to the rear of the dwelling is a contributing, ca. 1920, gable roof shed with weatherboard siding.

172. 924 Galloway Avenue ca. 1935 SY-5352 CB

One and one-half story Airplane Bungalow with a raised monitor roof section built ca. 1935. The dwelling has a continuous concrete foundation, an exterior of brick veneer, an asphalt shingled multiple gable roof and one interior end brick chimney with a chimney cap. The partial-width, gable roof entry porch has brick columns with swags and a closed brick railing. A wood stenciled, diamond shaped attic vent is located in the gable field of the porch. The main

United States Department of the Interior
National Park Service

National Register of Historic Places Continuation Sheet

Section number 7 Page 47

Galloway-Speedway Historic District
Memphis, Shelby County, Tennessee

entrance has a metal security door that hides the main door but the original four light transom is still visible. Windows are original six-over-one double hung wood sash with metal security bars. A soldier brick water table is surrounds the dwelling, as well as, a soldier brick beltcourse. A protruding gable roof bay is located on the east façade with a diamond shaped stenciled wood attic vent in the gable field.

(Shed, ca. 1970, NCB) Located to the rear of the dwelling is a non-contributing, ca. 1970, shed.

173. 925 Galloway Avenue ca. 1921 SY-5353 CB

This is a frame, one-story, Bungalow built ca. 1921. The dwelling has a continuous brick foundation, an exterior of asbestos shingle siding, an asphalt shingle jerkinhead roof and one exterior end and one interior brick chimneys. The jerkinhead and hipped roof, full-width porch has wrought iron columns. The main entrance has an original eight-light glass and wood panel door. Windows are original one-over-one double hung wood sash with metal security bars. A fixed, single-light window is located in the gable field on both the porch and the main roofline.

(Playhouse, ca. 1920, CB) Located to the rear of the dwelling is a contributing, original jerkinhead and hipped roof playhouse with weatherboard siding and original double, multi-glass and wood doors.

174. 930 Galloway Avenue ca. 1920 SY-5354 CB

This is a frame, one-story, Bungalow built ca. 1920. The dwelling has a continuous concrete foundation, an exterior of wired brick veneer, an asphalt shingle jerkinhead roof and one interior brick and one cut-off, exterior end brick chimney with a brick pattern detailing. The full-width, jerkinhead and hipped roof porch has brick columns with diamond tile detailing and a closed brick railing. The main entrance has an original multi-light glass and wood door with original ten-light and wood panel sidelights, a metal security door and surrounded by a patterned brick door lintel. Windows are original one-over-one double hung wood sash with diamond tile detailing in the surrounds. Stucco is located in the gable fields. A pattered brick beltcourse and water table surround the house. Two, single-light fixed windows are located in the front façade gable field.

175. 931 Galloway Avenue ca. 1920 SY-5355 CB

Standing at 931 Galloway Avenue is a one-story, frame, Bungalow built ca. 1920. The dwelling has a permastone covered foundation, an exterior of permastone siding, an asphalt shingle jerkinhead roof, one exterior end brick chimney and one interior brick flue with a chimney cap. The full-with, jerkinhead and hipped roof porch has battered brick columns, one brick pier and an open metal railing. Exposed roof rafters are located at the eaves of the porch. The main entrance has an eight-light glass and wood panel door with an original permastone keystone and a metal security door. Windows are original one-over-one double hung wood sash with permastone and keystone lintels. Single-light fixed windows are located in the gable fields.

(Garage, ca. 1940, CB) Located to the rear of the dwelling is a contributing, ca. 1940, hipped roof garage with sliding track vertical board doors.

176. 934 Galloway Avenue ca. 1913 SY-5356 CB

This is a one-story, frame, Bungalow built ca. 1913. The dwelling has a continuous concrete foundation, an exterior of wired brick veneer, an asphalt shingle multi-gabled roof and one interior concrete chimney with three clay chimney caps. The full-width, hipped and gable roof porch has brick columns and a closed brick and stucco railing. The main entrance door is unknown and the original transom and sidelights have been boarded over. Windows are original one-

United States Department of the Interior
National Park ServiceNational Register of Historic Places
Continuation SheetSection number 7 Page 48Galloway-Speedway Historic District
Memphis, Shelby County, Tennessee

over-one double hung wood sash with some windows having been replaced. A patterned brick water table surrounds the house. Two attic vent openings are located in the main facades gable field. A later gable roof addition has been added to the rear of the house. A wood carport has been built to the side of the house and is supported by metal posts.

(Shed, ca. 1967, NCB) Located to the off the rear of the carport is an added non-contributing shed.

177. 935 Galloway Avenue ca. 1922 SY-5357 CB

One- and one-half story, frame, Airplane Bungalow with a raised monitor roof section built ca. 1922. The dwelling has a continuous concrete foundation, an exterior of brick veneer, an asphalt shingle gable roof and an interior brick chimney. The full-width, gable roof porch has brick columns and a closed brick railing. The porch roof has exposed roof rafters. The main entrance has an original eight-light glass and wood door with an original four-light transom and a metal security door. Windows are original six-over-one double hung wood sash. Exposed roof rafters are located at the eaves of the raised monitor roof section.

178. 940 Galloway Avenue ca. 1920 SY-5358 CB

This is a frame, one- and one-half story, Bungalow built ca. 1920. The dwelling has continuous concrete block foundation, an exterior of stucco, an asphalt shingle jerkinhead roof with exposed roof rafters, a metal flue and an interior concrete chimney. The full-width porch has double and triple square wood posts on brick piers. The main entrance has an original six-light glass and wood panel door with an original three section, six-light transom and original eight light and wood panel sidelights. A secondary entrance also on the main façade has an original, fifteen-light glass and wood door with a rectangular transom that has been boarded. Windows are original one-over-one double hung wood sash. A ca. 1970, shed roof addition has been added to the rear façade.

179. 941 Galloway Avenue ca. 1922 SY-5359 CB

This is a frame, one-story Bungalow built ca. 1922. The dwelling has a continuous brick foundation, an exterior of vinyl siding, an asphalt shingle front gable roof and an interior central brick chimney. The full-width, gable and hipped roof porch has ca. 1980 wrought iron columns and railing. The main entrance has a replaced ca. 1980 glass and wood door with a metal security door but still retains the original sidelights that have been covered with metal security bars. Windows are ca. 2000, one-over-one double hung wood sash with metal security bars.

180. 945 Galloway Avenue ca. 1920 SY-5360 CB

At this location is a frame, one- and one-half story Bungalow built ca. 1920. The dwelling has an exterior of brick veneer, an asphalt shingle front gable roof and an interior brick chimney. The gable roof entry porch has brick columns and a closed brick railing. The main entrance has an original fifteen-light glass and wood door. Windows are original one-over-one double hung wood sash windows with a ca. 1980, large two-light picture window on the main façade. Vinyl soffits have been installed to cover the previously exposed roof rafters and paired, single-light, fixed windows are located in the gable fields.

181. 946 Galloway Avenue ca. 1920 SY-5361 CB

This is a frame, one-story Bungalow built ca. 1920. The dwelling has a continuous concrete block foundation, an exterior of brick veneer, an asphalt shingle hipped roof with exposed roof rafters and a metal flue. The full-width, gable and hipped roof porch has brick columns and a concrete floor. The main entrance has a ca. 1970 paneled wood door but retains the original three-light transom and one, nine-light sidelight. The other sidelight opening houses an air

United States Department of the Interior
National Park ServiceNational Register of Historic Places
Continuation SheetSection number 7 Page 49Galloway-Speedway Historic District
Memphis, Shelby County, Tennessee

conditioning unit. Windows are original one-over-one double hung wood sash. A multi-light attic window is located in the gable field of the porch.

182. 950 Galloway Avenue ca. 1920 SY-5362 CB

This is a frame, one- and one-half story Bungalow built ca. 1920. The dwelling has a continuous concrete block foundation, an exterior of brick veneer and stucco, an asphalt shingle hipped roof with exposed roof rafters and two interior brick chimneys (one with a stucco exterior). The gable roof entry porch has tapered wood columns on stone piers, and a wrought iron railing. A patio extends off the porch. Knee brace brackets and paired, three-light glass and wood attic windows are located in the gable field and exposed roof rafters are at the eaves. The main entrance has a ca. 1970 single-light vertical board door with a single-light rectangular transom. Metal awnings have been added to the porch and over the windows.

(Garage, ca. 1950, CB) Located to the rear of the dwelling is a contributing, ca. 1950 shed roof garage.

183. 951 Galloway Avenue ca. 1920 SY-5363 CB

Located at 951 Galloway Avenue is a frame, one- and one-half story Airplane Bungalow with a raised monitor roof section built ca. 1920. The dwelling has a stucco-covered foundation, an exterior of brick veneer, an asphalt shingle gable roof with exposed roof rafters and an interior end brick chimney. The gable and hipped roof porch has brick columns and a closed brick railing. The hipped roof section of the porch has been enclosed with ca. 1960, four-light metal casement windows with a central picture window. A diamond shaped attic vent is located in the gable field. The main entrance has a ca. 1990 flush wood door with a surround of small square structural glass blocks. Windows are original six-over-one double hung wood sash. A metal awning remains on one window. Flanking the chimney are six-light fixed glass and wood windows. The raised monitor roof section has small projecting shed roof bays with a single-light glass and wood fixed window.

(Garage, ca. 1960, NCB) Located to the rear of the dwelling is a non-contributing, ca. 1960 concrete block, two-open bay garage.

184. 954 Galloway Avenue ca. 1920 SY-5364 CB

This is a frame, one- and one-half story Bungalow built ca. 1920. The dwelling has a continuous concrete block foundation, an exterior of stucco, an asphalt shingle jerkinhead roof and an interior brick chimney. The full-width, hipped roof porch has tapered wood posts on brick piers. The main entrance has a boarded opening with an original single-light transom still visible. Windows are Craftsman one-over-one double hung wood sash. A set of paired Craftsman fixed twelve-light glass and wood windows are located in the gable field (one is boarded over). Knee brace brackets are located in the eaves.

185. 960 Galloway Avenue ca. 1920 SY-5366 CB

This is a frame, one-story Bungalow built ca. 1920. The dwelling has a continuous concrete block foundation, an exterior of stucco, an asphalt shingle jerkinhead roof and a metal flue. The full-width, hipped roof porch has tapered wood columns on brick piers with plinths, a poured concrete floor and a concrete block foundation. The main entrance has a replacement two-light glass and wood door with an original single-light transom. Windows are original Craftsman style one-over-one double hung wood sash with metal security bars. Two, six-over-six double hung metal sash replacement windows and vertical board are located in the main facades gable field. Knee brace brackets are

United States Department of the Interior
National Park ServiceNational Register of Historic Places
Continuation SheetSection number 7 Page 50Galloway-Speedway Historic District
Memphis, Shelby County, Tennessee

located at the eaves in the gable field. The porch columns have been detailed with a protruding wood strip and wood block on all sides and the top.

186. 961 Galloway Avenue ca. 1950 SY-5367 CB

At this location stands a frame, one- and one-half story, Colonial Revival influenced dwelling built ca. 1950. The dwelling has a continuous concrete foundation, an exterior of yellow brick veneer, an asphalt shingle side gable roof and an interior brick flue. The gable roof entry porch has square brick columns, a metal railing and a concrete floor. The main entrance has a solid wood panel door with a metal security door. Windows are original one-over-one double hung wood sash with brick sills and a brick header course lintel. A soldier brick beltcourse surrounds the dwelling. Aluminum siding and gable returns are located in the gable fields.

(Garage, ca. 1920, CB) Located to the rear of the dwelling is a contributing, ca. 1920, gable roof garage with hinged angled wood double doors and weatherboard siding.

187. 965 Galloway Avenue ca. 1921 SY-5368 CB

This is a frame, one- and one-half story Airplane Bungalow with a raised monitor roof section built ca. 1921. The dwelling has an exterior of brick veneer, an asphalt shingle jerkinhead roof and an exterior end brick chimney with a clay chimney cap. The jerkinhead entry porch has square brick columns with swaged brick flanks and concrete plinths. The main entrance has ca. 1970 diagonal three-diamond light glass and wood door with an original four-light transom and a metal security door. Windows are original six-over-one double hung wood sash. A soldier course water table surrounds the dwelling. The raised monitor roof section has two, triple set six-over-one double hung wood sash windows.

188. 966 Galloway Avenue ca. 1920 SY-5369 CB

One- and one-half story Bungalow built ca. 1920. The dwelling has an exterior of brick veneer and stucco, an asphalt shingle hipped roof, a stuccoed interior flue and a stuccoed interior chimney. The full-width, hipped roof porch has battered stone columns and a metal railing. The main façade has two entrances. One entrance has an unknown door but has a metal security door retains its original ten-light sidelights and original six-light transom which has been boarded. The other entrance also has an unknown door but has its original metal security door and an original three-light transom that has been boarded. Windows are original one-over-one double hung wood sash with security bars. A wood water table and beltcourse surround the dwelling. Located on the main façade is a hipped roof dormer with two attic vent openings.

(Garage, ca. 1940, CB) Located to the rear of the dwelling is a contributing, ca. 1940, front gable, one-bay garage with no door.

189. 970 Galloway Avenue ca. 1920 SY-5370 CB

This is a frame, one-story Bungalow built ca. 1920. The dwelling has a continuous concrete block foundation, an exterior of brick veneer and stucco, some replacement vertical board wood siding, an asphalt shingle gable roof with knee brace brackets and one concrete and one interior metal flue. The gable roof entry porch has tapered wood columns on brick piers, a closed brick railing and knee brace brackets in the gable field. A wood beltcourse surrounds the dwelling. The main entrance has an original single-light glass and wood panel door with an original single-light transom. Windows are original twelve-over-one double hung wood sash. Stucco and two, single-light fixed windows are located in the front facades gable field.

United States Department of the Interior
National Park Service

National Register of Historic Places Continuation Sheet

Section number 7 Page 51

Galloway-Speedway Historic District
Memphis, Shelby County, Tennessee

190. 971 Galloway Avenue ca. 1922 SY-5371 CB

This is a one- and one-half story, frame Airplane Bungalow with a raised monitor roof section built ca. 1922. The dwelling has a continuous stucco foundation, an exterior of brick veneer, an asphalt shingle gable roof and an interior end brick chimney. The full-width, hipped roof porch has square brick columns and a closed brick railing. The main entrance has a multi-light glass and wood door with an original four-light transom and a metal security door. Windows are original six-over-one double hung wood sash. Flanking the chimney are fixed six-light windows. Diamond shaped vents are located in the gable fields of the raised monitor roof section.

(Garage, ca. 1940, CB) Located to the rear of the dwelling is a contributing, ca. 1940 garage with an exterior of asbestos shingle siding, an asphalt shingle jerkinhead roof and a six-light and twenty-four wood panel overhead track door.

191. 974 Galloway Avenue ca. 1920 SY-5372 CB

At this location is a frame, one- and one-half story Bungalow built ca. 1920. The dwelling has a stucco covered foundation, an exterior of stucco and weatherboard, an asphalt shingle gable roof with exposed roof rafters and an interior central brick chimney covered with concrete. The full-width, incised porch has tapered brick columns. The main entrance has an original three-vertical light glass and wood door with a metal security door. Windows are original six-over-one double hung wood sash. Knee brace brackets are located in the gable fields along with paired four-light attic windows.

(Garage, ca. 1960, NCB) Located to the rear of the dwelling is a non-contributing, ca. 1960, two-bay, frame garage.

192. 975 Galloway Avenue ca. 1922 SY-5373 CB

This is a frame, one- and one-half story Bungalow built ca. 1922. The dwelling has a stucco exterior with a small amount of stick work, an asphalt shingle jerkinhead roof with exposed roof rafters, one exterior end brick chimney now covered with concrete and one interior end brick flue. The full-width, hipped roof porch has exposed roof rafters, battered brick columns and a concrete floor. The main entrance has its original fifteen-light glass and wood door with an original eight-light transom and original ten-light and wood panel sidelights. Windows are original one-over-one double hung wood sash with metal security bars. Three square metal vents are located in the gable field.

(Garage, ca. 1930, CB) Located to the rear of the dwelling is a contributing, ca. 1930, frame garage with an asphalt shingle gable roof, weatherboard siding, and no garage door.

193. 980 Galloway Avenue ca. 1920 SY-5374 CB

This is a frame, one-story Bungalow built ca. 1920. The dwelling has an exterior of brick veneer, an asphalt shingle jerkinhead roof with exposed roof rafters and a metal flue. The partial-width, jerkinhead roof porch has battered columns, exposed roof rafters and knee brace brackets. Located in the porch's gable field is a four-light fixed glass and wood attic window. The main entrance is not visible. Windows are original two-over-two double hung wood sash with metal security bars. Knee brace brackets are located in the main rooflines gable field.

(Shed, ca. 1980, NCB) Located to the rear of the dwelling is a non-contributing, ca. 1980, metal storage building.

United States Department of the Interior
National Park Service

National Register of Historic Places Continuation Sheet

Section number 7 Page 52

Galloway-Speedway Historic District
Memphis, Shelby County, Tennessee

194. 981 Galloway Avenue ca. 1920 SY-5375 CB

This is a frame, one-story Bungalow built ca. 1920. The dwelling has a continuous stucco covered foundation, an exterior of stucco, an asphalt shingle front gable roof with exposed roof rafters and one interior concrete chimney. The full-width, hipped roof porch has square wood posts on tapered stone piers. Exposed roof rafters are also on the porch. The dwelling has two entrances on the main façade. The main entrance has an original single-light glass and wood door with a large, single-light rectangular transom and original single-light sidelights. The secondary entrance on the main façade has an original fifteen-light glass and wood door and a storm door. Windows are original one-over-one double hung wood sash. Wood shingles are located in the gable fields.

195. 984 Galloway Avenue ca. 1920 SY-5376 CB

Located at 984 Galloway Avenue is a one- and one-half story, frame Bungalow built ca. 1920. The dwelling has a continuous concrete foundation, an exterior of vinyl siding, an asphalt shingle jerkinhead roof and one interior end stuccoed chimney with a clay chimney cap. The full-width, shed roof porch has vinyl sided tapered columns, a picket wood fence railing and outdoor carpeting. The main entrance has an original six-light and wood panel door and a metal security door. Windows are original one-over-one double hung wood sash with metal security bars.

(Shed, ca. 1930, CB) Located to the rear of the dwelling is a ca. 1930, gable front, frame shed with an exterior of vinyl siding, a solid wood door and six-light windows.

196. 985 Galloway Avenue ca. 1920 SY-5377 CB

At 985 Galloway Avenue stands a one-story, frame pyramid square plan dwelling with Bungalow style influences built ca. 1920. The dwelling has a continuous concrete foundation, an exterior of stucco, an asphalt shingle jerkinhead roof with exposed roof rafters, one metal flue and one concrete chimney with a metal cap. The full-width, hipped roof porch has exposed roof rafters and battered stone columns with concrete plinths. The porch has been enclosed with glass panels. The main entrance has an original single-light and single-wood panel glass and wood door with an original eight-light transom and original two-light and wood panel sidelights. Windows are original nine-over-one double hung wood sash

197. 990 Galloway Avenue ca. 1926 SY-5378 CB

This is a one- and one-half story, frame, asymmetrical plan, Airplane Bungalow with a raised monitor roof section built ca. 1926. The dwelling has continuous concrete foundation, an exterior of wired brick veneer, an asphalt shingle multi-gable roof with exposed roof rafters and one interior end brick chimney with a corbelled brick cap and a clay cap. The gable roof entry porch has square wired brick columns with a wired brick swag and a closed wired brick railing. Situated in the gable field of the porch is a diamond shaped wood attic vent. The main entrance is unknown however it does retain its original four-light transom and a metal security door. Windows are original six-over-one double hung wood sash with concrete lintels. The raised monitor roof section has two sets of triple, six-over-one double hung wood sash windows. Stucco is located in the gable fields. A soldier brick water table and a header brick beltcourse surround the dwelling.

(Garage, ca. 1930, CB) Located to the rear of the dwelling is a contributing, ca. 1930, frame garage with a hipped roof.

United States Department of the Interior
National Park Service

National Register of Historic Places Continuation Sheet

Section number 7 Page 53

Galloway-Speedway Historic District
Memphis, Shelby County, Tennessee

198. 991 Galloway Avenue ca. 1920 SY-5379 CB

This is a one- and one-half story, frame Bungalow built ca. 1920. The dwelling has an exterior of stucco, an interior concrete chimney and an asphalt shingle gable roof with exposed roof rafters. The full-width, hipped roof porch has exposed roof rafters, a concrete floor, square stone columns, two, small, round Doric wood columns and stone piers with plinths. The main entrance has a replacement solid wood door with a metal security door. Windows are original six-over-one double hung wood sash with metal security bars and diamond shaped stenciled wood surrounds. A wood water table surrounds the dwelling. Located in the gable field of the main roofline are three window openings. On the dwellings main façade are two, four-light fixed and one-single light fixed windows. Knee brace brackets are located at the eaves of the gable fields.

199. 995 Galloway Avenue ca. 1922 SY-5380 CB

This is a one- and one-half story, frame Bungalow built ca. 1922. The dwelling has an exterior of asbestos shingle siding, an asphalt shingle, multi-gabled roof with knee brace brackets and an interior end concrete and an interior concrete chimneys. The gable roof entry porch has knee brace brackets, square wood columns on rusticated stone piers and a closed concrete block railing. A patio extends off the porch. Two, six-light, fixed windows are located in the gable field of the porch. The main entrance has an original Craftsman design, single-light glass and wood door with an original single-light transom and a metal security door. Windows are original nine-over one double hung wood sash with metal security bars. A single-light fixed glass and wood window is located in the main facades gable field. On the east façade of the dwelling is a protruding shed roof bay with exposed roof rafters, original nine-over-one double hung wood sash windows, a solid wood door and an original screen door. On the west façade of the dwelling is a hipped roof, protruding bay with two-over-two double hung wood sash windows with metal security bars and an exterior of weatherboard siding.

200. 996 Galloway Avenue ca. 1920 SY-5381 CB

At this location is a one-story, frame, Bungalow built ca. 1920. The dwelling has an exterior of stucco, an asphalt shingle jerkinhead roof and an interior concrete chimney. The combination, jerkinhead and hipped, full-width, roof porch has stone columns. The main entrance has an original Craftsman design, single-light and two wood panel door of wide width. Windows are one-over-one double hung wood sash with metal security bars. A wood beltcourse and water table surrounds the dwelling. The front façade of the dwelling has been remodeled.

201. 1000 Galloway Avenue ca. 1920 SY-5382 CB

This is a frame, one- and one-half story Bungalow built ca. 1920. The dwelling has a concrete foundation, an exterior of stucco, an asphalt shingle jerkinhead roof with exposed roof rafters and an interior concrete chimney. The full-width, hipped roof porch has tapered wood columns on brick piers and a metal awning. The main entrance has an original Craftsman design, single-light glass and wood panel door with an original single-light transom and a metal security door. Windows are original Craftsman style, one-over-one double hung wood sash. A wood water table surrounds the dwelling. Knee brace brackets and two Craftsman style fixed light windows are located in the gable fields. A shed roof addition has been added to the rear façade of the dwelling.

202. 1001 Galloway Avenue ca. 1927 SY-5383 CB

One-and one-half story, frame Bungalow built ca. 1927. The dwelling has an exterior of synthetic siding, a combination jerkinhead and hipped roof of asphalt shingles and a metal flue. The full-width, hipped roof porch has been enclosed with screen panels, windows and a closed concrete railing. The main entrance is not visible due to the porch enclosure. The only visible door is the porch entrance that has a ca. 1970 two-light and aluminum door.

United States Department of the Interior
National Park Service

National Register of Historic Places Continuation Sheet

Section number 7 Page 54

Galloway-Speedway Historic District
Memphis, Shelby County, Tennessee

Windows are one-over-one double hung wood sash windows with storm windows and some two-over-two double hung wood sash windows also with storm windows. Located in the gable field on the main façade has two, fixed light glass and wood windows.

(Shed, ca. 1980, NCB) Located to the rear of the dwelling is a non-contributing, ca. 1980, shed.

203.1004 Galloway Avenue ca. 1920 SY-5384 CB

This is a frame, one-and one-half story, Bungalow built ca. 1920. The dwelling has an exterior of aluminum siding, an interior stucco covered chimney and an asphalt shingle multi-gabled roof. The partial-width, gable roof entry porch has exposed roof rafters, knee brace brackets, wrought iron columns on stuccoed piers and a closed stuccoed railing. An attic vent opening in the porch's gable field has wood lattice installed in it. The main entrance has an original, four-small light and fourteen wood panel door with a metal security door. Windows are original twelve-over-one double hung wood sash. A protruding shed roof bay is located on a side façade with exposed roof rafters and one window. Located on the roofline is a shed roof dormer with exposed roof rafters and two-over-two double hung metal sash windows. Knee brace brackets and wood lattice is located in the gable fields.

204. 1005 Galloway Avenue ca. 1922 SY-5385 CB

This is a frame, two-story, central passage plan Bungalow built ca. 1922. The dwelling has an exterior of vinyl siding, an interior end brick chimney and a gable roof. The full-width, shed roof porch has exposed roof rafters and Doric columns on stone piers with concrete plinths. The main entrance has an original diamond light and four wood panel door. Windows are nine-over-one double hung wood sash and replacement six-over-six double hung metal sash on the 2nd floor. An addition was built on the rear façade. Located on the roofline is a shed roof dormer with exposed roof rafters. Knee brace brackets are located in the gable fields.

205. 1010 Galloway Avenue ca. 1912 SY-5386 CB

Standing at 1010 Galloway Avenue is a frame, one-story Bungalow built ca. 1912 and is currently vacant. The dwelling has an exterior of stucco and an asphalt shingle gable roof with knee brace brackets. The partial-width, incised porch has a wrought iron railing, brackets and columns. A hipped roof extension is attached to the incised porch. The main entrance is unknown as it is boarded. Windows are original one-over-one-double hung wood sash with metal security bars now mostly boarded. A wood water table and beltcourse surround the house. A protruding shed roof bay is located on the side façade and has three boarded window openings.

206. 1011 Galloway Avenue ca. 1965 SY-5066 NCB

This is a ca. 1965, Ranch style duplex. The dwelling has an asphalt shingle hipped roof and one and an interior central brick flue. The incised porch entry has wrought iron columns. The main entrance has a ca. 1970 double diamond light and solid wood door with a metal security door. Windows are two-over-two horizontal light double hung metal sash. The dwelling is a non-contributing resource.

GREENLAW AVENUE

207. 1023 Greenlaw Avenue ca. 1927 SY-5397 CB

Located at 1023 Greenlaw Avenue is a one-story, frame Bungalow built ca. 1927. The dwelling has a stucco covered foundation, an asphalt shingle jerkinhead roof, an exterior of brick veneer and one interior end and one exterior end brick chimneys. The full-width, jerkinhead and hipped roof porch has exposed roof rafters, stuccoed battered columns

United States Department of the Interior
National Park Service

National Register of Historic Places Continuation Sheet

Section number 7 Page 55

Galloway-Speedway Historic District
Memphis, Shelby County, Tennessee

and a closed brick railing. The main entrance is unknown but the entrance does have a metal security door. Windows are original three-over-one vertical light double hung wood sash windows with concrete sills. A soldier brick beltcourse and water table surround the house. Two boarded up window openings and stucco are located in the main façade's gable field. On the west façade is a projecting bay with a side entrance that retains its original multi-light glass and wood door. On the east façade is also a projecting bay with a double set of windows.

208. 1027 Greenlaw Avenue ca. 1915 SY-5398 CB

This is a frame, one- and one-half story Bungalow built ca. 1915. The dwelling has a continuous brick foundation, an exterior of stucco, an asphalt shingle jerkinhead roof and one interior brick chimney with a clay chimney cap. The full-width, hipped roof porch has an arched milled frieze, square brick columns on brick piers with concrete plinths. The main entrance has a ca. 1980 Palladian light and aluminum door with an original, three-section (two-light-five-light-two-light) transom, original single-light glass and wood panel sidelights and a metal security door. A secondary entrance on the main façade has been boarded over. Windows are one-over-one double hung wood sash. A wood water table surrounds the dwelling. A protruding bay extends off the east façade with three, one-over-one double hung wood sash windows. Three, four-over-one double hung wood sash windows and stucco and stick work is located in the gable fields. A ca. 1950 gable roof wing was added to the rear façade. A plastic carport extends off the west façade of the dwelling and

(Shed, ca. 1980, NCB) A metal shed is located to the rear of the dwelling.

209. 1032 Greenlaw Avenue ca. 1913 SY-5399 CB

Standing at 1032 Greenlaw Avenue is a frame, two-story, American Foursquare style dwelling built ca. 1913. The dwelling has a continuous stucco covered foundation, an exterior of vinyl siding, an asphalt shingle hipped metal roof and a brick chimney with a clay chimney cap. The wraparound, hipped roof porch has Doric wood columns on brick piers with concrete plinths. The main entrance has a single-light glass and wood door. Windows are original one-over-one double hung wood sash. An original one-story rear wing has exposed roof rafters and an exterior of weatherboard and vinyl siding.

(Garage, ca. 1950, CB) Located to the rear of the dwelling is a contributing, ca. 1950, one-bay garage with a gable roof, no door and a shed roof extension.

210. 1033 Greenlaw Avenue ca. 1917 SY-5400 CB

This is a one- and one-half story, frame Bungalow built ca. 1917. The dwelling has an exterior of stucco with some stick detail, a gable roof of asphalt shingles and an interior concrete chimney. The gable roof entry porch has rusticated battered stone columns. The porch floor extends the width of the house as a patio. The main entrance has a ca. 1980 fanlight glass and wood door with an original three-light transom and original single-light and wood panel sidelights. Windows are replacement two-over-two horizontal light double hung vinyl sash windows with some remaining one-over-one double hung wood sash. Knee brace brackets and single-light fixed glass and wood windows are located in the gable fields. The side facades have projecting, gable roof windows bays.

(Shed, ca. 1970, NCB) Located to the rear of the dwelling is a non-contributing, ca. 1970, frame shed.

United States Department of the Interior
National Park Service

National Register of Historic Places Continuation Sheet

Section number 7 Page 56 Galloway-Speedway Historic District
Memphis, Shelby County, Tennessee

211. 1036 Greenlaw Avenue ca. 1928 SY-5401 CB

This is a one-story, frame Airplane Bungalow built ca. 1928. The dwelling has a continuous concrete foundation, an exterior of brick veneer, a cross gable roof of asphalt shingles and one interior and one exterior end brick chimneys. The full-width, gable and hipped roof porch has brick columns with a concrete diamond detail, exposed roof rafters, knee brace brackets and extends to a porte-cochere. A single-light glass and wood attic window is located in the porch's gable field. The main entrance a single-light glass and wood door with original single-light and wood panel sidelights. Windows are original three-over-one vertical light double hung wood sash windows with concrete sills. Three vertical light windows are located in the roofline gable field.

212. 1037 Greenlaw Avenue ca. 1917 SY-5402 CB

One-and one-half story, frame Bungalow built ca. 1917. The dwelling has an exterior of stucco and an asphalt shingle gable roof. The full-width, shed roof porch has brick columns and a closed brick railing. The porch columns connect with frame, segmental arches. The main entrance has a ca. 1960, single-light glass and wood door. Windows are original one-over-one double hung wood sash. A projecting, shed roof bay window is located on the east façade. On the main facades roofline is a gable roof dormer with exposed roof rafters, knee brace brackets and two, one-over-one double hung wood sash windows.

(Garage, ca. 1940, CB) Located to the rear of the dwelling is a contributing, ca. 1940, frame garage with an exterior of weatherboard siding, an asphalt shingle roof and vertical board doors.

213. 1042 Greenlaw Avenue ca. 1912 SY-5403 CB

This is a frame, one- and one-half story Bungalow built ca. 1912. The dwelling has a concrete foundation, an exterior of stucco, a jerkinhead roof of asphalt shingles with exposed roof rafters and one interior concrete chimney. The full-width, hipped roof porch has rough-cut, stone battered columns, a closed brick railing and is in the process of being enclosed. The main entrance has a ca. 1990, flush wood door with an original three section transom, original single-light and wood panel sidelights and a metal security door. Windows are original one-over-one double hung wood sash. Weatherboard siding is located in the skirt wall and in the gable fields and cornice area. Also located in the gable field, on the main façade, are two, single-light fixed glass and wood windows.

214. 1049 Greenlaw Avenue ca. 1917 SY-5406 CB

The property at 1049 Greenlaw Avenue is a frame, one- and one-half story Airplane Bungalow with a raised monitor roof section built ca. 1917. The dwelling has an exterior of stucco and a gable roof of asphalt shingles. The full-width, shed roof porch has exposed roof rafters, square wood posts on rough-cut stone piers and a concrete floor. The main entrance has an original single-light glass and wood door with an original three-light transom and original single-light sidelights. Windows are original one-over-one double hung wood sash. Some stick detailing is located in the side façade gable fields. Located on main facades roofline is a gable roof dormer with two, one-over-one double hung wood sash windows.

(Garage, ca. 1940, CB)

215. 1052 Greenlaw Avenue ca. 1920 SY-5407 CB

This is a frame, one- and one-half story Bungalow built ca. 1920. The dwelling has a continuous brick foundation, an exterior of vinyl siding and brick veneer, a jerkinhead roof of asphalt shingles and one interior concrete chimney. The jerkinhead roof porch has exposed roof rafters, triple square wood posts on brick piers and an open brick railing. The

United States Department of the Interior
National Park ServiceNational Register of Historic Places
Continuation SheetSection number 7 Page 57Galloway-Speedway Historic District
Memphis, Shelby County, Tennessee

main entrance has an unknown door but still retains its original single-light transom that has been boarded over. Some original Craftsman style one-over-one double hung wood sash windows with wood surrounds remain. On each side of the main entrance, the window openings have been reduced, enclosed and an eight-light fixed glass and wood window has been installed. Knee brace brackets are located in the gable fields and a wood water table surrounds the house. A protruding shed roof bay with a single window opening is located on a side façade. The house is currently under major renovation.

216. 1053 Greenlaw Avenue ca. 1917 SY-5408 CB

This is a frame, one- and one-half story Bungalow built ca. 1917. The dwelling has a continuous concrete foundation, an exterior of aluminum siding, an asphalt shingle gable roof and a metal flue. The shed roof porch has exposed roof rafters, tapered wood columns on stuccoed piers, square stuccoed columns and a closed brick railing. The main entrance has a ca. 1980 solid wood door with a metal security door. Windows are Craftsman style one-over-one double hung wood sash. A protruding hipped roof bay with three, Craftsman style, one-over-one double hung wood sash windows is located on the west façade. Located on the rear façade is an original shed roof wing. On the east façade is an entrance covered by a protruding gable roof bay. This secondary entrance retains its original ten-light glass and wood door with a metal security door.

217. 1056 Greenlaw Avenue ca. 1921 SY-5409 NCB

Standing at 1056 Greenlaw Avenue is a two-story, frame American Foursquare style dwelling built ca. 1921. The dwelling has a continuous stucco covered foundation, an exterior of vinyl siding, an asphalt shingle roof with a flare, one metal flue and one interior brick chimney. The hipped roof porch has been enclosed with square wood columns and screen panels. The main entrance has a solid wood door and a screen door. Windows are original one-over-one double hung wood sash. An original, one-story wing is located on the rear façade. An exterior wood staircase leads to a 2nd floor porch on the east façade.

218. 1057 Greenlaw Avenue ca. 1913 SY-5410 CB

This is a frame, two-story, American Foursquare style dwelling built ca. 1913. The dwelling has a continuous stucco covered foundation, an exterior of vinyl siding, an asphalt shingle hipped roof with a flare and an interior end brick chimney. The mansard roof porch has been enclosed with square brick columns, a closed concrete railing and screen panels. The main entrance is unknown but a metal security is in place. Windows are original one-over-one double hung metal sash with some original one-over-one double hung wood sash still remaining. Located on the rear façade is an original one-story, frame wing.

219. 1066-68 Greenlaw Avenue ca. 1924 SY-5411 CB

This is a frame, one-story Bungalow built ca. 1924. The dwelling has an exterior of brick veneer, a continuous stucco covered foundation, an asphalt shingle roof with exposed roof rafters and two interior brick chimneys with concrete chimney caps. The gable and hipped roof porch has exposed roof rafters, square brick columns and a closed brick railing with concrete plinths and arched concrete drains. The main façade has two entrances both with ca. 1990 six-panel aluminum doors with metal security doors. A header course brick lintel is located over both entrances. Windows are one-over-one double hung wood sash with those on the main (S) and west facades being boarded. A soldier course brick beltcourse surrounds the dwelling and a small attic vent is located in the gable fields. A protruding gable roof bay is located on both the east and west facades and has a square attic vent in the gable fields and a double set of windows. A ca. 1995, frame addition has been added to the rear façade. The addition has been enclosed with vertical board.

United States Department of the Interior
National Park ServiceNational Register of Historic Places
Continuation SheetSection number 7 Page 58Galloway-Speedway Historic District
Memphis, Shelby County, Tennessee**220. 1069 Greenlaw Avenue ca. 1975 SY-5412 NCB**

This is a frame, two-story apartment building built ca. 1975. The building has an exterior of brick veneer, a flat roof, four-light fixed windows and solid wood doors. The incised, individual porches have metal railing and metal posts. The building is non-contributing to the district.

221. 1072 Greenlaw Avenue ca. 1920 SY-5413 CB

One- and one-half story, frame Bungalow built ca. 1920. The dwelling has an exterior of brick veneer (skirt wall) and stucco, a jerkinhead roof of asphalt shingles and an interior concrete chimney. The full-width, hipped roof porch has stuccoed columns on rough-cut stone piers. The main entrance has an original single-light glass and wood door with an original three-section transom and single-light and single wood panel sidelights. Windows are original one-over-one double hung wood sash. Two-single light attic windows are located in the gable field on the main façade.

(Garage, ca. 1920, CB) Located to the rear of the dwelling is an original, open single-bay, frame garage with an asphalt shingle roof and an exterior of shiplap siding.

222. 1078 Greenlaw Avenue ca. 1913 SY-5414 CB

This is a frame, one- and one-half story Bungalow built ca. 1913. The dwelling has a continuous concrete foundation, a gable roof of asphalt shingles, an exterior of vinyl siding, one interior end and one interior central concrete chimneys. The full-width, shed roof porch has two, tapered wood columns on stone piers and two, stone battered columns and a metal shed roof awning. The main entrance has a three-light and three wood panel door with an original transom and sidelights that has been covered with vinyl siding. Windows are six-over-one and ten-over-one double hung wood sash. On the main façade is a gable roof dormer with two, multi-light attic windows. Bay windows are located on both side facades. An exterior metal stairway on the west façade leads to a half story entrance with a flush wood door.

223. 1081-83 Greenlaw Avenue ca. 1917 SY-5415 CB

Located at 1081-83 is a ca. 1917, frame, two-story apartment building. The building has an exterior of brick veneer, a continuous poured concrete foundation and a flat roof with concrete coping. On the main (S) façade is a two-story, partial-width, shed roof porch with square brick columns. At the top of the columns is a wood cut diamond panel design. The 1st floor of the porch has a solid brick railing with a concrete top rail. The porch roof is full-width on the 1st floor and has paired brackets. The 2nd floor railing has been removed and replaced with plywood panels. There are three entrances on the main façade. A four-light glass and wood door and an original eight-light glass and wood door is located on the 1st floor. The 2nd floor has a six-light glass and wood door. All the entrances have original rectangular, single-light transoms and soldier course brick surrounds. Windows are original one-over-one double hung wood sash with concrete sills and soldier course brick surrounds. A 2nd story porch is located on the rear façade and has been enclosed with wood panels on the 2nd floor and weatherboard on the 1st floor.

(Shed, ca. 1965, NCB) Located to the rear of the building is a non-contributing, ca. 1965, frame and metal shed.

224. 1084 Greenlaw Avenue ca. 1914 SY-5416 CB

This is a frame, one- and one-half story Bungalow built ca. 1914. The dwelling has an asphalt shingle, multi-gabled roof, an exterior of stucco and one exterior end stucco covered chimney with a clay chimney cap. The incised, shed roof porch has been enclosed with concrete and stone columns and screen panels. Two entrances are located on the main façade. The main entrance has an original, Craftsman style single-light and wood panel door with original

United States Department of the Interior
National Park Service

National Register of Historic Places Continuation Sheet

Section number 7 Page 59

Galloway-Speedway Historic District
Memphis, Shelby County, Tennessee

Craftsman style, single-light and single wood panel sidelights that match the door. The secondary entrance has a set of multi-light French doors. Windows are original Craftsman style and regular, one-over one double hung wood sash. A wood water table surrounds the dwelling and enclosed knee brace brackets are located in the gable fields. A porch has been added and semi-enclosed on the rear façade. On the main facades roofline is a hipped roof dormer with exposed roof rafters and three window openings; one with a two-light fixed window, one with screening and one with an AC unit. A protruding gable roof bay is located on the west façade.

225. 1085 Greenlaw Avenue ca. 1923 SY-5417 CB

One- and one-half story Airplane Bungalow with a raised hipped monitor roof section built ca. 1923. The dwelling has a continuous stucco covered foundation, a jerkinhead roof with exposed roof rafters and asphalt shingles and a metal flue. The hipped roof porch has exposed roof rafters, battered stone columns and a stuccoed closed railing. Arches connect the columns on the porch. The main entrance has an original six-light glass and wood door with an original ten-light transom, original four-light and single wood panel sidelights and a metal security door. Windows are original nine-over-one double hung wood sash. A wood water table and beltcourse surround the dwelling. A protruding bay on the east and west facades have a triple set of windows. The raised hipped monitor roof section has exposed roof rafters and two sets of paired windows.

226. 1088 Greenlaw Avenue ca. 1945 SY-5418 CB

This is a frame, one- and one-half story Minimal Traditional style dwelling built ca. 1945. The dwelling has an exterior of rusticated brick veneer, a continuous concrete foundation, a side gable roof of asphalt shingle, one interior brick flue and one large exterior brick chimney on the main façade. The steep, gable entry has a concrete patio. The main entrance has a ca. 1970, diamond-light and wood door with a metal security door. Windows are original nine-over-one double hung wood sash with metal security bars and concrete sills. A soldier brick beltcourse and a header brick water table surround the house. Stucco is located in the gable fields.

(Garage, ca. 1945, CB) Located to the rear of the dwelling is a contributing, ca. 1945 frame garage with an asphalt shingle hipped roof, an exterior of weatherboard and metal, double hinged doors.

227. 1089 Greenlaw Avenue ca. 1917 SY-5419 CB

This is a frame, one- and one-half story Bungalow built ca. 1917. The dwelling has a continuous stucco covered foundation, a jerkinhead and gable roof of asphalt shingles, metal flues and an exterior of stucco with some attempt at stick work. The hipped roof porch has exposed roof rafters, a large solid frieze, two battered stone columns, wrought iron posts and a wrought iron railing. The main entrance is unknown but it does have a metal security door. Windows are original Craftsman style, one-over-one double hung wood sash with metal security bars. A wood beltcourse and water table surround the dwelling. Located on the west and east facades are protruding gable roof bays with a triple set of windows. Some stick work and stucco along with two, ca. 2000 six-over-six double hung wood sash windows are located in the gable fields.

(Garage, ca. 1950, CB) Located to the rear of the dwelling is a ca. 1950, gable roof, two-bay garage with an exterior of stucco and the remains of an old brick driveway extending to the road.

United States Department of the Interior
National Park Service

National Register of Historic Places Continuation Sheet

Section number 7 Page 60

Galloway-Speedway Historic District
Memphis, Shelby County, Tennessee

228. 1094 Greenlaw Avenue ca. 1921 SY-5420 CB

At this location is a frame, one- and one-half story Bungalow built ca. 1921. The dwelling has an exterior of brick veneer, a jerkinhead roof of asphalt shingles and exposed roof rafters and an interior brick chimney. The full-width, hipped roof porch has exposed roof rafters and square brick columns. The main entrance has a single-light glass and wood door with an original three-light transom, original single-light sidelights and a metal security door. Windows are original one-over-one double hung wood sash with rough-cut concrete sills. Located in the gable fields are paired, single-light attic windows. One the east façades roofline is a hipped roof dormer with a single-light fixed window.

229. 1095 Greenlaw Avenue ca. 1914 SY-5421 CB

This is a frame, one-story Bungalow built ca. 1914. The dwelling has an exterior of weatherboard, an interior brick chimney and an asphalt shingle hipped roof with a rear gable wing and exposed roof rafters. The full-width, gable and hipped roof porch has Doric fluted columns on rough-cut concrete piers, an open pedestal railing and a single-fixed light window in the gable field. The main entrance has an original eight-light glass and wood door with an original three-section transom and original four-light and wood panel sidelights. Windows are original, paired one-over-one double hung wood sash. Attached to the rear façade is a small, frame addition with weatherboard siding.

(Garage with addition, ca. 1930: 1970, NCB) Located to the rear of the dwelling is a ca. 1930, frame garage with a gable roof and shiplap siding. Attached to the garage is a ca. 1970 gable roof addition on the main façade.

230. 1100 Greenlaw Avenue ca. 1912 SY-5422 CB

Standing at 1100 Greenlaw Avenue is a frame, one- and one-story Bungalow built ca. 1912. The dwelling has an exterior of brick veneer, an asphalt shingle jerkinhead roof with exposed roof rafters and an interior brick chimney. The full-width, hipped roof porch has exposed roof rafters, square brick columns, a closed brick railing and has been enclosed with wood panels and structural glass blocks. The main entrance door is not visible. Windows are original six-over-one double hung wood sash.

231. 1101 Greenlaw Avenue ca. 1914 SY-5423 CB

This is a frame, one-story Bungalow built ca. 1914. The dwelling has an exterior of concrete block, a jerkinhead roof of asphalt shingles and exposed roof rafters, a metal flue and one interior brick chimney. The full-width, hipped roof porch has exposed roof rafters, concrete block columns and a closed concrete block railing. The porch floor extends to the east to form patio extension. Two entrances are located on the main façade. One entrance has an original nine-light glass and wood door with an original three-section transom and original six-light and wood sidelights. The other entrance also has an original nine-light glass and wood door but has an original multi-light transom, six-light glass and wood panel sidelights and a metal security door. Windows are one-over-one double hung wood sash. An original shed roof porch was attached to the rear façade and has been enclosed with asbestos shingle siding. In the gable field of the main façade are four, single-light fixed attic windows.

(Garage, ca. 1930, CB) Located to the rear of the dwelling is a ca. 1930, frame garage with an asphalt shingled gable roof and an added extension of concrete block and a metal screen security door.

232. 1110 Greenlaw Avenue ca. 1921 SY-5424 CB

This is a frame, one-story Bungalow built ca. 1921. The dwelling has an exterior of brick veneer, a jerkinhead and gable roof of asphalt shingles with exposed roof rafters and one interior concreted chimney. The full-width, hipped roof porch has exposed roof rafters, brick columns and separate brick piers with concrete plinths. The main entrance

United States Department of the Interior
National Park Service

National Register of Historic Places Continuation Sheet

Section number 7 Page 61

Galloway-Speedway Historic District
Memphis, Shelby County, Tennessee

has a ca. 1970, diamond-light and wood door with a boarded transom and sidelights. Windows are original one-over-one double hung wood sash with some having been boarded with vertical boarded. A jerkinhead roof dormer on the east façade has exposed roof rafters and one window opening with screening. Two window openings (boarded) and a small vent is located in the main facades gable field.

(Shed, ca. 1970, NCB) Located to the rear of the dwelling is a non-contributing, ca. 1970, gable roof shed with rolled tar paper siding.

233. 1113 Greenlaw Avenue ca. 1928 SY-5425 CB

At 1113 Greenlaw Avenue stands a frame, one-story, pyramid square plan, Bungalow style influenced dwelling built ca. 1928. The dwelling has an exterior of brick veneer, an asphalt shingle hipped roof with exposed roof rafters and one interior central stucco covered chimney. The full-width, incised roof porch has exposed roof rafters and battered brick columns. The main entrance is unknown but it does have a metal security door. Windows are unknown and boarded with brick sills. A small, ca. 1950 addition has been added to the rear façade with a shed roof and shiplap siding. Two shed roof dormers are located on the roofline with asphalt shingle siding and three windows openings on each dormer.

(Garage, ca. 1940, CB)

234. 1117 Greenlaw Avenue ca. 1920 SY-5426 CB

This is a frame, one-story Bungalow built ca. 1920. The dwelling has an exterior of brick veneer, a jerkinhead and gable roof of asphalt shingles and exposed roof rafters and one interior brick chimney. The full-width, hipped roof porch has exposed roof rafters, brick columns and separate brick piers. The main entrance has an original eight-light glass and wood panel door with a filled-in, original transom and a metal security door. Windows are one-over-one double hung wood sash. A ca. 1930 addition with vertical board siding has been added to the rear façade. On the west façade is a protruding gable roof bay with two windows.

(Garage, ca. 1950, CB) Located to the rear of the dwelling is a ca. 1950, single-bay, frame garage with a gable roof, weatherboard siding and vertical board hinged doors.

235. 1121 Greenlaw Avenue ca. 1916 SY-5427 CB

This is a frame, one-story Bungalow built ca. 1916. The dwelling has a continuous stucco covered foundation, an exterior of stucco, a front gable roof of asphalt shingles and exposed roof rafters and one interior central brick chimney. The gable roof entry porch has exposed roof rafters, battered stone columns, a stuccoed closed railing and small stick work designs in the apex of the gable field. The main entrance has an original eight-light glass and wood panel door with a metal security door. Windows are original nine-over-one and one-over-one double hung wood sash. A wood water table surrounds the dwelling and a protruding gable roof bay is sited on the west façade.

United States Department of the Interior
National Park Service

National Register of Historic Places Continuation Sheet

Section number 7 Page 62

Galloway-Speedway Historic District
Memphis, Shelby County, Tennessee

NORTH PARKWAY AVENUE

236. 800, 900, 1000, 1100 Blocks of North Parkway Avenue ca. 1910 CS

North Parkway is a 150-foot wide paved roadway that extends east-west through the center of the Galloway-Speedway Historic District. The road was established ca. 1910 as part of the Memphis Parkway System. A wide, landscaped median divides the parkway and includes a variety of shrubs, plants, and mature trees. North Parkway was listed on the National Register of Historic Places in 1989 as part of the Memphis Parkway System Historic District.

237. 812-814 North Parkway Avenue ca. 1920 SY-5748 CB

Located at 812-814 North Parkway Avenue is a frame, one-story Bungalow design duplex built ca. 1920. The dwelling has a continuous poured concrete foundation, an exterior of brick veneer, a gable front roof of asphalt shingles and one interior brick chimney. The two, gable entry porches on the main façade have square brick columns and closed brick railings. Both entrances have original, three-vertical light and one wood panel Craftsman style doors with one having an original screen door and one having a storm door. Windows are original one-over-one double hung wood sash with wood sills.

238. 815 North Parkway Avenue ca. 1921 SY-5749 CB

Standing at this location is a frame, one-story, pyramid square plan dwelling built ca. 1921 and is currently vacant. The dwelling has a continuous brick foundation, an exterior of brick veneer, a ca. 2003, hipped roof of asphalt shingles and an interior concrete chimney. The full-width, incised porch has vinyl soffits, a vinyl cornice and is supported by square brick columns with concrete plinths. Two entrances are located on the main façade. One entrance has a single-light glass and wood door and the other has a two-light glass and wood door. Both doorways have been covered with wood panels but retain the original, two-light and three-light transoms and original single-light and wood panel sidelights. Windows are original one-over-one double hung wood sash with concrete sills and metal security bars. On the main façade is a hipped roof dormer with two, single-light fixed windows. A ca. 1950 addition has been added to the rear façade with an exterior of vinyl siding.

239. 818-20 North Parkway Avenue ca. 1920 SY-5750 CB

This is a frame, one-story Bungalow design duplex built ca. 1920. The dwelling has a continuous poured concrete foundation, an exterior of brick veneer, a gable front roof of asphalt shingles and one interior brick chimney. The two, gable entry porches on the main façade have square brick columns and closed brick railings. Both entrances have original, three-vertical light and one wood panel Craftsman style doors with original screen doors. Windows are original one-over-one double hung wood sash with wood sills.

240. 819 North Parkway Avenue ca. 1921 SY-5751 CB

One- and one-half story, frame Bungalow built ca. 1921. The dwelling has a continuous concrete block foundation, an exterior of brick veneer, a jerkinhead roof of asphalt shingles and one exterior end and one interior brick chimneys. The full-width, hipped and gable roof porch has exposed roof rafters, battered stone columns, a closed brick railing with a concrete top rail and concrete drains and stucco and one, single-light fixed window in the gable field. The main entrance has a multi-light glass and wood door with an original six-light transom with metal security bars, original ten-light sidelights with screening and security bars and a metal security door. Windows are original Craftsman style one-over-one double hung wood sash with concrete sills and metal security bars. A protruding double line brick water table and soldier course brick beltcourse surround the dwelling. Stucco and two, single-light fixed windows are located in the gable field on the main façade.

United States Department of the Interior
National Park Service

National Register of Historic Places Continuation Sheet

Section number 7 Page 63

Galloway-Speedway Historic District
Memphis, Shelby County, Tennessee

(Garage, ca. 1960, CB) Located to the rear of the dwelling is a ca. 1960, one-bay, frame garage with an exterior of shiplap siding, a gable roof, a metal track overhead door and scaling in the gable field.

241. 823 North Parkway Avenue ca. 1920 SY-5752 CB

At 823 North Parkway Avenue is a frame, one- and one-half story Bungalow built ca. 1920. The dwelling has a continuous stucco covered foundation, an exterior of brick veneer, multi-front gabled roof of asphalt shingles and an interior brick chimney. The full-width, hipped roof porch has exposed roof rafters, square brick columns with stone plinths and a closed brick railing with a concrete top rail. The porch has been partially enclosed with vertical board and windows. The main entrance has an original single-light glass and wood panel door with a metal security door. Windows are original Craftsman-style one-over-double hung wood sash with concrete sills. A soldier course brick beltcourse and a protruding double line brick water table surrounds the dwelling. Aluminum siding and a single-light fixed window have been installed in the gable field on the main façade.

(Shed, ca. 1970, NCB) Located to the rear of the dwelling is a ca. 1970, frame shed with a gable roof and a plywood door.

242. 824 North Parkway Avenue ca. 1917 SY-5753 CB

This is a frame, one- and one-half story Bungalow built ca. 1917. The dwelling has a continuous rusticated stone foundation, an exterior of stucco, an asphalt shingled hipped roof with flare, metal flues and two, exterior end stucco covered chimneys. The incised, full-width porch has one square stone column, an original tongue and groove ceiling and a closed brick railing that extends out to a patio. The door to the main entrance is not visible but it does have a metal and glass storm door. Windows are replacement one-over-one double hung wood sash with rusticated stone sills. On the east façade is a projecting bay under the extended roof flare. On the main façade is a hipped roof dormer.

(Garage, ca. 1950, CB) Located to the rear of the dwelling is a ca. 1950, two-bay garage with a hipped roof.

243. 828 North Parkway Avenue ca. 1920 SY-5754 CB

This is a frame, one and one-half story Bungalow built ca. 1920. The dwelling has a continuous poured concrete and stucco covered foundation, an exterior of brick veneer, a jerkinhead roof of asphalt shingles and an exterior end brick chimney. The full-width, incised roof porch has been totally enclosed with square brick columns, glass windows with metal security bars, a closed brick railing and in the gable field is stick work, stucco and a louvered attic vent. The only visible door is the door to the porch and it is a ca. 1980, nine-light glass and metal door. Windows are original one-over-one double hung wood sash with metal security bars. In the gable field on the main façade are stick work, stucco, and a nine-light fixed window. A protruding double brick water table surrounds the dwelling. On the east façade is a jerkinhead roof protruding bay with a triple set of windows, a metal awning and a three-light fixed window in the gable field.

(Shed, ca. 1970, NCB)

244. 829 North Parkway Avenue ca. 1925 SY-5755 CB

At 829 North Parkway Avenue stands a frame, two-story American Foursquare style dwelling built ca. 1925. The dwelling has an exterior of brick veneer, a continuous concrete block foundation and a hipped roof of asphalt shingles. The wraparound porch has a porte-cochere extension with square brick columns with wood capitals, a closed brick

United States Department of the Interior
National Park Service

National Register of Historic Places Continuation Sheet

Section number 7 Page 64

Galloway-Speedway Historic District
Memphis, Shelby County, Tennessee

railing with a concrete top rail and a concrete wheelchair ramp with a metal railing leading from the porch to the driveway. Windows are mostly replacement one-over-one and nine-over-one double hung vinyl sash with very few original one-over-one double hung wood sash remaining. The concrete sills under the windows appear to have been replaced or reformed. A brick soldier course beltcourse and water table surround the dwelling. On the east façade is a hipped roof bay with a side entrance that has a solid metal door with concrete steps and a metal railing and nine-over-one double hung windows and two, six-light fixed windows. On the rear façade is a 2nd floor metal staircase. On the roofline are hipped roof dormers with asphalt shingle siding and two, four-light fixed windows.

245. 833 North Parkway Avenue ca. 1925 SY-5756 CB

Sited at 833 North Parkway Avenue is a brick, one-story, ca. 1925, Classical Revival style influenced church with a large full basement level and a historic large two-story ell. The church was originally built as the Parkway Seventh Day Adventist Church but is currently not in use. The church has a continuous poured concrete foundation, a flat roof with concrete coping and an exterior of five-course American bond brick, which has been sandblasted. On the main (N) façade of the sanctuary section is a central, full-height portico with columns with Ionic capitals. The pediment has a leaf design in the center and is currently covered with chicken wire. The main entrance has paired, ca. 1980, steel and glass doors with an original rectangular single light transom and exterior metal security doors. Leading to the entrance is a wide set of concrete steps with a central iron railing. Flanking the entrance are narrow rectangular single-light windows with textured glass. Above the entrance are two, large square fixed windows. One has three vertical lights and the other has a single light fixed window. Both have textured glass. Flanking these windows are narrow rectangular windows identical to those flanking the entrance. The windows have large concrete sills and lintels. The main façade has two, four-light vertical windows above the main windows. Brick pilasters frame the entrance. A stretcher course brick beltcourse surrounds the church beneath a large wood cornice. On the east façade of the main church section at the basement level is an entrance with paired, single-light glass and wood doors with an original rectangular, single-light transom and a set of concrete steps leading down to the entrance.

The historic, large, two-story ell has two interior end brick chimneys each with arched chimney caps. The wing has original one-over-one double hung wood sash windows with soldier course lintels and concrete sills. The wing has a flat roof with concrete coping and a soldier course brick band painted white to match the main section's cornice. On the north façade of the wing is an exterior metal staircase leading to a 2nd story entrance that has an original single-light glass and metal door. A similar door is beneath the steps on the first floor. The entrance on the north façade of the wing has a ca. 1980, flush wood door and an original single-light square transom.

The interior of the vestibule has paired, single-light glass and wood doors that lead to the sanctuary. The main sanctuary has been heavily damaged and is in a severe state of deterioration with the ceiling having caved in.

246. 842 North Parkway Avenue ca. 1902 SY-5755 CB

This is a two-story American Foursquare style dwelling built ca. 1902. The dwelling has a continuous concrete block foundation, brick exterior, an asphalt shingled hipped roof of with a flare, and an exterior end brick and stucco covered chimney. The hipped roof, two-story porch has square brick columns and a closed brick railing with a concrete top rail. The 2nd floor has a wood lattice and screen enclosure. Both entrances on the main façade have ca. 1970, solid wood doors but retain their original transoms currently covered with wood and wood lintels. The 2nd floor entrance door is not visible. Windows are mostly one-over-one double hung wood sash and some replacement one-over-one vinyl sash, all having wood lintels and sills. A two-story metal porch has been added to the rear façade.

United States Department of the Interior
National Park Service

National Register of Historic Places Continuation Sheet

Section number 7 Page 65

Galloway-Speedway Historic District
Memphis, Shelby County, Tennessee

247. 848 North Parkway Avenue ca. 1935 SY-5758 CB

This is a frame, one-story Bungalow built ca. 1935. The dwelling has a continuous stucco covered foundation, an exterior of brick veneer and a gable and hipped roof of asphalt shingles. The full-width gable roof porch extends out to a porte-cochere and is supported by battered stone columns and a closed brick railing. The main entrance door is not visible but it does retain its original four-light and single wood panel sidelights with dentil detailing. Windows are replacement one-over-one double hung vinyl sash windows with concrete sills and original one-over-one double hung wood sash on the main façade. In the gable field are stucco and a three-light fixed window with an awning. A solid brick water table and a header brick beltcourse surround the dwelling.

248. 854-6 North Parkway Avenue ca. 1935 SY-5759 CB

One- and one-half story, frame Airplane Bungalow with a raised monitor roof section built ca. 1935. The dwelling has an exterior of brick veneer, a jerkinhead roof of asphalt shingles with vinyl soffits and one exterior end and one interior brick chimneys. The full-width, gable roof extends out to a porte-cochere and has vinyl soffits, knee brace brackets, square brick columns and closed brick railing. The main entrance has a ca. 1990, solid wood door with a metal security door. Windows are original one-over-one double hung wood sash. Knee brace brackets are located in the gable fields.

(Garage, ca. 1935, CB) Located to the rear of the dwelling is a frame garage with a gable roof of asphalt shingles and exposed roof rafters.

249. 858 North Parkway Avenue ca. 1930 SY-5760 CB

This is a frame, one- and one-half story Bungalow built ca. 1930. The dwelling has an exterior of stucco, a hipped roof of asphalt shingles and exposed roof rafters, metal flues and two interior concrete chimneys. The partial-width, gable roof porch extends out to the east into a patio and has double wood columns on a closed stone railing, added wood lattice and two, single-light fixed windows covered with wood panel. The main entrance has an original nine-light glass and three wood panel door with an original, rectangular three-light transom and a metal security door. Windows are original nine-over-one double hung wood sash. On the east façade roofline is a hipped roof dormer with two, single-light fixed windows.

250. 860 North Parkway Avenue ca. 1912 SY-5761 CB

Standing at 860 North Parkway Avenue is a frame, one- and one-half story Airplane Bungalow with a raised gabled monitor roof section built ca. 1912. The dwelling has a continuous concrete foundation, an exterior of brick veneer, a side gable roof of asphalt shingles and two interior brick chimneys. The arched gable roof canopy is supported by thick, oversized brackets over a small brick entry stoop/patio. The main entrance has an original fifteen-light glass and wood door with an arched transom enclosed with a wood panel. Windows are original nine-over-one double hung wood sash with three sets of paired, four-light glass and wood casement windows on the main façade. Located at the roofline are two, small gable roof dormers each with single-four-light fixed windows. On the east and west facades are original bay windows with four, six-over-one double hung wood sash windows. On the west façade, paired, four-light glass and wood design windows with wood sills and small brackets flank the chimney. The raised gabled monitor roof section has exposed roof rafters and an exterior metal staircase leading to the west façade (the entrance is not visible from the street). A ca. 1950, gable roof addition was added to the rear façade.

(Garage/Apartment, ca. 1912, CB) To the rear of the house is a two-story, frame garage/apartment with an asphalt shingle flat roof with a shed roof awning on the south façade, a central brick chimney and asphalt siding material on

United States Department of the Interior
National Park Service

National Register of Historic Places Continuation Sheet

Section number 7 Page 66

Galloway-Speedway Historic District
Memphis, Shelby County, Tennessee

the exterior. The entrance has a flush wood door and the windows are one-over-one double hung wood sash. The original garage bay opening has been enclosed with wood panels. Etched in the city sidewalk in front of the house are the words, "Laid 1948 by Koehler & Son".

251. 868 North Parkway Avenue ca. 1940 SY-5762 CB

Located at 868 North Parkway Avenue is a frame, one-story Minimal Traditional style dwelling with Colonial Revival influences built ca. 1940. The dwelling has a continuous concrete foundation, an exterior of brick veneer and a side gable roof of asphalt shingles. The central gable roof entry porch is supported by wrought iron posts and a wrought iron railing. The main entrance has a ca. 1970, single-light glass and wood door with a metal security door. Windows are original six-over-six double hung wood sash with metal security bars and brick sills. Shiplap siding and a louvered attic vent have been installed in the gable fields. An original gable roof wing is located on the rear façade.

252. 872 North Parkway Avenue ca. 1935 SY-5763 CB

This is a frame, one- and one-half story Bungalow built ca. 1935. The dwelling has a continuous stone foundation, an exterior of brick veneer with stone veneer on the main façade, a jerkinhead roof of asphalt shingles with exposed roof rafters and one exterior end brick chimney. The full-width, jerkinhead roof porch extends out to a porte-cochere and has exposed roof rafters, battered stone columns and an eight-light rectangular attic window in the gable field. Two entrances are located on the main façade. One entrance is not visible but the other has a ca. 1970, single-light glass and wood door. Both entrance retain their original five-light sidelights and metal security doors. Windows are original nine-over-one double hung wood sash. In the gable field of the main façade is a louvered, rectangular attic vent. On the west façade is a jerkinhead roof bay with two, nine-over-one double hung wood sash windows. On the east façade is a small, ca. 1960, shed roof wing with an exterior of stucco and two-over-two horizontal light double hung metal sash windows.

253. 876 (8) North Parkway Avenue ca. 1935 SY-5764 CB

At this location is a frame, two and one-half story American Foursquare style dwelling built ca. 1935. The dwelling has an exterior of brick veneer, a hipped roof of asphalt shingles and an interior brick chimney. The two-story porch has wrought iron posts, brackets and railings. Both entrances on the main façade have ca. 1980, flush wood doors with original five-light transoms covered with wood panels and metal security doors. Windows are original one-over-one double hung wood sash with wood lintels and sills. On the main façade is a hipped roof dormer with two, six-light fixed windows. A brick beltcourse surrounds the dwelling beneath the 2nd story windows.

254. 882-84 North Parkway Avenue ca. 1935 SY-5765 CB

This is a frame, one-story, H-plan, Minimal Traditional style dwelling built ca. 1935 with Bungalow and Tudor Revival influences. The dwelling has an exterior of brick veneer, a multi-gabled roof of asphalt shingles and one interior central brick chimney. The full-width, gable roof porch with a central cross gable has square brick columns, added wrought iron brackets, a closed brick railing, a concrete floor and a wood louvered attic vent and original, paired six-light attic casement windows in the gable field. Both entrances on the main façade have six-light glass and wood doors with metal security doors. On the east façade is a small projecting gable roof bay and a recessed entrance with an original single-light glass and wood door.

(Garage, ca. 1935, CB) To the rear of the dwelling is a ca. 1935, frame garage with an exterior of shiplap siding, a gable roof of asphalt shingles and paired vertical board hinged doors.

United States Department of the Interior
National Park Service

National Register of Historic Places Continuation Sheet

Section number 7 Page 67

Galloway-Speedway Historic District
Memphis, Shelby County, Tennessee

255. 888 North Parkway Avenue ca. 1935 SY-5766 CB

This is a frame, one-story Airplane Bungalow with an original, full two-story, raised monitor section built ca. 1935. The dwelling has a large, concrete block foundation, an exterior of brick veneer siding, a jerkinhead and hipped roof of asphalt shingles with exposed milled roof rafters and milled brackets and two interior brick chimneys. The full-width hipped and gable roof porch has exposed milled roof rafters, heavy brackets, square brick columns with a header course on the top and bottom and plain concrete capitals on brick piers, a closed brick railing with half-moon drains and a concrete top rail and stick work and stucco in the gable field. The main entrance has a ca. 1990, fanlight and paneled metal door. Windows are original six-over-one double hung wood sash with concrete sills. A concrete water table surrounds the dwelling. In the gable field on the main façade are two, replacement, single-light fixed windows and vinyl siding.

256. 892 North Parkway Avenue ca. 1935 SY-5767 CB

This is a frame, one- and one-half story Airplane Bungalow with a full, two-story, raised monitor roof section built ca. 1935. The dwelling has a continuous stucco covered foundation, an exterior of brick veneer, a jerkinhead roof of asphalt shingles, an interior brick and an exterior end brick chimney with a concrete cap. The full-width, jerkinhead and hipped roof porch extends out to porte-cochere and has exposed roof rafters, knee brace brackets, square brick columns, square brick piers, an open brick railing with a concrete top rail and two, nine-light fixed windows in the gable field. The main entrance has a ca. 1970, solid wood door with original ten-light and single wood panel sidelights and a storm door. Windows are original nine-over-one double hung wood sash with white wrought iron security bars and concrete sills. Protruding jerkinhead roof bays are located on the east and west facades with the west façade having a double set of windows and the east bay only having one window. The full two-story raised gabled monitor roof section has exposed roof rafters and gable clefts.

(Garage, ca. 1940, NCB) Located to the rear of the dwelling is a ca. 1940 frame garage with a gable roof and enclosed with screening to form a makeshift, unattached lanai.

257. 898 North Parkway Avenue ca. 1935 SY-5768 CB

One- and one-half story, frame Bungalow built ca. 1935. The dwelling has a continuous stucco covered foundation, an exterior of brick veneer, a multi-gabled roof of asphalt shingles, two metal flues and one, large exterior end chimney. The full-width, hipped and central gable roof porch extends out to a porte-cochere with square brick columns, a closed brick railing with a concrete top rail and stick work, stucco and two, screened openings in the gable field. The main entrance has an original six-light and wood panel door with an original single-light transom. Windows are original one-over-one double hung wood sash with metal security bars. Located in the gable fields are stick work, stucco and two screened openings. A protruding double line water table surround the dwelling. On the west façade has a triple set of windows. The protruding bay on the east façade has two windows.

(Garage, ca. 1940, CB) Located to the rear of the dwelling is a ca. 1940, frame, one-bay garage with a hipped roof of asphalt shingles with exposed roof rafters, an exterior of weatherboard siding and original hinged vertical board double doors.

258. 902 North Parkway Avenue ca. 1935 SY-5769 CB

This is a frame, one- and one-half story Bungalow built ca. 1935. The dwelling has a continuous stucco covered foundation, an exterior of brick veneer, a jerkinhead and hipped roof of asphalt shingles and an exterior end brick chimney. The full-width, clipped and hipped roof porch extends out to a porte-cochere and has battered brick columns,

United States Department of the Interior
National Park Service

National Register of Historic Places Continuation Sheet

Section number 7 Page 68

Galloway-Speedway Historic District
Memphis, Shelby County, Tennessee

a closed brick railing with a concrete top rail, some replacement wrought iron posts and brackets and stick work and stucco and a six-light fixed window in the gable field. The porch has been enclosed with screen panels. The main entrance door is not visible but it does retain its original ten-light transom, original four-light and wood panel sidelights and a metal security door. Windows are original nine-over-one double hung wood sash with concrete sills. A protruding, double line, brick water table surrounds dwelling. On the west façade is a jerkinhead roof protruding bay with a set of paired windows. A ca. 1950 addition with an exterior of wired brick veneer and an entrance with ca. 1970 fanlight door with a ca. 1970, metal security door was added to the rear façade.

(Garage, ca. 1940, CB) Located to the rear of the dwelling is a ca. 1940, frame, one-bay garage with a hipped roof of asphalt shingles, an exterior of weatherboard siding and wood panel overhead track door.

259. 914 North Parkway Avenue ca. 1925 SY-5770 CB

The property at 914 North Parkway Avenue is a frame, one- and one-half story Bungalow built ca. 1925. The dwelling has an exterior of brick veneer, a hipped roof of asphalt shingles with exposed roof rafters and two exterior end brick chimney. The partial-width, gable roof porch extend out into a patio and has exposed roof rafters, knee brace brackets, square brick columns, a closed brick railing, a metal shed roof awning, an arched ceiling of tongue and groove and a concrete diamond on each column-arched entry. The main entrance has an original, nine-light glass and two wood panel door with a large segmented arch single-light transom with solid course brick trim and Craftsman style, six-diamond light metal and glass sidelights. A secondary entrance on the main façade has a fifteen-light glass and wood door with a segmented arch single-light transom and a screen door. Windows are original one-over-one double hung wood sash set in segmented arched openings with concrete sills. A concrete water table surrounds the dwelling. On the east façade is a shed roof dormer. On the west façade is a one- and one-half story projecting shed roof bay with a three-light fixed attic window in the half-story and a tri-part one-over-one double hung wood sash windows with metal awnings in the first story.

(Garage, ca. 1950, CB) Located to the rear of the dwelling is a ca. 1950, frame garage with a hipped roof of asphalt shingles with exposed roof rafters and vertical board siding.

260. 915 North Parkway Avenue ca. 1930 SY-5771 CB

This is a frame, asymmetrical plan, one- and one-half story Airplane Bungalow with a raised gabled monitor roof section built ca. 1930. The dwelling has a continuous stucco covered foundation, an exterior of brick veneer, a hipped roof of asphalt shingles, and one exterior end and one interior brick and concrete chimneys. The full-width, hipped roof porch has battered brick columns with concrete plinths and concrete down facing arrow designs, a closed brick railing with half moon brick and concrete design drains, a metal awning and modillion blocks. The west end of the porch has an original enclosure of tall, rectangular, thin, Craftsman-style windows. An eyebrow dormer is located on the roofline of the enclosed section of the porch with a five-section fixed window. The main entrance has a Craftsman style glass and wood double door with an original nine-light transom and metal security doors. Windows are original Craftsman style one-over-one double hung wood sash with metal security bars and modillion blocks. A soldier course brick water table surrounds the dwelling. On the west façade is a protruding gable roof bay with brick quioning and three, Craftsman style windows. The raised gabled monitor roof section has exposed roof rafters, Craftsman style windows and stucco in the gable fields. A three-line high brick retaining wall remains between the front lawn and the sidewalk.

United States Department of the Interior
National Park Service

National Register of Historic Places Continuation Sheet

Section number 7 Page 69

Galloway-Speedway Historic District
Memphis, Shelby County, Tennessee

261. 920 North Parkway Avenue ca. 1927 SY-5772 CB

This is a frame, one- and one-half story Airplane Bungalow with a raised monitor roof section built ca. 1927. The dwelling has an exterior of brick veneer, a multi-gabled roof of asphalt shingles, one interior concrete chimney and one exterior end brick chimney. The partial-width, gable roof porch has exposed roof rafters, stone columns and closed brick railing and has been enclosed with windows with metal security bars. The porch extends out to a gable roof porte-cochere that has been enclosed with wood lattice. The main entrance door is not visible due to the enclosed porch but the entrance does retain its original multi-light transom. Windows are original six-over-one double hung wood sash with concrete sills and added metal shed roof awnings. Wood lattice vents are located in the gable fields. The raised monitor roof section has exposed roof rafters.

262. 921 North Parkway Avenue ca. 1927 SY-5773 CB

Located at 921 North Parkway Avenue is a frame, two-story American Foursquare style dwelling built ca. 1927. The dwelling has a continuous stucco covered foundation, an exterior of asbestos shingles and smoothed concrete on the main façade, a hipped roof of asphalt shingles with exposed milled roof rafters and two exterior end stucco covered chimneys. The full-width hipped roof porch has double, square stuccoed concrete columns and a closed stuccoed railing with swags on the east and west facades. The main entrance has an original single-light glass and wood door with an original single-light transom, original single-light and single wood panel sidelights and a metal security door. Windows are original one-over-one double hung wood sash with metal security bars. A wood beltcourse surrounds the dwelling. On the east façade is a shed roof dormer with two window openings.

(Garage w/Shed bay, ca. 1950, NCB) Located to the rear of the dwelling is a ca. 1950, frame, open-bay garage with a shed bay and an exterior of board and batten siding and plywood and a gable roof of asphalt shingles.

263. 924 North Parkway Avenue ca. 1930 SY-5774 CB

This is a frame, one- and one-half story Minimal Traditional dwelling with Tudor Revival style influences built ca. 1930. The dwelling has a continuous concrete foundation, an exterior of brick veneer, a steep pitched gable roof of asphalt shingles and an interior brick chimney. The full-width, triple gable roof porch has square brick columns, a tongue and groove ceiling and a metal railing. On the main façade is an arched recessed corbelled brick entrance with an original arched single-light and wood paneled door with a metal security door. Windows are original eight-over-one and six-over-one double hung wood sash. In the gable fields are stick work and stucco. On the west façade is an attached metal carport.

(Garage, ca. 1930, CB) Located to the rear of the dwelling is a ca. 1930, frame, garage with a gable roof of asphalt shingles, shiplap siding in the gable fields, an enclosed garage door and a pedestrian entrance.

264. 925 & 25A North Parkway Avenue ca. 1915 SY-5775 CB

At this location is a frame, two-story Apartment Building built ca. 1915 with Colonial Revival and Italianate influences. The dwelling has a continuous concrete foundation, an exterior of brick veneer and a flat roof with wood opening. The full-width, two-story, mansard/hipped roof porch has a pedimented cornice, square brick columns and a closed brick railing with a concrete top rail on the 1st floor and original double enclosed tapered wood columns, an open wood baluster railing and an original tongue and groove ceiling on the 2nd floor. On all three (two-1st floor and one-2nd floor) entrances on the main façade have original multi-light glass and wood door with original three-light rectangular transoms. The entrances on the first floor have metal security doors. Windows are original one-over-one double hung wood sash with concrete sills. A soldier brick beltcourse surrounds the dwelling. Metal, stenciled

United States Department of the Interior
National Park Service

National Register of Historic Places Continuation Sheet

Section number 7 Page 70

Galloway-Speedway Historic District
Memphis, Shelby County, Tennessee

diamond shaped attic vents are at the cornice. A ca. 1970, two-story addition with an exterior of vinyl siding was added to the rear façade.

265. 930 North Parkway Avenue ca. 1920 SY-5776 CS

This is a one-story, square brick pump station/wellhouse built ca. 1920. The structure has a continuous concrete foundation, a flat roof with concrete coping and a concrete cornice. The original wood panel door entrances have been replaced with metal fence doors and the windows on the east and west façades are one-over-one double hung wood sash with metal sectional panels and concrete sills. The interior of structure has the original square concrete well. The metal pumping mechanism is positioned a few feet in front of the structure.

266. 931 North Parkway Avenue ca. 1909 SY-5777 CB

This is a frame, one- and one-half story Bungalow built ca. 1909. The dwelling has a continuous stucco covered foundation, an exterior of brick veneer, an exterior end stepped chimney and a ca. 2003, asphalt shingled, side gable roof with brackets. The full-width shed roof porch has exposed roof rafters, a swaged cornice, rusticated stone columns, tapered wood columns on a closed brick railing with a concrete top rail, a concrete floor and steps and a swaged brick step entry. The main entrance has an original single-light and nine wood panel door with an original transom covered with wood panels, original single-light and wood panel sidelight, a metal security door and a screen door. Windows are original one-over-one double hung wood sash with concrete sills. A protruding double line brick water table above a concrete water table surrounds the dwelling. On the east façade is a protruding shed roof pay with a side entry and a window. On the main façade is a large gable roof dormer with exposed roof rafters, three, one-over-one double hung wood sash windows on the main façade and a single, one-over-one double hung wood sash windows on either side. The dormer also has an exterior of asphalt shingles and an attic vent and stucco in the gable field.

267. 935 North Parkway Avenue ca. 1927 SY-5778 CB

One- and one-half story, frame Airplane Bungalow with a full-width, raised hipped roof monitor roof section built ca. 1927. The dwelling has a continuous concrete and stucco covered foundation, an exterior of wired brick veneer, a jerkinhead and hipped roof of asphalt shingles, one interior end and one interior brick chimneys. The full-width, hipped roof porch extends out to a porte-cochere and has battered stone columns and an open concrete railing. The main entrance has a ca. 1980, six wood panel door but still retains its original eight-light transom, original eight-light and wood panel sidelights and a metal security door. Windows are original six-over-one double hung wood sash with concrete sills and metal security bars. A solid course beltcourse and a patterned brick water table surround the dwelling. Stucco and two, single-light fixed windows are in the gable fields.

(Shed, ca. 1990, NCB) Located to the rear of the dwelling is a non-contributing, ca. 1990, metal and wood shed.

268. 936 North Parkway Avenue ca. 1925 SY-5779 CB

This is a frame, one- and one-half story Airplane Bungalow with a full, raised jerkinhead monitor roof section built ca. 1925. The dwelling has a continuous concrete foundation, an exterior of wired brick veneer, a jerkinhead roof of asphalt shingles, one exterior end and one interior brick chimneys. The full-width hipped and jerkinhead roof porch extends out to a porte-cochere and has battered brick columns, a closed brick railing with a concrete top rail and stucco and a four-light fixed rectangular window in the gable field. The main entrance has an original Craftsman style, single-light glass and wood panel door with an original ten-light transom and original six-light and wood panel sidelights and a large concrete lintel. A side entrance on the east façade has an original Craftsman style single light and wood panel door with a storm door. Windows are original Craftsman style one-over-one double hung wood sash

United States Department of the Interior
National Park Service

National Register of Historic Places Continuation Sheet

Section number 7 Page 71

Galloway-Speedway Historic District
Memphis, Shelby County, Tennessee

with large concrete lintels and sills. A header course beltcourse and a protruding double line brick water table surround the dwelling. A protruding bay on the west façade has a triple set of windows. The raised jerkinhead monitor roof section has exposed roof rafters, an exterior of stucco and some enclosed window openings.

(Shed, ca. 1970, NCB) Located to the rear of the dwelling is a ca. 1970, frame shed with a shed roof of corrugated metal panel, an exterior of plywood, one-over-one double hung metal windows and a two panel wood door.

269. 940 North Parkway Avenue ca. 1923 SY-5780 CB

This is a frame, one- and one-half story Bungalow built ca. 1923. The dwelling has a continuous poured concrete foundation, an exterior of brick veneer, a hipped and front gable roof of asphalt shingles and one interior end brick chimney. The full-width, hipped and gable roof porch extends out to a porte-cochere with battered stone columns, a closed stone railing with a concrete top rail and stucco and a four-light fixed window in the gable field. The main entrance door is not visible but the entrance does retain its original eight-light transom, original six-light and wood panel sidelights and a metal security door. Windows are original nine-over-one double hung wood sash with concrete sills. A protruding double line brick water table surrounds the dwelling. In the gable field on the main façade are stucco and two window openings - one has a rectangular, four-light fixed window and the other has an AC unit installed in the space. On the west façade is a protruding bay with a triple set of windows. A ca. 1990, small, gable roof porch addition has been partially enclosed on the rear façade.

270. 941 North Parkway Avenue ca. 1917 SY-5781 CB

The residence at this location is a frame, one- and one-half story Bungalow built ca. 1917. The dwelling has an exterior of stucco, a continuous concrete foundation, a jerkinhead roof of asphalt shingles and two, exterior end concrete and stucco covered chimneys. The full-width, hipped and jerkinhead roof porch has battered brick columns, a metal railing and stucco and a painted-in, six-light fixed window in the gable field. To entrances are located on the main façade. One entrance has an original eight-light glass and wood panel door with a wood panel covered transom and the other entrance has a ca. 1980, six wood panel door with an original wood panel covered transom and original four-light sidelights covered with shutters. Both entrances have black screen doors. Windows are original six-over-one double hung wood sash. In the gable field on the main façade are stucco and two window openings - one with a six-light fixed window and the other with a screen panel. A wood beltcourse and water table surrounds the dwelling. On the west façade is a protruding jerkinhead bay with two windows. A ca. 1970, addition with an exterior of aluminum siding has been added to the rear façade.

271. 944 North Parkway Avenue ca. 1923 SY-5782 CB

This is a frame, one and one-half story Bungalow built ca. 1923. The dwelling has a continuous stucco covered foundation, an exterior of brick veneer, a jerkinhead roof of asphalt shingles and one exterior end brick chimney with a clay cap. The full-width, hipped and jerkinhead roof porch has battered stone columns, an open stone railing with a concrete top rail and stucco and one screen paneled window opening in the gable field. The main entrance has an original Craftsman style single-light glass and wood panel door with an original Craftsman style single light transom and original Craftsman style single-light and wood panel sidelights with security bars and a metal security door. Windows are original Craftsman style one-over-one double hung wood sash with concrete sills. A soldier course brick beltcourse surrounds the dwelling. In the gable field on the main façade are two, four-light fixed windows and stucco. On the west façade is a protruding bay with a triple set of windows.

United States Department of the Interior
National Park Service

National Register of Historic Places Continuation Sheet

Section number 7 Page 72

Galloway-Speedway Historic District
Memphis, Shelby County, Tennessee

272. 945 North Parkway Avenue ca. 1927 SY-5783 CB

Located at 945 North Parkway Avenue is a frame, one- and one-half story Airplane Bungalow with a raised monitor roof section built ca. 1927. The dwelling has a continuous stucco covered foundation, an exterior of brick veneer, a jerkinhead roof of asphalt shingles and two interior brick chimneys. The full-width, hipped and gable roof porch has exposed roof rafters, battered stone columns, a metal railing and stick work, stucco and a eight-light fixed window in the gable fields. The porch extends to a porte-cochere supported by replacement metal posts. The main entrance has a solid wood door with a storm door. Windows are original twelve-light casement windows with concrete sills. On the main façade, one set of the casement windows has been covered with wood panels. A soldier course brick beltcourse surrounds the dwelling. Stick work and stucco are located in the gable fields along with two window openings on the main facade, one of which has been covered with a wood panel and the other has a nine-light fixed window. The 2nd story sleeper section has a hipped roof of asphalt shingles with exposed roof rafters and an exterior of vinyl siding.

(Garage, ca. 1950, CB) Located to the rear of the dwelling is a ca. 1950, frame garage.

273. 950 North Parkway Avenue ca. 1923 SY-5784 CB

This is a frame, one-story Bungalow built ca. 1923. The dwelling has an exterior of wired brick veneer, a continuous concrete foundation, a front gable roof of asphalt shingles and an exterior end brick chimney with a concrete cap. The full width, gable and hipped roof porch extends out to a porte-cochere and has tapered brick columns on brick piers, a closed brick railing with a concrete top rail and half moon concrete and brick design drains. Two window openings with screening, partial brackets and stucco and stick work are in the gable field of the porch. The main entrance has an original multi-light glass and wood door with original twelve-light and wood panel sidelights. Windows are original three-over-one vertical light double hung wood sash windows with concrete sills and metal security bars. A patterned brick water table and sailor course brick beltcourse surround the dwelling. In the gable field on the main façade partial brackets, stick work, stucco, a sliding metal window and an AC unit filled window opening.

274. 954 North Parkway Avenue ca. 1923 SY-5785 CB

This is a frame, one-story Bungalow built ca. 1923. The dwelling has a continuous brick foundation, an exterior of wired brick veneer, a hipped and gable roof of asphalt shingles with exposed milled roof rafters and one interior an done interior end concrete chimney with a single cap. The full-width gable roof porch has double wood columns on brick piers, a closed brick railing with a concrete top rail and a tile floor. The main entrance has an original Craftsman style door with an original single-light transom. Windows are original nine-over-one double hung wood sash with soldier brick lintels and brick sills. On the east and west facades are hipped roof dormers with two, one-over-one double hung metal sash windows. A concrete water table and a soldier brick beltcourse surround the dwelling. In the gable field on the main façade are two, small, rectangular three-light fixed windows and stucco.

(Garage, ca. 1940, CB) Located to the rear of the dwelling is a ca. 1940, two-bay garage with a hipped roof with exposed roof rafters, a pedestrian entrance with a metal door and two replacement metal overhead track doors with fanlight windows.

275. 955 North Parkway Avenue ca. 1965 SY-5786 NCB

This is a two-story, brick veneer Apartment Building built ca. 1965. The building is non-contributing to the district.

United States Department of the Interior
National Park Service

National Register of Historic Places Continuation Sheet

Section number 7 Page 73

Galloway-Speedway Historic District
Memphis, Shelby County, Tennessee

276. 960 North Parkway Avenue ca. 1923 SY-5787 CB

This is a frame, one- and one-half story Bungalow built ca. 1923. The dwelling has a rusticated stone and stucco covered foundation, an exterior of brick and stone veneer, a gable roof of asphalt shingles and one interior brick chimney. The full-width, gable and shed roof porch has battered stone columns and a closed brick railing. The main entrance has an original nine-light glass and wood door with original six-light and wood panel sidelights. Windows are original one-over-one double hung wood sash with metal security bars. On the main facade is a shed roof dormer with four, single-light fixed windows and shuttered window openings. A concrete water table and a header course brick beltcourse surround the dwelling. On the east facade is a gable roof protruding bay with two windows.

277. 961 North Parkway Avenue ca. 1925 SY-5788 CB

Standing at 961 North Parkway Avenue is a frame, two-story, Colonial Revival style dwelling built ca. 1925. The dwelling has a continuous brick foundation, an exterior end brick chimney, a flat roof with a decorative brick patterned cornice and an exterior of brick veneer with decorative yellow brick corner quoining. The one-story, flat roof porch has a patio extension to the east side, a matching decorative brick cornice with varying rows of stretcher/header/soldier course red and yellow brick, square brick columns with concrete plinths, one wrought iron column, a closed brick railing with yellow and red soldier and stretcher course patterns, a brick floor and steps. The brick walkway to the porch steps has original brick piers and a wrought iron railing at the sidewalk. The main entrance has an original single-light glass and wood door with an original single-light rectangular transom, a soldier course lintel and a metal security door. Windows are original one-over-one double hung wood sash on the first floor and original six-over-one double hung wood sash on the 2nd floor. Windows have soldier course brick lintels and concrete sills. The dwelling has a soldier course yellow brick water table surrounding the dwelling. Basement windows are original single-light glass rectangular windows with textured glass and metal exterior security bars. An original, one-story shed roof wing with a brick exterior, one-over-one wood sash windows and a parapet roofline capped with terra cotta. Attached to the original wing is a small, one room hipped roof, projecting bay. The original decorative brick pattern detailing is in excellent condition and extensive. The decorative brick cornice has alternate red vertical and yellow horizontal soldier brick course brick framed by upper and lower header courses, then a stretcher course, then a header course. Beneath the cornice are three, small square metal vents. Beneath the vents is a band of soldier course brick. At the southeast (rear) corner of the dwelling is a short brick wall that extends to the east from the corner of the dwelling to a wood fence that encloses the rear yard. This small brick wall has a decorative diamond pattern of yellow and red brick. The wall ends at a brick column with decorative stretcher/header pattern yellow and red brick.

278. 964 North Parkway Avenue ca. 1923 SY-5789 CB

This is a frame, one- and one-half story Bungalow built ca. 1923. The dwelling has a continuous stucco covered and rusticated stone block foundation, an exterior of wired brick and stone veneer, a jerkinhead roof of asphalt shingles and one interior brick chimney. The full-width, gable roof porch has battered stone columns, a closed rusticated stone railing with a gray concrete top rail and stucco and a single-light fixed window in the gable field. The main entrance has an original nine-light glass and wood door with original six-light and single wood panel sidelights and a metal security door. Windows are original one-over-one double hung wood sash with metal security bars. On the main facade is a shed roof dormer with three shuttered openings. A concrete water table surrounds the dwelling. On the east facade is a protruding gable roof bay with two windows.

United States Department of the Interior
National Park Service

National Register of Historic Places Continuation Sheet

Section number 7 Page 74

Galloway-Speedway Historic District
Memphis, Shelby County, Tennessee

279. 965 North Parkway Avenue ca. 1920 SY-5790 CS

This is a one-story, square brick pump station/wellhouse built ca. 1920. The structure has a continuous concrete foundation, a flat roof with concrete coping and a concrete cornice. The original wood panel door entrances have been replaced with metal fence doors and the windows on the east and west façades are one-over-one double hung wood sash with metal sectional panels and concrete sills. The interior of structure has the original square concrete well. The metal pumping mechanism is positioned a few feet in front of the structure.

280. 970 North Parkway Avenue ca. 1917 SY-5791 CB

This is a frame, one-story Bungalow built ca. 1917. The dwelling has a continuous stucco covered foundation, an exterior of brick veneer, a jerkinhead roof of asphalt shingles with exposed roof rafters and wide eaves with wood brackets and one interior brick chimney. The full-width, hipped roof porch extends into a porte-cochere and has been enclosed with panels and tapered wood columns on piers. Brackets are in the eaves of the porch. The main entrance has a three-vertical light glass and wood door with a metal security door. Windows are original nine-over-one double hung wood sash. A header course water table and beltcourse surround the dwelling. On the east façade is a projecting bay with paired, nine-over-one double hung wood sash windows. In the gable field on the main façade are paired, nine-light fixed attic windows.

281. 971 North Parkway Avenue ca. 1915 SY-5792 CB

Located at 971 North Parkway Avenue is a frame, two-story remodeled American Foursquare style dwelling built ca. 1915. The dwelling has an exterior of stucco, a hipped roof of asphalt shingles and an interior end brick chimney with a cap. The original porch has been removed. The centrally located main entrance door is not visible but it does have a ca. 1990, metal and glass security door and retains its original single-light rectangular transom. Between the first and second floors is a shed roof cornice of asphalt shingles with a central arch over the main entrance. The cornice has large brackets and a tongue and groove ceiling. Windows are one-over-one double hung wood sash with metal shed roof awnings on the side facades. On the main façade is a bay window with three, one-over-one double hung wood sash windows.

282. 974 North Parkway Avenue ca. 1923 SY-5793 CB

This is a frame, one- and one-half story Bungalow built ca. 1923. The dwelling has an exterior of brick veneer, a jerkinhead roof of asphalt shingles and an interior brick chimney. The full-width, clipped and hipped roof porch has knee brace brackets, wrought iron columns, brackets on brick piers, a closed brick railing and a four-light fixed attic window in the gable field. The main entrance door is not visible but the entrance does retain its original four-light and wood panel sidelights with metal security bars. Windows are original one-over-one double hung wood sash with some metal awnings. A small projecting window bay on the east façade has exposed roof rafters. On the main façade is a jerkinhead roof dormer with three, four-light fixed windows and knee brace brackets. Knee brace brackets are also located in the other gable fields.

(Garage, ca. 1930, CB) Located to the rear of the dwelling is a ca. 1930, two-bay, frame garage with an exterior of aluminum siding and vertical wood panel double doors.

283. 975 North Parkway Avenue ca. 1927 SY-5794 CB

This is a frame, one- and one-half story Airplane Bungalow with a raised monitor roof section built ca. 1927. The dwelling has an exterior of brick veneer, a multi-gabled roof of asphalt shingles, one interior concrete and one exterior end brick chimneys. The full-width, gable roof porch extends into a porte-cochere and has battered brick columns, a

United States Department of the Interior
National Park Service

National Register of Historic Places Continuation Sheet

Section number 7 Page 75

Galloway-Speedway Historic District
Memphis, Shelby County, Tennessee

metal open railing and two, two-light fixed attic windows in the gable field. The main entrance has an original fifteen-light glass and wood door with original five-light sidelights. Windows are original nine-over-one double hung wood sash. In the gable field on the main façade are two, single-light fixed attic windows.

284. 980 North Parkway Avenue ca. 1923 SY-5795 CB

One- and one-half story, frame Bungalow built ca. 1923. The dwelling has a continuous stucco covered foundation, an exterior of brick veneer, a hipped roof of asphalt shingles with brackets and one exterior end brick chimney with a chimney cap and diamond and square concrete decorative panels. The full-width, hipped and gable roof porch has modillion blocks, a porte-cochere extension, square wood columns with painted brick detailing and wood capitals on square brick piers, a closed brick railing and a keyhole opening in the gable field. The main entrance has a single-light glass and wood door with an original single-light transom, metal security door and original dragon-motif iron lamps with round globes flanking the entry. Windows are original one-over-one double hung wood sash with paired sets on the main façade. A concrete beltcourse surrounds the dwelling. On the west façade is a projecting gable roof bay with oversized able returns and brackets. Also located on the west façade are original multi-light, stained glass sash windows flanking the chimney.

(Garage, ca. 1923, CB) Located to the rear of the dwelling is a ca. 1923, frame, garage with a hipped roof and sliding wood doors.

285. 981 North Parkway Avenue ca. 1927 SY-5796 CB

This is a frame, one- and one-half story Airplane Bungalow with a raised monitor roof section built ca. 1927. The dwelling has an exterior of brick veneer, a multi-gabled roof of asphalt shingles with paired brackets and one interior end brick chimney with a clay chimney cap. The full-width, side gable roof porch has a central gable over the entry, a porte-cochere extension, paired brackets, a tongue and groove ceiling, square stone columns which arch at the bottom and an open wood railing. The end columns of the porch and the porte-cochere have stone buttresses. The main entrance has a multi-light glass and wood door with original ten-light sidelights and an original seven-light transom. Windows are original Craftsman style, one-over-one double hung wood sash. Paired, four-light fixed attic windows are located in the gable field of the porch and on the main façade.

(Garage, ca. 1950/1990, NCB) Located to the rear of the dwelling is a non-contributing, ca. 1950, frame, two-open bay garage rebuilt ca. 1990 with a hipped roof of asphalt shingles and an exterior of aluminum siding.

286. 984 North Parkway Avenue ca. 1922 SY-5797 CB

This is a frame, one-story Bungalow built ca. 1922. The dwelling has a continuous concrete foundation, an exterior of brick veneer, a jerkinhead roof of asphalt shingles and an interior brick chimney with two caps. The full-width, hipped roof porch has short square wood columns on piers and a closed brick railing. The main entrance has an original four-light glass and wood door with a metal security door. Windows are original one-over-one double hung wood sash. On the west façade is a projecting jerkinhead roof bay. In the gable field on the main façade is a rectangular metal louvered vent. The eaves are covered by vinyl soffits.

287. 985 North Parkway Avenue ca. 1915 SY-5798 CB

This is a frame, one- and one-half story Airplane Bungalow with a raised hipped monitor roof section built ca. 1915. The dwelling has an exterior of stucco and brick veneer, a hipped roof with exposed roof rafters, one interior brick flue and one interior brick chimney. The full-width, jerkinhead and hipped roof porch has a stucco covered arched

United States Department of the Interior
National Park Service

National Register of Historic Places Continuation Sheet

Section number 7 Page 76

Galloway-Speedway Historic District
Memphis, Shelby County, Tennessee

cornice/frieze which connects square brick columns and a closed brick railing. The main entrance has a ca. 1990, paneled wood/metal door but retains its original single-light rectangular transom, original single-light and wood panel sidelights with metal security bars. Windows are Craftsman style, one-over-one and plain, one-over-one double hung wood sash. On the main façade is a hipped roof dormer with two, six-light fixed windows. On the side façade is a shed roof dormer with one window.

288. 990 North Parkway Avenue ca. 1921 SY-5799 CB

At 990 North Parkway Avenue is a frame, one- and one-half story Bungalow built ca. 1921. The dwelling has an exterior of brick veneer, a jerkinhead roof of asphalt shingles with exposed roof rafters and one exterior end brick chimney with decorative square and diamond panels and brick detailing. The full-width, hipped gable roof has a central jerkinhead and has exposed roof rafters, a porte-cochere extension, battered stone columns, a closed brick railing with arched openings, keystones and cornerstones and two, single-light fixed attic windows in the gable field. The main entrance has an original multi-light glass and wood door with its original eight-light transom and original sidelights. Windows are original one-over-one double hung wood sash with wood sills. On the east façade is a projecting jerkinhead roof bay with three, one-over-one double hung wood sash windows and a segmented arched attic window in the gable field.

(Garage, ca. 1945, CB) Located to the rear of the dwelling is a ca. 1945, frame, two-bay garage with a gable roof of asphalt shingles and vertical board hinged double doors.

289. 991 North Parkway Avenue ca. 1915 SY-5800 CB

This is a frame, one- and one-half story Bungalow with a raised monitor roof section built ca. 1915. The dwelling has an exterior of brick veneer and stucco, a hipped roof of asphalt shingles with exposed roof rafters, one exterior end and one interior brick chimneys. The full-width, hipped roof porch has large brackets, an arched frieze/cornice, square brick columns and a closed brick railing. The main entrance has a ca. 1950, six wood panel door but retains its original single-light transom and original single-light glass and wood sidelights. Windows are original Craftsman style and plain one-over-one double hung wood sash. On the main façade is a hipped roof dormer with two, single-light fixed windows.

290. 994 North Parkway Avenue ca. 1918 SY-5801 CB

Standing at 994 North Parkway Avenue is a frame, one- and one-half story, central passage plan, front gable dwelling built with Bungalow influences ca. 1918. The dwelling has an exterior of stucco and brick veneer, a multi-gabled roof of asphalt shingles with exposed roof rafters and two interior central brick chimneys. The full-width, hipped roof porch has exposed roof rafters, square brick columns, and a closed brick railing. The door to the main entrance is not visible but the entrance does retain its original four-light and single wood panel sidelights. Windows are original one-over-one double hung wood sash with metal security bars. On the east façade is a gable roof bay with a projecting gable. Knee brace brackets and a square louvered vent flanked by single-light fixed attic windows are in the gable field on the main façade.

291. 995 North Parkway Avenue ca. 1922 SY-5802 CB

At this location is a frame, two-story American Foursquare style dwelling built ca. 1922. The dwelling has an exterior of asbestos shingle siding, a hipped roof of asphalt shingles with exposed roof rafters and an exterior end brick chimney. The wraparound, hipped roof porch has a gable roof over the entry, exposed roof rafters, screen panels and a closed stuccoed railing. On the east façade of the wraparound porch is a small, hipped roof projecting bay. The main

United States Department of the Interior
National Park Service

National Register of Historic Places Continuation Sheet

Section number 7 Page 77

Galloway-Speedway Historic District
Memphis, Shelby County, Tennessee

entrance has an original large, oval single-light glass and wood door. Windows are ca. 2000, one-over-one double hung vinyl sash. On the main façade is a gable roof dormer with two attic vent openings. An original two-story side gable wing was added to the rear façade.

292. 999 North Parkway Avenue ca. 1925 SY-5803 CB

This is a frame, one- and one-half story Airplane Bungalow with a raised jerkinhead monitor roof section built ca. 1925. The dwelling has an exterior of brick veneer, a jerkinhead roof of asphalt shingles with exposed roof rafters and an exterior end brick chimney. The full-width, hipped and central jerkinhead roof extends into a porte-cochere and has exposed roof rafters, battered stone columns, a closed stone railing and a three-vertical light fixed attic window in the gable field. The main entrance has an original ten-light glass and wood panel door with an original single-light rectangular transom and a metal security door. Windows are original Craftsman style, one-over-one double hung wood sash with concrete sills and metal security bars. On the west façade is an original projecting shed roof bay window.

293. 1000 North Parkway Avenue ca. 1913 SY-5804 CB

This is a frame, one-story Bungalow built ca. 1913. The dwelling has an exterior of brick veneer, a hipped roof with a projecting gable bay on the main façade and bracketed eaves and one interior and one interior end brick chimneys. The full-width, incised porch has brick columns, decorative wrought iron brackets, added wrought iron posts, a closed brick railing and a sunburst pattern in the gable field. The main entrance has an original multi-light glass and wood door with an original nine-light transom and original six-light sidelights. Windows are original one-over-one double hung wood sash with metal security bars.

294. 1004 North Parkway Avenue ca. 1970 SY-5805 NCB

This is a ca. 1970, one-story brick veneer dwelling.

295. 1005 North Parkway Avenue ca. 1927 SY-5806 CB

The residence at this location is a frame, two-story American Foursquare style dwelling built ca. 1927 with Tudor Revival and Bungalow style influences. The dwelling has one interior concrete chimney, a large brick and stone, exterior end chimney with an arched cap and stone castellated top on the main façade, an exterior of stone and brick veneer, a asphalt shingled hipped roof with a flare and a stone skirt wall. The single bay gable front porch has exposed roof rafters, square stone columns on stone piers. The porch roof extends into a narrow side gable roof porte-cochere with similar stone columns for support. The porch floor continues the width of the façade as a patio and has an enclosed stone railing. The main façade has a large central projecting, two-story bay, in the center of which is the large brick and stone two-story chimney. The stonework on the chimney extends into an arch that connects to a stone porch columns that has a small brick lined arched opening in the center. The arch has a central stone keystone and voussoirs. The archway creates a small alcove to a secondary entrance that has a ca. 1970, single-light glass and wood door. Adjacent to the entrance is an original, tiny narrow two-panel storage door that leads to the chimney. The main entrance has ca. 1990, paneled wood door with an original single-light, rectangular transom and original sidelights covered with louvered shutters. Windows are four-over-one and one-over-one double hung wood sash. On the main façade is a hipped roof dormer with two, one-over-one double hung wood sash windows. On the first floor main façade is an arched brick-lined opening that has been filled in with concrete.

United States Department of the Interior
National Park Service

National Register of Historic Places Continuation Sheet

Section number 7 Page 78

Galloway-Speedway Historic District
Memphis, Shelby County, Tennessee

296. 1010 North Parkway Avenue ca. 1922 SY-5807 CB

This is a frame, one- and one-half story Airplane Bungalow with a raised monitor roof section built ca. 1922. The dwelling has an exterior of wired brick veneer, a multi-gabled roof of asphalt shingles and two exterior end brick chimneys with chimney caps and decorative diamond shaped tile and brick detailing. The partial-width, gable roof porch extends to a patio on the east façade and porte-cochere on the west façade. The porch has battered stone columns, a closed stone railing and horizontal diamond-lights divided in two in the gable field. The main entrance has a ca. 1980, flush wood door but it still retains its original eight-light transom, original ten-light sidelights with metal security bars and a metal security door. A secondary entrance on the east façade has a ca. 1990, wood panel door with an original segmented arched canopy supported by knee brace brackets. Windows are original three-over-one vertical light and one-over-one double hung wood sash. The large, raised monitor roof section has one-over-one double hung wood sash windows and an exterior of stucco.

(Garage, ca. 1950, CB) To the rear of the dwelling is a ca. 1950, frame garage with a hipped roof of asphalt shingles, an exterior of asbestos shingle siding and two, metal overhead track doors.

297. 1011 North Parkway Avenue ca. 1925 SY-5808 CB

One- and one-half story, frame Bungalow built ca. 1925 and has been neglected, is severely deteriorated and currently under renovation. Evidence of charred wood is apparent. The dwelling has a jerkinhead roof of asphalt shingles with exposed milled roof rafters, an exterior of brick veneer and two interior brick covered with concrete chimneys. The full-width, hipped roof porch on the main (N) façade has square brick columns on brick piers with a pierced brick railing. The porch floor extends slightly to the west as a patio. All doors and windows are presently covered with plywood panels. On the façade is a jerkinhead roof dormer. In the gable field of the main facade are two window openings.

(Garage, ca. 1925, CB) To the rear of the dwelling is a ca. 1925, frame garage with an exterior of weatherboard siding, a hipped roof of asphalt shingles with exposed roof rafters and two garage bays. One bay is covered with a plywood panels while the other has a ca. 1970, overhead track garage door.

298. 1020 North Parkway Avenue ca. 1912 SY-5809 CB

This is a frame, one- and one-half story Airplane Bungalow with a standing metal seam raised hipped monitor roof section built ca. 1912. The dwelling has an exterior of stucco and half-timbering, a standing metal seam, jerkinhead roof with exposed roof rafters and an interior end brick chimney. The full-width, jerkinhead and hipped roof porch has exposed roof rafters, square stone columns, a closed stone railing and a four-light fixed rectangular attic window in the gable field. The main entrance has an original nine-light glass and two-panel wood design door with original three-light sidelights and an original ten-light transom. Windows are original Craftsman style four-over-one vertical light double hung wood sash windows. In the gable field on the main façade is a set of paired, two-light fixed attic window. On the west façade is a jerkinhead roof bay.

(Garage, ca. 1930, CB) To the rear of the dwelling is a ca. 1930, frame garage currently being renovated with a hipped roof and plywood panel doors (the siding has been removed).

United States Department of the Interior
National Park Service

National Register of Historic Places Continuation Sheet

Section number 7 Page 79

Galloway-Speedway Historic District
Memphis, Shelby County, Tennessee

299. 1023 North Parkway Avenue ca. 1922 SY-5810 CB

Located at 1023 North Parkway Avenue is a frame, one- and one-half story Airplane Bungalow with a full, two-story raised monitor roof section on the rear façade built ca. 1922. The dwelling has an exterior of brick veneer, a hipped and gable roof of asphalt shingles, projecting gable bays and brackets, one interior end brick and concrete chimney with brick detailing at the top and one interior brick chimney with a concrete cap. The single bay, gable roof porch extends to a patio on the east side and a porte-cochere on the west side. The porch has square brick columns with concrete cross design detailing and a closed brick railing. The main entrance has an original fifteen-light glass and wood door with an original three-section transom (a three-light flanked by two-light) and original eight-light sidelights. A secondary entrance on the main façade leading to the patio area has an original paired, eight-light glass and wood doors with an original three-section (a four-light flanked by two-light) transom and original eight-light sidelights. An entrance on the east façade has an original fifteen-light glass and wood door with a small flat roof canopy supported by oversized fluted brackets. Windows are original, six-over-six double hung wood sash with metal security bars. On the east façade is a projecting bay window with four, six-over-six double hung wood sash windows. A curved driveway leads to and through the porte-cochere. In the gable field of the porte-cochere is a circular opening with a scroll design and floral band. In the gable fields are large scroll brackets, a large central rectangular panel with shield relief and scroll designs. Beneath is a female face/head in the keystone and a band of floral relief panels.

(Garage, ca. 1922, CB) To the rear of the dwelling is a ca. 1922, frame garage with a hipped roof of asphalt shingles with exposed roof rafters, an exterior of weatherboard and two sets of paired, six-light and three vertical panel hinged garage doors.

300. 1026 North Parkway Avenue ca. 1915 SY-5811 CB

This is a frame, one- and one-half story Bungalow built ca. 1915. The dwelling has an exterior of brick veneer, an asphalt shingled hipped roof with a flare, an interior metal flue and an interior concrete chimney. The full-width, hipped roof porch has square brick columns, a closed brick railing and has been partially enclosed with screen panels. The main entrance has a ca. 1990, glass and wood door but still retains its original three-part transom and original multi-diamond light sidelights. Windows are original multi-diamond light-over-one double hung wood sash. On the main and west facades are flared, hipped roof dormers with two, single-light fixed windows.

301. 1027 North Parkway Avenue ca. 1920 SY-5812 CB

This is a frame, one- and one-half story Bungalow built ca. 1920. The dwelling has a continuous concrete block foundation, an exterior of brick veneer, a jerkinhead roof of asphalt shingles and one exterior end and one interior brick chimneys. The full-width, jerkinhead and hipped roof porch extends into a porte-cochere with battered brick columns with concrete plinths, an open brick railing with a concrete top rail and stucco and two window opening-one with a three-light rectangular awning window in the gable field. The main entrance has a ca. 1970, solid wood door but retains its original four-light transom covered with screening and a metal security door. Windows are original, Craftsman style, one-over-one double hung wood sash with concrete sills. In the gable fields are two window openings and stucco. A soldier course brick water table and beltcourse and a wood cornice surrounds the dwelling. On the west façade is a protruding hipped roof bay with two windows.

302. 1032 North Parkway Avenue ca. 1912 SY-5813 CB

At 1032 North Parkway Avenue is a frame, one- and one-half story Bungalow built ca. 1912. The dwelling has a continuous brick foundation, an exterior of brick veneer and stucco and a gable roof of asphalt shingles. The full-width shed roof porch has square brick columns, a closed brick railing with a concrete top rail and a wood wheelchair

United States Department of the Interior
National Park Service

National Register of Historic Places Continuation Sheet

Section number 7 Page 80

Galloway-Speedway Historic District
Memphis, Shelby County, Tennessee

ramp. The main entrance has an original nine-light glass and wood panel door with original six-light and single wood panel sidelights and a metal security door. Windows are original one-over-one double hung wood sash with metal security bars. A concrete water table surrounds the dwelling. On the main façade is a shed roof dormer with four, single-light fixed windows with metal security bars. On the east façade is a protruding gable roof bay with two windows.

303. 1033 North Parkway Avenue ca. 1914 SY-5814 CB

Located at 1033 North Parkway Avenue is a frame, two-story, remodeled American Foursquare style dwelling built ca. 1914. The dwelling has an exterior of stucco with stick work detailing on the 2nd floor, an asphalt shingled hipped roof with a flare and one interior concrete chimney. The full-width, hipped roof porch extends out to carport with a large wood cornice, two battered stucco covered concrete columns, two square stucco covered columns and a closed stucco covered railing with a concrete top rail. The main entrance has an original single-opaque light glass and wood door with an original transom covered with wood panels and metal security boards and original single-light and wood panel sidelights with metal security bars. Windows are nine-over-one and one-over-one double hung wood sash with some nine-over-one double hung vinyl sash replacements. On the main façade is a hipped roof dormer with two, six-light fixed rectangular windows. On the east façade is a protruding hipped roof bay with three windows. Attached to the rear façade is an original one-story wing.

304. 1036 North Parkway Avenue ca. 1912 SY-5815 CB

This is a frame, one- and one-half story Bungalow built ca. 1912 and is currently under repair. The dwelling has an exterior of stucco and stone veneer, a jerkinhead roof of asphalt shingles and one interior brick chimney. The full-width gable roof porch has square stone columns, a closed stone block railing with a concrete top rail, brick piers with concrete plinths and stucco and a single-light fixed window in the gable field. The main entrance has an original nine-light glass and wood panel door with original six-light and wood panel sidelights. Windows are original one-over-one double hung wood sash with security bars. A concrete water table surrounds the dwelling. On the east façade is a protruding gable roof bay with two windows.

(Garage, ca. 1931. CB) To the rear of the dwelling is a ca. 1931, frame, two-bay garage with a hipped roof of asphalt shingles, an exterior of weatherboard siding and one set of vertical board double hinged doors (one set is missing).

305. 1037 North Parkway Avenue ca. 1922 SY-5816 CB

This is a frame, one- and one half story Airplane Bungalow with a raised hipped monitor roof section built ca. 1922. The dwelling has an exterior of brick veneer, a continuous poured concrete foundation, a jerkinhead roof of asphalt shingles and one exterior end brick and one interior brick chimney. The full-width, hipped and central jerkinhead roof porch extends off the east side to a patio and has vinyl soffits, a vinyl cornice, battered stone columns with plinths, an open concrete railing with a concrete top rail and a three-light rectangular fixed window and stucco in the gable field. The main entrance has an original eight-light glass and wood panel door with an original single-light transom and a metal security door. Windows are Craftsman style, one-over-one double hung wood sash with concrete sills and metal security bars. In the gable field on the main façade are stucco, two windows openings and a vinyl cornice. A soldier course water table and a sailor course beltcourse surround the dwelling. The raised hipped monitor roof section an exterior of vinyl siding. On the west façade is a protruding shed roof bay with two windows. A ca. 1975, vinyl sided addition has been added to the rear façade.

United States Department of the Interior
National Park ServiceNational Register of Historic Places
Continuation SheetSection number 7 Page 81Galloway-Speedway Historic District
Memphis, Shelby County, Tennessee**306. 1041 North Parkway Avenue ca. 1920 SY-5817 CS**

This is a one-story, square wired brick pump station/wellhouse built ca. 1920. The structure has a continuous concrete foundation, a flat roof with concrete coping and a concrete cornice. The original wood panel door entrances have been replaced with metal chain link fence doors and the single window opening on the east and west façades have been replaced with an open-patterned brick infill but still retain their concrete sills. The interior of structure has the original square concrete well. The metal pumping mechanism is positioned a few feet in front of the structure surrounded by chain link fence.

307. 1042 North Parkway Avenue ca. 1912 SY-5818 CB

At this location is a frame, one- and one-half story Bungalow built ca. 1912. The dwelling has a continuous concrete foundation, an exterior of brick veneer, a jerkinhead and gable roof of asphalt shingles and an interior brick chimney. The full-width, hipped roof porch has a porte-cochere extension, square brick columns, an open brick railing with a concrete top rail, some replacement wrought iron posts and decorative brackets. A portion of the east façade of the porch has been removed. The main entrance door is not visible but does have a metal security door. Windows are original twelve-over-one and one-over-one double hung wood sash with brick sills. A soldier brick water table surrounds the dwelling. Located in the gable fields are knee brace brackets, stick work, stucco and two, nine-light fixed windows on the main façade. An original wing is located on the rear façade.

(Shed, ca. 1980, NCB) To the rear of the dwelling is a non-contributing, ca. 1980, metal shed. Etched in the city sidewalk in front of the house are the words, "Laid 1949 By Cook & Nichol".

308. 1046-48 North Parkway Avenue ca. 1972 SY-5819 NCB

This is a rectangular plan, frame duplex built ca. 1972. The duplex has an exterior of wired brick veneer, a continuous concrete foundation and a hipped roof of asphalt shingles. On the main façade are two matching incised roof porches supported by wrought iron posts. The two main entrances have original single-light and wood panel doors with metal security doors and original storm doors. Windows are replacement one-over-one double hung vinyl sash.

(Shed, ca. 1980, NCB) To the rear of the dwelling is a non-contributing, ca. 1980 metal shed.

309. 1051 North Parkway Avenue ca. 1922 SY-5820 CB

One- and one-half story, frame Bungalow built ca. 1922 and remodeled. The dwelling has a continuous stucco covered foundation, an exterior of wired brick veneer, a front gable and hipped roof porch with asphalt shingles, one exterior end and one interior brick and concrete chimneys each with a single chimney cap. The full-width, hipped and gable roof porch has large brick battered columns, an open brick railing with a concrete top rail and stucco and a single-light fixed window in the gable field. The porch has been partially enclosed with aluminum siding and windows under the gable roof section. Two entrances are located on the main façade. One entrance has an original nine-light glass and wood panel door and the other has a ca. 1970, nine-light glass and metal door. Both entrances have metal security doors. Windows are original one-over-one double hung wood sash with storm windows, metal security bars and concrete sills. A soldier course beltcourse, a header course water table and a wood cornice surrounds the dwelling. On the west façade is a protruding gable roof bay with a set of paired windows and stucco, diamond stick detailing and gable returns in the gable field. A ca. 1940, small addition with an exterior of weatherboard siding is located on the rear façade.

United States Department of the Interior
National Park Service

National Register of Historic Places Continuation Sheet

Section number 7 Page 82

Galloway-Speedway Historic District
Memphis, Shelby County, Tennessee

(Mother-in-law Cottage, ca. 1922, CB) To the rear of the dwelling is a ca. 1922, frame garage/shed that has been converted into a mother-in-law cottage. The cottage has a hipped roof of asphalt shingles, an exterior of board and batten siding, six-over-six double hung wood sash windows, a small concrete chimney and a small weatherboard sided addition on the south façade.

310. 1050-56 North Parkway Avenue ca. 1957 SY-5821A & B NCB

This is a frame, one-story, front gable plan Bungalow influenced multiple residence apartment building built ca. 1957. The three-section building has been combined to form a U-shaped apartment building complex. The complex has an exterior of brick veneer, a hipped roof of asphalt shingles with false stepped parapets where the front sections meet the rear connector section and one interior brick chimney. The entrances all have ca. 1970, three, square single-light diagonally placed with wood panel doors, metal security doors and matching, hipped roof canopies. Windows are two-over-two horizontal light double hung wood sash with brick lintels and picture windows on the main façade. Triangular dormers are located in the gable fields with attic vents.

311. 1055 North Parkway Avenue ca. 1922 SY-5822 CB

This is a frame, one- and one-half story Bungalow built ca. 1922. The dwelling has an exterior of brick and stone veneer, a jerkinhead roof of asphalt shingles, one metal flue and one interior end brick chimney. The full-width gable roof porch has battered stone columns, a closed stone railing with a concrete top rail and stucco and a single-light fixed window in the gable field. The main entrance has an original nine-light glass and wood panel door with original six-light and wood panel sidelights with metal security bars and a metal security door. Windows are original one-over-one double hung wood sash with metal security bars and concrete sills. A soldier course beltcourse, wood cornice and wood water table surrounds the dwelling. On the west facade is a protruding gable roof bay with two windows. On the main façade is a shed a roof dormer with three, single-light fixed windows and stucco in the gable fields.

(Shed, ca. 1980, NCB) Located to the rear of the dwelling is a ca. 1980, non-contributing shed.

312. 1059 North Parkway Avenue ca. 1922 SY-5823 CB

The property at 1059 North Parkway Avenue is a frame, one- and one-half story Bungalow built ca. 1922. The dwelling has a continuous stucco covered foundation, an exterior of brick veneer, a hipped and gable roof of asphalt shingles and an interior end brick chimney. The full-width, gable and hipped roof porch has battered stone columns with concrete plinths, a closed brick railing with a concrete top rail and stick work and stucco in the gable field. The main entrance door is not visible but the entrance does retain its original six-light and wood panel sidelights and a metal security door. Windows are original one-over-one double hung wood sash with concrete sills. A wood cornice surrounds the dwelling. On the main façade is a gable roof dormer with three, single-light On the west façade is a protruding gable roof bay with two windows and stucco and a single-light fixed window are in the gable field. Stucco is also located in the gable fields of the main roofline.

(Garage, ca. 1950, CB) To the rear of the dwelling is a ca. 1950, frame, one-bay garage with a hipped roof of asphalt shingles, an exterior of plywood and an overhead metal track door with four-light fixed windows.

313. 1062 North Parkway Avenue ca. 1915 SY-5824 CB

This is a frame, one- and one-half story Bungalow built ca. 1915. The dwelling has a continuous stucco covered foundation, an exterior of brick veneer, a gable roof of asphalt shingles, one exterior end brick and one interior concrete chimney. The full-width, gable and hipped roof porch has battered brick columns, a closed concrete block

United States Department of the Interior
National Park Service

National Register of Historic Places Continuation Sheet

Section number 7 Page 83

Galloway-Speedway Historic District
Memphis, Shelby County, Tennessee

railing and has been enclosed with wood lattice and screening. In the gable field of the porch is a single-light awning window and stucco. The main entrance has an original six-light glass and wood panel door with a metal security door. Windows are original one-over-one double hung wood sash with concrete sills and wood surrounds. A soldier course beltcourse surround the dwelling. In the gable fields are stucco, gable returns and a single window opening. The gable field on the main façade has stucco, gable returns and two window openings covered with wood panels. On the west façade is a protruding bay with a set of paired windows.

(Garage, ca. 1915, CB) To the rear of the dwelling is a ca. 1915, frame, one-bay garage with a hipped roof of asphalt shingles with exposed roof rafters and an exterior of metal siding.

314. 1066 North Parkway Avenue ca. 1917 SY-5825 CB

Located at this address is a frame, one- and one-half story Airplane Bungalow with a raised monitor roof section built ca. 1917. The dwelling has a continuous stucco covered foundation, an exterior of brick veneer, a multi-gable roof of asphalt shingles, one metal flue and one exterior end brick chimney. The full-width, hipped roof porch has battered brick columns and an open brick railing. An original brick entrance path leads from the sidewalk to the porch steps. The main entrance has an original multi-light glass and wood door with a metal security door. Windows are original one-over-one double hung wood sash with concrete sills. A soldier course beltcourse surrounds the dwelling. The raised hipped monitor roof section has an exterior of asphalt shingle siding. Stucco and gable returns are located in the gable fields. In the gable field on the main façade are two, single-light fixed windows and stucco.

(Garage, ca. 1917, CB) To the rear of the dwelling is a ca. 1917, frame garage with a hipped roof of asphalt shingles, plywood siding and a lean-to addition. The garage is in a state of disrepair.

315. 1071 North Parkway Avenue ca. 1922 SY-5826 CB

This is a frame, one- and one-half story Bungalow built ca. 1922. The dwelling has a continuous concrete and stucco covered foundation, an exterior of brick veneer, a jerkinhead roof of asphalt shingles and one interior end brick chimney. The full-width, shed roof porch has a down-facing eave, exposed roof rafters, square stone columns with swags, a closed brick railing with a concrete top rail and half-moon design drains. The main entrance has an original single-light and wood panel door with an original single-light transom covered with a wood panel and a metal security door. Windows are six-over-one double hung vinyl sash with concrete sills. A soldier course brick water table and a sailor course brick beltcourse surround the dwelling. On the main façade is a jerkinhead roof dormer with two window openings and stucco. Stucco is also in the remaining gable field of the main roofline along with two louvered attic vents.

316. 1072 North Parkway Avenue ca. 1926 SY-5827 CB

At 1072 North Parkway Avenue stands a frame, one-and one-half story Airplane Bungalow with a raised hipped monitor roof section built ca. 1926. The dwelling has a continuous poured concrete foundation, a jerkinhead roof of asphalt shingles and one exterior end chimney. Documentation of the dwelling was difficult due to a high chain link security fence with barbed wire. The full-width hipped and jerkinhead roof porch has a porte-cochere extension, a wrought-iron railing and posts and a tile floor. The porte-cochere extension has wrought iron posts on brick piers with concrete plinths and wrought iron decorative brackets. The porch has been enclosed on the west side with structural glass blocks, brick and a ca. 1960, metal picture window with shutters. Stucco and one, three-light awning window is located in the gable field of the porch. The main entrance door is not visible but the entrance does have a metal security door with a concrete lintel and replacement, five-light sidelights. Windows are Craftsman style, one-over-one

United States Department of the Interior
National Park Service

National Register of Historic Places Continuation Sheet

Section number 7 Page 84

Galloway-Speedway Historic District
Memphis, Shelby County, Tennessee

double hung wood sash with many having been replaced. On the east façade is a protruding bay with a paired set of windows.

(Garage, ca. 1926, CB) To the rear of the dwelling is a ca. 1926, frame garage with a gable roof, an exterior of aluminum siding, a multi-glass and wood pedestrian door and metal double doors.

317. 1075 North Parkway Avenue ca. 1922 SY-5828 CB

This is a frame, one- and one-half story Bungalow built ca. 1922. The dwelling has a continuous stucco covered foundation, and exterior of stucco, a multi-gable roof of asphalt shingles, one exterior end brick and one interior brick chimneys. The full-width, hipped and gable roof porch has a large wood cornice, a porte-cochere extension, square brick columns on brick piers with concrete plinths and large dentil detailing, an open and closed brick patterned railing with a concrete top rail and stucco and a single-light, rectangular window in the gable field. The main entrance door is not visible but the entrance does have a metal security door. Windows are nine-over-one double hung sash possibly replacement vinyl with brick sills and metal security bars. A brick water table and beltcourse surrounds the dwelling. Stucco and a single window opening is located in the front gable field.

318. 1077 North Parkway Avenue ca. 1910 SY-5829 CB

This is a frame, two-story, American Foursquare style dwelling built ca. 1910. The dwelling has an exterior of brick veneer, an exterior end chimney and a hipped roof of standing metal seam. The full-width, hipped roof porch has square brick columns and a closed brick railing with a concrete top rail. The main entrance has an original single-light glass and wood door with an original decorative stain glass transom and original single-light wood panel sidelights. Windows are one-over-one double hung wood sash with concrete sills. On the roofline are two, hipped metal roof dormers with a single, one-over-one double hung wood sash window. A ca. 1960, small, one-story addition with an exterior of vinyl siding has been added to the rear façade.

319. 1078 North Parkway Avenue ca. 1920 SY-5830 CB

This is a frame, one- and one-half story Bungalow built ca. 1920. The dwelling has a continuous stucco covered foundation, an exterior of brick veneer, a front gable roof of asphalt shingles and one concrete and brick, exterior end chimney. The full-width, hipped roof porch has a porte-cochere extension, battered stone columns and a closed brick railing with a concrete top rail. The main entrance has a replacement, six wood panel door with an original ten-light transom, original single-light and wood panel sidelights and a concrete lintel. Windows are original Craftsman style, one-over-one double hung wood sash windows with concrete lintels and sills and metal security bars. A brick header course beltcourse and a protruding double-line brick water table. In the gable field of the main façade are two window openings with screening. On the east façade is a protruding bay with a triple set of windows.

(Garage/Barn, ca. 1920, CB) To the rear of the dwelling is a ca. 1920, frame garage with an exterior of vertical board siding, a gable roof, replacement, double hinged wood doors, six-light windows and stick work in the gable fields.

320. 1079 North Parkway Avenue ca. 1922 SY-5831 CB

Located a 1079 North Parkway Avenue is a frame, one- and one-half story Bungalow built ca. 1922. The dwelling has a continuous concrete foundation, an exterior of brick veneer, a jerkinhead roof of asphalt shingles and one exterior end brick chimney. The full-width, hipped and jerkinhead roof has a porte-cochere extension, battered stone columns with concrete plinths, a closed brick railing with a concrete top rail. The area behind the porte-cochere has been enclosed to form a makeshift enclosed garage. The main entrance has an original Craftsman style, single light and

United States Department of the Interior
National Park Service

National Register of Historic Places Continuation Sheet

Section number 7 Page 85

Galloway-Speedway Historic District
Memphis, Shelby County, Tennessee

wood panel door with an original ten-light transom, original Craftsman style single light and wood panel sidelights, a concrete lintel and a metal security door. Windows are original, Craftsman-style one-over-one double hung wood sash with concrete sills and a large concrete lintel over the triple set of windows on the main façade. A soldier course brick beltcourse and a protruding double-line brick water table surrounds the dwelling. IN the gable field on the main façade are two window openings and stucco. Stucco and a single, four-light rectangular window are in the remaining gable fields.

321. 1082 North Parkway Avenue ca. 1925 SY-5832 CB

This is a frame, one- and one-half story Bungalow built ca. 1925. The dwelling has an exterior of brick veneer, a continuous concrete block foundation, a front gable roof of asphalt shingles with some exposed roof rafters and one exterior end brick and concrete chimney. The full-width hipped and gable roof porch has a porte-cochere extension supported with angled wrought iron posts, battered brick columns, a closed brick railing and stucco, gable returns and a four-light fixed window in the gable field. The porch has been enclosed under the gable section with vinyl siding, windows and the brick railing. The main entrance has an original Craftsman style single-light glass and wood panel door with an original ten-light transom, original Craftsman-style three-light and single wood panel sidelights and a metal security door. Windows are original nine-over-one double hung wood sash with concrete sills. A soldier course beltcourse and a protruding double-line brick water table surround the dwelling. On the east façade is a protruding bay with a triple set of windows. In the gable field are stucco and a single window opening. In the gable field on the main façade are two window openings and stucco. A ca. 1970 porch has been added to the rear façade.

(Shed, ca. 1980, NCB) To the rear of the dwelling is a non-contributing, ca. 1980 shed.

322. 1083 North Parkway Avenue ca. 1928 SY-5833 CB

Standing at 1083 North Parkway Avenue is a frame, one- and one-half story Airplane Bungalow with a raised gabled monitor roof section built ca. 1928. The dwelling has a continuous concrete block and stucco covered foundation, an exterior of brick veneer, a multi-gabled roof of asphalt shingles, one interior end and one interior brick chimney. The full-width, hipped and protruding central gable roof porch has a porte-cochere extension, a wood cornice, heavy modillion blocks, square brick columns, an open brick railing with a concrete top rail and stucco and stick work in the gable field. The main entrance has an original multi-light glass and wood wide width door with an original thin, six-light transom. Windows are original nine-over-one double hung wood sash with concrete sills. A wood cornice and concrete water table surrounds the dwelling. Stick work, stucco and heavy modillion blocks and three, single-light fixed windows are located in the gable fields. The full-width, raised gabled monitor roof has an exterior of stucco and original nine-over-one double hung wood sash windows.

(Garage, ca. 1950, CB) .To the rear of the dwelling is a ca. 1950, frame garage with a hipped roof of asphalt shingles, an exterior of wood siding and two, original six-light and vertical board sliding track doors.

323. 1086 North Parkway Avenue ca. 1920 SY-5834 CS

This is a one-story, square wired brick pump station/wellhouse built ca. 1920. The structure has a continuous concrete foundation, a flat roof with concrete coping and a concrete cornice. The original wood panel door entrances have been replaced with metal chain link fence doors and the single window opening on the east and west façades have been replaced with an open-patterned brick infill but still retain their concrete sills. The interior of structure has the original square concrete well. The metal pumping mechanism is positioned a few feet in front of the structure surrounded by chain link fence.

United States Department of the Interior
National Park Service

National Register of Historic Places Continuation Sheet

Section number 7 Page 86

Galloway-Speedway Historic District
Memphis, Shelby County, Tennessee

324. 1094 North Parkway Avenue ca. 1920 SY-5835 CB

This is a frame, one- and one-half story Airplane Bungalow with a raised monitor roof built ca. 1920. The dwelling has a continuous concrete foundation, an exterior of wired brick veneer, a jerkinhead roof of asphalt shingles with exposed roof rafters, one exterior end and one interior brick chimneys. The full-width jerkinhead and hipped roof porch has exposed roof rafters, battered brick columns with concrete plinths, brick piers with concrete plinths and a closed brick railing with a concrete top rail. The main entrance has an original six-light glass and wood panel door with a metal security door. Windows are original Craftsman-style, one-over-one double hung wood sash with metal security bars. Stucco and one, two-light fixed window is in the gable field on the main façade. A soldier course brick beltcourse and water table surrounds the dwelling. On the west façade is a shed roof, protruding bay with a paired set of windows and exposed roof rafters. A ca. 1950 addition has been added to the rear façade with an exterior of aluminum siding.

(Shed, ca. 1980, NCB) To the rear of the dwelling is a ca. 1980, non-contributing shed and adjacent to the dwelling is a heavy plastic carport.

325. 1095 North Parkway Avenue ca. 1960 SY-5836 NCB

This is a two-story, frame Apartment Building built ca. 1960. The building has an exterior of wired brick veneer, an asphalt shingled front gable roof with a steeped false parapet positioned mid-way and one exterior end brick flue with a corbelled cap. The multiple entries have solid wood doors with shed roof metal canopies supported by metal posts. The rear entries also have metal canopies. Windows are one-over-one double hung metal sash with brick sills. A soldier course brick beltcourse surrounds the building and a triangular attic vent wall dormer is in the gable field on the main facade.

326. 1099 North Parkway Avenue ca. 1930 SY-5837 CB

At 1099 North Parkway Avenue is a frame, two-story, gable front Apartment building built ca. 1930. The dwelling has a continuous stucco covered foundation, an exterior of brick veneer, a front gable roof of asphalt shingles with modillion blocks in the eaves and a stepped parapet in the middle of the roofline and an exterior end brick chimney. The two, two-story, central hipped roof porches are located on the main (N) and side (E) façade. Both porches are identical with modillion blocks, a wood cornice, square brick columns with embedded diamond concrete detail inserts and a metal railing on the 2nd floor. The first floor entrances on both facades have original twelve-light glass and wood doors with a brick solder lintel and concrete square detail inserts flanking the corners. The second floor entrances on both facades have original multi-light glass and wood doors. Two secondary side entrances on the west façade have original, single-light and wood panel doors with its original hardware and one retaining its original screen door. Windows are original, three-over-one vertical light double hung wood sash with concrete sills and cast concrete square detail inserts flanking the corners of the windows. A brick soldier course water table and a sailor and soldier course beltcourse surround the dwelling. At the roofline is a hipped roof dormer with a louvered attic vent and a single-light fixed window. In the gable field on the main façade are two, single-light fixed windows and a triangular attic vent in the gable apex. The original iron coal shute cover remains on the east façade.

(Shed, ca. 1985, NCB) To the rear of the dwelling is a ca. 1985 frame shed.

United States Department of the Interior
National Park Service

National Register of Historic Places Continuation Sheet

Section number 7 Page 87

Galloway-Speedway Historic District
Memphis, Shelby County, Tennessee

327. 1100 North Parkway Avenue ca. 1922 SY-5838 CB

This is a frame, one- and one-half story, side passage plan Bungalow built ca. 1922. The dwelling has a continuous brick foundation, an exterior of brick veneer, a jerkinhead roof of asphalt shingles and two exterior end brick chimneys. The full-width, hipped roof porch has battered stone columns with rusticated stone plinths, a solid stone railing with detailed drains and a hipped roof dormer on the roofline. Two entrances are located on the main façade. One entrance a solid wood door with a metal security door while the other has an original multi-light glass and wood door with a metal security door. Windows are original nine-over-one double hung wood sash with concrete sills and metal security bars. Stick work, stucco and two, eight-light fixed windows are located in the gable field on the main façade. On the east facade is a hipped roof dormer with one window opening. Brackets have been positioned in the eaves.

328. 1111 North Parkway Avenue ca. 1920 SY-5839 CB

Located at 1111 North Parkway Avenue is a frame, two-story, American Foursquare style dwelling built ca. 1920. The dwelling has a continuous concrete foundation, an exterior of brick veneer, an asphalt shingled hipped roof with a flare and two interior brick chimneys. The full-width hipped roof porch has been altered from its original wraparound form and has square brick columns and a ca. 1960 metal railing. The portion of the porch that would have completed the wraparound form has been enclosed with brick veneer and windows. Outer, wood louvered, exterior doors have obscured the two entrances on the main façade but an original, rectangular single-light transom remains. Entrances on the side facades have original six-light and three vertical light and three wood panel doors. An entrance on the rear façade has an original single-light and three wood panel door. Windows are original one-over-one double hung wood sash with concrete sills. A concrete beltcourse separates the floors. On the main façade is a hipped roof dormer with an attic vent. An original, two-story hipped roof wing was added to the rear façade.

329. 1112 North Parkway Avenue ca. 1912 SY-5840 CB

This is a frame, two-story American Foursquare style dwelling built ca. 1912. The dwelling has a continuous concrete foundation, an exterior of brick veneer, a hipped roof of asphalt shingles and a metal flue. The two-bay, two-story, shed roof porch has square brick columns and an open brick railing on the first floor and square wood columns on wood piers with an open wood railing on the second floor. The two entrances on the first floor of the main façade have original, Craftsman style, six-light and wood panel doors and the two entrances on the second floor have Craftsman style original eight-light and wood panel doors. A secondary entrance on the west façade has an original, Craftsman-style, six-light and wood panel door with a gable roof canopy supported by knee brace brackets. Windows are original four-over-one double hung wood sash with concrete sills. On the west and main facades are gable roof dormers with window openings covered with vinyl siding and gable returns. The eaves are covered with vinyl.

330. 1113 North Parkway Avenue ca. 1915 SY-5841 CB

At 1113 North Parkway Avenue is a frame, one-story pyramid square plan, Traditional style dwelling built ca. 1915. The dwelling has an exterior of asbestos shingle siding, a hipped roof of asphalt shingles and an interior central brick chimney. The main entrance has a ca. 1990, six-panel wood door with a shed roof canopy supported by metal posts. Windows are original Craftsman style, one-over-one double hung wood sash with metal security bars. A shed roof wing has been added to the west façade. The house sits way back off the Parkway unlike the rest of the dwellings on the street. The dwelling could possibly have been originally a servant quarters for an adjacent residence.

**United States Department of the Interior
National Park Service**

**National Register of Historic Places
Continuation Sheet**

Section number 7 Page 88

Galloway-Speedway Historic District
Memphis, Shelby County, Tennessee

331. 1116 North Parkway Avenue ca. 1920 SY-5842 CB

Standing at 1116 North Parkway Avenue is a frame, two-story American Foursquare style dwelling built ca. 1920. The dwelling has a continuous concrete foundation, an exterior of brick veneer (1st floor) and stucco (2nd floor), a hipped roof of asphalt shingles and an interior brick chimney. The partial-width, hipped roof porch extends out to porte-cochere with square brick columns and has been totally enclosed with screen panels. The main entrance has an original fifteen-light glass and wood door with an original four-light transom and a metal security door. Windows are original nine-over-one double hung wood sash. Dormers on the east, main and west facades have a central eight-light fixed window flanked by four-light fixed windows. Modillion brackets have been placed in the eaves. A two-story, frame porch has been added to the rear façade.

United States Department of the Interior
National Park Service

National Register of Historic Places Continuation Sheet

Section number 8 Page 89

Galloway-Speedway Historic District
Memphis, Shelby County, Tennessee

STATEMENT OF SIGNIFICANCE

Summary

The Galloway-Speedway Historic District is located in the city of Memphis, Shelby County, Tennessee (2000 pop. 650,100). Memphis is located on the eastern banks of the Mississippi River in the southwestern corner of the state. The Galloway-Speedway Historic District is eligible for the National Register under Criteria A and C. The district is eligible under Criterion A for its role in the development and growth of Memphis during the early twentieth century. The neighborhood emerged around the newly created city parkway system as the city annexed major acreage to accommodate a rapidly expanding population. The district is also eligible under Criterion C for its architectural significance as a notable residential development of the early twentieth century. An architectural survey of Memphis completed in 1994 identified the Galloway-Speedway neighborhood as potentially eligible for the National Register. The district is residential in character and is centered around the National Register-listed North Parkway, which was developed between 1905 and 1913 as part of the Memphis Parkway System (NR 07/03/89). Buildings within the district are primarily single-family dwellings constructed from ca. 1902 to ca. 1950, with the vast majority of dwellings dating to the 1920s. The Craftsman/Bungalow design is the predominant architectural style of the neighborhood. Other architectural styles represented include Tudor Revival, Colonial Revival and American Foursquare designs. The district also includes some examples of vernacular and Folk Victorian house forms, particularly gabled ell and pyramid square plans. In addition to these dwellings, the district contains three contributing apartment buildings, two churches, one fire station, and four, public pump stations/wellhouses. The district contains 331 primary buildings, of which 309 or 94% would be considered contributing to the character of the district.

The district represents a large intact collection of contiguous early twentieth century dwellings in Memphis. These dwellings have not been significantly altered, and the district retains a strong sense of time and place. The appearance of the Galloway-Speedway Historic District has not been significantly altered and it retains much of its historic character. The Galloway-Speedway Historic District meets the registration requirements for the property type "Residential Historic Districts" set forth in the Multiple Property Documentation Form "Residential Development in Memphis, Shelby County, Tennessee" and "Residential Development in Memphis, Shelby County, Tennessee (Additional Documentation)."

Historical Overview

The Galloway-Speedway Historic District emerged as a middle-class neighborhood in the early twentieth century. One of many subdivisions established in what was a newly annexed area of Memphis, Galloway-Speedway reflects the growth and development of the city as it entered a new progressive era. In the late nineteenth century, Memphis suffered a series of yellow fever epidemics, which resulted in the deaths of thousands of its citizens. Following this period of loss and devastation, Memphis rapidly expanded at the turn of the century. Suburban development, modern transportation, and an increasing middle class population defined the nature of this growth as Memphis evolved into a modern city.

Founded in 1819, Memphis developed as a major center of the cotton trade by the 1850s. Its advantageous position on the Mississippi River supported a lucrative steamboat trade and the addition of interstate rail lines in 1857 amplified its commercial network. Throughout most of the Civil War, Union forces occupied Memphis, and, unlike many Southern cities, it emerged largely unscathed from the conflict. During the post war years, its location along the river and its system of working railroads gave Memphis an advantage over its war-torn counterparts and the city quickly

United States Department of the Interior
National Park Service

National Register of Historic Places Continuation Sheet

Section number 8 Page 90

Galloway-Speedway Historic District
Memphis, Shelby County, Tennessee

regained its status as the region's leading trade center.¹ The Memphis economy boomed, and the city grew rapidly as it prospered.

The city's growth and progress was impeded by a series of yellow fever epidemics, the most devastating of which occurred in the 1870s. In 1873, the disease left 2,000 people dead and along with an economic recession left the city financially strapped. Extreme heat, coupled with the city's unsanitary condition, were the main causes of the plague. In response, the city formed a board of health, which initiated cleaning of all streets, alleys, and public grounds and established a garbage service.² Despite these efforts, the disease struck again in 1878-1879, this time even more seriously, with over 6,000 dead during the two-year period. Thousands more fled the city, many of whom permanently settled elsewhere. By 1879, over half of the city's white population had left.³

It was soon determined that the city's privy vault system was the chief cause of the epidemic. Thousands of privy vaults were in use in the city. The vaults were typically forty feet deep and many had not been emptied for ten to forty years. Over 3,000 cisterns were located near the vaults and seepage from the privy system contaminated a large portion of the city's water supply. The construction of a sanitary sewer system and the use of a new, pure water supply put Memphis on the road to recovery. The city took on the task of emptying, fumigating and disinfecting the vaults with lime, zinc sulphate, and iron sulphate. In addition, dwellings of those who had contracted the disease were disinfected. Bedding and clothing were burned, and over one hundred houses were destroyed.⁴

The yellow fever epidemics, however, left Memphis financially strapped. Many of the city's white residents had abandoned the city during the years of the plague and some left permanently. With its wealthiest citizens gone, Memphis' tax base collapsed and the city was left bankrupt. As a result, the state repealed Memphis' charter and made it a "taxing district" under state control. The city remained in this powerless position for twelve years. During the 1880s and 1890s, Memphis gradually rebounded. The cotton market remained the foundation of the local economy and, along with various lumber related industries, created a demand for workers that brought a new influx of residents to the area. New railroad lines increased market connections, strengthened trade, and spurred economic growth. Memphis experienced rapid growth as the city rebounded during the last two decades of the nineteenth century. Its population soared, rising from 33,592 in 1880 to 64,495 in 1890. By 1900, it had reached over 102,000.⁵

A great demand for housing, particularly for the middle and working classes, accompanied the population boom, and substantial residential development followed. As commercial and industrial zones expanded, residential development moved away from the old city core. The number of residents living in suburban areas outside the legal city limits increased sharply. Extended streetcar lines eased transportation to these areas and spurred suburban development.⁶ During the 1890s, a movement arose among leading citizens to annex adjacent suburban areas and provide Memphis with a progressive agenda for the coming decades. Known as the "Greater Memphis Movement," the cause also

¹ Robert A. Sigafos, *From Cotton Row to Beale Street: A Business History of Memphis*. (Knoxville: University of Tennessee Press, 1979), 44-45.

² Goodspeed's *History of Tennessee From the Earliest Times to the Present* (Nashville: Goodspeed Publishing Co., 1887), 878.

³ Sigafos, 58-60; John E. Harkins, *Metropolis of the American Nile, An Illustrated History of Memphis & Shelby County*. (Woodland Hills, CA: Windsor Publications, Inc., 1982), 88-91.

⁴ Goodspeed, *History of Tennessee*, 878-879.

⁵ Harkins, *Metropolis of the American Nile*, 103.

⁶ John Linn Hopkins, "Historic Residential Resources of Memphis, Shelby County, TN." National Register of Historic Places Multiple Property Documentation Form, February 1998, E-6 – E-7.

United States Department of the Interior
National Park Service


National Register of Historic Places Continuation Sheet

Section number 8 Page 91

Galloway-Speedway Historic District
Memphis, Shelby County, Tennessee

supported the extension of water and sewer lines into outlying areas, the creation of a municipal water and gas company, new school construction, and the creation of city parks.⁷

As part of the Greater Memphis Movement and in order to accommodate its growing population, Memphis annexed a large area of approximately twelve square miles surrounding the city in 1899. The expansion, which roughly quadrupled the city's size, was primarily east of the city core and included some preexisting communities as well as large amounts of undeveloped land.⁸ In the ensuing years, heavy residential development occurred in the annexed area and numerous subdivisions, including the Galloway-Speedway neighborhood, emerged.



Map No. 1: Solid lines denote areas annexed to the city at dates noted. The Galloway-Speedway Historic District is outlined with a dashed line.

⁷ Ibid., E-10.

⁸ Harkins, *Metropolis of the American Nile*, 105-106.

United States Department of the Interior
National Park Service

National Register of Historic Places Continuation Sheet

Section number 8 Page 92

Galloway-Speedway Historic District
Memphis, Shelby County, Tennessee

The Galloway-Speedway neighborhood was established in the northeastern section of the annexed area. The Speedway Land Company, which formed in 1905 for the purpose of acquiring and developing lands in the area, initiated the development. The company was a partnership between leading real estate entrepreneur Robert Brinkley Snowden and prominent Memphis businessmen Charles C. Currier, William J. Brinkley, J.W. Canada, Finley W. Faxon and G.W. McRae, who invested a total of \$225,000 in the company.⁹ Snowden, whose family owned a substantial amount of land in the newly annexed area, was a staunch supporter of the Greater Memphis Movement and was a principal figure in the development of several subdivisions. The Speedway Land Company was Snowden's third major real estate project following the development of the Annesdale Park (Historic District NR 12/22/78) and Annesdale-Snowden (Historic District NR 10/25/79) neighborhoods in 1903 and 1906. These early ventures were established on Snowden family lands. Snowden and his associates formed the Speedway Land Company in order to acquire additional lands that had been in the Galloway family.¹⁰ In 1912, the Speedway Land Company established the Speedway Terrace Subdivision (NR 3/19/99).¹¹

Another major influence on the formation of the Galloway-Speedway area was the development of the Memphis Parkway System (NR 07/08/89). This system of scenic roadways was established from ca. 1909 to ca. 1913 for recreational purposes. The Parkways formed a "U" on the north, east, and south sides of the city and connected newly established city parks. The Memphis Parkway System reflected the ideals of the City Beautiful Movement, which greatly influenced city planning and civic landscapes in the early 1900s. The Parkways were part of the progressive agenda of the Greater Memphis Movement, and the northern leg of the route, North Parkway, serves as the central corridor of the Galloway-Speedway Historic District.

At the time of their construction, the Parkways were not intended for use as a major traffic route, but were meant to be linear parks used for scenic nature drives. The streetcar was the principal mode of transportation of the era, but as the use of automobiles increased, the parkways were resurfaced to handle automobile traffic.¹² The Parkways featured wide landscaped medians and were designed to attract residential development. When the route of the Parkways was chosen in 1902, a local newspaper stated, "This route was also selected with a view to invite selection and erection of handsome homes adorning their grounds on both sides of the Parkway . . ." ¹³ The original Parkway terminated at Manassas Avenue, one block west of the proposed boundaries of the Galloway-Speedway Historic District.

The Galloway-Speedway neighborhood appealed to the growing middle class and developed quickly. The availability of public utilities and the neighborhood's proximity to streetcar lines made it attractive to middle income residents, whose ability to own a home increased substantially in the early twentieth century. Throughout the first decades of the century, Memphis' population continued to grow and its economy boomed. By 1910 the city's population reached 131,105. This number climbed to 162,351 in 1920 and exceeded 253,000 by 1930. The prosperous economy also made it possible for more people to become homeowners. Jobs were plentiful and wages were high while the cost of

⁹ John Linn Hopkins and Marsha R. Oates, "Speedway Terrace Historic District," National Register of Historic Places Nomination Form, June 1998, 8-48.

¹⁰ *Ibid.*, 8-48-49.

¹¹ In the 1960s, the construction of Interstate 240 bisected the Speedway Terrace Subdivision. The eastern portion of this neighborhood was listed on the National Register in March 1999 as the Speedway Terrace Historic District. The portion west of Interstate 240 is within the boundaries of the proposed Galloway-Speedway Historic District. The district also includes a small portion of the Galloway Park Subdivision.)

¹² Martha Carver and Cathy Bruner. "Memphis Parkway System," National Register of Historic Places Nomination Form, February 1989, 8-2.

¹³ *Ibid.*, 8-3.

United States Department of the Interior
National Park Service

National Register of Historic Places Continuation Sheet

Section number 8 Page 93

Galloway-Speedway Historic District
Memphis, Shelby County, Tennessee

land and building materials were low. The result was a tremendous boom in housing construction, much of which occurred in the newly emerging suburbs. During the 1920s alone, over 10,000 single-family housing units were built in the Memphis area.¹⁴

Houses began to appear in the Galloway-Speedway neighborhood as early as 1902. However, the majority of dwellings in the district were constructed during the 1910s and 1920s. By 1915 there were approximately fifteen dwellings each on Greenlaw and Forrest avenues within the district, and twenty-five on Faxon Avenue. North Parkway, the district's central corridor had approximately thirteen dwellings by 1915, and an additional ten by 1918. The district rapidly filled out in the 1920s as construction continued to increase. In 1920 alone, around fifty new dwellings were built on Faxon Avenue, and between 1920 and 1922, thirty-four new houses appeared on Forrest Avenue. Throughout the decade approximately forty additional dwellings were constructed on North Parkway. Galloway Avenue, the southernmost street in the district, was slower to develop with only a handful of dwellings by 1915; but it too filled out with at least nineteen dwellings built on the street in 1920 and an additional fifteen by 1928.¹⁵

The Craftsman/Bungalow design was by far the overwhelming architectural style of choice among homebuilders in the Galloway-Speedway area. This contemporary design originated in California in the early 1900s and quickly became the most dominant style for smaller dwellings built throughout the country into the 1920s.¹⁶ Several examples found in the Galloway-Speedway district are what are known as Airplane bungalows. This variation of the popular style features a broad horizontal plan, multiple rooflines, and an accentuated second-story section, which was commonly used as a sleeping porch. This style was especially common in areas with a warm climate.¹⁷ The design's unusual name was derived from the similarity of its wide eaves and flared rooflines to the shape and form of aircraft wings. Another theory on the derivation of the name is that the second-story section resembles the cockpit of an aircraft, with the roofline forming the wings.

In addition to various Bungalow designs, the Galloway-Speedway neighborhood also features examples of American Foursquare, Colonial Revival, and Tudor Revival styles as well as a few pyramid square and gabled ell forms. The rising influence of the automobile can also be detected in the district as many residents erected garages and carports on their property. Several Bungalow dwellings in the district were also designed with porte-cocheres.

By 1922, a fire station was constructed in the neighborhood to serve the area, and residents had established two churches in the district. Fire Station No. 15 was constructed at the corner of Faxon Avenue and Decatur Street around 1920, and its Bungalow influenced design blends in with the surrounding neighborhood. The fire station was discontinued in the late twentieth century, and the building now serves as a Senior Citizens Center. Also around 1920, the Parkway Seventh Day Adventist Church was built at 833 North Parkway. This building is currently vacant. Construction on the Epworth M.E. Church South at 1120 Faxon Avenue began in 1914 and was completed in 1924. This Spanish Colonial Revival influenced building retains much of its original design and until recently continued to serve the community as the Good Samaritan United Methodist Church.

¹⁴ Sigafos, *From Cotton Row to Beale Street*, 153; Hopkins, "Historic Residential Resources of Memphis," E-14.

¹⁵ Information on approximate construction dates was compiled through data gathered from City Directories, Shelby County Tax Records, and Sanborn Fire Insurance Maps.

¹⁶ Virginia and Lee McAlester, *A Field Guide to American Houses*, (New York: Alfred A. Knopf, 1984), 454.

¹⁷ Herbert Gottfried and Jan Jennings, *American Vernacular Design 1870-1940*, (New York: Van Nostrand Reinhold Company, Inc., 1985), 225.

United States Department of the Interior
National Park Service

National Register of Historic Places Continuation Sheet

Section number 8 Page 94

Galloway-Speedway Historic District
Memphis, Shelby County, Tennessee

Historically, the residents of the Galloway-Speedway neighborhood were primarily from the middle class. City directories reveal that they were employed in a variety of occupations including salesmen, plumbers, firemen, policemen, carpenters, lumbermen, cashiers, dressmakers, grocers, and barbers. During the 1920s, Nathan Schatz lived at 930 Faxon Avenue and operated a fruit stand on North Front Street. His neighbor, Robin Obermiller at 970 Faxon Avenue, worked as a cashier for the American Bag Company. Carlyle Maddix, who owned the dwelling at 925 Forrest Avenue, was an agent for the National Union Fire Insurance Company. Also during the 1920s, residents on Galloway Avenue included John C. Worten, an assistant chemist with Memphis Power and Light, who lived at 925 Galloway Avenue, and W.T. Castles, a lumberman at 1004 Galloway Avenue. T. J. McCourtney lived at 931 North Parkway in the early 1920s and was a route foreman for the Bannon Coal & Ice Company. Anthony Ragghianti, a manager, lived at 815 North Parkway. On Greenlaw Avenue, R.I. Lane at the 1094 address served as general manager of the Shippers Cotton Company.¹⁸

Some area residents managed their own businesses. During the 1930s, local residents William and Julia Papas operated a seafood café in town and lived at 1033 Greenlaw Avenue. Nicholas J. Carimi resided at 1042 Greenlaw Avenue and owned a local pharmacy. Joseph Hahn of Faxon Avenue ran Hahn's Dry Goods Store and George C. Krack of Forrest Avenue managed Krack's Drug Company, with both businesses located on nearby Jackson Avenue in the 1930s. Also, Dolan D. English of 994 Faxon Avenue ran a grocery business on Jackson Avenue. Percy Todd, a plumber, and his wife Katherine lived at 1085 Greenlaw Avenue in 1930, and Dennis Maley, a fireman, lived at 1053 Forrest Avenue. Carl F. Peterson was a salesman and resided at 1100 North Parkway. His neighbor at 1062 North Parkway was John G. Papageorge, an employee of the Black Hawk Restaurant.¹⁹

The middle-class character of the district continued into the 1940s and 1950s. During the 1940s, residents included barber Louis Thornley at 870 Faxon Avenue, and John Toulaiatos of 1089 Faxon Avenue, who owned and operated the restaurant J.C. Grill. John Maynard of 940 Galloway Avenue worked as a salesman for the Woodson & Bozeman Company. The resident at 970 North Parkway was Lawrence Fox, an agent for the U.S. Internal Revenue Service. In 1950, Robert A. Gifford, a superintendent with Dan Shea Boiler Works, lived with his wife Nettie at 965 Faxon Avenue. Peter and Elizabeth Kay, who lived at 1085 Faxon Avenue, owned the Kitchenette Café, and Harry Engelberg, a salesman, lived at 958 Forrest Avenue. Mrs. Mary M. Boletta lived at 1042 Greenlaw Avenue in 1950 and worked as a typist for the State Employment Security Office. Isadore Brooks of 931 Galloway was a plumber, and Benjamin and Sylvia Sacharin of 1099 Forrest Avenue owned a local grocery store. A. Zeno Aubuchon found employment as a sign writer and lived with his wife Ida at 914 North Parkway. Charles Girolami of 872 North Parkway was a tile layer and contractor, and Frank A. Coscia of 841 Faxon Avenue, was a foreman at the Shelby Paper Box Company.²⁰

The Galloway-Speedway neighborhood continued to develop into the 1930s as houses were constructed on the few remaining lots. Only a few dwellings in the district date to the 1940s, and one or two were constructed in the 1950s. Throughout the late twentieth century, the Galloway-Speedway area persisted as a thriving middle-class neighborhood

¹⁸ Memphis City Directory, Memphis, TN: R.L. Polk Company, 1923.

¹⁹ Memphis City Directory, Memphis, TN: R.L. Polk Company, 1930.

²⁰ Memphis City Directory, Memphis, TN: R.L. Polk Company, 1940, 1950.

**United States Department of the Interior
National Park Service**

National Register of Historic Places Continuation Sheet

Section number 8 Page 95

Galloway-Speedway Historic District
Memphis, Shelby County, Tennessee

despite trends in the post-World War II era of moving to new suburban development east of the city. The neighborhood has also survived the construction of Interstate 240 along its eastern boundary in the mid-1960s, which separates Galloway-Speedway from the associated Speedway Terrace Historic District to the east. During this era the demographics of the neighborhood began to shift from predominantly white to predominately black. Today, the Galloway-Speedway district is a middle-class African American neighborhood.

The Galloway-Speedway area continues to be a cohesive neighborhood connected through its architectural design. The neighborhood has experienced some decline in recent decades with a few dwellings being razed; however, the majority of properties retain a high degree of their architectural integrity, and new construction in the district is minimal. The majority of the properties remain owner-occupied, and there is a renewed interest in preserving the historic character of the neighborhood among local residents.

United States Department of the Interior
National Park Service

National Register of Historic Places Continuation Sheet

Section number 9 Page 96

Galloway-Speedway Historic District
Shelby County, Tennessee

BIBLIOGRAPHY

- Bruner, Cathy. "Memphis Park and Parkway System." National Register of Historic Places Multiple Property Documentation Form, February 1989. Copy on file at the Tennessee Historical Commission, Nashville, Tennessee.
- Capers, Gerald M. Jr. *The Biography of a River Town, Memphis: Its Heroic Age*. New Orleans: Tulane University, 1966.
- Carver, Martha, and Cathy Bruner. "Memphis Parkway System." National Register of Historic Places Nomination Form, February 1989. Copy on file at the Tennessee Historical Commission, Nashville, Tennessee.
- Goodspeed's History of Tennessee From the Earliest Times to the Present*. Nashville: Goodspeed Publishing Co., 1887.
- Gottfried, Herbert, and Jan Jennings. *American Vernacular Design, 1870-1940, An Illustrated Glossary*. New York: Van Nostrand Reinhold Company, 1985.
- Harkins, John E. *Metropolis of the American Nile, An Illustrated History of Memphis & Shelby County*. Woodland Hills, CA: Windsor Publications, Inc., 1982.
- Hopkins, John Linn. "Historic Residential Resources of Memphis, Shelby County, TN." National Register of Historic Places Multiple Property Documentation Form, February 1998. Copy on file at the Tennessee Historical Commission, Nashville, Tennessee.
- Hopkins, John Linn and Marsha R. Oates. "Speedway Terrace Historic District." National Register of Historic Places Nomination Form, June 1998. Copy on file at the Tennessee State Historical Commission, Nashville, Tennessee.
- McAlester, Virginia and Lee. *A Field Guide to American Houses*. New York: Alfred A. Knopf, 1984.
- Memphis Chamber of Commerce, "Memphis: Advantages, Resources and Opportunities it Offers Manufacturers and Distributors." Memphis, TN: Hood, 1920.
- Memphis City Directories. Memphis, TN: R.L. Polk Company, 1911, 1923, 1930, 1940, 1950.
- Sigafoos, Robert A. *From Cotton Row to Beale Street: A Business History of Memphis*. Knoxville: University of Tennessee Press, 1979.
- Sanborn Map Co. *Fire Insurance Maps of Memphis, Shelby County, Tennessee*. 1897, 1907, 1927, and 1951 series.
- Witteman, *A Memphis Illustrated*. New York: Albertype Company, 1892

United States Department of the Interior
National Park Service

National Register of Historic Places Continuation Sheet

Section number 10 Page 97

Galloway-Speedway Historic District
Shelby County, Tennessee

VERBAL BOUNDARY DESCRIPTION

The boundary of the Galloway-Speedway Historic District includes the following parcels on City of Memphis tax maps:

Sheet E-9: Block 17-Parcels 21-40; Block 23-Parcels 14-22; Block 112-Parcels 1-4; Block 120-Parcel 1; Block 121-Parcels 1-39; Block 122-Parcels 2-40; and Block 123-Parcels 1-8, 10-20.

Sheet E-10: Block 18-Parcels 1-31; Block 19-Parcels 1,2,27,28; Block 82-Parcels 1-32; Block 83-Parcels 1-16; Block 98-Parcels 1,2; Block 99-Parcels 1,2,26,27.

Sheet DE-9: Block 14-Parcels 8-15; Block 16-Parcels 1-11; Block 17-Parcels 2-8, 10-20; Block 23-Parcels 1-5, 7-12, 23-26; Block 24-Parcels 13-25, ½ of 26; Block 111-Parcels 7-9.

Sheet DE-10: Block 20-Parcels 1-3, 24; Block 21-Parcels 1C, 3-13; Block 22-Parcels 1-4, 6-15; Block 23-Parcels 8,9,11-13; Block 24-Parcels 11-17; Block 25-Parcel 29.

Tax maps illustrating the boundary accompanies the nomination, and are drawn at 1" = 100' and accompany the nomination form.

BOUNDARY JUSTIFICATION


The boundary of the Galloway-Speedway Historic District includes all contiguous residential buildings retaining integrity along Faxon, Forrest, Galloway, Greenlaw and North Parkway avenues. The boundaries of the Galloway-Speedway Historic District were drawn to include all buildings historically associated with the neighborhood. The boundaries exclude Jackson Avenue to the north, which contains substantial post-1953 commercial development. Interstate 240 runs north-south and serves as the eastern boundary of the district. The district's western border is defined by the termination of the landscaped median of North Parkway at Leath Avenue. The original Memphis Parkway System ended one block further west at Manassas Avenue; however the dwellings along this block of North Parkway no longer retain sufficient architectural integrity, and thus the block was excluded from the district's boundaries. The southern boundary is drawn to exclude vacant lots and post-1953 residential and commercial development.

United States Department of the Interior
National Park Service

National Register of Historic Places Continuation Sheet

Section number 10 Page 98

Galloway-Speedway Historic District
Shelby County, Tennessee



Map of the district boundary lines for the Galloway Speedway Historic District.

**United States Department of the Interior
National Park Service**

National Register of Historic Places Continuation Sheet

Section number Photos Page 99

Galloway-Speedway Historic District
Memphis, Shelby County, Tennessee

PHOTOGRAPHS

Galloway Speedway Historic District
Memphis, Shelby County, Tennessee
Photo by: Thomason and Associates
Date: November 2003

Location of Negatives: Tennessee Historical Commission

- Photo No. 1 of 23: Streetscape, 900 Block Faxon Avenue. View to the SE.
- Photo No. 2 of 23: Streetscape, 900 Block Forrest Avenue. View to the NW.
- Photo No. 3 of 23: Streetscape 1000 Block Forrest Avenue. View to the SW.
- Photo No. 4 of 23: Streetscape of 900 Block Galloway Avenue. View NW.
- Photo No. 5 of 23: Streetscape of 1100 Block of Greenlaw Avenue. View SW.
- Photo No. 6 of 23: Streetscape of the median of North Parkway. View W.
- Photo No. 7 of 23: Streetscape of the 800 Block of North Parkway. View NE.
- Photo No. 8 of 23: Streetscape of the 900 Block of North Parkway. View W.
- Photo No. 9 of 23: Streetscape of the 1000 Block of North Parkway. View SW.
- Photo No. 10 of 23: 950 Faxon Avenue. View NW.
- Photo No. 11 of 23: 985 Faxon Avenue. View S.
- Photo No. 12 of 23: 985 Forrest Avenue. View S.
- Photo No. 13 of 23: 980 Forrest Avenue. View N.
- Photo No. 14 of 23: 1112 Forrest Avenue. View NW.
- Photo No. 15 of 23: 961 Galloway Avenue. View S.
- Photo No. 16 of 23: 971 Galloway Avenue. View SE.
- Photo No. 17 of 23: 1023 North Parkway. View S.

United States Department of the Interior
National Park Service

National Register of Historic Places

Continuation Sheet

Section number _____ Photos Page 100

Galloway-Speedway Historic District
Memphis, Shelby County, Tennessee

- Photo No. 18 of 23: Gable Detail, 1023 North Parkway. View S.
- Photo No. 19 of 23: Garage, 1023 North Parkway. View S.
- Photo No. 20 of 23: 961 North Parkway. View SW
- Photo No. 21 of 23: 925A & B North Parkway. View S.
- Photo No. 22 of 23: Epworth M. E. Church. 1120 Faxon Avenue. View NW.
- Photo No. 23 of 23: Fire Station No. 15, 1010 Faxon Avenue. View N.

United States Department of the Interior
National Park Service

National Register of Historic Places Continuation Sheet

Section number Photos Page 101

Galloway-Speedway Historic District
Memphis, Shelby County, Tennessee

Galloway Speedway Historic District Boundary Map with Photo Key.

