NFS Form 10-900	OMB No. 1024-0018 (Rev. 10-90)	
United States Department of the Interior National Park Service	MAY 2 9 1997	
NATIONAL REGISTER OF HISTORIC PLACES REGISTRATION FORM	NAL AUTOMATION DE L'OTTACES NETTOMAL FASIX SERVICE	
1. Name of Property		
historic name: Old Towne Orange Historic	District	
other names/site number: N/A		
2. Location		
street & number <u>see attached</u> city or town: <u>Orange</u> state <u>California</u> code <u>CA</u> county <u>Or</u>	not for publication	
3. State/Federal Agency Certification	***************************************	
As the designated authority under the National Hi I hereby certify that this <u>X</u> nomination meets the documentation standards for registering Historic Places and meets the procedural and prof Part 60. In my opinion, the property <u>X</u> meets Criteria. I recommend that this property be cons statemide <u>X</u> locally. (<u>See continuati</u>	request for determination of eligibility properties in the National Register of essional requirements set forth in 36 CFR does not meet the National Register idered significantnationally on sheet for additional comments.)	
Signature of certifying official	<u>May</u> 19,1997	
California Office of Historic Preservatio State or Federal agency and bureau	n	
In my opinion, the property meets Register criteria. (See continuation	does not meet the National sheet for additional comments.)	
Signature of commenting or other official	Date	
State or Federal agency and bureau		

.

•

,

Old Towne Orange Orange County, CA

4. National Park Service Certification I, hereby certify that this property is: _____ entered in the National Register See continuation sheet. determined eligible for the National Register See continuation sheet. determined not eligible for the National Register removed from the National Register other (explain): Date Signature of Keeper of Action 5. Classification

- Ownership of Property (Check as many boxes as apply)
- X private X public-local ___ public-State public-Federal Category of Property (Check only one box) building(s) X district site structure object Number of Resources within Property Contributing Noncontributing 1,230 512 buildings 0 sites 0 structures 0 objects

Number of contributing resources previously listed in the National Register 48 See continuation sheet Name of related multiple property listing: N/A

512 Total

Page 2

USDI/NPS NRHP Registration Form Old Towne Orange Orange County, CA	Page 3
6. Function or Use	
Historic Functions (Enter categories from instructions) Cat: See continuation sheet Sub: See contin	uation sheet
Current Functions (Enter categories from instructions) Cat <u>See continuation sheet</u> Sub: <u>See conti</u>	nuation sheet
7. Description	
Architectural Classification (Enter categories from ins Bungalow/Craftsman Mission/Spanish Colonial Revival Classical Revival Materials (Enter categories from instructions)	
foundation concrete, stone, brick roof terra cotta, asphalt, shingle walls stucco, weatherboard, brick other cast stone, wood, iron	

والمراجع والمحمد والمعامل والمراجع والمحمد والمراجعة والمحمد والمحمد والمراجع والمراجع والمراجع والمراجع والمح

Narrative Description (See continuation sheets.)

.

Old Towne Orange Orange County, CA

Page 4

8. Statement of Significance

Applicable National Register Criteria (Mark "x" in one or more boxes for the

criteria qualifying the property for National Register listing)

- X A Property is associated with events that have made a significant contribution to the broad patterns of our history.
- B Property is associated with the lives of persons significant in our past.
 - X C Property embodies the distinctive characteristics of a type, period, or method of construction or represents the work of a master, or possesses high artistic values, or represents a significant and distinguishable entity whose components lack individual distinction.
 - D Property has yielded, or is likely to yield information important in prehistory or history.

Criteria Considerations (Mark "X" in all the boxes that apply.)

- A owned by a religious institution or used for religious purposes.
- ____ B removed from its original location.
- C a birthplace or a grave.
- ____ D a cemetery
 - E a reconstructed building, object, or structure.
 - F a commemorative property.
 - G less than 50 years of age or achieved significance within the past 50 years.

Areas of Significance (Enter categories from instructions)

Transportation, Commerce, Industry, Agriculture, Architecture, Exploration/Settlement, Architecture

Period of Significance <u>1888-1940</u>	
Significant Dates <u>N/A</u>	
Significant Person <u>N/A</u>	
Cultural Affiliation <u>N/A</u>	
Architect/Builder various	

Narrative Statement of Significance (X See continuation sheets.)

Old Towne Orange Orange County, CA Page 5 9. Major Bibliographical References Bibliography. (X See continuation sheets.) Previous documentation on file (NPS) ____ preliminary determination of individual listing (36 CFR 67) has been requested. ____ previously listed in the National Register previously determined eligible by the National Register ____ designated a National Historic Landmark ____ recorded by Historic American Buildings Survey # recorded by Historic American Engineering Record # Primary Location of Additional Data State Historic Preservation Office ____ Other State agency Federal agency X Local government ____ University Other Name of repository: Orange Main Library 10. Geographical Data ______ Acreage of Property 515 UTM References (Place additional UTM references on a continuation sheet) Zone Easting Northing Zone Easting Northing 3739600 3 <u>11 422080</u> 1 11 420670 3739380 11 421900 3739710 4 11 422080 3738050

X See continuation sheet.

Verbal Boundary Description (X See continuation sheet.)

Boundary Justification (<u>X</u> See continuation sheet.)

Verbal Boundary Description and Justification are to be found at the end of Section 8.

Old Towne Orange Orange County, CA

Page 6

11. Form Prepared By

name/title_Steven G. McHarris organization_Old_Towne Preservation Association______date___1/9/97 street & number__P.O. Box 828_______telephone__(714) 639-6840 city or town__Orange_______state_CA__zip_code__92866

Additional Documentation

Submit the following items with the completed form:

Continuation Sheets

Maps

A USGS map (7.5 or 15 minute series) indicating the property's location. A sketch map for historic districts and properties having large acreage or numerous resources.

Photographs

Representative black and white photographs of the property. Additional items (Check with the SHPO or FPO for any additional items)

Property Owner

(Complete this item at the request of the SHPO or FPO.)
name various

street & number______telephone______telephone______

Paperwork Reduction Act Statement: This information is being collected for applications to the National Register of Historic Places to nominate proper ties for listing or determine eligibility for listing, to list properties, and to amend existing listings. Response to this request is required to obtain a benefit in accordance with the National Historic Preservation Act, as amended (16 U.S.C. 470 et seq.).

Estimated Burden Statement: Public reporting burden for this form is estimated to average 18.1 hours per response including the time for reviewing instructions, gathering and maintaining data, and completing and reviewing the form. Direct comments regarding this burden estimate or any aspect of this form to the Chief, Administrative Services Division, National Park Service, P.O. Box 37127, Washington, DC 20013-7127; and the Office of Management and Budget, Paperwork Reductions Project (1024-0018), Washington, DC 20503.

OMB Approval No. 1024-0018

NPS Form 10-900a (8-86)

United States Department of the Interior National Park Service

National Register of Historic Places Continuation Sheet

Section <u>2</u> Page <u>1</u>

Old Towne Orange, Orange County, California

Location:

Roughly bounded by Walnut Avenue, Waverly Street, W.O. Hart Park, La Veta Avenue, Clark Street, and Atchison Topeka Railroad track

OMB Approval No. 1024-0018

NPS Form 10-900a (8-86)

United States Department of the Interior National Park Service

National Register of Historic Places Continuation Sheet

Section ____5___Page___1____

The resource count includes these "non-building" features:

3 sites: W.O. Hart Park Plaza Park Orange Depot Park

4 objects: Nutwood Place 1906 Arroyo Stone Markers (includes 6 markers located at the Grand, Orange, and River Street Nutwood subdivision entrances)

Plaza Square Iron Hitching Post

414 E. Palmyra Concrete Hitching Post300 E. Chapman cast bronze 1887 Victorian fountain

These resources were previously listed in the National Register

Total:

48

National Register of Historic Places Continuation Sheet

Section number <u>6</u> Page <u>1</u> Old Towne Orange Historic District, Orange, CA

Function or Use

Historic Functions (Enter categories from instructions)

- 1. Domestic single dwellings, multiple dwellings.
- 2. Commerce/Trade business, professional, organizational, financial institution, department store, restaurant, warehouse.
- 3. Government post office
- 4. Education school, library.
- 5. Religion religious facility, church, church-related residence.
- 6. Recreation and Culture theater, outdoor recreation, sports facility, monument markers.
- 7. Agriculture processing, storage.
- 8. Industry manufacturing facility, industrial storage.
- 9. Landscape park, plaza, street furniture/object.
- 10. Transportation rail-related, road-related.

Current Functions (Enter categories from instructions)

- 1. Domestic single dwellings, multiple dwellings.
- 2. Commerce/Trade business, professional, organizational, financial institution, department store, restaurant, warehouse.
- 3. Government post office
- 4. Education school, library.
- 5. Religion religious facility, church, church-related residence.
- 6. Recreation and Culture theater, outdoor recreation, sports facility, monument markers.
- 7. Agriculture processing, storage.
- 8. Industry manufacturing facility, industrial storage.
- 9. Landscape park, plaza, street furniture/object.
- 10. Transportation rail-related, road-related.

(8-86)

Inited States Department of the Interior National Park Service

National Register of Historic Places Continuation Sheet

Section number _____7 Page _____1 Old Towne Orange Historic District, Orange, CA

NARRATIVE DESCRIPTION

The proposed Old Towne Orange Historic District (the District), locate between five major freeways in the center of urban Orange County ha withstood the pressures of growth throughout the decades. Once a smal agrarian community surrounded by citrus groves, farmland, and ranchir operations, Orange rapidly developed in the 1960's and 70's into a highl urbanized setting, leaving its historic downtown business district ar surrounding original neighborhood community primarily unchanged. Unlik many Southern California communities, Orange never experienced significan redevelopment or modernization of its original town area and thus retaine its original charm and character. This proposed National Registe nomination is the most significant of many preservation efforts for Ol Towne Orange.

The District consists of the original residential community, centra business district, and industrial area of Orange. The District retain its early 20th century character with mature street trees, early peric street lighting, subdivision monumentation, early period parks, trai depot, churches and the downtown commercial business district. There ar few intrusive non-contributing buildings in comparison to the number ar variety of contributing resources, with most having had little modificatic through the years.

The District is composed of historically interdependent buildings whic still exhibit the special ambiance associated with their time and place i history. On the whole, the homes and buildings are in a well-maintaine condition and retain their original architectural integrity. Distric buildings dating from the late 1880's, when the population was 866, throug 1940 are present and exhibit styles and architectural details unmatched i our present day housing tracts and planned communities. The complete stoc of downtown commercial buildings, industrial buildings, and surroundin residential homes and buildings, which are a part of the original tow settlement, remain in active use today, and represent a rare and importar reminder of the small town character once prevalent across the Souther California region.

The District core is represented by the Plaza and the Plaza Histori District buildings which consists of the original four-block commercia business district. These buildings, constructed largely during the 1905 1920 economic growth period, reflect the mode of construction and desig style popular in the Southern California region prior to 1925. The Plaz District acreage was originally set aside in 1871, but it was not unti 1886 that it was improved and the original fountain constructed (th original cast bronze fountain now sits in front of City Hall and th current fountain at the Plaza dates to 1936). Commercial buildings of th NPS Form 10-500-8 (8-86)

÷

United States Department of the Interior National Park Service

National Register of Historic Places Continuation Sheet

Section number <u>7</u> Page <u>2</u> Old Towne Orange Historic District, Orange, CA

Plaza Historic District are largely comprised of brick or concrete construction and veneer. The contributing early commercial buildings are primarily historic brick commercial with various examples of Mission Revival and one example of Corinthian columned Beaux Arts.

Surrounding the Plaza Historic District are four historic quadrants or neighborhoods which comprise the slightly larger than one square mile of original development in the City of Orange. This area is documented in the City of Orange General Plan as a local district with historic significance. Here a diversity of architectural styles, building types and neighborhood characteristics are represented. Homes and buildings from the 1880's through 1940 are still present in nearly the same concentrations as they existed prior to 1940. The streets are laid on a north-south east-west axis, supported by four spoke streets which radiate from the central Plaza and business district. Many of the residential streets have prominent homes situated on corners which provide a focal point from street t' street. Streets lined with numerous varieties of canopy trees or pal. trees provide countless beautiful neighborhood views and examples of traditional hometown character.

In general, there are four primary architectural periods and styles represented in the District: Victorian (1871-1900), Classical Revival (1900-1910), Craftsman and Bungalow (1910-1925), and Mediterranean Revival (1922-1935). While not every house or building is a pure example of its period, most draw heavily from the influences popular at the time of construction. The majority of the District houses have wood frame construction covered by wood siding or shingles with doublehung or casement windows and hipped and/or gabled roofs. They are built on raised foundations of cut stone, brick or cement and steps typically lead up to a front porch. Although numerous early detached garages still exist, they are not counted as contributing because many were not typically well constructed. Those remaining are generally in fair condition. The street lights, installed in the 1920's, are cast in cement and have fluted shafts on a octagonal base with a collar beneath the acorn shaped luminaries.

Most of the original houses have had only minor alterations such as concrete steps or composition shingles replacing the original wood steps or siding. More drastic alterations, such as enclosing front porches, stuccoing wooden siding and replacing windows with aluminum, are less common. A few houses were covered with asbestos shingles but as the District continues to be rehabilitated, more are having the asbestos shingles, and other inappropriate alterations removed. Some single family homes were converted to duplexes. These conversions seldom affected the outside appearance as most of these homes were originally built with tw front doors. Some of the larger homes with a main hallway entrance wer, also converted to multi-family use without exterior alterations. Some of NPS Form 10-900-a (8-86)

Jnited States Department of the Interior National Park Service

National Register of Historic Places Continuation Sheet

Section number <u>7</u> Page <u>3</u> Old Towne Orange Historic District, Orange, CA

the homes once multi-family have been or are presently being converted back to single family residences.

The dwellings in the proposed District also include former boarding and lodging houses, apartment buildings and cottages as well as estate homes. Most of the Districts estate homes are located along the larger spoke streets of Chapman Avenue and Glassell Street, while the Nutwood Place Subdivision and northwest quad/industrial area contain some of the most modest homes. The apartment buildings are closer to the Plaza Historic District as were the lodging and boarding houses. Overall, the District houses are predominantly one, one and one half, and two story, that are between 1000 and 2500 square feet in size.

The location of the Atchison Topeka & Santa Fe (AT&SF) rail line three blocks from the center of the business district provided opportunities for the development of industrial facilities for the receipt, packing and shipping of locally raised agricultural products. In 1900, the most important business was the fruit packing and shipping operations. Approximately 350 carloads of oranges were shipped out yearly, as well as lemons, walnuts, dried fruit, potatoes, peanuts, grapes, and cabbage. There are two historic packing house complexes that survive within the District. The earliest building is the Villa Park Orchard's Association Packing House complex which was built in 1919. The Richland Walnut Association building was constructed in 1924. In both cases the packing houses were constructed immediately adjacent to the rail line.

In 1914 the Orange Contracting and Milling Company built their yard and mill on Lemon Street. The false front industrial building consists of a wood frame sheathed with corrugated iron panels. The other false front industrial building within the District is the structure at 145 North Lemon Street that features pressed metal panels on the wall of the street facade.

During the 1920's larger industrial operations moved into the District's industrial area. In 1927 the Western Cordage Company, a rope manufacurer established in 1923, moved into the Richland Walnut Association Building. In 1928 the California Wire Company (1930 became the Anaconda Wire Company) built a complex of industrial buildings adjacent to the rail line between Palm Avenue and Maple Avenue. The buildings feature industrial steel windows and skylights to light the interior work areas. A cotton mill was originally established as a separate business to supply cotton yarn for the manufacture of weather proof wire and later became the California Cordage Company. It was located directly opposite the wire plant along the east side of Cypress (later used by Anaconda as the bare wire drawing mill). After 2 years of operation, machinery was sold and moved to a location on Lemon Street to start another mill. Another important early industrial business was the Ainsworth & Butler Lumber Company (1902 - 1914) at the

National Register of Historic Places Continuation Sheet

Section number _____7 Page _____4 Old Towne Orange Historic District, Orange, CA

corner of Maple Avenue and Cypress Street which supplied the majority of lumber and building materials to the growing Orange community during this period of growth.

Preservation Planning Background

In 1981, the City Council authorized preparation of a historic survey to identify, evaluate and document all pre-1940 buildings existing throughout the City. The purpose of the survey was to gather data needed to prepare a Historic Preservation Element of the City's General Plan. This survey was completed in 1982. The Council subsequently authorized an update and computerized listing of the original survey to further assess the City's historic resources. When the update was completed, it was presented to the City Council and Planning Commission in May 1992, at which time the Council took action to receive and file the report. Based upon the results of the original 1982 Orange Historic Survey and the updated 1992 Building Inventory, the City of Orange determined that there are special areas of historic importance in Orange that warrant preservation and conservation.

In 1982, the downtown Plaza Historic District was placed on the National Register of Historic Places. In 1983 the Historic Preservation Element was adopted into the City's General Plan. Included in the Element was the framework for a three-tiered planning approach to address the preservation needs of the adjacent historic residential neighborhood. The three concepts include: (1) adoption of design (by ord. '86) and demolition review (by ord. '88) processes in conjunction with sensitive land use planning, (2) the stimulation and promotion of neighborhood pride through a committed effort to revitalization, and (3) incentives for property owners to ensure ongoing preservation and revitalization efforts.

The District lies primarily within a larger area commonly known as "Old Towne" since July 1982. Old Towne encompasses the downtown area bounded by Walnut Avenue to the north, La Veta Avenue to the south, Cambridge Street to the east, Batavia Street to the west, and includes the Nutwood Place Subdivision and Hart Park south of La Veta Avenue. The Old Towne Orange Historic District proposes a more accurate and contiguous area which appears as it did during the period of documented significance. The proposed District contains a total of 1,237 contributing resources including numerous historic homes, six historic church sites (three historic buildings), three historic parks, three historic educational sites, several early industrial buildings, and includes the 35 historic buildings within the central business district. It is for this reason that the Old Towne neighborhood distinguishes itself from any other original settlement area within the City and County of Orange.

National Register of Historic Places Continuation Sheet

Section number _____7 Page _____5 Old Towne Orange Historic District, Orange, CA

The above mentioned 1992 Building Inventory reports finding a variety of architectural styles within the District. The predominant styles included: Bungalow, Hip Roof Cottage, Craftsman Bungalow, Craftsman, Mediterranean Revival, Victorian, Spanish Colonial Revival, Vernacular, California Bungalow, and Provincial Revival. Other notable but less frequent architectural examples include, Classic Box, Dutch Colonial Revival, Gothic, Italianate, Japo-Swiss/Craftsman, Moderne, Period Apartment Bldg., Prairie Influence, Victorian Cottage, Queen Anne Victorian, and Stone Bungalow.

The Plaza Historic District National Register Inventory reports a variety of brick commercial style buildings within the District. One notable bank of Corinthian columned Beaux Arts style is also present. Mission Revival style style is also present within the District.

National Register of Historic Places Continuation Sheet

Section number _____8 Page ____1 Old Towne Orange Historic District, Orange, CA

NARRATIVE STATEMENT OF SIGNIFICANCE

Historical Background and Significance:

The Old Towne Orange Historic District in the City of Orange, California, is nominated under National Register Criteria A and C. Under Criterion A, in the area of exploration/settlement, the District is the original community development which evolved from a pioneer settlement into an established center of the Orange County citrus industry during the years 1888 to 1940. These 52 years represent the period of development in which Orange began as a agricultural-based township and developed into a thriving small-town community, represented by distinct styles of architecture and methods of construction and craftsmanship which quickly diminished after 1940. The downtown Plaza marked the initial core of commercial development from which simultaneously evolved the surrounding early residential neighborhoods. Industrial development quickly followed suit with citrus and construction-related material yards, packing plants, an shipping/receiving businesses flourishing within the three short bloc between the Plaza and the Santa Fe rail line. Interdependent to onanother, commerce, industrial, and residential served the original Orange settlement. Under Criterion C, in the area of architecture, the District represents a large intact collection of early Southern California residential, commercial, and industrial buildings constructed during the years 1888 to 1940, with the majority maintained as such to present day. As discussed in more detail below, the significance in the District lies within the retention of so many early-period residential, commercial, and industrial structures which collectively retain the original town settlement architectural character and ambiance, and remains a central focus of community and civic pride to present day.

The town settlement of Orange traces its early beginnings to the breakup of the 1810 Spanish land grant Rancho Santiago de Santa Ana. When this sprawling cattle ranch was subdivided in the late 1860's, a Los Angeles lawyer, Alfred B. Chapman represented several parties in the partition suit. He took about four thousand acres as payment for his fees. Farm lots were first surveyed in the fall of 1870 ranging in size from ten to forty acres and divided in 1871, under the supervision of William T. Glassell (1827-1901). Four ten-acre lots were divided into eight 5-acre blocks with 20 lots in each block. These lot parcels were approximately 50 by 150 feet each, many with rear alley access.

The allocation of eight town lots in the center as a public square created the original Plaza Square. Walnut St. (now named Maple Ave.), bounded it on the north, Grape St. (now called Grand St.), on the east, Almond St. on the south and Lemon St. on the west. The two main intersecting streets we named Chapman Avenue and Glassell Street. The original name of the to was Richland, but this was changed to Orange by January 1875, when Mi.

National Register of Historic Places Continuation Sheet

Section number <u>8</u> Page <u>2</u> Old Towne Orange Historic District, Orange, CA

Chapman had the map recorded. The name had to be changed because there was another Richland in the State and the federal government refused to grant a duplicate post office. The town was incorporated April 6, 1888, as a sixth class city within Los Angeles County. Historic periodicals suggest that the reason for the early incorporation was to prevent saloons from coming to Orange and one of the first ordinances passed, was to prohibit the sale of intoxicating liquors. The size of the town at the time of incorporation was about three square miles, with a population of approximately 600. Additions to the town were made by subdividing the acreage tracts surrounding the original townsite, and naming such additions and their streets after the owner: such as Peter J. Shaffer and Nathan D. Harwood, Dewitt Clinton Pixley, and Charles Z. Culver. Other streets were named after their hometowns such as Palmyra and Batavia, New York. Daily life for most of Orange's early residents centered on small family ranches surrounding the townsite. Ten acres was a common size, at an average cost of \$300 per acre.

Like most Southern California communities, Orange was strongly affected by the Great Boom of the 1880's, especially since the Santa Fe Railroad (later AT&SF) entered Orange about four blocks west of The Plaza in August 1887. This land boom spurred the most important improvements to The Plaza. In 1886 the circular park pattern was designed and surveyed. Plantings (some of which still exist) and a central fountain completed the park. A number of the first brick commercial buildings also were constructed at this time, including the C. M. Woodruff store (1885) and the D. C. Pixley store (1886). These and other boom era brick buildings, or portions thereof, still stand and add to the District's sense of age and continuity. Water, a valued resource from the Orange Water Works, was delivered through a stove-pipe to what is now the Plaza and people hauled water in barrels to their homes. Flocks of sheep were allotted thirty minutes to drink at the fountain place.

Construction lay dormant in the aftermath of the great boom for over ten years. After 1900, another building period saw the construction of many of the most important structures in the Plaza Historic District. Examples of this early twentieth century building era are the N. T. Edwards Block (1905), the Ehlen & Grote Building (1907) and the Kogler Hardware Building (1916). The construction period slowed with the onset of World War I. The final building period influencing the composition of the District occurred during the 1920's. Notable buildings representing this period are the Orange or Pantages Theater (1928), the W. O. Hart Post Office (1926) and the former First National Bank Building (1928). This was the fourth and last construction period to have added buildings which now contribute to the District's historic significance. In later years, front and interior remodeling have altered some of the buildings, and some post World War II buildings mildly intrude.

National Register of Historic Places Continuation Sheet

Section number <u>8</u> Page <u>3</u> Old Towne Orange Historic District, Orange, CA

The original crop of Orange's agricultural era was not citrus, but grapes. Even at the time the city was named Orange, citrus crops were not abundant. Disaster hit the grape industry in 1886, when a blight destroyed all vineyards. Other crops such as apricots and walnuts were also successful, but were superseded by the citrus industry. By the late 1920's, Orange was one of the largest citrus producing areas in the State. This is reflected in the functions of at least two of the Plaza District's buildings. The first is the Santa Ana Valley Irrigation Company building of 1931. This 1877 cooperative water venture (through 1977) had its headquarters at this site. The Santa Ana Valley Irrigation Company served the farmers of Orange, Santa Ana and Tustin. Its control of water rights and extensive system of canals contributed significantly to the economic development of this area of Orange County. The second building of agricultural importance is the Orange County Fruit Exchange or Sunkist Building. The Orange County Fruit Exchange. This group marketed the citrus produc of Orange County under the famous "Sunkist" brand.

The Plaza Historic District was the commercial and social hub of the Orange Community and at one time held the principal banks, newspapers, stores and public institutions of Orange. Such business centers included the former Orange Building and Loan Bank, the Ehlen & Grote Building, the former First National Bank, the M. Dobner Block, and Watson's Drug Store. Many of these buildings have specific associations with early community leaders, including businessman D. C. Pixley, newspaperman W. O. Hart, and state senator N. T. Edwards. Social and humanitarian organizations also had their community headquarters here, such as the 1920's Elk's Building which continues to serve this benevolent order.

The Orange Public Library and the Orange Tribune, the first local newspaper were founded in 1885. Orange Postmaster Robert E. Tener (1850-1931) served as librarian, thus the library itself was originally housed in the Post Office Building on South Glassell. The Tribune was founded by Bill Ward (1842-1930), a Gold Country pioneer who made his opinions clear throughout the pages of the Tribune. A cautious believer in the "Boom", he left Orange at the end of 1887, selling the Tribune to Fred W. Clemons. Later revived as the Orange Post, the paper endured a succession of owners, operated for many years as an adjunct of the later Orange Daily News until 1946.

Acquired by the City in 1894, the Main Library operation and its outlying branches served the community to this day. Ward and Tener were both strong supporters of the efforts to create the Plaza park in 1886 and '87. By 1888, the Plaza was under construction. Mrs. Samuel Armor, wife of cit councilman and former county supervisor, organized the Women's Christia Temperance Union in the development of the Plaza. They raised \$200 through

National Register of Historic Places Continuation Sheet

Section number <u>8</u> Page <u>4</u> Old Towne Orange Historic District, Orange, CA

sponsoring community dinners, jubilees, and staging a play. Another highlight of 1886 was the formation of Orange's first bank, a statechartered institution known simply as The Bank of Orange. Though not all of the bank's capital came from Orange, local businessmen like D.C. Pixley and Jesse Arnold, who sat on the bank's Board of Directors, helped guide the bank's emergence as a major force in the community. It merged and was renamed the First National Bank of Orange in 1906. The bank survived until 1977. Today the building is occupied by a Wells Fargo branch office.

In August of 1887 Orange's Santa Fe depot opened alongside the tracks near West Chapman Avenue. The original building was replaced in 1938 by the present depot (closed since 1971 and subsequently purchased by the City of Orange for future preservation and reuse). The depot rail yard was recently improved in 1995 with the addition of a new platform and parking with period-style lighting and railings for the newly established Metrolink service. Orange's Depot Park, first developed in 1891, still survives as the oldest park in Orange. This park was recently improved and rededicated in 1996. Orange's other two railroads in 1888 were actually horse-drawn street cars: the Orange, McPherson & Modena and the Santa Ana, Orange & Tustin lines. The former was a short-lived line which ran from 1888 until 1891. The Santa Ana, Orange & Tustin line, which reached Orange in February of 1888, survived through various changes of ownership until it was finally taken over by the Pacific Electric line in 1906.

As late as 1881, the town still had only two organized churches. By 1888, that number had grown to six. Each of those pioneer churches continue to serve Orange today. The first congregation to organize in Orange was the Methodist Episcopal Church (now the First United Methodist Church of Orange) in 1873. They also built Orange's first church in 1875 on land donated by Chapman & Glassell on the east side of South Orange. This same land is owned by the church today. The only other church founded during Orange's first decade was the First Presbyterian Church, founded in 1874. Their first church (1881) was also built on land donated by Chapman & In 1888 the Rev. Alexander Parker was the church's pastor and a Glassell. well-known figure in the community, serving from 1883-1917. The next church to be founded in Orange was St. John's Lutheran Church, organized in 1882 by the Rev. Jacob Kogler, who would serve the congregation until 1917. Both the church and Rev. Kogler were mainstays in the lives of Orange's many German pioneers in the early days. Commonly known as the "German Church" in the 1880's, St. John's has also maintained a private school since its founding. The existing grandiose, Gothic church building was dedicated in 1914 and placed on the National Register on October 16, 1991.

National Register of Historic Places Continuation Sheet

Section number <u>8</u> Page <u>5</u> Old Towne Orange Historic District, Orange, CA

The First Christian Church of Orange was founded in 1883 with 19 charter members. From 1887 until 1963, their church was located at the southeast corner of Chapman and Grand. The First Baptist Church was founded in 1886. Their 1893 chapel at the corner of Almond and Orange is the oldest surviving church building in Orange. The newest congregation in 1888 Orange was the Trinity Episcopal Church. Its members met in a small church near the corner of Chapman and Lemon. It 1909, a year after Trinity became recognized as a separate church, a new church was built at the northeast corner of Maple and Grand, and presently serves as the Chapman University Chapel.

civic institution Another important was the Orange Intermediate School/Grammar School founded in 1872. After the old school had burned in the spring of 1886, Orange built a two-story school near the southeast corner of Sycamore Avenue and Glassell Street. This property had been donated to the Richland School District by Chapman and Glassell in 1877 The school housed K - 8 grades for approximately 40 years and then beca the Orange Intermediate School. This structure was placed on the Nationa. Register on April 13, 1993. This building was recently acquired in 1996 by Chapman University for the expansion of their law school program. In 1888 In 1888 the school's five teachers were under the leadership of Principal George Weeks who instituted many progressive changes and formalized the school's eight grades. The graduating class of 1888 consisted of just six students. At that time the closest high school was located in Los Angeles.

SETTLEMENT HISTORY

The Old Towne Orange Historic District is significant under Criterion A, in the area of exploration/settlement, because the area reflects an original community development that evolved historically into a cohesive neighborhood where the professional and trades people lived and did Many early residents were doctors, lawyers, and merchants. business. Thev developed the original downtown business district and resided in the adjacent subdivisions or ranches close to their shops and offices. Residents often worked, shopped and socialized in the downtown plaza area where the following services were rendered: Four excellent hotels, dry hardware, pharmacies, four clothing, grocery, physicians, aoods. confectionery, saddle and harness, millinery and dressmaking, feed store, wood and coal dealers, water companies offices, blacksmiths and wagon makers, boot and shoe makers, bankers, real estate, architects, surveyors, civil engineers, carpenters, painters, furniture shop, barbers, book and stationery, artists, musicians, and three theaters.

National Register of Historic Places Continuation Sheet

Section number <u>8</u> Page <u>6</u> Old Towne Orange Historic District, Orange, CA

Early Settlers & Community Leaders

A brief profile of eleven prominent District residents, who aided in establishing the community within the proposed District prior to the turn of the century through 1940, is as follows.

Sam Armor (1843-1933) arrived in 1875, and worked as a rancher, school teacher and carpenter until the mid-1880's when he built a wooden store building near the southwest corner of the Plaza, and opened a book and stationery store. In 1888 he replaced his first store with a new brick building, portions of which still stand today as part of the Ainsworth Block (100 W. Chapman). With the creation of Orange County in 1889, he served on the first Board of Supervisors, then later served on the Orange Board of Trustees. He also served as Orange's Justice of the Peace. His wife, Alice (1848-1939) served as editor and publisher of the Orange Post Trom 1892 to 1915. In his later years he prepared the first real history of Orange County in 1911 and helped to found the Orange County Historical Society in 1919. His home can still be found in the District at 363 S. Orange Street.

DeWitt Clinton Pixley (1857-1937) was Orange's most successful 19th century businessman. An 1881 arrival in Orange, he started in business here by purchasing one of Orange's first general merchandise stores, Robert L. Crowder & Co. In 1886 he built his own brick store building at 122 N. Glassell which still stands today. Pixley was also associated with many of Orange's early financial institutions including the Orange Building and Loan Association (founded 1887) and The Bank of Orange. Pixley served one term on the Orange County Board of Supervisors (1899-1903). He also served several terms as Orange's City Treasurer. His home can still be found in the District at 288 N. Olive Street.

Cornelius B. Bradshaw (1840-1932) was involved with each of these pioneer businessmen and was the city's only architect. Bradshaw's first major project in Orange was D.C. Pixley's new brick building in 1886. His last was the Kogler Hardware Co. store (143 N. Glassell) in 1916. In between, he designed virtually every major business block and many of the private homes in Orange. Among the best-surviving examples of his work are the I.O.O.F. Hall (112-120 E. Chapman) which opened in 1901, the Ehlen & Grote Company's "Big White Store" (108-126 S. Glassell), built in 1908, the Edwards Block (101-123 N. Glassell), built in 1905, and the original Orange Union High School Building (1905), now a part of Chapman University. Many of his downtown Orange buildings are now listed within the Plaza Historic District - National Register of Historic Places. NPS Form 10-900-a (8-86)

United States Department of the Interior National Park Service

National Register of Historic Places Continuation Sheet

Section number ____8 Page ____7 Old Towne Orange Historic District, Orange, CA

Albert S. Hamilton ran the Orange Livery stable, located midway down the block on the east side of North Glassell. Hamilton settled here in 1876 and in 1878 went into the livery business. Beside board and care for horses, Hamilton's livery kept a line of buggies for sale or rent. He also provided regular Omnibus service from the Santa Fe depot to the Palmyra Hotel. In mid-1888 the Orange Livery burned to the ground. Rather than rebuild, Hamilton had the St. James livery stable moved onto the site. Hamilton left town during the depression of the 1890's having declared bankruptcy early in 1895.

William Blasdale (1834-1892) settled in Orange in 1875, on a ranch at the northeast corner of Chapman and Tustin. He grew a variety of orchard crops including oranges, peaches and plums. In the late 1880's Blasdale had a two-story house built on his ranch. As development encroached, the house was moved to the northwest corner of Center and Santiago Blvd. in Villa Park, a neighboring community, where it stands today. The old Henry Gro⁺ house (169 N. Shaffer) was built by the same builder, and is a virtual tw to the original Blasdale house. Blasdale served as a director of the pioneering Orange Fruit Growers Association in 1880. In 1884 he was elected by the stockholders to his first term as a director of the Santa Ana Valley Irrigation Co. which conveyed water from the Santa Ana River to the Orange township and surrounding communities. He served two additional terms in 1888-89 and 1889-90 and, during each of his terms, acted as president of the water company. In 1888, shortly before the incorporation of Orange, he was appointed to fill an unexpired term on the Orange School Board. Blasdale served as Orange's first mayor from April, 1888 to September, 1890.

Dr. Orville P. Chubb (ca. 1830-1894) was one of the leading figures in the drive to incorporate Orange. He arrived in Orange in the mid-1880's, best remembered for the Orange, McPherson & Modena Street Railway and the Hotel Rochester. Chubb helped to back the line which linked the three communities during 1888 and '89 and served as its president. But the collapse of the "Boom" brought the end of the mule-drawn cars. The Hotel Rochester was also subject to the collapse of the "Boom." Built on Chubb's property at the southwest corner of Chapman and Lemon, the three story brick building dominated Orange's sparse skyline for decades, beginning in 1888 until the building was finally razed in 1931. He served three years from 1888 - 1891 on the Board of Trustees. His son, Mont. P. Chubb was also active in city affairs and served a term as City Marshall in the mid-1890s.

Charles Z. Culver (ca. 1849- 19??), born in Palmyra, New York, had moved to Orange in 1881 and established himself as one of the area's m prominent raisin grape growers. In 1885 he entered the real est business, opening an office in Los Angeles and declaring himself the "Santa

National Register of Historic Places Continuation Sheet

Section number <u>8</u> Page <u>8</u> Old Towne Orange Historic District, Orange, CA

Ana Valley Immigration Agent." Most of his immigrants were recruited from around his old hometown, as were many of his business partners. But Culver continued farming, until the winter of 1886-87 when he began work on Orange's Palmyra Hotel. When completed in July 1887, the large, two-story building had cost \$40,000, much of it supplied by Culver's many partners and investors. Some of Culver's other local projects included the Culver Hotel Tract, the Culver Home Tract (which featured its own tiny Plaza at the intersection of Orange and Washington), a number of small rental cottages and the surviving Palmyra Hotel Annex (205 E. Palmyra), listed on the National Register of Historic Places. But in 1888, as the "Boom" began to falter, so did Culver's finances. Shortly thereafter, on June 18, 1888, Culver resigned from the Board of Trustees. In October, Culver set off for Baja California never to return.

Henri F. Gardner (1852-1918) arrived in Orange in 1873 and began construction of a home on his 20-acre ranch along Glassell Street near the Santiago Creek. Gardner was involved with the Santa Ana Valley Irrigation Company from the time of its incorporation in 1877. He acted briefly as a Director of the company in 1880, was its Secretary/Treasurer in 1881-82 and beginning in 1892 served as Superintendent of the entire system for several years. When the collapse of the "Boom" left him heavily in debt, Gardner was careful to preserve the home ranch on Glassell. Portions of that land are still owned by his descendants to this day. Prior to his election as one of Orange's original City Trustees, Gardner's only elective office had been as a member of the Orange School Board. His first term as a City Trustee was only for two years, but in 1890 he won re-election to a four year term. In his later years Gardner divided his time between his property in Orange, Richfield and Los Angeles.

Peter J. Shaffer (1823-1907) was one of Orange's earliest pioneers, buying land in A.B. Chapman's Richland Farm Lots tract which surrounded Orange in 1871, and in 1874 building a substantial two-story home that stands today. Shaffer cultivated a wide variety of crops including almonds, apples, apricots, figs, walnuts, acres and acres of grains, and oranges. By 1881 he owned some 250 acres locally. Like most of the prominent ranchers in town, he was concerned with the success of the Santa Ana Valley Irrigation Company and served a term on its Board of Directors in 1878-79. Shaffer received one of the two four-year terms on Orange's new Board of Trustees, but did not seek re-election in 1892. In his later years he moved back and forth between Orange and Santa Ana. His home is considered the oldest remaining in Orange, built in 1874 at a cost of \$2,500. It is located in the District at 221 N. Orange Street.

Walter M. Scott (1842-1910) was born in Batavia, New York and raised in Wisconsin, settling in Orange where he acquired a substantial orange grove. Like many prominent men in Orange, Scott went into the real estate business

NPS Form 10-900-a (8-86)

United States Department of the Interior National Park Service

National Register of Historic Places Continuation Sheet

Section number <u>8</u> Page <u>9</u> Old Towne Orange Historic District, Orange, CA

during the "Boom", forming a partnership with Dr. Frank Seeber about 1886 that lasted several years. He served as Marshall in 1888 until retiring in April, 1892. He was appointed to Orange's Board of Trustees to fill the remaining two years of William Blasdale's second term. That same month he also received his commission as Orange's sixth Postmaster. He served in this dual role until the spring of 1894. Scott later moved to Santa Ana in the fall of 1894 to serve as Orange County Recorder until the end of 1902. He later served the county between 1907-1910 as the new County Assessor.

Andrew Cauldwell (ca. 1831-??) moved from New York state to Orange shortly after 1880, and established himself as a grower of the area's first major cash crop - raisin grapes. In 1883, along with his son and W.L. Witherbee, another local vineyardist, he founded Orange's first packing house at Maple and Grand. Initially, Cauldwell & Co. only packed and shipped raisins, but after the grape blight they moved into Orange packing. In 1889 they moved their building to the new Santa Fe tracks to simplify shipping. Under the supervision of Cauldwell's son, attorney A.B. Cauldwell, the packing hou remained in operation until 1893. Andrew Cauldwell was active in the drive for Orange's incorporation and served as a Judge at the April 6th election where he was also elected our first City Clerk. In 1887-88, Cauldwell served a term as President of the Santa Ana Valley Irrigation Company. He also served as founding President of the Orange Board of Industries, organized on December 8, 1888. The Board of Industries was the first attempt to form a local Chamber of Commerce. Cauldwell served on the fivemember Board of Commissioners which oversaw the election that separated the area from Los Angeles County and created Orange County on June 4, 1889. In late 1890, Cauldwell moved back East, perhaps to Washington D.C. where he had family.

HISTORIC RESOURCES

The homes and buildings included in the proposed Old Towne Historic District are those built prior to 1940 which still retain the majority of their original architectural integrity. The majority of the addresses are residential. Of these, a variety of historic architectural styles are present, but most are from the Craftsman period (1910-25). Those constructed between 1910-15 tend to be fully Craftsman while those built after 1925 are the bungalows which were a derivative of the Craftsman style. These Craftsman period houses are complemented by a strong representation of pre-1900 Victorian era homes which formed the original residential character of Orange. These are typically located on corner lots, but originally served as grove and ranch houses. In addition, a portion of the listings are from the Classical Revival period (1900-10) and are predominantly one story and simple in character. There are also sr homes from the Mediterranean Revival period (1922-35) and they

National Register of Historic Places Continuation Sheet

Section number <u>8</u> Page <u>10</u> Old Towne Orange Historic District, Orange, CA

generally located on the fringes of the District. The proposed District is unique among Orange County cities in that 1,237 properties remain intact.

The District has been evaluated and photographed by its four major spoke streets (Chapman Avenue and Glassell Street) which radiate from their intersection at the downtown commercial Plaza Historic District. The spoke streets create four distinct quadrants from which much of the District has been delineated. A description of the four quads, the spoke streets, and the Plaza Historic District follows. The later photo-documentation of typical street settings within the District identified these areas with the letters A - E preceding each photograph number.

The Northeast Quad is generally bounded by Chapman Avenue, Glassell Street, Waverly Street and Walnut Avenue. Homes and buildings located along Chapman and Glassell are presented in the later section entitled Spoke Streets.

The southwestern most portion of the quad is part of the original 1871 platt for the City of Orange. The remaining portion of the quad is part of subdivisions that date primarily to after the turn of the century. Subdivisions in this quad include: Library Tract - 1908, Bonnie Brae Tract - 1905, Cole's Sub. - 1901, Davis Cole's Add. - 1904, C.C. Honey's Sub. - 1905, W.H. Clayton's Tract #215 - 1905, Tract 480 - 1923, Marx's Sub. - 1923, Craddick's Sub. - 1906, Welch and Harrod's Resub. - 1908, Welch and Harrod's Add. - 1909, Cottage Home Tract - 1907, Maplewood Tract #202 - 1920, Maplewood Tract #136 - 1920, Henry Grote's Add. - 1887, Angelino Tract - 1887, and Valencia Park Tract - 1906. This quad, along with the others, served as an in-town neighborhood.

Only four square blocks of this quad were subdivided in the late 1880's (streets generally bounded by Shaffer Street, Chapman Avenue, Cambridge Street and Maple Avenue). The remaining portion of the quad was subdivided largely after 1905 with much of it not subdivided until 1920. This contrasts greatly with the other quads which were subdivided primarily in the late 1880's. Thus, there are primarily Craftsman era homes with several of those in the Classical Revival period, and a wide array of Craftsman bungalows, which are the most abundant selection in the proposed District.

The **Southwest Quad** is generally bounded by AT&SF railroad, Chapman Avenue, Glassell and La Veta Avenue, and also includes the Pixley/Parker street neighborhood. Homes and buildings located along Chapman Avenue, Glassell Street, and the Plaza Historic District are presented later in this section.

National Register of Historic Places Continuation Sheet

Section number _____8 Page _____11___ Old Towne Orange Historic District, Orange, CA

The northeastern most portion of the quad is part of the original 1871 platt for the City of Orange. The remaining portion of the quad is part of the subdivisions that date primarily to the boom of the 1880's. Subdivisions in this quad include: Chas. E. Spotts Sub. - 1913, Kordes Tract - 1887, Chubbs Add. - 1886, Beach's Add. - 1885, Palmyra Square - 1896, La Veta Home Tract -1923, McCoys Add. - 1887, Phelps Tract - 1887, and Gardners Add. - 1887. This quad served as an in-town neighborhood. The influence of the railroad produced some of the earliest remaining homes.

Similar to the other quads, this one contains large anchor homes which housed the earliest, and usually the most prominent settlers. Some homes from the Classical Revival period and many from the Craftsman period were infilled in the early part of this century after the removal of the large groves. The homes which do remain are primarily good, intact period examples.

The **Northwest Quad** is generally bounded by Chapman Avenue, Glasssell Street, Walnut Avenue and the AT&SF rail line. Homes and buildings located along Chapman Avenue, Glassell Street and the Plaza Historic District are presented later in the section.

The southeastern most portion of the quad is part of the original 1871 platt for the City of Orange. The remaining portion of the quad is part of subdivisions that date primarily to the boom of the 1880's and just after the turn of the century. Subdivisions in this quad include: Spotts Villa Tract #965 - 1933, Hollister's Sub. - 1906, G. H. Pirie's Home Tract -1907, Caudwell and Wetherbee Add. - 1887, Richland Farm Lots - 1883, Arthur West Add. - no date, Longfellow Tract - 1887, Davis Tract - 1887, and Halladay Tract - 1886. This is one of four quads which make up the original township of Orange.

The majority of contributing homes in this quad are Craftsman bungalows from the period 1915-25. The railroad packing house and industrial buildings of the quad interface with modest houses that were built on the western edge of the District. These houses largely located on Pixley, Cypress and Lemon Streets, are one story wood frame residences that provided homes for workers who were occupied by the industrial facilities and packing houses in the area. Mrs. Carrie Martinez, who lived at 177 North Cypress Street, and Mr. Bernardino Martizes, who lived with his wife Frances at 185 North Cypress Street, were identified in the 1907 Directory as laborers. Mr. and Mrs. M.C. Cuddelback lived at 177 North Cypress. Mr. Cuddelback was listed as a retired builder. Their homes were typical small square box design wood frame residences with a hipped or pyramidal roof and a projecting front porch. This turn-of-the-century style of residenc was replaced by the bungalow style of home. An example of this type of NPS Form 10-900-a (8-86)

Inited States Department of the Interior National Park Service

National Register of Historic Places Continuation Sheet

Section number <u>8</u> Page <u>12</u> Old Towne Orange Historic District, Orange, CA

house was the residence at 155 North Lemon Street built in 1920 by Rebecca Gillogy, the widow of a carpenter. The bungalow style house features a large front porch, low pitched roof with projecting eaves.

This quad is also home to the 1938 Santa Fe Depot which represents the transition between the Spanish Colonial Revival style and the Moderne style. The exterior of the building, with its arcaded outdoor Waiting Room, plaster walls and red tile roof, represents an architectural idiom that was soon to pass out of favor. The Streamline Moderne details of the entrances and the Waiting Room are indicative of architectural design and development in this industrial age. The 1891 park adjacent to the train station retains a number of trees that were planted by the citizens who originally created the park. The trees represent species that were particularly popular in the late nineteenth century.

The **Southeast Quad** is generally bounded by Chapman Avenue, Glassell Street, La Veta Avenue/Santiago Creek and Waverly Street. Homes and buildings located along Chapman and Glassell are presented in the later section entitled Spoke Streets.

The northwestern most portion of the quad is part of the original 1871 platt for the City of Orange. The remaining portion of the quad is part of subdivisions that date primarily to the boom of the 1880's. Subdivisions in this quad include: Shaffer's Add. - 1886, C.Z. Culver Home Tract - 1887, C.Z. Culver Hotel Tract - 1887, Grand Ave. Add. - 1887, George Atchison Sub. - 1905, Harwood's Add. - 1887, Kogler and Geiger's Add. - 1887, Cosart Add. - 1904, A.L.C. Bibbers Resub. - 1906, Palm Place - 1908, Hartwicks Sub. - 1910, Lockwoods Add. - 1886, Craddick's Home Tract - 1906, and the Nutwood Place Sub. - 1906. Historically, this quad, along with the others, served as an in-town neighborhood.

The quad also contains the Nutwood Tract subdivision, located south of La Veta Street immediately adjacent to W.O. Hart Park. The Nutwood Tract was subdivided in 1906 as a distinct neighborhood entity known as Nutwood Place. The streets offered the first departure from the regular grid street pattern and are narrower than in the District area to the north. These streets remain in place today and are still oriented toward the Santiago Creek riverbed in W.O. Hart Park. This neighborhood was the first to have paved streets, even before street paving in the Plaza. The neighborhood contains a variety of homes which are predominantly larger Craftsman and smaller Bungalow homes from the 1910-25 period. The neighborhood is identified by prominent arroyo stone entry markers which announce "Nutwood Place" on either side of all the entry streets. NPS Form 10-900-a (8-86)

United States Department of the Interior National Park Service

National Register of Historic Places Continuation Sheet

Section number _____8_ Page _____13_ Old Towne Orange Historic District, Orange, CA

Similar to the other quads, this one contains large anchor homes which housed the earliest, and usually the most prominent, settlers. Most of the homes are of the Classical Revival and Craftsman styles. This quad represents the most solid concentration of early homes in Orange. Very few newer houses or intrusions exist, particularly in the northern and westernmost portions of the quad. Nearly one example of every architectural style which evolved in Orange exists in this quad. The vast majority, however, are of the Craftsman and bungalow styles.

The **Spoke Streets** historically served as main arterials to and from downtown Orange to this day. Chapman Avenue and Glassell Street are the only two streets which radiate from the Plaza. The Spoke Streets contain some of the largest homes built in the early years of Orange. Before the days of the modern automobile, it was advantageous to live close to the downtown and, therefore, the lots along Chapman Avenue and Glassell Street were at a premium. Generally, both North and South Glassell Street as we! as East Chapman Avenue contain the prominent residences of the City pioneers and date from the turn of the century to the Craftsman period. Homes that are farther from the downtown, particularly along East Chapman Avenue, are large, affluent Mediterranean Revival homes. Many doctors, contractors, merchants and others of wealth and prominence lived along these Spoke Streets. Several average-sized homes were also constructed amongst the larger ones.

In the 1920's new commercial buildings were being erected on Chapman Avenue, west of the Plaza. These one story buildings featured large glass display windows and glazed entrance doors set into a facade veneered with decorative brick and terra cotta. A good example of the 1920's vernacular commercial buildings is the structure at 401 West Chapman Avenue. During this period, Southern California became an active market for the sale of cars in the 1920's. There are two buildings along West Chapman Avenue that were designed expressly to serve this new form of transportation. The new vernacular commercial building at 402 West Chapman Avenue served as the home in 1924 for O.A. Haley Company, which is believed to be the first auto dealership in Orange. The service station at 237 West Chapman Avenue is believed to be the first gas station in Orange. The restrained Streamline Moderne details of the building indicate that it may date from the late 1920's or early 1930's . Additionally, in 1935 the Post Office was erected at 305 West Chapman Avenue. Designed in the Spanish Colonial Revival style, the Post Office introduced a new architectural note to the vocabulary of building types on Chapman Avenue. Most of these early buildings are in well-maintained condition and retain their original architectural integrity.

National Register of Historic Places Continuation Sheet

Section number <u>8</u> Page <u>14</u> Old Towne Orange Historic District, Orange, CA

The Plaza Historic District contains fifty-three buildings of which thirtyfive are historic and contributing to the significance of the district. The majority of these are brick commercial in style, however a few concrete buildings may also be found. The district centers upon The Plaza, a public square. The Plaza was laid out in 1886 and has been in continuous use since that date. The circular park in the center of The Plaza holds a fountain dating from 1937 and a number of mature trees, some of which date from the park's creation. Brick sidewalks and planters were added to the corners in 1970. The Plaza is the hub from which two streets radiate in four The north-south street is Glassell Street and the east-west directions. street is Chapman Avenue. The buildings within the first block north and south and the first one and one-half blocks east and west of The Plaza include most of the Plaza Historic District. Almost all of the buildings within the Plaza District adjoin one another to form a continuous row of structures. Few breaks appear between buildings giving the District a listinct appearance as a single commercial area. While a few of the Jistrict's building facades have been altered over the years in almost all such instances, the rear portions of these buildings have successfully preserved the original brick construction style and appearance. The Plaza District presents its component parts in a holistic manner by not simply focusing on facades or store fronts as measures of the degree of historic integrity.

Currently the District maintains its commercial uses primarily within the Plaza area although these have changed in recent years as the agricultural economic base of Orange has been replaced with increased urbanization. A number of antique dealers are located in this area taking advantage of the historic atmosphere. Also, several office professional firms specializing in engineering, architecture and planning have located here. These examples of present District occupants reflect the changes that have affected the district and reinforce the importance of preserving the character and ambiance of small town America on the rapidly evolving Southern California landscape.

BOUNDARY DESCRIPTION

The Old Towne Orange Historic District is located in the City of Orange. The District is located in the original downtown area and incorporates the existing National Register Plaza Historic District. The proposed boundaries follow property lines, streets and a rail line, and are roughly bounded by Walnut Avenue on the north, Atchison, Topeka and Santa Fe (AT&SF) rail right-of-way, and Clark, Parker and Glassell Streets on the west, La Veta Avenue and Santiago Creek to the south, and Cambridge and Waverly Streets on the east. Precise boundaries are located on the accompanying base map. NPS Form 10-900-a (8-86)

United States Department of the Interior National Park Service

National Register of Historic Places Continuation Sheet

Section number <u>8</u> Page <u>15</u> Old Towne Orange Historic District, Orange, CA

BOUNDARY JUSTIFICATION

The boundaries of the proposed Old Towne Orange Historic District delineate the original residential, industrial, and business community of Orange from the late 1880's through 1940. The District incorporates the heart of the historic downtown commercial and business center (circa 1905-20). The proposed boundaries reflect the early downtown subdivisions of Orange which originated from the first building boom of the late 1880's, again occurring just after the turn of the century, and continuing through the 1920's. The District experienced a steady infill of building construction during the 1930's.

Much of the area outside the proposed boundary experienced either a loss in architectural integrity or was under citrus cultivation into the 1950's and 60's before subdivision occurred, thus being excluded from District consideration. This is particularly noticeable in the area west of t AT&SF railway where substantial "newer" construction and concentrations altered, non-contributing structures depart from the continuity and pre 1940's context within the proposed District. Only the South Clark, Parker, Pixley, and West Culver Street neighborhood remains intact as an exception and is included in the proposed District. The remaining boundaries follow a distinct development pattern occurring after 1940, primarily in the 1950's and 60's. The proposed District boundary provides a distinct delineation between the original historic Orange community and the neighborhood sprawl and suburban character of later development periods.

The proposed District contains a comprehensive array of 1888 to 1940 industrial, and commercial building types residential, and various architectural styles which make this area almost as eclectic and independent as it was originally. The values enlisted under Criterion A are addressed in the historic quintessence of Orange and the City's founding, the demonstration of early Southern California appearance and lifestyle, and the amiable values of its citizens. The principles of Criterion C are exhibited in the physical Old Towne Historic District contributing buildings which are interdependent in function and location within the overall District and still display a special ambiance associated with their time and place in history.

NPS Form 10-900-a (8-86)

United States Department of the Interior National Park Service

National Register of Historic Places Continuation Sheet

Section number _____9 Page ____1 Old Towne Orange Historic District, Orange, CA

MAJOR BIBLIOGRAPHICAL REFERENCES

National Register of Historic Places, The Plaza Historic District, Orange Community Historical Society, 1982

Santa Fe Depot Area Specific Plan, City of Orange, 1993

<u>Old Towne Orange, A Walk Through History & Brochure</u>, Kathleen Less and Philip Brigandi, 1992

<u>Orange California History, A Compilation Of Various Sources</u>, Orange Public Library, 1995

<u>Color It Orange, A Selection of Stories About the City of Orange</u>, Orange Community Historical Society, 1993

<u>A Place Called Home, Orange's Architectural Legacy</u>, Phil Brigandi and Karen Wilson Turnbull, 1990

<u>A New Creation, The Incorporation of the City of Orange 1888</u>, Phil Brigandi, 1988

Growth and Progress of Orange, Chamber of Commerce Report, August 1959

<u>City of Orange General Plan Historic Preservation Element</u>, City of Orange Planning Department, 1983

<u>Historic Inventory Old Towne - Photo Records Volumes I - V</u>, City of Orange Planning Department, 1982

Historic Preservation Design Guidelines for Old Towne Orange, California, City of Orange, August 1985

<u>Historic Preservation Design Guidelines for Old Towne Orange, California,</u> City of Orange, August 1995

City of Orange Historic Building Inventory Update, Final Report, AEGIS, October 1991

City of Orange Directories, Florence Flippen Smiley, City of Orange, CA

Old Towne Orange Historic Resources Base Map, City of Orange Planning Department, 1996

Local History Ephemera Files, Orange Public Library, City of Orange, CA

National Register of Historic Places Continuation Sheet

Section number _____7 Page ____6 Old Towne Orange Historic District, Orange, CA

1. 215 E. Almond c1915 Craftsman Historical Name: AP Number: 390-392-01 A one and one-half story Craftsman house with single, side-facing gable roof and contrasting, front facing gable dormer. Main roof extends forward to form full-width porch supported by brick piers connected by a brick porch wall.

2. 218 E. Almond

c1929 Bungalow Historical Name: AP Number: 390-392-01 Single-story and single-gable bungalow with main roof being comprised of a side-facing gable. A contrasting, front-facing gable forms entry porch overhang supported by Colonial-like columns.

3. **220 E. Almond** 1901 Historical Name: AP Number: 390-653-20 Non-Contributor

4. **225 E. Almond** 1922 Historical Name:

AP Number: 390-663-08 Non-Contributor

5. 230 E. Almond

c1920 Bungalow Historical Name: AP Number: 390-392-11 Single-story clapboard bungalow with L-plan and tri-gable roof. Main entry is at center front, slightly recessed beneath main facade of house.

6. **318 E. Almond** Historical Name: AP Number: 390-393-12 Non-Contributor

National Register of Historic Places Continuation Sheet

Section number _____7 Page _____7 Old Towne Orange Historic District, Orange, CA

7. **332 E. Almond** Historical Name: AP Number: 390-393-11 Non-Contributor

8. 414 E. Almond

1909 Hip Roof Cottage Historical Name: AP Number: 390-394-11 Single-story house with steep-pitched, hip roof and clapboard siding. Small hipped dormer is on front portion of roof; a smaller hip extension of main roof forms entry porch overhang supported by characteristic Classical columns.

9. 422 E. Almond

1905 Hip Roof Cottage Historical Name: AP Number: 390-394-10 This single-story house has both Classical Revival and Craftsman bungalow influences. The house is single-story, has clapboard siding and a hip roof. It is built on a box plan. An unusual feature for the period is a smaller gable projection, pedimented and embellished with fish scale singles. Below the porch, supports are treated in the Craftsman manner.

10.430 E. Almond

c1910 Stone Bungalow Historical Name: AP Number: 390-394-09 What makes this bungalow home unusual is the stone facing used throughout. The format of the house incorporates classic bungalow formatting built on a rectangular plan with double, front-facing gable. The stone facing makes it a one-of-a-kind house in Orange.

11.440 E. Almond 1941 Historical Name: AP Number: 390-394-08 Non-Contributor

يحاد بصبحه منافع وبرود ووريديسوس والارتهامين بالمداد الالات الديمية

United States Department of the Interior National Park Service

National Register of Historic Places Continuation Sheet

Section number _____7 Page ____8 Old Towne Orange Historic District, Orange, CA

12.506 E. Almond c1905 Hip Roof Cottage Historical Name: AP Number: 390-431-01 Box plan house with steep-pitched, hip roof and circular, wrap-around porch. The circular porch is complemented by a pedimented gable face adjacent which features a large, transomed picture window. Classical columns support the porch overhang.

13.514 E. Almond

1922 Bungalow Historical Name: AP Number: 390-431-02 Small, single-story bungalow with single, shallow-pitched, side-facing gable roof and smaller front-facing gable attic dormer. Main entry is via a former porch recessed beneath main portion of house; this porth is supported by an elephantine pier articulated by ornamental bricks at the base.

14.501 -515 E. Almond

1929 Mediterranean Revival

Historical Name: St. John's Lutheran School AP Number: 390-442-01

This is a one-story school building in the Mediterranean Revival style. The building features a symmetrical design which includes a central entry flanked by windows and a projecting corner wing on either side. The building is constructed in brick and has an adobe tiled roof. The main entry includes an arched parapet and an inner entry arch. This same arch is repeated again in the transom above the double door entrance. Terra cotta molding outlines both the inner and outer arch. Six sash windows with six-over-six panes are located on either side of the entrance; each of these windows has a reliever arch with a fanlight transom. The projecting corner walls are embellished with corner quoins and a diamond arrangement of contrasting brick. The building is in excellent condition and maintains its original architectural integrity.

15.524 E. Almond

1904 Hip Roof Cottage Historical Name:

AP Number: 390-431-03

Single-story house built on a box plan with clapboard siding and a steeppitched hip roof. A smaller, front-facing gable is above the corner porch and serves as an attic dormer. Main entry is beneath the recessed corner porch, supported by wood posts.

National Register of Historic Places Continuation Sheet

Section number _____7 Page _____9 Old Towne Orange Historic District, Orange, CA

16.530 E. Almond

1914 Craftsman Historical Name:

AP Number: 390-431-04

A single-story bungalow with single, front-facing gable roof. The house has clapboard siding at the base, but the upper portion of the gable face is sheathed in shingles. A full-width porch is recessed below the main portion of the house. This porch overhang is supported by characteristic elephantine piers with arroyo stone bases.

17.535 E. Almond

1923 Craftsman Bungalow Historical Name: AP Number: 390-442-20 Single-story, clapboard bungalow with shallow-pitched, double front-facing gables. Forwardmost gable forms entry porch overhang supported by tapered piers.

18.540 E. Almond

1908 Hip Roof Cottage Historical Name: AP Number: 390-431-05 A single-story, box plan house with pyramidal roof and clapboard siding. Corner porch is recessed beneath main portion of the house and is supported by characteristic classical column.

19.543 E. Almond

1946 Historical Name: AP Number: 390-442-19 Non-Contributor

20.545 E. Almond 1961 Historical Name: AP Number: 390-442-18 Non-Contributor

National Register of Historic Places Continuation Sheet

Section number _____7 Page _____0 Old Towne Orange Historic District, Orange, CA

21.548 E. Almond 1977 Historical Name: AP Number: 390-431-06 Non-Contributor

22.601 E. Almond

1913 Craftsman Bungalow Historical Name: AP Number: 390-442-17 Single-story, clapboard bungalow with double, front-facing gable roof. Forwardmost gable forms entry porch overhang supported by tapered piers.

23.604 E. Almond

1909 Historical Name: AP Number: 390-431-07 Non-Contributor

24.607 E. Almond

1913 Craftsman Bungalow Historical Name: AP Number: 390-442-16 Single-story clapboard bungalow with double, front-facing gable roof. Forwardmost gable forms entry porch overhang supported by wide piers. Added embellishment is provided by ornamental purlins beneath the eaves and by dentils along the frontmost gable face.

25.612 E. Almond

1909 Hip Roof Cottage Historical Name: AP Number: 390-431-08 Single-story, box plan house with clapboard siding and pyramidal roof. No porch is present. Entry is at center, flanked by a large, double-hung window on either side.

26.615 E. Almond

1913 Craftsman Bungalow Historical Name: AP Number: 390-442-15 Single-story, clapboard bungalow with double, front-facing gables. Smaller, forwardmost gable forms entry porch overhang supported by wide piers. Vertical slatting and purlins at the eaves ornament the house.

/

National Register of Historic Places Continuation Sheet

Section number _____7 Page _____11 Old Towne Orange Historic District, Orange, CA

27.618 E. Almond 1966 Hip Roof Cottage Historical Name: AP Number: 390-431-09 A single-story, box plan house with clapboard siding and steep-pitched hip roof. Small hipped dormer is located on front portion of roof. Entry is via a corner recessed porch supported by Classical columns.

28.624 E. Almond

1914 Bungalow Historical Name: AP Number: 390-431-10 Single-story, clapboard bungalow with double, front-facing gable roof. Frontmost gable forms entry porch overhang supported by wide piers. Ornamental purlins grace the eaves. The front facade is adorned by a large, 3-part picture window.

29.627 E. Almond

Historical Name: AP Number: 390-442-14 Non-Contributor

30.638 E. Almond

1909 Hip Roof Cottage Historical Name: AP Number: 390-431-11 A single-story clapboard house with box plan and steep-pitched hip and gable roof. The house sits on a corner lot, and a large, corner wrap-around porch defines the entry; main door is also on the corner. The porch roof is supported by ornate turned columns with jigsawn brackets at the top. Two gabled dormers have ornamental shingles and vented transoms.

31.639 E. Almond

Historical Name: AP Number: 390-442-13 Non-Contributor

32.708 E. Almond 1904 Victorian Historical Name: Honey House AP Number: 390-432-22 Non-Contributor

National Register of Historic Places Continuation Sheet

Section number _____7 Page _____12 Old Towne Orange Historic District, Orange, CA

33.**714 E. Almond** Historical Name: AP Number: 390-432-23 Non-Contributor

34.**729 E. Almond** Historical Name: AP Number: 390-443-11 Non-Contributor

35.**730 E. Almond** Historical Name: AP Number: 390-432-02 Non-Contributor

36.**734 E. Almond** Historical Name: AP Number: 390-432-03 Non-Contributor

37.**742 E. Almond** Historical Name: AP Number: 390-432-04 Non-Contributor

38.800 E. Almond Historical Name: AP Number: 390-432-07 Non-Contributor

39.802 E. Almond Historical Name: AP Number: 390-432-05 Non-Contributor

40.806 E. Almond Historical Name: AP Number: 390-432-06 Non-Contributor

National Register of Historic Places Continuation Sheet

Section number _____7 Page _____13 Old Towne Orange Historic District, Orange, CA

41.831 E. Almond Historical Name: AP Number: 390-444-11 Non-Contributor

42.914 E. Almond

Bungalow Historical Name: AP Number: 390-461-02 A single story clapboard bungalow. The main portion of the house is covered by a single side-facing gable roof while a smaller front-facing gable forms the entry porch. The porch columns are simple 4x4's adorned at the base and top by molding. Two sets of two double hung windows are placed on either side of the door.

43.924 E. Almond

Mediterranean Revival Historical Name: AP Number: 390-461-03 A single story rectangle plan house with stucco siding, a flat roof and an attached garage. A front entry portico is formed by a rectangular projection with large opening. Both the porch portico and main house have raised parapets at the center with adobe tiles. The front picture window has a leaded glass transom.

44.932 E. Almond

Bungalow Historical Name: AP Number: 390-461-04

Originally a single story bungalow, this structure has had a second story added to it. The original portion of the structure has been stuccoed. The porch is formed by a front facing gable and is supported by piers comprised of stucco bases and wood posts on top. Matching picture windows with mullioned transoms and two double hung windows are on either side of the entry.

United States Department of the Interior National Park Service

National Register of Historic Places Continuation Sheet

Section number _____7 Page _____14 Old Towne Orange Historic District, Orange, CA

45.940 E. Almond

Transitional Cottage Historical Name: AP Number: 390-461-05

A 1 1/2 story brick and stucco box plan house. The entry is recessed and in a atrium/terrarium type setting formed by 3' brick walls extending from the house walls and a fountain and brick setting benches. The roof is a combination of gabled and parapet styles. A front and side gable seem to sit in the middle of the parapet. A single dormer extends off the other side. The front mullioned windows are in a stucco portion of the wall with adobe tile hoods over them.

46.1010 E. Almond

1937 Transitional Revival Historical Name: AP Number: 390-462-01 A single story clapboard L-plan house with double front facing gabled roof and a single side gable. A portion of the forward most front gable forms a small porch. The porch pier is formed by a concrete base and a classical wood post on top. The backward front gable is adorned with shingles. An ornamented brick chimney is present.

47.1012 E. Almond

1905 Victorian Historical Name: AP Number: 390-462-02

A 1 1/2 story clapboard rectangular plan house. A steep front and back facing gable forms the main portion of the roof. Two side facing dormers are accented with shingles as is the front facing gable. A large open porch running the full length of the house is placed on the side of the house. It is supported by simple wooded 4x4's. A small front porch is placed over the entry door and a window. The porch is supported by purlins. Both porches have a roof similar to a hipped roof. The eaves articulated with ornamental rafter tails.

National Register of Historic Places Continuation Sheet

Section number _____7 Page _____15 Old Towne Orange Historic District, Orange, CA

48.1014 E. Almond

1905 Victorian Historical Name: AP Number: 390-462-03 A single story box plan house with wide lap siding and a steep-pitched hipped roof. A small hipped dormer is present on the front facade. A small concrete, un-roofed porch forms the entry to the house. The entry door is accented by two narrow windows. The wide eaves are embellished with ornamental rafter tails.

49.122 W. Almond

Historical Name: AP Number: 390-654-01 Non-Contributor

50.206 W. Almond

1902 Classic Box Historical Name: AP Number: 390-653-21 This eclectic home combines features from both the Classical Revival style and the Craftsman style. Boxy formatting, hip roof and dormers, and rotund columns suggest Classical Revival. Arroyo stone columns on corner porch and brick on first story suggest Craftsman influences. Also notable is a large, recessed corner porch and arched windows on front and side facades.

51.220 W. Almond Historical Name: AP Number: 390-653-20 Non-Contributor

52.225 W. Almond 1924 Bungalow Historical Name: AP Number: 390-663-08 Vacant Lot

National Register of Historic Places Continuation Sheet

Section number _____7 Page _____16 Old Towne Orange Historic District, Orange, CA

53.229 W. Almond c1910 Rock Bungalow Historical Name: AP Number: 390-663-07 This rectangular plan house has a single-gable roof. Most notable is the arroyo stone on the first floor below the roof line. A corner recessed porch is supported by a large stone pier. Ornamental bargeboard is on front-facing gable.

54.230 W. Almond

Historical Name: AP Number: 390-653-01 Non-Contributor

55.237 W. Almond

c1915 Craftsman Bungalow Historical Name: AP Number: 390-663-06 Built with a rectangular plan, this house has a double, front-facing gable.

The front porch is supported by wide, elephantine piers common to Craftsman styling. Beneath the eaves are ornamental purlins. An ornamental transomed window is in the frontmost gable, and a large transomed picture window is near the entry.

56.305 W. Almond

1923 Vernacular Historical Name:

AP Number: 390-662-10

This is a small, single-story clapboard church with a single gable roof. The corner entry is articulated by a rectilinear entry tower with a pyramidal roof. Casement windows around the building are arranged in pairs, and each is crowned with a large, stained glass transom. These arched windows are repeated in the entry tower. Triangular bracket supports are located beneath the eaves on the front gable face. The church was built adjacent to a small, Classical Revival style house which still forms part of the church. These two are connected in such a way that together they appear as one building. The church shows slight Craftsman influence but is more a vernacular adaptation, incorporating structural and economic pragmatics. The arched windows and entry tower are characteristic of small rural churches. The building is well-maintained and exhibits its original architectural integrity.

ببيه فالتاسف معتقد ومعاودوا وراد والرا

United States Department of the Interior National Park Service

National Register of Historic Places Continuation Sheet

Section number _____7 Page _____17 Old Towne Orange Historic District, Orange, CA

57.426 W. Almond

1924 Mediterranean Revival

Historical Name:

AP Number: 390-651-05

A large, rectangular plan industrial building located adjacent to the railroad tracks incorporates brick on the sides and a front facade with Mission influences. A characteristic Mission-like parapet is at the front entry. Below, fenestration incorporates recessed, rectangular windows of which centermost windows have recessed arches.

58.186 N. Atchison

1938 Mediterranean Revival Historical Name: Santa Fe Depot & Railroad Park AP Number: 039-170-01

This property includes a Mediterranean Revival style train depot and an accompanying park. The depot is built on a rectangular plan with three distinct wings and a loading dock. Each of the wings is in varying elevations and includes a gabled roof facing in contrasting directions. The roof is sided in adobe tiles while the facades are in stucco. The main entry features a curved canopy with mullioned transoms above. The adjoining park is a small park, recently upgraded and rededicated by the City for public usage in association with the depot restoration. The property is slightly triangular and includes several large trees, a picnic bench, sitting benches and a well maintained lawn. The park is in a very well maintained condition, and refurbishment and restoration of the depot has commenced. Since the 1982 survey, restoration and compatible conversion of this building for dining and entertainment has commenced with completion anticipated in early 1997.

59.125 N. Cambridge

1

1922 Bungalow Historical Name: AP Number: 386-061-09 A single-story bungalow with tri-gable roof and wide lap siding. Main portion of the house is covered by a single side-facing gable roof, while a centrally located, front-facing gable extends the full width of the front facade and forms an entry porch overhang. This is supported by wide tapered piers and the upper gable face is embellished with vertical slatting.

National Register of Historic Places Continuation Sheet

Section number _____7 Page _____18 Old Towne Orange Historic District, Orange, CA

60.133 N. Cambridge

1923 Mediterranean Revival

Historical Name:

AP Number: 386-061-08

A single-story, modified box plan house with stucco siding and flat roof. The central portion of the front facade is distinguished by a projecting entry porch overhang with large arched openings and a tile hood. A large, arched picture window adorns the remaining portion of the front facade. A porte cochere is to the side and is supported by round columns.

61.141 N. Cambridge

1923 Bungalow Historical Name: AP Number: 386-061-07 A single-story clapboard bungalow with tri-gable roof. Main portion of the house is covered by a single gable roof with side-facing gables, while a front-facing gable extends forward on the front facade to form the entry porch overhang. This is supported by wide piers connected by a low concrete porch wall. Ornamental bargeboards and rafter tails embellish the eaves.

62.142 N. Cambridge

1923 Bungalow Historical Name: AP Number: 386-074-13 A single-story clapboard bungalow with a rectangular plan and multi-gable roof. The roofline takes on unusual proportions with the way the main, sidefacing gable extends forward to form a 3/4-width porch overhang. This is supported by piers comprised of brick bases and wood posts on top.

63.149 N. Cambridge

1923 Bungalow Historical Name: AP Number: 386-061-06 A single-story, tri-gable bungalow with wide lap siding on the facades. The main portion of the house is covered by a single-gable roof with side-facing gables. A large, wide front-facing gable forms an entry porch overhang. This is supported by piers with brick bases and wood posts on top. Vertical slatting adorns the upper gable face. The main door is beneath the porch and is flanked on either side by multi-pane side vents.

National Register of Historic Places Continuation Sheet

Section number _____7 Page _____19 Old Towne Orange Historic District, Orange, CA

64.150 N. Cambridge

1924 Bungalow Historical Name: AP Number: 386-074-14 A single-story, clapboard bungalow with tri-gable roof. Main portion of the house is covered by a single gable roof with side-facing gables, while a front-facing gable extends forward on the front facade to form the entry porch overhang. This is supported by wide piers connected by a low concrete porch wall. Ornamental bargeboards and rafter tails embellish the eaves.

65.157 N. Cambridge

1923 Bungalow Historical Name: AP Number: 386-061-05 A single-story bungalow with single front-facing gable roof. The original siding on the house, which was probably clapboard, has since been covered over with stucco. The front entry is beneath the gable overhang and there is now a recessed arch entry to the main door.

66.**160 N. Cambridge** 1950

Historical Name: AP Number: 386-074-15 Non-Contributor

67.166 N. Cambridge

1923 Bungalow Historical Name: AP Number: 386-074-16 A single-story bungalow with wide lap siding and multi-gable roof. The front facade is distinguished by three front-facing gables. The forwardmost gable forms the entry porch overhang and is supported by piers of cast concrete. A cast concrete chimney is present on the rearmost portion of the house.

68.167 N. Cambridge

1923 Bungalow Historical Name: AP Number: 386-061-04

A single-story bungalow with shallow-pitch, multi-gable roof. The front facade is distinguished by a full-width recessed porch supported by piers with brick bases and wood posts on top. There is a connecting brick porch wall with half-size piers at the center near the entry stoop. Original clapboard siding is now covered by asbestos shingles.

National Register of Historic Places Continuation Sheet

Section number _____7 Page _____20 Old Towne Orange Historic District, Orange, CA

69. 174 N. Cambridge

1923 Bungalow Historical Name: AP Number: 386-074-17

A single-story bungalow with shallow-pitch, multi-gable roof. The main portion of the house is covered by a single-gable roof with side-facing gables, while nearly the full width of the front facade is articulated by a front-facing gable that extends forward to form the porch overhang. This is supported by piers with brick bases and wood posts on top. The original clapboard siding has since been covered by asbestos shingles.

70.175 N. Cambridge

1936 Historical Name: AP Number: 386-061-03 Non-Contributor

71.182 N. Cambridge

1833 Provincial Revival Historical Name: AP Number: 386-074-18 A single-story stucco house with steep-pitch, multi-gable roof. The house is built in the English Revival tradition with Tudor Revival influences present in the use of half-timbering on the front facade. The house is built on an L-plan with the main entry being in the apex of the ell.

72.183 N. Cambridge

1923 Bungalow Historical Name: AP Number: 386-061-02 A single-story bungalow with shallow-pitch, multi-gable roof and clapboard siding on the facades. The front of the house is articulated by two frontfacing gables, the forwardmost of which forms the entry porch overhang. This is supported by wide piers with cast concrete bases and wood posts on top. Board and batten and vertical slatting adorn the upper gable face.

73.192 N. Cambridge

1939 Historical Name: AP Number: 386-074-19 Non-Contributor

National Register of Historic Places Continuation Sheet

Section number _____7 Page _____21 Old Towne Orange Historic District, Orange, CA

74.202 N. Cambridge

1895 Victorian Cottage Historical Name: AP Number: 386-084-12 A single-story house with clapboard siding and steep-pitch, multi-gable roof. The roofline takes on an L-plan with the frontmost leg of the ell forming a large entry porch overhang. This is supported by wood posts with classical treatment on the capitals. Ornamental turned balusters form the balustrade which connects the six porch posts. The large, front-facing gable features both square butt and fish scale shingles. A high ornamental brick chimney emanates from the center of the roof.

75.205 N. Cambridge 1949 Historical Name: AP Number: 386-091-11 Non-Contributor

76.208 N. Cambridge 1945 Historical Name: AP Number: 386-084-13 Non-Contributor

77.213 N. Cambridge 1947 Historical Name: AP Number: 386-091-10 Non-Contributor

78.215 N. Cambridge

1923 Bungalow Historical Name: AP Number: 386-091-09 A single-story bungalow with ornamental lap siding and multi-gable roof. The main portion of the house is covered by a single side-facing gable roof which extends forward across three-quarters of the front facade to form the entry porch overhang. At this point the roof is supported by piers with brick bases and wood posts on top. The piers are connected by a low brick wall. There is a smaller front-facing gable which intersects the porch overhang.

The

United States Department of the Interior National Park Service

National Register of Historic Places Continuation Sheet

Section number _____7 Page _____2 Old Towne Orange Historic District, Orange, CA

79.218 N. Cambridge

1947 Historical Name: AP Number: 386-084-14 Non-Contributor

80.222 N. Cambridge

1925 Mediterrranean Revival Historical Name: AP Number: 386-084-15 A single-story bungalow with flat roof and stucco siding on the facades. house features the typical array of pseudo-Mediterranean embellish including use of adobe tiles along the roof edge and on the porch entry

house features the typical array of pseudo-Mediterranean embellishment, including use of adobe tiles along the roof edge and on the porch entry as a hood. The front facade is divided into two wings, one which extends forward of the other. The center portion of this wing has an arched entry portico. Either side of the front facade extends forward in an ornamental fashion.

81.225 N. Cambridge 1996 Historical Name: AP Number: 386-091-08 Non-Contributor

82.231 N. Cambridge

1923 Bungalow Historical Name: AP Number: 386-091-07 A one story house with shiplap siding and low-pitched roof with two front vented gables. One-half of the original full width front porch has been enclosed, ceiling off half of the front window area. The remaining porch is supported by tapered wood piers on brick bases with wood-slatted balustrade.

83.232 N. Cambridge

1922 Bungalow Historical Name: AP Number: 386-084-16 A single-story bungalow with ornamental lap siding and multi-gable roof. Three-quarters of the front facade is comprised of a recessed porch which is supported by tapered piers. Two smaller front-facing gables are also present on the front facade, and each acts as an attic dormer.

1

National Register of Historic Places Continuation Sheet

Section number _____7 Page _____23 Old Towne Orange Historic District, Orange, CA

84.241 N. Cambridge

1923 Mediterranean Revival Historical Name:

AP Number: 386-091-06

A single-story house with stucco siding and flat roof. The house is comprised of an irregular plan with various planes jutting forward of one another. The centermost portion of the front facade is distinguished by a tile hood and the main entry is below enclosed within an ornamental framing. Double-hung windows span all facades, and the upper sashes are mullioned.

85.242 N. Cambridge 1941 Historical Name: AP Number: 386-084-17 Non-Contributor

86.251 N. Cambridge

1922 Bungalow Historical Name: AP Number: 386-091-05 A single-story clapboard bungalow with multi-gable roofline comprised of a juxtaposition between a side-facing gable and a front-facing gable. The side-facing gable extends forward to form an entry porch overhang and is supported by piers with brick bases and round columns on top. The front door is the original mullioned door.

87.252 N. Cambridge

1921 California Bungalow Historical Name: AP Number: 386-084-18 A single-story clapboard bungalow with multi-gable roof with side-facing gables. The centermost portion of the front facade is distinguished by a small gable entry portico supported by Colonial columns. A large 3-part window flanks either side of the main entry which is comprised of the original door.

National Register of Historic Places Continuation Sheet

Section number _____7 Page _____24 Old Towne Orange Historic District, Orange, CA

88.261 N. Cambridge

1924 Bungalow Historical Name: AP Number: 386-091-04 A single-story, tri-gable bungalow with clapboard siding on the facades. The main portion of the house is covered by a single-gable roof with side-facing gables, while the front facade is distinguished by a wide front-facing gable porch overhang. This is supported by piers that incorporate ornamental brick on the bases and wood posts on top.

89.262 N. Cambridge

1921 California Bungalow Historical Name: AP Number: 386-084-19 A single-story clapboard

A single-story clapboard bungalow with roofline comprised of clipped gables. The main portion of the house is covered by a single gable-roof with sidefacing clipped gables. To the side a small bay projection is defined, also with a small clipped gable. The entry portico features a clipped gable as well, and beneath it the main door is flanked on either side by fluted pilasters. The brick facing on the lower half of the front facade is a later addition.

90.271 N. Cambridge

1924 Bungalow Historical Name: AP Number: 386-091-03 A single-story clapboard bungalow with double front-facing gable roof. The forwardmost gable forms the entry porch overhang and is supported by piers. To the side of the porch gable is a pergola which is also supported by an identical pier. Entry is at center and flanked on either side by a large picture window with mullioned transom.

91.272 N. Cambridge 1921 Bungalow

Historical Name: AP Number: 386-084-20 Rectangular plan with central door and no porch. Wide shed dormer.

a construction of the second structure of the second s

United States Department of the Interior National Park Service

National Register of Historic Places Continuation Sheet

Section number _____7 Page _____25 Old Towne Orange Historic District, Orange, CA

92.281 N. Cambridge

1923 Bungalow Historical Name: AP Number: 386-091-02 A single-story bungalow with single front-facing gable roof. What was probably original clapboard siding has since been covered with asbestos shingles. The front half of the facade is defined by a recessed corner porch which is supported by a pier comprised of a brick base and wood posts on top. There is a double door entry.

93.282 N. Cambridge

1923 Bungalow Historical Name: AP Number: 386-084-21 A single-story clapboard bungalow with shallow-pitch, multi-gable roofline. A large recessed corner porch, which wraps around from the front to the side of the house, is supported by piers composed of brick bases and wood posts on top. The house is otherwise simple and unadorned.

94.291 N. Cambridge

1923 Bungalow Historical Name: AP Number: 386-091-01 A single-story clapboard bungalow with double front-facing gable roof. The forwardmost gable forms the entry porch overhang and is supported by piers with brick bases and wood posts on top.

95.292 N. Cambridge

1923 Bungalow Historical Name: AP Number: 386-084-22 A single-story clapboard bungalow with shallow-pitch, multi-gable roofline. The front facade is distinguished by a centrally located front-facing gable which is intersected by the main roofline. The house is built on a modified L-plan with the main entry in the apex of the ell. There is also a simple pergola present sheltering the entry.

an interaction of the state of

United States Department of the Interior National Park Service

National Register of Historic Places Continuation Sheet

Section number _____7 Page _____26 Old Towne Orange Historic District, Orange, CA

96.303 N. Cambridge

1923 Bungalow Historical Name: AP Number: 386-121-11 A single-story clapboard house with double front-facing gable roof. The forwardmost gable forms the entry porch overhang and is supported by tapered piers with brick bases and wood posts on top.

97.311 N. Cambridge

1923 Bungalow Historical Name: AP Number: 386-121-10 A single-story, tri-gable bungalow with wide lap siding on the facades. The main portion of the house is covered by a single-gable roof with side-facing gables, while a front-facing gable extends forward to form the entry porch overhang. This is supported by tapered piers and ornamental brick bases.

98.317 N. Cambridge

1922 Bungalow Historical Name: AP Number: 386-121-09 A single-story clapboard bungalow with multi-gable roof. The center front of the house is articulated by a front-facing gable and is supported by piers with concrete bases and wood posts on top. A large arch connects these piers.

99.320 N. Cambridge

1919 Historical Name: AP Number: 386-134-15 Non-Contributor

100. 325 N. Cambridge

1937 Bungalow Historical Name: AP Number: 386-134-15 A single-story clapboard bungalow with double front-facing gable roof. The front entry is comprised of a porch recessed beneath the main facade of the two front-facing gables. A portion of the forwardmost and the pergola to the side are supported by tapered piers. Cross-ties are present in the upper gable faces.

المتعجم ويوجو ويربين المراجع والمراجع

United States Department of the Interior National Park Service

National Register of Historic Places Continuation Sheet

Section number _____7 Page _____27 Old Towne Orange Historic District, Orange, CA

101. 332 N. Cambridge
1922 Bungalow
Historical Name:
AP Number: 386-134-16
A single-story clapboard bungalow with double front-facing gable roof. Entry
is on the center side of the frontmost gable and above it a pergola forms an
entry porch overhang.

102. 339 N. Cambridge

c1905 Hip Roof Cottage Historical Name: AP Number: 386-121-07 A single-story house with box plan, clapboard siding and steep-pitch, hip roof. A small hip dormer is present on the front portion of the roof. Onehalf of the front facade is defined by a recessed porch which is supported by classical columns. The original wood door is still present, and on either side of the front facade there is a large picture window with mullioned transom.

103. 340 N. Cambridge

1917 Bungalow Historical Name: AP Number: 386-134-17 Non-Contributor. A single-story bungalow with wide lap siding and single front-facing gable roof. A smaller, front-facing gable overhang forms the entry porch and is supported by wood posts. The brick work on the foundation is probably a later addition. Since the 1982 survey, this structure has been severely altered by inappropriate board and batten siding and aluminum windows.

104. **347** N. Cambridge 1951 Historical Name: AP Number: 386-121-06

AP Number: 386-121-0 Non-Contributor

National Register of Historic Places Continuation Sheet

Section number _____7 Page _____28 Old Towne Orange Historic District, Orange, CA

105. 348 N. Cambridge

1929 Bungalow Historical Name: AP Number: 386-134-18 A single-story clapboard bungalow with clapboard siding and double frontfacing gable roof. The forwardmost gable forms the entry poorch overhang and is supported by piers comprised of brick bases and tapered wood posts on top. Vertical lattice work adorns the porch gable.

106. 349 N. Cambridge

1901 Hip Roof Cottage Historical Name: AP Number: 386-121-05 A single-story box plan house with clapboard siding and steep pitch, hip roof. A small hip dormer is present on the front portion of the roof. A small entry overhang acts as an entry porch and is now supported by wood posts. There probably has been some change in this structure.

107. 356 N. Cambridge
1913 Bungalow
Historical Name:
AP Number: 386-134-19
A single-story bungalow built on a modified L-plan with steep-pitch, multigable roof. There is no porch present. Entry is located beneath the eaves
of the main roof.

108. **364 N. Cambridge** 1954 Historical Name: AP Number: 386-134-20 Non-Contributor

109. 374 N. Cambridge
1910 Hip Roof Cottage
Historical Name:
AP Number: 386-134-21
A single-story box plan house with steep-pitch, hip roof and smaller hip
dormer on the front portion of the roof. What was originally probably
clapboard siding has since been covered with asbestos shingles. One-half of
the front facade is defined by a recessed corner porch supported by wood
posts.

National Register of Historic Places Continuation Sheet

Section number _____7 Page _____29 Old Towne Orange Historic District, Orange, CA

110. **382 N. Cambridge** 1953 Historical Name: AP Number: 386-134-22 Non-Contributor

111. 390 N. Cambridge

c1910 Transitional Historical Name: AP Number: 386-134-23

A two-story house built on an L-plan with steep-pitch, multi-gable roof. The short leg of the ell forms a front-facing gable, which results in an angled bay window on the first story. A smaller front-facing gable on the other half of the front facade forms the entry porch overhang. It is now supported by wrought iron posts which are a replacement for the original. Triangular bracket supports grace the eaves throughout.

112. 128 S. Cambridge

1914 Craftsman Historical Name: AP Number: 390-444-03 Large, single-story Craftsman home with clapboard siding and single, sidefacing gable roof. Main roof extends forward to form a full-width porch overhang supported by classic Craftsman piers. Slatted balustrade connects these piers; large transomed picture windows adorn the front facade. A small, shed dormer acts as an attic vent.

113. 133 S. Cambridge

1926 Commercial Historical Name: AP Number: 390-451-21 A single-story "mom and pop" store still in use for that purpose. Building is built on box plan with clapboard siding and flat roof. The facade results in an ornamental parapet across the front. Typical wood frame, double doors provide the main entry.

114. 136 S. Cambridge
1912 Hip Roof Cottage
Historical Name:
AP Number: 390-444-04
Single-story house with hip roof, box plan and now covered by asbestos
siding. A contrasting, front-facing gable acts as an attic vent. Entry is
via a corner, recessed porch supported by wide piers.

National Register of Historic Places Continuation Sheet

Section number _____7 Page _____30 Old Towne Orange Historic District, Orange, CA

115. 143 S. Cambridge

1887 Altered Victorian Historical Name: AP Number: 390-451-20 Non-Contributor. The front facade of this house has been modified over the years to reflect a Provincial Revival style. However, the proportions in terms of height, steep-pitched gable roof and the L-plan reflect the original Victorian quality. The house is now embellished with half timbering and an ornamental stone entry distinguished by an arched opening.

116. 144 S. Cambridge

1920 Craftsman Bungalow Historical Name: AP Number: 390-444-05 Single-story bungalow with shallow-pitched, double, front-facing gables. Forwardmost gable forms entry porch overhang supported by wide piers. Entry is beneath at center; main door is flanked by side-lites.

117. 152 S. Cambridge 1910 Hip Roof Cottage Historical Name: AP Number: 390-444-06 Single-story box plan house with clapboard siding and steep-pitched, hip roof. A small hipped dormer projects from the front portion of the roof. Entry is via a corner recessed porch supported by Craftsmanesque wood posts.

118. 153 S. Cambridge c1890 Victorian Historical Name: AP Number: 390-451-19 A large, two-story Victorian house with steep-pitched, multi-gable roof and shiplap siding. The house is built on a slight L-plan with a small, but ornately embellished, entry porch in the apex of the ell. Each of the upper gable faces features fishscale and arched cross-ties. A multitude of shrubbery all but conceals the house.

National Register of Historic Places Continuation Sheet

Section number _____7 Page _____31 Old Towne Orange Historic District, Orange, CA

119. 156 S. Cambridge

1912 Craftsman Historical Name:

AP Number: 390-444-07

One and one-half story Craftsman home with rectangular plan and single, sidefacing, gable roof. The house is sided in clapboard. Main roof extends forward to form full-width porch overhang supported by tapered piers. A front-facing, Siamese gabled dormer is located on the front portion of the roof; ornamental purlins and an ornamentally framed vent articulate this dormer.

120. 159 S. Cambridge

1890 Victorian Cottage Historical Name:

AP Number: 390-451-18

Small, single-story cottage with steep-pitched hip roof and unusual steeppitched gable extension of roof which forms entry porch overhang. The house incorporates a variety of influences, indicating there have been some changes over the years. The small porch overhang supported by Classical Revival piers indicates Classical Revival influences, while the large picture windows to either side indicate Craftsman influences. Most notable Victorian features are the original main door, embellished transom in the front-facing gable and the ornamental brackets beneath the eaves.

121. 167 S. Cambridge

c1895 Victorian Historical Name:

AP Number: 390-451-17

A single-story Victorian cottage with multi-gable roof and shiplap siding. The house is characteristically Victorian, particularly in the ornamental fretwork used in the brackets of the eaves and the posts on the porch overhang. Windows are framed in the classic Victorian manner.

122. 168 S. Cambridge

1912 Bungalow Historical Name:

AP Number: 390-444-08

Single-story bungalow with clapboard siding and side-facing, gable roof. A front-facing gable extends forward in the center of the front facade to form the entry porch overhang. It is supported by characteristic piers, while the main entry is beneath with large windows on either side. Ornamental purlins grace the eaves throughout.

National Register of Historic Places Continuation Sheet

Section number _____7 Page _____32 Old Towne Orange Historic District, Orange, CA

123. **175 S. Cambridge** 1946 Historical Name: AP Number: 390-451-16 Non-Contributor

124. **176 S. Cambridge** 1912 Craftsman Historical Name: AP Number: 390-444-09 A Craftsman style structure with rafters and beams. Porch spa

A Craftsman style structure with low-pitched single-gabled roof and exposed rafters and beams. Porch spans the entire length of front facade and features elephantine posts and arroyo stone bases. Siding is wood shiplap with double-hung wood windows. A font shed dormer provides for attic venting and an interior brick chimney is present.

125. **181 S. Cambridge** 1948 Historical Name: AP Number: 390-451-15 Non-Contributor

126. **186 S. Cambridge** 1910 Hip Roof Cottage Historical Name: AP Number: 390-444-10 A hip roof cottage on a square plan with distinctive four-sloped, falred hip roof with vented dormers. Molded rakeboard, double-uung windows, and wood clapboard siding is present. Enclosed front porch may have been open when originally constructed.

127. **191 S. Cambridge** c1915 Craftsman Historical Name: AP Number: 390-451-14

One and one-half story Craftsman home built on a rectangular plan with clapboard siding and single, side-facing gable roof. A large, front-facing gabled dormer incorporates four double-hung windows and cross-ties across the front bargeboard. The main roof extends forward to form a full-width porch supported by characteristic tapered piers. Large picture windows flank the main entry at center. Since the 1982 survey, this structure has been altered with inappropriate porch enclosure.

National Register of Historic Places Continuation Sheet

Section number _____7 Page _____33 Old Towne Orange Historic District, Orange, CA

128. 203 S. Cambridge
1923 Bungalow
Historical Name:
AP Number: 390-461-01
A characteristic, single-story bungalow built on a rectangular plan with
clapboard siding and tri-gable roof. Main house is covered by a side-facing

clapboard siding and tri-gable roof. Main house is covered by a side-facing gable roof; the front-facing gable extends forward to form the entry porch overhang supported by Colonial-like columns. Entry is beneath at center.

129. 204 S. Cambridge
1909 Bungalow
Historical Name:
AP Number: 390-432-08
A single-story bungalow built on a rectangular plan with single, side-facing
gable roof. A large, full-width, front-facing gable originally formed entry
porch but has since been enclosed, giving the house a modified appearance.

130. 218 S. Cambridge c1925 Provincial Revival Historical Name: AP Number: 390-432-09 This single-story stucco house, built on an L-plan with steep-pitched gable roof, shows attempts at incorporating Provincial Revival influences. Gable roof follows the L-plan of the house with a large, front-facing gable and a smaller, front-facing gable which forms the entry portico.

131. **219 S. Cambridge** 1961 Historical Name: AP Number: 390-461-20 Non-Contributor

132. **223 S. Cambridge** 1961 Historical Name: AP Number: 390-461-19 Non-Contributor

National Register of Historic Places Continuation Sheet

Section number _____7 Page _____34 Old Towne Orange Historic District, Orange, CA

133. 226 S. Cambridge

1935 Provincial Revival Historical Name:

AP Number: 390-432-10

A provincial revival bungalow-type residence on a rectangular plan with gabled roof, exposed rafter tails, and ridge beam extensions. large gay window flanked by four pane lindel-type sidelights are present. Windows are wooden and siding is stucco. An arched entry protal and exterior stucco chimney are present.

134. **229 S. Cambridge** 1961 Historical Name: AP Number: 390-461-18 Non-Contributor

135. 231 S. Cambridge 1919 Bungalow Historical Name: AP Number: 390-461-17 A single-story bungalow with shallow-pitched, multi-gable roof and ornamental clapboard siding. Main roof is comprised of a single, side-facing gable. A full-width, front-facing gable forms the front facade in part and also a recessed entry porch overhang. House has been altered through the use of brick on the front facade.

136. 236 S. Cambridge
1926 Provincial Revival
Historical Name:
AP Number: 390-432-11
A provincial revival residence on a box plan with two front facing steep
pitched gables with single-paned picture window, flanked by six-paned linteltype window openings. Entry is centered between gables. Roof consists of
simulated thatch with exterior brick chimney.

137. **238 S. Cambridge** 1941 Historical Name: AP Number: 390-432-12 Non-Contributor

National Register of Historic Places Continuation Sheet

Section number _____7 Page _____35 Old Towne Orange Historic District, Orange, CA

138. 247 S. Cambridge

1919 Craftsman Bungalow Historical Name: AP Number: 390-461-16 A single-story, clapboard bungalow with shallow-pitched, double front-facing gables. The forwardmost gable forms entry porch overhang supported by piers. Wide vertical slats adorn the upper face of each gable and are complemented by the ornamental clapboard siding.

139. **252 S. Cambridge** 1941 Historical Name: AP Number: 390-434-12 Non-Contributor

140. **276 S. Cambridge** 1913 Historical Name: AP Number: 390-434-13 Non-Contributor

141. **101 N. Center** Historical Name: AP Number: 039-254-21 Non-Contributor

142. **132 N. Center** 1966 Historical Name: AP Number: 039-253-33 Non-Contributor

143. 143 N. Center

1912 Craftsman Historical Name: AP Number: 039-254-06 A 1-1/2 story house with wide lap siding and single-gable roof with sidefacing gables. There is also a large front-facing gable dormer which is ornamented with cross-ties and an ornamental transom vent. The main roof extends forward to form a full-width porch and is supported by wide tapered piers with arroyo stone bases. The main entry is at center and flanked on either side by a large 3-part window.

National Register of Historic Places Continuation Sheet

Section number _____7 Page _____36 Old Towne Orange Historic District, Orange, CA

144. 153 N. Center

1910 Craftsman Historical Name: AP Number: 039-254-05

A 1-1/2 story Craftsman house with wide lap siding, and the main roof comprised of a single gable with side-facing gables. There also is present a large front-facing gable dormer ornamented with cross-ties, purlins and two combination window/vent transoms. The main roof extends forward to form the full-width porch and is supported by arroyo stone piers. These piers are connected by a slatted balustrade. The original door with oval pane is still present.

145. 158 N. Center

1909 Craftsman Bungalow Historical Name: AP Number: 039-253-16

A single-story bungalow with wide lap siding and gable roofline. There is a small front-facing gable dormer with ornamental purlins and an attic transom. The house features a large corner wrap-around porch which is a recessed porch supported by wood posts on top of a high porch wall. The original wood door with vertical pane is still present.

146. 163 N. Center

1915 Bungalow Historical Name: AP Number: 039-254-04 A single-story bungalow with shingled siding and single, shallow-pitch gable roof which is front-facing. There is a full-width porch recessed beneath the main roof. This porch overhang is supported by piers of cast masonry. The original wood door with glass panes is still present.

147. 164 N. Center

1

1919 Bungalow Historical Name: AP Number: 039-253-31 A single-story house with combination lap and shingle siding, and a frontfacing, single-gable roof. There is a full-width porch recessed beneath the main roof. This porch is supported by wide piers on top of a cast concrete masonry wall. The original door with glass pane is still present.

National Register of Historic Places Continuation Sheet

Section number _____7 Page _____37 Old Towne Orange Historic District, Orange, CA

148. 168 N. Center

1925 Bungalow Historical Name:

AP Number: 039-253-31

A single-story bungalow with wide lap siding and double front-facing gable roof. The format of the house is arranged a little differently than usual in that the gable projection is located on the centermost portion of the front facade and the entry is to the side of this gable projection. A large mullioned, 3-part window is present on the frontmost portion of the facade.

149. 171 N. Center

1909 Bungalow Historical Name: AP Number: 039-254-03

A single-story bungalow with clapboard siding on the lower portion and shingles on the upper gable face. The roofline is a single-gable roof with a front-facing gable. There is a full-width porch recessed beneath the main portion of the roof. The porch is supported by wide piers with brick bases and wood posts on top. The house is distinguished by ornamental rafter tails, purlins, and dentils running across the lower gable face.

150. 176 N. Center

1912 Bungalow Historical Name: AP Number: 039-253-19 A single-story bungalow with wide lap siding and double front-facing gable roof. The forwardmost gable forms the entry porch overhang and is supported by slender wood posts. Ornamental purlins grace the eaves, while the lower portion of the front facade features two large, 3-part transomed windows.

151. 181 N. Center

1914 Bungalow Historical Name: AP Number: 039-254-02 A single-story clapboard bungalow with single-gable roof with front-facing gable. A full-width porch is present which is recessed beneath the main roof. The porch is now supported by ornamental iron piers which are certainly a replacement for the original. The house is embellished with cross-ties in the upper gable face, purlins and an ornamental transomed window. The lower portion of the house features the original front door with glass panes, flanked on either side by a large, transomed picture window.

National Register of Historic Places Continuation Sheet

Section number _____7 Page _____38 Old Towne Orange Historic District, Orange, CA

152. **190 N. Center**

1903 Gable Roof Cottage Historical Name: AP Number: 039-253-20 This house has been considerably altered, although there is no mistaking the original portions of the house. What was originally a clapboard house with multi-planed roofline and dynamic wrap-around circular porch has since been modified to include an enclosure of the porch using brick facing. A portion of the clapboard facade, the two gables, and the original roofline are still intact.

153. 191 N. Center

1908 Hip Roof Cottage Historical Name: AP Number: 039-254-01 A single-story box plan house with clapboard siding and steep-pitch, hip roof. There is a slender gable dormer present on the front portion of the roof. The main roof extends forward to form a full width porch overhang which is supported by classical columns atop a clapboard porch wall.

154. 222 N. Center

1913 Bungalow Historical Name: AP Number: 039-243-15 A single-story bungalow with clapboard siding and double front-facing, gable roof. The forwardmost gable forms the entry porch overhang and is supported by tapered piers.

155. 225 N. Center

1924 Mediterranean Revival Historical Name: AP Number: 039-244-09 A box plan bungalow with stucco facades and a flat roof. While not totally Mediterranean, this house certainly incorporates a Pueblo feel through the use of the entry porch porticos in either side of the front facade. There is a slight stepped parapet as well, and the porch piers include raised pilasters.

National Register of Historic Places Continuation Sheet

Section number _____7 Page _____39 Old Towne Orange Historic District, Orange, CA

156. 231 N. Center
1911 Bungalow
Historical Name:
AP Number: 039-244-08
Non-Contributor. Since the 1982 survey, this structure has been severely
altered by totally inappropriate remodeling with second story addition.

157. 232 N. Center 1904 Victorian Historical Name:

AP Number: 039-243-16 A two-story clapboard house with steep-pitch, multi-gable roof. The front facade is comprised of two pedimented front-facing gables, the smaller and lower of which shelters the corner entry porch and is supported by classical columns. The rearmost, front-facing gable is considerably ornamented through the use of transoms fashioned in a semi-Palladian manner. Ornamental jigsawn bargeboard is present in both gables. The wide eaves of the house are also ornamented with brackets.

158. **240 N. Center** 1920 Modified Mediterranean Revival Historical Name: AP Number: 039-243-17 A single-story house with modified box plan, textured stuccoed siding and a flat roof. There is a half-sized porch extension which is supported by wide piers. The house may have been re-sided, as the siding does not appear to be original.

159. 241 N. Center
1921 Bungalow
Historical Name:
AP Number: 039-244-07
A single-story clapboard bungalow with shallow-pitched gable roof. The house
is built on an L-plan, and the short leg of the ell results in a front-facing
gable face. To the side is an open porch, and the main door is sheltered by
a slight gabled portico supported by ornamental brackets.

160. 247 N. Center
1919 Altered Bungalow
Historical Name:
AP Number: 039-244-06
A single-story bungalow with ornamental lap siding and shallow-pitch, gable
roof. One-half of the front facade is occupied by a porch overhang which is

National Register of Historic Places Continuation Sheet

Section number _____7 Page _____40 Old Towne Orange Historic District, Orange, CA

supported by elephantine piers. Since the 1982 survey, this structure has been altered with inapproporate brick porch addition.

161. **250 N. Center** 1920 Historical Name: AP Number: 039-243-18 Non-Contributor

162. **253 N. Center** 1977 Historical Name: AP Number: 039-244-05 Non-Contributor

163. 258 N. Center

1910 Bungalow Historical Name: AP Number: 039-243-19 A single-story bungalow with wide lap siding and double front-facing gable roof. The forwardmost gable forms the entry porch overhang and is supported by tapered piers above a porch wall. The upper gable faces are ornamented with small brackets, ornamental exposed beams and vertical wood slats.

164. 264 N. Center

1913 Bungalow Historical Name: AP Number: 039-243-20 A single-story bungalow with wide lap siding and double front-facing, gable roof. The forwardmost gable forms the entry porch overhang and is supported by tapered piers above a porch wall. The original door with window panes is still present. Either side of the front facade features a large picture window with an ornamentally mullioned transom.

165. **267 N. Center** 1938 Historical Name: AP Number: 039-244-04 Non-Contributor

National Register of Historic Places Continuation Sheet

Section number _____7 Page _____ Old Towne Orange Historic District, Orange, CA

166. 272 N. Center

1923 Bungalow Historical Name: AP Number: 039-243-21 A single-story clapboard bungalow with multi-gabled, shallow-pitch roof. One-half of the front facade is occupied by a large corner, wrap-around porch. This porch is supported by a wide tapered pier with an ornamental brick base.

167. **273 N. Center** 1906 Hip Roof Cottage Historical Name: AP Number: 039-244-03 Non-Contributor. Due to inappropriate alterations.

168. 279 N. Center

1909 Bungalow Historical Name: AP Number: 039-244-02 A single-story bungalow with wide lap siding and double front-facing, gable roof. The forwardmost gable forms the entry porch overhang and is supported by slender wood posts.

169. 280 N. Center c1915 Craftsman Historical Name: AP Number: 039-243-22 A two-story house with single gable roof with side-facing gable faces. The facades of the house are now covered by asbestos shingles. There is a large front facing, gable dormer on the front portion of the roof. The main roof extends forward to form a full-width porch and is supported by colonial-type columns.

170. **288 N. Center** 1911 Bungalow Historical Name: AP Number: 039-243-23 A single-story clapboard bungalow with single-gable roof and side-facing gables. The roof extends forward to form a half recessed porch and is supported by slender wood posts.

Į

National Register of Historic Places Continuation Sheet

Section number _____7 Page _____42 Old Towne Orange Historic District, Orange, CA

171. 289 N. Center

1906 Hip Roof Cottage Historical Name: AP Number: 039-244-01 A single-story clapboard house with steep-pitch, hip roof contrasted by a gabled wing on the side. What was once probably a corner wrap-around porch has since been enclosed.

172. 305 N. Center

1905 Hip Roof Cottage Historical Name: AP Number: 039-232-11 A single-story clapboard house with box plan and steep-pitch, hip roof. The roofline also features two pedimented gables which act as attic dormers which are embellished with fish scale shingles and an ornamentally framed transomed vent. A separate roof extension on the front facade once formed a full-width porch but has since been enclosed.

173. 313 N. Center
1915 Bungalow
Historical Name:
AP Number: 039-232-10
A single-story bungalow with lap siding and double front-facing, gable roof.
The forwardmost gable forms the entry porch overhang and is supported by
tapered piers with brick bases and wood on top. Ornamental purlins grace the
eaves.

174. **323 N. Center** c1905 Hip Roof Cottage Historical Name: AP Number: 039-232-09 This is a small box-plan cottage with clapboard siding and steep-pitch, hip roof. A small gabled attic dormer is present on the front portion of the roof. Just below is a nearly full-width porch with its own separate roof extension that is supported by Victorian turned posts connected with an ornamental balustrade. This small-scale house is indicative of the simplistic homes built by the early settlers and pioneers in Orange. Since the 1982 survey, this structure has been altered with inappropriate porch rail.

National Register of Historic Places Continuation Sheet

Section number _____7 Page _____43 Old Towne Orange Historic District, Orange, CA

175. 333 N. Center

1922 Bungalow Historical Name: AP Number: 039-232-08 A single-story bungalow with lap siding and single-gable roof with sidefacing gables. A small gabled attic dormer is present as is a small gabled entry over the main door. The portico is embellished with an arch with a large arch connecting brackets.

176. 339 N. Center

1920 Bungalow Historical Name: AP Number: 039-232-07 A single-story box plan bungalow with wide lap siding and double frontfacing, gable roof. The smaller, forwardmost gable forms the entry porch overhang which is located on the center front of the house. The overhang is supported by large wood posts. Vertical slatting in the upper gable faces act as embellishment.

177. 345 N. Center

c1920 Bungalow Historical Name: AP Number: 039-232-06 A single-story house with double front-facing, gable roof and facades now covered by asbestos shingles. The smaller, forwardmost gable located on the center of the front facade forms an entry porch overhang and is supported by slender wood posts.

178. 353 N. Center c1915 Bungalow Historical Name: AP Number: 039-232-05 A single-story bungalow with wide lap siding and single-gable roof with sidefacing gables. A small gabled attic dormer is present as is a small gabled entry portico over the main door.

National Register of Historic Places Continuation Sheet

Section number _____7 Page _____44 Old Towne Orange Historic District, Orange, CA

179. 363 N. Center
1920 Bungalow
Historical Name:
AP Number: 039-232-04
A single-story bungalow with shallow-pitch, gable roof and facades now
covered by asbestos shingles. The main portion of the house is covered by a
roof with side-facing gables, while a narrower front-facing gable in the
center of the front facade forms an entry porch overhang. This is supported
by wood posts and ornamented with vertical slatting.

180. **373 N. Center** 1922 Normandy Eclectic Historical Name: AP Number: 039-232-03 Non-Contributor

181. **383 N. Center** 1966 Historical Name: AP Number: 039-232-02 Non-Contributor

182. **393 N. Center** 1920 Historical Name: AP Number: 039-232-01 Non-Contributor

183. **413 N. Center** c1925 Mediterranean Revival Historical Name: AP Number: 039-223-12 This is a single-story box plan house with stucco facades and flat roof reminiscent of the Mediterranean Revival style. Though not really Mediterranean, the house does incorporate a front-facing gable-enclosed projection flanked on either side by an entry. Large mullioned windows are present on either side of the gable projection, and the gable wing itself contains two small mullioned, arched windows. The raised parapet on the house is reminiscent of the Pueblo Revival influences.

National Register of Historic Places Continuation Sheet

Section number _____7 Page _____45 Old Towne Orange Historic District, Orange, CA

184. 423 N. Center

1923 Bungalow Historical Name: AP Number: 039-223-11 Non-Contributor. Though the format and style of this house are intact, it has been considerable altered through the use of stucco on the facades and the changing of the windows. The house is a basic California bungalow with double front-facing, gable roof of which the forwardmost gable forms an entry porch overhang supported by slender wood posts.

185. 427 N. Center

1923 Bungalow Historical Name: AP Number: 039-223-10 A single-story clapboard bungalow with single-gable roof with side-facing gables. The main entry is just off center and is articulated by a small gabled portico just above. A pair of large, double-hung windows are on either side of the entry.

186. 433 N. Center

1923 Bungalow Historical Name: AP Number: 039-223-09 A small box-plan clapboard house with single-gable roof with side-facing gables. The house is simple and unadorned except for the small portico overhang above the entry door.

187. **437** N. Center Historical Name: AP Number: 039-223-08 Non-Contributor

188. **445 N. Center** 1920 Bungalow

Historical Name: AP Number: 039-223-07 Though this house still retains its original format and style, it has been altered through the use of stucco on the facades. The house is a modified box-plan with a tri-gable roof line with each of the gables front-facing. The forwardmost of these forms the entry porch overhang and is supported by tapered piers. The original hardwood door is still present.

National Register of Historic Places Continuation Sheet

Section number _____7 Page _____46 Old Towne Orange Historic District, Orange, CA

189. **453 N. Center**

1926 Mediterranean Revival Historical Name: AP Number: 039-223-06 A single-story box plan house with stucco facades and a flat roof. The house is simple and unadorned and harks to the Mediterranean Revival style through the use of adobe tiles at the roof ridge line. A small recessed portico shields the main entry.

190. 463 N. Center

1925 Bungalow Historical Name: AP Number: 039-223-05 Non-Contributor. Since the 1982 survey, this structure has been severely altered by an inappropriate second story addition.

191. 469 N. Center

1927 Mediterranean Revival Historical Name: AP Number: 039-223-04 A single-story stucco house with box plan and flat roof. The entry is comprised of a recessed portico with arched openings and tile hood above. The roofline is also articulated with adobe tiles.

192. 477 N. Center

1931 Spaniah Colonial Revival Historical Name: AP Number: 039-223-03 A single-story house with textured stucco siding and multi-gable roofline.

The house is built on a modified L-plan with the front-facing gable elongated to form an entry portico which is accessed via a large arch opening. The roof is sided with adobe tiles.

193. **485 N. Center** 1923 Bungalow Historical Name:

AP Number: 039-223-02

A single-story bungalow with wide lap siding and single front-facing gable roof. The house is simple and unadorned except for the small shed portico over the main entry.

National Register of Historic Places Continuation Sheet

Section number _____7 Page _____47 Old Towne Orange Historic District, Orange, CA

194. 489 N. Center

1923 Bungalow Historical Name: AP Number: 039-223-01 A single-story bungalow with wide lap siding and single-gable roof with sidefacing gables. A small front-facing gable attic dormer is also present. The main entry is shielded by a small gable portico with ornamental bracket supports.

195. **111 S. Center** 1970 Historical Name: AP Number: 390-384-01 Non-Contributor

196. **121 S. Center** 1925 Spanish Colonial Revival Historical Name: AP Number: 390-384-04 This one-story building has accomodated the Women's Club since it was built in 1925. Built on a rectangular plan with gable roof in the rear and stucco facades, the building features a modified Mission Revival entry portico; this includes an ornately arched opening below. Tile hoods are on either side of the entry parapet. Four mullioned glass doors form the entrance.

197. **151 S. Center** 1946 Historical Name: AP Number: 390-384-05 Non-Contributor

National Register of Historic Places Continuation Sheet

Section number _____7 Page _____48 Old Towne Orange Historic District, Orange, CA

198. 171 S. Center

1921 Prairie Influenced

Historical Name: St. John's Lutheran Church Parsonage AP Number: 390-384-07

This is the St. John's Lutheran Church Parsonage and has been added to the National Register along with the church building and Walker Hall in 1992. 171 S. Center is the old parsonage, a two-story house built in the Prairie style and constructed as the parsonage for St. John's Church. As is typical of the style (which is rare in the urban context in Southern California) the house includes a flat roof and stucco facades. The house is built on a box plan with symmetrical posture. Entry is at front center, defined by a rectilinear, projecting portico which is echoed on the second story. A fullwidth balcony with ornamental balustrade is on the second story. A large, arched opening leads off the balcony to French doors that lead to the interior. The large entry door with plate glass windows is flanked on either side by matching side-lights. The house is in excellent condition and retains the full breadth of its original architectural integrity.

199. 185 S. Center

1914-29 Gothic Historical Name: St. John's Lutheran Church AP Number: 390-384-08 St. John's Lutheran Church, is a large brick structure fashioned in the Gothic tradition. The building is distinguished by a large corner steeple

Gothic tradition. The building is distinguished by a large corner steeple and a second, smaller one on the opposite front corner. A gable connects the two steeples. Each steeple is a rectilinear formation topped with battlements, a high tent roof and a cross. The larger steeple contains a large pointed arch vent with a clock face. The main entry is composed of a three-part compound, pointed arched portal with moulded archivolts and ornamental capitals on the pilasters. The upper portion of these and other similar doors on the building feature trefoil and quatrefoil tracery of stained glass. A large pointed (Gothic) arch window is above the main entry and repeated again on the sides of the building. Each has stained glass. The building is in excellent condition and features its original architectural integrity.

200. 206 S. Center 1943 Historical Name: AP Number: 390-393-10 Non-Contributor

National Register of Historic Places Continuation Sheet

Section number _____7 Page _____49 Old Towne Orange Historic District, Orange, CA

201. 209 S. Center

1919 Bungalow Historical Name: AP Number: 390-394-01

A one-story bungalow built on a rectangular plan with a single gable, shallow-pitched roof. Original siding is covered with asbestos shingles. The main entry is recessed beneath an entry gable articulated by vertical slatting. The original door with mullioned glass window is flanked on either side by identical side lights.

202. 218 S. Center c1920 Bungalow Historical Name: AP Number: 390-393-09 A T-plan clapboard bungalow with shallow-pitched, tri-gable roof. Frontfacing gable forms entry wing of house. Main door is at center flanked by three high, narrow vertical windows on either side.

203. **223 S. Center** 1924 Mediterranean Revival Historical Name: AP Number: 390-394-02 A large, boxy stucco house with a flat roof. Distinct Mediterranean Revival influences are derived from the raised parapet which is accented by adobe tiles in the two smaller adobe tiled hoods over the main front windows. The entry is at center beneath a small gabled portico accented with adobe tiles.

204. **228 S. Center** 1950 Historical Name: AP Number: 390-393-08 Non-Contributor

205. **231 S. Center** c1910 Hip Roof Cottage Historical Name: AP Number: 390-394-03 This is a box plan house with pyramidal roof and clapboard siding. No porch exists, but a small, front-facing gable with cross-ties and attic venting is located on the front half of the house. Large picture windows flank either side of the main entry.

National Register of Historic Places Continuation Sheet

Section number _____7 Page _____50 Old Towne Orange Historic District, Orange, CA

206. **234 S. Center** 1913 Bungalow Historical Name: AP Number: 390-393-07 A single-story clapboard bungalow with double, front-facing gables. The forwardmost gable forms the entry porch overhang supported by tapered piers.

207. 237 S. Center 1916 Historical Name: AP Number: 390-394-04 Non-Contributor

208. 242 S. Center

1916 Craftsman Historical Name: AP Number: 390-393-06 A one and one-half story clapboard Craftsman house with single, side-facing gable roof which is contrasted by a smaller, front-facing gabled dormer. The main roof extends forward to form a full-width porch supported by classic Craftsman piers. Embellishment on the dormer includes ornamentally framed transom window, purlins and cross-ties at the bargeboard.

209. 257 S. Center

1922 Hip Roof Cottage Historical Name: AP Number: 390-398-01

A single-story bungalow with clapboard siding and clipped gable roof. Double, front-facing clipped gables are paired in an unusual way. The frontmost gable extends forward to form the entry porch overhang supported by Colonial columns. To either side of this gable a pergola is extended and also supported by round columns. Since the 1982 survey, this structure has been altered with inappropriate porch posts and rail in a Victorian style.

210. **258 S. Center** 1914 Historical Name: AP Number: 390-397-10 Non-Contributor

National Register of Historic Places Continuation Sheet

Section number _____7 Page _____51 Old Towne Orange Historic District, Orange, CA

211. **259 S. Center** Historical Name: AP Number: 390-414-08 Non-Contributor

212. 265 S. Center c1920 Bungalow Historical Name: AP Number: 390-398-02 A single-story clapboard bungalow with double, front-facing gable roof. Forwardmost gable forms entry porch overhang supported by wide piers.

213. **266 S. Center** 1920 Bungalow Historical Name: AP Number: 390-397-09

A clapboard, rectangular plan bungalow with tri-gable roof. Main portion of house is covered by a single, side-facing gable roof; front-facing gable, centrally located on the front facade, forms the entry porch overhang. This gable is supported by elephantine piers and is ornamented by a framed attic vent and dentils which span the full width of the gable face. Three large picture windows are located across the front facade.

214. 274 S. Center

c1915 Craftsman Historical Name: AP Number: 390-397-08 This is a full two-story home with single, front-facing gable roof. House is sheathed in clapboard. A small shed overhang forms a full-width porch beneath and is supported by tapered piers. Double door entry indicates duplex usage of house. Ornamental purlins grace the eaves. Lattice work is located in the uppermost portion of the front gable.

215. 275 S. Center
1875 Victorian-era Settlement House
Historical Name: Methodist Church Parsonage
AP Number: 390-398-03
Non-Contributor. Since the 1982 survey, this structure has been replaced
with a wood sided, multi-gabled craftsman-style duplex.

National Register of Historic Places Continuation Sheet

Section number _____7 Page _____52 Old Towne Orange Historic District, Orange, CA

216. **317 S. Center** 1946 Historical Name: AP Number: 390-404-01 Non-Contributor

217. **327 S. Center** 1917 Historical Name: AP Number: 390-404-02 Non-Contributor

218. 328 S. Center 1910 Hip Roof Cottage Historical Name: AP Number: 390-403-19 A single-story, box plan house with a steep-pitched, hip roof and clapboard siding. A smaller, front-facing gable forms the attic dormer. Entry is via a corner porch recessed beneath the main portion of the house and is supported by a Classical column. Wide eaves are ornamented by brackets.

219. **335 S. Center** 1906 Hip Roof Cottage Historical Name: AP Number: 390-404-03 Non-Contributor

220. **336 S. Center** 1964 Historical Name: AP Number: 390-403-18 Non-Contributor

221. **343 S. Center** 1912 Bungalow Historical Name: AP Number: 390-404-04 A single-story, clapboard bungalow with double, front-facing gables. The frontmost gable originally formed the entry porch overhang but has been enclosed in recent years. This gable face is ornamented with dentils and a framed attic dormer.

National Register of Historic Places Continuation Sheet

Section number _____7 Page _____53 Old Towne Orange Historic District, Orange, CA

222. 344 S. Center

1905 Bungalow Historical Name: AP Number: 390-403-17 A clapboard bungalow with hip roof. A separate hip roof extends forward to form the entry porch overhang supported by slender piers. A pergola is located adjacent to the porch overhang. Since 1982, an attempt has been made toward restoration. Some details are too Victorian.

223. **351 S. Center** c1920 Craftsman Bungalow Historical Name: AP Number: 390-404-05 This is a rectangular plan bungalow with clapboard siding and double, frontfacing gable roof. Forwardmost gable forms entry porch overhang supported by tapered piers. Exposed beams and triangular bracket supports adorn the front facade.

224. **352 S. Center** 1909 Hip Roof Cottage Historical Name: AP Number: 390-403-16 A box plan clapboard house with steep-pitched hip roof. A small, frontfacing gable forms the attic dormer. A separate roof extension forms the porch overhang supported by three Classical columns.

225. **357 S. Center** 1921 California Bungalow Historical Name: AP Number: 390-404-06

This is a classic California bungalow with a rectangular plan, clapboard siding and single, side-facing gable roof contrasted by a centrally located, front-facing gable which forms the entry porch overhang. This front-facing gable is the architectural focal point of the house and incorporates a clipped gable return at the eaves supported by Colonial columns. A pergola is located to either side.

1

National Register of Historic Places Continuation Sheet

Section number _____7 Page _____54 Old Towne Orange Historic District, Orange, CA

226. **360 S. Center** 1912 Craftsman Bungalow Historical Name: AP Number: 390-403-15 A single-story, clapboard bungalow with hip roof and gable extension to one side which forms the entry porch overhang supported by wide piers of clapboard with stucco bases. The front-facing gable is ornamented with dentils and ornamentally framed attic vent and purlins. Large picture windows with diamond pane transoms flank either side of main entry.

227. **367 S. Center** 1909 Hip Roof Cottage Historical Name: AP Number: 390-404-07 A box plan house with steep-pitched hip roof contrasted by smaller, frontfacing gable which forms the Cttic dormer. Entry is via a recessed corner porch supported by Classical columns.

228. **368 S. Center** 1910 Hip Roof Cottage Historical Name: AP Number: 390-403-14 A box plan house with pyramidal roof and board and batten siding. Corner recessed porch forms the entry focal porch supported by Classical columns with wide pier bases.

229. **375 S. Center** 1912 Craftsman Historical Name: AP Number: 390-404-08 One and one-half story Craftsman house with rectangular plan and single, side-facing gable roof complemented by a smaller, front-facing gabled dormer. The main roof extends forward to form a full-width porch overhang. Entry is slightly off center flanked by large, three-part picture windows on each side. Front facade is board and batten and appears as if some alterations have been made to the house.

230. **376 S. Center** 1955 Historical Name: AP Number: 390-403-13 Non-Contributor

National Register of Historic Places Continuation Sheet

Section number _____7 Page _____55 Old Towne Orange Historic District, Orange, CA

231. 381 S. Center
1931 Bungalow
Historical Name:
AP Number: 390-404-09
A single-story, clapboard bungalow with double, front-facing gables.
Smaller, forwardmost gable forms entry porch overhang supported by tapered
piers.

232. 393 S. Center

c1905 Hip Roof Cottage Historical Name: AP Number: 390-404-10 A single-story clapboard house with steep-pitched, hip roof and box plan. A small, front-facing gable accents the front roofline. A nearly full-width porch overhang extends from the main facade supported by Classical columns. Low porch wall connects the columns.

233. **405 S. Center** 1954 Historical Name: AP Number: 390-414-01 Non-Contributor

234. 406 S. Center

1909 Hip Roof Cottage Historical Name: AP Number: 390-413-24 A clapboard, box plan house of one story with steep-pitched, hip roof and small, front-facing attic dormer gable. Entry is via a corner porch which is recessed beneath main portion of house and is supported by a single, Classical column. A large, single-pane picture window with leaded glass transom is on front facade.

235. 414 S. Center

1917 Craftsman Bungalow Historical Name: AP Number: 390-413-23 A single-story, clapboard bungalow with shallow-pitched, double front-facing gables. The forwardmost gable forms the entry porch overhang supported by piers. Wide vertical slatting ornaments each of the gable faces.

National Register of Historic Places Continuation Sheet

Section number _____7 Page ____56 Old Towne Orange Historic District, Orange, CA

236. **415 S. Center** Historical Name: AP Number: 390-414-02 Non-Contributor

237. **420 S. Center** 1909 Hip Roof Cottage Historical Name: AP Number: 390-413-22 A single-story clapboard house with box plan and pyramidal roof. A smaller, front-facing gable acts as a dormer window and is sheathed in shingles. Entry is via a corner porch recessed beneath main roof and supported by Classical columns.

238. **421 S. Center** 1954 Historical Name: AP Number: 390-414-03 Non-Contributor

239. **427 S. Center** 1954 Historical Name: AP Number: 390-414-04 Non-Contributor

240. **430 S. Center** 1964 Historical Name: AP Number: 390-413-21 Non-Contributor

241. **436 S. Center** 1907 Hip Roof Cottage Historical Name: AP Number: 390-413-20 A single-story, box plan house with clapboard siding and a steep-pitched, hip roof. A small pedimented gable sheathed in shingles with an ornamental transom vent is located to the side of the house on the front portion of the roof and is contrasted by a corner recessed porch supported by Classical columns.

National Register of Historic Places Continuation Sheet

Section number _____7 Page _____57 Old Towne Orange Historic District, Orange, CA

242. **437 S. Center** 1947 Historical Name: AP Number: 039-223-08 Non-Contributor

243. 444 S. Center

1919 Bungalow Historical Name: AP Number: 390-413-19 A single-story, clapboard bungalow with shallow-pitched, front-facing gable roof. Main entry is via a recessed corner porch supported by wide piers also sheathed in clapboard. Wide vertical slatting accents the upper gable face. Eaves feature exposed rafters.

244. **447 S. Center** 1954 Historical Name: AP Number: 390-414-06 Non-Contributor

245. **454 S. Center** 1907 Hip Roof Cottage Historical Name: AP Number: 390-413-18 A single-story, box plan house sheathed in clapboard with a steep-pitched, hip roof. A small, front-facing hipped dormer is located on the front portion of the roof. A corner porch is recessed beneath the main portion of the house and is supported by Classical columns. Two picture windows, each with a transom, are located on the front facade.

246. **454 S. Center** 1954 Historical Name: AP Number: 390-414-07 Non-Contributor

247. **459 S. Center** 1925 Historical Name: AP Number: 390-414-08 Non-Contributor

National Register of Historic Places Continuation Sheet

Section number _____7 Page _____58 Old Towne Orange Historic District, Orange, CA

248. **460 S. Center** 1930 Bungalow Historical Name: AP Number: 390-413-17 Single-story bungalow with wide clapboard siding and shallow-pitched, double, front-facing gable roof. Forwardmost gable forms entry porch overhang supported by thin wood posts.

249. 464 S. Center

1921 Craftsman Bungalow Historical Name: AP Number: 390-413-16 A single-story bungalow with wide clapboard siding and double, front-facing gables. Forwardmost gable forms entry porch overhang supported by wide concrete piers topped by wood posts. A pergola, also supported by an identical pier, is located to the side of the porch gable.

250. 469 S. Center

c1890 Victorian Historical Name: AP Number: 390-414-09 A two-story house with shiplap siding and multi-gable roof. Entry is beneath the separate porch extension with a pedimented gable and turned posts with ornamental brackets. High narrow windows are characteristic of the Victorian period. Bargeboard on gables has some ornamentation.

251. 477 S. Center

1899 Victorian Historical Name: AP Number: 390-414-10 A two-story house with L-plan characterized by a large, front-facing gable with return at eaves of the gable. A porch covering attached to the main facade wraps around the forwardmost gable and has a slatted balcony ballustrade supported by thin wood posts. This is probably a later addition.

252. **480 S. Center** 1912 Historical Name: AP Number: 390-413-15 Non-Contributor

National Register of Historic Places Continuation Sheet

Section number _____7 Page _____59 Old Towne Orange Historic District, Orange, CA

253. 481 S. Center

1917 Craftsman Bungalow Historical Name: AP Number: 390-414-12 A single-story bungalow with rectangular plan and single, side-facing gable roof. This is contrasted by a small shed dormer which acts as the attic outlet. The main house extends forward to form full-width porch overhang supported by four piers. The two outermost piers are large circular columns; the innermost piers are concrete column bases with smaller, thinner columns on top.

254. 484 S. Center

1908 Bungalow Historical Name: AP Number: 390-413-14 A single-story clapboard bungalow with gable roof and separate, adjacent portico entry consisting of a small shed roof and wood post supports. Since the 1982 survey, this structure has been altered with an inappropriate addition.

255. 101 E. Chapman

1928 Beaux Arts Bank Historical Name: First National Bank AP Number: 039-251-20 See National Register Plaza Historic District list.

256. **112 E. Chapman** 1901 Historical Name: Odd Fellows Hall or Watson's Drug Store AP Number: 390-381-21 See National Register Plaza Historic District list.

257. **119 E. Chapman** 1965 Historical Name: AP Number: 039-251-21 See National Register Plaza Historic District list.

258. **208 E. Chapman** 1905 Historical Name: AP Number: 390-382-02 See National Register Plaza Historic District list.

National Register of Historic Places Continuation Sheet

Section number _____7 Page _____60 Old Towne Orange Historic District, Orange, CA

259. **211 E. Chapman** 1925 Historical Name: Elk's Building AP Number: 039-252-07 See National Register Plaza Historic District list.

260. **212 E. Chapman** 1904 Historical Name: AP Number: 390-382-03 See National Register Plaza Historic District list.

261. **217 E. Chapman** 1950 Historical Name: AP Number: 039-252-08 See National Register Plaza Historic District list.

262. **227 E. Chapman** 1979 Historical Name: AP Number: 039-252-09 Non-Contributor

1

263. **300 E. Chapman** 1887 Victorian-era Fountain Historical Name: AP Number: 390-383-01 This is a three-tiered fountain constructed of sculpted metal. Water splashes over the edges of the shallow bowls with ruffled edges and also pours forth from the beaks of sculpted birds beneath the lowest bowl. The main pool has a concrete shell and a black tiled bottom.

National Register of Historic Places Continuation Sheet

Section number _____7 Page _____61 Old Towne Orange Historic District, Orange, CA

264. 307 E. Chapman

c1905 Classical Revival Historical Name: AP Number: 039-253-23

This is a very large, two-story house which dates to just after the turn of the century. The house takes on a particularly unusual appearance due to the fact that the front portion was modified within the first 20 years after construction. The front portion of the house features large, two-story fluted columns with simple capitals and a second story balcony recessed below the main roof. Double French doors are featured on the upper story in the front; double hung windows are present on the lower story. The rear and sides of the house feature the typical Classical Revival elements--bay windows, ornamented gables and hip rooflines. Since the 1982 survey, this structure has been altered with appropriate balcony railing.

265. **345 E. Chapman** 1963 Historical Name: AP Number: 039-253-12 Non-Contributor

266. 414 E. Chapman

1910 Bungalow with Queen Anne Cottage Features Historical Name: Lewis Ainsworth House AP Number: 390-384-02 This house is the Lewis Ainsworth House which is the official restored house museum for the City of Orange. The house features unusual proportions. It

museum for the City of Orange. The house features unusual proportions. It is a single-story house with a multi-gable roofline which features three, front-facing gables. Recessed beneath the roof is a full curvalinear porch featuring an entrance on either side of the projecting bay in the center. Palladian transoms are present in each of the upper gable faces; a large, picture window with transom is present below. Ornamental jigsawn work adorns the brackets of the porch posts. This was added to the Nationl Register of Historic Places in 1981.

National Register of Historic Places Continuation Sheet

Section number _____7 Page _____62 Old Towne Orange Historic District, Orange, CA

267. 431 E. Chapman

1920 Craftsman Historical Name: AP Number: 039-254-11 This is a two-story Craftsman house with clapboard siding and multi-gable roofline. The house is distinguished by a second story located predominantly on the rear half of the house. The lower story in front features a large, front-facing gable supported by elephantine piers. The entry is beneath this porch gable. The original door with mullioned, plate glass windows is still present, flanked on either side by side lites. A large, three-part picture window with transom is on either side of the main entry. An ornamental brick chimney is located on the side of the house.

268. **439 E. Chapman** 1965 Historical Name: AP Number: 039-254-12 Non-Contributor

269. **450 E. Chapman** 1965 Historical Name: AP Number: 390-384-03 Non-Contributor

270. **506 E. Chapman** Historical Name: AP Number: 390-382-03 Non-Contributor

271. **513 E. Chapman** 1956 Historical Name: AP Number: 386-071-18 Non-Contributor

272. **516 E. Chapman** Historical Name: AP Number: 390-441-15 Non-Contributor

National Register of Historic Places Continuation Sheet

Section number _____7 Page _____63 Old Towne Orange Historic District, Orange, CA

273. **524 E. Chapman** 1981 Historical Name: AP Number: 390-441-04 Non-Contributor

274. **531 E. Chapman** 1969 Historical Name: AP Number: 386-071-09 Non-Contributor

275. 532 E. Chapman

c1915 Craftsman Historical Name: AP Number: 390-441-16 What was originaly a Craftsman style bungalow has been modified in more recent years. The house is defined by clapboard siding and multi-gable roofline with ornamental purlins beneath the roof eaves. The major part of the house is still intact, but the frontmost portion, on which a porch was probably located, has been modified to include brickwork and enclosure of most of the original porch.

276. **541 E. Chapman** 1969 Historical Name: AP Number: 386-071-10 Non-Contributor

277. **600 E. Chapman** c1930 Streamline Moderne Historical Name: AP Number: 390-441-18

This is a single-story office building constructed in the Streamline Moderne style. As is typical of this style, which was popular in the Thirties, the roof is flat and the facades are sided in stucco. All of the corners are curved as are the windows which round the corners. The windows are of glass brick, also very typical of the style. Horizontal banding at the cornice and across the entry is in excellent condition and very much retains its original architectural integrity.

National Register of Historic Places Continuation Sheet

Section number _____7 Page _____64 Old Towne Orange Historic District, Orange, CA

278. **601 E. Chapman** 1953 Historical Name: AP Number: 386-072-19 Non-Contributor

279. **615 E. Chapman** c1914 Craftsman Historical Name: AP Number: 386-072-08

This is a large, two-story house with distinct Craftsman influences combined with several unusual features. The house has a single, side-facing gable roof with each of the gables clipped. The house is sided in elongated shingles which add an important architectural feature. The main entry is at the first story on the center beneath a roof extension supported by very rotund columns. A double door entry with mullioned panes is present. The house features large windows which add to the architectural character. An addition on the east side has been made in recent years but does not significantly detract from the original architecture. This house has the potential for elibibility in the National Register pending development of more historic information associated with it. Since the 1982 survey, this structure has had a change of use from residential to professional.

280. **616 E. Chapman** 1967 Historical Name: AP Number: 390-441-09 Non-Contributor

281. **626 E. Chapman** 1912 Craftsman Historical Name: AP Number: 390-441-19

A one and one-half story Craftsman house with single siding and single, sidefacing gable roof. A front-facing dormer features ornamental exposed beams. The main roof extends forward to form a full-width porch supported by tapered piers with arroyo stone bases. The low connecting porch wall, half piers along the stoop, and the chimney are also of arroyo stone. The house is an excellent Craftsman example and comes close to being as pure an example of that style as there is in Orange. Since the 1982 survey, this structure has had a change of use from residential to professional.

National Register of Historic Places Continuation Sheet

Section number _____7 Page _____65 Old Towne Orange Historic District, Orange, CA

282. 636 E. Chapman

c1925 Mediterranean Revival Historical Name: AP Number: 390-441-20 This is a single-story, box plan house with stucco facades and a flat roof. The house features the rectalinear projection common on the Mediterranean style that incorporates a slight Pueblo influence. The house was built on a symmetrical plan with entry recessed and distinguished by a large arched opening with raised pilasters. To either side of the entry is a large, mullioned picture window with an adobe tile hood.

283. **702 E. Chapman** 1926 Spanish Colonial Revival Historical Name: Bartling House AP Number: 390-443-01

This is a one-story house built in the Spanish Colonial Revival style. The house design is symmetrical with the main entry located at front center and flanked on either side by large picture windows. The hip roof and portico have adobe tiles; thefacades have stucco siding. The entry portico has a large arched opening which is complemented by Roman arched, picture windows on the front facade. Wide eaves feature pairs of ornamentally scrolled bracket. The west side of the house includes a second entrance, featuring a porch and fountain in Hermosa tiles. The house is in excellent condition and has been restored to its original condition on the exterior and interior.

284. 705 E. Chapman

1908 Craftsman Historical Name:

AP Number: 386-073-07

This is a large, two-story house with wide lap siding and gable roofline. The house is built on a box plan with symmetrical front facade. The entry comprises the architectural statement on the house, featuring a gable dormer on the upper story with an arched opening leading to a recessed balcony. The roof extension below is supported by ornamental brackets with an entry door flanked by side lites. An angled bay is located on the south half of the front facade.

285. 707 E. Chapman 1959 Historical Name: AP Number: 386-073-08 Non-Contributor

National Register of Historic Places Continuation Sheet

Section number _____7 Page _____66 Old Towne Orange Historic District, Orange, CA

286. **729 E. Chapman** 1958 Historical Name: AP Number: 386-073-09 Non-Contributor

287. 811 E. Chapman

c1922 Spanish Colonial Revival Historical Name: AP Number: 386-074-09

This is a large, two-story house with a box plan, stucco facades and a flat roof. The center portion of the house is distinguished by a rectalinear projection which houses a recessed entry beneath. The arched opening of this entry is accented by two rotund columns. On either side of the entry are mullioned French doors with adobe tile hoods. Adobe tiled hoods are also located on the cornice around the entire circumference of the upper portion of the house. The windows on the second story have been modified over the years.

288. **813 E. Chapman** Historical Name: AP Number: 386-074-10 Non-Contributor

289. 820 E. Chapman 1924 Spanish Colonial Revival Church Historical Name: AP Number: 390-444-12 This is a Spanish Colonial Revival church built during the mid-20's when this style was at the height of its popularity. Typical to the style, the church features stucco facades and adobe tiling, coupled with a Mission oriented cupola and bell tower. The main front entry of the church features a large gabled face with three arched entry openings incorporating floral relief work around the recessed portion of these openings. A large rosette stained glass window is featured just above. The cupola which is to the side features arched openings and a domed tower crowned with a cross on top.

290. **850 E. Chapman** Historical Name: AP Number: 390-444-02 Non-Contributor

National Register of Historic Places Continuation Sheet

Section number _____7 Page _____67 Old Towne Orange Historic District, Orange, CA

291. **910 E. Chapman** c1925 Spanish Colonial Revival Historical Name: AP Number: 390-451-23 This is a large, two-story h

This is a large, two-story house with adobe tiled, hip roof and stucco facades. The house occupies a corner lot and plays a prominent role as a distinguished house along East Chapman. The house features a second story balcony defined by a balcony wall with raised pilasters. A mullioned door with mullioned side lites forms the entry to this balcony and are flanked on either side by by a large, three-part window. The entry below is slightly recessed and accessed via a stoop. The entry is articulated with ornamental pilasters on either side of the main door. A large, fixed-pane window is also present on either side of the main entry. A porte cochere with piers modeled after the pilasters of the main entry is featured on the side of the house.

292. **924 E. Chapman** 1921 Craftsman Historical Name: AP Number: 390-451-02 Non-Contributor. Due to commercial alterations of this Craftsman style building.

293. **932 E. Chapman** 1924 Spanish Colonial Revival Historical Name: AP Number: 390-451-03 This is a small, single-story Spanish Colonial Revival bungalow with stucco facades and an adobe tiled, gable roof. The roofline profile of the house is fashioned in an L-plan with the short leg resulting in a front-facing gable adorned with a large mullioned, picture window. The entry is recessed beneath a small projection with an arched opening. The remaining half of the front facade is articulated by a projection with raised pilasters which is carried through in the porte cochere on the side of the house.

National Register of Historic Places Continuation Sheet

Section number _____7 Page _____68 Old Towne Orange Historic District, Orange, CA

294. 940 E. Chapman

1913 Craftsman Historical Name: AP Number: 390-451-04 A one and one-half story Craftsman house with single, side-facing gable roof and clapboard siding. A large, front-facing gable dormer is present and features mullioned windows. The main roof originally extended forward to form a full-width porch which was supported by arroyo stone piers. This porch has since been enclosed, although the piers are still present.

295. **1005 E. Chapman** 1959 Historical Name: AP Number: 386-062-45

Non-Contributor

296. 1006 E. Chapman

1937 Spanish Colonial Revival Historical Name: AP Number: 390-452-01

This is another of the large, stately Spanish Colonial Revival homes that were built by the wealthier businessmen along East Chapman. This is a twostory house with stucco facades and an adobe tiled, hip roof. The entry is at center via a small recessed opening. For the most part, the house is simple and unadorned, with the primary architectural focus being on the many mullioned windows. A three-tiered fountain is located in front of the entry.

297. 1015 E. Chapman

1924 Spanish Colonial Revival Historical Name: AP Number: 386-062-46 This is a small, single-story Spanish Colonial Revival bungalow with stucco facades and a flat roof complemented by adobe tiled hoods. The house is built on a symmetrical, rectangular plan with the entry at center, which is contrasted by two raised projections on either side. The entry is recessed beneath the main roof and is enclosed by a low patio wall.

298. **1025 E. Chapman** 1936 Historical Name: AP Number: 386-062-47 An L-shaped stucco commercial building with no special ornamentation.

National Register of Historic Places Continuation Sheet

Section number _____7 Page _____69 Old Towne Orange Historic District, Orange, CA

Also

299. 110 W. Chapman 1905 Historical Name: AP Number: 390-664-01 See National Register Plaza Historic District list. 300. 118 W. Chapman 1915 Historical Name: AP Number: 390-664-02 See National Register Plaza Historic District list. 301. 133 W. Chapman 1920 Historical Name: Jorn Building Addition AP Number: 039-174-11 See National Register Plaza Historic District list. 302. 201 W. Chapman 1912 Historical Name: AP Number: 039-173-14 See National Register Plaza Historic District list. 303. 204 W. Chapman 1916 Historical Name: AP Number: 390-663-17 See National Register Plaza Historic District list. 304. 207 W. Chapman 1910 Brick Commercial Historical Name: AP Number: 039-173-13 Non-Contributing. Extensive remodeling removes this from District. refer to National Register Plaza Historic District list. 305. 212 W. Chapman 1968 Historical Name: AP Number: 390-663-16 See National Register Plaza Historic District list.

National Register of Historic Places Continuation Sheet

Section number _____7 Page ____70 Old Towne Orange Historic District, Orange, CA

306. **221 W. Chapman** 1926 Brick Commercial Historical Name: W.O. Hart Post Office AP Number: 039-173-11 See National Register Plaza Historic District list.

307. **222 W. Chapman** 1885 Victorian Historical Name: Vineland Home

AP Number: 390-663-01

What has been known historically as the Vineland Home is comprised of a twostory building with a hip roof and regularly spaced, sash windows. Ornamental brackets embellish the chimney, but other than this the building is simple and unadorned. A sketch of the building reveals that it was originally built on the rear of a one-story, L-plan Victorian cottage. Today, that house is replaced by a stucco store-front, commercial building which renders the original hotel building nearly invisible from the street. The 1886 sketch reveals that the hotel building remains in its architectural state and always was barely visible from the street due to the presence of the house in front. Since the 1982 survey, two windows have been removed and the fire escape stairs and the open back area are enclosed.

308. **234 W. Chapman** 1920 Brick Commercial Historical Name: AP Number: 390-663-01 Non-Contributor

309. 235 W. Chapman 1925 Moderne Historical Name: AP Number: 039-173-10 What is currently an auto repair shop was originally a small gas station and, in fact, one of the first in Orange. This structure consists of two projecting bays, each supported by columns. The roof of each of these bays is in the curvalinear style with banding typical of Moderne structures.

National Register of Historic Places Continuation Sheet

Section number _____7 Page ____71 Old Towne Orange Historic District, Orange, CA

310. 308 W. Chapman 1935 Spanish Colonial Revival Historical Name: AP Number: 390-662-18 This is a single-story post office building comprised of a rectangular plan with stucco facades and adobe tile roof. The building features a slightly recessed entry with transom window and wrought iron balustrades ascending stoop to the entry. Windows include large, mullioned sash windows. The building was built to serve as a post office and still has that function.

311. **319 W. Chapman** 1973 Historical Name: AP Number: 039-172-15 Non-Contributor

312. **321 W. Chapman** 1922 Historical Name: AP Number: 039-172-11 Non-Contributor

313. **324 W. Chapman** 1946 Historical Name: AP Number: 390-662-16 Non-Contributor

314. **335 W. Chapman** Historical Name: AP Number: 039-172-10 Non-Contributor

315. **396 W. Chapman** 1955 Historical Name: AP Number: 390-662-01 Non-Contributor

National Register of Historic Places Continuation Sheet

Section number _____7 Page _____72 Old Towne Orange Historic District, Orange, CA

316. 401 W. Chapman

c1920 Brick Commercial Historical Name:

AP Number: 039-171-12

Since its construction, this single-story brick building has been used for commercial purposes. As typical with commercial buildings of this era, the lower portion of the store front is devoted almost exclusively to showcase windows. The double door entry features wood doors with a single, plate glass window and transom above. Transom windows were located across all of the windows on the lower portion of the building, but signs have since been placed in these transoms. Horizontal banding distinguishes the cornice.

317. 424 W. Chapman

1921 Brick Commercial Historical Name: AP Number: 390-661-01

This is a single-story commercial building with flat roof and combined brick and stucco siding. The building sits on the curbside lot line and includes wide, showcase window bays separated by brick pilasters. The parapet is raised at each of the main entries and receives unusual detailing on the main corner of the building. Here the brick pilasters rise above the parapet and flank two, modified Mission style raised parapets. An ornamental arrangement of contrasting brick is placed along the parapet walls and along the cornice line of the building. A narrow tile hood just below the cornice extends along the upper portion. The building is in good condition and retains its original, architectural integrity down to the original entry doors and transom windows.

318. **337 S. Clark** 1959 Historical Name: AP Number: 041-132-30 Non-Contributor

Į

319. 339 S. Clark
1927 Mediterranean Revival
Historical Name:
AP Number: 041-132-03
Rectangular plan with flat roof in ornamental tile ridges in roof.
Characteristic stucco siding with arched porte cochere. Gabled entry portico
has arched opening and small arched window to the side.

National Register of Historic Places Continuation Sheet

Section number _____7 Page ____73 Old Towne Orange Historic District, Orange, CA

320. **343 S. Clark** 1961 Historical Name: AP Number: 041-132-28 Non-Contributor

321. **345 S. Clark** 1961 Historical Name: AP Number: 041-132-27 Non-Contributor

322. **351 S. Clark** 1961 Historical Name: AP Number: 041-132-25 Non-Contributor

323. 353 S. Clark
1925 Bungalow
Historical Name:
AP Number: 041-132-05
Modified L-plan, clapboard siding and shallow pitched, gable roof. Frontmost
gable face includes a large multi-paned, three-part window. Two pairs of
large, multi-paned windows flank either side of main entry door.

324. **367 S. Clark** 1946 Historical Name: AP Number: 041-132-06 Non-Contributor

325. **375 S. Clark** 1927 Mediterranean Revival Historical Name: AP Number: 041-132-07 Box plan, flat roof and stucco siding. Roof edges are highlighted with adobe tiles. Frontmost entry is through projecting vertical portico with arched openings. Small tile hoods adorn windows on front facade.

National Register of Historic Places Continuation Sheet

Section number _____7 Page ____74 Old Towne Orange Historic District, Orange, CA

326. 125 N. Cleveland

c1920 Bungalow Historical Name: AP Number: 386-072-06 A single-story clapboard bungalow with multi-gable roof. The majority of the front facade is comprised of a large front-facing gable with a smaller frontfacing gable which forms the entry porch overhang. This is supported by wide ornamental, concrete piers and also features ornamental purlins and an ornamentally framed attic vent.

327. **132 N. Cleveland** 1931 Bungalow Historical Name: AP Number: 386-071-11 A single-story clapboard bungalow with double front-facing, gable roof. The forwardmost gable forms the entry porch overhang and is supported by tapered piers. Exposed beams grace the eaves of the house.

328. **135** N. Cleveland 1920 Bungalow Historical Name: AP Number: 386-072-05 A single-story bungalow with ornamental lap siding and shallow-pitched, gable roof. The main portion of the house is covered by a single-gable roof with side-facing gable which extends forward along three-quarters of the front facade to form an entry porch overhang. It is supported by large triangular supports. Just above is a small front-facing, attic dormer with exposed beams and ornamental attic vent.

329. 140 N. Cleveland

c1921 Bungalow Historical Name: AP Number: 386-071-12 A single-story bungalow with wide lap siding and single-gable roof with sidefacing gables. A small entry portico is articulated with a small, frontfacing gable supported by an ornamental arrangement of exposed beams.

National Register of Historic Places Continuation Sheet

Section number _____7 Page _____75 Old Towne Orange Historic District, Orange, CA

330. 145 N. Cleveland

1910 Craftsman Historical Name:

AP Number: 386-072-04

A 1-1/2-story Craftsman house with clapboard siding and single-gable roof with side-facing gables. There is also a front-facing gable dormer ornamented with cross-ties and purlins. One-half of the front facade is distinguished by a recessed porch which is supported by ornamental wood posts. Large picture windows adorn the front facade, and each features beveled glass transoms.

331. 148 N. Cleveland

1920 Bungalow Historical Name: AP Number: 386-071-13

A single-story bungalow with shallow-pitch, multi-gable roof. Facade is now covered with asbestos siding. The house is distinguished by a large corner wrap-around porch formed by an extension of the main side-facing gable roof. This porch overhang is supported by piers comprised of brick bases and wood posts on top. There is a smaller, front-facing gable whose facade is adorned with a large transomed picture window. The original front door with three vertical panes is still present and is flanked on either side by side lites.

332. 155 N. Cleveland

1921 Prairie Historical Name: AP Number: 386-072-03

A two-story box plan house with stucco facade and flat roof. The house incorporates features of the praire style pioneered by architect Frank Lloyd Wright. The wide overhanging eaves and horizontal banding between the first and second story are typical of the style. There is a large projecting entry porch which is supported by wide ornamental concrete piers and connected by a large arch opening.

333. 156 N. Cleveland

1932 Bungalow Historical Name: AP Number: 386-071-14 A single-story clapboard bungale front-facing, gable roof on th

A single-story clapboard bungalow with multi-gable roof which includes double front-facing, gable roof on the front facade. The forwardmost gable here forms the entry porch overhang and is supported by tapered piers.

فالعابة المبهد المتحديون التاري

United States Department of the Interior National Park Service

National Register of Historic Places Continuation Sheet

Section number _____7 Page _____76 Old Towne Orange Historic District, Orange, CA

334. 162 N. Cleveland

1922 Spanish Colonial Historical Name: AP Number: 386-071-15 A spanish colonial residence on a rectangular plan with red-tiled low-pitched roof and double-hung multi-paned wooden windows. The front porch fronts half of the front facade and features a flat roof with single pole posts. An exterior brick chimney, stucco siding, and single-board window sills are present.

335. 165 N. Cleveland

1922 California Bungalow Historical Name: AP Number: 386-072-02 A single-story bungalow w

A single-story bungalow with single side-facing, gable roof and a frontfacing gable entry porch overhang centrally located along the front facade. This overhang is supported by ornamental wood posts. All the roof gables are clipped. Large combination of three casement windows is present on the front facade.

336. 216 N. Cleveland

c1920 Bungalow Historical Name: AP Number: 386-081-12 A single-story bungalow with double front-facing, gable roof and facades now covered by asbestos shingles. The forwardmost gable forms the entry porch overhang and is supported by tapered piers with brick bases. Ornamental slatting adorns the upper portion of each gable face.

337. 224 N. Cleveland

1914 Bungalow Historical Name: AP Number: 386-081-13 A single-story bungalow with single front-facing, gable roof and facades now covered by asbestos shingles. What was probably originally a recessed porch has since been enclosed. The brickwork on the front foundation is not original.

United States Department of the Interior National Park Service

National Register of Historic Places Continuation Sheet

Section number _____7 Page ____7 Old Towne Orange Historic District, Orange, CA

338. 227 N. Cleveland

1914 Bungalow Historical Name: AP Number: 386-082-08 A single-story bungalow with single front-facing, gable roof and facades now covered by asbestos shingles. Entry is via a small recessed porch. The house is simple and unembellished except for the ornamental purlins beneath the eaves.

339. **232 N. Cleveland** 1909 Historical Name: AP Number: 386-081-14 Non-Contributor

340. 233 N. Cleveland

1915 Bungalow Historical Name: AP Number: 386-082-07 This bungalow incorporates both Victorian and Classical influences in a most unusual way. The house is a basic box plan bungalow with wide lap siding and double front-facing, gable roof. The forwardmost gable acts as the entry porch overhang and is supported by fluted classical columns. The upper gable faces have the Victorian type embellishment comprised of spindle work.

341. 241 N. Cleveland

1920 Bungalow Historical Name: AP Number: 386-082-06 A single-story bungalow with ornamental lap siding and double front-facing, gable roof. The main portion of the house is covered by a single frontfacing gable, while attached to the front facade is a smaller front-facing gable which forms a full-width entry porch overhang. This is supported by tapered piers. Vertical slatting in the upper gable faces create an ornamental feel. Since the 1982 survey, this structure has been altered with inappropriate porch rail and removal of porch pier.

342. **244 N. Cleveland** Historical Name: AP Number: 386-081-15 Non-Contributor

National Register of Historic Places Continuation Sheet

Section number _____7 Page _____78 Old Towne Orange Historic District, Orange, CA

343. 247 N. Cleveland

1919 Bungalow Historical Name: AP Number: 386-082-05 A single-story bungalow with wide lap siding and double front-facing, gable roof. The forwardmost gable forms the entry porch overhang and is supported by tapered piers. Vertical slatting in the gable faces creates ornamentation.

344. 248 N. Cleveland

1919 Bungalow Historical Name: AP Number: 386-081-16 A single-story bungalow with ornamental lap siding and shallow pitched, multi-gable roof. The main portion of the house is covered by a single-gable roof with side-facing gables. A third gable which faces the front of the house extends forward to form the entry porch overhang. It is supported by wood posts and connected by a slatted balustrade.

345. **255 N. Cleveland** 1912 Bungalow Historical Name: AP Number: 386-082-04 A single-story bungalow with wide lap siding and double front-facing, gable roof. The forwardmost gable forms the entry porch overhang and is supported by wood posts. Cross-ties and triangular bracket supports ornament the upper gable faces.

346. **256 N. Cleveland** 1920 Historical Name: AP Number: 386-081-17 Non-Contributor

347. **264 N. Cleveland** 1914 Craftsman Historical Name: AP Number: 386-081-18 A single-story house with wide lap siding and single side-facing, gable roof which is contrasted by a smaller front-facing, gable dormer. What was originally a full-width porch has since been enclosed. Since the 1982 survey, this structure has been altered with appropriate reopening of porch and appropriate porch rail.

National Register of Historic Places Continuation Sheet

Section number _____7 Page _____79 Old Towne Orange Historic District, Orange, CA

348. **265 N. Cleveland** 1977 Historical Name: AP Number: 386-082-03 Non-Contributor

349. **272 N. Cleveland** 1912 Vernacular Bungalow Historical Name: AP Number: 386-082-03

A two-story house with wide lap siding and multi-gable roof. The front facade is distinguished by a large front-facing gable with flared eaves. What was originally a corner recessed porch has since been enclosed, but the original pier is still present. Cross-ties adorn the upper gable face as do triangular bracket supports.

350. **273 N. Cleveland** 1911 Historical Name: AP Number: 386-082-02 Non-Contributor

351. 280 N. Cleveland

1914 Bungalow Historical Name: AP Number: 386-081-20

A single-story bungalow with ornamental lap siding and steep-pitched, multigable roof. The main portion of the house is covered by a single-gable roof with side-facing gables. A full-width front-facing gable forms the entry porch overhang. This is supported by wood piers with concrete bases and wood posts on top. The original wood door is still present and features three window panes. This door is flanked on either side by large transomed, picture windows.

352. **288 N. Cleveland** c1923 Mediterranean Revival Historical Name: AP Number: 386-081-21

A single-story box plan house with stucco facades and flat roof. The house features an entry porch projection on the front facade also of stucco. This is supported by large piers. The stepped parapet around the roofline creates the only embellishment on the house.

National Register of Historic Places Continuation Sheet

Section number _____7 Page _____80 Old Towne Orange Historic District, Orange, CA

353. **289 N. Cleveland** Historical Name: AP Number: 386-082-27 Non-Contributor

354. 310 N. Cleveland

1914 Historical Name: AP Number: 386-131-13 Box-shaped church with small square popped out entry which was likely a steeple. Siding is clapboard material.

355. 317 N. Cleveland

1922 Bungalow Historical Name: AP Number: 386-132-08

A single-story bungalow with wide lap siding and shallow-pitched, multi-gable roof. The main portion of the house is covered by a single gable roof with side-facing gables. A nearly full-width, front-facing gable forms the entry porch overhang. This is supported by tapered piers and features slatted wood in the upper gable face.

356. 324 N. Cleveland

1923 Bungalow Historical Name: AP Number: 386-131-14 A single-story bungalow with ornamental lap siding and multi-gable roof with

all gables being clipped at the peak. The main portion of the house is covered by a single gable roof with side-facing gables. A large front-facing gable extends forward to form the entry porch overhang. This is supported by tapered piers. This gable is embellished with dentils and an ornamental transom vent. Since the 1982 survey, this structure has been altered with inappropriate rock veneer on piers and wing walls.

357. 325 N. Cleveland

1909 Bungalow Historical Name: AP Number: 386-132-07

A single-story clapboard bungalow with double front-facing, gable roof. The forwardmost gable originally formed an entry porch overhang but has since been enclosed. The original tapered piers are still present.

National Register of Historic Places Continuation Sheet

Section number _____7 Page _____81 Old Towne Orange Historic District, Orange, CA

358. 332 N. Cleveland

1890 Hip Roof Cottage Historical Name: AP Number: 386-131-15 This is a small, single-story box plan house with shiplap siding and modified hip roof. The front facade features a separate roofed extension which forms the entry porch overhang. This is supported by slim wood posts. High, narrow windows indicate the Victorian period.

359. **335 N. Cleveland** N/A Historical Name: AP Number: 386-132-06 Non-Contributor

360. **340 N. Cleveland** 1968 Historical Name: AP Number: 386-131-16 Non-Contributor

361. 343 N. Cleveland

1922 Bungalow Historical Name: AP Number: 386-132-05 A single-story clapboard bungalow with rectangular plan and shallow=pitched, multi-gable roof. The main portion of the house is covered by a single gable roof with side-facing gables. A centrally located front-facing gable forms the entry porch overhang. This is supported by tapered piers. The original mullioned door is still present. On either side of the porch is located a large 3-part transomed window.

362. **348 N. Cleveland** 1909 Hip Roof Cottage Historical Name: AP Number: 386-131-17 A single-story box plan house with wide lap siding and steep-pitched, hip roof. The front facade is adorned with a small pedimented gable which is embellished with fish scale shingles. Attached to the front facade is a separate roofed overhang which forms the entry porch and is now supported by wrought iron piers, a replacement for the original. Since the 1982 survey, this structure has been altered with inappropriate clay tile roofing.

National Register of Historic Places Continuation Sheet

Section number _____7 Page _____82 Old Towne Orange Historic District, Orange, CA

363. **355 N. Cleveland** 1921 Bungalow

Historical Name: AP Number: 386-132-04

A single-story bungalow with wide lap siding and clipped gable roof. The front facade features an unusual clipped gable with a return at the eaves which extends on either side to form what was probably originally a full-width porch. It has since been enclosed.

364. 356 N. Cleveland

1922 Bungalow Historical Name: AP Number: 386-131-18 A single-story bungalow with wide lap siding and double front-facing, gable roof. The forwardmost gable forms the entry porch overhang and is supported by wide piers with concrete bases and wood posts on top.

Į

365. **365 N. Cleveland** 1947 Historical Name: AP Number: 386-132-03 Non-Contributor

366. **368 N. Cleveland** 1946 Historical Name: AP Number: 386-131-19 Non-Contributor

367. **371 N. Cleveland** 1957 Historical Name: AP Number: 386-132-02 Non-Contributor

368. **372 N. Cleveland** 1924 Historical Name: AP Number: 386-131-20 Non-Contributor

National Register of Historic Places Continuation Sheet

Section number _____7 Page _____83 Old Towne Orange Historic District, Orange, CA

369. 115 E. Culver 1920 California Bungalow Historical Name: AP Number: 390-401-10 Single-story bungalow with lap siding and single, side-facing gable roof. There is a double entry indicating duplex usage. Each entry is covered by a small portico gable with diagonal braces.

370. **212 E. Culver** 1909 Historical Name: AP Number: 390-412-01 Non-Contributor

371. 231 E. Culver c1915 Craftsman Bungalow Historical Name: AP Number: 390-402-11 Small, single-story bungalow with single, front-facing gable roof. The main roof extends forward to form a full-width porch overhang supported by tapered piers. Ornamental purlin and slatted venting adorn the upper gable face.

372. 333 E. Culver

1919 Craftsman Bungalow Historical Name: AP Number: 390-403-11 Small, single-story, tri-gable, clapboard bungalow with main roof comprised of side-facing gables and a front-facing gable on the central portion of the facade supported by wide piers. Entry is beneath at center.

373. **337 E. Culver** c1905 Hip Roof Cottage Historical Name: AP Number: 390-403-12 Single-story house with lap siding and a steep-pitched, hip roof. The house features a large, wrap-around corner porch and a front-facing bay window gable. The gable on the bay window is pedimented while the porch and columns are treated in the usual Classical manner.

National Register of Historic Places Continuation Sheet

Section number _____7 Page _____84 Old Towne Orange Historic District, Orange, CA

374. **354 E. Culver** 1910 Historical Name: AP Number: 390-413-25 Non-Contributor

375. 407 E. Culver

c1905 Hip Roof Cottage Historical Name: AP Number: 390-404-10 A single-story house with hip roof and box plan. A small, pedimented gable adorns the front of the roof; just offset from center is an attached porch supported by Classical columns.

376. 415 E. Culver

c1905 Hip Roof Cottage Historical Name: AP Number: 390-404-11 A single-story house with both a gable and a steep-pitched hip roof. The house has symmetrical proportions with a nearly full-width front porch extending from the main roof and supported by Classical columns. There is a smaller hipped dormer on the front side of the roof.

377. 504 E. Culver

1909 Hip Roof Cottage Historical Name: AP Number: 390-131-75 A single-story hip roof cottage with combination hip and gable roof. A fullwidth front porch is recessed beneath the main roof and is supported by wood posts. Entry is at center beneath porch and is flanked on either side by large picture windows with transoms.

378. **511 E. Culver** 1922 Craftsman Bungalow Historical Name: AP Number: 390-422-23

A single-story, clapboard bnungalow with double, front-facing gables. The forwardmost gable forms the entry porch overhang supported by tapered piers with brick bases.

National Register of Historic Places Continuation Sheet

Section number _____7 Page _____85 Old Towne Orange Historic District, Orange, CA

379. 512 E. Culver 1909 Hip Roof Cottage Historical Name: AP Number: 390-131-05 A single-story, box plan house with steep-pitched hip roof contrasted by a smaller, front-facing pedimented gable. Entry is via a recessed corner porch supported by Classical columns.

380. 519 E. Culver 1921 California Bungalow Historical Name: AP Number: 390-422-22 A single-story clapboard bungalow with single, side-facing gable roof contrasted by both a front-facing attic gable vent, dormer vent and a smaller, entry portico gable. Entry is beneath at center, flanked on either side by a pair of windows.

381. 527 E. Culver 1924 Bungalow Historical Name: AP Number: 390-422-21 A single-story, tri-gable bungalow with symmetrical proportions derived from a front-facing gable porch overhang in the center front facade. Porch gable is supported by tapered piers and entry is via either side of the porch.

382. **526 E. Culver** 1912 Craftsman Historical Name: AP Number: 390-131-06 This is an unusual house, both for its proportion and styling. Primarily, it has a large rectangular plan, gable structure with clapboard siding. A smaller, front-facing gable at the first story defines the porch overhang and attached is a full wrap-around porch. The porch is supported in five places by tapered piers with brick bases. Since the 1982 survey, this structure has been altered with appropriate rear addition, sufficiently compatible and not intrusive.

383. **535 E. Culver** 1921 Historical Name: AP Number: 390-422-20 Non-Contributor

National Register of Historic Places Continuation Sheet

Section number _____7 Page _____86 Old Towne Orange Historic District, Orange, CA

384. 536 E. Culver

1906 Hip Roof Cottage Historical Name: AP Number: 390-131-07 A single-story, box plan and clapboard house with a steep-pitched hip roof. A small dormer with hip roof is on the front portion. Entry is via recessed corner porch supported by Classical columns.

385. 543 E. Culver

1914 Craftsman Bungalow Historical Name: AP Number: 390-422-19 A single-story bungalow with lap siding and double, front-facing gables. The smaller, forwardmost gable forms the entry porch overhang supported by tapered piers with brick bases. Ornamental purlins grace the eaves.

386. 546 E. Culver

1908 Hip Roof Cottage Historical Name: AP Number: 390-131-08 A single-story house with clapboard siding and pyramidal roof. The main roof is contrasted by a smaller, front-facing gable with cross-ties and ornamental bargeboard. Probably the original entry was beneath the corner porch which has since been enclosed.

387. **552 E. Culver** Historical Name: AP Number: 390-131-77 Non-Contributor

388. **555 E. Culver** 1915 Craftsman Historical Name: AP Number: 390-422-18 One and one-half story Craftsman house with main roof comprised of sidefacing gable contrasted by front-facing dormer gable. The main roof extends forward to form what was originally a porch overhang but has since been enclosed with large, multi-pane windows. Porch overhang is supported by tapered piers. The house has lap siding.

National Register of Historic Places Continuation Sheet

Section number _____7 Page _____87 Old Towne Orange Historic District, Orange, CA

389. 556 E. Culver

1915 Craftsman Historical Name:

AP Number: 390-131-76

A one and on-half story Craftsman house built on a rectangular plan with single, side-facing gable roof contrasted by a small shed dormer on the front portion. The main roof extends forward to form a full-width porch supported by tapered elephantine piers. Entry is beneath at center, flanked on either side by large, three-part windows. Since the 1982 survey, this structure has been altered with inappropriate side addition and vertical board siding.

390. 569 E. Culver

c1915 Craftsman Historical Name: AP Number: 390-422-16

A one and one-half story Craftsman house with rectangular plan, clapboard siding and a single, side-facing gable roof contrasted by a front-facing dormer gable. There is a full-width porch recessed beneath the main porch supported by wide piers with lap siding. Two smaller, half-size piers define the front stoop entry and are connected to the other piers by slatted balustrade.

391. 577 E. Culver

1915 Craftsman Bungalow Historical Name: AP Number: 390-422-15 A single-story bungalow with lap siding and tri-gable roof. Front portion of house is defined by a large, front-facing gable which forms the full-width entry porch. This gable is adorned by a three-part window with transom.

392. 585 E. Culver
1924 Mediterranean Revival
Historical Name:
AP Number: 390-422-13
A single-story bungalow scale house with a box plan, stucco siding and a flat
roof. The front facade is defined by raised pilasters at the corners. Roof
ridges are articulated with adobe tiles.

National Register of Historic Places Continuation Sheet

Section number _____7 Page _____88 Old Towne Orange Historic District, Orange, CA

393. 595 E. Culver

1914 Craftsman Historical Name: AP Number: 390-422-13 A one and one-half story Craftsman house with clapboard siding and primary roof comprised of side-facing gables. This roof is contrasted by a frontfacing dormer gable ornamented with a pair of multi-pane transoms and crossties between the bargeboards. The main roof extends forward to form a fullwidth porch supported by wide tapered piers connected to a low porch wall.

394. **605 E. Culver** Historical Name: AP Number: 390-442-17

Non-Contributor

395. **618 E. Culver** 1921 Bungalow

Historical Name: AP Number: 390-131-10 A single-story clapboard bungalow with double, front-facing gables. The forwardmost gable forms the entry porch overhang supported by piers with clapboard bases and wood posts atop.

396. 630 E. Culver c1910 Hip Roof Cottage Historical Name: AP Number: 390-131-11 A single-story, clapboard house with steep-pitched hip roof contrasted by a smaller, pedimented, front-facing gable defining the front facade and a large corner, wrap-around porch supported by Classical columns.

397. 632 E. Culver
1908 Hip Roof Cottage
Historical Name:
AP Number: 390-131-12
A single-story clapboard house with pyramidal roof extending forward to form
a large, wrap-around porch supported by Classical columns. This is
contrasted and offset by a pedimented gable defining the remainder of the
front facade.

National Register of Historic Places Continuation Sheet

ş

Section number _____7 Page _____89 Old Towne Orange Historic District, Orange, CA

398. 638 E. Culver

c1915 Craftsman Historical Name: AP Number: 390-131-13 A one and one-half story Craftsman home built on a rectangular plan with clapboard siding. The main roof has a large, side-facing gable contrasted by a front-facing dormer gable with vented transom and ornamental purlins. The main roof extends forward to form a full-width porch supported by very wide tapered piers.

399. 652 E. Culver

1911 Craftsman Historical Name: AP Number: 390-131-14 A one and one-half story Craftsman house with clapboard siding. The main roof has side-facing gables. A front-facing dormer gable has multi-pane windows in a modified palladian fashion and ornamental purlins beneath the dormer eaves. The main roof extends forward to form a full-width porch overhang supported by wide tapered piers with arroyo stone bases.

400. **720 E. Culver** 1926 Provincial Revival Historical Name: AP Number: 390-131-15 A provincial revival rectanuglar plan residuece with side gabled roof and arched gabled entry portal. Siding is stucco with double-hung wood windows and lintel type openings (4/1 paned). Exposed rafter tails are present.

401. 742 E. Culver

1925 Craftsman Bungalow Historical Name: AP Number: 390-131-16 A single-story bungalow with double, front-facing gables. The larger gable forms the main roof, while the lower gable is located exactly parallel to the larger gable. This has a a full-width porch overhang supported by tapered piers with brick bases.

National Register of Historic Places Continuation Sheet

Section number _____7 Page _____90 Old Towne Orange Historic District, Orange, CA

402. 804 E. Culver
1912 Bungalow
Historical Name:
AP Number: 390-131-17
A single-story clapboard bungalow with gable roof and square shingles in the
upper, front-facing gable face. Multi-pane windows are across the front
facade; a smaller, square gabled bay is on the side.

403. **810 E. Culver** Historical Name: AP Number: 390-131-80 Non-Contributor

404. **816 E. Culver** c1905 Hip Roof Cottage Historical Name: AP Number: 390-131-19 A single-story house with box plan, lap siding and pyramidal roof. The pyramidal roof is contrasted by a smaller gable, defining one-half of the front facade. What was originally a corner porch has since been enclosed.

405. **215 W. Culver** c1920 Gable Roof Cottage Historical Name: AP Number: 390-603-11 Non-Contribotor. Since the 1982 survey, this building no longer is considered to be of historic architectural significance.

406. **225 W. Culver** 1920 Bungalow Historical Name: AP Number: 390-603-22 Tri-gabled bungalow with each of the three gables facing front. Centermost gable is largest. Two smaller gables at either end form entry porch porticos. Each is supported by piers with wood posts. Slatting adorns upper gable faces.

407. **504 W. Culver** 1926 Bungalow Historical Name: AP Number: 041-142-23 Low to the ground clapboard bungalow with single-gable roof.

National Register of Historic Places Continuation Sheet

Section number _____7 Page _____91 Old Towne Orange Historic District, Orange, CA

408. **512 W. Culver** 1925 Bungalow Historical Name: AP Number: 041-142-24 Double front-facing, clapboard bungalow with frontmost gable forming entry porch overhang. This gable is supported by slim tapered posts. Entry is at center and flanked on either side by double-hung windows.

409. **518 W. Culver** c1895 Victorian Cottage Historical Name: AP Number: 041-142-25 Vertical emphasis common to Victorian era homes. Steep pitched, gable roof with L-plan to gable and corresponding plan on shiplap siding on facades. Special roof overhang in apex of ell forms porch overhang. Entry is just beneath this.

410. 525 W. Culver
1924 Bungalow
Historical Name:
AP Number: 041-134-11
Small, double-gable bungalow with two front-facing gables and clapboard
siding. Frontmost gable forms entry porch overhang and is supported by wood
posts. Entry is just beneath.

411. **526 W. Culver** 1912 Historical Name: AP Number: 390-131-06 Non-Contributor

412. **527 W. Culver** 1924 Bungalow Historical Name: AP Number: 041-134-10 Non-Contributor. Low to the ground, clapboard bungalow with double, frontfacing gables. Foremost gable forms entry porch overhang and is supported by wood posts. Vertical slatting adorns uppermost portion of gable face. Since the 1982 survey, this structure has been severely altered by inappropriate aluminum windows and stucco siding.

National Register of Historic Places Continuation Sheet

Section number _____7 Page _____92 Old Towne Orange Historic District, Orange, CA

413. **528 W. Culver** 1925 Bungalow Historical Name: AP Number: 041-142-27 Small bungalow home with single-gable roof and clapboard siding. Smaller gabled portico forms entry and is supported by wood posts.

414. 539 W. Culver 1928 Provincial Revival Historical Name: AP Number: 041-134-09 A single-story stucco rectangular plan provincial revival residnece sith mult-gabled chingled roof. Entry contains multi-arched portico. Large arched, mullioned window on front facade. Large matching arched windows also exist on west facing facade.

415. **552 W. Culver** 1984 Historical Name: AP Number: 390-131-77 Non-Contributor

416. **603 W. Culver** 1923 Craftsman Bungalow Historical Name: AP Number: 041-133-16 Bungalow home with double, front-facing gables and clapboard siding on facades below. Frontmost gable forms entry porch overhang and is adorned with dentils in upper gable face. Since the 1982 survey, this structure has been altered with inappropriate stucco siding.

417. **611 W. Culver** 1925 Mediterranean Revival Historical Name: AP Number: 041-133-15 Small, low-to-the-ground, Mediterranean Revival bungalow with flat roof and stucco siding. Interesting character to this house is derived from the wall extensions both at the roof and on the sides. Double arched porte cochere forms driveway entry. Low wall screens stoop which forms main entry to house. Awnings span full width of front facade.

National Register of Historic Places Continuation Sheet

Section number _____7 Page _____93 Old Towne Orange Historic District, Orange, CA

418. 618 W. Culver
1924 California Bungalow
Historical Name:
AP Number: 041-141-26
Double-gable, clapboard bungalow with smaller gable symmetrically placed at
center of front facade and forming entry porch overhang. This gabled portico
is supported by tapered piers. Entry is beneath at center.

419. **619 W. Culver** 1924 Spanish Colonial Revival Historical Name: AP Number: 041-133-14 Flat roof, stucco sided, L-plan Spanish Colonial Revival bungalow. Special arched entry is located in apex of ell. Roof of this entry porch is tiled.

420. **629 W. Culver** 1926 Provincial Revival Historical Name: AP Number: 041-133-13 A single-story provincial revival stucco box residuece with simple gable over front entry.

421. **631 W. Culver** 1946 Historical Name: AP Number: 041-133-12 Non-Contributor

422. **643 W. Culver** 1924 Mediterranean Revival Historical Name: AP Number: 041-133-11 Flat roof with adobe tiled ridges, stucco facades on rectangular plan. Entry is at center and flanked by picture windows on either side. What appears to be a slightly later gabled porch overhang is located across front facade.

National Register of Historic Places Continuation Sheet

Section number _____7 Page _____94 Old Towne Orange Historic District, Orange, CA

423. **703 W. Culver** 1930 Spanish Colonial Revival Historical Name: AP Number: 041-132-13 U-plan Spanish Colonial Revival bungalow with front-facing gables on either end of front. Roof is of adobe tiles while siding is in stucco. Large arched, picture window adorns front of larger gable face. Entry is in center of U.

424. **711 W. Culver** 1928 Gable Roof Cottage Historical Name: AP Number: 041-132-12 Small, simple box with single-gable roof and clapboard siding. Entry is at center.

425. **719 W. Culver** 1926 California Bungalow Historical Name: AP Number: 041-132-11 Multi-gable bungalow with clapboard siding. Front-facing gable forms entry porch overhang and is supported by round columns. Entry is at center beneath.

426. **720 W. Culver** 1926 Historical Name: AP Number: 390-131-15 Non-Contributor

427. **727 W. Culver** 1924 Spanish Colonial Revival Historical Name: AP Number: 041-132-10 Multi-gable roof, stucco siding, large arched windows and arched opening to entry.

428. **737 W. Culver** 1923 Bungalow Historical Name: AP Number: 041-132-09 Non-Contributor. Since the 1982 survey, this structure has been replaced with a non-compatible duplex.

National Register of Historic Places Continuation Sheet

Section number _____7 Page _____95 Old Towne Orange Historic District, Orange, CA

429. **743 W. Culver** 1929 Provincial Revival Historical Name: AP Number: 041-132-08 Multi-gable roof with steep pitch and rolled eaves. Stucco siding. Main entry has separate, smaller gabled overhang. Since the 1982 survey, this structure has been altered with inappropriate window replacements.

430. **123 N. Cypress** 1965 Historical Name: AP Number: 039-172-09 Non-Contributor

431. **129 N. Cypress** 1965 Historical Name: AP Number: 039-172-08 Non-Contributor

432. **136 N. Cypress** 1941 Historical Name: AP Number: 039-171-03 Non-Contributor

433. **142 N. Cypress** 1937 Brick Commercial Historical Name:

AP Number: 039-171-05 A brick commercial building with low-pitched roof and wooden facade on a rectangular plan. No windows are present. A industrial wooden sliding door is present on each end of the building.

434. **143 N. Cypress** 1952 Historical Name: AP Number: 039-172-07 Non-Contributor

National Register of Historic Places Continuation Sheet

Section number _____7 Page _____96 Old Towne Orange Historic District, Orange, CA

435. 153 N. Cypress
1923 Brick Commercial
Historical Name:
AP Number: 039-172-06
A large warehouse style brick commercial building on a rectangular plan.
Large industrial sliding doors in center of building are flanked by streetlevel double-hung single-paned wooden windows.

436. **158 N. Cypress** 1971 Historical Name: AP Number: 039-171-11 Non-Contributor

437. **159 N. Cypress** 1923 Historical Name: AP Number: 039-172-05 Non-Contributor

438. **171 N. Cypress** c1905 Hip Roof Cottage Historical Name:

AP Number: 039-172-04 A single-story house with box plan and truncated hip roof. The original siding has since been covered with asbestos shingles. A full-width front porch extends across the front facade and is supported by wood posts. Entry is at center and is flanked on either side by a sash window. Since the 1982 survey, this structure has deteriorated.

439. 177 N. Cypress c1905 Hip Roof Cottage Historical Name: AP Number: 039-172-03 A single-story box plan house with clapboard siding and truncated hip roof. The house has a nearly full-width front porch supported by 2 x 4's. This house has the same symmetrical and simple appearance as others on this block. Since the 1982 survey, this structure has deteriorated.

National Register of Historic Places Continuation Sheet

Section number _____7 Page _____97 Old Towne Orange Historic District, Orange, CA

440. **185 N. Cypress** c1905 Hip Roof Cottage. Historical Name: AP Number: 039-172-02 This house is identical to the one next door at 177 N. Cypress. A singlestory box plan house with clapboard siding and truncated hip roof. The house has a nearly full-width front porch supported by 2 x 4's. This house has the same symmetrical and simple appearance as others on this block. Since the 1982 survey, an inappropriate addition has been added, and the house has deteriorated.

441. **190 N. Cypress** 1967 Historical Name: AP Number: 039-171-09 Non-Contributor

442. **191 N. Cypress** c1900 Vernacular Settlement House Historical Name: AP Number: 039-172-01 Vacant Lot

443. 200 N. Cypress 1924 Industrial Historical Name: AP Number: 390-651-01 This building complex consists of a full block on both sides which have always been put to industrial use. The building complex is one-story with brick facade. The roofline is alternately flat and domed, but always screened by a raised parapet. The building is built up to the sidewalk.

brick facade. The roofline is alternately flat and domed, but always screened by a raised parapet. The building is built up to the sidewalk. Large multi-paned windows are spaced across the facades. A small row of accent brick highlights the cornice. The building is simple and unadorned.

444. **321 N. Cypress** 1978 Historical Name: AP Number: 039-151-09 Non-Contributor

National Register of Historic Places Continuation Sheet

Section number _____7 Page _____98 Old Towne Orange Historic District, Orange, CA

445. **337 N. Cypress** 1917 Historical Name: AP Number: 039-151-08 Non-Contributor

446. **343 N. Cypress** c1895 Victorian Cottage Historical Name: AP Number: 039-151-07

A single-story house built on an L-plan with shiplap siding and steep-pitched gabled roof. There is a double entry in the apex of the ell which also forms the entry porch and is covered by a separate shed roof overhang supported by 2×4 's. The high, narrow, double hung windows and centrally located chimney indicate the house was built prior to 1900.

447. 350 N. Cypress

1933 Industrial Historical Name: AP Number: 039-150-01 This is the Villa Park Orchard's Association Packing House which was originally the Santiago Orange Grower's Association Packing House. The original portion of the packing house built in 1919 is still present on the site but is much obscured by the more recent building. The building is still in use as a packing house today. It is constructed in a warehouse style and has been adapted to the needs of the building owners. It's a simple boxy building with a flat roof and stucco facades.

448. 353 N. Cypress

c1920 Bungalow Historical Name: AP Number: 039-151-06 Non-Contributor. Since the 1982 survey, this structure has replaced with a auto body repair shop industrial-type building.

449. 365 N. Cypress

c1920 Gable Roof Cottage Historical Name: AP Number: 039-151-05 Non-Contributor. A single-story box plan house with clapboard siding and single-gabled roof. Entry is sheltered by its own separate, simple portico. Since the 1982 survey, this structure has been severely altered by stucco and aluminum windows.

National Register of Historic Places Continuation Sheet

Section number _____7 Page _____99 Old Towne Orange Historic District, Orange, CA

450. **373 N. Cypress** c1920 Bungalow Historical Name: AP Number: 039-151-04 A single-story clapboard bungalow with L-plan and multi-gable roof. The house is simple and unadorned. Since the 1982 survey, this structure has been altered with inappropriate windows.

451. 379 N. Cypress

c1920 Bungalow Historical Name: AP Number: 039-151-03 A small, single-story clapboard bungalow with shallow-pitched multi-gable roof with vertical slats in the gable vent. The house is built on the symmetrical plan with a centrally located, front-facing gable forming the entry porch. Double-entry indicates the house was intended for duplex usage. Since the 1982 survey, this structure has been altered with an inappropriate porch enclosure.

452. **383 N. Cypress** 1966 Historical Name: AP Number: 039-151-02 Non-Contributor

453. **393 N. Cypress** 1987 Historical Name: AP Number: 039-151-29 Non-Contributor

454. **405 N. Cypress** Historical Name: AP Number: 039-142-12 Non-Contributor

455. **413 N. Cypress** 1919 Vernacular Historical Name: AP Number: 039-142-11 This is a simple, small and probably hand-constructed house. It is built of board and batten with a single gabled roof which extends forward to form a nearly full-width porch overhang.

National Register of Historic Places Continuation Sheet

Section number _____7 Page _____100___

Old Towne Orange Historic District, Orange, CA

456. 417 N. Cypress

1919 Gable Roof Cottage Historical Name: AP Number: 039-142-10 A single-story bungalow with single front-facing gabled roof. A full-width porch is formed by a separate roof extension and is supported by 2 x 4's. The original siding has since been covered with asbestos shingles. Double doors indicate that the house was originally intended for duplex usage.

457. **421 N. Cypress** 1923 Historical Name: AP Number: 039-142-09 Non-Contributor

458. **435 N. Cypress** 1920 Historical Name: AP Number: 039-142-08 Non-Contributor

459. 445 N. Cypress

1920 Bungalow Historical Name: AP Number: 039-142-07 This is a single-story clapboard bungalow built on an L-plan with multigabled roof. Entry is near the apex of the ell and the main roof extends forward at this point to form the entry porch overhang. It is supported by simple 2 x 4's with a connecting slatted balustrade.

460. **455 N. Cypress** 1922 Historical Name: AP Number: 039-142-06 Non-Contributor

461. 465 N. Cypress
1913 Bungalow
Historical Name:
AP Number: 039-142-05
A small, box plan house with single-gabled roof. The main roof extends
forward to form a full-width porch overhang which is supported by 2 x 4's.
The house is very simple and very basic.

United States Department of the Interior National Park Service

National Register of Historic Places Continuation Sheet

Section number _____7 Page _____101

Old Towne Orange Historic District, Orange, CA

462. **469 N. Cypress** 1904 Historical Name: AP Number: 039-142-04 Non-Contributor

463. **481 N. Cypress** 1981 Historical Name: AP Number: 039-142-03 Non-Contributor

464. **491 N. Cypress** Historical Name: AP Number: 039-142-02 Non-Contributor

465. **125 S. Cypress** 1979 Historical Name: AP Number: 390-662-02 Non-Contributor

466. **128 S. Cypress** c1909 Industrial

Historical Name: Red Fox Orchards AP Number: 390-661-02 This former packing house is a most pragmatic industrial building exhibiting no particular style. The long, boxy structure has a flat roof and shiplap siding. The building follows the contour of the railroad tracks on the west side and even has its own spur line which connects with the loading docks of the packing house. The main street-facing facade has a stepped parapet with a remnant of the old sign, "Sunkist Consolidated Orange Growers. The building is in a deteriorated state and unused at this time. Since the 1982 survey, this structure has been altered with appropriate conversions to accomodate contemporary use.

467. **135 S. Cypress** 1979 Historical Name: AP Number: 390-662-03 Non-Contributor

National Register of Historic Places Continuation Sheet

Section number _____7 Page _____102

Old Towne Orange Historic District, Orange, CA

468. 145 S. Cypress

c1910 Hip Roof Cottage Historical Name: AP Number: 390-662-04 Box plan house with pyramidal roof and facades now covered by asbestos shingles. Separate pedimented gable forms entry portico and is supported by slender columns typical of the Classical Revival homes. Decorative shingles on the gabled portico and broad eaves with decorative brackets further distinguish the house.

469. 153 S. Cypress c1910 Hip Roof Cottage Historical Name: AP Number: 390-662-05 Steep pitched, gable roof, shiplap siding and front-facing gable form the entry porch overhang. This gable is supported by Classical Revival columns. Windows are framed typical of the period. Since the 1982 survey, this structure has undergone restoration.

470. 154 S. Cypress

1889 Victorian Historical Name: AP Number: 390-661-03 Non-Contributor. Since the 1982 survey, this structure has been replaced with a auto detail shop. The building contains some victorian style features.

471. 160 S. Cypress
1930 Industrial
Historical Name:
AP Number: 390-661-04
A conrete structure supported by metal piers and roofed with metal material.

National Register of Historic Places Continuation Sheet

Section number _____7 Page _____103

Old Towne Orange Historic District, Orange, CA

472. 163 S. Cypress

1889 Victorian w/Eastlake Influence Historical Name: Parker House AP Number: 390-662-06

This is a large, two-story Victorian house with the typical Victorian massing and detailing. Though simpler than the Victorians located in more urban areas, this is quite detailed for a rural Victorian which was once surrounded by some farmland. The two-story house has shiplap siding and a combined gable and mansard roof. A larger wrap-around porch is supported by ornate turned columns. Each of the upper gable faces and the gabled dormer in front are embellished with jigsawn bargeboard with an inner arch and a drop spindle as well as combined fish-scale and saw-toothed shingling. Wide eaves are embellished with ornamental brackets like those on each of the window hoods. The house is in good condition, though in need of painting, and retains its original architectural integrity to an excellent degree. This residence was added to the National Register of Historic Places in 1989. Since the 1982 survey, this structure has undergone major restoration.

473. 173 S. Cypress

c1915 Craftsman Bungalow Historical Name: AP Number: 390-662-07 Single, front-facing gable roof with lap siding on facades. A porch spans full width of front of house beneath main roof extension. Entry is at center with large picture windows flanked on either side.

474. **180 S. Cypress** 1948 Historical Name: AP Number: 390-661-05 Non-Contributor

475. 191 S. Cypress

c1920 Craftsman Bungalow Historical Name:

AP Number: 390-662-08

Double, front-facing gables above an L-plan house. Lap siding is used on all facades. Entry is beneath a separate porch overhang in apex of ell. Ornamental cross-ties and purlins adorn upper gable faces. Frontmost gable has a large, three-part picture window. Since the 1982 survey, this structure has been altered with inappropriate, two story second unit in the rear.

The

These

United States Department of the Interior National Park Service

National Register of Historic Places **Continuation** Sheet

Section number 7 Page 104

Old Towne Orange Historic District, Orange, CA

476. 193 S. Cypress

1921 Vernacular Historical Name: AP Number: 390-662-09 This is a small, single-story clapboard church with a single gable roof. corner entry is articulated by a rectilinear entry tower with a pyramidal roof. Casement windows around thebuilding are arranged in pairs, and each is crowned with a large, stained glass transom. These arched windows are repeated in the entry tower. Triangular bracket supports are located beneath the eaves on the front gable face. The church was built adjacent to a small, Classical Revival style house which still forms part of the church. two are connected in such a way that together they appear as one building. The church shows slight Craftsman influence but is more a vernacular adaptation, incorporating structural and economic pragmatics.

The arched windows and entry tower are characteristic of small rural churches. The building is well-maintained and exhibits its original architectural integrity.

477. 200 S. Cypress

1924 Industrial Historical Name: AP Number: 390-651-01 A single-story industrial building with a flat roof and facades built to the lot line. Brick is used along the lower foundation wall and in the pilasters; plaster is used above. Entry is defined by a double door (not original) with side lights. Brick pilasters are on either side with a large arched connecting transom.

478. 209 S. Cypress 1972 Historical Name: AP Number: 390-652-01 Non-Contributor

479. 219 S. Cypress 1973 Historical Name: AP Number: 390-652-02 Non-Contributor

National Register of Historic Places Continuation Sheet

Section number _____7 Page _____105___

Old Towne Orange Historic District, Orange, CA

480. **225 S. Cypress** 1932 Historical Name: AP Number: 390-652-03 Non-Contributor

481. **235 S. Cypress** 1951 Historical Name: AP Number: 390-652-04 Non-Contributor

482. **243 S. Cypress** c1905 Hip Roof Cottage Historical Name: AP Number: 390-652-05 A single-story, box plan house with clapboard siding and steep-pitched, hip roof. Entry is via a recessed corner porch supported by a Classical column.

483. 246 S. Cypress
1923 Mediterranean Revival
Historical Name:
AP Number: 390-651-02
A boxy house with flat roof and flush stucco sides. Entry is at corner
recessed beneath main portion of house. Paired, double-hung windows are
located across front and sides.

484. 255 S. Cypress 1923 California Bungalow Historical Name: AP Number: 390-652-06 A irregular plan bungalow residence with multi-gables and clapboard siding. The entry is formed by a suspended gable with ornamental brackets. The front door is flanked by 2 sets of paired multi-mullioned (10-light) windows. A similar set windows is present on the facade of a front facing gable. Brick piers and a brick chimney are present.

National Register of Historic Places Continuation Sheet

Section number _____7 Page _____106

Old Towne Orange Historic District, Orange, CA

485. 263 S. Cypress 1923 Craftsman Bungalow Historical Name: AP Number: 390-652-07 Low to the ground, single-story bungalow with very shallow pitched roof. Main portion of house is covered by side-facing gable, while a smaller, front-facing gable extension forms entry porch overhang. This overhang is supported by wide tapered columns. Entry is beneath and flanked on either side by large transomed, picture windows. Vertical slatting adorns front gable entry. 486. 273 S. Cypress 1959 Historical Name: AP Number: 390-652-08 Non-Contributor 487. 280 S. Cypress 1946 Historical Name: AP Number: 390-651-09 Non-Contributor 488. 294 S. Cypress 1926 Spanish Colonial Revival Historical Name: AP Number: 390-651-10 Small bungalow-scale house, but multi-faceted due to varying elevations and extensions. Main roof is flat with parapet with tiled ridges. A gable extension and smaller, rectangular porch extension is dressed with arched openings. Both have tiled roofs. 489. 106 N. Glassell 1913 Brick Commercial Historical Name: D. F. Campbell Building or Campbell's Opera House AP Number: 039-174-13 See National Register Plaza Historic District list.

490. **107 N. Glassell** Brick Commercial Historical Name: AP Number: 039-251-30 See National Register Plaza Historic District list.

National Register of Historic Places Continuation Sheet

Section number _____7 Page _____107___

Old Towne Orange Historic District, Orange, CA

491. **114 N. Glassell** 1899 Brick Commercial Historical Name: AP Number: 039-174-14 Non-Contributor. Original facade has been extensively remodeled. Also refer to National Register Plaza Historic District list.

492. **122 N. Glassell** 1952 Brick Commercial Historical Name: AP Number: 039-174-06 Non-Contributor. Original facade has been extensively remodeled. Also refer to National Register Plaza Historic District list.

493. **123 N. Glassell** 1905 Brick Commercial Historical Name: N.T. Edward's Block AP Number: 039-251-06 Non-Contributor. See National Register Plaza Historic District list.

494. **124 N. Glassell** 1952 Brick Commercial Historical Name: AP Number: 039-174-15 Non-Contributor. See National Register Plaza Historic District list.

495. **131 N. Glassell** 1916 Brick Commercial Historical Name: Kogler Hardware Building AP Number: 039-251-29 See National Register Plaza Historic District list.

496. **138 N. Glassell** 1931 Historical Name: AP Number: 039-174-24 Non-Contributing. Facade has been extensively remodeled. Also refer to National Register Plaza Historic District list.

National Register of Historic Places Continuation Sheet

Section number 7 Page 108

Old Towne Orange Historic District, Orange, CA

497. 149 N. Glassell 1919 Brick Commercial Historical Name: AP Number: 039-251-25 Non-Contributor. The current building appears to be newer and out of character with the District. Also refer to National Register Plaza Historic District list. 498. 153 N. Glassell 1915 Brick Commercial Historical Name: AP Number: 039-251-26 Non-Contributing. The facade has been extensively remodeled. Also refer to National Register Plaza Historic District list. 499. 154 N. Glassell 1914 Brick Commercial Historical Name: Santa Ana Valley Irrigation Company Building AP Number: 039-174-02 See National Register Plaza Historic District list. 500. 161 N. Glassell 1922 Brick Commercial Historical Name: M. Eltistie Building AP Number: 039-251-27 See National Register Plaza Historic District list. 501. 162 N. Glassell 1925 Brick Commercial Historical Name: AP Number: 039-174-17 See National Register Plaza Historic District list. 502. 172 N. Glassell 1925 Concrete Theater Historical Name: Orange or Pantages Theater AP Number: 039-174-18 See National Register Plaza Historic District list.

National Register of Historic Places Continuation Sheet

Section number _____7 Page _____109

Old Towne Orange Historic District, Orange, CA

503. **177 N. Glassell** 1912 Brick Commercial Historical Name: Eltistie Addition AP Number: 039-251-24 See National Register Plaza Historic District list.

504. 201 N. Glassell 1982 Historical Name: AP Number: 039-241-23 Non-Contributor

505. 202 N. Glassell 1953 Historical Name: AP Number: 039-163-11 Non-Contributor

506. 205 N. Glassell

1921 Period Apartment Building Historical Name: AP Number: 039-241-10 This is a two-tiered apartment building outfitted with a flat roof and wide lap siding on the facades. This building has a boxy format and is simple and unadorned.

507. 224 N. Glassell

1905 Altered Victorian Historical Name: AP Number: 039-163-12 This is a two-story clapboard house with steep-pitched, gable roof including two large, front-facing gables with a return at their eaves. Entry is via a corner recessed porch now supported by wood posts but which probably originally had Classical column supports. Windows are framed in the Period manner, and the larger of the two front-facing gables features ornamental exposed beams and a small ornamental vent.

National Register of Historic Places Continuation Sheet

Section number 7 Page 110

Old Towne Orange Historic District, Orange, CA

508. 229 N. Glassell

1915 Craftsman Bungalow Historical Name:

AP Number: 039-241-09

A single-story bungalow with wide lap siding and double, front-facing gable roof. The forwardmost gable forms the entry porch overhang and is supported by tapered piers. Each of the upper gable faces is distinguished by ornamental purlins, cross-ties and a vented transom. The original door is still present and features four vertical panes.

509. 234 N. Glassell

c1910 Hip Roof Cottage Historical Name: AP Number: 039-163-13 This is a single-story 1

This is a single-story house with modified L-plan and steep-pitched hip roof. The short leg of the ell results in a small, front-facing gable projection which features a large, three-part with diamond pane header, window. The main roof extends forward on one side to form a large, wrap-around corner porch. This porch is supported by Classical columns. The original door is still present and features a single paned window with dentils.

510. 237 N. Glassell

c1920 Bungalow Historical Name: AP Number: 039-241-08 A single-story bungalow with wide lap siding and steep-pitched, multi-gable roof. Entry is via a recessed portico articulated with Classical pilasters. A brick chimney rises up the front face of the house.

511. 244 N. Glassell 1906 Hip Roof Cottage Historical Name: AP Number: 039-163-14

A single-story box plan house with clapboard siding and steep-pitched hip roof. A small gable attic dormer is present and features a palladian transom. Entry is via a corner recessed porch supported by wood posts.

512. **245 N. Glassell** 1938 Historical Name: AP Number: 039-241-07 Non-Contributor

National Register of Historic Places Continuation Sheet

Section number _____7 Page _____111

Old Towne Orange Historic District, Orange, CA

513. **253 N. Glassell** 1927 Historical Name: AP Number: 039-241-06 Non-Contributor

514. **260 N. Glassell** c1920 Bungalow Historical Name:

AP Number: 039-163-15 A single-story bungalow with wide lap siding and multi-gable roof. Frontfacing gable extends forward to form a half-entry porch and is supported by an ornamental turned post which is probably a replacement of the original. The original entry door is still present and features four plate glass windows.

515. **261 N. Glassell** c1905 Classic Box Historical Name: AP Number: 039-241-05 This is a large, two-story house which was originally built in the Classical Revival style but has been altered through the addition of a storefront on the lower level. As was typical of the house of this period, this one originally featured a box plan with steep-pitched, hip roof and small, hip dormer. The house has wide lap siding. A recessed corner porch probably was present originally but was removed when the storefront addition was made. Since the 1982 survey, the inappropriate storefront addition has been improved.

516. **264 N. Glassell** 1910 Historical Name: AP Number: 039-163-16 Non-Contributor

National Register of Historic Places Continuation Sheet

Section number 7 Page 112

Old Towne Orange Historic District, Orange, CA

517. **269 N. Glassell** 1905 Hip Roof Cottage Historical Name: AP Number: 039-241-04 A single-story clapboard house with steep-pitched, hip and gable roof. The house is built in a modified L-plan with the short leg of the ell resulting in a front-facing gable with a modified palladian transom. The remaining half of the house is devoted to a large circular, wrap-around porch supported by Classical columns. The original door with plate glass window is still present. Accompanying this door on the side is a large, three-part window with transom.

518. 274 N. Glassell

1913 Craftsman Historical Name: AP Number: 039-163-17

This is a large, two-story Craftsman house with single, side-facing gable roof and combination shingle and lap siding. A large, front-facing gable dormer is present and features a balcony with slatted balustrade and a recessed entry comprised of an ornamental door with diamond pane side vents on either side. The main roof extends forward to form a full-width porch which is supported by tapered piers atop an arroyo stone porch wall. Large picture windows with transoms flank either side of the main entry. Since the 1982 survey, this structure has undergone restoration and has been altered with appropriate balcony remodel.

519. 277 N. Glassell

1905 Hip Roof Cottage Historical Name: AP Number: 039-241-05

This is a single-story clapboard structure with hip roof and double front entry. The right entry is immediatedly via a stoop. On the left side is a small hip dormer with shingle siding and ornamental exposed rafter tails. On the left side is a cut-away porch supported by Classical columns. The original door is still in place and features a single plate glass window flanked on either side by narrow sash windows. This is complemented by a three-part window to the side. All are ornamentally framed.

National Register of Historic Places Continuation Sheet

Section number 7 Page 113

Old Towne Orange Historic District, Orange, CA

520. 284 N. Glassell

1921 Dutch Colonial Revival

Historical Name: AP Number: 039-163-18

This is a large, two-story house with a gambrel roof fashioned after the Dutch tradition. The entry is articulated by a large pedimented portico supported by Classical columns. The original door is still in place and flanked on either side by mullioned side lites. Two large, picture windows with transoms adorn the lower half of the front facade. Groupings of sash windows with eight-over-one pane arrangements adorn the upper facade.

521. 285 N. Glassell

c1910 Bungalow Historical Name: AP Number: 039-241-03 A single-story bungalow with steep-pitched, hip and gabled roof with wide lap siding. The house combines elements of both the Classical Revival and the Bungalow styles. The house is built in a modified L fashion with the short leg of the ell resulting in a small, pedimented gable dormer with sawtooth shingles and a louvered vent.

522. 287 N. Glassell

1910 Bungalow Historical Name: AP Number: 039-241-02 Non-Contributor

523. **291 N. Glassell** 1912 Bungalow Historical Name: AP Number: 039-241-01 A single-story house with wide lap siding and multi-gable roof with wide overhangs and knee braces. The front porch is enclosed with ribbon windows.

524. 304 N. Glassell

1909 Craftsman Historical Name: AP Number: 039-153-07 This is a two-story Craftsman house with single, side-facing gable roof and wide lap siding. A large, front-facing gable dormer with ornamental purlins is present also. One-half of the front facade is devoted to a recessed porch which is supported by wood posts. Large, three-part windows are present on the lower story of the front facade.

National Register of Historic Places **Continuation** Sheet

Section number _____7 Page _____114__

Old Towne Orange Historic District, Orange, CA

525. 312 N. Glassell 1915 Altered Craftsman Historical Name: AP Number: 039-153-08 This is a classic, single-story Orange bungalow but has been significantly modified on the front of the property through the addition of a boxy stucco storefront. The original lap siding, gable roof, windows and door are still present on the sides and rear of the house.

526. 320 N. Glassell 1917 Craftsman Historical Name: AP Number: 039-153-09 A one and one-half story house with clapboard siding and single, side-facing gable roof. A large, front-facing gable dormer is present, ornamented with

purlins and an ornamental transom window. What was originally a full-width porch was later enclosed, but the original porch piers with brick bases are still present. Since the 1982 survey, this structure has been altered with appropriate partial front porch restoration.

527. 328 N. Glassell 1914 Craftsman Historical Name: AP Number: 039-153-10 A single-story box plan bungalow with single, front-facing gable roof with wide eave overhangs and knee braces. One-half of the front facade is devoted to a recessed porch supported by a slender wood pier. The house is simple and unadorned. Since the 1982 survey, this structure has been altered with inappropriate porch remodeling.

National Register of Historic Places Continuation Sheet

Section number 7 Page 115

Old Towne Orange Historic District, Orange, CA

528. 333 N. Glassell

1922, 1923, 1928 Neo-Classicism Historical Name: Orange Union High School (3 separate buildings) AP Number: 039-230-02

Now occupied by Chapman University, three original neo-classicism buildings stand symetrically arranged as the former Orange Union High School. They are the central 1922 Wilkenson Hall which is a monumental proportioned building finished in a smooth concrete surface with front facade of four smooth shaft columns with unadorned capitals, smooth parapet, decorative cornice, facia, and crown moldings and decorative window treatments. This building is flanked by the 1923 Memorial Auditorium, and the 1928 Founders Hall which are mirror images of each other and display similar neo-classicism features without the special front entry portico window treatment but with a colossal pedimented porticos which highlight the facade flanked by a single smooth shafted pilaster. Windows are more modest but large 6-light sashes. The building exteriors appear to be in excellent condition. These buildings were placed on the National Register of Historic Places in 1975.

529. 338 N. Glassell

c1920 Bungalow Historical Name: AP Number: 039-153-11 A single-story clapboard bungalow with multi-gable roof. The front-facing gable which extends forward originally formed the porch overhang but was later enclosed. The original tapered piers on cast masonry bases are still present.

530. 344 N. Glassell

c1910 Hip Roof Cottage Historical Name: AP Number: 039-153-12 A single-story clapboard house with box plan and steep-pitched, hip roof. A small gable dormer is also present on the front portion of the roof and features a small slatted balustrade balcony. The main roof extends forward in an attached fashion to form a nearly full-width porch which is supported by Classical columns.

National Register of Historic Places Continuation Sheet

Section number _____7 Page _____116__

Old Towne Orange Historic District, Orange, CA

531. 370 N. Glassell

c1910 Mediterranean Revival Historical Name: Central Grammar School AP Number: 039-150-02

This large, two-story building was originally a school and served as the Orange Unified School District office. The building was constructed in a Mediterranean Revival style with strong Renaissance influences in a monumental fashion common to institutional buildings of the period. The building is on a rectilinear plan with an adobe tile roof and stucco facades. The central entry is the architectural focal point and includes a large, front-facing gable, wall flanked on either side by modified towers with hip The lower portion of the entry features two large pilasters on the roofs. outside and six smaller pilasters on the interior; these and the wall above are embellished in an ornamental arrangement of brick. The upper portion of the entry wing includes six Roman arched windows with brick framing. The cornice of this entry gable includes a brick embellishment of small arches. The building is in excellent condition and retains its original architectural appearance. It was added to the National Register of Historic Places in 1992.

532. **402 N. Glassell** 1920 Historical Name: AP Number: 039-144-13 Non-Contributor

533. **410 N. Glassell** c1920 California Bungalow Historical Name: AP Number: 039-144-14

Non-Contributor. A single-story bungalow with multi-gable roof and wide lap siding. Most of the house is covered by a single-gable roof with sidefacing, clipped gables. Two parallel, front-facing gable dormers, each with clipped gables, adorn the upper front portion of the roof and define the main entry which is below. This entry is recessed and distinguished by the original wood door with mullioned side lites. Since the 1982 survey, this structure has been severely altered by remodeling for office use, the door eliminated and windows changed.

National Register of Historic Places Continuation Sheet

Section number _____7 Page _____117__

Old Towne Orange Historic District, Orange, CA

534. **418 N. Glassell** 1929 Provincial Revival Historical Name: AP Number: 039-144-15 A provincial revival residence on a regatular plan with lintel-type window openings with six-pane wood windows. Exterior brick chimney features dual chimney pots. Roof consists of simulated thatch. Entry is gabled with wooden diagonal braces over stucco.

535. **428 N. Glassell**

1907 Hip Roof Cottage Historical Name: AP Number: 039-144-16

Non-Contributor. A single-story, box plan house with clapboard siding and steep-pitched, hip roof. A small, gable dormer with a keystone transom is present on the front portion of the roof. What was originally a corner recessed porch has since been screened in, but the original Classical columns are still present. It looks as though the porch was enclosed early, given the presence of the older style screen door. Since the 1982 survey, this structure has been severely altered by remodeling for office use--all fenestrations changed.

536. 434 N. Glassell

1902 Hip Roof Cottage Historical Name: AP Number: 039-144-17

A single-story, box plan house with steep-pitched, hip roof. What was originally clapboard siding has since been stuccoed. At the same time, modifications were made to the recessed porch which would have originally been supported by Classical columns but is now characterized by a large, arched opening. Despite the porch modifications and stuccoing, everything else about the house retains the original design.

537. 446 N. Glassell

1902 Hip Roof Cottage Historical Name: AP Number: 039-144-18

A hip roof cottage (Richardson Romanesque Revival) with distincitve flared roof eaves on a box plan. Diamond-paned transomed windows are scattered in a leanear pattern with a large single-paned bay window topped with similar diamond shaped windows present on the fornt facade. A multi-arched porch is present with rounded corners. Decorative molded fascia boards are also featured.

National Register of Historic Places Continuation Sheet

Section number 7 Page 118

Old Towne Orange Historic District, Orange, CA

538. 452 N. Glassell 1903 Hip Roof Cottage Historical Name: AP Number: 039-144-19 A single-story, box plan house with steep-pitched, hip roof and a sloping roofline which results in exceptionally wide eaves. A petite gable dormer is present on the front portion of the roof. Entry is via a corner recessed porch supported by Classical columns. The remaining front half of the facade is defined by an angled bay window of which each plane has its own window pane. 539. 462 N. Glassell 1918 Craftsman Bungalow Historical Name: AP Number: 039-144-20 This is a single-story bungalow with multi-gable roof and siding which is now covered by asbestos shingles. The roof is fashioned in an L-plan with the short leg resulting in a projecting, front-facing gable extension which acts as the entry porch overhang. This is supported by tapered piers on brick bases. The original wood door with plate glass windows is still present. It is flanked on either side by large picture windows with beveled glass transoms. 540. 470 N. Glassell 1978 Historical Name: AP Number: 039-144-21 Non-Contributor 541. 480 N. Glassell 1969 Historical Name: AP Number: 039-144-31 Non-Contributor 542. 108 S. Glassell 1905 Brick Commercial Historical Name: Ehlen and Grote Building AP Number: 390-664-11 See National Register Plaza Historic District list.

National Register of Historic Places Continuation Sheet

Section number 7 Page 119

Old Towne Orange Historic District, Orange, CA

543. **109 S. Glassell** 1910 Brick Commercial Historical Name: AP Number: 390-381-02 See National Register Plaza Historic District list.

544. **110 S. Glassell** 1909 Brick Commercial Historical Name: AP Number: 390-664-10 See National Register Plaza Historic District list.

545. **119 S. Glassell** Brick Commercial Historical Name: AP Number: 390-381-03 See National Register Plaza Historic District list.

546. **121 S. Glassell** Historical Name: AP Number: 390-381-05 Non-Contributor. See National Register Plaza Historic District list.

547. **131 S. Glassell** 1906 Brick Commercial Historical Name: Gunther Building AP Number: 390-381-06 Non-Contributor. A new building and addition was added and partially surrounds original building. The total facade change is out of character with the District. Also refer to National Register Plaza Historic District list.

548. **135 S. Glassell** 1924 Historical Name: AP Number: 390-381-07 Non-Contributor. See National Register Plaza Historic District list.

National Register of Historic Places Continuation Sheet

Section number 7 Page 120

AP Number: 390-381-11

See National Register Plaza Historic District list.

Old Towne Orange Historic District, Orange, CA

549. 141 S. Glassell 1923 Brick Commercial Historical Name: Boring Block Addition AP Number: 390-381-08 Non-Contributor. Also refer to National Register Plaza Historic District list. 550. 142 S. Glassell 1914 Brick Commercial Historical Name: Mr. Dobner Building AP Number: 390-664-09 See National Register Plaza Historic District list. 551. 144 S. Glassell 1926 Brick Commercial Historical Name: AP Number: 390-664-08 See National Register Plaza Historic District list. 552. 155 S. Glassell 1910 Brick Commercial Historical Name: J. P. Boring Block AP Number: 390-381-09 Non-Contributor. Also refer to National Register Plaza Historic District list. 553. 178 S. Glassell Historical Name: AP Number: 390-664-07 See National Register Plaza Historic District list. 554. 185 S. Glassell 1922 Brick Commercial Historical Name: AP Number: 390-381-10 See National Register Plaza Historic District list. 555. 195 S. Glassell 1923 Historical Name: Orange County Fruit Exchange or Sunkist Building

National Register of Historic Places Continuation Sheet

Section number _____7 Page _____121__

Old Towne Orange Historic District, Orange, CA

556. **205 S. Glassell** 1905 Hip Roof Cottage Historical Name: AP Number: 390-391-01 A A classic hip roof box plan cottage with wood-shingled siding and doublehung windows. Three such windows ornament the front facade. A canopied kneebrace is present over the front door.

557. **210 S. Glassell** 1973 Historical Name: AP Number: 390-654-19 Non-Contributor

558. 221 S. Glassell

1903 Victorian Historical Name: AP Number: 390-391-02 This is a two-story, turn-of-the-century house in the style sometimes known as Princess Anne. The Princess Anne style is a derivative of the larger

as Princess Anne. The Princess Anne style is a derivative of the larger Queen Anne style but incorporates more simplified detailing and design which was popular after the turn- of-the-century. The two-story clapboard house features a complex roofline with steep-pitched gables. The house is built on a modified L-plan with the apex of the ell resulting in a porch overhang supported by Classical columns. Turned balisters are on the ornamental balustrade connecting the porch posts. The largest, front-facing gable features an ornamental window in somewhat of a reverse palladian style.

559. **226 S. Glassell** 1972 Historical Name: AP Number: 390-654-18 Non-Contributor

560. **229 S. Glassell** Historical Name: AP Number: 390-391-03 Non-Contributor

National Register of Historic Places Continuation Sheet

Section number _____7 Page _____122___

Old Towne Orange Historic District, Orange, CA

561. **239 S. Glassell** c1905 Victorian Historical Name:

AP Number: 390-391-04 Like the house next door at 221 South Glassell, this one is also fashioned in what was sometimes called the Princess Anne style. This too is a large, twostory house with multi-gable roofline and built on an L-plan. A large, wraparound porch is present and the porch overhang is supported by columns with Corinthian capitals. The short leg of the ell results in a front-facing, gable wing with exposed beam ornamentation, a small vented transom and a large, three-part picture window with transom on the first story. The original wood door with plate glass window is still present.

562. 244 S. Glassell c1905 Hip Roof Cottage Historical Name: AP Number: 390-654-17 A two-story house with steep-pitched, hip roof and wide lap siding. What was probably originally clapboard was maybe later covered with the present lap siding. Also what was originally probably a corner porch supported by Classical columns has since been enclosed. All of the windows and remaining format of the house remain original. Since the 1982 survey, the front porch has been reopened but an extra, not entirely appropriate, porch added.

563. **254 S. Glassell** 1894 Victorian Historical Name:

AP Number: 390-654-16

A small, one and one-half story house built on an L-plan with steep-pitched, gable roof and shiplap siding. The house features two front-facing, gable dormers each with arched transoms and the rearmost with elaborate transom sash window. The apex of the ell is characterized by an entry porch overhang supported by wood posts. The house is an excellent, unaltered example of a pre-1900 cottage-scale house in Orange.

United States Department of the Interior National Park Service

National Register of Historic Places Continuation Sheet

Section number _____7 Page _____123

Old Towne Orange Historic District, Orange, CA

564. **257 S. Glassell** c1910 Hip Roof Vernacular Historical Name: AP Number: 390-395-01 This is an unusually designed house in that it incorporates the format and massing of the Classical Revival period but is coupled with more bungalow architectural detailing. It is a box plan which features a complex, hip roofline and clapboard siding on the facades. The entry is recessed and features a double door entry, indicating the house was originally intended to be used as a duplex.

565. 262 S. Glassell

1898 Victorian Cottage Historical Name: AP Number: 390-654-15

A small, cottage-scale, pioneer dwelling with multi-gable roofline and shingle siding which probably replaces the original shiplap siding. The house is built on a modified rectangular plan and features a single, frontfacing gable projection. To the side of this an extra roof overhang forms the entry porch supported by a single wood post. The house is basic and unadorned, reflecting the fact that a very modest budget and limited resources were used to build the house. Since the 1982 survey, this structure has been altered with acceptable Victorian ornamentation.

566. **265 S. Glassell** c1920 Bungalow Historical Name:

AP Number: 390-395-02 A single-story clapboard bungalow with double, front-facing gable roof. Forwardmost gable forms the entry porch overhang and is supported by tapered piers. Vertical slatting adorns the upper portions of the gable. Large picture windows are present on the lower portion of the front facade.

567. **272 S. Glassell** 1900 Altered Victorian Historical Name:

AP Number: 390-654-14

Non-Contributor. This house has been modified over the years, but its origins in the turn-of-the-century period are clear. The house features typical steep-pitched, gabled roof and simple embellishment which characterizes early houses in Orange. The house has since been stuccoed, and all the windows, doors and entry have been substantially modified.

National Register of Historic Places Continuation Sheet

Section number 7 Page 124

Old Towne Orange Historic District, Orange, CA

568. **275 S. Glassell** Historical Name: AP Number: 390-395-03 Non-Contributor

569. 281 S. Glassell

1904 Hip Roof Cottage Historical Name: AP Number: 390-395-04

A single-story house with combination hip and gable roof and clapboard siding which has since been covered by asbestos shingles. The house has a squatty, boxy quality typical of the period, but this is enhanced by a large, wraparound, corner porch supported by wide columns with Corinthian capitals. An important element of the house is the large, boxy picture windows with diamond pane transoms. Near the porch entrance is a small, transomed window with stained glass and an ornamental frame.

570. **282 S. Glassell** 1948 Historical Name: AP Number: 390-654-13 Non-Contributor

571. 291 S. Glassell 1904 Hip Roof Cottage Historical Name: AP Number: 390-395-05 A single-story, box plan house with clapboard siding and steep-pitched, hip roof. Hip dormers are also present along the roofline. Entry is via a corner recessed porch supported by Classical columns. Windows are framed in the manner typical of the period.

572. 292 S. Glassell c1915 Craftsman Historical Name: AP Number: 390-654-12 A two-story house with shallow-pitched, multi-gable roofline and wide lap siding on the facades. The house features the second story portion located predominantly on the rear half of the house while the front, lower story is characterized by several gables. One-half of the front facade is devoted to a large entry porch which is supported by wood posts. A brick chimney with special detailing rises up the front of the house. The house features many windows typical of the Craftsman period.

National Register of Historic Places Continuation Sheet

Section number _____7 Page _____125__

Old Towne Orange Historic District, Orange, CA

573. **301 S. Glassell** 1979 Historical Name: AP Number: 390-401-01 Non-Contributor

574. **320 S. Glassell** 1950 Historical Name: AP Number: 390-601-01 Non-Contributor

575. **330 S. Glassell** 1923 Mediterranean Revival Historical Name: AP Number: 390-601-02 This is a small apartment c

This is a small apartment complex built on a rectangular plan with a flat roof and stucco facades. Each of the entries is articulated by a small portico with adobe tile hoods and ornamental braces. In addition, this same hood arrangement is located on the front facade over the windows.

576. 334 S. Glassell

1

c1900 Victorian Historical Name: AP Number: 390-601-02 This is an unusual turn-of-the-century house for Orange which features a steep-pitched, gable roof in combination with a corner turret with a conical roof. Juxtaposed opposite to the turret is a large entry porch supported by Classical Columns. An ornamental brick chimney is also present. The add-on on the north side of the house is a later addition and does detract from the original architectural appearance.

577. **335 S. Glassell** c1915 Craftsman Bungalow Historical Name: AP Number: 390-401-02 A single-story bungalow with lap siding and double, front-facing gable roof. The forwardmost gable forms the entry porch overhang and is supported by brick piers. These piers are connected by a low, brick porch wall.

National Register of Historic Places Continuation Sheet

Section number _____7 Page _____126

Old Towne Orange Historic District, Orange, CA

578. 345 S. Glassell

c1915 Craftsman Bungalow Historical Name:

AP Number: 390-401-03

A single-story bungalow with lap siding and double, front-facing gable roof. The forwardmost gable forms the entry porch overhang and is supported by brick piers. The original entry door is still present and features six small, plate glass windows. On either side are large picture windows with transoms. Ornamental purlins grace the eaves.

579. 350 S. Glassell

c1915 Craftsman Historical Name: AP Number: 390-601-03

This is a large, two-story Craftsman house designed in much the same manner as many of the Greene & Greene houses in Pasadena. The multi-gable roofline is repeated in the roof overhang of the large, wrap-around porch. This overhang is supported by wood posts on brick bases. The vertical slatting on the upper porch gable faces is also present on the main gables. The original entry door is still present; its extra large width is particularly notable as are the vertical glass panes and the flanking sidelights. The house is in excellent condition and retains its original architectural character.

580. 353 S. Glassell

1926 Mediterranean Revival

Historical Name: AP Number: 390-401-04

This is a small, single-story, box plan Mediterranean Revival house built with simplistic architectural detailing. The house features a flat roof coupled with stuccoed facades. As typical of the period, there are several projecting wings with the entry formed by a special enclosed portico with large openings and a tile hood.

581. 360 S. Glassell

1925 Eastlake Historical Name: AP Number: 390-601-04

A two-story residential structure with features of Victorian and Italianate style. Front facade appears to identify with Victorian and features a tower. Siding is wood shiplap and facade also features single-light double-hung wood windows. The original structure is of rectangular plan.

National Register of Historic Places Continuation Sheet

Section number _____7 Page _____127__

Old Towne Orange Historic District, Orange, CA

582. 361 S. Glassell 1914 Altered Hip Roof Cottage Historical Name: AP Number: 390-401-05 A single-story, clapboard bungalow with multi-hip roof. The house appears to have undergone some modification over the years, of which the prominent bay window and stoop are probably the primary examples. The house is basically simple and unadorned.

583. 368 S. Glassell

c1915 Craftsman Bungalow Historical Name: AP Number: 390-601-05

A single-story bungalow with wide lap siding and double, front-facing gable roof. The forwardmost gable forms the entry porch overhang and is supported by tapered piers on molded cast concrete bases. A low porch wall connects these piers. The original entry door with plate glass windows is still present and is flanked on either side by a large, three-part picture window with leaded glass transom. Cross-ties and purlins adorn the upper gable faces.

584. 369 S. Glassell

1925 Mediterranean Revival Historical Name: AP Number: 390-401-06

This is a small, box plan bungalow designed with Mediterranean Revival and some Mission Revival influences. The house is characteristically designed with a flat roof and stucco facades. It is built on a modified L-plan with one-half of the front facade devoted to a large, entry porch arcade with arched openings. Two Mission style parapets are also located on the front facade. Double entry doors on the remaining half of the front facade are sheltered by a tile hood.

National Register of Historic Places Continuation Sheet

Section number _____7 Page _____128__

Old Towne Orange Historic District, Orange, CA

585. **374 S. Glassell** c1895 Victorian Historical Name: AP Number: 390-601-06

A one and one-half story Victorian house with combination clapboard and ornamental siding. The roof is comprised of several steep-pitched gables. The smaller of the two, front-facing, pedimented gables defines the angled bay window of the front facade. This bay window features sash windows on either side with ornamental frames and a fixed-glass pane on the frontmost portion with a leaded glass transom. Both of the upper gable faces feature sawtooth shingles and ornamentally framed windows and attic transom. The house is a good Victorian example, though some question remains as to whether the house was remodeled just after the turn-of-the-century. Since the 1982 survey, this structure has had a change of use from residential to professional.

586. 377 S. Glassell

c1915 Craftsman Bungalow Historical Name: AP Number: 390-401-07 A single-story bungalow with ornamental lap siding and shallow-pitched, multi-gable roof. The house is predominantly covered by a single, sidefacing gable, while two, front-facing gables are juxtaposed to this for contrast. The original door with mullioned glass panes is still present. Large windows with mullioned headers are also present on the front facade. Since the 1982 survey, the original front door has been removed.

587. **385 S. Glassell** Historical Name: AP Number: 390-401-08 Non-Contributor

588. **391 S. Glassell** 1923 Historical Name: AP Number: 390-401-09 Non-Contributor

National Register of Historic Places Continuation Sheet

Section number _____7_ Page ____129__

Old Towne Orange Historic District, Orange, CA

589. **392 S. Glassell** c1905 Hip Roof Cottage Historical Name: AP Number: 390-601-19 Non-Contributor. Since the 1982 survey, this structure has been replaced with a 2-story office/professional building.

590. **403 S. Glassell** Historical Name: AP Number: 390-411-01 Non-Contributor

591. 406 S. Glassell

1903 Victorian Cottage Historical Name: AP Number: 390-602-01

A single-story clapboard house with combination steep-pitched and gabled roof. The house is built on an L-plan with the short leg of the ell resulting in a front-facing gabled projection which forms an angled bay window on the lower half. These windows are distinguished by ornamental brackets. This upper gable face is distinguished by a sunray embellishment. A large corner, wrap-around porch is present and is supported by Classical columns.

592. **413 S. Glassell**

1904 Hip Roof Cottage Historical Name: AP Number: 390-411-02 A single-story clapboard house with box plan and steep-pitched, hip roof. A small gabled dormer is present on the front portion of the roof and features an ornamentally framed transom vent and fish scale shingles. Entry is via a corner recessed porch supported by Classical columns.

National Register of Historic Places Continuation Sheet

Section number _____7 Page _____130

Old Towne Orange Historic District, Orange, CA

593. **416 S. Glassell** 1903 Victorian Cottage Historical Name: AP Number: 390-602-02 A two-story clapboard house with steep-pitched, multi-gabled roofline. The entry is distinguished by a pedimented gabled entry portico supported by wood posts with ornamental jigsawn brackets. The inner portion of the pediment is adorned with fish scale shingles. To the side a special roof extension forms an enclosed sun porch. The original screen door with jigsawn wood is still present. The upper front, gable face is adorned with ornamental brackets and a half-moon transomed vent.

594. **419 S. Glassell** 1904 Historical Name: AP Number: 390-602-04 Non-Contributor

595. **419 S. Glassell** 1904 Hip Roof Cottage Historical Name: AP Number: 390-411-23 A single-story house with combination steep-pitched, hip and gabled roof. The house is unusual in that its siding is formed of cast concrete blocks. Entry is via the corner recessed porch supported by Classical columns. The front-facing gable features a return at the eaves and also a half-moon, sunray embellishment. An angled bay window is located on the side of the house.

596. **436 S. Glassell** 1961 Historical Name: AP Number: 390-411-07 Non-Contributor

597. **437 S. Glassell** 1908 Hip Roof Cottage Historical Name: AP Number: 390-411-05 A single-story, box plan house with clapboard siding and combination steeppitched, hip and gabled roof. A small entry portico is distinguished by a pedimented gable supported by Classical columns.

1

National Register of Historic Places Continuation Sheet

Section number 7 Page 131

Old Towne Orange Historic District, Orange, CA

598. 445 S. Glassell

c1915 Bungalow Historical Name:

AP Number: 390-411-06

A single-story bungalow with wide lap siding and multi-gabled roof. The house is predominantly covered by a single-gabled roof with side-facing gables, but this is juxtaposed by two smaller, front-facing gables. One-half of the front facade is devoted to a porch which is supported by wide, tapered piers. The front facade features two three-part windows with ornamental transoms.

599. **453 S. Glassell**

1904 Post Victorian Vernacular Historical Name: AP Number: 390-411-07 This is a modified, two-story house with clapboard siding and single, frontfacing gabled roof. A separate porch roof extension across the full width of the front facade is supported by slender wood posts. The original door with plate glass windows is still present. Since the 1982 survey, this structure has been altered with turned baluster rail and panel door.

600. 454 S. Glassell

1922 Mediterranean Revival Historical Name: AP Number: 390-602-05

A single-story, box plan house with stucco facades and a flat roof. As is characteristic of the style, there are several different projecting wings. In this case, the entry portico projects forward and is characterized by a large, arched opening. A small ornamental opening is present above the door, and the curvilinear pattern of this opening is echoed in the main entry door below. To either side are French windows with mullioned panes. Above each of these windows is an adobe tile hood.

601. 458 S. Glassell

1916 Craftsman Bungalow Historical Name: AP Number: 390-602-21

A single-story bungalow with wide lap siding and multi-gabled roof. Two front-facing gables characterize the front facade, and the forwardmost of these gabled forms the entry porch overhang. it is supported by tapered piers. Each of the upper gable faces features an ornamental transomed window with ornamental purlins. The original entry door is still present, flanked on either side by large windows with transoms.

National Register of Historic Places Continuation Sheet

Section number _____ 7_ Page _____ 132__

Old Towne Orange Historic District, Orange, CA

602. **461 S. Glassell** 1921 Bungalow Historical Name: AP Number: 390-411-08 A simple, single-story bungalow with wide lap siding and single, front-facing gabled roof. The entry was originally via a corner recessed porch supported by brick piers, but it appears that this was later enclosed. The entry is still on the side, covered by a shed roof extension.

603. **469 S. Glassell** 1922 Historical Name: AP Number: 390-411-09 Non-Contributor

604. 472 S. Glassell

1897 Queen Anne Victorian Historical Name: AP Number: 390-602-07

This is a very large, two and one-half story house with shiplap siding and combination steep-pitched, hip and gabled roof. The most predominant and distinguishing feature of the house is the corner turret with conical roof. This is juxtaposed by a projecting wing on the other side of the front facade which is defined by a pedimented gable on the uppermost portion and ornamentally framed windows below. What was originally a wide front porch has since been enclosed and modified somewhat. The entry is now recessed. All the windows are the high, narrow variety common to the Victorian period. They feature mullioned panes unusual for the period and ornamental molding around the windows.

605. **480 S. Glassell** Historical Name: AP Number: 390-602-08 Non-Contributor

606. **481 S. Glassell** Historical Name: AP Number: 390-441-10 Non-Contributor

National Register of Historic Places Continuation Sheet

Section number _____7 Page _____133

Old Towne Orange Historic District, Orange, CA

607. **488 S. Glassell**

1912 Craftsman Bungalow

Historical Name: AP Number: 390-602-09

A one and one-half story bungalow with wide lap siding and multi-gabled roof. The front facade is characterized by a large, front-facing gable which originally formed a porch overhang but was later enclosed. The original piers are still present. The upper gable face is adorned with cross-ties, a louvered transom and ornamental purlins. Two sculpted lions adorn the half piers on the side of the stoop.

608. **503 S. Glassell** Historical Name: AP Number: 390-101-01 Non-Contributor

609. **525 S. Glassell** 1936 Gothic Revival Historical Name: AP Number: 390-101-15 A gothic revival rectangular plan residence with richardsonian brich arch on front large window and features a gabled portal entry. Roof features multiple high-pitched gables with high ridge beam. Siding is stucco with wood windows present.

610. **533 S. Glassell** 1950 Historical Name: AP Number: 390-101-13 Non-Contributor

611. **549 S. Glassell** 1949 Historical Name: AP Number: 390-101-17 Non-Contributor

```
612. 655 S. Glassell
1941
Historical Name:
AP Number: 390-106-14
Non-Contributor
```

National Register of Historic Places Continuation Sheet

Section number 7 Page 134

Old Towne Orange Historic District, Orange, CA

613. 127 N. Grand c1915 Bungalow Historical Name: AP Number: 039-253-08 A single-story shingled bungalow with double front-facing, gable roof. The forwardmost gable forms the entry porch overhang and is supported by wide piers with brick bases. Shingling on the house is composed of elongated, staggered butt shingles which is unusual for Orange. A large 3-part transomed window adorns the front facade.

614. **133 N. Grand**

1915 Craftsman Historical Name: AP Number: 039-253-07 A 1-1/2 story house with gable roof and wide lap siding. The main roof extends forward to form a full-width and wrap-around porch; this overhang is supported by large, fluted elephantine piers. Cross-ties embellish the upper gable faces.

615. 143 N. Grand

1905 Victorian Historical Name: AP Number: 039-253-06 A 2-story house with shiplap siding and steep-pitched, multi-gable roof. The main portion of the roof is fashioned in an L-plan with the short leg of the ell forming the front gable face. The remaining half of the front facade is devoted to a porch and the overhang is supported by wide wood posts. The porch connecting wall is faced with ornamental shingles. A small hipped dormer is present just above the porch.

616. **146 N. Grand** 1948 Historical Name: AP Number: 039-252-04 Non-Contributor

617. **157 N. Grand** 1965 Historical Name: AP Number: 039-253-32 Vacant Lot

National Register of Historic Places Continuation Sheet

Section number _____7 Page _____135___

Old Towne Orange Historic District, Orange, CA

618. **183 N. Grand**

1905 Transitional Historical Name: AP Number: 039-253-29 A 2-story house with shiplap siding on the first story and clapboard siding on the second story. The roofline is composed of a single-gable, frontfacing roof. A full-width porch is present and extends from the first story of the house and is supported by wood posts. Wide eaves throughout feature exposed rafters. Ornamental purlins and vertical slatting embellish the upper gable face.

619. 191 N. Grand

c1900 Victorian Historical Name: AP Number: 039-253-01 A high two-story house with a single front-facing, steep-pitched gable roof. One-half of the front facade is devoted to a recessed entry porch supported by a classical column. The original siding has been covered by asbestos shingles. A smaller gabled dormer is present on the side facing Maple Street.

620. 215 N. Grand

1909 Combination Brown Shingle, Gothic Historical Name: Trinity Episcopal Church AP Number: 039-243-24

This church building has the characteristics of the typical Victorian rural church with Gothic influence but incorporates these characteristics with the then (cir. 1910) popular shingle and Craftsman styles. The building is built on a rectangular plan and features a single gable roof contrasted by a The tower does not form the entry, as is common on rectilinear bell tower. the other old churches in Orange; it rises above the main roof and results in a pyramidal roof and a cross. The building is sided in natural unpainted shingles common to the Craftsman period. Pointed arch windows, common on the churches emulating the Gothic tradition, are located on either side of the building. The main entry portico is styled in a Craftsman manner. Also in the Gothic tradition is the trefoil tracery above each of the louvered panels The adjacent parsonage is in the Brown Shingle style in the bell tower. which was predominantly popular in Northern California. The roofline is multi-gable and the facades are sided in unpainted shingles. A small entry portico with a pointed arch inset shelters the entry. Both the church and the parsonage building are in excellent condition and have been determined eligible for the National Register.

National Register of Historic Places Continuation Sheet

Section number _____7 Page _____136

Old Towne Orange Historic District, Orange, CA

621. 222 N. Grand

1912 Craftsman Historical Name:

AP Number: 039-242-16

A single-story house with wide lap siding and single-gable roof with sidefacing gables. A low shed attic dormer is present on the front portion of the roof. The main roof extends forward to form a full-width porch overhang and is supported by elephantine piers. The original hardwood door with plate glass windows is still present.

622. 225 N. Grand

c1915 Craftsman Historical Name: AP Number: 039-243-09

A 1-1/2 story house house with single-gable roof of which the gables are side The original siding has been recovered with asbestos shingles. A facing. low shed dormer window is present on the front portion of the roof. The main roof extends forward to form a full-width porch overhang and is supported by elephantine piers. Large 3-part transomed windows flank either side of the main entry.

623. **230 N. Grand** 1909 Hip Roof Cottage Historical Name: AP Number: 039-242-17 A single-story clapboard cottage with steep-pitched, hip roof. A small pedimented gable attic dormer is present on the front portion of the roof. Just below, covering one-half of the front facade, is a wide gabled porch overhang supported by classical columns atop ornamental brick piers.

624. 231 N. Grand

1912 Craftsman Historical Name: AP Number: 039-243-08 A 1-1/2 story clapboard house with single, side-facing gable roof. There is a large front-facing gable dormer on the front portion of the roof which is ornamented with purlins and a louvered transom. One-half of the front facade is devoted to a recessed porch supported by a tapered pier. There is a double entry. The original hardwood doors are still present. Large 3-part transomed windows are present on the front facade.

National Register of Historic Places Continuation Sheet

Section number 7 Page 137

Old Towne Orange Historic District, Orange, CA

625. 238 N. Grand

c1900 Victorian

Historical Name: AP Number: 039-242-18

A 2-story clapboard house with combination steep-pitched, hip and gable roof. The house is built on a modified L-plan with one corner devoted to a large wrap-around porch supported by classical columns. The front-facing gable features an ornamental attic vent. Exceptionally wide eaves on the house are embellished with ornamental brackets.

626. 243 N. Grand

c1921 Gable Roof cottage Historical Name: AP Number: 039-243-07

A single-story clapboard cottage with steep-pitched, multi-gable roof. The front facing gabled porch overhang is located at the center of the front facade and is supported with Colonial columns connected by an ornamental balustrade. An ornamental transom vent is located in the front of this gable face.

627. 246 N. Grand

1920 Bungalow Historical Name: AP Number: 039-242-19 A single-story bungalow with ornamental lap siding and shallow-pitched, multi-gable roof. There are two front-facing gables to the roofline, the forwardmost is the entry porch overhang supported by wood posts.

628. 247 N. Grand

1913 Bungalow Historical Name: AP Number: 039-243-06

A single-story bungalow with lap siding and multi-gable roof. The roofline takes on an L format. The frontmost leg of the ell results in a front-facing gable, the entry porch overhang. This is supported by tapered piers atop brick bases connected with a low brick porch wall. The original front door with plate glass windows is still present. The upper portion of the porch gable has an unusually shaped attic vent.

National Register of Historic Places Continuation Sheet

Section number _____7 Page _____138

Old Towne Orange Historic District, Orange, CA

629. **254 N. Grand** c1920 Bungalow Historical Name: AP Number: 039-242-20 A single-story clapboard bungalow with roofline which follows a T-plan. The roof is gabled with each of the gable peaks being clipped. The front-facing gable in the center of the front facade acts as the entry porch overhang. It is supported by wood posts and flanked on either side by an ornamental pergola which is also supported by wood posts.

630. **257 N. Grand** 1912 Bungalow Historical Name: AP Number: 039-243-05 A single-story bungalow with single-gable roof with side-facing gables. A low shed dormer is present on the front portion of the roof. The original siding has been covered by asbestos shingles. What was originally a fullwidth porch overhang has since been enclosed, but the original piers are still present.

631. **262 N. Grand** 1942 Historical Name: AP Number: 039-242-21 Non-Contributor

632. **265 N. Grand** c1915 Bungalow Historical Name: AP Number: 039-243-04 A single-story bungalow with single-gable roof comprised of side-facing gables. A low shed dormer is present on the front portion of the roof. The original siding has since been covered with asbestos shingles. One-half of the front facade is recessed beneath the main roof to form an entry porch. Large 3-part transomed windows are present on the front facade.

National Register of Historic Places Continuation Sheet

Section number _____7_ Page _____139___

Old Towne Orange Historic District, Orange, CA

633. 268 N. Grand

1904 Hip Roof Cottage Historical Name: AP Number: 039-242-22 A single-story box plan house with clapboard siding and steep-pitched, hip roof. A small gabled attic dormer is present on the front portion of the roof. Main entry is via a recessed corner porch supported by classical columns.

634. 275 N. Grand

1921 Bungalow Historical Name: AP Number: 039-243-03 A single-story bungalow based on an L-plan with ornamental lap siding and a shallow-pitched, multi-gable roof. One-half of the front facade is devoted to a porch which is supported by colonial-like columns. Multi-paned casement windows are present on either side of the main door.

635. **276 N. Grand** 1919 Craftsman Historical Name: AP Number: 039-242-23 A single-story bungalow with double front-facing, gable roof. The original lap siding has since been covered by asbestos shingles. The forwardmost gable forms the entry porch overhang which is supported by piers with wood posts on top. Ornamental brackets and purlins are present on the porch gable. The original hardwood door and screen door are still present and are flanked on either side of the front facade by large 3-part transomed windows.

636. **281 N. Grand** c1905 Hip Roof Cottage Historical Name: AP Number: 039-243-02 A single-story box plan house with clapboard siding and steep-pitched, hip roof. The house features a full wrap-around porch across the front and side facades. The porch has its own separate overhang which is supported by slim wood posts connected by a slatted balustrade. Since the 1982 survey, this structure has been altered by removal of porch and change in windows and siding.

The main

United States Department of the Interior National Park Service

National Register of Historic Places Continuation Sheet

Section number _____7 Page _____140___

Old Towne Orange Historic District, Orange, CA

637. 284 N. Grand c1915 Craftsman Historical Name: AP Number: 039-242-24 A 2-story house with clapboard siding and multi-gable roofline. The frontmost portion of the house features a wide front-facing gable which extends forward to form a full-width porch. This is supported by wood posts connected by a slatted ballustrade.

638. 287 N. Grand

1910 Bungalow Historical Name: AP Number: 039-243-01

A single-story bungalow with single-gable roof with side-facing gables. low shed dormer is present on the front portion of the roof. The original siding of the house has since been covered with asbestos shingles.

roof extends forward to form a full-width porch which is supported by piers with brick bases and wood posts on top. An ornamental brick chimney is visible on the roof.

639. 292 N. Grand

c1915 Bungalow Historical Name: AP Number: 039-242-25 A single-story bungalow with wide lap siding and double front-facing, gable The forwardmost gable forms the entry porch overhang and is supported roof. The front facade contains two large picture windows with by tapered piers. single-paned transoms.

640. 124 S. Grand 1958 Historical Name: AP Number: 390-382-07 Non-Contributor

641. 148 S. Grand 1958 Historical Name: AP Number: 390-382-08 Non-Contributor

National Register of Historic Places Continuation Sheet

Section number 7 Page 141

Old Towne Orange Historic District, Orange, CA

642. **154 S. Grand** Historical Name: AP Number: 390-382-09 Non-Contributor

643. **176 S. Grand** Historical Name: AP Number: 390-382-11 Non-Contributor

644. 204 S. Grand c1920 Craftsman Bungalow Historical Name: AP Number: 390-392-10 A low, single-story clapboard bungalow with shallow-pitched, multi-gable roof. The front facade is distinguished by a centrally located gable which extends forward to form the entry porch overhang. Cross-ties in the upper gable face provide ornamentation; a pergola is located to either side. The porch overhang is supported by wide piers with brick bases and wood posts on top.

645. **211 S. Grand** 1960 Historical Name: AP Number: 390-393-01 Non-Contributor

646. **212 S. Grand** c1905 Hip Roof Cottage Historical Name: AP Number: 390-392-09 A single-story clapboard house with box plan and pyramidal roof. What was once an open corner porch recessed beneath the roof has since been enclosed. The large boxy window with diamond paned transom is typical of the period. Since the 1982 survey, this structure has been altered with appropriate side wing enlargement which complements the original.

National Register of Historic Places Continuation Sheet

Section number _____7 Page _____142

Old Towne Orange Historic District, Orange, CA

647. **224 S. Grand** 1910 Victorian Cottage

Historical Name:

AP Number: 390-392-08

Non-Contributor. A single-story box plan house with clapboard siding and multi-planed roof. The front portion of the house features a small dormer attic gable embellished with fish scale shingles and jigsaw bargeboard. Also located on the front is an attached porch which was originally a full-width porch, but one-half has been enclosed. The original remaining portion of the porch includes ornamental turned posts and spindle work beneath the roof of the porch. Windows are vertical, characteristic of the Victorian period and are framed in the Victorian manner. Since the 1982 survey, this structure has been severely altered by a multiple unit addition. The house has been restored.

648. **225 S. Grand** 1924 Mediterranean Revival Historical Name: AP Number: 390-393-02 A single-story box plan house with stucco siding and flat roof. Most notable feature of the house is the front facade which includes a circular entry portico supported by Classical columns with an ornamental balcony balustrade above. Flanked on either side of this porch are large picture windows with tile hoods.

649. 230 S. Grand

1913 Craftsman Historical Name: AP Number: 390-392-07 A one and one-half story Craftsman home with a rectangular plan, clapboard siding and a single-gable roof with side-facing gables. Also located on the upper portion of the house is a front-facing dormer gable with cross-ties and ornamental purlins. Entry is via a corner porch recessed beneath the main portion of the house. The porch is supported by fluted, tapered piers connected by a low, clapboard porch wall.

650. **231 S. Grand** 1948 Historical Name: AP Number: 390-393-03 Non-Contributor

National Register of Historic Places Continuation Sheet

Section number 7 Page 143

Old Towne Orange Historic District, Orange, CA

651. **240 S. Grand** c1915 Craftsman Historical Name: AP Number: 390-392-06 A one and one-half story Craftsman home with rectangular plan, clapboard siding and single-gable roof with side-facing gables. There is also a large, front-facing dormer gable which includes a small, ornamentally framed transom window with beveled glass and four pairs of casement windows. The main roof extends to form a full-width porch supported by elephantine piers which are fluted and have Classical caps.

652. **271 S. Grand** 1904 Hip Roof Cottage Historical Name: AP Number: 390-397-02 A single-story house with clapboard siding and pyramidal roof. There is a smaller dormer gable projection on the front portion of the roof which includes saw-tooth shingles and a framed attic vent. Main entry is beneath a recessed corner porch supported by wood posts.

653. 272 S. Grand 1919 Gable Roof Cottage Historical Name: AP Number: 390-396-09 A very small, bungalow cottage with multi-gable roof and facades now covered by asbestos shingles. A centrally located shallow-pitched, front-facing gable covers the entry on the center front facade, flanked on either side by a double-hung window.

654. **320 S. Grand** 1923 California Bungalow Historical Name: AP Number: 390-402-20 A single-story bungalow with wide lap siding and shallow-pitched, multi-gable roof. The front facade is distinguished by a centrally located entry porch gable supported by wood posts.

655. **329 S. Grand** c1910 Hip Roof Cottage Historical Name: AP Number: 390-403-02 A single-story, clapboard house with steep-pitched, hip roof. The main entry is via a recessed corner porch supported by slim Classical columns.

National Register of Historic Places Continuation Sheet

Section number 7 Page 144

Old Towne Orange Historic District, Orange, CA

656. **335 S. Grand** 1908 Hip Roof Cottage Historical Name: AP Number: 390-403-03 A single-story, box plan, clapboard house with steep-pitched, hip roof contrasted by a small hipped dormer. Entry is via corner recessed porch supported by posts sheathed in clapboard. The two most ornamental features are the dormer and large, four-part, double-hung windows on the front facade.

657. 340 S. Grand c1915 Craftsman Historical Name: AP Number: 390-402-18 A one and one-half story Craftsman house with lap siding and single-gable roof contrasted by a front-facing gabled dormer. The main roof extends forward to form entry porch overhang supported by elephantine piers.

658. **343 S. Grand** 1909 Hip Roof Cottage Historical Name: AP Number: 390-403-04 A single-story, clapboard house with steep-pitched, hip roof and a contrasting smaller pediment gable over one-half of the front facade. Beneath is a large diamoned-paned picture window. Entry is at center via a recessed porch supported by a single Classical column with a Corinthian capital.

659. **350 S. Grand** 1908 Hip Roof Cottage Historical Name: AP Number: 390-402-17 A single-story, clapboard house with box plan and steep-pitched, hip roof. A hip roof dormer, with wide eaves, is on the front portion of the roof. Main entry is via a corner recessed porch supported by a Classical column.

National Register of Historic Places Continuation Sheet

Section number 7 Page 145

Old Towne Orange Historic District, Orange, CA

660. **351 S. Grand** 1909 Hip Roof Cottage Historical Name: AP Number: 390-403-05 A single-story, clapboard house with double-hip roof and large, circular wrap-around porch. The main roof extends forward to form the porch overhang supported by Classical columns with Corinthian capitals. the frontmost portion of the facade, with its own separate hip roof, features a three-part window with diamond-paned transom.

661. 354 S. Grand

1915 Craftsman Bungalow Historical Name: AP Number: 390-402-16 A single-story house with lap siding and single-gable roof with side-facing gables. There is also a smaller shed dormer which is the attic vent. The main entry is via a corner recessed porch supported by an elephantine pier with brick base and wood top.

662. 359 S. Grand

1913 Craftsman Bungalow Historical Name: AP Number: 390-403-06

A one and one-half story Craftsman house with wide lap siding and a singlegable roof with side-facing gables. There is also a front-facing dormer gable projection ornamented with purlins, cross-ties between the bargeboard and a framed attic vent. The main roof extends forward to form a full-width porch supported by tapered piers of arroyo stone with wood tops. The arroyo stone piers are connected by a slatted balustrade.

663. **360 S. Grand** 1946 Historical Name: AP Number: 390-402-15 Non-Contributor

National Register of Historic Places Continuation Sheet

Section number 7 Page 146

Old Towne Orange Historic District, Orange, CA

664. **365 S. Grand** 1907 Hip Roof Cottage Historical Name: AP Number: 390-403-07 A single-story house with box plan and steep-pitched, hip roof contrasted by a hip roof dormer on the front portion. Main entry is via a corner recessed porch supported by wood posts which are probably a later addition. Wide eaves on the house feature ornamental rafter tails.

665. 368 S. Grand
1904 Hip Roof Cottage
Historical Name:
AP Number: 390-402-14
A one-story, box plan, clapboard house with steep-pitched hip roof and a
small hip roof dormer. Entry is via a recessed corner porch supported by
three classical columns. An angled bay window is on the north side.

666. 373 S. Grand
1910 Bungalow
Historical Name:
AP Number: 390-403-08
A single-story, bungalow-scale home with rectangular plan, lap siding and a
single, front-facing gable roof. Main entry is via a corner recessed porch
supported by a group of three Classical columns. Triangular bracket supports
grace the eaves on the front facade. Since the 1982 survey, this structure
has been altered with inappropriate porch post replacement and rock veneer
foundation.

667. **374 S. Grand** c1920 Craftsman Bungalow Historical Name: AP Number: 390-402-13 A single-story, bungalow house with lap siding and single, front-facing gable roof. The main roof extends forward to form a full-width porch overhang supported by tapered piers. Ornamental embellishments on the house include purlins beneath the eaves, an ornamentally framed attic vent and a slatted balustrade on the porch.

National Register of Historic Places Continuation Sheet

Section number _____7 Page _____147 Old Towne Orange Historic District, Orange, CA

668. 383 S. Grand

1913 Craftsman Bungalow

Historical Name: AP Number: 390-403-09 A single-story bungalow with rectangular plan and double, front-facing The forwardmost gable extends forward to form the entry porch gables. overhang supported by tapered piers. There is a connecting, slatted balustrade between the piers. Ornamental purlins grace the eaves.

669. 384 S. Grand

c1915 Craftsman Historical Name: AP Number: 390-402-12 A one and one-half story house with wide lap siding and a single, side-facing gable roof and front-facing dormer gable with cross-ties and three-part transom window. One-half of the front facade is devoted to a recessed corner porch supported by a tapered wood pier.

670. 391 S. Grand

1915 Craftsman Bungalow Historical Name: AP Number: 390-403-10 A single-story bungalow with double, front-facing gables. The forwardmost gable forms the entry porch overhang supported by fluted, tapered piers. Embellishments on the base include ornamental purlins and dentils on the front gable faces. Adjacent to the porch is a pergola.

671. 394 S. Grand 1910 Craftsman Bungalow

Historical Name:

AP Number: 390-402-11

A single-story house with single-gable roof with side-facing gables. There is a small, shed dormer with diamond-paned transom also. Entry is via a corner, recessed porch supported by a single pier with wood base and wood posts on top. All windows on the front facade include upper panes with diamond-paned windows.

National Register of Historic Places Continuation Sheet

Section number _____7 Page ____148__

Old Towne Orange Historic District, Orange, CA

672. 404 S. Grand 1906 Bungalow Historical Name: AP Number: 390-412-24 A single-story, clapboard bungalow with rectangular plan and single, frontfacing gable roof. A smaller, front-facing gable runs parallel to the main roof across the full width of the house, forming an entry porch overhang supported by Classical columns. Triangular brackets grace the eaves.

673. 405 S. Grand

1909 Craftsman Historical Name:

AP Number: 390-413-01

A two-story house with single, front-facing gable roof and lap siding on the first floor and square shingle siding on the second story. The porch is formed by a separate attached roof at the single story which includes a gable definition of the entry supported by wood posts treated in the Classical manner. Another notable feature of the house is the ornamental purlins and rafter tails beneath the eaves.

674. 413 S. Grand

1916 Craftsman Bungalow Historical Name: AP Number: 390-413-02 A single-story bungalow with lap siding and multi-gable roof. Front facade is composed of two front-facing gables, the smaller of which forms the entry porch overhang supported by wide piers. Exposed beams with ornamental tails and latticed attic venting further ornament the house. A large, picture window with transom is centered beneath the entry gable.

675. 414 S. Grand

1916 Craftsman Historical Name: AP Number: 390-412-23 A one and one-half story Craftsman house with rectangular plan, clapboard siding and single, side-facing gable roof. There is a smaller, front-facing dormer gable ornamented by triangular bracket supports and a leaded glass, transom window. The main roof extends forward to form a full-width porch supported by piers with brick bases. Since the 1982 survey, this structure has been altered with an inappropriate porch enclosure.

National Register of Historic Places Continuation Sheet

Section number 7 Page 149

Old Towne Orange Historic District, Orange, CA

676. 421 S. Grand

1921 Craftsman Bungalow

Historical Name: AP Number: 390-413-03

A low, single-story bungalow with clapboard siding and multi-gable roof comprised of shallow-pitched, clipped gables. The principal part of the front facade has a gable roof over the porch supported by piers with concrete bases and wood posts atop.

677. 424 S. Grand

1906 Hip Roof Cottage Historical Name: AP Number: 390-412-22

A single-story cottage with a box plan, wide lap siding and pyramidal roof. Victorian ornamentation is present in the smaller, front-facing attic dormer, ornamented with fish scale shingles and decorative bargeboard. The front window is also framed in an ornamental Victorian manner. The recessed corner is supported bny ornamental posts with decorative spindle work at the brackets.

678. 429 S. Grand

1920 Bungalow Historical Name: AP Number: 390-413-04 A single-story bungalow with lap siding and double, front-facing gable roof. The forwardmost gable originally formed the entry porch overhang but has since been enclosed. Since the 1982 survey, this structure has been altered with inappropriate re-opening of the porch.

679. 430 S. Grand

1916 Craftsman Historical Name: AP Number: 390-412-21 A one and one-half story Craftsman house with rectangular plan, lap siding and a single, side-facing gable roof. There is a front-facing dormer gable on the front portion of the roof ornamented by decorative purlins and a 3part transom window fashioned in the palladian manner. The main roof extends forward to form a full-width porch supported by tapered piers with brick bases.

National Register of Historic Places Continuation Sheet

Section number 7 Page 150

Old Towne Orange Historic District, Orange, CA

680. 438 S. Grand

1904 Hip Roof Cottage Historical Name:

AP Number: 390-412-20

A single-story, box plan clapboard house with a steep-pitched, hip roof contrasted by a smaller, hip gable on front portion. Entry is via a corner recessed porch supported by Classical columns. Wide eaves are ornamented by decorative brackets.

681. 439 S. Grand

1904 Craftsman Bungalow Historical Name: AP Number: 390-413-05 A single-story bungalow with double, front-facing gable roof and slump stone siding on the lower portion and square shingles on the upper gable faces. The forwardmost gable forms the entry porch overhang supported by slump stone piers in the low slump stone connecting wall. Cross-ties are in the upper gable faces.

682. 446 S. Grand

1916 Craftsman Bungalow Historical Name: AP Number: 390-412-19 Single-story bungalow with double, front-facing gables. The forwardmost gable forms the entry porch overhang supported by tapered piers with brick bases. The house is now covered by asbestos siding. Ornamental purlins and wood ornamentation around the upper portions of the piers provide embellishment.

683. **447 S. Grand** 1910 Historical Name: AP Number: 390-413-06 Non-Contributor

National Register of Historic Places Continuation Sheet

Section number 7 Page 151

Old Towne Orange Historic District, Orange, CA

684. 453 S. Grand

1909 Hip Roof Cottage Historical Name:

AP Number: 390-413-07

Single-story, clapboard house with box plan and a steep-pitched hip roof. There is a small hip-roof dormer with louvered attic venting on the front portion of the roof. Entry is via a corner recessed porch supported by Classical columns. The original door with single, square pane, is also present. Two large, picture windows with multi-paned transoms are on the front facades.

685. **454 S. Grand**

1909 Craftsman Bungalow Historical Name: AP Number: 390-412-18 A low, single-story bungalow with multi-gable roof and elongated, square butt, shingle siding. The lower foundation of the house is sided in ornamental lap siding. A single-gable main roof with side-facing gables is contrasted by two smaller, front-facing gables, one of which is the attic vent and the other defines half of the front facade. A half-sized porch is recessed beneath the main roof supported by elephantine piers of concrete.

686. **458 S. Grand**

1913 Craftsman Bungalow Historical Name: AP Number: 390-412-17 A single-story, tri-gable bungalow now covered with asbestos siding. The house is built on a rectangular plan, the main portion of which is covered by a single-gable roof with side-facing gables. The center front facade is defined by a large, front-facing gable which forms the entry porch overhang supported by tapered piers with arroyo stone bases.

687. 461 S. Grand

1915 Craftsman Bungalow Historical Name: AP Number: 390-413-08

A single-story bungalow with rectangular plan, tri-gable roof and asbestos siding. The main portion of the house is covered by a single-gable roof which is contrasted by a smaller, front-facing gable entry porch in the center of the front facade. The porch is supported by elephantine piers with brick bases. Ornamental purlins and louvered venting further distinguish the front gable.

National Register of Historic Places Continuation Sheet

Section number _____7 Page _____152___

Old Towne Orange Historic District, Orange, CA

688. 469 S. Grand

1909 Hip Roof Cottage Historical Name: AP Number: 390-413-09 A single-story, clapboard house with box plan and a steep-pitched, hip roof. There is a small dormer with hip roof on the front portion. Main entry is via a recessed corner porch supported by Classical columns.

689. 470 S. Grand

1912 Craftsman Bungalow Historical Name: AP Number: 390-412-16 Single-story, clapboard bungalow with double, front-facing gable roof. The forwardmost gable forms the entry porch overhang and is supported by tapered piers. Ornamental purlins provide embellishment.

690. 475 S. Grand

1920 California Bungalow Historical Name: AP Number: 390-413-10 A single-story clapboard bungalow with a single-gable roof with side-facing gables. A centrally located, front-facing gable forms the entry porch overhang and is supported by a paired combination, one each square and Colonial-type column. Double French doors provide the entry at center, flanked on either side by tri-part casement windows.

691. 478 S. Grand

1904 Hip Roof Cottage Historical Name: AP Number: 390-412-15 A single-story clapboard house with box plan and hip roof. A smaller, hip roof dormer is included. What was the original porch has since been enclosed, and the original Classical columns are no longer present. The house features exceptionally wide eaves with ornamental brackets below. Since the 1982 survey, this structure has been altered with appropriate reopening of the front porch.

National Register of Historic Places Continuation Sheet

Section number 7 Page 153

Old Towne Orange Historic District, Orange, CA

692. 484 S. Grand
1923 Mediterranean Revival
Historical Name:
AP Number: 390-412-14
A low, single-story box plan house with stucco siding and flat roof. The
front half of the facade is defined by a recessed entry porch with a large
arch opening.

693. **487 S. Grand** c1915 Craftsman Historical Name: AP Number: 390-413-11 A two-story house with a steep-pitched, multi-gable roof and lap siding now covered by asbestos shingles. The front facade is characterized by a frontfacing gable with cross-ties and a recessed porch below supported by tapered piers. Entry door is at center with a large, picture window with transom on either side.

694. **492 S. Grand** c1920 California Bungalow Historical Name: AP Number: 390-412-13 A single-story bungalow with tri-gable roof and siding now covered by asbestos. The main portion of the house is covered by a single-gable roof with side-facing gables, contrasted by a centrally located, front-facing gable over a porch overhang supported by wood posts.

695. **493 S. Grand** 1922 Bungalow Historical Name: AP Number: 390-413-12 A single-story, clapboard bungalow with single, front-facing gable roof contrasted by a smaller, front-facing gable porch overhang supported by ornamental posts. The original door with three small, rectangular panes is still present.

National Register of Historic Places Continuation Sheet

Section number 7 Page 154

Old Towne Orange Historic District, Orange, CA

696. **504 S. Grand** 1922 Bungalow Historical Name: AP Number: 390-102-14 A single-story clapboard bungalow with single-gabledroof with side-facing, clipped gables. Entry is via a projecting portico supported by ornamental wood posts. The house is otherwise simple and unadorned. Since the 1982 survey, this structure has been altered by a large garage apartment addition.

697. **505 S. Grand** 1901 Victorian Historical Name: AP Number: 390-103-01

This is a large, two-story, rural Victorian house with steep-pitched, multigabled roof and asbestos shingles covering the original shiplap siding. The house is build on a modified L-plan and features a full-width front porch with a separate roof overhang supported by ornamental turned columns. The primary entry is distinguished by a pedimented gable with jigsawn brackets. An angled bay window is present adjacent to the front door on the lower story. The same jigsawn brackets which adorn the porch portico are also located beneath the eaves around the house. The original front door is still in place and features flashed glass in both the door and transom window above. This house is a good Victorian example, but the presence of the asbestos shingles and other slight modifications make it slightly different from the average.

698. **515 S. Grand**

1919 Craftsman Bungalow Historical Name: AP Number: 390-103-02 A one and one-half story clapboard house with single, side-facing gabled roof. A large, front-facing gabled dormer is present with four, single-pane windows. The main roof extends forward to form a full-width porch overhang and is supported by wide, square piers. On either side of the main entry is located a large, three-part transomed window.

National Register of Historic Places Continuation Sheet

Section number _____7_ Page _____155___

Old Towne Orange Historic District, Orange, CA

699. **520 S. Grand**

1914 Craftsman Bungalow Historical Name: AP Number: 390-102-12 A one and one-half story Craftsman house with wide lap siding and single, side-facing gabled roof. The main roof extends forward to form a full-width porch which is supported by tapered piers. The original door with plate glass windows is present, flanked on either side by large, transomed picture windows. A front-facing, gabledd dormer with combination louvered and glass transom is also present.

700. **528 S. Grand** 1919 Historical Name: AP Number: 390-102-11 Non-Contributor

701. **529 S. Grand** 1916 Craftsman Bungalow Historical Name: AP Number: 390-103-25 A single-story bungalow with clapboard siding and shallow-pitched, multigabled roof. The full width of the front facade is articulated by a large, front-facing gable which extends forward to form a full-width porch. This gable is supported by ornamental concrete piers on the outer edges and half piers with wood posts on top on the inner portion near the entry. Ornamental exposed beams characterize the eaves around the house.

702. **536 S. Grand** 1934 Bungalow Historical Name: AP Number: 390-102-10 A single-story clapboard bungalow with single, front-facing gabled roof. What was originally a full-width porch was later enclosed, but the porch posts are still present.

National Register of Historic Places Continuation Sheet

Section number _____7 Page _____156__

Old Towne Orange Historic District, Orange, CA

703. 545 S. Grand

1912 Craftsman Historical Name: AP Number: 390-103-24

This is a large, two-story Craftsman house with clapboard siding and a multigabled roofline. The house has dynamic and complex proportions and is distinguished by a gabled projection on the lower story which forms the entry porch overhang. This overhang is supported by wide piers with concrete bases and wood posts on top. Half-timbering embellishes the upper porch gable. Ornamental purlins and latticed work embellish the remaining gables around the house.

704. 552 S. Grand

c1920 Bungalow Historical Name: AP Number: 390-102-09

A single-story bungalow with ornamental lap siding and double, front-facing gabled roof. The forwardmost gable forms the entry porch overhang and is supported by piers comprised of brick bases with wood posts on top. Vertical slatting, exposed beams and triangular bracket supports distinguish each of the upper gable faces. This property is distinguished by the presence of a very large and old Monterey Pine tree. Since the 1982 survey, an inappropriate second unit has been added to the site.

705. 604 S. Grand

1911 Hip Roof Cottage Historical Name: AP Number: 390-105-10 A small, single-story co

A small, single-story cottage with wide lap siding and hip roof. A separate roof extension defines a small entry porch which is supported by wood posts. Entry is at center and flanked on either side by a double-hung window. Since the 1982 survey, this structure has been altered with appropriate porch railings.

National Register of Historic Places **Continuation Sheet**

Section number _____7 Page _____157 Old Towne Orange Historic District, Orange, CA

706. 610 S. Grand 1920 Craftsman Bungalow Historical Name: AP Number: 390-105-09 A single-story bungalow with ornamental lap siding and shallow-pitched, The house features two entries, indicating the intention for gabled roof. duplex usage originally. Each entry is articulated by a shallow-pitched, gabled portico supported by piers with wide concrete bases and wood posts on top. A small shed dormer is located in the center portion of the front roof. The central portion of the front facade features two large, sash windows with mullioned upper sashes.

707. 620 S. Grand

1970 Historical Name: AP Number: 390-105-08 Non-Contributor

708. 628 S. Grand 1973 Historical Name: AP Number: 390-105-07 Non-Contributor

709. 636 S. Grand 1916 Historical Name: AP Number: 390-105-06 Non-Contributor

710. 651 S. Grand 1921 Historical Name: AP Number: 390-104-03 Non-Contributor

National Register of Historic Places Continuation Sheet

Section number _____7 Page _____158

Old Towne Orange Historic District, Orange, CA

711. **667 S. Grand** c1915 Craftsman Historical Name: AP Number: 390-104-04

A large, two-story Craftsman house characterized by a single-gabled roof with side-facing gables. This is in contrast to a large, front-facing gabled dormer with a balustrade and shingle embellishment in the upper gable face. The main roof extends forward to form a half porch which is supported by concrete piers and connecting, slatted balustrade. A large entry features the original door flanked on either side by side lites.

712. 121 N. Harwood

c1915 Bungalow Historical Name: AP Number: 386-073-07 A two-story house on a rectangular plan with a steep-pitched, gable roof. A complementary gable dormer is present. Entry door is on side, though no entry porch is present.

713. 130 N. Harwood

c1915 Bungalow Historical Name: AP Number: 386-072-10 A single-story bungalow with wide lap siding and a double front-facing, gable roof. The forwardmost gable forms entry porch overhang and is supported by

roof. The forwardmost gable forms entry porch overhang and is supported by taper piers atop a lap-sided porch wall with connecting slatted balustrade. Original door with plate glass windows is present; also on the inner porch facade are three mullioned casement windows.

714. **131 N. Harwood** 1890 Board and Batten Victorian Cottage Historical Name: AP Number: 386-073-06 This is a single-story board and batten house representative of the early, hand-built, settlement houses in Orange. The roof is both gabled and with a saltbox slope. The house is built on a modified L-plan with the entry being in the apex of the ell. A small attached roof, supported by slender bracketed posts, acts as the entry porch overhang. The house is basic, simple and unadorned, reflecting the attention to economy and lack of resources available at the time the house was constructed in 1890. Considering the age and construction method, the house is in excellent condition and retains its original architectural appearance.

National Register of Historic Places Continuation Sheet

Section number _____7 Page _____159__

Old Towne Orange Historic District, Orange, CA

715. **138 N. Harwood** 1911 Bungalow Historical Name:

AP Number: 386-072-11

A single-story house with combination hip and gable roof. The original siding has since been covered by asbestos shingles. a front-facing gable forms the entry porch overhang which is supported by tapered piers. A pergola is located to the side. Dentils and an ornamental transom are present in the front porch gable. The front facade is adorned by an angled bay window which features a large picture with mullioned transom, which is identical to the one on the other half of the front facade.

716. 139 N. Harwood

1920 Bungalow Historical Name: AP Number: 386-073-05 A single-story bungalow with wide lap siding and double front-facing, gable roof. The rearmost gable actually forms the entry porch overhang which is supported by a tapered pier. The house is simple and basically unembellished.

717. 145 N. Harwood

1919 Bungalow Historical Name: AP Number: 386-073-04 A single-story bungalow with ornamental lap siding and multi-gable, shallowpitched roof. Two front-facing gables distinguish the front facade. The entry has its own small overhang and is comprised of the original door with diamond-pane glass plate.

718. **146 N. Harwood**

1913 Bungalow Historical Name: AP Number: 386-072-12 A single-story bungalow with wide lap siding and double, front-facing gable roof. The entry is on the side of the forwardmost gable. Ornamental purlins grace the eaves. Since the 1982 survey, this structure has been altered with inappropriate shutters.

National Register of Historic Places Continuation Sheet

Section number 7 Page 160

Old Towne Orange Historic District, Orange, CA

719. **154 N. Harwood** 1913 Spanish Colonial Revival Historical Name: AP Number: 386-072-13 A small single-story Spanish Colonial Revival bungalow with stucco facades and multi-gabled roof with adobe tiles. The house was built in a modified Lplan with the short leg of the ell resulting in an elongated front-facing gable. A small arch opening shelters the main entry. A recessed arch window and arch gateway entrance are present on the front portion of the house.

720. 159 N. Harwood

1920 Bungalow Historical Name: AP Number: 386-073-03 A single-story bungalow with ornamental lap siding and multi-gable roof. Centrally located, front-facing gable forms the entry porch overhang and is supported by wood posts.

721. **162 N. Harwood** 1927 Spanish Colonial Revival Historical Name: AP Number: 386-072-14 A single-story, rectangular plan house with stucco siding and single-gable, adobe tile roof. Entry is via a recessed porch which is supported by a large arch opening.

722. **169 N. Harwood** c1922 Spanish Colonial Revival Historical Name: AP Number: 386-073-02 A two-story house with textured stucco siding and flat roof. Three large arched openings articulate a recessed porch, while an adobe tile hood defines the upper front of the house.

723. **172 N. Harwood** 1947 Historical Name: AP Number: 386-072-15 Non-Contributor

Α

United States Department of the Interior National Park Service

National Register of Historic Places Continuation Sheet

Section number _____7_ Page _____161

Old Towne Orange Historic District, Orange, CA

724. 180 N. Harwood 1948 Historical Name: AP Number: 386-072-16 Non-Contributor

725. 205 N. Harwood 1922 Bungalow Historical Name: AP Number: 386-083-11 A single-story clapboard bungalow with shallow-pitched, multi-gable roof. front-facing gable and side-facing gable intersect to form a half-sized recessed porch which is supported by piers with concrete bases and wood posts on top. A large transomed picture window is located on the frontmost facade.

726. 213 N. Harwood

1924 Mediterranean Revival Historical Name: AP Number: 386-083-10 A single-story box plan house with stucco siding and a flat roof with raised parapets. The small projection on the front facade forms an entry portico with arched openings. Adobe tile hoods adorn the front windows.

727. 225 N. Harwood

c1920 Bungalow Historical Name: AP Number: 386-083-09 A single-story clapboard bungalow with shallow-pitched, multi-gable roof. The main portion of the house is covered by a single-gable roof with sidefacing gables. A centrally located, front-facing gable forms the entry porch overhang. It is supported by tapered piers with brick bases. There is a double entry. Both have original doors indicating duplex usage of the house.

728. 232 N. Harwood

1914 Gable Roof Cottage Historical Name: AP Number: 386-082-14

This is a small box-plan clapboard house with single-gable roof with sidefacing gables. The main roof extends forward to form a full-width porch overhang, supported by slim wood posts. The house is very small, simple and unembellished, indicating that it was probably hand built with no architect or contractor involved.

National Register of Historic Places Continuation Sheet

Section number 7 Page 162

Old Towne Orange Historic District, Orange, CA

729. 237 N. Harwood

1921 Bungalow Historical Name: AP Number: 386-083-08 A single-story clapboard bungalow

A single-story clapboard bungalow with shallow-pitched, multi-gable roof. A centrally located, front-facing gable forms a porch overhang and is supported by colonial columns. The main roof extends forward on either side and is also supported by the same type of columns. The original, multi-paned glass door and screen door are still present and are flanked by side lites.

730. 240 N. Harwood

1909 Bungalow Historical Name: AP Number: 386-082-15 This is a small, single-story bungalow with a single, front-facing gable roof. The original clapboard siding has been covered by asbestos shingles. There is a small roof overhang above the front door and window which acts as a full-width entry porch and is supported by wood posts.

731. 245 N. Harwood

1922 Mediterranean Revival Historical Name: AP Number: 386-083-07 This is a single-story box plan house with stucco siding and flat roof. A centrally located, projecting entry portico is articulated by a large arched opening. To either side of the entry is a large 3-part window. The masonry work on the lower portion of the house is probably a later addition.

732. **246 N. Harwood** 1959 Historical Name: AP Number: 386-082-16 Non-Contributor

733. **252 N. Harwood** 1931 Spanish Colonial Revival Historical Name: AP Number: 386-082-17

A single-story house with rectangular plan, textured stucco siding and double, front-facing, gable roof. The roof is of adobe tiles. Entry is on the side of the frontmost gable and is comprised of a small recessed porch with a wide pier support. A large 3-part window on the front facade is set within an embossed arched embellishment.

National Register of Historic Places Continuation Sheet

Section number _____7 Page _____163__

Old Towne Orange Historic District, Orange, CA

734. **253 N. Harwood** 1922 Mediterranean Revival

Historical Name:

AP Number: 386-083-06

A single-story house with stucco facades and flat roof. The house is built on a modified L-plan with a small entry portico porch in the apex of the ell. The entry portico is comprised of a large, half-sized arch opening and a tile hood.

735. 256 N. Harwood

1931 Spanish Colonial Historical Name: AP Number: 386-082-18 This house is identical to that at 252 N. Harwood--a single-story house with rectangular plan, textured stucco siding and double, front-facing, gable roof. The roof is of adobe tiles. Entry is on the side of the frontmost gable and is comprised of a small recessed porch with a wide pier support. A large 3-part window on the front facade is set within an embossed, arch embellishment.

736. 264 N. Harwood

1922 Bungalow Historical Name: AP Number: 386-082-19 A single-story clapboard bungalow with single, front-facing, gable roof. Entry is via a corner recessed porch which is supported by a slim wood post. A small octagonal transom window is present on the front facade.

737. **269 N. Harwood** c1924 Spanish Colonial Revival Historical Name: AP Number: 386-083-04 This single-story house combines Mediterranean and Provincial Revival influences. The house is built on a L-plan and includes stucco facades with steep-pitched, gable roof. The entry is at the center of the front-facing gable facade and is comprised of a multi-paned, arched door beneath a recessed arched entry portico. The main entry is flanked on either side by large arched windows. The pitch of the roof and the stucco facades indicate the Provincial influences. The arches indicate the Mediterranean influences.

National Register of Historic Places Continuation Sheet

Section number _____7 Page _____164 Old Towne Orange Historic District, Orange, CA

738. 273 N. Harwood

1925 Mediterranean Revival Historical Name: AP Number: 386-083-03 A single-story box plan house with textured stucco siding and a flat roof with raised parapets. The front facade is distinguished by a projecting entry portico with three large arched openings and a gabled tile roof. The two front windows are 3-part transomed windows with an arched embellishment above.

739. 276 N. Harwood

c1930 Spanish Colonial Revival Historical Name: AP Number: 386-082-20 This is a single-story house with modified rectangular plan and single, front-facing, gable roof. The roof features adobe tiles. Entry is via a corner recessed porch supported by a wide stucco-sided pier. The house is otherwise simple and unembellished.

740. 278 N. Harwood

1930 Spanish Colonial Revival Historical Name: AP Number: 386-082-21 This house is identical to that at 276 N. Harwood--a single-story house with modified rectangular plan and single, front-facing gable roof. The roof features adobe tiles. Entry is via a corner recessed porch supported by a wide stucco-sided pier. The house is otherwise simple and unembellished.

741. 283 N. Harwood

1921 Bungalow Historical Name: AP Number: 386-083-02 A single-story bungalow with wide lap siding and multi-gable roof. The main portion of the house is covered by a single-gable roof with side-facing gables. There is also a small front-facing, gabled attic dormer and a frontfacing, gable porch overhang supported by wide wood posts. The main door is beneath at center and flanked on either side by a double-hung window.

National Register of Historic Places Continuation Sheet

Section number _____7_ Page _____165_ Old Towne Orange Historic District, Orange, CA

742. 291 N. Harwood 1928 Prinvincial Revival Historical Name: AP Number: 386-083-01 This house incorporates a Provincial Revival influence through the use of the steep-pitched, gable roof. The house is built on a modified L-plan and has wide lap siding. A narrow, front-facing gable forms the entry porch portico which is accessed through a large arched opening.

743. 315 N. Harwood 1914 Bungalow Historical Name: AP Number: 386-133-10 A small, single-story bungalow with wide lap siding and single-gable roof with side-facing gables. The main roof extends forward to form a full-width porch which is supported by narrow wood posts connected by a slatted balustrade.

744. 316 N. Harwood

1903 Victorian Historical Name: AP Number: 386-132-14 A single-story house built on an L-plan with steep-pitched, gable roof and shiplap siding. The short leg of the ell results in a large front-facing gable which is embellished in its upper face with sawtooth shingles. Just below are a pair of high, narrow, double-hung windows. Entry is in the apex of the ell and is sheltered by a small roof overhang.

745. 324 N. Harwood c1915 Bungalow Historical Name: AP Number: 386-132-15 A single-story bungalow with wide lap siding and single, front-facing, gable roof. A small gabled portico is present on the center of the front facade and is supported by piers comprised of concrete bases and narrow wood posts. Vertical slatting and cross-ties adorn the gables.

National Register of Historic Places Continuation Sheet

Section number 7 Page 166

Old Towne Orange Historic District, Orange, CA

والمصاوفة فالتكليون فالجنوف فكتواك والأوار الارار

746. **325 N. Harwood** 1910 Bungalow Historical Name: AP Number: 386-133-09 A small, single-story bungalow with clapboard siding and double, front-facing gable roof. The smaller, forwardmost gable forms an entry porch overhang and is supported by tapered wood posts.

747. **335 N. Harwood** c1920 Bungalow Historical Name: AP Number: 386-133-08 A single-story bungalow with wide lap siding and double, front-facing gable roof. The smaller forwardmost gable forms the entry porch overhang and is supported by tapered wood posts. Triangular bracket supports and vertical slatting in the porch gable ornament the house.

748. **336 N. Harwood** 1909 Hip Roof Cottage Historical Name: AP Number: 386-132-16 A 1-1/2 story box plan house with modified hip roof which results in a small gabled dormer at the peak. The main roof extends forward to form a fullwidth porch supported by slender wood posts. The original siding has been covered with asbestos shingles.

749. **340 N. Harwood** 1977 Historical Name: AP Number: 386-132-17 Non-Contributor

750. **341 N. Harwood** c1905 Victorian Cottage Historical Name: AP Number: 386-133-07 A single-story clapboard house with steep-pitched, multi-gable roof. The two parallel, front-facing gables are present on the front facade, and each is embellished with ornamental shingles. Entry is via a corner recessed porch supported by wood posts with a row of connecting jigsawn ornament at the top portion of the porch.

National Register of Historic Places Continuation Sheet

Section number 7 Page 167

Old Towne Orange Historic District, Orange, CA

751. **345 N. Harwood** 1920 Bungalow Historical Name: AP Number: 386-133-06 A single-story bungalow with wide lap siding and multi-gable roof. The front facade is articulated by a front-facing, gabled porch overhang suppored by wood posts. The house is rather simple and unembellished.

752. **350 N. Harwood** c1930 Spanish Colonial Revival Historical Name: AP Number: 386-132-18 A single-story house built on an L-plan with textured stucco siding and a multi-gable, adobe tile roof. Entry is at the apex of the ell, and there is no porch or portico of any kind. The windows on this house have been modified from the original. Since the 1982 survey, this structure has been altered with appropriate windows and features closer to its original design.

753. **356 N. Harwood** Historical Name: AP Number: 386-132-19 Non-Contributor

754. **359 N. Harwood** 1925 Bungalow Historical Name: AP Number: 386-133-05 A single-story clapboard bungalow with single, front-facing, gable roof. A full-width porch is recessed beneath the main roof overhang and is supported by tapered piers with brick bases.

755. **364 N. Harwood** 1954 Historical Name: AP Number: 386-132-20 Non-Contributor

756. **365 N. Harwood** Historical Name: AP Number: 386-133-04 Non-Contributor

National Register of Historic Places Continuation Sheet

Section number _____7 Page _____168 Old Towne Orange Historic District, Orange, CA

والمادي والمحافظ والمتعاد والمتعاصية والمتعادية والمحافظ والمحافظ والمحافظ والمحافظ والمحافظ والمحافظ

757. 374 N. Harwood 1912 Bungalow Historical Name: AP Number: 386-132-21 A single-story clapboard house with single-gable roof with side-facing gables. A small, centrally located, pedimented gable portico is present on the front facade and is supported by slender wood posts.

758. 375 N. Harwood

1903 Gable Roof Cottage Historical Name: AP Number: 386-133-03 A single-story house built on an L-plan with shiplap siding and steeppitched, multi-gable roof. Entry is at the apex of the ell beneath a corner porch supported by wood posts. An angled bay window is present on the side of the house.

759. 381 N. Harwood 1971 Historical Name: AP Number: 386-132-22 Non-Contributor

760. 384 N. Harwood 1906 Hip Roof Cottage Historical Name: AP Number: 386-132-22 A single-story box plan house with clapboard siding and steep-pitched, hip The corner of the house features a large, wrap-around porch which is roof. supported by classical columns atop a clapboard porch wall.

761. 393 N. Harwood 1920 Historical Name: AP Number: 386-133-01 Non-Contributor

762. 394 N. Harwood 1956 Historical Name: AP Number: 386-132-23 Non-Contributor

National Register of Historic Places Continuation Sheet

Section number 7 Page 169

Old Towne Orange Historic District, Orange, CA

763. 523 N. Harwood 1924 Dutch Gabled Provincial Historical Name: AP Number: 386-231-14 A rectangular plan house with multi-gabled roof and tongue and groove wide siding. The roof has 2 side facing gables articulated with clipped gables. A very steep gable forms an entry. The stucco chimney is set in a second front facing gable. The door and windows are arched.

764. **533 N. Harwood** 1924 Provincial Revival Historical Name: AP Number: 386-231-15 A stucco house built on an irregular rectangular plan. The roof consist of two gables facing side to side and the other front to back. The front to back gable meets the other at its center and is several feet higher. The street side of the side to side gable frames the shed roof of the entry portico. The entry portico and the side wall extending over the driveway have arched openings.

765. **553 N. Harwood** Historical Name: AP Number: 386-231-16 Non-Contributor

766. **130 S. Harwood** 1948 Historical Name: AP Number: 390-441-13 Non-Contributor

767. **133 S. Harwood** 1935 Historical Name: AP Number: 390-443-19 Non-Contributor

National Register of Historic Places Continuation Sheet

Section number _____7 Page _____170

Old Towne Orange Historic District, Orange, CA

768. 135 S. Harwood

c1915 Craftsman Bungalow Historical Name: AP Number: 390-443-18 A single-story bungalow with wide lap siding and single-gable roof with a front-facing gable. A full-width porch is recessed beneath the main portion of the and is supported by tapered piers with brick bases. The upper gable face features a three-part window, including a large, fixed pane window in the center with double transom and multi-paned, double-hung windows on either side. Ornamental purlins grace the eaves.

769. 141 S. Harwood

1905 Hip Roof Cottage Historical Name: AP Number: 390-443-17 A small, single-story clapboard house with hip roof and small, recessed entry porch on the corner.

770. 142 S. Harwood

c1915 Craftsman Bungalow Historical Name: AP Number: 390-442-09 A small Craftsman bungalow with two super-imposed front-facing gables with vertical slat vents and knee braces. The front gable covers a front porch and is supported by wood posts on plastered piers. A large, cottage-style window faces onto the porch. There is a large addition in the rear.

771. 146 S. Harwood

c1915 Craftsman Bungalow Historical Name: AP Number: 390-442-22 A low, single-story bungalow with shallow-pitched, double, front-facing gables and now covered by asbestos siding. The smaller forwardmost gable forms the entry porch overhang supported by tapered piers.

772. **150 S. Harwood** 1977 Historical Name: AP Number: 390-442-21 Non-Contributor

National Register of Historic Places Continuation Sheet

Section number 7 Page 171

Old Towne Orange Historic District, Orange, CA

773. **151 S. Harwood** 1906 Hip Roof Cottage Historical Name: AP Number: 390-443-16 A small, one-story cottage built on a box plan with a steep-pitched hip roof. What was originally a full-width front porch, probably supported by Classical columns, was enclosed early on; this enclosure features several mullioned, casement windows. Original siding has since been covered with replacement lap siding.

774. 158 S. Harwood

1922 Bungalow Historical Name: AP Number: 390-442-11 A single-story bungalow with shallow-pitched and double, front-facing gable roof. Siding is now covered by asbestos shingles. The forwardmost gable originally must have formed the entry porch overhang but has since been enclosed.

775. 161 S. Harwood

1919 Bungalow Historical Name: AP Number: 390-443-15 A single-story house with single gable roof with front-facing gables and wide lap siding. A recessed corner porch is supported by wood posts.

776. 168 S. Harwood

1923 Bungalow Historical Name: AP Number: 390-442-12 A single-story clapboard bungalow with multi-gable roof and front-facing gable which forms entry porch overhang. This is supported by tapered piers.

777. 169 S. Harwood

1909 Hip Roof Cottage Historical Name: AP Number: 390-443-14 A single-story clapboard house with modified box plan and multi-planed roof. Entry is via a corner recessed porch supported by Classical columns. Two smaller gables are present, one on the front and one on the side. Each is embellished with ornamental shingles.

متوار الحجاب المحمومة محيطته التار بحمل طوعت التي الدياء بتحديد بالوالحا

National Register of Historic Places **Continuation** Sheet

Section number _____7 Page _____172 __ Old Towne Orange Historic District, Orange, CA

والمتحافي والحاد والحصيصة واحتار وورداني فالمساعف فالمحتم ووووران المالك مترد الكالمركز المرور بأنوانها

778. 175 S. Harwood Historical Name: AP Number: 390-443-13 Non-Contributor

779. 191 S. Harwood 1910 Victorian Historical Name: AP Number: 390-443-12 A single-story clapboard house with hip roof. A full-width porch is attached to the front of the house and is supported by ornamental, turned posts. Located above the center front facade is an ornamental gable which serves as an attic vent. It is embellished with ornamental shingles and an ornamental bargeboard.

780. 215 S. Harwood 1904 Historical Name: AP Number: 390-432-22 Non-Contributor

781. 235 S. Harwood 1938 Historical Name: AP Number: 390-432-21 Non-Contributor

782. 268 S. Harwood 1935 Bungalow Historical Name: AP Number: 390-433-11 A single-story L-plan bungalow with clapboard siding and multi-gable roof. Entry is at apex of ell. House is simple and unembellished.

783. 269 S. Harwood 1944 Historical Name: AP Number: 390-434-01 Non-Contributor

National Register of Historic Places Continuation Sheet

Section number _____7 Page _____173__

Old Towne Orange Historic District, Orange, CA

784. **509 E. Jefferson** 1951 Historical Name: AP Number: 386-141-26 Non-Contributor

785. **521 E. Jefferson** 1946 Historical Name: AP Number: 386-141-23 Non-Contributor

786. 533 E. Jefferson

c1920 Bungalow Historical Name: AP Number: 386-141-22 A single-story clapboard bungalow with multi-gable roof. The center of the front facade is adorned with a front-facing gabled porch overhang supported by tapered piers with ornamental brick bases and wood posts on top. The original hardwood door with plate glass windows is still present.

787. 541 E. Jefferson

c1920 Bungalow Historical Name: AP Number: 386-141-21

A single-story clapboard bungalow with double, front-facing gable roof. The forwardmost gable forms the entry porch overhang and is supported by piers comprised of ornamental brick bases and wood posts on top. To either side of the main entry door is a large 3-part window with a transom over the center window.

788. **545 E. Jefferson** c1920 Provincial Revival Historical Name: AP Number: 386-141-20

A single-story clapboard house built on an L-plan with a steep-pitched, multi-gable bonnie roof. Entry is at the apex of the ell via a small entry portico. The house incorporates Provincial Revival influences through its massing and refined profile with steep-pitched gables.

The

United States Department of the Interior National Park Service

National Register of Historic Places **Continuation Sheet**

Section number 7 Page 174

Old Towne Orange Historic District, Orange, CA

789. 557 E. Jefferson

c1915 Modified Bungalow Historical Name: AP Number: 386-141-19 Non-Contributor. The original bungalow with flagstone siding was replaced with a new bungalow style residence.

790. 603 E. Jefferson c1905 Mediterranean Revival Historical Name: AP Number: 386-141-18 A single-story box plan house with stucco facade and flat roof with slightly raised parapets at the corners. The front facade is articulated by an entry portico with a high arched opening and gable roof with adobe tiles.

791. 611 E. Jefferson c1925 Mediterranean Revival Historical Name: AP Number: 386-141-17 A single-story box plan house with stucco facades and flat roof. A large recessed entry portico is supported by wide stucco piers. Adobe tiles highlight the roof ridges.

792. 615 E. Jefferson 1936 Classical Revival Historical Name: AP Number: 386-141-16 A classical revival residence on a rectangular plan with single-pane 4/1 bay windows with matching sidelights, detailed cornice molding, and rake board. The roof contains a single high-pitched gable. A complimentary porch addition with greco/roman columns appears to have been added.

793. 631 E. Jefferson c1920 Bungalow Historical Name: AP Number: 386-141-15 A single-story clapboard bungalow with three, front-facing gables. forwardmost gable forms an entry porch overhang and is supported by tapered piers. These piers have brick bases which extend along the foundation wall of the house. It may not be original. The gable on the left side is an addition.

National Register of Historic Places **Continuation Sheet**

Section number _____7 Page ____175 Old Towne Orange Historic District, Orange, CA

(i) A set the set of a set of the set of the destate of the set of the set

794. 643 E. Jefferson 1979 Historical Name: AP Number: 386-141-14 Non-Contributor

795. 127 E. LaVeta 1956 Historical Name: AP Number: 390-411-11 Non-Contributor

796. 128 E. LaVeta 1953 Historical Name: AP Number: 390-101-12 Non-Contributor

797. 222 E. LaVeta 1921 Craftsman Bungalow Historical Name: AP Number: 390-102-01 A single-story bungalow with multi-gable roof and wide lap siding. Roof gables form an L arrangement with the main entry being at the apex of the A pergola flanks the side of the house and is supported by wide ell. concrete piers with wood tops.

798. 226 E. LaVeta

1917 Craftsman Bungalow Historical Name: AP Number: 390-102-13 A single-story bungalow with double, front-facing gables and a combination clapboard siding along the foundation wall and wide lap siding on the upper portions of the house. The forwardmost gable forms the entry porch overhang supported by wide tapered piers connected by a slatted balustrade.

799. 322 E. LaVeta

Historical Name: AP Number: 390-103-03 Non-Contributor

National Register of Historic Places Continuation Sheet

Section number 7 Page 176

Old Towne Orange Historic District, Orange, CA

800. **330 E. LaVeta** 1920 Craftsman Bungalow Historical Name: AP Number: 390-103-04 A single-story, tri-gable bungalow with ornamental lap siding. Main portion of the house is covered by a single-gable roof with side-facing gables. A centrally located, front-facing gable forms the entry porch overhang supported by tapered piers.

801. **333 E. LaVeta** 1953 Historical Name: AP Number: 390-413-13 Non-Contributor

802. **336 E. LaVeta** 1917 Craftsman Bungalow Historical Name: AP Number: 390-103-05 A low, single-story bungalow with shallow-pitched, multi-gable roof and wide lap siding. Roof gables form an L-plan, and the entry is via a corner porch beneath the main roof extension. This portion of the roof is supported by piers with wood posts on top.

803. **344 E. LaVeta** 1920 Bungalow Historical Name: AP Number: 390-103-06 Single-story clapboard bungalow with double, front-facing gables. A small shed roof attached to the front facade forms the entry porch overhang and is supported by tapered piers with concrete bases and wood tops. Each of the planes of the front facade has a large picture window with diamond-paned transom.

National Register of Historic Places Continuation Sheet

Section number _____7 Page _____177

Old Towne Orange Historic District, Orange, CA

804. 352 E. LaVeta

1912 Craftsman Historical Name: AP Number: 390-103-07

A one and one-half story Craftsman house with single-gable roof with sidefacing gables and wide lap siding. A dormer with smaller gable is on the front portion of the roof, embellished with a three-part window, cross-ties between the bargeboard and ornamental purlins. Entry is via a corner recessed porch supported by a tapered pier atop a low connecting porch wall. Ornamental purlins grace the remaining eaves of the house.

805. 360 E. LaVeta

1921 Craftsman Bungalow Historical Name: AP Number: 390-103-08

A single-story bungalow with shallow-pitched, double, front-facing gables. Siding is now covered by asbestos shingles on the facades. The smaller, forwardmost gable forms the entry porch overhang supported by elephantine piers with concrete bases and wood posts on top.

806. **415 E. LaVeta** 1962 Historical Name: AP Number: 390-103-14 Non-Contributor

807. **420 E. LaVeta** 1923 Mediterranean Revival Historical Name: AP Number: 390-103-09 A single-story box plan house with flat roof and stucco facades. An entry portico is formed by an extension of the main facade with three large, arched openings and a tile hood roof. The ridges of the main roof are ornamented with adobe tiles.

808. **428 E. LaVeta** Historical Name: AP Number: 390-103-10 Non-Contributor

National Register of Historic Places Continuation Sheet

Section number _____7 Page _____178_

Old Towne Orange Historic District, Orange, CA

809. 433 E. LaVeta
1922 Bungalow
Historical Name:
AP Number: 390-414-13
A single-story, simple unadorned bungalow with single, front-facing gable
roof and small gable entry portico.

810. 437 E. LaVeta

1919 Craftsman Bungalow Historical Name: AP Number: 390-414-15 A single-story clapboard bungalow with shallow-pitched, double, front-facing gables. The forwardmost gable forms the entry porch overhang supported by tapered piers with concrete bases and wooden posts on top. Notable feature of the house is two large picture windows with ornamentally paned transoms.

811. 445 E. LaVeta

1919 Craftsman Bungalow Historical Name: AP Number: 390-414-14 A single-story clapboard bungalow with shallow-pitched, double, front-facing gables. The forwardmost gable forms the entry porch overhang supported by tapered piers with concrete bases and wood posts on top. Vertical slatting ornaments the upper gable face of the porch; narrow slatting defines the connecting balustrade below.

812. 505 W. LaVeta 1926 Pressed Tin Western False Front Historical Name: AP Number: 041-142-15 A rectangular plan warehouse building with main gable roof and pressed tin, western false front on front facade. Uppermost portion of front facade features a stepped parapet. An ornamental pattern has been pressed into the tin. Since the 1982 survey, this structure has undergone restoration.

813. 513 W. LaVeta 1926 Mediterranean Revival Historical Name: AP Number: 041-142-14 A small, one-story house with stucco facades and a flat roof. Entry is defined by a portico extension with rectilinear openings.

National Register of Historic Places **Continuation Sheet**

Section number _____7 Page _____179 Old Towne Orange Historic District, Orange, CA

814. 517 W. LaVeta

1924 Craftsman Bungalow Historical Name: AP Number: 041-142-13 Double, front-facing gables with shallow pitch and clapboard siding on facades. Forwardmost gable is smaller and forms entry porch overhang. It is supported by tapered piers. Entry is beneath.

815. 525 W. LaVeta

1932 Historical Name: AP Number: 041-142-33 A small clapboard residence located in rear of deep lot. Contains recessed front entry on a modified box plan.

816. 533 W. LaVeta

1923 Craftsman Bungalow Historical Name: AP Number: 041-142-11 Double, front-facing gables with shallow pitch and foremost gable forming entry porch overhang. This gable is supported by tapered piers. Entry is beneath. House is sided in lap siding.

817. 541 W. LaVeta 1924 Historical Name: AP Number: 041-142-10 Non-Contributor

818. 121 N. Lemon c1940 Western False-Front Historical Name: AP Number: 039-173-09 This is a very small, single-story commercial building with a rectangular plan, a single-gabled roof and a western falsefront parapet. The building has been stuccoed and modified on the front facade.

819. 133 N. Lemon 1946 Historical Name: AP Number: 039-173-08 Non-Contributor

National Register of Historic Places Continuation Sheet

Section number 7 Page 180

Old Towne Orange Historic District, Orange, CA

820. **145 N. Lemon** 1922 Western False-Front Historical Name: AP Number: 039-173-25 This is a large industrial building with combination wood-lap siding and ornamental pressed tin. The building features the typical rectangular plan with single-gabled roof falsified by a large stepped parapet which disguises the true smallness of the building. The ornamental pressed tin on the upper portion of the parapet was common to the period and is a rare remaining architectural complement.

821. 153 N. Lemon

1914 Bungalow Historical Name: AP Number: 039-173-06 A single-story bungalow with double front-facing gabled roof. The forwardmost gable, while not covered by a porch, forms the entry portion of the building.

822. 165 N. Lemon
1914 Bungalow
Historical Name:
AP Number: 039-173-05
A single-story box plan house with wide-lap siding and single front-facing
gabled roof. No porch is present at this time. The house is simple and
unadorned.

823. 171 N. Lemon

c1905 Hip Roof Cottage Historical Name: AP Number: 039-173-04 A single-story box plan house with clapboard siding and steep-pitched hip roof. A small, hipped dormer is present on the front portion of the roof. Entry is via a corner recessed porch supported by a classical column.

824. **187 N. Lemon** 1944 Historical Name: AP Number: 039-173-03 Non-Contributor

National Register of Historic Places Continuation Sheet

Section number _____7 Page _____181

Old Towne Orange Historic District, Orange, CA

825. 189 N. Lemon

1906 Hip Roof Cottage

Historical Name: AP Number: 039-173-02

A single-story box plan house with clapboard siding and steep-pitched roof. A small pedimented gable with ornamental shingles is present on the front portion of the roof. Just beneath, in a central location, is a separate porch overhang supported by classical columns. Entry is beneath at center. Since the 1982 survey, this structure has undergone restoration.

826. 193 N. Lemon

c1905 Hip Roof Cottage Historical Name: AP Number: 039-173-01 A single-story box plan house with combination hip and gable roof. The house is built on a box plan and incorporates clapboard siding. What was originally a nearly full-width front porch has since been enclosed. Brick chimneys with ornamental cornices emerge from the center of the roof.

827. 233 N. Lemon

1914 Industrial Historical Name: AP Number: 039-162-21 What were originally two separate, industrial Western, Falsefront style industrial buildings were joined together in later years. The two buildings have similar descriptions in that both are built on a basic rectangular plan and feature a single-gable roof obscured by the large stepped Western Falsefront. The front facades of the building are in rolled tin.

828. 253 N. Lemon

c1920 bungalow Historical Name: AP Number: 039-162-04 A single-story house with multi-gabled shallow pitched roof. The original clapboard siding has since been covered by asbestos shingles. A front-facing gable forms the entry porch overhang and is located along the center of the front facade. This is supported by slender tapered piers. Vertical venting distinguishes this gable face. The entry door is at center and is flanked on either side by side lites.

National Register of Historic Places **Continuation Sheet**

Section number _____7 Page _____182 Old Towne Orange Historic District, Orange, CA

829. 269 N. Lemon c1920 Bungalow Historical Name: AP Number: 039-162-03 A single-story clapboard bungalow with shallow-pitched multi-gable roof. Three-fourths of the front facade is covered by a front-facing gable overhang which forms the entry porch. Entry is beneath and is flanked on either side by half-size side lites. Since the 1982 survey, this structure has been altered with inappropriate stucco siding.

830. 273 N. Lemon Historical Name: AP Number: 039-162-02 Non-Contributor

831. 311 N. Lemon 1909 Bungalow Historical Name: AP Number: 039-152-05 A single-story house with wide-lap siding and steep-pitch gable roof. Entry is via a corner recessed porch supported by Classical columns.

832. 321 N. Lemon 1906 Bungalow Historical Name: AP Number: 039-152-04 A single-story clapboard house with single front-facing gable roof. Entry is located beneath a small gabled entry portico supported by 2 x 4's. Since the 1982 survey, this structure has been altered with inpropriate faux brick panels.

833. 327 N. Lemon 1905 Victorian Historical Name: AP Number: 039-152-03 A two-story house built on an L-plan with shiplap siding and steep-pitched gable roof. The house is a classic rural farm house built prior to 1900 particularly in the Midwest. Entry is in the apex of the ell beneath a separate roofed extension which forms an entry porch. This porch overhang is supported by ornamentally trimmed posts characteristic of the Victorian Period.

834. 328 N. Lemon

ne stand har an an anna an an an an air an a' bhaile a' bhaile a' bhaile an bhaile an bhaile an an an an an an

United States Department of the Interior National Park Service

National Register of Historic Places **Continuation Sheet**

Section number _____7 Page _____183 Old Towne Orange Historic District, Orange, CA

1922 Bungalow Historical Name: AP Number: 039-151-18 A single-story clapboard bungalow with shallow-pitch, multi-gable roof. Α front-facing gable is located in the centermost portion of the front facade and forms an entry porch overhang. Entry is beneath at center and flanked on either side by large three-part picture windows with mullioned sections. 835. 336 N. Lemon

1925 Bungalow Historical Name: AP Number: 039-151-19 A single-story clapboard bungalow with rectangular plan and shallow-pitch, multi-gable roof. The main portion of the house is covered by a single sidefacing gable roof while a centrally located front-facing gable forms the entry porch overhang. This is supported by elephantine piers with ornamental brick bases.

836. 337 N. Lemon 1904 Double Hip Roof Cottage Historical Name: AP Number: 039-152-02 Non-Contributor. Since the 1982 survey, this structure appears to have been replaced.

837. 344 N. Lemon 1958 Historical Name: AP Number: 039-151-20 Non-Contributor

838. 345 N. Lemon 1937 Historical Name: AP Number: 039-152-01 Non-Contributor

839. 356 N. Lemon 1928 Historical Name: AP Number: 039-151-21 Non-Contributor

National Register of Historic Places Continuation Sheet

Section number _____7 Page _____184 Old Towne Orange Historic District, Orange, CA

840. 360 N. Lemon

1923 Bungalow Historical Name:

AP Number: 039-151-22

A single-story bungalow with shallow-pitch, multi-gable roof. The original siding has been covered with asbestos shingles. A centrally located frontfacing gable forms the entry porch overhang and is supported by tapered piers. It appears as though the original screen door is still present on the house and is particularly notable for its ornamentation. Since the 1982 survey, the structure's original screen door has been removed.

841. 388 N. Lemon

1905 Hip Roof Cottage Historical Name: AP Number: 039-151-26 A single-story box plan house with steep-pitch, hip roof. A hitched dormer is present on the front portion of the roof. One-half of the front facade is devoted to a recessed entry porch supported by wood posts.

842. 402 N. Lemon

1905 Hip Roof Cottage Historical Name: AP Number: 039-142-13 A small, single-story box plan house with truncated hip roof. The original siding has been covered with asbestos shingles. A full-width porch is present on the front facade and has its own separate roof extension supported by wood posts. These posts are connected by a slotted balustrade.

843. 405 N. Lemon

1913 Bungalow Historical Name: AP Number: 039-143-12 A single-story house with single side-facing gable roof. The main roof extends forward to form a full-width porch supported in four places by tapered piers. Since the 1982 survey, this structure has been altered by inappropriate siding and porch post.

844. 412 N. Lemon

more thank a second of the second second

United States Department of the Interior National Park Service

National Register of Historic Places Continuation Sheet

Section number 7 Page 185

Old Towne Orange Historic District, Orange, CA

1913 Bungalow Historical Name: AP Number: 039-142-14 A single-story house with wide-lap siding and single-front facing gable roof. One-half of the front facade is devoted to a recessed porch which forms the entry. This porch has since been screened. Since the 1982 survey, this structure has been altered by stucco siding. 845. **415 N. Lemon**

c1900 Hip Roof Cottage Historical Name: AP Number: 039-143-11 A single-story box plan house with clapboard siding and steep-pitch, hip roof which results in an unusual small gable attic dormer. Nearly full-length porch is present and is defined by a separate roof extension supported by wood posts.

846. **419 N. Lemon** 1915 Bungalow Historical Name: AP Number: 039-143-10

A single-story house with wide-lap siding and single side-facing gable roof. A shed dormer is present on the front portion of the roof. A large angled bay window is present beneath the roof, the side of which is the main entry. Since the 1982 survey, this structure has deteriorated.

847. **420 N. Lemon** 1913 Bungalow Historical Name: AP Number: 039-142-15 A single-story bungalow with wide-lap siding and double front-facing gable roof. The forwardmost gable forms the entry porch overhang which is now supported by ornamental iron posts. Cross-ties on the upper gable faces ornament the appearance of the house. Since the 1982 survey, this structure has been altered with inappropriate fencing.

National Register of Historic Places Continuation Sheet

Section number 7 Page 186

Old Towne Orange Historic District, Orange, CA

848. **426 N. Lemon** 1914 Bungalow Historical Name: AP Number: 039-142-16 A single-story bungalow with wide-lap siding and intersecting gable roof. The front-facing gable in combination with the separate roof extension form the entry porch which is supported by wood posts on a solid rail.

849. 428 N. Lemon

1911 Bungalow Historical Name: AP Number: 039-142-17 A single-story house with wide-lap siding and single side-facing gable roof. An unusual appearance is derived from the two small front-facing gabled dormers.

850. 429 N. Lemon
1914 Bungalow
Historical Name:
AP Number: 039-143-09
A single-story bungalow with double front-facing gable roof. The forwardmost
gable forms the entry porch overhang which is supported by wood posts. The
original siding has since been covered with asbestos shingles.

851. 437 N. Lemon
1914 Bungalow
Historical Name:
AP Number: 039-143-08
A single-story bungalow with wide-lap siding and single front-facing gable
roof. An additional front-facing gable, smaller than the main one, forms the
entry porch overhang and is supported by tapered wood piers. Since the 1982
survey, this structure has deteriorated.

852. 442 N. Lemon

1911 Bungalow Historical Name: AP Number: 039-142-18 A single-story house built on an L-plan with steep-pitch, gable roof. house has been considerably altered through the use of stucco and ornam

A single-story house built on an L-plan with steep-pitch, gable roof. The house has been considerably altered through the use of stucco and ornamental iron porch piers. The return of the eaves on the gable and windows clearly indicates the true age and style of the house.

United States Department of the Interior National Park Service

National Register of Historic Places Continuation Sheet

Section number _____7 Page _____187

Old Towne Orange Historic District, Orange, CA

853. 450 N. Lemon
1910 Bungalow
Historical Name:
AP Number: 039-142-19
A single-story house with rectangular plan and single side-facing gable roof.
A centrally located front-facing gable forms the entry porch overhang and is
supported by wood posts. The house is typical of the bungalow period but has
been modified through the use of stucco on the facades.

854. **451 N. Lemon** 1954 Historical Name: AP Number: 039-143-29 Non-Contributor

855. 460 N. Lemon

1917 Vernacular Historical Name: AP Number: 039-142-20 Non-Contributor. A two-story boxy house with single front-facing gable roof where there is a return of the eaves. Entry is via a corner recessed porch supported by wood posts. The house is very simple and unadorned. Since the 1982 survey, this structure has been severely altered by totally remodeling.

856. 469 N. Lemon

1919 Modified Bungalow Historical Name: AP Number: 039-143-04 Non-Contributor. A single-story clapboard bungalow with single front-facing gable roof. Entry is via a corner recessed porch supported by wood posts. Since the 1982 survey, this structure has been severely altered by totally remodeling.

857. 470 N. Lemon

c1920 Bungalow Historical Name: AP Number: 039-142-21 A single-story bungalow cottage with wide lap siding and single front-facing gable roof. Smaller centrally located front-facing gable extends forward to form the entry porch overhang. It is supported by wood posts with a connecting slatted balustrade.

National Register of Historic Places Continuation Sheet

Section number _____7 Page _____188___

Old Towne Orange Historic District, Orange, CA

858. 477 N. Lemon c1920 Bungalow Historical Name: AP Number: 039-143-03 A single-story bungalow with wide lap siding and double front-facing gable roof. The forwardmost gable forms the entry porch overhang and is supported by wood posts.

859. 480 N. Lemon
1906 Bungalow
Historical Name:
AP Number: 039-142-22
A single-story bungalow with wide lap siding and steep-pitch, multi-gable
roof. The roof is fashioned in an L-plan with the short leg of the ell
resulting in a front-facing gable which originally formed a recessed porch
but has since been enclosed.

860. **483 N. Lemon** 1954 Historical Name: AP Number: 039-143-02 Non-Contributor

861. 484 N. Lemon
1910 Bungalow
Historical Name:
AP Number: 039-142-23
A single story house with wide lap siding and single front-facing gable roof.
One-half of the front facade is defined by a recessed porch supported by
ornamental wood posts.

862. 492 N. Lemon 1913 Hip Roof Cottage Historical Name: AP Number: 039-142-25 A single-story house built on a L-plan with a steep-pitch, hip and gable roof. The apex of the ell once featured an open porch but has since been enclosed. The shiplap siding and roofline profile indicate that the house may well be much older than the 1913 date.

NPS Form 10-900-a (8-86)

OMB Approval No. 1024-0018

United States Department of the Interior National Park Service

National Register of Historic Places Continuation Sheet

Section number _____7 Page _____189 Old Towne Orange Historic District, Orange, CA

863. 504 N. Lemon 1923 Hip Roof Cottage Historical Name: AP Number: 039-131-14 A multi-gabled, stucco sided, modified L-plan with corner entry. Original tall and narrow multi-paned windows are present with some double-hung windows.

864. 512 N. Lemon 1923 Hip Roof Cottage Historical Name: AP Number: 039-131-15 A small, wood lapped sided residence with single gable roof, box plan. Front entry has slope, small decorative overhang.

865. 520 N. Lemon 1947 Historical Name: AP Number: 039-131-16 Non-Contributor

866. 528 N. Lemon 1923 Hip Roof Cottage Historical Name: AP Number: 039-131-17 A small box plan Bungalow residence with front gable over front porch. Small columns on concrete piers hard up front gable. A pair of oversize single windows with mullioned top flank at the entry. Garage emulates front house roof line.

867. 536 N. Lemon 1920 Hip Roof Cottage Historical Name: AP Number: 039-131-18 A stucco modified box plan, with shed roof over entry and peaked roof over shed roof. Recessed entry with front porch.

868. 544 N. Lemon 1921 Hip Roof Cottage Historical Name: AP Number: 039-131-19 A stucco residence with 2 front facing gables, one covering front entry. Stone has been added on corner facade.

National Register of Historic Places Continuation Sheet

Section number _____7 Page _____190

Old Towne Orange Historic District, Orange, CA

here a series a series and the second market the second and the second second and the second s

869. **554 N. Lemon** 1923 Hip Roof Cottage Historical Name: AP Number: 039-131-20 Non-Contributor

870. **566 N. Lemon** 1962 Historical Name: AP Number: 039-131-21 Non-Contributor

871. 568 N. Lemon
1923 Hip Roof Cottage
Historical Name:
AP Number: 039-131-22
A wood lapped sided Bungalow, rectangular plan, two front facing gables.
Front porch enhanced by small elephantine pillars on concrete piers. Front
entry flanked by a large picture window.

872. 578 N. Lemon
1923 Hip Roof Cottage
Historical Name:
AP Number: 039-131-23
A small wood lapped sided Bungalow with two front facing gables in box plan.
Porch leading to entry flanked by two large picture windows.

873. 580 N. Lemon
1922 Hip Roof Cottage
Historical Name:
AP Number: 039-131-24
Two front facing gables on a wood lap sided, box plan bungalow home. Two
pillars concrete piers hold up front gable. Entry is flanked by a pair of
double hung windows.

874. 592 N. Lemon
1924 Hip Roof Cottage
Historical Name:
AP Number: 039-131-25
A small wood lap sided Bungalow, box plan style with front gable covering
entry. Two layer windows flank entry. An extension of roof line suggests
possible addition.

OMB Approval No. 1024-0018

United States Department of the Interior National Park Service

National Register of Historic Places Continuation Sheet

Section number _____7 Page _____191__

Old Towne Orange Historic District, Orange, CA

875. 594 N. Lemon
1922 Hip Roof Cottage
Historical Name:
AP Number: 039-131-26
A small wood lap sided, box plan residence, no gables. Flat front with two
windows flanking front door.

876. 143 S. Lemon

1928 Mediterranean Revival Historical Name: Orange Armory AP Number: 390-663-04 This is a Mediterranean Revival influenced building constructed for an institutional purpose. This is a large, two-story, rectangular plan building with a single gable roof covered in adobe tiles. The facades are sided in textured stucco. The fenestration includes regularly spaced, multi-paned windows at the second story and two large mullioned windows on the first story flanking either side of the main entry. The entry is reached via a stoop and is composed of a large arched entry of rusticated stone. A small gabled parapet on the front further emphasizes the entry. The building is in well-maintained condition and exhibits its original architectural integrity.

877. 146 S. Lemon

c1910 Hip Roof Cottage Historical Name: AP Number: 390-662-15 Box plan house with a steep-pitched, hip roof and wide overhanging eaves. House is now sided in asbestos shingles. Entry is beneath a separate, symmetrically placed, porch overhang supported by Classical columns. Either side of the main entry is flanked by large transomed, picture windows.

878. **156 S. Lemon** c1910 Vernacular Historical Name: AP Number: 390-662-14 Rectangular plan house with single, front-facing gable roof with steep pitch to gable. House is sided in clapboard. Main entry is at front center beneath separate tilt-up porch overhang. Large transomed, picture windows flank either side of entry.

OMB Approval No. 1024-0018

United States Department of the Interior National Park Service

National Register of Historic Places Continuation Sheet

Section number _____7 Page _____192___

Old Towne Orange Historic District, Orange, CA

879. **166 S. Lemon** 1916 Historical Name: AP Number: 390-662-13 Non-Contributor

880. 173 S. Lemon 1923 Mediterranean Revival Bungalow Court Historical Name: AP Number: 390-663-05 This U-plan Bungalow Court is comprised of a boxy formatted building with flat roof and tiled ridges. Siding is in stucco. This is one of two Bungalow Courts located in Old Towne Orange and is part of a very popular movement in the early 20's for consolidating families under one roof. At the rear of this structure is a small cottage facing the alley. It has a gable roof and weatherboard siding and simple, multi-pane wood sash windows.

881. 176 S. Lemon c1915 Craftsman Historical Name: AP Number: 390-662-12 A one and one-half story house with side-facing, gable roof and single, front-facing gable to dormer. House is sided in clapboard. Main entry is beneath corner porch which is recessed beneath main roof. Porch wall and support piers are of brick. Craftsman slatting and transomed windows adorn the front gabled dormer.

882. 186 S. Lemon
1924 California Bungalow
Historical Name:
AP Number: 390-662-11
This is a small, low-to-the-ground, bungalow cottage with shallow-pitched,
gable roof. Front-facing gable forms entry porch overhang and is supported
by wood posts. Main entry is at center beneath and is flanked by side
lights.

OMB Approval No. 1024-0018

United States Department of the Interior National Park Service

National Register of Historic Places Continuation Sheet

Section number _____7 Page _____193

Old Towne Orange Historic District, Orange, CA

883. 206 S. Lemon

c1910 Hip Roof Cottage Historical Name:

AP Number: 390-652-21

Modified L-plan house with a steep-pitched, hip roof contrasted by frontfacing gable with return at the eaves. Roof extends forward in apex of ell to form entry porch overhang and is supported by Modified Classical columns. Ornamental vent on front-facing gable is complemented by a pair of doublehung windows below.

884. 210 S. Lemon

c1920 Craftsman Bungalow Historical Name: AP Number: 390-652-21

A duplex bungalow with box plan and single main, front-facing gable roof. Just below is a secondary, front-facing gable which forms entry porch overhang and is supported by tapered piers. A pair of doors is just beneath and flanked on either side by a large transomed picture window. Ornamental purlins are located beneath the eaves on front portion of house.

885. **216 S. Lemon** 1967 Historical Name: AP Number: 390-652-20 Non-Contributor

886. 223 S. Lemon c1915 Bungalow Historical Name: AP Number: 390-653-02 Low-to-the-ground bungalow with very shallow pitched roof comprised of a single, front-facing gable. House is sided in clapboard. A secondary roof extension forms entry porch overhang and is supported by piers comprised of concrete bases and wood posts on top. Two pairs of windows flank either side of main entry. 225 S. Lemon is a separate unit with living quarters above the garage. It is built with bungalow features.

National Register of Historic Places Continuation Sheet

Section number _____7 Page _____194__

Old Towne Orange Historic District, Orange, CA

887. 228 S. Lemon
1921 Bungalow
Historical Name:
AP Number: 390-652-19
A tri-gable roof with each gable front-facing. Two forwardmost gables are
supported by tapered piers comprised of concrete bases and wood tops.
Arrangement of gables is in a symmetrical fashion. House is sided in
clapboard. Gable venting and slatting adorn gable faces.

888. **233 S. Lemon** 1961 Historical Name: AP Number: 390-653-03 Non-Contributor

889. **244 S. Lemon** 1978 Historical Name: AP Number: 390-652-22 Non-Contributor

890. **245 S. Lemon** 1963 Historical Name: AP Number: 390-653-04 Non-Contributor

891. **253 S. Lemon** 1924 Historical Name: AP Number: 390-653-05 Non-Contributor

ł

892. **262 S. Lemon** 1921 Bungalow Historical Name: AP Number: 390-652-15 Small, low-to-the-ground bungalow with double, front-facing gables. Smaller gable symmetrically placed beneath main gable and forms entry porch overhang. It is supported by wood posts. Entry is at center and flanked by double-hung window on either side.

National Register of Historic Places Continuation Sheet

Section number _____7 Page _____195___

Old Towne Orange Historic District, Orange, CA

893. **263 S. Lemon** 1964 Historical Name: AP Number: 390-653-06 Non-Contributor

894. **270 S. Lemon** 1963 Historical Name: AP Number: 390-652-14 Non-Contributor

895. 272 S. Lemon c1920 Bungalow Historical Name: AP Number: 390-652-14 Low-to-the-ground bungalow cottage with shallow pitched, multi-gable roof. Single, front-facing gable forms entry porch overhang and is supported by wood piers. House is sided in clapboard.

896. **277 S. Lemon** 1963 Historical Name: AP Number: 390-653-07 Non-Contributor

897. 290 S. Lemon c1910 Hip Roof Cottage Historical Name: AP Number: 390-652-13 Clapboard siding and hip roof with small, pedimented gable on center front of roof. Roof extension forms entry porch overhang and is supported by Classical columns.

898. **311 S. Lemon** 1971 Historical Name: AP Number: 390-603-18 Non-Contributor

National Register of Historic Places Continuation Sheet

Section number 7 Page 196

Old Towne Orange Historic District, Orange, CA

899. **335 S. Lemon** 1963 Historical Name: AP Number: 390-603-17 Non-Contributor

900. **341 S. Lemon** 1971 Historical Name: AP Number: 390-603-16 Non-Contributor

901. **349 S. Lemon** 1971 Historical Name: AP Number: 390-603-15 Non-Contributor

902. **357 S. Lemon** 1922 Historical Name: AP Number: 390-603-23 A single story structure with high-pitched, single gabled roof and crown molding. Siding is wood with double-hung wood windows and large facia board and clover detail embelishment.

903. **367 S. Lemon** 1922 Historical Name: AP Number: 390-603-23 Non-Contributor

904. **385 S. Lemon** 1990 Historical Name: AP Number: 390-603-21 Non-Contributor

National Register of Historic Places Continuation Sheet

Section number _____7_ Page _____197__

Old Towne Orange Historic District, Orange, CA

905. **112 E. Maple**

1912 Brick Commercial Historical Name: AP Number: 039-251-22 A large brisk commercial single-story box plan building. Distinctive entublature with projecting cornice is present. A large bay single-paned window flanks the entry.

906. 137 E. Maple

c1905 Classic Box Historical Name: AP Number: 039-241-12 A large, two-story box plan house with multi-hip and gable roof built in a modified Classic Box tradition. The house is considerably altered from its original form with the addition of a chapel building adjacent and a firststory storefront. The remaining portions of the house have also since been stuccoed. Since the 1982 survey, this structure has been altered to make the storefront a little more compatable.

907. 203 E. Maple

c1920 Bungalow Historical Name: AP Number: 039-242-11 A single-story bungalow with lap siding and single-gable roof with sidefacing gables. A smaller, front-facing gable entry portico is supported by colonial-like columns. The original hardwood door with plate glass windows is still present and is flanked on either side by 3-part transomed windows.

908. 211 E. Maple

c1915 Craftsman Historical Name: AP Number: 039-242-12 A large two-story house with clapboard siding and multi-gable roof. The second story is located over the rear half of the house. A full-width front porch, comprised of a front-facing gable overhang, is supported by wide piers with brick bases and wood posts on top. These piers are connected by a slatted balustrade whose theme is carried out in the upper gable face above.

National Register of Historic Places Continuation Sheet

Section number 7 Page 198

Old Towne Orange Historic District, Orange, CA

909. 225 E. Maple

c1915 Craftsman Historical Name:

AP Number: 039-242-13

This house is identical to the one at 211 E. Maple--a large two-story house with clapboard siding and multi-gable roof. The second story is located over the rear half of the house. A full-width front porch, comprised of a frontfacing gable overhang, is supported by wide piers with brick bases and wood posts on top. These piers are connected by a slatted balustrade whose theme is carried out in the upper gable face above.

910. 227 E. Maple

1910 Craftsman bungalow Historical Name: AP Number: 039-242-14 A single-story bungalow

A single-story bungalow with wide lap siding and double, front-facing gable roof. The foremost gable originally formed the entry porch overhang but has since been enclosed. The original tapered piers are still present. The other front-facing gable results in an angled bay window and is adorned by three large windows on either of the panes. Ornamental purlins and ornamental transoms in the upper gable faces further adorn the house.

911. 235 E. Maple

c1905 Hip Roof Cottage Historical Name: AP Number: 039-242-15 A 1-1/2 story clapboard house with multi-gable and hip roof. The house has a full wrap-around porch on one corner which is supported by wide clapboard piers. A small hipped dormer with two sash windows is present on the front portion of the roof, as is a small pedimented gable with shingle embellishment.

912. **319 E. Maple**

c1900 Modified Hip Roof Cottage Historical Name: AP Number: 039-243-12

A one-story house with a steep-pitched, hip and gable roof. A pedimented gable with fish-scale shingles and a louvered transom extend forward to form the entry porch overhang. This overhang is supported by ornate turned columns, typical of the Victorian era. Except for the porch posts, the entire house below the eaves has been altered through the replacement of the windows and door and by stuccoing the facades.

National Register of Historic Places Continuation Sheet

Section number 7 Page 199

Old Towne Orange Historic District, Orange, CA

913. **320 E. Maple** 1916 Modified Bungalow Historical Name:

AP Number: 039-253-22

A single-story bungalow with ornamental lap siding and tri-gable roof. The main portion of the house is covered by a single-gable roof with side-facing gables. A full-width, front-facing gable forms the entry porch overhang. This is supported by wide piers with concrete bases and wood posts on top. The original wood door with plate glass windows is still present on the center of the front facade. Since the 1982 survey, this structure has been altered with an inappropriate lattice porch screen.

914. 327 E. Maple

1917 Bungalow Historical Name: AP Number: 039-243-13 A single-story bungalow with ornamental lap siding and multi-gable roof. The house was built on a modified L-plan, the entry being in the apex of the ell. The brickwork on the lower foundation of the house was probably a later addition.

915. 335 E. Maple

1920 Mediterranean Revival Historical Name: AP Number: 039-243-14

A single-story box plan house with stucco facades and flat roof. The house is fashioned in a symmetrical manner with the center portion of the front facade devoted to a large entry portico which features large, arched openings and a raised parapet with Mission influence. On either side are large, transomed picture windows over which hang adobe tile hoods. Ornamental attic vents are present just above these hoods. The original door with multi-paned windows is still present and is flanked on either side by side lites.

916. 336 E. Maple

1915 Bungalow Historical Name: AP Number: 039-253-21

A single-story clapboard bungalow with double, front-facing gable roof. The forwardmost gable forms the entry porch overhang and is supported by tapered piers. The main entry is beneath, featuring a very elaborate wood screen door with spindlework. Large, transomed picture windows are located on either side of the door.

National Register of Historic Places Continuation Sheet

Section number _____7 Page _____200

Old Towne Orange Historic District, Orange, CA

917. **405 E. Maple** c1915 Bungalow Historical Name: AP Number: 039-244-10 A single-story bungalow with rectangular plan, wide lap siding and a singlegable roof with side-facing gables. The centermost portion of the front facade features an extension of the roof which culminates in an entry porch overhang supported by slim wood posts. Main entry is beneath at center and is flanked on either side by side lites.

918. **413 E. Maple** 1911 Bungalow Historical Name: AP Number: 039-244-11 A single-story bungalow with wide lap siding and multi-gable roof. The house is built in a modified L-plan with the short leg of the ell resulting in the entry porch overhang. This is supported by wide piers. The original door with plate glass windows is still present. Ornamental purlins and an ornamentally framed transom vent, as well as two ornamental brick chimneys, adorn the house.

919. **419 E. Maple** 1909 Craftsman Historical Name: AP Number: 039-244-12 A 1-1/2 story clapboard house with single-gable roof with side-facing gables. A shed dormer rises out of the front portion of the roof and includes 3 sash windows. One-half of the front facade is devoted to a large recessed porch supported by wide clapboard piers. The remaining portion of the front facade is composed of an angled bay window with a single sash window in each of the bay panes.

920. **427 E. Maple** 1915 Craftsman Historical Name: AP Number: 039-244-13 A 1-1/2 story house with wide lap siding and gable roof. A large, frontfacing gable dormer is present on the front portion of the roof. The main roof extends forward to form a full-width porch overhang and is supported by wood piers. The original door with multi-plate glass windows is still present.

National Register of Historic Places Continuation Sheet

Section number 7 Page 201

Old Towne Orange Historic District, Orange, CA

921. **437 E. Maple** 1905 Classic Box Historical Name: AP Number: 039-244-14 An ample two-story clapboard house with combination hip and gable roof. The house features a large, corner wrap-around porch supported by classical columns atop a clapboard porch wall. The frontmost leg of the house includes a front-facing gable with shingles and ornamental transomed vent. The original door and screen door are still present on the house. Since the 1982 survey, this structure has been altered with appropriate rear addition.

922. 515 E. Maple

1923 Mediterranean/Italianate Revival Historical Name: Dr. Domann House AP Number: 386-081-10

This is a two-story Mediterranean Revival style house with specific Italianate influence. The house features an adobe tile, hip roof with a small arched dormer. The house is constructed in brick which is unique in Orange. Built on a box plan, a symmetrical format is utilized in the arrangement of the central entry and the fenestration. The door is sheltered by a wide portico with a shallow arch; this portico is supported by decorative scroll brackets like those beneath the wide eaves at the cornice line. Each of the windows and the cornice line is ornamentally framed in contrasting brick; this same brick work is carried out in the cornice of the chimney. The house is excellently maintained and remains in its original state. This house has been determined eligible for the National Register.

923. **526 E. Maple** 1922 Bungalow Historical Name: AP Number: 386-071-17 A single-story bungalow with rectangular plan and single-gable roof. The original siding has since been covered by asbestos shingles. The house has an unusual entry which is comprised of a gabled portico within the large arched opening. Below is a large door with ornamentally paned side lites and a large, arched transom above. Two small eyelid dormers with lattice venting are present also on the front portion of the roof.

National Register of Historic Places Continuation Sheet

Section number _____7 Page _____202

Old Towne Orange Historic District, Orange, CA

924. **527 E. Maple** 1914 Craftsman Historical Name: AP Number: 386-081-11 A large two-story house with ornamental lap siding and multi-gable roof. The second story portion of the house is located over the rear half of the structure. The lower front is comprised of two front-facing gables, the forwardmost of which forms a large entry porch overhang. This is supported by piers comprised of brick bases and wood posts on top.

925. **535 E. Maple** c1915 Bungalow Historical Name: AP Number: 386-081-12 A single-story bungalow with wide lap siding and multi-gable roof. The main portion of the front of the house is comprised of two front-facing gables:

portion of the front of the house is comprised of two front-facing gables; the forwardmost one acts as an entry porch overhang. Cross-ties and triangular bracket supports adorn the upper gable faces; below the original wood door with plate glass windows is still present.

926. 536 E. Maple

1914 Bungalow Historical Name: AP Number: 386-071-16 A single-story bungalow with wide lap siding and multi-gable roof. The front of the house is articulated by doublefront-facing gables, the forwardmost of which acts as the entry porch overhang. It is supported by wide piers composed of bricks; the bricks are connected by a slatted ballustrade.

927. **604 E. Maple** 1931 Spanish Colonial Revival Historical Name: AP Number: 386-072-01 A single-story house built on an L-plan with stucco facades and gable roof with adobe tiles. Entry is at the apex of the ell and sheltered by a small, adobe tiled hood. An ornamental chimney is present on the side of the house.

National Register of Historic Places Continuation Sheet

Section number 7 Page 203

Old Towne Orange Historic District, Orange, CA

928. **605 E. Maple** 1913 Modified Post Victorian Historical Name: AP Number: 386-082-09 A two-story house with steep-pitched, gable roof and a full-width front porch present at the first story of the lower front facade. This porch has its own separate roof overhang which is supported by wood posts.

929. **610 E. Maple** 1954 Historical Name: AP Number: 386-072-18 Non-Contributor

930. 613 E. Maple

1914 Craftsman Historical Name: AP Number: 386-082-10

A 1-1/2 story house with wide lap siding and single-gable roof with sidefacing gables. A large, front-facing, gabled dormer is also present. The main roof extends forward to form a full-width porch overhang, supported by tapered piers on the outermost extremities and by narrow turned posts in the center portion of the porch. These posts harken back to the Victorian-type embellishment. The original door with plate glass windows is still present and is flanked on either side by a trio of sash windows.

931. 616 E. Maple

1912 Hip Roof Cottage Historical Name: AP Number: 386-072-17 A two-story clapboard house with multi-hip and gable roof. The high hip dormer is present on the front facade. What was originally a recessed corner porch was enclosed circa 1930 and replaced by gabled porticos supported by wide ornamental posts. Since the 1982 survey, this structure has been altered with appropriate porch rail and columns.

National Register of Historic Places Continuation Sheet

Section number 7 Page 204

Old Towne Orange Historic District, Orange, CA

932. **621 E. Maple** c1915 Bungalow Historical Name: AP Number: 386-082-11 A single-story bungalow with wide lap siding and single-gable roof with sidefacing gables. A low shed dormer is also present on the front portion of the roof. One-half of the front facade is devoted to a large recessed porch supported by brick piers. The house features a double entry, each with the original door.

933. **629 E. Maple** 1971 Historical Name: AP Number: 386-082-12 Non-Contributor

934. 633 E. Maple 1909 Craftsman Historical Name: AP Number: 386-082-13 A two-story Craftsman home with wide lap siding and multi-gable roof. A wide shed dormer with two pairs of transomed windows is present on the front portion of the roof. The main roof extends forward to form a full-width porch, supported by stone piers connected by a long, low stone wall. This same stone work is featured in the chimney at the rear of the house. The original door is still present and is flanked on either side by a trio of sash windows.

935. **704 E. Maple** c1905 Hip Roof Cottage Historical Name: AP Number: 386-073-01 A single-story clapboard house with hip and gable roof. The house features a large, corner, wrap-around porch supported by classical columns with

large, corner, wrap-around porch supported by classical columns with Corinthian capitals. Both the front and side wings of the house have gables and feature large transomed windows with ornamental transoms in the upper gable faces.

National Register of Historic Places Continuation Sheet

Section number 7 Page 205

Old Towne Orange Historic District, Orange, CA

936. 714 E. Maple

1920 Victorian Historical Name: AP Number: 386-073-18 Two-story, multi-gabled Victorian with covered porch entry and secondary entry on side. Front facing window is large with leaded glass mullion. Clapboard siding with wrapping eaves. Porch overhang is supported by two ornate columns.

937. 910 E. Maple

1941 Historical Name: AP Number: 386-061-01 Non-Contributor

938. **115 W. Maple** 1924 Bungalow Historical Name: AP Number: 039-163-10 A single-story clapboard bungalow with double front-facing gable roof. A small attached porch is located between the forwardmost and rear gables, and the entry is just beneath. Since the 1982 survey, this structure has undergone restoration.

939. 123 W. Maple

1917 Brick Commercial Historical Name: Sunshine Apartments AP Number: 039-163-09 This is a two-story brick apartment building built on a rectangular plan. Sash windows are spaced at regular intervals across both the first and second stories. The roof is flat, but wide eaves shelter the horizontal banding at the cornice line. The two street entries are simple with just a low stoop and accompanying side walls marking their location. The building is typical of the brick commercial and multi-family buildings that were constructed during the twenties. The building is in fair condition but exhibits its original architectural integrity. Since the 1982 survey, this structure has undergone restoration.

940. **139 W. Maple** 1917 Historical Name: AP Number: 039-163-09 Non-Contributor

National Register of Historic Places Continuation Sheet

Section number _____7 Page _____206__

Old Towne Orange Historic District, Orange, CA

941. **210 W. Maple** 1965 Historical Name: AP Number: 039-173-22 Non-Contributor

942. 224 W. Maple

c1920 Bungalow Historical Name: AP Number: 039-173-19 A single-story bungalow with wide lap siding and single front-facing gable roof. The house has been modified using stucco on the side facades and brick on the lower foundation wall.

943. 235 W. Maple 1920 Historical Name: AP Number: 039-162-23 Non-Contributor

944. **305 W. Maple** 1924 Historical Name: AP Number: 039-161-17 Vacant Lot

945. **402 W. Marietta** 1924 Mediterranean Revival Historical Name: AP Number: 390-651-08 Small, box plan house with stucco sides, flat roof and tiles at roof edges. Front entry is at center beneath arcaded portico. Large picture windows are on either side.

946. **408 W. Marietta** 1924 Mediterranean Revival

Historical Name: AP Number: 390-651-07 Small, box plan house with stucco siding and flat roof. Main entry is beneath large recessed arched opening and is flanked by large picture windows on either side.

National Register of Historic Places Continuation Sheet

Section number _____7 Page _____207

Old Towne Orange Historic District, Orange, CA

947. **409 W. Marietta** 1924 Mediterranean Revival Historical Name: AP Number: 390-651-03 A box plan house with stucco sides and adobe tiles at roof ridges. House is distinguished by raised parapet and corner pilasters. Also included is a prominent pilastered entry and tile hoods above picture windows on either side.

948. 414 W. Marietta

1924 Mediterranean Revival Historical Name: AP Number: 390-651-06 Small, box plan duplex with stucco siding and flat roof. Adobe tiles are at roof ridges. Each entry is beneath an arched portico.

949. 415 W. Marietta

1924 Mediterranean Revival Historical Name: AP Number: 390-651-04 Small, box plan house with stucco siding and flat roof. Adobe tiles are at roof ridges. Main entry is at center and is flanked by three-part windows on either side.

950. **418** Montgomery Pl. 1915 Historical Name: AP Number: 041-142-31 Non-Contributor

951. **436** Montgomery Pl. 1972 Historical Name: AP Number: 041-142-21 Non-Contributor

952. **442** Montgomery Pl. 1970 Historical Name: AP Number: 041-142-20 Non-Contributor

National Register of Historic Places Continuation Sheet

Section number _____7 Page _____208

Old Towne Orange Historic District, Orange, CA

953. **448** Montgomery Pl. 1979 Historical Name: AP Number: 041-142-19 Non-Contributor

954. **456** Montgomery Pl. 1924 Historical Name: AP Number: 041-142-18 Non-Contributor

955. **472** Montgomery Pl. 1939 Historical Name: AP Number: 041-142-30 Non-Contributor

956. **480** Montgomery Pl. 1949 Historical Name: AP Number: 041-142-34 Non-Contributor

957. 524 E. Moreland Dr.

c1928 Mediterranean Revival Historical Name: AP Number: 390-442-02 A single-story bungalow with stucco facades and a flat roof. Entry is via a projection from the main facade defined by vertical walls with large arched openings. To either side of the porch portico is a large picture window with multi-paned transom covered by a tiled hood. The main facade of the house features a raised parapet. The porch also has a raised parapet.

958. **536 E. Moreland Dr.** c1928 Mediterranean Revival Historical Name: AP Number: 390-442-03 This house is identical to the one next door at 524 Moreland with the exception that the windows are large, three-part windows with narrow, doublehung windows flanking a large single-pane window with multi-pane transom.

National Register of Historic Places Continuation Sheet

Section number 7 Page 209

Old Towne Orange Historic District, Orange, CA

959. **544 E. Moreland Dr.** 1948 Historical Name: AP Number: 390-442-04 Non-Contributor

960. **600 E. Moreland Dr.** 1945 Historical Name: AP Number: 390-442-05 Non-Contributor

961. 604 E. Moreland Dr.

c1928 Mediterranean Revival Historical Name: AP Number: 390-442-06 A single-story, box plan house with stucco facades and flat roof. Entry is at center via a portico projection which features a large arched opening. To either side are a pair of casement windows with tile hoods. The front facade has a stepped parapet and raised pilasters; the roof line all around is ornamented with adobe tiles.

962. **608 E. Moreland Dr.** c1928 Mediterranean Revival Historical Name: AP Number: 390-442-07 A single-story, box plan house with stucco facades and flat roof. Entry is via an arched portico projection flanked on either side by a large, doublehung window.

963. 612 E. Moreland Dr. c1915 Craftsman Bungalow Historical Name: AP Number: 390-442-08 A single-story bungalow with shallow-pitched, multi-gable roof and sheathing which includes wide lap siding at the lower foundation wall and clapboard above. Entry is via a recessed gable over a porch supported by wide piers. Jigsawn ornamentation and exposed beams adorn the porch gable face. All windows are ornamentally framed.

National Register of Historic Places Continuation Sheet

Section number _____7 Page _____210

Old Towne Orange Historic District, Orange, CA

964. **621 E. Moreland Dr.** 1950 Historical Name: AP Number: 390-441-10 Non-Contributor

965. **114 N. Olive** 1910 Western False Front Historical Name: AP Number: 039-173-21 A single-story rectangular plan commercial structure with a single-gable roof and a rolled tin falsefront. The building has been modified but is interesting for its early history.

966. **119 N. Olive** 1914 Brick Commercial Historical Name: AP Number: 039-174-09 Non-Contributing. The current building is relatively new. Also refer to National Register Plaza Historic District list.

967. **123 N. Olive** 1925 Brick Commercial Historical Name: Ward's Cookie Factory AP Number: 039-174-08 See National Register Plaza Historic District list.

968. **124 N. Olive** 1957 Historical Name: AP Number: 039-173-15 Non-Contributor

969. **152 N. Olive** 1985 Historical Name: AP Number: 039-173-26 Non-Contributor

970. **153 N. Olive** Historical Name: AP Number: 039-174-25 Non-Contributor

National Register of Historic Places Continuation Sheet

Section number 7 Page 211

Old Towne Orange Historic District, Orange, CA

971. **193 N. Olive** Historical Name: AP Number: 039-174-01 Non-Contributor

972. 200 N. Olive 1970 Historical Name: AP Number: 039-163-06 Non-Contributor

973. 204 N. Olive c1905 Victorian Historical Name: AP Number: 039-162-11 A two-story house with steep-pitch, multi-gable roof and probably clapboard siding which is now covered by asbestos shingles. There is a full-width and partial wraparound porch on the lower front facade covered by its own separate roof extension which includes a pedimented gable with ornamental shingles. A large 3-part window ornaments the front facade. Since the 1982 survey, this structure has undergone restoration.

974. 213 N. Olive 1915 Craftsman Bungalow Historical Name: AP Number: 039-163-08 A single-story bungalow cottage with ornamental lap siding and double, frontfacing gable roof. Forwardmost gable forms the entry porch overhang and is supported by wide wood piers. Ornamental purlins and lattice work in the upper gable faces adorn the house.

975. **214 N. Olive** 1923 Spanish Colonial Revival Bungalow Court Historical Name: AP Number: 039-162-12 A very simple one-story boxy building with flat roof and stucco facades. The structure is simple, basic, and unadorned.

976. **223 N. Olive** 1972 Historical Name: AP Number: 039-163-07 Non-Contributor

National Register of Historic Places Continuation Sheet

Section number 7 Page 212

Old Towne Orange Historic District, Orange, CA

977. **224 N. Olive** 1958 Historical Name: AP Number: 039-162-13 Non-Contributor

978. **236 N. Olive** 1910 Craftsman Bungalow Historical Name: AP Number: 039-162-14 This is a large two-story house which plays upon the bungalow styling in a most unusual way. The house features three large front-facing gables, all arranged in symmetrical fashion. The center entry is beneath a porch with a separate roof overhang supported by wide tapered piers. Just above is a recessed balcony with slatted balustrade.

979. 243 N. Olive 1908 Gable Roof Cottage Historical Name: AP Number: 039-163-05 A 1-1/2 story house with clapboard siding and steep pitch, gable roof. A small hip dormer is present on the front portion of the roof. The main roof extends forward to form a full width porch which is supported by classical columns. The house is an interesting variation on the Classical Revival style which incorporates some Craftsman features in the way the porch is formed by the main roof extension.

980. **244 N. Olive** 1967 Historical Name: AP Number: 039-162-15 Non-Contributor

981. **251 N. Olive** 1923 California Ranch Historical Name: AP Number: 039-162-16 This is an unusual structure for Orange. It appears as though it may have originally been small apartments or some sort of lodging house. It is a single-story structure with gable roof which extends forward to form a large arcade supported by wood posts. Most notable is the wide board and batten siding.

A smaller

United States Department of the Interior National Park Service

National Register of Historic Places **Continuation Sheet**

Section number <u>7</u> Page <u>213</u>

Old Towne Orange Historic District, Orange, CA

982. 254 N. Olive c1905 Hip Roof Cottage Historical Name: AP Number: 039-162-16 A single-story box plan house with clapboard siding and steep pitched, hip roof. A small hip dormer is present on the front portion of the roof. Entry is via a corner recessed porch supported by a Classical column.

983. 261 N. Olive

c1911 Bungalow Historical Name: AP Number: 039-163-03 A two-story house with steep-pitched, multi-gable roof and combination board and batten and lap siding. The front-facing gable extends forward to form an entry porch overhang which is supported by wood piers on arroyo stone bases. A small gable dormer is also present.

984. 264 N. Olive

1919 Bungalow Historical Name: AP Number: 039-162-17 A single-story clapboard bungalow with double front-facing gable roof. The forwardmost gable forms the entry porch overhang and is supported by wood Since the 1982 survey, this structure has been altered with piers. inappropriate fencing.

985. 272 N. Olive 1919 Bungalow Historical Name: AP Number: 039-162-18 A single-story clapboard bungalow with double front-facing gable roof. The forwardmost gable forms the entry porch overhang and is supported by wood piers. Since the 1982 survey, this structure has been altered with inappropriate fencing.

986. 277 N. Olive c1915 Bungalow Historical Name: AP Number: 039-163-02 A single-story bungalow with single front-facing gable roof. parallel gable also front-facing forms a full-width porch and is supported by very wide tapered piers. The building is faced in stucco and features a double entry indicating original duplex usage.

National Register of Historic Places Continuation Sheet

Section number _____7 Page _____214__

Old Towne Orange Historic District, Orange, CA

987. 287 N. Olive 1921 Bungalow Court Historical Name: AP Number: 039-163-02 A bungalow court of simple, single-story bungalow with clapboard siding and single front-facing gable roof. The first entry is via a recessed corner porch supported by wood posts and connecting slatted balustrade. The second entry is in the rear.

988. **288 N. Olive** 1895 Victorian w/Queen Anne influence Historical Name: AP Number: 039-162-19 This is a large 2-1/2 story Victorian house with a Classical Revival entry porch. As is typical of the Victorians and of the Queen Anne Victorians in particular, the house is large and has irregular proportions and an irregular roofline. The roof includes hip, gable and conical sections. The house is sided in ship-lap siding except for the pedimented entry gable which features wavy shingles. The front-facing gable includes a conical hood, paired sash windows and an ornamental moulding between the windows on the first and second level. The entry porch features a pedimented gable supported by

Classical columns. It appears that this porch has been partially enclosed, but was probably done so in the early part of the century. The house is in excellent condition and exhibits its original architectural appearance.

989. 291 N. Olive

1921 Bungalow Historical Name: AP Number: 039-163-01 A single-story clapboard bungalow with multi-gable roof. The house is predominantly covered by a single-gable roof with side-facing gables, while three front-facing gables are also present. The main roof extends forward to form a full-width porch and is supported by Colonial columns. Main entry is at center and is flanked on either side by a series of multi-paned windows.

990. **304 N. Olive** c1920 Bungalow Historical Name: AP Number: 039-152-08 A single-story clapboard bungalow with double front-facing gable roof. The main entry door is shielded by a slight canope overhang flanked on either side by casement windows.

National Register of Historic Places Continuation Sheet

Section number _____7 Page _____215

Old Towne Orange Historic District, Orange, CA

991. **312 N. Olive** c1920 Bungalow Historical Name: AP Number: 039-152-09 A single-story clapboard bungalow with single front-facing gable roof. What was originally a full porch has since been enclosed. The house is otherwise simple and unembellished.

992. **320 N. Olive** 1920 Bungalow Historical Name: AP Number: 039-152-10 A single-story bungalow with lap siding and double front-facing gable roof. The forwardmost gable forms the entry porch overhang and is supported by ornamental iron piers, a replacement for the original.

993. **321 N. Olive** 1915 Bungalow Historical Name: AP Number: 039-153-04 A single-story bungalow with shallow pitch, gable roof. Centrally located front-facing gable extends forward to form an entry porch and is supported by tapered piers.

994. **331 N. Olive** 1921 Bungalow Historical Name: AP Number: 039-153-03 A single-story bungalow with wide lap siding and shallow-pitch, multi-gable roof. The front facade of the structure results in a front-facing gable which extends forward to form the entry porch overhang. This overhang is supported by tapered piers and a connecting balustrade.

995. 332 N. Olive
1911 Bungalow
Historical Name:
AP Number: 039-152-11
A single-story bungalow with multi-gable roof. The original sizing has been
covered with asbestos shingles. Centrally located front-facing gable extends
forward to form the entry porch and is supported by piers.

National Register of Historic Places Continuation Sheet

Section number _____7 Page ____216_ Old Towne Orange Historic District, Orange, CA

996. 336 N. Olive 1915 Bungalow Historical Name: AP Number: 039-152-12 A single-story bungalow with lap siding and single front-facing gable roof. One-half of the front facade is devoted to a recessed porch supported by a tapered pier. Since the 1982 survey, this structure has been altered with inappropriate porch enclosure.

997. 341 N. Olive

1915 Bungalow Historical Name: AP Number: 039-153-02 A single-story bungalow with single shallow-pitch, front facing gable roof. The main roof extends forward to form a full-width porch and is supported by wide piers. The house has been stuccoed, which is a modification of the original siding.

998. 348 N. Olive 1909 Bungalow Historical Name: AP Number: 039-152-13 A single-story bungalow with single front-facing, gable roof. The original siding has been covered with asbestos shingles. Small entry portico is supported by wood posts.

999. 349 N. Olive Historical Name: AP Number: 039-153-01 Non-Contributor

1000.404 N. Olive 1915 Historical Name: AP Number: 039-143-16 Non-Contributor

National Register of Historic Places Continuation Sheet

Section number 7 Page 217

Old Towne Orange Historic District, Orange, CA

1001.412 N. Olive 1920 Bungalow Historical Name: AP Number: 039-143-17 Non-Contributor. A single-story bungalow with wide lap siding and double front-facing gable roof. The forwardmost gable forms the entry porch overhang and is supported by wood posts. The main entry is flanked on either side by a pair of casement windows. Since the 1982 survey, this structure has been severely altered by stucco and aluminum windows.

1002.**420 N. Olive** 1947 Historical Name: AP Number: 039-143-18 Non-Contributor

1003.**421 N. Olive** Historical Name: AP Number: 039-144-09 Non-Contributor

1004.428 N. Olive

1914 Bungalow Historical Name: AP Number: 039-143-19 A single-story house with wide lap siding and single side-facing, gable roof. The main roof extends forward to form a nearly full-width porch and is supported by classical columns on concrete bases. Since the 1982 survey, this structure has been altered by porch enclosure and second unit.

1005.429 N. Olive

1914 Bungalow Historical Name: AP Number: 039-144-08 A single-story bungalow with double front-facing, gable roof. The lower gable forms the entry porch overhang and is supported by slender wood posts. The house has been stuccoed, which is a modification of its original character. Since the 1982 survey, this structure has added a somewhat compatible second unit.

National Register of Historic Places Continuation Sheet

Section number 7 Page 218

Old Towne Orange Historic District, Orange, CA

1006.435 N. Olive 1921 Historical Name: AP Number: 039-144-07 Non-Contributor

1007.436 N. Olive 1917 Bungalow Historical Name: AP Number: 039-143-20 Non-Contributor. A 1-1/2 story house with wide lap siding and principally a single side-facing, gable roof. A small, front-facing gable dormer is also present. The main roof extends forward to form a full width porch and is supported by 2' x 4's.

1008.437 N. Olive c1920 Bungalow Historical Name: AP Number: 039-142-08 A single-story bungalow with wide lap siding and shallow-pitch, multi-gable roof. The centrally located front-facing gable extends forward to form the entry porch overhang and is supported by tapered piers.

1009.445 N. Olive c1924 Bungalow Historical Name: AP Number: 039-144-06 A single-story bungalow with wide lap siding and shallow-pitch, gable roof. The house is covered by a single side-facing, clipped gable roof for the most part, while a centrally located, front-facing gable shelters a recessed entry porch. The main door consists of a large mullioned plate glass window and is flanked on either side by mullioned side lites. 1010.446 N. Olive

1914 Bungalow Historical Name: AP Number: 039-143-21 A single-story clapboard bungalow with single , front-facing gable roof. A lower, smaller front-facing gable forms the entry porch overhang which is supported by wood posts. A low connecting clapboard porch wall is also present.

National Register of Historic Places Continuation Sheet

Section number 7 Page 219

Old Towne Orange Historic District, Orange, CA

1011.**453 N. Olive** 1941 Historical Name: AP Number: 039-144-05 Non-Contributor

1012.**454 N. Olive** 1920 Historical Name: AP Number: 039-143-22 Non-Contributor

1013.460 N. Olive 1921 Historical Name: AP Number: 039-143-23 Multi-gabled stucco L-shaped home with matching double hung windows and a covered flat roof porch with small wood supports.

1014.463 N. Olive 1966 Historical Name: AP Number: 039-144-04 Non-Contributor

1015.468 N. Olive 1916 Historical Name: AP Number: 039-143-24 Small and simple brick box-shaped residential home.

1016.469 N. Olive 1961 Historical Name: AP Number: 039-144-03 Non-Contributor

National Register of Historic Places Continuation Sheet

Section number _____7 Page _____ 220

Old Towne Orange Historic District, Orange, CA

1017.474 N. Olive 1918 Bungalow Historical Name: AP Number: 039-143-25 A single-story clapboard bungalow with single side-facing gable roof. A small front-facing gabled portico shelters the entry. The brick siding along the foundation wall is probably a later addition.

1018.477 N. Olive 1961 Historical Name: AP Number: 039-144-02 Non-Contributor

1019.480 N. Olive 1923 Bungalow Historical Name: AP Number: 039-143-26 A single-story clapboard bungalow with double front-facing, gable roof. The forwardmost gable forms the entry porch overhang and is supported by tapered piers. The original door is still present which features mullioned glass plates.

1020.**486 N. Olive** 1920 Historical Name: AP Number: 039-143-27 Non-Contributor

1021.492 N. Olive
1918 Bungalow
Historical Name:
AP Number: 039-143-28
A single-story clapboard bungalow with double front-facing gable roof. The
forwardmost gable houses the entry and may have originally supported an open
porch. Sun ray wood embellishment articulates each of the front gable faces.

National Register of Historic Places Continuation Sheet

Section number 7 Page 221

Old Towne Orange Historic District, Orange, CA

1022.495 N. Olive 1916 Bungalow Historical Name: AP Number: 039-142-01 A single-story bungalow with wide lap siding and double front-facing gable The forwardmost gable forms the entry porch overhang and is supported roof. by slender tapered piers. Entry is beneath at center and is flanked on either side by a pair of casement windows with mullioned transoms. 1023.115 S. Olive 1908 Brick Commercial Historical Name: AP Number: 390-664-03 See National Register Plaza Historic District list. 1024.127 S. Olive 1923 Brick Commercial Historical Name: AP Number: 390-664-04 See National Register Plaza Historic District list. 1025.139 S. Olive 1923 Brick Commercial Historical Name: AP Number: 390-664-05 See National Register Plaza Historic District list. 1026.153 S. Olive Historical Name: AP Number: 390-664-06 Non-Contributor 1027.170 S. Olive Historical Name: AP Number: 390-663-11 Non-Contributor 1028.170 S. Olive Historical Name: AP Number: 390-663-10 Non-Contributor

National Register of Historic Places Continuation Sheet

Section number _____7 Page _____222__

Old Towne Orange Historic District, Orange, CA

1029.**170 S. Olive** Historical Name: AP Number: 390-663-12 Non-Contributor

1030.**190 S. Olive** 1958 Historical Name: AP Number: 390-663-09 Non-Contributor

1031.203 S. Olive c1890 Victorian Cottage Historical Name: AP Number: 390-654-02 A one-story house with shiplap siding and a combination mansard and gable roof. The house originally was built on a slight L-plan with a large wraparound porch. This porch was later enclosed, which significantly alters the appearance of the house. Wide eaves are embellished with simple arched brackets. A side entrance off Almond retains the original porch with ornate turned columns and slatted balustrade.

1032.215 S. Olive
1911 Craftsman
Historical Name:
AP Number: 390-654-03
A one and one-half story house with single, side-facing gable roof and
smaller, front-facing gabled dormer. House is sided in clapboard, and what
was probably the original front porch has since been enclosed. Since the
1982 survey, this structure has been altered with inappropriate window
shutters.
1033.224 S. Olive

1918 Craftsman Historical Name: AP Number: 390-653-19 Large, two-story home with horizontal emphasis. Second story is recessed above first story. Lower story is distinguished by two parallel front-facing gables. Frontmost gable forms entry porch overhang. Porch is supported by piers consisting of brick bases and wood post caps. Large, three-part transomed picture window is on front beneath porch.

National Register of Historic Places Continuation Sheet

Section number 7 Page 223

Old Towne Orange Historic District, Orange, CA

1034.225 S. Olive 1922 Craftsman Bungalow Historical Name: AP Number: 390-654-04 Small, single-story house with double, front-facing gables. Frontmost gable forms entry porch overhang and is supported by wide piers. House is sheathed in clapboard with some vertical venting in gable faces.

1035.232 S. Olive 1922 Craftsman Bungalow Historical Name: AP Number: 390-653-18 Single-story house sheathed in clapboard on a rectangular plan. Main portion of house has side-facing gable, but two smaller, front-facing gables provide added contrast. Main roof extends to form entry porch overhang.

1036.235 S. Olive

1920 Craftsman Historical Name: AP Number: 390-654-05 Two-story, Craftsman home with second story located in a recessed fashion above first story. Double, front-facing gables form first story and are sheathed in arroyo stone. Frontmost gable forms entry porch overhang and is supported by arroyo stone tapered piers. Large, three-part windows adorn front, while ornamental purlins distinguish the gable eaves. Entire lower facade is faced in arroyo stone.

1037.242 S. Olive 1902 Transitional Victorian Historical Name: AP Number: 390-653-17 This is a large, two-story The house includes a multi-ga

This is a large, two-story house built with Classical Revival influences. The house includes a multi-gable roof and facades sided in clapboard. Built on a modified L-plan, the main body of the house is covered by a single gable roof with side-facing gables, while the short leg of the "L" results in a front-facing gable. The apex of this ell contains an attached overhang supported by Classical columns which form a large wrap-around porch. These columns are connected by a short balustrade with ornamental turned balusters. The front-facing gable includes an angled bay window on the lower story and considerable embellishment on the upper gable face; this embellishment consists of a return of the eaves, ornamental bargeboard and a circular, keystoned attic vent. The house is in need of some maintenance, but exhibits its full original, architectural integrity.

National Register of Historic Places Continuation Sheet

Section number 7 Page 224

Old Towne Orange Historic District, Orange, CA

1038.245 S. Olive 1914 Craftsman Bungalow Historical Name: AP Number: 390-654-06 Low-to-the-ground bungalow with extremely shallow pitched roof and clapboard siding. Frontmost gable forms wide entry porch overhang and is supported by wide tapered, concrete piers.

1039.**252 S. Olive** 1915 Craftsman Bungalow Historical Name: AP Number: 390-653-16 Single-story clapboard bungalow with double, front-facing gables. Forwardmost gable forms entry porch overhang and is supported by tapered piers.

1040.253 S. Olive 1913 Craftsman Bungalow Historical Name: AP Number: 390-654-07 Single-story, low-to-the-ground bungalow with L-plan formed by formatting of gables. Frontmost gable and main roof extension form wide porch overhang which is supported by tapered columns. Columns are slumpstone at the foundation and have wood caps.

1041.261 S. Olive 1914 Craftsman Bungalow Historical Name: AP Number: 390-654-08 Single-story, rectangular-plan bungalow with clapboard siding and single, front-facing gable roof. Ornamental purlins accentuate front eaves. Porch is supported by elephantine piers.

1042.262 S. Olive c1905 Hip Roof Cottage Historical Name: AP Number: 390-653-15 Single-story clapboard house with a steep-pitched, hip roof and small, gabled dormer on front face of roof. Recessed corner porch is supported by Classical column, and a large, three-part picture window adorns the frontmost facade.

National Register of Historic Places Continuation Sheet

Section number 7 Page 225

Old Towne Orange Historic District, Orange, CA

1043.264 S. Olive 1914 Bungalow Historical Name: AP Number: 390-653-14 Small, rectangular plan bungalow with main roof composed of a side-facing gable. Smaller, centrally located, front-facing gable extends forward to form entry porch overhang. House is sheathed in clapboard. Entry is at center front.

1044.270 S. Olive 1902 Rural Victorian Historical Name: AP Number: 390-653-13 Two-story clapboard house with a rectangular plan and single, front-facing gable roof. Smaller overhang at first story in front forms porch and is supported by Classical columns, the frontmost portion of which is a pedimented gable. Large, three-part picture window is in front.

1045.284 S. Olive 1895 Hip Roof Cottage Historical Name: AP Number: 390-653-12 Small, single-story house with pyramidal roof and small attic gable in front. Corner porch is recessed beneath main roof and is supported by Classical columns. Pairs of high vertical windows indicate Victorian period. Since the 1982 survey, this structure has been altered by an attached, two-story garage addition.

1046.290 S. Olive c1910 Classic Box Historical Name: AP Number: 390-653-11 Large, full, two-story box plan house with clapboard siding and a steeppitched, hip roof. Major alteration has been made on the front facade above the original porch overhang. The lower story porch is supported by Classical columns, and entry is at center beneath.

1047.**317 S. Olive** 1959 Historical Name: AP Number: 390-601-17 Non-Contributor

National Register of Historic Places Continuation Sheet

Section number _____7 Page _____226

Old Towne Orange Historic District, Orange, CA

1048.**320 S. Olive** 1904 Victorian Cottage Historical Name: AP Number: 390-603-02 Small, single-story L-plan cottage now covered with asbestos siding. Apex of ell is location of porch overhang supported by ornamental columns characteristic of Victorian era homes.

1049.**331 S. Olive** 1923 Mediterranean Revival Historical Name: AP Number: 390-601-16 Non-Contributor. Since the 1982 survey, this structure has been severely altered by an inappropriate second story addition.

1050.**339 S. Olive** c1920 Craftsman Bungalow Historical Name: AP Number: 390-601-15 Non-Contributor. Since the 1983 survey, this structure has been severely altered by an inappropriate second story addition.

1051.340 S. Olive 1923 Craftsman Bungalow Historical Name: AP Number: 390-603-04 Small, single-story bungalow, clapboard siding and double-front-facing gable roof. Foremost gable forms entry porch overhang and is supported by tapered piers. A porte cochere is located to the side and is also supported by a tapered pier.

1052.349 S. Olive c1915 Craftsman Historical Name: AP Number: 390-601-14 A one and one-half story Craftsman home with single, side-facing gable contrasted by smaller, front-facing gabled dormer. House is sheathed in clapboard. Main roof extends forward to form wide porch overhang and is supported by tapered piers comprised of arroyo stone bases and wood tops. Large, transomed picture windows flank either side of main door.

National Register of Historic Places Continuation Sheet

Section number 7 Page 227

Old Towne Orange Historic District, Orange, CA

1053.**350 S. Olive** c1898 Rural Victorian Historical Name: AP Number: 390-603-05 Large, two-story house with rectangular plan and single, side-facing gable roof. Main entry is via recessed corner porch supported by wood posts. Ornamental fretwork comprises the balustrade and connecting links between porch posts.

1054.356 S. Olive 1906 Hip Roof Cottage Historical Name: AP Number: 390-603-06 Single-story, box plan house with a steep-pitched, hip roof and clapboard siding. Main roof extends forward to form entry porch overhang and is supported by wood posts. Porch posts are connected by slatted balustrade. Main entry is beneath at center. Since the 1982 survey, this structure has been altered with inappropriate posts.

1055.**357 S. Olive** c1895 Hip Roof Cottage Historical Name: AP Number: 390-601-13 Small, single-story box plan house with flattened hip roof and shiplap siding. Separate, smaller roof extends across full width of front facade and forms porch overhang. It is supported by wood posts connected by slatted balustrade.

1056.**364 S. Olive** 1930 Historical Name: AP Number: 390-603-07 Non-Contributor

1057.**365 S. Olive** c1915 Craftsman Historical Name: AP Number: 390-601-12 Non-Contributor. Since the 1982 survey, this structure has been severely altered by an inappropriate second story addition and two-story second unit wing.

National Register of Historic Places Continuation Sheet

Section number _____7 Page _____228

Old Towne Orange Historic District, Orange, CA

1058.**371 S. Olive** 1920 Bungalow Historical Name: AP Number: 390-601-11 Single-story, low-to-the-ground bungalow with single, front-facing gable roof. Main entry is recessed beneath the porch which is supported by large tapered columns. Large transomed, picture windows flank either side of the main entry at center.

1059.376 S. Olive c1905 Hip Roof Cottage Historical Name: AP Number: 390-603-08 Single-story, box plan house with a steep-pitched, hip roof and smaller gable section on forwardmost portion of front facade which forms an angled bay window. A corner porch is supported by Classical-like columns. The strongest ornamental feature of the house is the gable projection which has a recessed half moon.

1060.**381 S. Olive** Historical Name: AP Number: 390-601-10 Non-Contributor

1061.**384 S. Olive** 1978 Historical Name: AP Number: 390-601-09 Non-Contributor

1062.392 S. Olive
1917 Bungalow
Historical Name:
AP Number: 390-603-10
Small clapboard cottage with U-plan and multi-gable roof. Entry is at center
of U. Garage appears to be attached to house and probably a later addition.

National Register of Historic Places Continuation Sheet

Section number 7 Page 229

Old Towne Orange Historic District, Orange, CA

1063.393 S. Olive c1915 Craftsman Historical Name: AP Number: 390-601-09 A one and one-half story Craftsman home with rectangular plan and single, side-facing, gable roof complemented by smaller, front-facing gabled dormer. Main roof extends forward to form wide porch overhang and is supported by elephantine piers. Two large picture windows with wide transoms flank either side of main entry which is at center. Ornamental purlins adorn eaves of gabled dormer. 1064.397 S. Olive c1920 Bungalow Historical Name: AP Number: 390-402-10 Single-story clapboard bungalow with double, front-facing gables. Foremost gable originally formed entry porch overhang but has since been enclosed. 1065.405 S. Olive c1920 Craftsman Bungalow Historical Name: AP Number: 390-602-19 Single-story bungalow with double, front-facing gable roof and clapboard siding. Frontmost gable forms entry porch overhang and is supported by tapered piers. Ornamental purlins are beneath gable eaves. 1066.411 S. Olive Historical Name: AP Number: 390-602-18 Non-Contributor 1067.423 S. Olive Historical Name: AP Number: 390-602-20 Non-Contributor 1068.437 S. Olive 1920 Bungalow Historical Name: AP Number: 390-602-16

Single-story bungalow with box plan and single, front-facing gable roof which extends forward to form main porch overhang. This overhang is supported by wood posts.

National Register of Historic Places Continuation Sheet

Section number _____7 Page _____230 Old Towne Orange Historic District, Orange, CA

1069.445 S. Olive c1920 Bungalow Historical Name: AP Number: 390-602-15 Non-Contributor. Since the 1982 survey, this structure has been replaced with a multi-gable, wood-sided craftsman style fourplex.

1070.455 S. Olive

1919 Bungalow Historical Name: AP Number: 390-602-14 Low-to-the-ground, single-story bungalow with rectangular plan, single sidefacing roof and clapboard siding. The design of this house is given an unusual twist through the use of two smaller, gabled attic dormers which project from the main roof. Since the 1982 survey, this structure has been altered with inappropriate front door replacement.

1071.465 S. Olive

c1910 Vernacular Historical Name: AP Number: 390-602-13 A full two-story home sheathed in clapboard with a rectangular plan and single side-facing gabled roof complemented by a smaller pedimented gable in front. The entry is beneath a gabled portico which projects forward and is enclosed. Three-part windows adorn the facade in various places.

1072.475 S. Olive

Bungalow Historical Name: AP Number: 390-602-12 Single-story bungalow with clapboard siding and double front-facing gable roof. Frontmost gable is location of entry.

1073.485 S. Olive c1920 Craftsman Bungalow Historical Name:

AP Number: 390-602-11

Low-to-the-ground, rectangular plan Craftsman Bungalow with single, sidefacing gable roof and clapboard siding. Main roof extends forward to form wide porch overhang and is supported by piers. Large, three-part transomed picture windows with multi-paned transoms flank either side of main entry which is at center. A shed attic dormer peeps up from the main roof.

National Register of Historic Places Continuation Sheet

Section number _____7 Page _____231

Old Towne Orange Historic District, Orange, CA

1074.**123 N. Orange** 1966 Historical Name: AP Number: 039-252-06 Non-Contributor

1075.**123 N. Orange** 1966 Historical Name: AP Number: 039-252-05 Non-Contributor

1076.**123 N. Orange** 1966 Historical Name: AP Number: 039-252-10 Non-Contributor

1077.**132 N. Orange** 1966 Historical Name: AP Number: 039-251-10 Non-Contributor

1078.**144 N. Orange** 1915 Historical Name: AP Number: 039-251-03 Non-Contributor

1079.**184 N. Orange** 1960 Historical Name: AP Number: 039-251-16 Non-Contributor

1080.**191 N. Orange** 1928 Historical Name: AP Number: 039-252-16 Non-Contributor

ļ

National Register of Historic Places Continuation Sheet

Section number 7 Page 232

Old Towne Orange Historic District, Orange, CA

1081.213 N. Orange c1920 Bungalow Historical Name: AP Number: 039-242-11 A single-story bungalow with multi-gable roof and wide lap siding on the facades. The house is built in an L-plan with the short leg resulting in a front-facing gable. To the side is a gabled entry portico supported by colonial columns and fashioned in the Colonial Revival style.

1082.215 N. Orange 1920 Bungalow

Historical Name: AP Number: 039-242-11 A single-story house with wide lap siding and single-gable roof. The center portion of the house is articulated by a front-facing, gabled porch overhang supported by slender wood posts. Double doors indicate duplex useage. The house is simple, small and unadorned.

1083.**220 N. Orange** 1969 Historical Name: AP Number: 039-241-13

1084.221 N. Orange

Non-Contributor

1874 Victorian Historical Name: AP Number: 039-242-10

This is a large, two-story house with shiplap siding and multi-gable roof. The house has undergone some alterations done in an uncomplimentary manner circa 1925. The house is currently built in a U-plan with the center of the U forming the entry, embellished on the entry exterior by a gabled portico supported by classical columns. A double-story bay window is present to the side of the entry and features typical Victorian embellishment above and below the windows. Since the 1982 survey, it appears that a pyramid roof has been removed.

National Register of Historic Places Continuation Sheet

Section number 7 Page 233

Old Towne Orange Historic District, Orange, CA

1085.230 N. Orange 1908 Bungalow Historical Name: AP Number: 039-241-14 A single-story bungalow with combination lap and shingled siding and a roofline comprised of double front-facing gables. The entry is to the side of the frontmost gable. Ornamental bargeboard and rafter tails distinguish the eaves.

1086.**231 N. Orange** 1961 Historical Name: AP Number: 039-242-09 Non-Contributor

1087.233 N. Orange

c1920 Bungalow Historical Name: AP Number: 039-242-09 A single-story clapboard bungalow with multi-gable roof. The front facade is comprised of three front-facing gables, of which the two outermost gables form entry porch overhangs supported by tapered piers. There is an entry beneath each porch, indicating duplex useage of the house.

1088.237 N. Orange

1917 Bungalow Historical Name: AP Number: 039-242-08 Non-Contributor

1089.238 N. Orange c1908 Bungalow Historical Name: AP Number: 039-241-15 This is a single-stor

This is a single-story bungalow with double front-facing, gable roof. The forwardmost gable forms the entry porch overhang. The original siding of the house has since been covered with asbestos shingles. The original door with plate glass windows and large, beveled transomed window to the side are still present. An earlier house may have been constructed on this site, which may form the skeleton for this present facade.

National Register of Historic Places Continuation Sheet

Section number _____7 Page _____234___

Old Towne Orange Historic District, Orange, CA

1090.243 N. Orange

1913 Bungalow Historical Name: AP Number: 039-242-07 A single-story bungalow with wide lap siding and double, front-facing, gable roof. The forwardmost gable forms the entry porch overhang and is supported by tapered piers with cast concrete bases. A low porch wall and half-sized piers are also composed of cast concrete. The original door with plate glass windows is still present. Adjoining it is a large picture window with a transom window.

1091.246 N. Orange

c1906 Bungalow Historical Name: AP Number: 039-241-16 A single-story bungalow with wide lap siding and double, front-facing gable roof. The forwardmost gable forms the entry porch overhang which is supported by tapered piers above a stone base. Ornamental purlins grace the eaves. An earlier structure was probably built on this site in 1906 and later remodeled into the present facade around 1915.

1092.254 N. Orange

c1910 Hip Roof Cottage Historical Name: AP Number: 039-241-17 A single-story clapboard house with box plan and steep-pitched, hip roof. There is also a hipped dormer present on the front portion of the roof. Entry is via a large corner recessed porch supported by brick piers which are probably a later addition.

1093.259 N. Orange

1914 Craftsman Historical Name: AP Number: 039-242-06 A 1-1/2 story house with wide lap siding and single, side-facing gable roof. A front-facing gabled dormer is also present and features ornamental purlins. One-half of the front facade is comprised of a recessed entry porch supported by wide piers. A grouping of four transomed windows is also present on the front facade.

National Register of Historic Places Continuation Sheet

Section number _____7 Page _____235

Old Towne Orange Historic District, Orange, CA

1094.261 N. Orange 1916 Altered Bungalow Historical Name: AP Number: 039-242-05 A single-story bungalow with wide lap siding and multi-gable roof. The front facade is comprised of a single, front-facing gable supporting a threequarter size recessed porch. The porch is supported by piers with a small connecting, slatted balustrade. The remaining half of the front facade is almost fully enclosed by windows. Brickwork is probably a later addition.

1095.262 N. Orange

1908 Hip Roof Cottage Historical Name: AP Number: 039-242-04 A single-story box plan house with clapboard siding and steep-pitched, hip roof. A small hipped dormer is present on the front portion of the house. Entry is via a corner recessed porch supported by a single classical column.

1096.267 N. Orange

c1915 Bungalow Historical Name: AP Number: 039-242-04 A single-story bungalow with lap siding and double, front-facing gable roof. The forwardmost gable forms the entry porch overhang and is supported by piers with wood posts on top.

1097.270 N. Orange 1910 Bungalow Historical Name: AP Number: 039-241-19 A single-story bungalow with wide lap siding and double, front-facing gable roof. The forwardmost gable forms the entry porch overhang and is supported by wood posts. Exposed beams in the upper gable faces act as embellishment as well as serve a functional purpose.

1098.275 N. Orange 1915 Colonial Revival Historical Name: AP Number: 039-242-03 A colonial revival residuece with sidtincitve gambrel roof on a rectangular plan. Kneebraced canopied over door, double-hung windows with 6/1 windows, and detailed crown molding are present.

National Register of Historic Places Continuation Sheet

Section number 7 Page 236

Old Towne Orange Historic District, Orange, CA

1099.278 N. Orange 1912 Hip Roof Cottage Historical Name: AP Number: 039-241-20 A single-story clapboard house with combination hip and gable roof. The house is built on a modified L-plan with the front leg of the ell resulting in a small pedimented gable with a recessed entry porch beneath. This porch is supported by a slim wood post. The front portion of the house is covered by a grouping of sash windows.

1100.283 N. Orange

1918 Bungalow Historical Name: AP Number: 039-242-02 A single-story bungalow with ornamental lap siding and double, front-facing gable roof. The forwardmost gable forms the entry porch overhang and is supported by tapered piers.

1101.286 N. Orange

1910 Hip Roof Cottage Historical Name: AP Number: 039-241-21 A single-story clapboard house with combination hip and gable roof. A large corner wrap-around porch is the primary feature of this house. The porch is articulated by a pedimented gable overhead, supported by piers with clapboard bases and wood posts on top. Wide eaves are embellished with ornamental brackets.

1102.294 N. Orange 1908 Hip Roof Cottage Historical Name: AP Number: 039-241-22 A single-story clapboard house with combination hip and gable roof. The house features a large corner wrap-around porch supported by classical columns. A portion of this porch has since been enclosed. The house is built on a modified L-plan with the frontmost leg of the ell resulting in a pedimented gable ornamented with fishscale shingles.

National Register of Historic Places Continuation Sheet

Section number _____7 Page _____237___

Old Towne Orange Historic District, Orange, CA

1103.295 N. Orange 1920 Bungalow Historical Name: AP Number: 039-242-01 A single-story bungalow with wide lap siding and gable roof. A low shed dormer with shingle facing is present on the front portion of the roof. Entry is beneath an arched portico supported by classical columns. To either side are large 3-part picture windows. 1104.111 S. Orange 1912 Brick Commercial Historical Name: Barger's Hall AP Number: 390-382-01 See National Register Plaza Historic District list. 1105.120 S. Orange c1915 Single-Story Brick Commercial Historical Name: AP Number: 390-381-21 This is a very small, single-story, rectangular plan brick structure with ornamental brick used at the cornice line. 1106.123 S. Orange Historical Name: AP Number: 390-382-06 Non-Contributor 1107.126 S. Orange 1914 Brick Commercial Historical Name: Alfred Kuhn Building AP Number: 390-381-18 See National Register Plaza Historic District list. 1108.132 S. Orange Historical Name: AP Number: 390-381-17 Non-Contributor 1109.136 S. Orange Historical Name: AP Number: 390-381-16 Non-Contributor

National Register of Historic Places Continuation Sheet

Section number _____7 Page ____238__ Old Towne Orange Historic District, Orange, CA

1110.154 S. Orange Historical Name: AP Number: 390-381-15 Non-Contributor

1111.161 S. Orange 1969 Historical Name: AP Number: 390-382-10 Non-Contributor

1112.174 S. Orange 1978 Historical Name: AP Number: 390-381-22 Non-Contributor

1113.182 S. Orange

1891 Victorian w/Gothic Revival Influences Historical Name: First Baptist Church AP Number: 390-382-12

This vernacular church incorporates Victorian and some Gothic influences. This is a one-story church building with multi-gable roofline and combination shiplap and shingle siding. The building includes three, street-facing gables contrasted by the corner entry tower. This tower, like many in the Gothic tradition, is comprised of a raised box crowned by a mansard roof. Pointed arch transoms on the lower level and arched louvers on the upper level embellish the tower along with the moulding on the cornice. The remaining portions of the facade are characterized by large, arched, stained glass windows with tracery and ornamental fish-scale shingles in the upper gable faces. The building has been restored and converted to restaurant use. building is excellently maintained and exhibits its The original architectural integrity. In the rear is a compatible addition. This building was recently added to the National Register of Historic Places.

1114.191 S. Orange 1924 Brick Commercial Historical Name: AP Number: 390-382-12 This is a single-story brick building with flat roof. There are two portions of the front facade on either end which project forward, and the center portion in between is articulated by a tile hood roof.

National Register of Historic Places Continuation Sheet

Section number 7 Page 239

Old Towne Orange Historic District, Orange, CA

1115.204 S. Orange c1915 Craftsman Historical Name: AP Number: 390-391-10 A large, two-story house with lap siding and a single, front-facing gable roof. Entry is via a corner cut-out porch. A side porch with brick piers is present off Almond Street. The house is simple and unadorned.

1116.205 S. Orange

1896 Victorian Historical Name: AP Number: 390-392-01 Though this Victorian-era home has undergone some modifications, it retains much of its original formatting and style. This is a two-story house built on an L-plan with the frontmost portion of the ell resulting in an angled bay window with a gable face above. Originally there was a large corner, wraparound porch supported by thin wood posts and a connecting balustrade with ornamental ballasters. The porch has since been enclosed. Since the 1982 survey, this structure has had a change of use from residential to commercial.

1117.212 S. Orange

1911 Craftsman Historical Name: AP Number: 390-391-09 A large, two-story Craftsman with side-facing gable topped by a narrow, front-facing gable with heavy sticks work. Chicago style windows and front door are framed with tapered, flat board trim. Across the front is an under roof porch with wood posts on brick piers.

1118.215 S. Orange

1918 Craftsman Bungalow Historical Name: AP Number: 390-392-02 A low, single-story bungalow with shallow-pitched, multi-gable roof and wide lap siding. Entry is via a large gable extension of the main roof and is supported by tapered piers. The roof extends on the side, covering a bay projection and also a pergola on either side of the bay.

National Register of Historic Places Continuation Sheet

Section number _____7 Page ____240 Old Towne Orange Historic District, Orange, CA

1119.220 S. Orange 1911 Craftsman Historical Name: AP Number: 390-391-08 A one and one-half story Craftsman house with a single-gable roof, sidefacing gables and wide lap siding. A gable roof dormer on the front is ornamented with cross-ties on the bargeboard and ornamental purlins. The main roof extends forward to form the porch overhang supported by wide tapered piers. It appears that half of the porch has since been enclosed.

1120.221 S. Orange

c1895 Victorian Historical Name: AP Number: 390-392-03 This is a single-story cottage-scale house with narrow shiplap siding and a flattened hip roof. The main entry is via a corner recessed porch supported by ornamental turned posts and ornamental brackets above. A front-facing gable is located on the opposite portion of the front facade and features fish scale shingles, spindle work and ornamental jigsawn bargeboard. Since the 1982 survey, this structure has been altered with appropriate stair rail and fence.

1121.230 S. Orange 1913 Craftsman Historical Name: AP Number: 390-391-07 A two-story clapboard house with multi-gable roof. The second story portion is recessed over the rear half of the house while the front half is defined by two front-facing gables. The forwardmost gable is flanked by double-hung windows across the front which is contrasted by brick piers and a connecting wall.

National Register of Historic Places Continuation Sheet

Section number 7 Page 241

Old Towne Orange Historic District, Orange, CA

1122.233 S. Orange c1922 Mediterranean Revival Historical Name: Roland Court (5 separate buildings) AP Number: 390-392-04 This is a one-story bungalow court built on a U-plan. The roof is flat with adobe tiles along the cornice line; the facades are sided in stucco. the most distinguishing feature of the building is the three-part, arched entry gate; a large central arch with an ornamental parapet is flanked on either side by a smaller arch. The interior entries are all articulated by entry porticos with adobe tiles. The building is simple and relatively unembellished but representative of the Twenties era bungalow courts. The building is in excellent condition and exhibits its original architectural integrity.

1123.238 S. Orange

1913 Craftsman Historical Name: AP Number: 390-391-06

A one and one-half story Craftsman house with wide lap siding and singlegable roof with side-facing gables. Front portion of the roof also features a shed dormer. The main roof extends to form a full-width porch which is supported by tapered piers with arroyo stone bases and an arroyo stone connecting wall.

1124.239 S. Orange

c1920 Bungalow Historical Name: AP Number: 390-392-05 A single-story bungalow with lap siding and double, front-facing gable roof. The smaller, forwardmost gable forms the entry porch overhang supported by wood posts atop wide piers. Vertical venting and dentils as well as exposed

beams ornament the upper gable faces.

1125.256 S. Orange

1917 Craftsman Historical Name: AP Number: 390-395-10 A one and one-half story Craftsman house with side-facing, gable roof with a front-facing, gable roofed dormer with an ornamentally framed window and louvered vent and ornamental purlins beneath the eaves. The main roof extends forward to form a full-width porch overhang supported by wide brick piers. The house is now sheathed in asbestos siding.

National Register of Historic Places Continuation Sheet

Section number _____7 Page _____242___

Old Towne Orange Historic District, Orange, CA

1126.257 S. Orange 1915 Craftsman Historical Name: AP Number: 390-396-01 A one and one-half sgtory Craftsman house with side-facing, gable roof contrasted by a front-facing, gable roof dormer. The house is now sheathed in asbestos siding. The main roof extends forward to form a full-width porch supported by tapered piers and a low connecting porch wall. Entry is at center, flanked on either side by a large, three-part window with horizontal transom.

1127.265 S. Orange

c1900 Victorian Historical Name: AP Number: 390-396-02 A two-story house built in a simple, rural farmhouse style. The main roofline is comprised of a hip roof. Beneath, at the first story, there is a roof projection which forms a full-width porch supported by wood posts. Pairs of narrow vertical windows adorn the front facade.

1128.**266 S. Orange** Historical Name: AP Number: 390-395-09 Non-Contributor

1129.266 S. Orange Historical Name: AP Number: 390-395-09 Non-Contributor

1130.271 S. Orange 1953 Historical Name: AP Number: 390-396-03 Non-Contributor

The

United States Department of the Interior National Park Service

National Register of Historic Places **Continuation Sheet**

Section number 7 Page 243

Old Towne Orange Historic District, Orange, CA

1131.272 S. Orange c1905 Victorian Historical Name: AP Number: 390-395-08 A large, two-story house with clapboard siding and multi-gable roof. house is built somewhat on a T-plan with the stem of the T forming the frontmost facade, resulting in a circular bay window on the first story and a gable face on the upper story. Entry is via a corner porch supported by clapboard piers. Ornamental bargeboard on the front gable face along with exposed beams at the first story provide ornamentation.

1132.282 S. Orange

1911 Hip Roof Cottage Historical Name: AP Number: 390-395-07 A single-story house with hip and gable roof and wide lap siding. The frontfacing gable forms the entry porch overhang and is supported by slim tapered piers. On either side of the main entry is a large, three-part window with multi-pane transom. The front gable features ornamental shingles and a louvered vent.

1133.292 S. Orange

C1905 Hip Roof Cottage Historical Name: AP Number: 390-395-06 A single-story, box plan house with clapboard siding and a steep-pitched, hip roof with a smaller hip roof over a dormer on the front portion. What was originally a corner recessed porch has since been screened in, but the original Classical column with Corinthian capital is still present. The house features very wide eaves adorned with ornamental brackets.

1134.315 S. Orange 1919 Prairie Style Influence Historical Name: AP Number: 390-402-01 This is a two-story house with a distinct Prairie style (Frank Lloyd Wright inspired) quality about it. The house features a flat roof with multiplaned, stucco siding on the facades. A porch projects forward and is supported by very wide round columns. Pairs of French doors are present in four places on the front facade. Horizontal banding, typical of the Prairie style, is present on the house. This style is rare for Orange.

National Register of Historic Places Continuation Sheet

Section number 7 Page 244

Old Towne Orange Historic District, Orange, CA

1135.325 S. Orange c1915 Craftsman Historical Name: AP Number: 390-402-02 Non-Contributor. Since the 1982 survey, this structure has been severely altered by a total remodel so that historical significance is lost.

1136.331 S. Orange

1904 Hip Roof Cottage Historical Name: AP Number: 390-402-03 This house has undergone modifications over the years. Most visible is the stucco siding. It is a box plan house with steep-pitched hip roof and a recessed corner porch supported by wood posts with ornamental brackets.

1137.339 S. Orange

1913 Craftsman Bungalow Historical Name: AP Number: 390-402-04 A single-story clapboard bungalow with multi-gable roof. The front facade is defined by a full-width porch with a gable overhang supported by tapered piers on brick bases. The piers are connected by a slatted balustrade. Entry is at center and flanked on either side by a large, three-part window with multi-paned transom.

1138.344 S. Orange

1917 Hip Roof Cottage Historical Name: AP Number: 390-401-17 A single-story house with shiplap siding and pyramidal roof. What was formerly a nearly full-width porch has since been enclosed. A separate roof extension covers the porch on the front facade, supported by thin wood posts atop a connecting porch wall.

1139.347 S. Orange

1914 Craftsman Bungalow Historical Name: AP Number: 390-402-05

A single-story bungalow with lap siding and double, front-facing gable roof. The forwardmost gable forms the entry porch overhang and is supported by thin tapered piers. The upper gable faces are adorned with dentils, ornamentally framed windows and vents, and ornamental purlins.

National Register of Historic Places Continuation Sheet

Section number 7 Page 245

Old Towne Orange Historic District, Orange, CA

1140.355 S. Orange 1921 California Bungalow Historical Name: AP Number: 390-402-06 A low, single-story clapboard bungalow with single-gable roof with sidefacing gables. A small overhead extension on the center of the front facade forms the entry portico and is supported by wood posts. Entry is beneath at center.

1141.356 S. Orange c1905 Victorian Historical Name: AP Number: 390-401-16 This is a two-story house with multi-planed roof and shiplap siding. The roof is comprised of both gable and hip elements. Full-width porch at the first story is defined by an attached roof overhang with a small pedimented gable. The entire porch overhang is supported by wide piers with wood posts on top. These piers are connected by a slatted balustrade.

1142.360 S. Orange 1938 Historical Name: AP Number: 390-401-15 Non-Contributor

1143.363 S. Orange

1913 Craftsman Bungalow Historical Name: Samuel and Alice Armor House AP Number: 390-402-07 This is a one-story bungalow with a double, front-facing gable roof and wide lap siding on the facades. The forwardmost gable forms the entry porch overhang supported by elephantine piers on brick bases. A low, slatted balustrade connects the full-height and half-sized piers. Ornamental, triangular bracket supports grace the eaves. A small mullioned transom is present in the frontmost gable face. The original door with vertical glass panes is still present. The house is in good condition and retains the full body of its original architectural integrity.

1144.**368 S. Orange** 1948 Historical Name: AP Number: 390-401-14 Non-Contributor

فالمحاج والمحاج بمعام معتمد فالمرجو ومرجع المرجو ويعامرون والمالي المالي المالية المالية

United States Department of the Interior National Park Service

National Register of Historic Places Continuation Sheet

Section number _____7 Page _____246

Old Towne Orange Historic District, Orange, CA

1145.371 S. Orange 1920 California Bungalow Historical Name: AP Number: 390-402-08 A single-story clapboard bungalow with the main portion of the house covered by a single-gable roof with side-facing gables. The center front of the house features a gable porch overhang supported by Colonial columns and some horizontal wood ornamentation on the gable face. The front door consists of a single glass plate with 15 small glass panes. The door is flanked by glass side-lights.

1146.**375 S. Orange** 1947 Historical Name: AP Number: 390-402-09 Non-Contributor

1147.378 S. Orange 1890 Hip Roof Cottage Historical Name: AP Number: 390-401-13 This is a small Hip roof cottage with an L-plan, shiplap siding and a combined flattened hip and gable roof. The porch is formed in the apex of the ell. It has its own separate roof overhang supported by wood posts. The frontmost leg of the ell features a gable-face embellished with ornamental shingles and jigsawn embellishments in the bargeboard. Also present is a large picture window with ornamental framing.

1148.384 S. Orange 1914 Craftsman Historical Name: AP Number: 390-401-12 A two-story Craftsman home with wide lap siding and multi-gable roof. The second story portion of the house is over the rear half, while the lower story is defined by a wide, shallow-pitched gable overhang which forms the porch. This is supported by wide piers with ornamental capitals; the upper gable face includes vertical slatting which is repeated on the porch balustrade below.

National Register of Historic Places Continuation Sheet

Section number 7 Page 247

Old Towne Orange Historic District, Orange, CA

1149.394 S. Orange 1909 Gable Roof Cottage Historical Name: AP Number: 390-401-11 A single-story clapboard house with multi-gable roof. A large corner porch is formed by the main roof extension and is supported by Classical columns with Corinthian capitals. The other half of the front facade results in an angled bay window with a shingled gable above. A curved bay window is present on the side of the house. Ornamental rafter tails and brackets adorn the wide eaves.

1150.397 S. Orange Historical Name:

AP Number: 390-402-10 Non-Contributor

1151.404 S. Orange

1909 Craftsman Bungalow Historical Name: AP Number: 390-411-22 A single-story clapboard bungalow with single, front-facing gable roof. The upper gable face is sheathed in shingles with a row of fish scale shingles just beneath. Entry is via a corner recessed porch supported by a wide clapboard pier. Dentils and ornamental purlins and a spire in the peak of the gable further embellish this house.

1152.412 S. Orange c1920 Craftsman Bungalow Historical Name: AP Number: 390-411-21 A single-story bungalow with double, front-facing gable roof and ornamental lap siding. The entry porch is formed by a small, front-facing gable which runs parallel to the main roof gable and is supported by elephantine piers which have since been remodeled using wood.

National Register of Historic Places Continuation Sheet

Section number _____ 7 Page _____ 248___

Old Towne Orange Historic District, Orange, CA

1153.**413 S. Orange** c1905 Victorian Historical Name: AP Number: 390-412-02 This two-story, L-shaped plan, short returns at the gable ends

This two-story, L-shaped plan, simple Victorian house has boxed cornices with short returns at the gable ends, and has shiplap siding. A shed roof covers the narrow porch in the "L." Two doors open onto the porch. In the front wing is a double-hung, single-pane window on each floor. There is decorative wood trim in the peak of the gable and under each window sill.

1154.420 S. Orange

1913 Craftsman Bungalow Historical Name: AP Number: 390-411-20 This one-story Craftsman bungalow has a side-facing gable roof with shed dormer. Across the front is an under roof porch. The porch has field stone piers at the end corners. Flanking the concrete steps to the porch are field stone wing walls and short fieldstone piers. Wood posts on the piers support the arched header beam.

1155.421 S. Orange

1914 Craftsman Bungalow Historical Name: AP Number: 390-412-03 A single-story bungalow with lap siding and double, front-facing gables. A small entry porch is formed in one corner portion of the forwardmost gable.

1156.428 S. Orange
1886 Victorian
Historical Name:
AP Number: 390-411-19
This is a two-story Victorian house with a multi-gable roof and combination
shiplap/shingle siding. What was the original porch has since been enclosed.
The front gable face is adorned with ornamental, square butt shingles and
ornamental framing around both the attic vent and windows.

1157.429 S. Orange 1938 Historical Name: AP Number: 390-412-04 Non-Contributor

National Register of Historic Places Continuation Sheet

Section number _____7 Page ____249

Old Towne Orange Historic District, Orange, CA

1158.435 S. Orange 1908 Hip Roof Cottage Historical Name: AP Number: 390-412-05 A single-story clapboard bungalow with multi-hip roof and a small recessed entry porch beneath the front facade. The house is otherwise simple and unadorned.

1159.436 S. Orange

1910 Craftsman Historical Name: AP Number: 390-411-18 A one and one-half story craftsman house with a single, side-facing gable roof contrasted by front-facing gable dormer. A full-width porch is formed by the extension of the main; this is supported by tapered piers on the outside edges and Classical columns on the inside portions. All of the piers and columns have arroyo stone bases. Also, the foundation of the house is of arroyo stone. Ornamental purlins grace the eaves.

1160.442 S. Orange

1905 Transitional Classical Revival Historical Name: AP Number: 390-411-17 A two-story house with multi-gable roof and clapboard siding. Entry is via a corner recessed porch supported by Classical columns. An unusual appearance to the house is derived from a large, flush front-facing gable face. This gable features a return at the eaves and a pair of double-hung windows in the upper portion of the gable. It appears as though the original door is still present.

1161.443 S. Orange

1922 Bungalow Historical Name: AP Number: 390-412-06 A single-story, tri-gable bungalow with clapboard siding. The main portion of the house is comprised of a single-gable roof with side-facing gables. A centrally placed, front-facing gable with return at the eaves forms the entry porch overhang and is supported by wide wood posts. A three-part louvered vent is present in this gable face.

National Register of Historic Places Continuation Sheet

Section number _____7 Page _____250

Old Towne Orange Historic District, Orange, CA

1162.450 S. Orange
1914 Bungalow
Historical Name:
AP Number: 390-411-16
A two-story clapboard house with single, front-facing gable roof. A smaller
roof extends forward from the front facade and aids in forming the recessed
porch supported by wood posts atop wide concrete piers.

1163.453 S. Orange

1915 Craftsman Bungalow Historical Name: AP Number: 390-412-07 A small, single-story bungalow with a single, shallow-pitched, front-facing gable roof and ornamental lap siding. A recessed porch occupies one-half of the front facade; its overhang is supported by a pier with concrete base and wood posts on top. Exposed beams act as ornamentation on the porch overhang.

1164.459 S. Orange 1903 Victorian Historical Name: AP Number: 390-412-06 A Victorian cottage with multi-planed roof and shiplap siding. The house is treated in the usual Victorian manner by having a complex and dynamic roof comprised of hip and gable sections and combined shiplap siding with ornamental shingles in each of the front-facing gables. A small pedimented, front-facing gable forms an entry porch overhang and is supported by ornamental turned posts. Decorative bargeboard is also in this porch gable.

1165.460 S. Orange 1912 Craftsman Historical Name: AP Number: 390-411-15 A one and one-half story Craftsman house with lap siding and single-gable roof with side-facing gables. The front portion of the roof features a front-facing gable dormer with ornamental purlins and an ornamentally framed, multi-paned transom window. The main roof extends forward to form a fullwidth porch supported by arroyo stone piers. Half piers flank either side of the entry stoop. The main door is at center; on either side are located large, three-part windows with transoms.

National Register of Historic Places Continuation Sheet

Section number _____ 7 Page _____ 251___

Old Towne Orange Historic District, Orange, CA

1166.468 S. Orange 1909 Craftsman Historical Name: AP Number: 390-411-14 A one and one-half story Craftsman house with a single-gable roof with sidefacing gables contrasted by a smaller, front-facing gable dormer. The lower portion of the house is sheathed in slump stone; the dormer is sheathed in shingles. The main roof extends forward to form a wide porch overhang and is supported by piers. The dormer features half timbering and exposed beams. Entry is off-center and a large, three-part picture window with transom is on the front facade.

1167.469 S. Orange c1900 Gable Roof Cottage Historical Name: AP Number: 390-412-09 A small, single-story cottage with shiplap siding and single, front-facing gable roof. A full-width porch is formed by a separate hip extension and is supported by wood posts. Entry is center and flanked on either side by a double-hung window.

1168.476 S. Orange

1912 Craftsman Historical Name: AP Number: 390-411-13 A one and one-half story Craftsman house with wide lap siding and singlegable roof with side-facing gables. A front-facing, gable dormer is present and is ornamented with cross-ties in the upper gable face and ornamental purlins below. The house features only a half porch which is supported by a pier. The original wood door with three, small rectangular panes is present; on each portion of the front facade there is a large, three-part window with diamond-paned transom.

1169.477 S. Orange

1908 Craftsman Bungalow Historical Name: AP Number: 390-412-10 A single-story, rectangular plan house with wide lap siding and single-gable roof with front-facing gable. What was probably a corner recessed porch has since been enclosed. The foundation of the house is sheathed in arroyo stone and half-size piers line either side of the entry stoop.

National Register of Historic Places Continuation Sheet

Section number 7 Page 252

Old Towne Orange Historic District, Orange, CA

1170.**482 S. Orange** Historical Name: AP Number: 390-411-12 Non-Contributor

1171.**485 S. Orange** 1916 Craftsman Bungalow Historical Name: AP Number: 390-412-11

A one and one-half story house with wide lap siding and roof comprised of a single-gable section with side-facing gables. This is contrasted by a front-facing, gable dormer ornamented with cross-ties, purlins and a multi-pane, transom window. The main window extends forward to form a full-width porch supported by tapered piers connected by slatted balustrade. Entry is at center, flanked on either side by a pair of double-hung windows with transom.

1172.493 S. Orange

1911 Craftsman Historical Name: AP Number: 390-412-12 A single-story house with single-gable roof with side-facing gables. There is a smaller shed dormer with three-part louvered opening at the front portion of the roof. The main entry is via a corner recessed porch supported by a tapered pier. The house is currently sheathed in asbestos siding.

1173.510 S. Orange 1949 Historical Name: AP Number: 390-101-11 Non-Contributor

1174.**515 S. Orange** 1919 Bungalow Historical Name: AP Number: 390-102-02 A small, single-story clapboard bungalow with single, side-facing gable roof. The main entry is distinguished by a pergola overhang in the central portion of the front facade. Located on either side are large, three-part windows with central transoms.

National Register of Historic Places Continuation Sheet

Section number _____7 Page _____253___

Old Towne Orange Historic District, Orange, CA

1175.**518 S. Orange** 1949 Historical Name: AP Number: 390-101-10 Non-Contributor

1176.525 S. Orange 1919 Historical Name: AP Number: 390-102-03 A small box shaped stucco sided home with a wood-trimmed flat roof and three vertical windows offset from covered entry and includes a large picture window.

1177.**528 S. Orange** 1914 Historical Name: AP Number: 390-101-09 Non-Contributor

1178.**535 S. Orange** 1918 Craftsman Bungalow Historical Name: AP Number: 390-102-04 A single-story bungalow w

A single-story bungalow with wide lap siding and shallow-pitched, multigabled roof. One-half of the front facade is devoted to a projecting gable which forms the entry porch overhang. This gable is supported by piers composed of wide bases and smaller posts on top. Cross-ties in the upper gable face add embellishment. The original door with plate glass windows is still present.

1179.545 S. Orange
1923 Bungalow
Historical Name:
AP Number: 390-102-05
A single-story clapboard bungalow with shallow-pitched, multi-gabled roof.
The central portion of the front facade features a projecting gable which
acts as an entry overhang. This is now supported by ornamental iron posts, a
replacement of the original. The original door with plate glass windows is
still present and is flanked on either side by large, three-part picture
windows.

National Register of Historic Places Continuation Sheet

Section number 7 Page 254

Old Towne Orange Historic District, Orange, CA

1180.604 S. Orange
1925 California Bungalow
Historical Name:
AP Number: 390-106-13
A single-story clapboard bungalow with single-gabled roof with side-facing
gables. The entry is located at the center and is articulated by a small
gabled portico with an inner arched bracket support. The house is otherwise
simple and unembellished.

1181.609 S. Orange

1915 Craftsman Historical Name: AP Number: 390-105-01 A one and one-half story house with wide lap siding and single, side-facing gabled roof. A small shed dormer is located on the front portion of the roof. The main roof extends forward to form what was once a full-width porch but has since been enclosed on one-half.

1182.612 S. Orange

1914 Craftsman Historical Name: AP Number: 390-106-11 A one and one-half story house with wide lap siding and single, side-facing gabled roof. The front-facing gable dormer with purlins and louvered transom is present. The entry is recessed beneath the main roof; no porch is present. It appears that there has been some modification on the front facade, specifically this includes the brick facing along the lower half of the front facade.

1183.615 S. Orange
1927 Provinincial Revival
Historical Name:
AP Number: 390-105-02
A L-plan single-story residence with stucco facade and gable roof. The entry
is at the apex of the wall beneath an extension of the front facing gable. A
picture window framed by a set of 3 double-hung mullioned windows is present
on the front facade.

National Register of Historic Places Continuation Sheet

Section number 7 Page 255

Old Towne Orange Historic District, Orange, CA

1184.620 S. Orange

1915 Craftsman Bungalow Historical Name: AP Number: 390-106-10

A single-story bungalow with wide lap siding and single-gabled roof with side-facing gables. The house takes on an unusual appearance based on the entry which is defined by a shallow-pitched, gabled projection. This projection is supported by large, battened stone columns at the corners. The porch is enclosed by a double door entry with wide side lites on either side. On either side of these are large, transomed picture windows. Since the 1982 survey, this structure has been altered with appropriate removal of the porch door, revealing the original door.

1185.621 S. Orange

c1915 Craftsman Historical Name: AP Number: 390-105-03

A large, two-story Craftsman house with wide lap siding and single, sidefacing gabled roof. Two gable dormers are present, of which the forwardmost is the larger and most elaborate. It features exposed beams, triangular bracket supports, and a large mullioned window. The main roof extends forward to form a full-width porch supported by piers constructed of wide concrete bases and wood posts on top.

1186.626 S. Orange

1913 Bungalow Historical Name:

AP Number: 390-106-09

A regtangular plan, single-story bungalow with gable roof and wide-lap siding. The large front facing gable may have formed a front proch which has since been enclosed. The upper gable face is ornamented with small brackets and vertical wood slats framing a small window.

1187.629 S. Orange

1915 Bungalow Historical Name: AP Number: 390-105-04

A single-story rectangular plan bungalow residence with multi gables and wide-lap siding. The large front facing gable forms the entry proch which almost extends the full length of the structure. Wooden columns atop massive brick piers which support the proch roof at the corners. The brick piers repeat at a smaller scale at the lower steps of the porch and at the entry opening. A single board between the peirs forms the porch wall.

National Register of Historic Places Continuation Sheet

Section number _____7 Page ____256__

Old Towne Orange Historic District, Orange, CA

1188.635 S. Orange 1971 Historical Name: AP Number: 390-102-05 Non-Contributor

1189.636 S. Orange
1920 Craftsman
Historical Name:
AP Number: 390-106-08
A two-story house with ornamental lap siding and shallow-pitched, multigabled roof. The second story is on the rear half of the house; the front
story is characterized by two, front-facing gables. The forwardmost gable
forms the entry porch overhang and is supported by a combination of wood
posts with angular brace supports. Large, mullioned picture windows are
present on either side of the main door.

1190.114 E. Palm c1915 Bungalow Historical Name: AP Number: 039-241-01 A single-story bungalow with wide lap siding and tri-gable roof. The main portion of the house is covered by a single gable roof with side-facing gables. A narrow front-facing gable forms what was once an entry porch overhang. It has since been enclosed with glass windows.

1191.230 E. Palm c1920 Bungalow Historical Name: AP Number: 039-242-25 A single-story bungalow with wide lap siding and double, front-facing gable roof. The forwardmost gable forms the entry porch overhang and is supported by tapered piers. Ornamental purlins grace the eaves.

1192.236 E. Palm

c1915 Bungalow Historical Name: AP Number: 039-242-25 A single-story bungalow with wide lap siding and multi-gable roof. The main portion of the house is covered by a single gable roof with side-facing gables accented by a smaller gabled porch on the side of the house. A wide, front-facing gable forms a full entry porch overhang supported by tapered piers.

National Register of Historic Places Continuation Sheet

Section number 7 Page 257

Old Towne Orange Historic District, Orange, CA

1193.421 E. Palm
1917 Bungalow
Historical Name:
AP Number: 039-232-12
A single-story clapboard bungalow with single, front-facing gable roof. A
smaller, front-facing gable forms the entry porch overhang and is supported
by wide piers with concrete bases. The original hardwood door with plate
glass windows is still present in the center of the front facade.

1194.522 E. Palm
1913 Bungalow
Historical Name:
AP Number: 386-081-22
A single-story bungalow with ornamental lap siding and single-gable roof with
front-facing gable. A small gabled entry portico is present which is
adjoined by a pergola on either side to form a full-width porch in front.
The original door with plate glass windows is still present.

1195.**525 E. Palm** 1964 Historical Name: AP Number: 386-131-12 Non-Contributor

1196.537 E. Palm 1914 Church Building Historical Name: AP Number: 386-131-13 A single-story box plan structure with wide lap siding and steep-pitched, hip roof. The front entry to the church is distinguished by a large, hipped projecting wing which acts as a modified cupola.

1197.603 E. Palm

c1915 Bungalow Historical Name: AP Number: 386-132-09 A single-story bungalow with wide lap siding and single-gable roof with sidefacing gable. The main roof slopes forward to form a full-width porch supported by slender wood posts. A small shed dormer is on the front portion of the roof. Since the 1982 survey, this structure has been altered with inappropriate bay window and porch screen.

National Register of Historic Places Continuation Sheet

Section number _____7 Page _____258

Old Towne Orange Historic District, Orange, CA

1198.**608 E. Palm** 1922 Historical Name: AP Number: 386-082-28 Non-Contributor

1199.**613 E. Palm** 1914 Historical Name: AP Number: 386-132-10 Non-Contributor

1200.623 E. Palm

c1895 Victorian cottage Historical Name: AP Number: 386-132-11 A two-story house with shiplap siding and steep-pitched, multi-gable roof. The house is built on a modified L-plan with entry on the apex of the ell. There is a small shed overhang which forms a porch over the entry. High narrow windows are characteristic of the Victorian period.

1201.631 E. Palm

1917 Bungalow Historical Name: AP Number: 386-132-12 A small, single-story bungalow distinguished by double, front-facing gable roof. The original siding has since been covered with asbestos shingles. The smaller, forwardmost gable forms the entry porch overhang and is supported by tapered piers on concrete bases. Vertical slatting above ornaments the gable.

1202.640 E. Palm c1900 Board & Batten, Hip Roof Cottage Historical Name: AP Number: 386-082-24 This is a small pioneer type, probably handbuilt, structure with a simple box plan and steep-pitched, hip roof echoing the classical revival tendency of the period. Board and batten siding, however, is an indication that it is probably not contractor built. There is a nearly full-width porch in the front which has its own separate shed roof overhang supported by wood posts with ornamental brackets in between.

National Register of Historic Places Continuation Sheet

Section number _____7 Page _____259

Old Towne Orange Historic District, Orange, CA

1203.641 E. Palm 1905 Hip Roof Cottage Historical Name: AP Number: 386-132-13 This is the typical turn-of-the-century house with box plan, clapboard siding and steep-pitched, hip roof. Entry is via a corner recessed porch supported by a single classical column. A hipped dormer is on the upper front portion of the roof.

1204.648 E. Palm 1923 Bungalow Historical Name: AP Number: 386-082-23 This is a single-story clapboard bungalow with single, shallow-pitched gable roof with side-facing gables. The center portion of the front facade is adorned by an entry porch portico with a gable roof supported by slender wood posts.

1205.654 E. Palm 1923 Bungalow Historical Name: AP Number: 386-082-22 A single-story bungalow with rectangular plan and single-gable roof with side-facing gables. Original siding has since been covered with asbestos shingles. The center portion of the front facade is distinguished by a gabled entry portico with tapered piers. Original door with plate glass panes is still present. Sine the 1982 survey, the clapboard siding has been restored.

1206.705 E. Palm 1923 Bungalow Historical Name: AP Number: 386-133-11 This is a single-story clapboard bungalow with double, front-facing gable roof. The smaller, front-facing gable forms an entry porch overhang over recessed corner porch. The porch overhang is supported by tapered wood piers on brick bases. There is a dramatic entry presented by a plate glass window door flanked on either side by mullioned side lites.

National Register of Historic Places Continuation Sheet

Section number 7 Page 260

Old Towne Orange Historic District, Orange, CA

1207.709 E. Palm 1923 Bungalow Historical Name: AP Number: 386-133-12 A single-story clapboard bungalow with multi-gable roof. The front-facing gable forms an entry porch overhang supported by wood posts. Vertical slatting in the upper gable face acts as embellishment. Since the 1982 survey, this structure has been altered with inappropriate solid porch rail.

1208.715 E. Palm 1912 Bungalow Historical Name: AP Number: 386-133-13 A single-story bungalow with lap siding and a single, front-facing gable roof. The house is basic and unembellished.

1209.**725 E. Palm** 1915 Bungalow Historical Name: AP Number: 386-133-14 A single-story bungalow with wide lap siding and double.

A single-story bungalow with wide lap siding and double, front-facing gable roof. The forwardmost gable forms the entry porch overhang supported by slender wood posts atop a low porch wall.

1210.732 E. Palm

1923 Mediterranean Revival Historical Name: AP Number: 386-083-21 This house is one of several in Orange which is a simplified take-off on the Mediterranean Revival bungalows. It's a simple, rectangular plan house with stucco siding on the facades and with a flat roof. A projection on the front part of the house forms an entry porch portico. Please note: there is a large remodeled side addition on the house.

1211.740 E. Palm

1923 Mediterranean Revival Historical Name: AP Number: 386-083-20 This house is identical to that at 732 E. Palm--a simplified take=off on the Mediterranean Revival bungalow. It is a simple rectangular plan with stucco siding on the facades and with a flat roof. A projection on the front part of the house forms an entry porch portico.

National Register of Historic Places Continuation Sheet

Section number _____7 Page _____261

Old Towne Orange Historic District, Orange, CA

1212.817 E. Palm c1927 Mediterranean Revival Historical Name: AP Number: 386-134-12 A single-story, Mediterranean Revival bungalow with stucco siding on the facades and with a flat roof with raised parapets on the corners. The house is built on a modified L-plan, the entry being in the apex of the ell enclosed by an arched entry portico. A tile hood is present over both the entry portico and the picture windows in the front facade.

1213.827 E. Palm

1921 Bungalow Historical Name: AP Number: 386-134-13

A single-story clapboard bungalow with shallow-pitched, multi-gable roof. Main portion of the house is covered by a single-gable roof with side-facing gables. A wide front-facing gable forms the entry porch overhang supported by wood piers atop brick bases. Main entry consists of a mullioned plate glass door with mullioned side lites.

1214.837 E. Palm

1921 Bungalow Historical Name: AP Number: 386-134-14 A single-story bungalow with shallow-pitched, multi-gable roof. The original siding has since been covered with asbestos shingles. The roof line is composed of two juxtaposing gables, one side-facing and the other a small front-facing gable which also acts as an attic dormer vent.

1215.917 E. Palm

1931 Bungalow Historical Name: AP Number: 386-121-12 A single-story clapboard bungalow with double, front-facing gable roof. The forwardmost gable forms the entry porch overhang and is now supported by wrought iron posts, a replacement for the original.

National Register of Historic Places Continuation Sheet

Section number _____7 Page _____262___

Old Towne Orange Historic District, Orange, CA

1216.**926 E. Palm** 1924 Bungalow

Historical Name:

AP Number: 386-091-23

A single-story clapboard bungalow with shallow-pitched, multi-gable roof. Main portion of the house is covered by a single-gable roof with side-facing gables. A front-facing gable acts as an entry porch overhang supported by wrought iron piers, a replacement for the original.

1217.931 E. Palm

1923 Bungalow Historical Name: AP Number: 386-091-23 A rectangular plan house with multi-gables and clapboard siding. The main portion of the house is covered by a side to side gable. A front facing gable extends forward to form the entry porch overhang. This is supported by classical columns and dentils running across the lower gable face. The front facade is embellished by 3 sets of paired windows.

1218.118 W. Palm

c1920 Bungalow Historical Name:

AP Number: 039-163-19

A single-story clapboard bungalow with multi-gable roof. The roof is fashioned in an L-plan with the short leg resulting in a front-facing gable which forms the entry porch overhang. This gable is supported by slender wood posts atop ornamental concrete bases. There is a connecting slatted balustrade contrasted by slatting in the upper gable face. This bungalow house has a built-in garage which was probably a later addition.

1219.133 W. Palm c1915 Bungalow Historical Name: AP Number: 039-153-06 A single-story clapboard bungalow with single front-facing gable roof. The main roof extends forward to form a full-width porch which is supported by tapered piers atop wood bases. The lower foundation wall and half-piers near the porch stoop are also of brick The double entry indicates the house was originally intended for duplex usage.

National Register of Historic Places Continuation Sheet

Section number _____7 Page _____263

Old Towne Orange Historic District, Orange, CA

1220.141 W. Palm

1915 Bungalow

Historical Name: AP Number: 039-153-05

A single-story clapboard bungalow with double front-facing gable roof. The forwardmost gable forms the entry porch overhang and is supported by tapered piers on brick bases. The main entry is flanked on either side by a trio of sash windows with ornamental upper sashes. This is complemented by the leaded glass transom in the porch gable face. Since the 1982 survey, this structure has been altered with in appropriate fencing.

1221.230 W. Palm

c1915 Bungalow

Historical Name: AP Number: 039-162-20

A single-story bungalow with wide lap siding and multi-gable roof. The centrally located front-facing gable extends forward to form the entry porch overhang and is supported by tapered piers on concrete bases. The original door with plate glass windows is beneath and flanked on either side by windows with mullioned transoms.

1222.233 W. Palm

1912 Bungalow Historical Name: AP Number: 039-152-07

A single-story bungalow with ornamental lap siding and double front-facing gable roof. The lower, smaller front-facing gable runs parallel to the main roof gable and acts as an entry porch overhang supported by tapered piers. Vertical slatting provides ornamentation in the upper gables.

1223.237 W. Palm 1941 Historical Name: AP Number: 039-152-06 Non-Contributor

National Register of Historic Places Continuation Sheet

Section number _____7 Page _____264

Old Towne Orange Historic District, Orange, CA

1224.238 W. Palm c1915 Bungalow Historical Name: AP Number: 039-162-01 A single-story bungalow with wide lap siding and shallow-pitch, multi-gable roof. The front facade features three front-facing gables of which the widest acts as an entry porch overhang defining a wrap-around porch. Porch gables are supported by wood posts on concrete bases.

1225.303 W. Palm 1954 Historical Name: AP Number: 039-151-28 Non-Contributor

1226.205 E. Palmyra 1888 Victorian Historical Name: C.Z. Culver House AP Number: 390-396-04 This is a large, three-story Victorian house with a multi-gable roofline. The original siding has since been covered with asbestos shingles. The house is comprised of robust and dynamic massing typical of the Queen Anne style Victorians. Built on a modified box plan, the house features several bay projections. A larger, wrap-around porch extends the full width of the front facade and around the east side. This porch is characterized by an attached roof with a gable portico at the point of entry. The porch is supported by

ornate turned columns with ornamental brackets. The third story dormer in front includes a balcony with ornamental balustrade. The house is in excellent condition and retains its original architectural integrity except for the newer siding. The original siding is probably still underneath. The house was added to the National Register of Historic Places in 1986.

1227.214 E. Palmyra

1909 Hip Roof Cottage Historical Name: AP Number: 390-402-24

A single-story Classical-Revival house with wide lap siding and pyramidal roof. The roof extends forward to form a large corner, wrap-around porch supported by Classical columns. A modified gambrel dormer is present on the front portion of the roof.

National Register of Historic Places Continuation Sheet

Section number _____7 Page _____265___

Old Towne Orange Historic District, Orange, CA

1228.215 E. Palmyra c1920 Bungalow Historical Name: AP Number: 390-396-05 Non-Contributor. Since the 1982 survey, this structure has been demolished and replaced with a garage for 205 Palmyra.

1229.220 E. Palmyra

c1900 Hip Roof Cottage Historical Name: AP Number: 390-402-23 A single-story house with flattened hip roof and gable roof portions on the rear of the house. What was once a full-width porch has since been enclosed, although it appears to have been done in earlier days of the house. What was the porch overhang is a separate roof extension and is supported by wood posts.

1230.221 E. Palmyra

1915 Craftsman Bungalow Historical Name: AP Number: 390-396-06 A single-story bungalow with double, front-facing gable roof and ornamental lap siding. The forwardmost gable forms the entry porch overhang supported by round columns connected by slatted balustrade.

1231.225 E. Palmyra

c1920 Bungalow Historical Name: AP Number: 390-396-07 A single-story house with multi-gable roof and entry beneath a corner recessed porch supported by wide tapered piers. The shiplap siding indicates pre-1900 origins.

1232.230 E. Palmyra 1908 Hip Roof Cottage Historical Name: AP Number: 390-402-22 A single-story clapboard house with pyramidal roof and corner recessed porch supported by a single round Classical column.

National Register of Historic Places Continuation Sheet

Section number 7 Page 266

Old Towne Orange Historic District, Orange, CA

1233.235 E. Palmyra

1919 Craftsman Bungalow Historical Name: AP Number: 390-396-08 A single-story clapboard bungalow with a multi-gable roof. This house has an unusually complex roofline, one portion of which extends forward to form a porch overhang supported by a wide pier. The main door is the original hardwood door with small rectangular pane and is flanked on either side by side vents.

1234.238 E. Palmyra

1909 Hip Roof Cottage Historical Name: AP Number: 390-402-21 Single-story, box plan, clapboard house with steep-pitched hip roof and small, hip dormer in front. Entry is via a corner recessed porch supported by a classically treated wood post. A low slatted balustrade connects the posts and house. A large picture window with mullioned transom distinguishes the front facade. Since the 1982 survey, the front door has been relocated, the porch steps replaced, and the dormer altered.

1235.305 E. Palmyra

c1905 Hip Roof Cottage Historical Name: AP Number: 390-397-03 A single-story clapboard house with a steep-pitched, hip and gable roof. The most notable feature is the corner, wrap-around porch supported by wide Classical columns. The window on the facade curves with the curvature of the porch. Either side of the house contains a gable face with an angled bay window and ornamentation in the upper gable face.

1236.306 E. Palmyra 1963 Historical Name: AP Number: 390-403-01 Non-Contributor

National Register of Historic Places Continuation Sheet

Section number 7 Page 267

Old Towne Orange Historic District, Orange, CA

1237.313 E. Palmyra 1908 Hip Roof Cottage Historical Name: AP Number: 390-397-04 A single-sgtory house with pyramidal roof and smaller, front-facing gable which articulates the corner recessed porch. The porch is supported by Classical columns and the front facade contains a large, three-part window with multi-pane transom.

1238.**314 E. Palmyra** 1923 Mediterranean Revival Historical Name: AP Number: 390-403-23 A single-story, stucco bungalow with flat roof. Main entry is at center via a recessed porch defined by a large arched opening. Main door is flanked by side lites. On either side of the porch entry is a large, fixed-pane, picture window with adobe tiled hood.

1239.321 E. Palmyra 1904 Hip Roof Cottage Historical Name: AP Number: 390-397-05 A single-story clapboard house with combination hip and gable roof. Entry is via a corner recessed porch supported by Classical columns. Two gables, one on the side and one on the front, are embellished with ornamental shingles and an attic vent transom. A smaller, hip dormer is on the front facades. Exceptionally wide eaves are ornamented with brackets. Since the 1982 survey, this structure has been altered with inappropriate porch steps.

1240.322 E. Palmyra 1903 Hip Roof Cottage Historical Name: AP Number: 390-403-22 A single-story clapboard house with hip roof and small hip dormer on the front portion of the roof. Main entry is via a corner recessed porch supported by Classical columns with Corinthian capitals.

National Register of Historic Places Continuation Sheet

Section number _____7 Page _____268___

Old Towne Orange Historic District, Orange, CA

1241.329 E. Palmyra c1910 Transitional Historical Name: AP Number: 390-397-06 A one and one-half story house with shiplap siding and multi-gable roof. The large gable face on the front facade is defined by a return at the eaves and a small corner, recessed porch with separate roof overhang supported by thin wood posts. Since the 1982 survey, this structure has been altered with appropriate porch posts and rail.

1242.330 E. Palmyra

1912 Craftsman Historical Name: AP Number: 390-403-21

A single-story clapboard bungalow with double, front-facing gables of which the forwardmost gable forms the entry porch overhang. This overhang is supported by tapered piers connected by a low porch wall. Ornamental purlins grace the eaves. Since the 1982 survey, this structure has been altered with inappropriate porch stair rails.

1243.338 E. Palmyra

1905 Hip Roof Cottage Historical Name: AP Number: 390-403-20 A single-story house originally with clapboard siding, much of which has now been covered with asbestos siding. The roof is defined by several hip portions. The main portion of the roof results in a large, wrap-around corner porch. There is a small hip dormer present on the front portion of the roof. Porch supports are Classical columns with Corinthian capitals.

1244.339 E. Palmyra 1907 Transitional Historical Name: AP Number: 390-397-07 A two-story clapboard house with multi-gable roof of which the front facade is defined by a large, front-facing gable with a return at the eaves. Entry is via a corner recessed porch supported by a Classical column. The side of the house is defined by a large, projecting gable dormer on the second story which results in an angled bay window on the first story. Ornamental brackets are on the front gable base.

National Register of Historic Places Continuation Sheet

Section number _____7 Page _____269

Old Towne Orange Historic District, Orange, CA

1245.403 E. Palmyra 1904 Hip Roof Cottage Historical Name: AP Number: 390-398-04 A single-story clapboard house with hip roof and two hip dormers and a corner, wrap-around porch supported by Classical columns. A concrete hitching post is present in the front yard of this contributing residence. This is one of only two original hitching posts remaining in their original location within the District.

1246.417 E. Palmyra

1922 Bungalow Historical Name: AP Number: 390-398-05 A single-story clapboard bungalow with shallow-pitched, multi-gable roof. Entry is via a corner recessed porch supported by a wood post. Since the 1982 survey, a large, inapproproate in scale addition has been built in the rear.

1247.421 E. Palmyra

1913 Craftsman Bungalow Historical Name: AP Number: 390-398-06 A one and one-half story bungalow with wide lap siding and multi-gable roof. The front-facing gable defines the porch overhang and is supported by tapered piers. The upper, front-facing gable face is embellished with a three-part window with transom, with purlins beneath the eaves and lattice work for attic venting.

1248.422 E. Palmyra

1915 Craftsman Bungalow Historical Name: AP Number: 390-404-23 A single-story bungalow with double, front-facing gable roof. The house was originally sided in clapboard, no doubt, but is now covered by asbestos siding. The forwardmost gable forms the entry porch overhang and is supported by piers of concrete bases with wood posts on top.

National Register of Historic Places Continuation Sheet

Section number 7 Page 270

Old Towne Orange Historic District, Orange, CA

1249.429 E. Palmyra 1928 Mediterranean Revival Historical Name: AP Number: 390-398-07 A single-story stucco house with a flat roof. The entry is via a porch with a large, ornamental opening and a tile hood above. The arch of the porch opening is carried out on the adjacent three-part picture window.

1250.430 E. Palmyra 1916 Prairie Influenced

Historical Name: AP Number: 390-404-22 A single-story house with stucco siding and flat roof. Entry is via a large recessed porch built beneath the main portion of the house and supported by wide concrete piers. A large picture window with transom is on either side of the porch. Entry is at center. The original door is still present and is flanked by original side lites.

1251.435 E. Palmyra

1895 Victorian Historical Name: AP Number: 390-398-03

A large, two-story home set on a corner which played an anchor role in the neighborhood. The house has shiplap siding and a multi-gable roof treated in the Victorian manner. A porch at the first story is defined by a separate roof overhang now supported by wrought iron posts which have been modified from the original. Windows around the house are the large, narrow Victorian windows and are ornamentally framed in the Victorian manner. A modified palladian window is present in the upper, front-facing gable face. Ornamental jigsawn brackets grace the eaves around the house.

1252.440 E. Palmyra

1903 Transitional Historical Name: AP Number: 390-404-21

A two-story house with combination slump stone, clapboard and shingle siding and a large gable roof. Entry is via a corner recessed porch supported by Classical columns. The remaining half of the front facade on the first story is defined by an angled bay window with a large window on each bay side. The low porch wall is of slump stone, the first story is in clapboard, and the upper gable face is embellished with shingles. Brackets grace the eaves at the first story; a large, arched three-part window is featured in the upper gable face.

National Register of Historic Places Continuation Sheet

Section number _____7 Page _____271

Old Towne Orange Historic District, Orange, CA

1253.504 E. Palmyra

1913 Bungalow Historical Name: AP Number: 390-421-01

A single-story bungalow house with wide lap siding and single, side-facing gable roof. Small dormer gable is present in front. The main roof extends forward to form a full-width porch overhang and is supported by wood posts. The front door is the original door with window panes and is flanked in an unusual way by multi-paned side lites. A large, three-part window with transom is present on the other half of the front facade.

1254.505 E. Palmyra

1909 Bungalow Historical Name:

AP Number: 390-433-22

This is a very large, two-story house with clapboard siding and combination hip and gable roof. The most notable feature of the house is the double decked corner, wrap-around porch on both the first and second floors. Each is supported by a Classical column with Corinthian capital. Wide eaves of the house are graced with ornamental brackets. Large framed windows are located throughout the facade, and of a notable presence is the small, stained glass transom on the front portion of the house.

1255.511 E. Palmyra

1920 California Bungalow Historical Name: AP Number: 390-433-21

A single-story bungalow with clapboard siding and tri-gable roof, each gable resulting in a small clipped gable. The front-facing gable occupies the center of the front facade and may have originally supported an open porch which has since been enclosed. Large, three-part window with transom is on either side of the porch projection.

1256.512 E. Palmyra

1913 Craftsman Bungalow Historical Name:

AP Number: 390-421-02

A single-story house with wide lap siding and single, side-facing gable roof. A wide shed dormer with windows of ornamental glass is on the front portion of the roof. One-half of the front facade is comprised of a recessed porch supported by a tapered pier.

National Register of Historic Places Continuation Sheet

Section number 7 Page 272

Old Towne Orange Historic District, Orange, CA

1257.**517 E. Palmyra** 1921 Craftsman Bungalow

Historical Name:

AP Number: 390-433-20

A single-story house with wide lap siding and multi-gable roof with shallowpitched gables. The front facade of the house is defined by a wide, frontfacing gable extending forward to form a full-width porch supported by piers with brick bases and wood posts on top. Entry is at center, flanked on either side by a large, three-part window.

1258.520 E. Palmyra

1912 Craftsman Historical Name: AP Number: 390-421-03

A one and one-half story Craftsman house with wide lap siding and single, side-facing gable roof. The main roof is contrasted by a front-facing gable dormer ornamented with louvered venting, ornamental purlins and cross-ties in the upper gable face. An ornamental brick chimney is also present. The main roof extends forward to form a full-width porch supported by arroyo stone piers with fluted posts on top.

1259.521 E. Palmyra

1921 Provincial Revival Historical Name: AP Number: 390-433-19

A single-story house with steep-pitched, multi-gable roof and stucco siding. Entry is via a centrally located, recessed porch beneath a small gable face. Two front-facing gables articulate the front portion of the house; each is embellished with half timbering. The arched opening to the entry and the windows on either side are framed in ornamental brick.

1260.528 E. Palmyra

1914 Craftsman Bungalow Historical Name: AP Number: 390-421-04

A single-story house with wide lap siding and multi-gable roof, all gables side-facing. The main portion of the roof extends forward in the center to form a porch overhang and is supported by wide piers with wood posts on top. The original door with single large pane is present on the front. Since the 1982 survey, this structure has been altered with appropriate porch rail removal.

National Register of Historic Places Continuation Sheet

Section number 7 Page 273

Old Towne Orange Historic District, Orange, CA

1261.535 E. Palmyra

1918 Craftsman Historical Name: AP Number: 390-433-18

A one and one-half story clapboard house with single, side-facing gable roof contrasted by a front-facing dormer gable. Entry is via a centrally located recessed porch and is flanked on either side by a large, three-part window with ornamental beveled glass transom. The front-facing dormer gable is embellished with dentils, louvered venting and ornamental purlins.

1262.536 E. Palmyra

1913 Craftsman Bungalow Historical Name: AP Number: 390-421-05 A single-story bungalow

A single-story bungalow with wide lap siding and shallow-pitched, multi-gable roof. The main entry is at front center and is defined by a gable projection which forms an entry porch and is supported by brick elephantine piers. The porch gable features exposed beams in the Oriental manner.

1263.544 E. Palmyra

1919 Craftsman Bungalow Historical Name: AP Number: 390-421-06 A single-story, tri-gable bungalow with wide lap siding. The main portion of the house is covered by a single-gable roof with side-facing gables; a centrally located, front-facing gable forms what was originally a porch overhang. This porch has since been screened in. Tapered piers support the gable overhang which is also ornamented by a framed transom and ornamental purlins.

1264.545 E. Palmyra

1923 Bungalow Historical Name: AP Number: 390-433-17 A single-story bungalow with clapboard siding and multi-gable, shallowpitched roof fashioned in an L-plan with the short leg resulting in a frontfacing gable face. The remaining portion of the front facade is defined by a recessed porch supported by an elephantine pier.

National Register of Historic Places Continuation Sheet

Section number _____7 Page _____274

Old Towne Orange Historic District, Orange, CA

1265.552 E. Palmyra

1925 Eclectic Historical Name: AP Number: 390-421-07 This is a large, two-story house with Provincial Revival influences. The house is comprised of stucco siding with steep-pitched, multi-gable roof fashioned in an L-plan. The short leg of the ell results in a large, frontfacing gable face with the uppermost peak having been clipped. Windows are grouped largely in pairs. The front door is Cotswold style.

1266.**604 E. Palmyra** 1965 Historical Name: AP Number: 390-421-08 Non-Contributor

1267.605 E. Palmyra 1921 Bungalow Historical Name: AP Number: 390-433-16 A single-story bungalow with wide lap siding and shallow-pitched, multi-gable roof. One-half of the front facade is comprised of a recessed porch now supported by wrought iron posts, a replacement for the original.

1268.610 E. Palmyra 1965 Historical Name: AP Number: 390-421-09 Non-Contributor

1269.**615 E. Palmyra** 1916 Craftsman Historical Name: AP Number: 390-433-16 A large, one-story Craftsman house with wide lap siding and single, sidefacing gable roof. A wide shed dormer is present on the front portion of the roof. One-half of the front facade is comprised of a recessed porch supported by a tapered pier.

National Register of Historic Places Continuation Sheet

Section number 7 Page 275

Old Towne Orange Historic District, Orange, CA

1270.625 E. Palmyra

1922 Craftsman Bungalow Historical Name: AP Number: 390-433-14 A single-story house with shallow-pitched, multi-gable roof arranged in an Lplan and siding now covered by asbestos. The short leg of the ell on the gable roof extends forward to form the entry porch overhang which is supported by thin wood posts. This upper gable face is ornamented with slats.

1271.628 E. Palmyra

1909 Hip Roof Cottage Historical Name: AP Number: 390-421-10 A one and one-half story house with shiplap siding and hip roof with a small hip dormer on the front portion. The full front of the house is comprised of a recessed porch beneath the main roof overhang supported by wood posts with a connecting porch wall. Entry is at center.

1272.631 E. Palmyra

1909 Vernacular Historical Name: AP Number: 390-433-13 A small, single-story clapboard house with multi-gable roof primarily comprised of side-facing gables. The center front of the house consists of a small, gable entry portico supported by tapered piers.

1273.639 E. Palmyra

1921 Bungalow Historical Name: AP Number: 390-433-12 A single-story clapboard bungalow with single, front-facing gable roof. A parallel gable, slightly smaller and shorter, is present on the front facade which defines what may have once been an open porch but has since been enclosed.

National Register of Historic Places Continuation Sheet

Section number _____7_ Page _____276_

Old Towne Orange Historic District, Orange, CA

1274.640 E. Palmyra

c1910 Transitional Historical Name: Dr. Ida Parker Home AP Number: 390-421-11 This is a two-story, Classical Revival style house with multi-gable roofline and clapboard siding. A large, full-width, front-facing gable is contrasted with a smaller, angled bay window on the northeast corner of the house and the large, wrap-around porch on the opposite corner. An attached roof that rounds the corner forms the porch overhang supported by simple Classical columns; a small pediment marks the entry on the porch overhang. The upper gable face in front features a semi-Palladian arrangement formed by the three-part window and louvered transom above. The house is in good condition and retains its full original architectural integrity.

1275.701 E. Palmyra

c1905 Hip Roof Cottage Historical Name: AP Number: 390-434-25 A single-story clapboard house with hip roof and smaller, front-facing gable on the front plane of the roof. Entry is via a corner recessed porch supported by wood posts. Original screen door is still present on the house. Since the 1982 survey, this structure has been altered with inappropriate aluminum window.

1276.**713 E. Palmyra** 1911 Transitional Historical Name: AP Number: 390-434-24 A two-story house with rectangular plan and single, front-facing gable roof. Entry is via a corner recessed porch supported by wood posts. Ornamental purlins grace the eaves.

1277.**721 E. Palmyra** 1950 Historical Name: AP Number: 390-434-23 Non-Contributor

National Register of Historic Places Continuation Sheet

Section number _____7 Page _____277__

Old Towne Orange Historic District, Orange, CA

1278.733 E. Palmyra

1907 Hip Roof Cottage Historical Name: AP Number: 390-434-22 A one and one-half story house with combination clapboard and wide lap siding and combination hip and gable roof. The main portion of the roof extends forward to form a large corner, circular wrap-around porch supported by Classical columns. The remaining front facade is defined by a wing that extends forward and is articulated by a pedimented gable. In this gable face there is a large window with ornamental transom.

1279.737 E. Palmyra 1906 Hip Roof Cottage Historical Name: AP Number: 390-434-21 A one and one-half story house with clapboard siding and combination hip and gable roof. The front facade is defined by a half corner porch supported by Classical columns. Just above there is a pedimented gable with ornamental bargeboard on the front portion of the roof.

1280.**739 E. Palmyra** 1949 Historical Name: AP Number: 390-434-20 Non-Contributor

1281.803 E. Palmyra 1919 Historical Name: AP Number: 390-434-19 Non-Contributor

1282.807 E. Palmyra 1958 Historical Name: AP Number: 390-434-18 Non-Contributor

National Register of Historic Places Continuation Sheet

Section number 7 Page 278

Old Towne Orange Historic District, Orange, CA

1283.815 E. Palmyra

1922 California Bungalow

Historical Name: AP Number: 390-434-17

A single-story clapboard bungalow with single, side-facing gable roof. The front facade is defined by a small, arched entry portico supported by large curvalinear brackets. The main door is framed by an arched frame. Large, multi-paned windows flank either side of the main entry.

1284.817 E. Palmyra c1920 Bungalow Historical Name: AP Number: 390-434-16 A single-story clapboard house with shallow-pitched, multi-gable roof. The house is built in a U-plan with the legs of the U resulting in front-facing, gable porch overhangs. Each has its own separate entrance, indicating duplex usage of the house. Each gable is supported by piers with brick bases and wood posts on top, arranged in an ornamental fashion to adorn these gable faces.

1285.831 E. Palmyra 1940 Historical Name: AP Number: 390-434-15 Non-Contributor

1286.837 E. Palmyra 1940 Historical Name: AP Number: 390-434-14 Non-Contributor

1287.119 W. Palmyra c1920 Bungalow Historical Name: AP Number: 390-654-12 Low-to-the-ground bungalow cottage with multi-gable roof and wide clapboard siding. Bungalow is built on an L-plan with entry in apex of ell.

1288.**126 W. Palmyra** Historical Name: AP Number: 390-601-18 Non-Contributor

National Register of Historic Places **Continuation Sheet**

Section number _____7 Page _____279 Old Towne Orange Historic District, Orange, CA

1289.127 W. Palmyra 1906 Hip Roof Cottage Historical Name: AP Number: 390-654-11 Single-story, box plan house with a steep-pitched, hip roof and clapboard siding. Wide entry porch has its own separate roof which extends forward and is supported by Classical columns. The house has a raised foundation, and the main entry is reached via a stoop. A small gabled pediment adorns the center front of the house.

1290.139 W. Palmyra 1977 Historical Name: AP Number: 390-654-10 Non-Contributor

1291.206 W. Palmyra

c1915 Craftsman Historical Name: AP Number: 390-654-10 One and one-half story Craftsman home with single, side-facing gable roof contrasted with smaller, front-facing gabled dormer. Main roof extends forward to form entry porch overhang and is supported by elephantine piers with brick bases. A smaller gabled adjunct is on the side of the house and is also supported by an elephantine pier. Ornamental purlins grace the gable eaves.

1292.219 W. Palmyra

1904 Hip Roof Cottage Historical Name: AP Number: 390-653-10 Small, single-story house with a steep-pitched hip roof and wood shingle siding which is a later addition to the house. A small hipped dormer graces the front portion of the roof, while an additional extension forms an entry porch overhang. The house has been modified in the front porch portions and through the use of a more contemporary siding.

National Register of Historic Places Continuation Sheet

Section number _____7 Page _____280___

Old Towne Orange Historic District, Orange, CA

1293.222 W. Palmyra

1897 Victorian Historical Name: AP Number: 390-603-20

This Victorian era house has been remodeled in such a way as to make it even more Victorian than it originally was. What was at first a simple homestead house has been remodeled by the present owner in order to make of the house a more ornate Victorian style. The house features a basic box plan with sidefacing gable to which a front-facing gable has been added with an angled bay window and a unique palladian transom in the uppermost portion of this front gable. Ornamental porch posts, decorative brackets and other work on the house is very characteristic of the Victorian period.

1294.225 W. Palmyra

1919 Bungalow Historical Name: AP Number: 390-653-09

Low-to-the-ground, single-story bungalow with shallow pitched, single, frontfacing gable roof and a box plan. Smaller secondary gable to the side of the house on the front side extends forward to form an entry porch overhang and is supported by two wood posts.

1295.226 W. Palmyra

1913 Craftsman Bungalow Historical Name: AP Number: 390-603-19

Single-story clapboard bungalow with double, front-facing gable roof. Frontmost gable forms entry porch overhang and is supported by elephantine piers with arroyo stone bases. Ornamental purlins distinguish the eaves. Wide transomed, picture wondows and handcrafted door distinguish the front facade.

1296.231 W. Palmyra 1968 Historical Name: AP Number: 390-653-08 Non-Contributor

National Register of Historic Places Continuation Sheet

Section number _____7 Page _____281__

Old Towne Orange Historic District, Orange, CA

1297.305 W. Palmyra c1910 Hip Roof Cottage Historical Name: AP Number: 390-652-13 Single-story house with modified L-plan, hip roof and clapboard siding. Frontmost portion extends forward to form a gable face. Entry is beneath main roof overhang in apex of ell.

1298.**313 W. Palmyra** 1946 Historical Name: AP Number: 390-652-12 Non-Contributor

1299.**325 W. Palmyra** Historical Name: AP Number: 390-652-11 Non-Contributor

1300.**327 W. Palmyra** 1939 Historical Name: AP Number: 390-652-10 Non-Contributor

1301.335 W. Palmyra 1916 Craftsman Bungalow Historical Name: AP Number: 390-652-09 Single-story clapboard bungalow with shallow pitched, single-gable roof. Roof extends forward to form entry porch overhang and is supported by unique combination of posts to form piers. Slatting in front gable face adds ornamentation.

1302.604 W. Palmyra

1925 Provincial Revival Historical Name: AP Number: 041-133-25 Two-story, stucco house with multi-gable roof. Gables are clipped. Smaller, single-story gable projections form separate wings of the house and are highlighted by curved extensions of the lower facade on the sides.

National Register of Historic Places Continuation Sheet

Section number 7 Page 282

Old Towne Orange Historic District, Orange, CA

1303.614 W. Palmyra

1926 Provincial Revival

Historical Name: AP Number: 041-133-26

Single-story house with steep pitched, multi-gable roof. House is built on a U-plan with each of the extensions of the U having a separate gable. Entry is recessed beneath center of U. Large arched picture window, which is multi-paned, adorns one of the front-facing gables.

1304.656 W. Palmyra

1920 Craftsman Bungalow Historical Name: AP Number: 041-133-27 Low-to-the-ground, single-story bungalow with shallow pitched, multi-gable roof and clapboard siding. Frontmost gable extends forward to form entry porch overhang and is supported by tapered piers. A porte cochere is located to the side and is also supported by tapered piers.

1305.664 W. Palmyra

1946 Provincial Revival Historical Name: AP Number: 041-133-02 Single-story clapboard house built on an L-plan with multi-gable roof. Frontmost portion of ell extends forward and incorporates half-timbering and a large picture window. Please note: While the house was built post-1940, it incorporates the stylistic features of the earlier architectural periods.

1306.690 W. Palmyra

1906 Vernacular Historical Name: AP Number: 041-133-01 A large, two and one-half story vernacular farmhouse with a multi-gable roofline. The original siding has been covered with asbestos shingles. Each upper gable features ornamental exposed beams and a transom of louvered vents and mullioned windows. А large boxy, wrap-around porch in the Mediterranean/Prairie Style was added circa 1925 which significantly disguises the original style of the house. A porte-cochere is located to the side.

National Register of Historic Places Continuation Sheet

Section number _____7 Page ____283

Old Towne Orange Historic District, Orange, CA

1307.704 W. Palmyra c1900 Rural Vernacular Historical Name: AP Number: 041-132-22 Two-story, tri-gable, L-plan house with steep pitched, gable roof and shiplap siding. The main entry is beneath the porch extension at the corner of the lower story and is supported by slender ornamental posts. Windows are framed in the Victorian manner, and a small ornamental transom is in uppermost portion of front gable face. 1308.714 W. Palmyra 1946 Historical Name: AP Number: 041-132-23 Non-Contributor 1309.720 W. Palmyra 1929 Historical Name: AP Number: 041-132-24 Non-Contributor 1310.730 W. Palmyra 1947 Historical Name: AP Number: 041-132-02 Non-Contributor 1311.798 W. Palmyra c1905 Craftsman Historical Name: AP Number: 041-132-29 Two-story house with a box plan and single, front-facing gable roof contrasted by smaller, side-facing gable dormers and a porch covering on lower story of front supported by Classical columns. Windows are framed in the period manner. Ornamental purlins grace the eaves. 1312.322 S. Parker

1946 Historical Name: AP Number: 041-132-21 Non-Contributor

National Register of Historic Places Continuation Sheet

Section number 7 Page 284

Old Towne Orange Historic District, Orange, CA

1313.**323 S. Parker** 1949 Historical Name: AP Number: 041-133-03 Non-Contributor

1314.328 S. Parker 1908 Bungalow Historical Name: AP Number: 041-132-20 Single-story clapboard bungalow with double, front-facing gables. Decorative shingles are located in upper gable faces. Ornamental purlins grace the eaves. Entry is at front of rearmost gable. There is a porch overhang supported by columns. Entry is beneath.

1315.331 S. Parker 1927 Mediterranean Eclectic Historical Name: AP Number: 041-133-04 This is an unusual, single-story home constructed of brick with definite Spanish influences. House has a low-to-the-ground horizontal quality, flat roof with a large arcade entry along the front facade embellished with three large arched openings. This arcade has adobe tile hood.

1316.338 S. Parker 1924 Bungalow Historical Name: AP Number: 041-132-19 Single-story clapboard bungalow with single, front-facing gable roof. Smaller roof projection forms entry porch overhang. This is symmetrically placed along the front facade and is supported by tapered piers with brick bases. Ornamental purlins grace the eaves.

1317.340 S. Parker
1926 Bungalow
Historical Name:
AP Number: 041-132-18
A modified L-plan stucco bungalow residence with a front facing gable, arched
openings around entry, and a low stucco wall.

National Register of Historic Places Continuation Sheet

Section number _____7 Page _____285

Old Towne Orange Historic District, Orange, CA

1318.341 S. Parker 1926 Historical Name: AP Number: 041-133-05 Non-Contributor

1319.347 S. Parker 1924 Bungalow Historical Name: AP Number: 041-133-06 A single-story box plan bungalow with stucco siding and multi-gabled roof with a projecting gabled porch. A decorative arch spans the driveway leading to the garage.

1320.352 S. Parker 1927 Mediterranean Revival Historical Name: AP Number: 041-132-17 A single-stry stucco box plan mediterranean revival residnece with multigables and finished with flat tiles roof in rear. Large front facing arched windows with side panels enhance the front entry, which also contains a large front door with vertical side lights.

1321.**355 S. Parker** 1938 Historical Name: AP Number: 041-133-07 Non-Contributor

1322.**361 S. Parker** 1946 Historical Name: AP Number: 041-133-08 Non-Contributor

1323.**362 S. Parker** 1923 Historical Name: AP Number: 041-132-16 Non-Contributor

National Register of Historic Places Continuation Sheet

Section number 7 Page 286

Old Towne Orange Historic District, Orange, CA

1324.**366 S. Parker** 1941 Historical Name: AP Number: 041-132-15 Non-Contributor

1325.**373 S. Parker** 1954 Historical Name: AP Number: 041-133-09 Non-Contributor

1326.377 S. Parker

1928 Mediterranean Revival Historical Name: AP Number: 041-133-10

Two-story house designed in an unusual manner with Mediterranean Revival influences. Main portion of house is on a square plan with flat roof and parapeted walls. A smaller gable extension forms another wing of the house. Porte cochere extends from the side of the house. It and a hood above the French doors at the entry are of adobe tiles. Multi-paned casement windows are located around the house.

1327.**378 S. Parker** 1947 Historical Name: AP Number: 041-132-14 Non-Contributor

1328.127 N. Pine c1923 Mediterranean Revival Historical Name: AP Number: 386-074-08 A single-story, box plan house with stucco siding on the facades and with a flat roof. A front entry portico is formed by a rectalinear projection with large arched openings. Both the porch portico and main house have raised parapets, particularly at the corners, which emphasize the southwestern feel of the house. Adobe tile hoods are present above each of the windows on the front facade.

National Register of Historic Places Continuation Sheet

Section number 7 Page 287

Old Towne Orange Historic District, Orange, CA

1329.130 N. Pine
1905 Gable Roof Cottage
Historical Name:
AP Number: 386-073-11
A single-story house with predominently shiplap siding and with steep-pitched
gable roof. The main portion of the house is covered by a single side-facing
gable. A smaller front-facing gabled dormer is embellished with ornamental
shingles. Forward porch was previously present on the house but has since
been enclosed. The porch roof and piers are still present.

1330.138 N. Pine
1914 Bungalow
Historical Name:
AP Number: 386-073-12
A single-story bungalow with wide lap siding and single front-facing, gable
roof. A full-width porch is recessed beneath the main roof supported by
tapered piers above a low porch wall. Cross-ties embellish the upper gable
face.

1331.143 N. Pine
1922 Bungalow
Historical Name:
AP Number: 386-074-21
A single-story clapboard bungalow with shallow-pitched, gable roof. Roofline
is comprised of two counter-posing gables, one a side-facing gable which
extends forward and forms an entry porch overhang. This is supported by
piers comprised of brick bases and wood posts on top. The front-facing gable
acts as an attic dormer.

1332.146 N. Pine 1921 Bungalow Historical Name: AP Number: 386-073-13 A single-story clapboard bungalow with shallow-pitched, multi-gable roof. The main entry is via a corner recessed doorway. Siding is shiplapped with front facade displaying two sets of picture windows flanked by double-hung windows.

National Register of Historic Places Continuation Sheet

Section number _____7_ Page ____288

Old Towne Orange Historic District, Orange, CA

1333.**151 N. Pine** 1924 Bungalow Historical Name: AP Number: 386-074-06 A single-story clapboard bungalow with double, front-facing gable roof. The forwardmost gable forms the entry porch overhang and is supported by wide, round columns.

1334.**154 N. Pine** 1961 Historical Name: AP Number: 386-073-14 Non-Contributor

1335.**157 N. Pine** 1925 Bungalow Historical Name: AP Number: 386-074-05 A single-story clapboard bungalow with multi-gable roof. The projecting, front-facing gable forms a wide entry porch overhang supported by tapered piers.

1336.160 N. Pine 1921 Bungalow Historical Name: AP Number: 386-073-15 A single-story bungalow with wide lap siding and multi-gable roof. Entry is via a corner recessed porch in the front-facing gable. The porch overhang is supported by a wide wood post. The front-facing gable is clipped at the peak.

1337.163 N. Pine
1924 Bungalow
Historical Name:
AP Number: 386-074-04
A single-story bungalow with lap siding and double, front-facing gable roof.
The forwardmost gable forms the entry porch overhang supported by tapered
piers.

National Register of Historic Places Continuation Sheet

Section number 7 Page 289

Old Towne Orange Historic District, Orange, CA

1338.172 N. Pine 1920 Mediterranean Revival Historical Name: AP Number: 386-073-16 A single-story house with modified L-plan, stucco siding on the facades and a flat roof. A high cupola rises above the main roof, with arched openings below, to form the entry portico. A grouping of three arched, mullioned windows is present on either side of the front facade. The cupola is crowned with adobe tiles. Hoods are present on the remaining portions of the front facade.

1339.173 N. Pine
1924 Bungalow
Historical Name:
AP Number: 386-074-03
A single-story bungalow with multi-gabled, shallow-pitched roof. The
original clapboard siding has since been covered by asbestos shingles. The
main portion of the house is covered by a single, side-facing gable roof. A
smaller front-facing gable forms an entry porch overhang supported by round
columns.
1340.181 N. Pine

1924 Bungalow Historical Name: AP Number: 386-074-02 A single-story clapboard bungalow with gable roof, largely a single frontfacing gable. A full-width porch across the front facade is supported by piers with brick bases.

1341.192 N. Pine 1923 Spanish Colonial revival Historical Name: AP Number: 386-073-17 A single-story house with stucco facades and adobe tiled roof. The house is comprised of an irregular plan built on a symmetrical format, emphasis being on the center entry portico. This is comprised of a gabled overhang with large, arched opening. The main door is a large wood door with side lites flanking it on either side. A pair of casement windows on either side of the entry portico features an ornamental ball relief picturing a vase with fruits. A low wall with brick capping surrounds the front portion of the house.

National Register of Historic Places Continuation Sheet

Section number 7 Page 290

Old Towne Orange Historic District, Orange, CA

1342.193 N. Pine 1928 Spanish Colonial Revival Historical Name: AP Number: 386-074-01 A single-story house with stucco facades and multi-gable roof with adobe tiles. The tiling on the roof is the ornamental Dutch tile variety. Two steep-pitched, front-facing gables are present, the forwardmost of which slopes out to form an entry portico with large arched openings. Arched windows are present across the main portions of the front facade.

1343.205 N. Pine

1923 Provincial Revival Historical Name: AP Number: 386-084-11 This is a single-story house with Tudor Revival influences. The house has an overall Hansel and Gretal appeal derived from a very steep-pitched, gable roof with clipped gables. Half-timbering is in the upper gable faces. Arched windows and porch openings embellish the lower facades. The house is built on a box plan with stucco facades.

1344.206 N. Pine

1929 Spanish Colonial Revival Historical Name: AP Number: 386-083-12 This is a large, two-story house with stucco facades and adobe tiled, hip roof. The house is built on a box plan with a symmetrical emphasis derived by the centrally located, recessed entry portico. A balcony with iron railing is located above.

1345.213 N. Pine

1922 Bungalow Historical Name: AP Number: 386-084-10 A single-story clapboard bungalow with gable roof. Two small, front-facing gables rise out of the front portion of the roof. Below there is a fullwidth porch formed by the extension of the main roof and supported by round Colonial-like columns. The large picture windows in front have ornamental glass transoms.

National Register of Historic Places Continuation Sheet

Section number 7 Page 291

Old Towne Orange Historic District, Orange, CA

1346.214 N. Pine 1926 Spanish Colonial Revival Historical Name: AP Number: 386-083-13 A large, two-story house with modified rectangular plan, stucco facades and adobe tiled, gable roof. Entry is on the south end of the front facade and is noted by a large rectalinear projection with an arched opening on the first story for the main door and an arched opening above for a balcony entrance. Globed lights are present in their own lodge on either side of the main entry.

1347.221 N. Pine 1926 Mediterranean Revival Historical Name: AP Number: 386-084-09 A single-story box plan house with stucco facades and flat roof. A raised, stepped parapet is present along the front facades. The main entry is via an arched opening which leads to a recessed entry portico. Adobe tile hoods are above the front windows.

1348.222 N. Pine 1926 Spanish Colonial Revival Historical Name: AP Number: 386-083-14 A single-story house built on an L-plan with stucco facades and adobe tiled, gable roof. The main entry is via two large, arched openings which form a modified arcade along the front inner portion of the front facade. A large, arched mullioned window is present on the front-facing gable facade.

1349.229 N. Pine 1923 Mediterranean Revival Historical Name: AP Number: 386-084-08 A single-story house built on a modified U-plan with stucco facades and flat roof. Raised parapets on both the main house and the entry portico suggest Southwest influence. Entry is via a large arched opening into an entry portico. Adobe tiled hoods are present over the front windows.

National Register of Historic Places Continuation Sheet

Section number _____7 Page _____202

Old Towne Orange Historic District, Orange, CA

1350.237 N. Pine
1924 Mediterranean Revival
Historical Name:
AP Number: 386-084-07
A single-story house built on a modified U-plan with stucco facades and flat
roof. Entry is in the inner portion of the U beneath an adobe tiled hood.
The main door is of double, mullioned glass.

1351.240 N. Pine
1936 Spanish Colonial Revival
Historical Name:
AP Number: 386-083-15
A single-story house built on an L-plan with stucco facades and adobe tiled,
gable roof. Entry is at the apex of the ell. An arcade with arched openings
is located in the extension of the front-facing gable.

1352.245 N. Pine 1924 Mediterranean Revival Historical Name: AP Number: 386-084-06 A single-story house with stucco facades and flat roof. The house is built on the symmetrical plan with centrally located entry beneath the rectilinear projection with rectangular opening. Raised parapets suggest the Pueblo influence.

1353.250 N. Pine 1949 Historical Name: AP Number: 386-083-16 Non-Contributor

1354.253 N. Pine 1923 Bungalow Historical Name: AP Number: 386-084-05 A single-story bungalow with clapboard siding and multi-gable roof. The roofline profile is determined by two crossing gables, one a side-facing gable which extends forward to form the entry porch overhang. It is supported by wood piers of caste concrete and wood posts on top. The frontfacing gable acts as a small attic dormer.

National Register of Historic Places Continuation Sheet

Section number 7 Page 293

Old Towne Orange Historic District, Orange, CA

1355.261 N. Pine

1923 Bungalow

Historical Name:

AP Number: 386-084-04

A single-story clapboard bungalow with cross-connecting front and side-facing gables. The side-facing gable extends forward to form the entry porch overhang supported by piers of caste concrete and wood posts on top. The front-facing gable acts as a small attic dormer. Since the 1982 survey, this structure has been altered with inappropriate rock veneer on porch piers.

1356.262 N. Pine

1923 Bungalow Historical Name: AP Number: 386-083-17 A single-story clapboard bungalow with tri-gable roof. The main portion of the house is covered by a single, side-facing gable roof. The front-facing gable forms the entry porch overhang supported by piers of wood posts atop brick bases.

1357.269 N. Pine

1922 Bungalow Historical Name: AP Number: 386-084-03 A single-story clapboard bungalow with multi-gable roof. The main portion of the house is covered by a single, side-facing gable. A small, front-facing, clipped gable is on the ridge of the roof along with a front-facing, gabled entry porch. The porch is now supported by iron piers, a replacement for the original. Since the 1982 survey, this structure has been altered with appropriate porch posts and rear addition.

1358.270 N. Pine

c1920 Altered Bungalow Historical Name: AP Number: 386-084-02 A single-story clapboard bungalow with gable roof. A centrally located, front-facing gable with clipped peak and return at the eaves forms an entry porch overhang supported by tapered piers with brick bases. The main entry beneath is flanked on either side by side lites.

National Register of Historic Places Continuation Sheet

Section number _____7 Page _____294

Old Towne Orange Historic District, Orange, CA

1359.277 N. Pine
1921 Bungalow
Historical Name:
AP Number: 386-084-02
A single-story clapboard house with shallow-pitched, multi-gable roof. A
large, corner wrap-around porch is beneath the gable projections, supported
by shallow, elephantine piers atop high concrete bases. The original door
with plate glass windows is still present.

1360.278 N. Pine 1923 Bungalow Historical Name: AP Number: 386-083-19 A single-story bungalow with wide lap siding and steep-pitched, multi-gable roof. A small, front-facing gable forms the entry porch overhang which is supported by tapered piers with ornamental brick bases and wood on top.

1361.285 N. Pine 1924 Mediterranean Revival Historical Name: AP Number: 386-084-01 A single-story box plan house with stucco facades and a flat roof. A rectilinear projection with arched openings forms the entry portico in the center of the front facade. Both the main house and entry portico feature stepped parapets. Adobe tiled hoods are over each of the windows on the front.

1362.304 N. Pine 1905 Gable Roof Cottage Historical Name: AP Number: 386-133-15 A two-story house built on an L-plan with shiplap siding and multi-gable roof. What was originally a full-width porch has since been partially enclosed and altered in an incompatible manner. The original porch was defined by a roof overhang at the first story supported by slim wood posts. Since the 1982 survey, decorative elements have been added to the porches.

National Register of Historic Places Continuation Sheet

Section number _____7 Page _____295

Old Towne Orange Historic District, Orange, CA

1363.305 N. Pine
1922 Bungalow
Historical Name:
AP Number: 386-134-11
A single-story house with lap siding and multi-gable roof. Two small, frontfacing gables define the front facade. The main, side-facing gable roof
extends forward to form a large entry porch supported by tapered piers on
brick bases.

1364.318 N. Pine 1904 Victorian Cottage Historical Name: AP Number: 386-133-16 A single-story house with L-p

A single-story house with L-plan and combination steep-pitched, hip and gable roof. The original siding has been covered with asbestos shingles. Entry is at the apex of the ell with a separate porch overhang supported by ornamental trimmed posts. Porch posts and configurations suggest the Victorian Period, while the large picture window next to the main door in the roofline profile suggests the Classical/Revival, turn-of-the-century styles. Since the 1982 survey, this structure has been altered by removal of roof, being replaced with steep gable.

1365.323 N. Pine

c1920 Bungalow Historical Name: AP Number: 386-134-10 A single-story bungalow with wide single, front-facing gable roof. The original siding has been covered by asbestos shingles. Main entry is via a small corner, recessed porch supported by wood posts.

1366.325 N. Pine 1919 Bungalow Historical Name: AP Number: 386-134-09 A single-story bungalow with lap siding and gable roof. A centrally located, front-facing gable forms the entry porch overhang supported by pairs of wood posts.

1367.**328 N. Pine** 1966 Historical Name: AP Number: 386-133-17 Non-Contributor

National Register of Historic Places Continuation Sheet

Section number _____7 Page _____296

Old Towne Orange Historic District, Orange, CA

1368.**333 N. Pine** 1908 Hip Roof Cottage Historical Name: AP Number: 386-134-08 A single-story box plan house with clapboard siding and steep-pitched, hip roof A small hipped dormer is present on the front facade. Entry is via a corner recessed porch supported by clapboard posts. Wide eaves are embellished with ornamental brackets.

1369.334 N. Pine
1903 Hip Roof Cottage
Historical Name:
AP Number: 386-133-18
A single-story house with shiplap siding and combination steep-pitched, hip
and gable roof. Front-facing gable is embellished with ornamental shingles.
The house originally incorporated a L-plan with an entry and porch formed in
the apex of the ell. This has since been modified to have windows.

1370.340 N. Pine 1910 Board and Batten, Gable Roof Cottage Historical Name: AP Number: 386-133-19 This is a small cottage scale house which, very likely, was hand built without architect or contractor assistance. The house is a small, simple, box plan format with single-gable roof. A full-width porch is present with its own separate overhang and slim wood posts. The house is sided in board and batten, indicating hand construction.

1371.**341 N. Pine** 1922 Bungalow Historical Name: AP Number: 386-134-07 Non-Contributor

1372.349 N. Pine
1922 Bungalow
Historical Name:
AP Number: 386-134-07
A one-story L-plan bungalow with gable roof and wide lap siding. Entry is at
apex of ell. The house is simple and unadorned.

National Register of Historic Places Continuation Sheet

Section number _____7 Page _____297

Old Towne Orange Historic District, Orange, CA

1373.**350 N. Pine** 1955 Historical Name: AP Number: 386-133-20 Non-Contributor

1374.355 N. Pine 1914 Historical Name: AP Number: 386-134-05 Non-Contributor

1375.360 N. Pine 1957 Historical Name: AP Number: 386-133-21 Non-Contributor

1376.365 N. Pine 1904 Hip Roof Cottage Historical Name: AP Number: 386-134-04 A single-story box plan house with steep-pitched, hip roof. The original clapboard siding has since been covered with asbestos shingles. A small hipped dormer is on the front of the roof. Entry is via a corner recessed porch now supported by an ornamental iron pier, a replacement for the original.

1377.366 N. Pine 1917 Altered Bungalow Historical Name: AP Number: 386-133-22 A single-story clapboard bungalow with single, front-facing gable roof. No porch is present, though one may have been located on the front of the house originally but has since been enclosed. The house is simple and unembellished.

National Register of Historic Places Continuation Sheet

Section number 7 Page 298

Old Towne Orange Historic District, Orange, CA

1378.373 N. Pine 1909 Hip Roof Cottage Historical Name: AP Number: 386-134-03 A single-story house with combination steep-pitched, hip and gable roof. The house is built on a box plan. Original siding has since been covered with asbestos shingles. No porch is present, though what was once a porch may have since been enclosed.

1379.374 N. Pine c1920 Bungalow Historical Name: AP Number: 386-133-23 A single-story house built on a rectangular plan with clapboard siding and single, side-facing gable roof. Entry is beneath a small gabled portico. The presence of two doors indicate the house was built as a duplex.

1380.383 N. Pine 1922 Bungalow Historical Name: AP Number: 386-134-02 A single-story bungalow with lap siding and multi-gable roof. A large corner, wrap-around porch is located beneath the main roof supported by tapered piers on ornamental brick bases. A slatted balustrade connects the piers.

1381.384 N. Pine 1910 Historical Name: AP Number: 386-133-24 Non-Contributor

1382.**394 N. Pine** 1985 Historical Name: AP Number: 386-133-27 Non-Contributor

1383.508 N. Pine 1953 Historical Name: AP Number: 386-231-09 Non-Contributor

OMB Approval No. 1024-0018

United States Department of the Interior National Park Service

National Register of Historic Places Continuation Sheet

Section number 7 Page 299

Old Towne Orange Historic District, Orange, CA

1384.522 N. Pine 1926 Spanish Colonial Historical Name: AP Number: 386-231-08 A spanish colonial residence sith stucco and wood siding on a rectangular plan. Large arch-framed multi-paned wooden windows with lintel openings are present on front facade. An arched entry portal with classical door surround is present. The roof is red tiled with molded tile cornice and multi gables.

1385.523 N. Pine 1924 Modified Mediterranean Revival Historical Name: AP Number: 386-232-10 A stucco house built on an irregular rectangular plan. The roof consists of two gables, one facing side to side and the other front to back. The front to back gable meets the other at its center and is several feet higher. The street side of the side to side gable frames the shed roof of the entry portico. The entry portico and the side wall extending over the driveway have attached openings.

1386.525 N. Pine 1926 Mediterranean Revival Historical Name: AP Number: 386-231-08 A Mediterranean Revival home with multi-gabled red Spanish tile roof and plaster siding. Scroll like decorative treatment at gable end corners. Arched entry is covered with a tower like area with matching arched treatment near chimney. Large front window has mullions and two sidelights. Low stucco wall accents front rectangular plan.

1387.533 N. Pine 1925 Modified Mediterranean Revival Historical Name: AP Number: 386-232-07 A combination gabled and parapet roof, rectangular plan stucco house. A front facing gable extends to form an entry portico. The portico has 9 rectangular openings. A portion of the side to side gable forms the remaining front facade. The roof is covered with adobe tiles.

National Register of Historic Places Continuation Sheet

Section number _____7 Page _____300___

Old Towne Orange Historic District, Orange, CA

1388.**536 N. Pine** 1939 Mediterranean Revival Historical Name: AP Number: 386-231-07 An irregular L-plan house with stucco siding and multi-gabled roof. forward facing, wood siding, gables and a side facing gable built over

An irregular L-plan house with stucco siding and multi-gabled roof. Two forward facing, wood siding, gables and a side facing gable built over the driveway dominate the facade. The front mast portion of the house contains a mullioned window. A suspended shed roof overhang covers the entry which is set in the apex of the main house and its front most portion.

1389.**543 N. Pine** 1925 Provincial Revival Historical Name: AP Number: 386-232-08 A square plan stucco house. The parapet and portico roof are covered in adobe tiles. The portico has arched openings. The mullioned door is original and matches the mullioned picture window.

1390.**552 N. Pine** 1926 Modified Mediterranean Revival Historical Name: AP Number: 386-231-06 A rectangular plan house with stucco siding and parapet and gabled roof. The side facing and front facing gabled have adobe tiles. The entry is centered in the front facade. The front facing gable wall contains a metal roofed bay window.

1391.**553 N. Pine** 1925 Spanish Colonial Revival Historical Name: AP Number: 386-232-07 A rectangular plan stucco house with parapet roof. The front porch extends the full length of the facade and the wall extends on both sides to form side walls. The large porch has a tiled roof and is delineated from the house by a decorative parapet wall.

1392.132 S. Pine 1940 Historical Name: AP Number: 390-443-04 Non-Contributor

National Register of Historic Places Continuation Sheet

Section number 7 Page 301

Old Towne Orange Historic District, Orange, CA

1393.**137 S. Pine** c1905 Transitional Historical Name: AP Number: 390-444-12 A large, two-story house with clapboard siding and multi-gable roof.

A large, two-story house with clapboard siding and multi-gable roof. The most notable feature of the house is the complex roofline contrasted by the large, wrap-around porch supported by classical columns. The main portion of the roof is defined by a large, side-facing gable and a front-facing gable with a return at the eaves. French doors and a slatted balcony balustrade define the front portion of the house. The original door is still present and is flanked by side lites.

1394.142 S. Pine 1941 Historical Name: AP Number: 390-443-05 Non-Contributor

1395.147 S. Pine c1920 Mediterranean Revival Historical Name: AP Number: 390-444-12 This is the Emanuel Lutheran School and is comprised of a large, single-story structure with stucco siding and a flat roof of adobe tiles. The main entry is articulated by a large, arched recessed opening with ornamental parapet above.

1396.**152 S. Pine** c1905 Hip Roof Cottage Historical Name: AP Number: 390-443-06 A small, single-story clapboard house with pyramidal roof. A full-width porch is present on the front facade, defined by a separate roof extension supported by wood posts connected by a slatted balustrade.

1397.**162 S. Pine** 1977 Historical Name: AP Number: 390-443-07 Non-Contributor

National Register of Historic Places Continuation Sheet

Section number 7 Page 302

Old Towne Orange Historic District, Orange, CA

1398.172 S. Pine
1934 Bungalow
Historical Name:
AP Number: 390-443-08
A single-story bungalow with a single-gable roof staggered as three-frontfacing gables. The house has since had its original siding covered with
asbestos.

1399.176 S. Pine

1920 Bungalow Historical Name: AP Number: 390-443-09 A single-story house with single, shallow-pitched, front-facing roof. What was originally a recessed porch to the entry has since been enclosed.

1400.184 S. Pine 1925 Craftsman Bungalow Historical Name: AP Number: 390-443-10 A single-story bungalow with double, shallow-pitched, front-facing gable roof. Forwardmost gable forms the entry porch overhang supported by wide elephantine concrete piers.

1401.194 S. Pine 1996 Historical Name: AP Number: 390-443-11 Non-Contributor. New wood-sided and multi-gabled craftsman-style residence constructed on a formerly vacant lot.

1402.307 S. Pixley 1951 Historical Name: AP Number: 041-134-16 Non-Contributor

1403.315 S. Pixley 1950 Historical Name: AP Number: 041-134-18 Non-Contributor

National Register of Historic Places Continuation Sheet

Section number _____7 Page _____ 303___

Old Towne Orange Historic District, Orange, CA

1404.320 S. Pixley 1937 Historical Name: AP Number: 041-133-24 Non-Contributor

1405.**323 S. Pixley** 1936 Historical Name: AP Number: 041-134-19 Non-Contributor

1406.**331 S. Pixley** 1926 Provincial Revival Historical Name: AP Number: 041-134-03 A rectangular plan, stucco sided provincial revival residence with front facing chimney and roof gable. The facade contains several sets of vertical windows and front entry is enhanced with an arched opening, a large front door and 2 small accent windows.

1407.332 S. Pixley 1927 Provincial Revival Historical Name: AP Number: 041-133-23 A provincial revival residence with brick facade and 2 front facing deep gables, enhanced with small wood slatted openings. Front entry has low brick wall protecting front door with matching vertical side lights. large front arched window highlights the front facade.

1408.337 S. Pixley 1949 Historical Name: AP Number: 041-134-14 Non-Contributor

National Register of Historic Places Continuation Sheet

Section number 7 Page 304

Old Towne Orange Historic District, Orange, CA

1409.340 S. Pixley 1925 Mediterranean Revival Historical Name: AP Number: 041-133-22 Single-story, Mediterranean Revival bungalow with stucco facade and flat roof. Most notable are the angled facade extensions and the stepped parapet with tiled ridges. A separate tile hooded projection with large arched opening forms the entry porch.

1410.345 S. Pixley 1949 Historical Name: AP Number: 041-134-13 Non-Contributor

1411.348 S. Pixley 1926 Provincial Revival Historical Name: AP Number: 041-133-21 A wood sided rectangular plan provincial revival residnece with 2 frontfacing gables and matching set of windows. Entry is protected by low brick wall. Front door has matching side light doors.

1412.352 S. Pixley 1927 Spanish Colonial Revival Historical Name: AP Number: 041-133-20 Single-story, U-plan house combining Spanish Colonial Revival and Provincial influences. Roof is gabled with tile facing. Arched picture windows on front facade emphasize Spanish Colonial influence.

1413.353 S. Pixley 1928 Bungalow Historical Name: AP Number: 041-134-05 A small, rectangular plan bungalow with a single, front-facing gable roof. A smaller, central gable overhang in front forms the entry porch and is supported by a grouping of wood posts.

National Register of Historic Places Continuation Sheet

Section number _____7 Page _____ 305

Old Towne Orange Historic District, Orange, CA

1414.362 S. Pixley 1927 Spanial Colonial Revival Historical Name: AP Number: 041-133-19 Single-story bungalow-scale house built on an L-plan with front gable face incorporating a large arched, multi-paned window and ornamental tiles along he roof eave. Apex of ell has separate arcaded entry with two large, arched openings and a tile hooded roof.

1415.365 S. Pixley 1928 Bungalow Historical Name: AP Number: 041-134-06 Clapboard bungalow influenced house with single-gable roof and smaller, clipped front-facing gable.

1416.368 S. Pixley 1938 Historical Name: AP Number: 041-133-18 Non-Contributor

1417.**369 S. Pixley** 1925 Mediterranean Revival Historical Name: AP Number: 041-134-07 Non-Contributor. Since the 1982 survey, this structure has been severely altered by remodeling, including new roofline.

1418.**374 S. Pixley** 1937 Historical Name: AP Number: 041-133-17 Non-Contributor

1419.375 S. Pixley 1947 Historical Name: AP Number: 041-134-08 Non-Contributor

National Register of Historic Places Continuation Sheet

Section number _____7 Page _____306___

Old Towne Orange Historic District, Orange, CA

1420.404 S. Pixley 1925 Pueblo Historical Name: AP Number: 041-141-25 A pueblo styled residence with flat roof and tile accentuating the roof line. Front entry is covered with decorative wrought iron treatment and matching single windows.

1421.407 S. Pixley 1924 Historical Name: AP Number: 041-142-01 Non-Contributor

1422.411 S. Pixley 1924 Bungalow Historical Name: AP Number: 041-142-01 A small, clapboard box with single gable roof which extends forward to form a full-width porch. Entry is at center with a sash window on either side. Since the 1982 survey, this structure has been altered with inappropriate stucco siding.

1423.412 S. Pixley 1923 Historical Name: AP Number: 041-141-24 Non-Contributor

1424.416 S. Pixley 1928 Bungalow Historical Name: AP Number: 041-141-23 A very small bungalow cottage with double, front-facing gables. Original siding is covered with asbestos shingles. Forwardmost gable forms entry overhang and is supported by wood posts.

1425.418 S. Pixley 1946 Historical Name: AP Number: 041-141-22 Non-Contributor

National Register of Historic Places Continuation Sheet

Section number _____ 7 Page _____ 307___

Old Towne Orange Historic District, Orange, CA

1426.419 S. Pixley 1956 Historical Name: AP Number: 041-142-28 Non-Contributor

1427.427 S. Pixley 1924 Historical Name: AP Number: 041-142-32 Non-Contributor

1428.428 S. Pixley 1922 Bungalow Historical Name: AP Number: 041-141-21 A single-story multi-gabled Bungalow with side entry and 3-paneled window facing front. Front facade is enhanced with double panel windows.

1429.434 S. Pixley

1929 Bungalow Historical Name: AP Number: 041-141-20 A single-story, clapboard bungalow with unusual combination of double, frontfacing gables. Front facade is in an L-format, and entry is at apex of ell. Large picture window on frontmost gable face has multi-pane transom.

1430.435 S. Pixley

1924 Bungalow Historical Name: AP Number: 041-142-03 Single-story clapboard bungalow with double, front-facing gable. Forwardmost gable forms entry porch overhang and is supported by elephantine piers.

1431.443 S. Pixley 1984 Historical Name: AP Number: 041-142-04 Non-Contributor

National Register of Historic Places Continuation Sheet

Section number 7 Page 309

Old Towne Orange Historic District, Orange, CA

1437.467 S. Pixley 1924 Bungalow Historical Name: AP Number: 041-142-07 Single-story, clapboard bungalow with double, front-facing gables. Forwardmost gable forms entry porch overhang and is supported by tapered piers.

1438.475 S. Pixley 1936 Bungalow Historical Name: AP Number: 041-142-08 Non-Contributor. Single-story, box plan clapboard bungalow with single, front-facing gable roof. A smaller, gabled portico is located symmetrically in center of front facade and forms entry porch overhang. Since the 1982 survey, this structure has been severely altered by total remodeling to simulate Mediterranean look.

1439.483 S. Pixley 1924 Bungalow Historical Name: AP Number: 041-142-09 Single-story, rectangular plan bungalow with single, shallow-pitched, sidefacing gable roof. The contrasting front-facing gable projection forms entry porch overhang and is supported by wood posts. Since the 1982 survey, this structure has been altered by construction of a two-story attached garage and apartment unit.

1440.1 Plaza Square 1886 Plaza Park Historical Name: Plaza Square AP Number: 000-000-00 The Plaza Square consists of a circular park with a fountain dating from 1937 and several mature trees, shrubbery, and rose gardens. The park forms a rotary from which Chapman and Glassell streets radiate in four directions. The Plaza was added to the National Register of Historic Places in 1978. Also refer to National Register Plaza Historic District list.

1441.10 Plaza Square N/A Historical Name: AP Number: 390-381-20 Non-Contributor

National Register of Historic Places Continuation Sheet

Section number _____7 Page _____310___

Old Towne Orange Historic District, Orange, CA

1442.20 Plaza Square 1927 Brick Commercial Historical Name: Old Orange Building and Loan Bank AP Number: 390-381-19 See National Register Plaza Historic District list.

1443.26 Plaza Square 1902 Brick Commercial Historical Name: M.L. Willits Building AP Number: 390-381-01 See National Register Plaza Historic District list.

1444.**55 Plaza Square** 1912 Brick Commercial Historical Name: Jorn Building AP Number: 039-174-12 See National Register Plaza Historic District list.

1445.60 Plaza Square 1905 Brick Commercial Historical Name: Pixley Newspaper Office AP Number: 039-174-10 See National Register Plaza Historic District list.

1446.**77 Plaza Square** 1905 Brick Commercial Historical Name: AP Number: 039-251-31 See National Register Plaza Historic District list.

1447.119 E. River c1915 Bungalow Historical Name: AP Number: 390-101-05 A small, single-story clapboard bungalow with rectangular plan and single, front-facing gabled roof. The house is very simple and unadorned. Entrance is from the side beneath a small gabled portico.

National Register of Historic Places Continuation Sheet

Section number 7 Page 311

Old Towne Orange Historic District, Orange, CA

1448.127 E. River 1919 Craftsman Bungalow Historical Name: AP Number: 390-101-06 A small, single-story bungalow with a single, front-facing gabled roof. The original siding is still present on the forwardmost gable, but the remainder of the house has since been covered with asbestos shingles. A front-facing, projecting gable forms the entry porch overhang and is supported by piers with wide concrete bases and smaller wood posts on top. To either side of the main entry door is a pair of sash windows.

1449.**130 E. River** 1963 Historical Name: AP Number: 390-106-12 Non-Contributor

1450.**131 E. River** 1958 Historical Name: AP Number: 390-101-07 Non-Contributor

1451.137 E. River c1915 Craftsman Bungalow Historical Name: AP Number: 390-101-08 A single-story house with single, side-facing gabled roof. The original siding has since been covered with asbestos shingles. A wide shed dormer is present on the front portion of the roof. One-half of the front facade is devoted to a recessed porch supported by piers with brick bases.

1452.205 E. River 1946 Historical Name: AP Number: 390-102-06 Non-Contributor

National Register of Historic Places Continuation Sheet

Section number _____7 Page _____312___

Old Towne Orange Historic District, Orange, CA

1453.213 E. River 1921 Bungalow Historical Name: AP Number: 390-102-07 A small, single-story bungalow with wide lap siding and single, front-facing gabled roof. One-half of the front facade is devoted to a recessed porch supported by wood posts. The original door with mullioned-pane, plate glass windows is still present. An unusual sunray embellishment adorns the upper front gable face.

1454.225 E. River

1904 Vernacular Historical Name: AP Number: 390-102-08

The style of this house is very difficult to pinpoint, since it appears that the house has undergone modifications over the years, particularly in the period prior to 1925. The house is very large and is built on a box plan, which incorporates a steep-pitched, side-facing gabled roof with a full-width front porch typical of the Craftsman period. The roof slopes forward at an unusual angle and features two small shed dormers on the front portion. The most distinguishing aspect of this property is the large Sycamore tree in the front yard. This tree is estimated to be 350 to 500 years old. During World War II, the tree was studied by the National Geographic Society because of its age. It is one of forty trees protected and maintained by the City of Orange as a landmark tree.

1455.303 E. River 1946 Historical Name: AP Number: 390-103-23 Non-Contributor

1456.**315 E. River** 1939 Historical Name: AP Number: 390-103-22 Non-Contributor

1457.**323 E. River** 1939 Historical Name: AP Number: 390-103-20 Vacant Lot

National Register of Historic Places Continuation Sheet

Section number _____7 Page _____313__

Old Towne Orange Historic District, Orange, CA

1458.**327 E. River** 1919 Historical Name: AP Number: 390-103-19 Non-Contributor

1459.330 E. River c1920 Bungalow Historical Name: AP Number: 390-104-01 A single-story bungalow with shallow-pitched, multi-gabled roofline. The original siding on the facades has been covered with asbestos shingles. The front entry is characterized by a projecting gable supported by slender wood posts. The entry door, which is not original, is flanked on either side by picture windows with transoms. A pergola is located to the side of the porch entry.

1460.334 E. River 1924 Vernacular Historical Name: AP Number: 390-104-02 A small rectangular box pan with low-pitched gabled roof and exposed rafters. The small partial-width proh matches the front facade and foor gable. The entry door is flanked by single double-hung windows.

1461.337 E. River 1919 Historical Name: AP Number: 390-103-18 Non-Contributor

1462.338 E. River 1914 Historical Name: AP Number: 390-104-05 Non-Contributor

1463.**371 E. River** Historical Name: AP Number: 390-103-17 Non-Contributor

National Register of Historic Places Continuation Sheet

Section number _____7 Page _____314

Old Towne Orange Historic District, Orange, CA

1464.133 N. Shaffer

1913 Craftsman Historical Name: AP Number: 386-071-07 A one and one-half story rectangular plan house with lap siding and single, side-facing gable roof. A small, front-facing gabled dormer is also present in the front and features an ornamental transom. The main roof extends forward to form a full-width porch supported by piers with brick bases. Triangular bracket supports in exposed beams adorn the eaves around the house.

1465.143 N. Shaffer

1912 Bungalow Historical Name: AP Number: 386-071-06 A single-story house with wide lap siding and multi-gable roof. The front facade is comprised of a double, front-facing gable with a forward roofline, the forwardmost of which forms the entry porch overhang. This is supported by tapered piers.

1466.146 N. Shaffer

1903 Classic Box Historical Name: AP Number: 039-254-15 A high, two-story clapboard house with box plan and flattened, hip roof. A large, corner wrap-around porch on the first story is supported by ornamental, turned columns, harking back to the Victorian Period. Wide eaves are adorned with pairs of ornamental brackets. Since the 1982 survey, this structure has undergone restoration.

1467.151 N. Shaffer

1887 Vernacular Pioneer Historical Name: AP Number: 386-071-05 A single-story house with shiplap siding and single, front-facing gable roof. No porch is present, but the high, narrow windows' inner-framing define the house as being from the Victorian Period. Since the 1982 survey, this structure has been appropriately altered.

National Register of Historic Places Continuation Sheet

Section number _____7 Page _____315___

Old Towne Orange Historic District, Orange, CA

1468.**154 N. Shaffer** c1887 Gable Roof Cottage Historical Name: AP Number: 039-254-16 A small, single-story house with wide-lap siding and steep-pitched, multigable roof. Across the front facade is a full-width porch with its own separate roof overhang supported by wood posts. These posts are connected by a slatted balustrade. Entry is at center, flanked on either side by a pair of sash windows.

1469.**159 N. Shaffer** 1988 Historical Name: AP Number: 386-071-04 Non-Contributor

1470.164 N. Shaffer

1911 Craftsman Historical Name: AP Number: 039-254-17 A large, one and one-half story house with lap siding and single, side-facing gable roof. A large hipped dormer with a balcony and accompanying overhang are present on the front portion of the roof. The main roof extends forward to form a full-width porch supported by fluted piers. Entry is at center, flanked on either side by windows.

1471.169 N. Shaffer

1889 Spanish Italianate Victorian Historical Name: AP Number: 386-071-03

A large, two-story house with box plan, shiplap siding and flattened hip roof. The windows are ornamentally framed with jigsawn wood; the entry is at center on the first story. Originally a large, ornamental porch surrounded this entry but has since been removed. The house has an elaborate cornice defined by wide eaves and pairs of ornamental brackets. Since the 1982 survey, this structure has undergone partial restoration.

National Register of Historic Places Continuation Sheet

Section number _____7 Page _____316__

Old Towne Orange Historic District, Orange, CA

1472.**172 N. Shaffer** 1912 Bungalow Historical Name: AP Number: 039-254-18 A single-story bungalow with wide lap siding and double, front-facing gable roof. The forwardmost gable forms the entry porch overhang supported by tapered piers on arroyo stone bases. The exposed beams are fashioned as triangular bracket supports which add ornamentation to the eaves of the house. The main door is flanked by side lites. Windows on the front facade feature ornamentally mullioned, upper sashes.

1473.**177 N. Shaffer** 1949 Historical Name: AP Number: 386-071-02 Non-Contributor

1474.182 N. Shaffer 1913 Bungalow Historical Name: AP Number: 039-254-19 A single-story bungalow with double, front-facing gable roof. The original siding has been covered by asbestos shingles. The forwardmost gable forms the entry porch overhang supported by wood posts atop a low porch wall. Exposed beams, used both as triangular bracket supports and as ornamentation on the front facade, are on the upper gable faces.

1475.192 N. Shaffer

1905 Victorian Historical Name: AP Number: 039-254-20 This is a large, two-story house with clapboard siding and combination hip and gable roof. The house features a large, elaborate, corner wrap-around porch supported by classical columns. Pedimented gable with ornamental woodwork in the gable faces adorn each entry to the porch. Sizing and formatting of the windows and columns, the siding and roofline, all suggest the Classical Revival influences; the wrap-around porch and ornamentation in porch gables suggest Victorian influences.

National Register of Historic Places Continuation Sheet

Section number 7 Page 317

Old Towne Orange Historic District, Orange, CA

1476.**195 N. Shaffer** 1914 Craftsman Historical Name: AP Number: 386-071-01 A large, two-story Crafts

A large, two-story Craftsman house with clapboard siding and a single, sidefacing gable roof. A large, front-facing gabled dormer with balcony is on the front portion of the roof. The main roof extends forward on the front and sides to form a full-width front and wrap-around porch. The porch is supported by fluted, tapered piers. Main entry is at front center--a door with plate glass windows flanked by complementary side lites on either side. Also, to either side of the front door is a large, three-part picture window with mullioned transoms.

1477.222 N. Shaffer

1920 Bungalow Historical Name: AP Number: 039-244-15 A single-story clapboard bungalow with multi-gable roof. The house is built on a modified L-plan with the entry in the apex of the ell. The roof extends over the entry to form a large entry porch supported by piers with a connecting slatted balustrade.

1478.227 N. Shaffer

1914 Bungalow Historical Name: AP Number: 386-081-09 A single-story bungalow with wide-lap siding and double, front-facing gable roof. The main roof extends forward to form the entry porch overhang supported by tapered piers on top of brick bases. Ornamental purlins and lattice grace the upper gable faces.

1479.232 N. Shaffer

1920 Bungalow Historical Name: AP Number: 039-244-16 Non-Contributor. A single-story bungalow with double, front-facing gable roof. The forwardmost gable forms the entry porch overhang supported by piers with wood posts on top. The house has been considerably modified through the use of stucco siding on the facades and ornamental masonry on the frontmost gable and porch. The original door with plate glass panes is still present.

National Register of Historic Places Continuation Sheet

Section number 7 Page 318

Old Towne Orange Historic District, Orange, CA

1480.235 N. Shaffer

c1895 Gable Roof Cottage Historical Name: AP Number: 386-081-08 What was originally a Victorian frame house was substantially remodeled in 1909 to reflect the then popular bungalow style. Generally, the house has a bungalow appearance, but closer scrutiny reveals the original Victorian details. Shiplap siding and a multi-gable roof are present with a centrally located, front-facing gable forming the entry porch overhang supported by tapered piers. The door is clearly Victorian and is treated in the Victorian manner. To the side is a bay window of high, narrow windows characteristic of the Victorian styling.

1481.240 N. Shaffer

1905 Hip Roof Cottage Historical Name: AP Number: 039-244-17 A single-story clapboard house with combination hip and gable roof. The house is built on an L-plan, featuring a large corner, wrap-around porch supported by classical columns. Entry is beneath in the apex of the ell. The original door is still present.

1482.241 N. Shaffer

1929 Bungalow Historical Name: AP Number: 386-081-07 A single-story clapboard bungalow with single, front-facing gable roof. A one-half size corner porch is formed beneath the main portion of the house and is sheltered by a shed roof extension supported by wood posts. The original door with plate glass window is still present.

1483.248 N. Shaffer

1909 Bungalow Historical Name: AP Number: 039-244-18 A single-story house with wide lap siding and double, front-facing gable roof. The forwardmost gable forms the entry porch overhang supported by wood posts atop a low porch wall. Ornamental purlins and cross-ties embellish the upper gable faces. The main door is flanked on either side by a three-part window with multi-paned transom.

National Register of Historic Places Continuation Sheet

Section number 7 Page 319

Old Towne Orange Historic District, Orange, CA

1484.251 N. Shaffer 1914 Bungalow Historical Name: AP Number: 386-081-06 A single-story house with double, front-facing gable roof. The original siding has since been covered with asbestos shingles. The forwardmost gable forms the entry porch overhang supported by tapered piers atop masonry bases.

1485.256 N. Shaffer

1909 Bungalow Historical Name: AP Number: 039-244-19

A single-story clapboard bungalow with multi-gable roof. The house is built on a modified L-plan with the short leg of the ell extending forward to form an entry porch. The foundation is skirted in such a manner as to give the house a special flair. The porch is supported by a trio of wood posts atop a clapboard porch wall. Ornamental brackets and a bay window to the side of the porch further highlight the house.

1486.259 N. Shaffer

1915 Craftsman Historical Name: AP Number: 386-081-05

A two-story Craftsman house with ornamental lap siding on the facades and shallow-pitched, multi-gable roof. The house is distinguished by a second story portion, primarily over the rear half of the house, and a large corner, wrap-around porch supported by wood posts. Entry is beneath the porch roof at center, and the original wood door with plate glass windows is still present and is flanked on either side by large picture windows with mullioned transoms.

1487.264 N. Shaffer

c1915 Craftsman Historical Name: AP Number: 039-244-20 A one and one-half story house with single, side-facing gable roof and wide lap siding. A front facing, gabled dormer features a three-part transom window. Main roof extends forward to form a full-width porch which is supported by arroyo stone piers. Square bay windows on the sides of the house, which connote Craftsman homes, are present.

National Register of Historic Places Continuation Sheet

Section number _____7 Page _____320__

Old Towne Orange Historic District, Orange, CA

1488.265 N. Shaffer 1913 Bungalow Historical Name: AP Number: 386-081-04 A single-story bungalow with double, front-facing gable roof and combination clapboard and shingle siding. The forwardmost gable forms the entry porch overhang supported by tapered wood piers. Large transomed picture windows are featured on the front facade.

1489.272 N. Shaffer

c1915 Bungalow Historical Name: AP Number: 039-244-21 A single-story bungalow with wide lap siding and double, front-facing gable roof. The forwardmost gable forms the entry porch overhang supported by tapered wood piers. Upper gable faces are distinguished by cross-ties. Original door with plate glass windows is still present and flanked on either side with large, three-part picture windows.

1490.275 N. Shaffer

1913 Bungalow Historical Name: AP Number: 386-081-03 A single-story bungalow with wide lap siding and multi-gable roof fashioned in an L-plan. The front-facing gable forms the entry porch overhang supported by wide elephantine piers. A large picture window with mullioned transoms is present on the front facade.

1491.280 N. Shaffer

1910 Bungalow Historical Name: AP Number: 039-244-22

A single-story bungalow with single, front-facing gable roof. The original clapboard siding has since been covered with asbestos shingles. A full-width, recessed porch is supported by tapered piers. The original door with plate glass panes is still present. Ornamentally exposed beams adorn the lower portion of the upper gable face. Since the 1982 survey, this structure has been altered by a two story addition.

National Register of Historic Places Continuation Sheet

Section number 7 Page 321

Old Towne Orange Historic District, Orange, CA

1492.283 N. Shaffer

1914 Altered Bungalow Historical Name: AP Number: 386-081-02 A single-story bungalow with lap siding and double, front-facing gable roof. The forwardmost gable forms the entry porch overhang supported by slender wood posts. The low porch wall is faced with arroyo stone. Since the 1982 survey, this structure has been altered with inappropriate brick porch.

1493.288 N. Shaffer

1910 Craftsman Historical Name: AP Number: 039-244-23 A one and one-half story house with wide lap siding and single, side-facing gable roof. A shed dormer with casement windows is on the front of the roof. What was originally a full-width porch beneath the main roof extension has since been albeit in a compatible way. The front facade of the house now features almost solid, multi-paned windows.

1494.291 N. Shaffer

1916 Craftsman Bungalow Historical Name: AP Number: 386-081-01 A single-story craftsman bungalow with ornamental lap siding and multi-gable roof. Main portion of the house is covered by a single-gable roof with sidefacing gables. A centrally located front-facing gable forms an entry porch overhang. The overhang and pergolas to either side of it are supported by very wide, concrete columns. Entry is at center beneath the overhang.

1495.305 N. Shaffer 1976 Historical Name:

AP Number: 386-131-11 Non-Contributor

National Register of Historic Places Continuation Sheet

Section number _____7 Page _____322___

Old Towne Orange Historic District, Orange, CA

1496.306 N. Shaffer

1920 Bungalow Historical Name: AP Number: 039-232-13 A single-story bungalow with ornamental lap siding and shallow-pitched, multi-gable roof. The house is distinguished by a large, corner wrap-around porch beneath an extension of the main roof and supported by elephantine piers with concrete bases. Two smaller, front-facing gables with vertical slatting are attic dormers.

1497.314 N. Shaffer

1921 Bungalow Historical Name: AP Number: 039-232-14 A single-story bungalow with wide lap siding and clipped, tri-gable roof. Main portion of the house is covered by a single-gable roof. The central, front-facing gable forms the entry porch overhang supported by elephantine piers. Lattice work in the upper gable face distinguishes its facade. Since the 1982 survey, the lattice gable on this structure has been replaced by inappropriate plywood.

1498.317 N. Shaffer

1922 Bungalow Historical Name: AP Number: 386-131-10 A single-story bungalow with ornamental lap siding and shallow-pitched, multi-gable roof. The roof is fashioned in a semi-L-plan with the frontfacing gable forming the entry overhang supported by piers of ornamental brick bases with wood posts on top. The original door, featuring a single, plate glass window, is beneath its center entry.

1499.322 N. Shaffer

1907 Hip Roof Cottage Historical Name: AP Number: 039-232-15 A single-story house with modified L-plan and combination steep-pitched, hip and gable roof. Separate roof overhang defines porch located in the apex of the ell. A front-facing gable features a return at the eaves. Since the 1982 survey, this structure has been altered with appropriate siding restoration.

National Register of Historic Places Continuation Sheet

Section number _____7 Page _____323

Old Towne Orange Historic District, Orange, CA

1500.325 N. Shaffer 1914 Bungalow Historical Name: AP Number: 386-131-09 A single-story clapboard bungalow with single, front-facing gable roof. A full-width porch, supported by tapered, wide fluted piers on the exterior and slender tapered piers near the entry, is recessed beneath the main portion of the house.

1501.330 N. Shaffer 1917 Bungalow

Historical Name: AP Number: 039-232-16 A single-story clapboard bungalow with single, front-facing gable roof. Entry is via a corner recessed porch supported by slim wood posts.

1502.333 N. Shaffer

1904 Hip Roof Cottage Historical Name: AP Number: 386-131-08 A single-story clapboard house with combination steep-pitched, hip and gable roof. A full-width porch on the front facade is defined by a separate roof overhang supported by slender wood posts. Entry is beneath at center. The boxy, symmetrical quality of the house is typical of the Classical Revival homes of the period, although this house does not incorporate the reform embellishment.

1503.341 N. Shaffer 1936 Provincial Revival Historical Name: AP Number: 386-131-07 A single-story house with modified L plan, wide lap siding and steep-pitched, gable roof. Two front-facing gables articulate the front facade joined by a wide brick chimney. No porch is present. The house echoes the format and massing of the Provincial Revival houses, although it does not incorporate the embellishment typical of that style.

National Register of Historic Places Continuation Sheet

Section number _____7 Page _____324

Old Towne Orange Historic District, Orange, CA

1504.342 N. Shaffer c1920 Bungalow Historical Name: AP Number: 039-232-17 A single-story house with single, front-facing gable roof. The original siding has since been covered with asbestos shingles. Main entry is at center covered by a gabled portico with an inner arch. Large, double-hung windows are on either side of the entry.

1505.349 N. Shaffer

c1905 Bungalow Historical Name: AP Number: 386-131-06 A single-story bungalow with wide lap siding and single-front-facing gable roof. One-half of the front facade is defined by a recessed entry porch now supported by ornamental iron piers, a replacement of the original. Crossties and purlins ornament the upper gable face.

1506.**352 N. Shaffer** 1912 Historical Name: AP Number: 039-232-18 Non-Contributor

1507.**357 N. Shaffer** c1905 Gable Roof Cottage Historical Name: AP Number: 386-131-05

A single-story house built on an L-plan with steep-pitched, gable roof. Original siding has been covered with asbestos shingles. Entry is at the apex of the ell and has its own separate overhang supported by slender wood posts. Two high, ornamental brick chimneys are present and emanate from the central portion of the house.

1508.358 N. Shaffer

1910 Altered Bungalow Historical Name: AP Number: 039-232-19

/

A single-story clapboard bungalow with single, front-facing gable roof. A smaller, front-facing gable with a shallower pitch articulates a full-width entry porch overhang supported by concrete base piers with wood posts on top. Since the 1982 survey, this structure has been altered with inappropriate porch rail, posts and stickwork.

National Register of Historic Places Continuation Sheet

Section number _____7 Page _____ 325___

Old Towne Orange Historic District, Orange, CA

1509.360 N. Shaffer 1948 Historical Name: AP Number: 039-232-20 Non-Contributor

1510.**361 N. Shaffer** 1948 Historical Name: AP Number: 386-131-04 Non-Contributor

1511.**368 N. Shaffer** 1948 Historical Name: AP Number: 039-232-21 Non-Contributor

1512.**373 N. Shaffer** 1962 Historical Name: AP Number: 386-131-03 Non-Contributor

1513.**382 N. Shaffer** 1925 Historical Name: AP Number: 039-232-22 Non-Contributor

1514.383 N. Shaffer 1911 Vernacular Historical Name: AP Number: 386-131-02 A single-story box plan house with clapboard siding and steep-pitched, hip roof. Entry is via a recessed portico at the center. The house originally had a recessed corner porch but has since been enclosed and the original porch posts are still visible. Since the 1982 survey, this structure has been altered with inappropriate gable roof.

National Register of Historic Places Continuation Sheet

Section number 7 Page 326

Old Towne Orange Historic District, Orange, CA

1515.390 N. Shaffer

1910 Bungalow Historical Name: AP Number: 039-232-23 A one and one-half story house with combination clapboard and shingle siding. Clapboard is on the lower portion, while the upper gable face is adorned with ornamental shingles. The roof is comprised of a single, front-facing gable with a side-facing gabled dormer. Entry is via a recessed corner porch supported by a clapboard pier. Exposed beams are fashioned as triangular braces and further ornament the upper portions of the house.

1516.393 N. Shaffer

1906 Gable Roof Cottage Historical Name: AP Number: 386-131-01

A one and one-half story clapboard house with single, side-facing gable roof. The smaller, front-facing dormer is on the front portion of the roof. The main roof extends forward to form a full-width porch supported by round columns in the Classical fashion. Entry is beneath at center. The house incorporates an unusual combination of Classical Revival and Craftsman elements. Formatting is Craftsman while columns and windows are typical of the Classical period.

1517.406 N. Shaffer

1909 Craftsman Historical Name: AP Number: 039-223-16

A one and one-half story Craftsman house with wide lap siding and single, side-facing gable roof. Front-facing gabled dormer is also present. This dormer is ornamented with a little balcony balustrade, mullioned transom window, cross-ties and ornamental purlin. The main roof extends forward to form a full-width porch supported by piers with brick bases and wood posts on top. Entry is beneath at center and flanked on either side by a large picture window with mullioned transom.

National Register of Historic Places Continuation Sheet

Section number _____7 Page _____327__

Old Towne Orange Historic District, Orange, CA

1518.409 N. Shaffer 1909 Craftsman Historical Name: AP Number: 386-142-22 This is a two-story house built in the Craftsman style with added details which make the house unique. The house is built on a modified box-plan and includes a multi-gable roof. Siding is clapboard. A large, wrap-around porch is on both the street-facing sides. An attached roof provides the porch overhang supported by elephantine piers. An ornamental balustrade connects these piers. The main entry is on the corner of the house and includes an angled format for the door and flanking sidelights. The second story includes a sleeping porch with sloping roof, elephantine piers, an ornamental balustrade and curved latticework along the sides. Ornamentally carved rafter tails are beneath the eaves and the porch roof. The house is in excellent condition and in its original architectural state.

1519.**414 N. Shaffer** 1946 Historical Name: AP Number: 039-232-17 Non-Contributor

1520.422 N. Shaffer 1947 Historical Name: AP Number: 039-232-18 Non-Contributor

1521.430 N. Shaffer 1947 Historical Name: AP Number: 039-232-19 Non-Contributor

1522.440 N. Shaffer

1922 Bungalow Historical Name: AP Number: 039-223-20 A single-story clapboard bungalow with double, front-facing gable roof. Forwardmost gable forms the entry porch overhang supported by tapered piers of ornamental brick bases with wood posts on top. Large picture windows with mullioned transoms are on the front facade.

National Register of Historic Places Continuation Sheet

Section number 7 Page 328

Old Towne Orange Historic District, Orange, CA

1523.444 N. Shaffer 1921 Spanish Colonial Revival Historical Name: AP Number: 039-223-21 A single-story house built on an L-plan with stucco facades and adobe tiled, gable roof. Entry is at the apex of the ell where a recessed portico is formed with an ornamental arched opening. Combination arched and rectalinear windows are on the front facade.

1524.456 N. Shaffer

1922 Bungalow Historical Name: AP Number: 039-223-22 A single-story clapboard bungalow with double, front-facing gable roof. Forwardmost gable forms the entry porch overhang supported by classical round columns. Since the 1982 survey, this structure has undergone major restoration.

1525.461 N. Shaffer

1925 Provincial Revival Historical Name: AP Number: 386-141-25 A single-story house with wide lap siding and steep-pitched, gable roof. The house has Provincial Revival influences, althouth it does not incorporate the embellishment typical of that style. The house is built on a slight L plan with the entry in the apex of the ell. The front-facing gable has an extended slop to form the entry portico.

1526.464 N. Shaffer

1923 Bungalow Historical Name: AP Number: 039-223-23 A single-story clapboard house with shallow-pitched, multi-gable roof. The house is built on a modified L-plan with the front-facing gable extending forward to incorporate a recessed entry porch. This gable and adjacent pergola are supported by brick piers which may not be original.

1527.469 N. Shaffer 1933 Historical Name: AP Number: 386-141-24 Non-Contributor

National Register of Historic Places Continuation Sheet

Section number _____7 Page _____329___

Old Towne Orange Historic District, Orange, CA

1528.472 N. Shaffer

1925 Mediterranean Revival Historical Name: AP Number: 039-223-24 A single-story house with stucco facades and combination flat and gable roof. Entry is via a recessed portico with a large arched opening. The stepped parapet incorporates adobe tiled ridges which are complemented by the adobe tile window hood on the front facade.

1529.477 N. Shaffer

1922 Mediterranean Revival Historical Name: AP Number: 386-141-03 A single-story house with stucco facades and flat roof. The house is built on a slight L plan with the entry in the apex of the ell. A separate addition was included and forms a recessed portico with arched opening and adobe tiled hood. Roof ridges also are adorned with adobe tiles.

1530.480 N. Shaffer 1929 Historical Name: AP Number: 039-223-25 Non-Contributor

1531.482 N. Shaffer

1929 Modified Provincial Revival Historical Name: AP Number: 039-223-26

A single-story house with ornamental lap siding and steep-pitched, multigable roof. The house is clearly fashioned after the Provincial Revival style but does not incorporate the typical embellishment of that style. Entry is in the apex of the ell beneath an independent gable projection supported by a Classical column. The original door with plate glass window is still present, flanked on either side of the front facades by a pair of double-hung windows.

1532.485 N. Shaffer 1946 Historical Name: AP Number: 386-141-02 Non-Contributor

National Register of Historic Places Continuation Sheet

Section number _____7 Page _____330

Old Towne Orange Historic District, Orange, CA

1533.**491 N. Shaffer** 1947 Historical Name: AP Number: 386-141-01 Non-Contributor

1534.496 N. Shaffer

1924 Bungalow Historical Name: AP Number: 039-223-27 A single-story bungalow with wide lap siding and single, front-facing gable roof. Smaller, centrally located, projecting gable forms the entry porch overhang supported by wood posts.

1535.133 S. Shaffer

1920 Hip Roof Cottage Historical Name: AP Number: 390-441-03 A single-story clapboard house with combination hip and gable roof resulting in an L-plan. The short leg of the ell is the gable portion which is comprised of a front-facing gable with a return at the eaves. A small, ornamentally framed, louvered transom is visible. The entry porch is located in the apex of the ell. It has its own separate roof extension supported by ornamentally turned posts.

1536.**154 S. Shaffer** 1958 Historical Name: AP Number: 390-384-06 Non-Contributor

National Register of Historic Places Continuation Sheet

Section number 7 Page 331

Old Towne Orange Historic District, Orange, CA

1537.184 S. Shaffer

1927 Mediterranean Revival Historical Name: Walker Memorial AP Number: 390-384-06

This is the Walker Memorial which, along with the St. John's Lutheran Church, has been determined eligible for the National Register as part of the St. John's complex of buildings. Walker Memorial Hall is built in the then popular Mediterranean Revival style with strong Renaissance Revival influences. The building includes a 600-seat auditorium, kitchen, dining room, meeting room and lobby. The building is constructed in brown brick with a large, prominent entry defined by a rectilinear tower and adobe tiled roof. A canopy hangs above the entry which features a raised entrance with an ornamental iron balustrade. The south half of the front facade includes a stepped parapet; the north half features an arched parapet. Renaissance arches house the mullioned casement windows which occur in a regular pattern across the facade. The building is in excellent, well-maintained condition and exhibits its original architectural integrity.

1538.226 S. Shaffer

1902 Hip Roof Cottage Historical Name: AP Number: 390-394-07 A single-story house with lap siding and a steep-pitched hip roof. A small hip dormer is present on the front portion of the house. Entry is via a corner recessed porch which has since been enclosed but was originally supported by wood posts.

1539.227 S. Shaffer

1921 Craftsman Bungalow Historical Name: AP Number: 390-431-22 A single-story bungalow with double, front-facing, gable roof and facades which are now covered by stucco. The frontmost gable forms a full-width entry porch overhang supported by tapered piers with ornamental brick bases and wood posts on top.

1540.230 S. Shaffer 1965 Historical Name: AP Number: 390-394-06 Non-Contributor

National Register of Historic Places Continuation Sheet

Section number 7 Page 332

Old Towne Orange Historic District, Orange, CA

1541.236 S. Shaffer c1920 Bungalow Historical Name: AP Number: 390-394-05 This bungalow incorporates Period Revival influences, notably English or Provincial. The house is defined by a steep-pitched, multi-gable roof and stucco siding with shingles present in the upper gable faces. A front-facing gable defines the entry which is comprised of a multi-pane door inside a small, recessed entry portico. Ornamental purlins and a reversed spire on the gable peaks are notable embellishments. Since the 1982 survey, this structure has been altered with inappropriate window replacements.

1542.260 S. Shaffer

1920 Prairie Influence Historical Name: AP Number: 390-398-10 A single-story stucco house with flat roof and raised parapet and pilasters. Entry is via a porch projection with wide opening. Horizontal banding and the overall horizontal quality of the house are indicative of the Praire School Residential architecture established by Frank Lloyd Wright.

1543.**262 S. Shaffer** 1922 Craftsman Bungalow Historical Name: AP Number: 390-398-09 A single-story clapboard bungalow with double, front-facing gable roof. The forwardmost gable forms the entry porch overhang and is supported by tapered piers.

1544.**312 S. Shaffer** 1903 Bungalow Historical Name: AP Number: 390-404-21 Non-Contributor

National Register of Historic Places Continuation Sheet

Section number _____7 Page _____333___

Old Towne Orange Historic District, Orange, CA

1545.328 S. Shaffer

1907 Vernacular Historical Name: AP Number: 390-404-20 A small, single-story house with a single, side-facing gable roof with a sloping angle to the gable. A small shed dormer is present on the front. What was probably a full-width porch has since been enclosed. This house is simple and unembellished. Since the 1982 survey, this structure has been altered with appropriate reopening of the front porch.

1546.336 S. Shaffer

1917 Bungalow Historical Name: AP Number: 390-404-19 This is a single-story house with double, front-facing gable roof and ornamental lap siding. The forwardmost gable originally formed the entry porch overhang which has since been enclosed.

1547.344 S. Shaffer

1905 Hip Roof Cottage Historical Name: AP Number: 390-404-18 A single-story clapboard house with a steep-pitched hip roof and corner recessed entry porch. The porch has since been screened in but originally was supported by Classical columns. Since the 1982 survey, this structure has been altered with inappropriate siding and aluminum windows.

1548.**352 S. Shaffer** 1977 Historical Name: AP Number: 390-404-17 Non-Contributor

1549.362 S. Shaffer

1920 Bungalow Historical Name: AP Number: 390-404-16 A single-story bungalow once of clapboard, now covered by asbestos siding. A multi-gable roof with parallel, front-facing gables define the front portion of the house. The forwardmost gable forms the entry porch overhang and is supported by tapered piers.

National Register of Historic Places Continuation Sheet

Section number 7 Page 334

Old Towne Orange Historic District, Orange, CA

1550.368 S. Shaffer 1920 Craftsman Bungalow Historical Name: AP Number: 390-404-15 A single-story bungalow with wide lap siding and double, front-facing gable roof. The forwardmost gable forms the entry porch overhang and is supported by piers with wood posts on top. The upper gable faces are ornamented by widely spaced, exposed beams.

1551.373 S. Shaffer

c1920 Bungalow Historical Name: AP Number: 390-422-25 This is a simple, small clapboard bungalow with single, side-facing gable roof. No porch is present. Entry is directly from the front facade. Two, three-part windows are also present on the front facade.

1552.373 S. Shaffer

c1920 Bungalow Historical Name: AP Number: 390-422-25 This is a simple, small clapboard bungalow with single, side-facing gable roof. No porch is present. Entry is directly from the front facade. Two, three-part windows are also present on the front facade.

1553.374 S. Shaffer

1911 Craftsman Bungalow Historical Name: AP Number: 390-404-14 A single-story house with wide lap siding and double, front-facing gable roof. The forwardmost gable originally formed the entry porch overhang but has since been enclosed. The original slim, tapered piers are still visible. The eaves are embellished with triangular bracket supports; louvered attic transoms are present on both of the gable faces.

1554.375 S. Shaffer

1923 Bungalow Historical Name: AP Number: 390-422-25 A single-story simple clapboard bungalow with single, side facing gable roof. No porch is present. Entry is directly from the front facade. two, threepart windows are also present on the front facade.

National Register of Historic Places Continuation Sheet

Section number _____7 Page _____335__

Old Towne Orange Historic District, Orange, CA

1555.380 S. Shaffer

1910 Craftsman Bungalow Historical Name: AP Number: 390-404-13 A single-story clapboard bungalow with double, front-facing gable roof. The forwardmost gable forms the entry porch overhang and is supported by slim tapered piers. Triangular bracket supports grace the eaves; the upper gable faces are defined by louvered attic venting.

1556.387 S. Shaffer Historical Name:

AP Number: 390-422-24 Non-Contributor

1557.394 S. Shaffer

c1915 Craftsman Historical Name: AP Number: 390-404-12 A one and one-half story Craftsman house with combination board and batten and lap siding. The main roof is comprised of a single gable with sidefacing gables contrasted by a front-facing gable dormer. What was originally a full-width porch supported by arroyo stone piers has since been screened in. Ornamental purlins and louvered venting with diamond-pane transoms ornament the dormer gable. Also notable is the porte cochere which extends from the side of the house and has a gable overhang supported by arroyo stone piers.

1558.404 S. Shaffer 1954 Historical Name: AP Number: 390-414-26 Non-Contributor

1559.**412 S. Shaffer** 1954 Historical Name: AP Number: 390-414-25 Non-Contributor

National Register of Historic Places Continuation Sheet

Section number _____7_ Page _____336___

Old Towne Orange Historic District, Orange, CA

1560.418 S. Shaffer 1954 Historical Name: AP Number: 390-414-24 Non-Contributor

1561.425 S. Shaffer 1919 Vernacular Historical Name: AP Number: 390-131-74 This unusual, one-of-a-kind house is distinguished by steep-pitched, multigable roof and ship lap siding. The entry is via a porch formed by one of two parallel, front-facing gables; the porch overhang is supported by slim wood posts. The house shows signs of having been much modified over the years.

1562.**428 S. Shaffer** 1954 Historical Name: AP Number: 390-414-23 Non-Contributor

1563.438 S. Shaffer 1954 Historical Name: AP Number: 390-414-22 Non-Contributor

1564.442 S. Shaffer 1954 Historical Name: AP Number: 390-414-21 Non-Contributor

/

1565.445 S. Shaffer 1921 Bungalow Historical Name: AP Number: 390-131-73 A small, single-story clapboard bungalow with single, front-facing gable roof. What was probably a recessed corner porch has since been enclosed. The house is simple and unembellished.

National Register of Historic Places Continuation Sheet

Section number _____7 Page _____337___

Old Towne Orange Historic District, Orange, CA

1566.447 S. Shaffer 1923 Bungalow Historical Name: AP Number: 390-131-72 A single-story clapboard bungalow with double, front-facing gable roof. The smaller, forwardmost gable forms the entry porch overhang and is supported by thin posts.

1567.**454 S. Shaffer** 1954 Historical Name: AP Number: 390-414-20 Non-Contributor

1568.**462 S. Shaffer** 1920 Historical Name: AP Number: 390-414-19 Non-Contributor

1569.470 S. Shaffer
1925 Bungalow
Historical Name:
AP Number: 390-414-18
A small, single-story bungalow with tri-gable roof and siding now covered by
asbestos. Center frontmost portion of the house is comprised of a frontfacing gable which forms entry porch overhang supported by wood posts.

1570.478 S. Shaffer 1910 Transitional Historical Name: AP Number: 390-414-17 An unusual, two-story clapboard house with single, front-facing gable roof. A full-width porch is located beneath the second story and is supported by fluted tapered piers. The original hardwood door with oval pane is still present.

National Register of Historic Places Continuation Sheet

Section number 7 Page 338

Old Towne Orange Historic District, Orange, CA

1571.484 S. Shaffer

1923 Bungalow Historical Name: AP Number: 390-414-16 A small, single-story bungalow with clapboard siding and single, front-facing gable roof. A smaller, front-facing gable forms the entry portico and is supported by wood posts. Since the 1982 survey, this structure has been altered with inappropriate porch millwork.

1572.**522 S. Shaffer** 1961 Historical Name: AP Number: 390-103-29 Non-Contributor

1573.407 E. Sycamore 1910 Historical Name: AP Number: 039-223-13 A small boxed shape stucco sided home with recessed entry and small stucco overhangs over side windows. Windows and doors accented with ornamental wood mullions.

1574.419 E. Sycamore

1928 Bungalow Historical Name: AP Number: 039-223-14 A single-story bungalow with lap siding and single, front-facing gable roof. The second, front-facing gable, centrally located on the front facade, forms a slight entry porch overhang supported by wood posts. The original door with plate glass windows is still present.

1575.420 E. Sycamore c1920 Altered Bungalow

Historical Name: AP Number: 039-232-12 This is a typical City of Orange bungalow which originally had clapboard siding but has since been stuccoed over. This detracts from the original architectural integrity of the house. The house is built on a basic box plan with a single, front-facing gable roof. Entry is at the center of the front facade beneath the shed porch overhang supported by wood posts. A large, double-hung window flanks either side of the main entry.

National Register of Historic Places Continuation Sheet

Section number 7 Page 339

Old Towne Orange Historic District, Orange, CA

1576.425 E. Sycamore 1928 Bungalow Historical Name: AP Number: 039-223-15 A single-story house with lap siding and single-gable roof with side-facing gables. The front entry is at the center of the front facade beneath a large gabled portico with an inner arched opening. This portico is supported by wide piers.

1577.**522 E. Sycamore** 1947 Historical Name: AP Number: 386-131-23 Non-Contributor

1578.**530 E. Sycamore** 1946 Historical Name: AP Number: 386-131-22 Non-Contributor

1579.**540 E. Sycamore** 1946 Historical Name: AP Number: 386-131-21 Non-Contributor

1580.**602 E. Sycamore** 1956 Historical Name: AP Number: 386-132-01 Non-Contributor

1581.**610 E. Sycamore** 1956 Historical Name: AP Number: 386-132-25 Non-Contributor

National Register of Historic Places Continuation Sheet

Section number _____7 Page _____340__

Old Towne Orange Historic District, Orange, CA

1582.**615 E. Sycamore** 1956 Historical Name: AP Number: 386-141-16 Non-Contributor

1583.**620 E. Sycamore** 1956 Historical Name: AP Number: 386-132-24 Non-Contributor

1584.724 E. Sycamore 1919 Historical Name: AP Number: 386-133-26 Small box-shaped Bungalow with small covered porch entry and matching double hung front windows. Concrete walls front garden area.

1585.**730 E. Sycamore** 1987 Historical Name: AP Number: 386-133-28 Non-Contributor

1586.802 E. Sycamore 1922 Historical Name: AP Number: 386-134-01 Non-Contributor

1587.**135 W. Sycamore** Historical Name: AP Number: 039-144-12 Non-Contributor

National Register of Historic Places Continuation Sheet

Section number _____7 Page _____341__

Old Towne Orange Historic District, Orange, CA

1588.145 W. Sycamore c1923 Western Gothic Revival Historical Name: AP Number: 039-144-28 A two-story church building with a gable roof and clapboard siding. The entry is defined by a rectilinear tower with a small gable portico. The windows have a mullioned upper pane and transoms above. It is simple and unadorned.

1589.209 W. Sycamore 1923 Bungalow Historical Name: AP Number: 039-143-15 A single-story house with shallow-pitch, gable roof. A front-facing gable formes the entry porch overhang and is supported by wood posts. The original

clapboard siding has been covered with asbestos shingles.

1590.215 W. Sycamore

1923 Bungalow Historical Name: AP Number: 039-143-14 A single-story bungalow with wide lap siding and double front-facing gable roof. The forwardmost gable forms the entry porch overhang and is supported by wood posts.

1591.223 W. Sycamore 1914 Historical Name: AP Number: 039-143-13 Non-Contributor

1592.**314 W. Sycamore** 1954 Historical Name: AP Number: 039-151-25 Non-Contributor

National Register of Historic Places Continuation Sheet

Section number _____7 Page _____342__

Old Towne Orange Historic District, Orange, CA

1593.325 E. Toluca c1915 Craftsman Historical Name: AP Number: 390-103-26 This house incorporates both Craftsman and Colonial Revival bungalow features. The house is unusual for the way that it incorporates a full twostory with single, side-facing gabled roof. The main entry is articulated by a centrally located projecting gable which forms a small entry overhang. This is supported by Colonial columns. This entry porch is treated in the same manner as was done on the Colonial Revival bungalows.

1594.334 E. Toluca 1939 Historical Name: AP Number: 390-103-21 Non-Contributor

1595.**335 E. Toluca** 1963 Historical Name: AP Number: 390-103-27 Non-Contributor

1596.**340 E. Toluca** 1946 Historical Name: AP Number: 390-103-15 Non-Contributor

1597.405 E. Toluca 1935 Historical Name: AP Number: 390-103-13 Non-Contributor

1598.435 E. Toluca 1968 Historical Name: AP Number: 390-103-13 Non-Contributor

1

United States Department of the Interior National Park Service

National Register of Historic Places Continuation Sheet

Section number 7 Page 343

Old Towne Orange Historic District, Orange, CA

1599.504 E. Van Bibber

1919 Bungalow Historical Name: AP Number: 390-422-01 A single-story clapboard bungalow with multi-gable roof. Main portion of the house is covered by a single, side-facing gable roof. The center, frontmost portion of the house features a front-facing gable which extends downward to form the entry porch overhang supported by wood posts. Behind this porch is a smaller, front-facing gable which acts as the attic dormer.

1600.505 E. Van Bibber

1920 Bungalow Historical Name: AP Number: 390-421-23 A single-story bungalow with lap siding and multi-gable roof. The front facade is defined by a large, front-facing gable projection and includes a grouping of three pairs of multi-pane, casement windows.

1601.511 E. Van Bibber 1919 Bungalow Historical Name: AP Number: 390-421-22 A single-story bungalow with multi-gable roof and siding which is now covered with asbestos. The main portion of the house is covered by a single-gable roof with side-facing gables, but a third gable, which is front-facing, forms the entry porch overhang and is supported by wood posts. The upper porch gable face is adorned with slatting. The original front door with multi-pane windows is still present.

1602.512 E. Van Bibber
1927 Bungalow
Historical Name:
AP Number: 390-422-02
A single-story clapboard bungalow with multi-gable roof; each gable is
clipped. The front half of the house is comprised of a forward gable
extension which forms the entry porch overhang; this is supported by wide
piers with concrete bases and wood posts on top. Wide vertical slatting
adorns the upper gable.

National Register of Historic Places Continuation Sheet

Section number _____7 Page _____344___

Old Towne Orange Historic District, Orange, CA

1603.520 E. Van Bibber

1922 California Bungalow Historical Name: AP Number: 390-422-03 A single-story clapboard bungalow with single-gable roof with side-facing gables. A small, front-facing gable forms the entry portico and is supported by ornamental brackets. Front entry is at center, flanked on either side by a pair of double-hung windows.

1604.525 E. Van Bibber

1919 Bungalow Historical Name: AP Number: 390-421-20 A single-story bungalow with wide lap siding and single, front-facing gable roof. Entry is via a corner recessed porch which is supported by a wood post. An angled bay window in the front features a hood roof and window on each plane.

1605.528 E. Van Bibber

c1920 Craftsman Bungalow Historical Name: AP Number: 390-422-04 A single-story bungalow with wide lap siding and multi-gable roof. The front facade is comprised of three, front-facing gables. The center gable is located over the main portion of the house; on either side two smaller, front-facing gable extensions form porch overhangs which are supported by tapered wood piers. Beneath each porch gable is an entry, indicating duplex usage.

1606.**529 E. Van Bibber** 1919 Historical Name: AP Number: 390-421-21 Non-Contributor

1607.**536 E. Van Bibber** 1920 Craftsman Bungalow Historical Name: AP Number: 390-422-05

A single-story clapboard bungalow with shallow-pitched, multi-gable roof. The roof is arranged in an L-plan with the frontmost leg of the ell extending forward to form an entry porch overhang supported by wide piers with concrete bases and tapered wood posts on top.

National Register of Historic Places Continuation Sheet

Section number _____7 Page _____345___

Old Towne Orange Historic District, Orange, CA

1608.539 E. Van Bibber

1922 California Bungalow Historical Name: AP Number: 390-421-19 A single=story bungalow with tri-gable roof. The main portion of the house is covered by a single-gable roof with side-facing gables. A narrower, front-facing gable extension forms an entry portico. It is supported by Colonial columns. The main entry is at center, flanked on either side by side lites. To either side of the porch is a large, three-part window.

1609.545 E. Van Bibber

1921 Bungalow Historical Name: AP Number: 390-421-18 A single-story clapboard bungalow with multi-gable roof. One-half of the front facade is articulated by a front-facing gable extension which forms an entry porch overhang and is supported by wood posts. The main entry door is beneath, flanked by side lites.

1610.**546 E. Van Bibber** 1924 Provincial Revival Historical Name: AP Number: 390-422-06 A single-story house with stucco siding and multi-gable roof in the Provincial Revival tradition. The house is built on an L-plan and features many multi-pane windows. Rolled eaves distinguish the roofline.

1611.551 E. Van Bibber

1922 Bungalow Historical Name: AP Number: 390-421-17 A single-story clapboard bungalow with a shallow, front-facing gable roof. The main roof extends forward to form a full-width porch and is supported by wood posts atop a brick porch wall. Entry is at center and flanked on either side by a double-hung window.

National Register of Historic Places Continuation Sheet

Section number _____7 Page _____346

Old Towne Orange Historic District, Orange, CA

1612.552 E. Van Bibber

1915 Bungalow Historical Name: AP Number: 390-422-07 A single-story bungalow with ornamental lap siding and double, front-facing gable roof. The forwardmost gable originally formed an entry porch overhang but has since been enclosed. The original tapered wood piers are still in evidence. Since the 1982 survey, this structure has been altered with appropriate redesign of porch windows.

1613.559 E. Van Bibber

1922 Bungalow Historical Name: AP Number: 390-421-16 A single-story clapboard bungalow with double, front-facing gable roof. The forwardmost gable forms the entry porch overhang and is supported by tapered piers. A large picture window with multi-pane transom is present on either side of the main entry.

1614.560 E. Van Bibber

1910 Bungalow Historical Name: AP Number: 390-422-08 A single-story bungalow with lap siding and single, side-facing gable roof. No porch is present, but two small, front-facing gables adorn the roof with matching double-light small windows. The font door is flanked by dual double hung wood windows.

1615.567 E. Van Bibber

1921 Bungalow Historical Name: AP Number: 390-421-15 A single-story bungalow with lap siding and multi-gable roof. The main portion of the house is covered by a single-gable roof with side-facing gables. A smaller, front-facing gable projection forms the entry porch overhang in the front, now supported by wrought iron piers which are a replacement of the original.

National Register of Historic Places Continuation Sheet

Section number 7 Page 347

Old Towne Orange Historic District, Orange, CA

1616.568 E. Van Bibber

1923 Craftsman Bungalow Historical Name: AP Number: 390-422-09 A very small bungalow cottage with clapboard siding and double, front-facing gable roof. The smaller, forwardmost gable forms the entry porch overhang and is supported by round columns. A pergola is to the side. Both the front door and two windows on the front facade are mullioned.

1617.575 E. Van Bibber

1920 Craftsman Bungalow Historical Name: AP Number: 390-421-14 A single-story clapboard bungalow with shallow-pitched, multi-gable roof. The house is arranged on a modified L-plan with the entry at the apex of the ell. The roof extends forward at this point to form an entry porch overhang supported by tapered piers.

1618.576 E. Van Bibber

1908 Craftsman Bungalow Historical Name: AP Number: 390-422-10 A single-story bungalow with wide lap siding and single, front-facing gable roof. A full-width, recessed porch on the front facade is supported by wood piers with diagonal braces. Triangular bracket supports and an ornamental transom are featured on the front facade.

1619.584 E. Van Bibber

1921 Bungalow Historical Name: AP Number: 390-422-11 A single-story bungalow with wide lap siding and single-gable roof with sidefacing gables. A small entry portico is formed by a front-facing gable extension and is supported by wood piers. Since the 1982 survey, this structure has been altered with inappropriate second unit addition.

National Register of Historic Places Continuation Sheet

Section number _____ 7 Page _____ 348___

Old Towne Orange Historic District, Orange, CA

1620.590 E. Van Bibber

c1900 Victorian Historical Name: AP Number: 390-422-12 A two-story house with shiplap siding and multi-gable roof. The front facade is distinguished by a full-width porch with its own separate roof overhang which results in a small gable with inner arch at center front. Porch supports include ornamental wood posts connected by ballustrade with ornamental ballisters.

1621.637 E. Van Bibber

c.1917 Bungalow Historical Name: AP Number: 390-421-13 A bungalow with lap siding and gable roof with projecting beams and a brick end chimney. This was on the same property as 639 East Van Bibber but is now a separate lot.

1622.639 E. Van Bibber
1917 Bungalow
Historical Name:
AP Number: 390-421-12
A single-story bungalow with wide lap siding and single-gable roof with side
facing gables. No porch is present, but a small pergola-like structure at
the center front shelters the entry. To one side is a pair of multi-pane
casement windows; to the other side is an arrangement of six, small casement
windows, each with a multi-pane transom.

1623.420 E. Walnut 1921 Spanish Colonial Revival Historical Name: AP Number: 039-223-28 A single-story house with modified box plan, stucco facades and combination flat and gable roof. Entry is via an arcade which covers half of the front facade and features three large, arched openings. A tiled hood articulates this arcade. Both the roof ridges and front-facing gable are faced with adobe tiles.

Ϊ

National Register of Historic Places Continuation Sheet

Section number _____ 7 Page _____ 349___

Old Towne Orange Historic District, Orange, CA

1624.524 E. Walnut 1925 Bungalow Historical Name: AP Number: 386-141-04 A single-story, clapboard bungalow with single, side-facing gable roof. A smaller, front-facing gable forms the entry porch overhang supported by Colonial columns. A pergola on either side of this porch entry is also supported by Colonial columns.

1625.**528 E. Walnut** 1937 Historical Name: AP Number: 386-141-05 Non-Contributor

1626.**538 E. Walnut** 1939 Bungalow Historical Name: AP Number: 386-141-06 A single-story bungalow with wide lap siding and single, side-facing gable roof. A smaller, front-facing gable forms the entry porch overhang supported by piers.

1627.548 E. Walnut
1929 Bungalow
Historical Name:
AP Number: 386-141-07
A single-story, clapboard bungalow with single, front-facing gable roof. A
small, front-facing gabled portico, supported by wood posts, forms the entry
porch. The original door with plate glass window is still present.

1628.600 E. Walnut 1949 Historical Name: AP Number: 386-141-08 Non-Contributor

National Register of Historic Places Continuation Sheet

Section number _____7 Page _____350__

Old Towne Orange Historic District, Orange, CA

1629.604 E. Walnut

1927 Provincial Revival Historical Name: AP Number: 386-141-09 A single-story house with stucco facades and steep-pitched, multi-gable roof. Two front-facing gables articulate the front facade, the smaller of which forms an entry portico with large arched opening. A large, wide chimney is adjacent to the entry portico. On the upper gable is half-timbering.

1630.612 E. Walnut

1926 Mediterranean Revival Historical Name: AP Number: 386-141-10 A single-story, box plan house with stucco facades and stepped parapet. A rectilinear projection, on the center portion of the front facade with three large arched openings, forms the entry portico. Entry is beneath and flanked on either side by a three-part window with tile hood.

1631.620 E. Walnut
1926 Provincial Revival
Historical Name:
AP Number: 386-141-11
A single-story house with stucco facades and steep-pitched, multi-gable roof.
The house clearly tries to emulate the Provincial Revival style but does not
incorporate the typical detailing of the period. Rolled eaves, however, are
characteristic of the style.

1632.630 E. Walnut 1941 Historical Name: AP Number: 386-141-12 Non-Contributor

1633.638 E. Walnut 1930 Provincial Revival Historical Name: AP Number: 386-141-13 A single-story house built on a U-plan with stucco facades and steep-pitched, multi-gable roof. The two front-facing gables are on either leg of the U, the larger of which features a large picture window with ornamental brick molding. Entry is in the inner portion of the U, and an ornamental brick chimney is on the side of the house.

National Register of Historic Places Continuation Sheet

Section number 7 Page 351

Old Towne Orange Historic District, Orange, CA

1634.705 E. Walnut 1927 Historical Name: AP Number: 386-231-13 Non-Contributor

1635.715 E. Walnut 1924 Bungalow Historical Name: AP Number: 386-231-12 A single-story, clapboard bungalow with multi-gable roof featuring clipped gables. The main portion of the house is covered by a single-gable roof while a centrally located, front-facing gable forms an entry porch overhang. This is supported by piers with brick bases. A brick chimney is located to the side of the porch.

1636.**721 E. Walnut** 1946 Historical Name: AP Number: 386-231-11 Non-Contributor

1637.733 E. Walnut
1926 Mediterranean Revival
Historical Name:
AP Number: 386-231-10
A single-story, box plan house with stucco facades and flat roof. A recessed
entry with a large arched opening and tile hood articulates the front facade.
Brick on the lower foundation wall may not be original.

1638.803 E. Walnut
1924 Provincial Revival
Historical Name:
AP Number: 386-232-11
A single-story house with shiplap siding and steep-pitched, multi-gable roof.
A small, front-facing gable forms an entry portico supported by iron piers, a
replacement of the original. A wide stepped chimney is on the front facade.

National Register of Historic Places Continuation Sheet

Section number _____7 Page _____352

Old Towne Orange Historic District, Orange, CA

1639.815 E. Walnut
1924 Bungalow
Historical Name:
AP Number: 386-232-12
A single-story, clapboard bungalow with single-gable roof with side-facing
gables. A centrally located, front-facing gable forms the entry porch
overhang supported by piers with ornamental brick bases. All of the roof
gables are clipped.

1640.823 E. Walnut

1924 Bungalow Historical Name: AP Number: 386-232-13 A single-story, clapboard bungalow with tri-gable roof. The main portion of the house is covered by a single-gable roof with side-facing gables. A centrally located, front-facing gable forms the entry porch overhang supported by piers with ornamental brick bases and wood posts on top. The original door with three plate glass windows is still present.

1641.833 E. Walnut
1924 Bungalow
Historical Name:
AP Number: 386-232-14
A hip roof bungalow residential structure with front porch featuring
Romanesque porch columns and a hip roof porch overhang. Wood shiplap siding
and wood 6/1 and 4/1 windows are present.

1642.**132 W. Walnut** 1922 Bungalow Historical Name: AP Number: 039-144-27 A single-story bungalow with parallel front-facing gables. The forwardmost gable forms a full-width entry porch and is supported by wood posts.

1643.140 W. Walnut
1919 Bungalow
Historical Name:
AP Number: 039-144-26
A single-story bungalow with ornamental lap siding and shallow-pitch gable
roof. A centrally located, front facing gable forms the entry porch overhang
and is supported by wood piers on concrete bases.

National Register of Historic Places Continuation Sheet

Section number _____7 Page _____353__

Old Towne Orange Historic District, Orange, CA

1644.150 W. Walnut c1915 Bungalow Historical Name: AP Number: 039-144-01 A single-story clapboard bungalow with single side-facing gable roof with gables being clipped. The shed dormer is present on the front portion of the roof. The central portion of the front roof extends forward to shield a recessed entry. The main door features mullioned plate glass and is flanked on either side by 3-part transomed windows.

1645.224 W. Walnut

1905 Hip Roof Cottage Historical Name: AP Number: 039-143-01 A single-story house with clapboard siding and steep-pitch, hip and gable roof. The house is built on a modified L-plan with the apex of the ell being devoted to what was once probably a large wraparound porch but now only covers the front portion of the facade. The porch overhang is supported by Classical columns.

1646.311 W. Walnut

1923 Bungalow Historical Name: AP Number: 039-131-13 A single-story bungalow with single side-facing gable roof. The original siding has been covered with asbestos shingles. One-half of the front facade is devoted to a recessed entry porch which is supported by wood posts.

1647.118 E. Washington
c1920 Vernacular
Historical Name:
AP Number: 390-396-11
A small, single-story cottage with single-gable roof and siding now covered
with asbestos. The gable is elongated on one side while the entry is on the
side facade and has its own small, gable portico projection.

National Register of Historic Places Continuation Sheet

Section number _____7 Page _____354___

Old Towne Orange Historic District, Orange, CA

1648.205 E. Washington

c1920 Craftsman Bungalow Historical Name: AP Number: 390-392-05

A single-story bungalow with wide lap siding and multi-gable roof. The house is located on a corner lot and has a double entry, indicating duplex usage originally. The main front facade has a centrally located gable projection which forms the entry porch overhang supported by piers with wood posts and a connecting balustrade. Exposed beams in the gable face and slatted venting provide embellishment. An identical gable projection is located on the side of the house as well.

1649.214 E. Washington

c1915 Craftsman Bungalow Historical Name: AP Number: 390-396-01

A single-story, tri-gable bungalow with siding now covered by asbestos. The main portion of the house is covered by a single-gable roof with side-facing gables. A centrally located, front-facing gable on the front facade provides an entry porch. This is supported by tapered piers with a connecting, low porch wall. Two doors are located beneath the porch, indicating duplex usage. Original doors with window panes are still present.

1650.217 E. Washington

c1920 Bungalow Historical Name: AP Number: 390-392-06 A single-story house with wide lap siding and single, front-facing gable roof. The main entrance is via a corner recessed porch which is supported by a wood post and has a connecting slatted balustrade.

1651.226 E. Washington

1904 Hip Roof Cottage Historical Name: AP Number: 390-396-12 A single-story house with box plan, hip roof and siding now covered by asbestos. One-half of the front facade is defined by a corner recessed porch which is now supported by wrought iron piers, a replacement of the original. A small pedimented gable on the front portion of the roof features a louvered transom. The wide eaves of the main roof are adorned with ornamental brackets.

National Register of Historic Places Continuation Sheet

Section number 7 Page 355

Old Towne Orange Historic District, Orange, CA

1652.230 E. Washington 1915 Bungalow

Historical Name: AP Number: 390-396-11 A single-story bungalow with wide lap siding and single, front-facing gable roof. What was originally a recessed corner porch has since been enclosed, but the original wood piers and slatted balustrade are still present. Since 1982 survey, this structure has been altered with inappropriate vent covering.

1653.236 E. Washington

1907 Hip Roof Cottage Historical Name: AP Number: 390-396-10 A single-story clapboard house with modified L-plan and combination gable roof. The entry is via a corner porch formed by an extension of the main hip roof and is supported by Classical columns with Corinthian capitals. The remaining half of the front facade is articulated by a front-facing, pedimented gable. Wide eaves throughout are ornamented with brackets. The original front door and accompanying screen door are still present.

1654.306 E. Washington

1904 Transitional Historical Name: AP Number: 390-397-01 A two-story house with a single, front-facing gable roof and siding now covered by asbestos. A full-width front porch is present on the first story. This has its own separate roof overhang supported by Classical columns. Entry is at center. The original front door is still present.

1655.**315 E. Washington** 1955 Historical Name: AP Number: 390-393-04 Non-Contributor

1656.**318 E. Washington** 1952 Historical Name: AP Number: 390-397-12 Non-Contributor

/

National Register of Historic Places Continuation Sheet

Section number _____7 Page _____356

Old Towne Orange Historic District, Orange, CA

1657.323 E. Washington

1916 Bungalow Historical Name:

AP Number: 390-393-05

A single-story bungalow with lap siding and double, front-facing gable roof. The forwardmost gable forms the entry porch overhang and is supported by ornamental columns. Cross-ties and triangular bracket supports adorn both front gable faces. Since the 1982 survey, this structure has been altered with inappropriate porch posts, stick work and front door.

1658.326 E. Washington

c1920 California Bungalow Historical Name: AP Number: 390-397-11 A single-story clapboard house with single-gable roof with side-facing gables. Either side of the front facade is defined by a small gabled entry portico with diagonal brace supports. Double entry indicates duplex usage.

1659.426 E. Washington

1922 California Bungalow Historical Name: AP Number: 390-398-11 A single-story clapboard bungalow with multi-gable roof. Main portion of the house is covered by a single-gable roof with side-facing, clipped gables. The front-facing gable in the center portion of the front facade forms the entry porch overhang and is supported by round columns. A pergola is located on either side and is also supported by wide, round columns. The main entry is at center, flanked on either side by side vents.

1660.504 E. Washington

1908 Hip Roof Cottage Historical Name: AP Number: 390-433-01 A single-story clapboard house with hip roof and corner recessed porch. The porch is supported by a singular column. The front portion of the roof also features a small gable projection which is embellished with ornamental shingles and jigsawn work.

National Register of Historic Places Continuation Sheet

Section number _____7 Page _____357__

Old Towne Orange Historic District, Orange, CA

1661.505 E. Washington

1904 Hip Roof Cottage Historical Name:

AP Number: 390-431-23

This single-story cottage-scale house embodies both Victorian and turn-ofthe-century features. The box plan and pyramidal roof are clearly turn-ofthe-century, while the porch posts and front pedimented gable ornamentation are Victorian. The house incorporates a full-width porch across the front facade which is supported by ornamental turned posts. A small pedimented gable on the front of the roof features ornamental shingles and an ornamentally framed transom. It should be noted that the wood shake shingles are not original and are a later addition.

1662.513 E. Washington

1914 Craftsman Bungalow Historical Name:

AP Number: 390-431-21

A single-story clapboard bungalow with double, front-facing gables. The forwardmost gable forms the entry porch overhang and is supported by wide piers. The house has been modified in more recent years to include stucco siding and a brick veneer at the foundation wall. Neither is original.

1663.514 E. Washington

1920 California Bungalow Historical Name: AP Number: 390-433-02 A single-story clapboard bungalow with single, shallow-pitched gable roof with side-facing gables. An additional front-facing gable is located on the center portion of the front facade and forms the entry portico.

1664.521 E. Washington
1909 Hip Roof Cottage
Historical Name:
AP Number: 390-431-20
A single-story box plan house with clapboard siding and hip roof. Entry is
via a corner recessed porch which has been modified to include wrought iron
posts. Front-facing, pedimented gable is located on the front portion of the
roof and features ornamental shingles and an ornamentally framed attic vent.

National Register of Historic Places Continuation Sheet

Section number _____7 Page _____358

Old Towne Orange Historic District, Orange, CA

1665.524 E. Washington

1909 Hip Roof Cottage Historical Name: AP Number: 390-433-03 A single-story, box plan house with clapboard siding and hip roof. Entry is via a corner recessed porch supported by a single, Classical column. A small, pedimented gable is present on the front portion of the roof. Also notable is the double entry with original screen doors.

1666.532 E. Washington
1909 Bungalow
Historical Name:
AP Number: 390-433-04
A single-story clapboard bungalow with single, shallow-pitched, front-facing
gable roof. What was once a corner recessed porch has since been enclosed.
The house is simple and unembellished. Since the 1982 survey, this structure
has been altered with inappropriate remodeling and removal of chimney.

1667.**535 E. Washington** 1909 Bungalow Historical Name: AP Number: 390-431-19 A single-story house with wide lap siding and hip roof. Present on the front facade are two, front-facing gable faces, the smaller of which forms an angled bay window, and the larger of which supports a second, smaller gable which forms an entry portico. These gables give the house an unusual distinction.

1668.**539 E. Washington** c1915 Hip Roof Cottage Historical Name: AP Number: 390-431-18 A single-story, box plan clapboard house with hip roof. Front facade is articulated with a small entry porch overhang.

1669.540 E. Washington
1911 Hip Roof Cottage
Historical Name:
AP Number: 390-433-05
A single-story, box plan house with clapboard siding and hip roof. A frontfacing, gable dormer is present on the front of the roof. The house features
wide eaves but no porch is present.

National Register of Historic Places Continuation Sheet

Section number 7 Page 359

Old Towne Orange Historic District, Orange, CA

1670.**547 E. Washington** 1971 Historical Name: AP Number: 390-431-17 Non-Contributor

1671.548 E. Washington 1909 Hip Roof Cottage Historical Name: AP Number: 390-433-06 A single-story, box plan house with clapboard siding and hip roof. Entry is via a corner recessed porch, though no porch support is present. A small, pedimented gable is present on the front portion of the roof and is embellished with an ornamentally framed attic vent.

1672.604 E. Washington

1919 Craftsman Bungalow Historical Name: AP Number: 390-433-07 A single-story bungalow with wide lap siding and double, front-facing gable roof. The forwardmost gable forms the entry porch overhang and is supported by tapered piers. Ornamental purlins grace the eaves.

1673.605 E. Washington

c1905 Hip Roof Cottage Historical Name: AP Number: 390-431-16 A single-story, box plan house with clapboard siding and hip roof. One-half of the front facade is articulated by a corner recessed porch and is supported by a Classical column with Corinthian capital. A small, pedimented gable, attic dormer is present on the front portion of the roof and has an ornamentally framed, transom vent.

1674.610 E. Washington

1910 Hip Roof Cottage Historical Name: AP Number: 390-433-08

A single-story house with modified box plan, clapboard siding and multi-hip roof. The house features a staggered front facade with the frontmost portion extending into a full-width porch supported by four Classical columns. A dormer gable is present just above the porch overhang. The original door and screen door are still present on the house.

National Register of Historic Places Continuation Sheet

Section number _____7 Page _____360

Old Towne Orange Historic District, Orange, CA

1675.**615 E. Washington** 1973 Historical Name: AP Number: 390-431-15 Non-Contributor

1676.**622 E. Washington** 1907 Historical Name: AP Number: 390-433-09 A rectangular plan single

A rectangular plan single stoy residence with hipped roof and a small front facing gable which is ornamented by vertical wooden slats. The entry is beneatha a corner of the hipped roof. A clasical column and small window are present at the porch.

1677.623 E. Washington

1915 Craftsman Historical Name: AP Number: 390-431-14 A one and one-half story house with clapboard siding and single-gable roof with side-facing gables. A smaller, front-facing dormer gable is also present. It is ornamented with jigsawn brackets and an ornamentally framed vent. The main roof extends forward to form the full-width porch overhang and is supported by piers with concrete bases and wood posts on top. Entry is just off center and is flanked on either side by a large, fixed-pane picture window with transom.

1678.629 E. Washington

1914 Bungalow Historical Name: AP Number: 390-431-13 A single-story clapboard bungalow with a multi-gable roof fashioned in an Lplan. The short leg of the ell results in a front-facing gable porch overhang and is supported by wood posts.

National Register of Historic Places Continuation Sheet

Section number 7 Page 361

Old Towne Orange Historic District, Orange, CA

1679.630 E. Washington

1913 Craftsman Historical Name: AP Number: 390-433-10 A one and one-half story clapboard house with single, side-facing gable roof and small, front-facing gable dormer. The dormer is embellished with ornamental bracket supports and a beveled glass transom. One-half of the front facade is occupied by a recessed porch supported by a tapered pier atop a low porch wall.

1680.637 E. Washington

1935 Mediterranean Revival Historical Name: AP Number: 390-431-12 A low-to-the-ground, single story, stucco bungalow with box plan and flat roof. The house is otherwise simple and unembellished except for the gabled entry portico, large arched opening and tile hood.

1681.**711 E. Washington** 1946 Historical Name: AP Number: 390-432-20 Non-Contributor

1682.712 E. Washington
1919 Craftsman Bungalow
Historical Name:
AP Number: 390-434-02
A single-story bungalow with wide lap siding and double, front-facing gable
roof. The forwardmost gable forms the entry porch overhang and is supported
by wood posts. Exposed beams adorn the upper gable faces.

1683.720 E. Washington 1921 Bungalow Historical Name: AP Number: 390-434-03 A small, single-story clapboard bungalow with single, front-facing gable roof. A smaller, gable projection on the center front facade forms an entry porch overhang supported by wood posts.

National Register of Historic Places Continuation Sheet

Section number 7 Page 362

Old Towne Orange Historic District, Orange, CA

1684.**721 E. Washington** 1951 Historical Name: AP Number: 390-432-19 Non-Contributor

1685.**727 E. Washington** 1945 Historical Name: AP Number: 390-432-18 Non-Contributor

1686.728 E. Washington

1921 California Bbungalow Historical Name: AP Number: 390-434-04 A single-story, clapboard bungalow with tri-gable roofline, each gable being clipped. The main portion of the house is covered by a side-facing gable roof; a centrally located, front-facing gable projection forms the entry porch overhang supported by thin wood posts. Entry is at center, flanked by side lites. To either side of the porch is a grouping of three windows with transoms.

1687.736 E. Washington

1917 Craftsman Bungalow Historical Name: AP Number: 390-434-05 A single-story, clapboard bungalow with a single, front-facing gable roof. A smaller, front-facing gable is located at the center front facade and forms the entry porch overhang supported by thin wood posts. Since the 1982 survey, this structure has been altered with inappropriate false rock veneer on piers and door frame.

1688.737 E. Washington

1978 Historical Name: AP Number: 390-432-17 Non-Contributor

National Register of Historic Places Continuation Sheet

Section number _____7 Page _____363

Old Towne Orange Historic District, Orange, CA

1689.742 E. Washington

1919 Craftsman Bungalow Historical Name:

AP Number: 390-434-06

A single-story bungalow with wide lap siding and multi-gable roof. The front facade is articulated by a smaller, front-facing gable running parallel to the main gable and forming the entry porch overhang. This is supported by piers with brick bases and wood posts on top and features slatting and beams arranged in an ornamental fashion.

1690.**743 E. Washington** Historical Name: AP Number: 390-432-16 Non-Contributor

1691.801 E. Washington 1938 Historical Name: AP Number: 390-432-15 Non-Contributor

1692.804 E. Washington

1917 Gable Roof Cottage Historical Name: AP Number: 390-434-07 A single-story house with single, front-facing gable roof with a side extension. Siding is asbestos. A smaller, front-facing gable porch overhang is present on the front facade supported by wood posts. Entry is beneath at center and flanked on either side by multi-pane casement windows.

1693.811 E. Washington 1962 Historical Name: AP Number: 390-432-14 Non-Contributor

National Register of Historic Places Continuation Sheet

Section number _____7 Page _____364__

Old Towne Orange Historic District, Orange, CA

1694.812 E. Washington

1921 Worker Housing Historical Name: AP Number: 390-434-08 An irregular plan modest worker house with multi-gables, wide shiplap siding, and double hung windows. The strucutre sits in rear of lot with the main portion of the house fromed by a side facing gable. The garage is attached to the home by a shed roof.

1695.**818 E. Washington** 1928 Provincial Revival

Historical Name: AP Number: 390-434-09 A single-story stucco house with steep-pitched, multi-gable roof fashioned in the Provincial Revival manner. Popular at this time were Provincial influences on the housing stock, and this house incorporates the typically used rolled eaves and large arched windows and arched openings.

1696.**819 E. Washington** 1946 Historical Name: AP Number: 390-432-13 Non-Contributor

1697.828 E. Washington

1919 Craftsman Bungalow Historical Name: AP Number: 390-434-10 A single-story bungalow with wide lap siding and front-facing gable roof. The main roof extends forward to form a full-width porch and is supported by tapered piers. The upper gable face is ornamented with vertical slatting and exposed beams arranged in an ornamental fashion.

1698.838 E. Washington 1922 Bungalow

Historical Name: AP Number: 390-434-11 A single-story clapboard bungalow with single, front-facing gable roof. What was originally a full-width porch has since been enclosed, but the original porch piers are still present.

National Register of Historic Places **Continuation** Sheet

Section number <u>7</u> Page <u>365</u>

Old Towne Orange Historic District, Orange, CA

1699.121 N. Waverly 1935 Mediterranean Revival Historical Name: AP Number: 386-062-09 A single-story Mediterranean Revival residence with stucco siding and front facing gable which forms the entry portico and is accessed by an arched opening. Roof is adobe tile. A large picture window flanks the front entrance.

1700.131 N. Waverly 1923 Dutch Colonial Revival Historical Name: AP Number: 386-062-08 A single-story Dutch Colonial Revival with wood lap siding and multi-gabled

clipped roof. The main portion of the home is covered by a single-gabled roof with side facing gables. The centrally located front facing gable forms an entry porch overhang with pergolas to the entry porch and the end of the pergolas. Matching mullion windows are present on the front door with side lights and two pairs of windows on either side of the front facade

1701.139 N. Waverly 1923 Mediterranean Revival Historical Name: AP Number: 386-062-07 single-story Mediterranean Revival stucco residence, originally with Α rectangular floor plan. The front facade is articulated by a hip roof and also a flat parapet roof. The entry portico is formed by a shed roof extension from the wall. This portico is enhanced by three arched openings on the side and a large arch opening as the entry. An elaborate picture window is present.

1702.140 N. Waverly 1926 Provincial Revival Historical Name: AP Number: 386-061-11 A single story clapboard house with steep pitched multi-gable roof. Entry is recessed between gables with covered porch. Front facing picture window flanked by two mullioned smaller windows. The other gabled extension has same smaller mullioned windows. An extension of front gable forms a wing wall.

National Register of Historic Places Continuation Sheet

Section number 7 Page 366

Old Towne Orange Historic District, Orange, CA

1703.147 N. Waverly 1937 Provincial Revival Historical Name: AP Number: 386-062-06 A single story, stucco sided Provincial Revival residence with L-Plan. A steep pitched front facing gable covered with wide wood lapped siding forms the entry. No porch is present. A mullioned window with thirty lights enhances the forward facing facade.

1704.148 N. Waverly

1923 Gable Roof Cottage Historical Name: AP Number: 386-061-12 A single story Cottage with wood lap siding and multi-gabled roof. Main portion of the home is covered by a single gable roof with side facing gables. The centrally located front facing gable forms an entry porch overhang with pergolas to either side, supported by wooden columns. Two pairs of vertical mullioned windows flank the entry.

1705.155 N. Waverly

1924 Craftsman Bungalow Historical Name: AP Number: 386-062-05 A single story Bungalow with multi-gabled roof and wood lap siding. The forward mist gable is an extension of the home. A low shed roof forms the entry porch. The front door is accented by side lights.

1706.156 N. Waverly

1936 Provincial Revival Historical Name: AP Number: 386-061-13 A one-story stucco residence with two front facing gables trimmed with wide wood lap siding at the peaks which is carried forward to the garage. A covered entry and small side entrance enhances the home. A mullioned picture window with twenty lights enhances the front facade. The smaller mullioned windows are near the entry.

National Register of Historic Places Continuation Sheet

Section number _____7 Page _____367___

Old Towne Orange Historic District, Orange, CA

1707.163 N. Waverly 1924 Mediterranean Revival Historical Name: AP Number: 386-062-04 A single story box plan Mediterranean Revival residence with stucco facade and flat roof. Raised parapets are on both the main home entrance and side entrance, and the garage entry portico.

1708.166 N. Waverly 1933 Spanish Colonial Revival Historical Name: AP Number: 386-061-14 A single-story Spanish Colonial Revival with stucco siding and multi-gabled roof line home built on a modified L-Plan with front facing gables which form an entry portico which is accessed by an arched opening. Roof is sided in adobe tiles. Large rounded windows enhances the front facade. Rear garage emulates rounded arch styles with door openings.

1709.**173 N. Waverly** 1924 California Bungalow Historical Name: AP Number: 386-062-03 A Bungalow style residence of irregular floor plan, stucco sided single story structure. Combination of gabled and shed roofs. The home is set back on lot with a brick garage in front.

1710.**174 N. Waverly** 1923 transitional Prairie Historical Name: AP Number: 386-061-15 A Prairie style single story residence with stucco siding and flat roof. Entry is via porch which projects forward the full length of the front facade. A pair of picture windows flanked by two double hung windows is visible on the front facade. Top of parapet trimmed in wood with rounded vent openings. The side entrance is recessed.

National Register of Historic Places Continuation Sheet

Section number _____7 Page _____368___

Old Towne Orange Historic District, Orange, CA

1711.182 N. Waverly

1930 Craftsman Bungalow Historical Name: AP Number: 386-061-16 A single story Craftsman Bungalow with wood lap siding and a tri gable roof. The house features two entries, indicating the intention for original duplex use. Each entry is articulated by a shallow to medium pictured gable portico supported by piers with wood posts. The front has two symmetrical sets of windows.

1712.183 N. Waverly 1924 Craftsman Bungalow Historical Name: AP Number: 386-062-02 A large two story Craftsman with multigabled roof and wood lap siding. A front facing gable forms the entry porch. This gable is supported by piers with concrete bases. Angled brackets and exposed rafter tails are visible.

1713.**191 N. Waverly** 1951 Historical Name: AP Number: 386-062-01 Non-Contributor

1714.**192 N. Waverly** 1946 Historical Name: AP Number: 386-061-17 Non-Contributor

1715.204 N. Waverly 1950 Historical Name: AP Number: 386-091-12 Non-Contributor

1716.212 N. Waverly 1944 Historical Name: AP Number: 386-091-13 Non-Contributor

National Register of Historic Places Continuation Sheet

Section number 7 Page 369

Old Towne Orange Historic District, Orange, CA

1717.216 N. Waverly

1948 Craftsman Bungalow Historical Name: AP Number: 386-091-14 A multi-gabled Bungalow residence with wide wood lapped siding, in a box plan. One of the front facing gables forms the entry. Classical columns on ornamental, placed on brick, piers surround the entry porch. The gables are enhanced by short returns at eaves. A small side entry porch forms an extension of the roof. A pair of picture windows flanked by small double hung windows are present on the front facade.

1718.228 N. Waverly 1924 Historical Name: AP Number: 386-091-15 Non-Contributor

1719.232 N. Waverly 1924 California Bungalow Historical Name: AP Number: 386-091-16 A small multi-gabled Bungalow with wood lapped siding. The plan is rectangular with two large picture windows on the front facade. A small front entry is covered with another gable, showing four gables on front facade. A pergola entry is present on the side.

1720.242 N. Waverly 1953 Historical Name: AP Number: 386-091-17 Non-Contributor

1721.252 N. Waverly 1924 Craftsman Bungalow Historical Name: AP Number: 386-091-18 A single-story multigabled roof Bungalow with wood lap siding. A large shallow front facing gable forms an entry porch which extends the full length of the house. The porch is supported by wooden columns supported by ornamental placed brick piers.

Α

United States Department of the Interior National Park Service

National Register of Historic Places Continuation Sheet

Section number _____7 Page _____370

Old Towne Orange Historic District, Orange, CA

1722.262 N. Waverly 1951 Historical Name: AP Number: 386-091-19 Non-Contributor

1723.272 N. Waverly 1923 California Bungalow Historical Name: AP Number: 386-091-20 A single-story, L-plan, multi-gabled Bungalow with wood lap siding. A front facing gable forms the entry porch supported by a wood columns and brick piers. The front entry door is flanked by side lights. A mullion side entry door is visible.

1724.282 N. Waverly 1924 California Bungalow Historical Name: AP Number: 386-091-21 A single-story L-plan Bungalow with multi-gable roof and wood lap siding. shed roof forms the front porch. Two brick piers with wood columns support the overhang. Two double hung picture windows flank the door. A south side gable covers the entry porch.

1725.292 N. Waverly 1924 California Bungalow Historical Name: AP Number: 386-091-22 A single-story multi-gabled Bungalow with wood lap siding on a rectangular plan. A front facing gable forms the entry porch supported by a set of three wooden columns atop ornamentally placed brick piers. Two transom picture windows flank the entry.

1726.133 S. Waverly 1990 Historical Name: AP Number: 390-452-16 Non-Contributor

National Register of Historic Places Continuation Sheet

Section number <u>7</u> Page <u>371</u>

Old Towne Orange Historic District, Orange, CA

1727.**138 S. Waverly** 1946 Historical Name: AP Number: 390-451-06 Non-Contributor

1728.143 S. Waverly 1926 Spanish Colonial Revival Historical Name: AP Number: 390-452-15 A single story house built on an L-plan with stucco facades and an adobe tiled gable roof. The main entry is formed by an extension of one roof and is articulated by arched opening bay window with mullioned windows present on the front facade.

1729.144 S. Waverly 1925 Mediterranean Revival Historical Name: AP Number: 390-451-07 A single story box plan residence with stucco facade and flat roof raised parapets are on both the main house and the entry porticos (garage also). The side entry portico mirrors the front one. Front facade has two pairs of triple windows and porch the whole length of the house.

1730.**151 S. Waverly** 1940 Provincial Revival Historical Name: AP Number: 390-452-14 Non-Contributor

1731.**152 S. Waverly** 1941 Historical Name: AP Number: 390-451-08 Non-Contributor

National Register of Historic Places Continuation Sheet

Section number _____7 Page _____372

Old Towne Orange Historic District, Orange, CA

1732.156 S. Waverly

1929 Tudor Revival Historical Name: AP Number: 390-451-09 A one and a half story Tudor Revival with a multi-gabled clipped roof and stucco sidings. Multiple mullioned windows are on the facade inclusive of a set of three mullioned picture windows. A chimney rests against the south side gable. A small extension of the roof provides an uncovered structural entry.

1733.**159 S. Waverly** 1939 Provincial Revival Historical Name: AP Number: 390-452-13 A hipped roof, stucco sided house in a modified box plan, with recessed, angled entry. The small front extension has its own smaller hipped roof. A wide decorative trim accents bottom portion of front roof.

1734.**164 S. Waverly** 1947 Historical Name: AP Number: 390-451-10 Non-Contributor

1735.167 S. Waverly

1938 Mediterranean Revival Historical Name: AP Number: 390-452-12 A parapet multi-gabled adobe tiled roof house with stucco siding on an Lplan. A front facing gable extension farms the entry porch. Through adobe vents placed above a large picture window on front facade. A small parapet roof garage is present.

1736.174 S. Waverly

1938 Mediterranean Revival Historical Name: AP Number: 390-451-11 A Mediterranean Revival residence with parapet roof and adobe tiled, multigables roof on an L-Plan. A large concrete tapered chimney is present on the side of the house. An extension of the roof forms the entry. Varying sizes of mullioned windows are present on front facade.

National Register of Historic Places Continuation Sheet

Section number 7 Page 373

Old Towne Orange Historic District, Orange, CA

1737.**175 S. Waverly** 1937 Provincial Revival Historical Name: AP Number: 390-452-11 Provincial Revival residence with a steep pitched multi-gabled roof on a smooth stucco rectangular plan. One of the two front facing gables forms an entry portico with a large arched opening. A large stucco chimney is present on front facade.

1738.182 S. Waverly

1931 Modified Cottage Historical Name: AP Number: 390-451-12 A multigabled Bungalow with wood lapped siding. A front facing gable forms the entry porch which is supported by wooden supports on concrete piers. The original porch appears to have been enclosed. The steep gables have an ornamental element in peak.

1739.183 S. Waverly

1937 Provincial Revival Historical Name: AP Number: 390-452-10 A stucco-sided L-Plan residence with steep pitched single-story gable roof. The two front facing gables are joined and one forms an entry portico with an arched opening. A large stucco chimney is present on the side. Two pairs of double hung mullioned windows are present on facade. The rear gable is higher than the front gable and forms a slight peak on roof.

1740.191 S. Waverly 1940 Historical Name: AP Number: 390-452-09 Non-Contributor

1741.**192 S. Waverly** 1949 Historical Name: AP Number: 390-451-13 Non-Contributor

OMB Approval No. 1024-0018

NPS Form 10-900a (8-86)

United States Department of the Interior National Park Service

National Register of Historic Places Continuation Sheet

Section 10 Page 1

Old Towne Orange Orange County, California

additional UTM references:

	Zone	Easting	Northing
5.	11	421510	3738350
6.	11	421510	3737540
7.	11	421090	3737540
8.	11	421090	3737960
9.	11	420390	3737960
10.	11	420390	3738380

OMB Approval No. 1024-0018

NPS Form 10-900a (8-86)


United States Department of the Interior National Park Service

National Register of Historic Places Continuation Sheet

Section <u>Photo Info</u> Page 1

Old Towne Orange Orange County, CA

Photographer: Steven G. McHarris Date of Photos: October, 1996 Location of Negatives: Old Towne Preservation Association P.O. Box 828 Orange, CA 92866



OLDTOWNE. CITY OF ORANGE

