2045



NATIONAL REGISTER

NPS FORM 10-900 (Rev. 8-86) OMB No. 1024-0018 [SD-SHPO # ECA-OH-597-1/89] [use paper with at least 25% cotton rag content, use NLQ or LQ printer]

United States Department of the Interior -- National Park Service NATIONAL REGISTER OF HISTORIC PLACES -- REGISTRATION FORM

This form is for use in nominating or requesting determinations of eligibility for individual properties or districts. See instructions in <u>Guidelines</u> <u>for Completing National Register Forms</u> (National Register Bulletin 16). Complete each item by marking "x" in the appropriate box or by entering "NA" for "not applicable." For functions, styles, materials, and areas of significance, enter only the categories and subcategories listed in the instructions. For additional space use continuation sheets (Form 10-900a). Type all entries.

 Name of Property historic name: Drake, H other name/ site number 	attie O. and Henry, Octo : NA	agon House		
2. Location street & number: 605 Th city, town: Huron state: SOUTH DAKOTA c	ird Street Street, S.W. ode: SD county: Beadle	/!	NA/ not for p NA/ vicinity 005 zip cod	,
3. Classification Ownership of Property:	Category of Property	Number of Resour		
	-	Number of Resour Contributing	Noncontrib	outing
Ownership of Property:	/XX/ building(s)	Contributing	Noncontrib	outing buildings
Ownership of Property: /XX/ private / / public-local / / public-state	/XX/ building(s) / / district / / site	Contributing	Noncontrib	outing buildings sites
Ownership of Property: /XX/ private / / public-local	/XX/ building(s) / / district / / site	Contributing	Noncontrib	outing buildings sites
Ownership of Property: /XX/ private / / public-local / / public-state	/XX/ building(s) / / district / / site	Contributing	Noncontrib	outing buildings sites structures

11. Form Prepared by

name/title: Tamra Misner, with technical assistance by John Rau, SHPO staff

organization: date: October 28, 1991

street & number: P. O. Box 731 telephone: 605-886-4065

city or town: Watertown state: SOUTH DAKOTA zip code: 57201

page 2: Hattie O. and Henry Drake Octagon House property name	, Beadle county	, SOUTH DAKOTA state
4. State/Federal Agency Certification		
As the designated authority under the National Historical Historical Historical Historical Historical Historical Register of Historical Places and measurequirements set forth in 36 CFR Part 60. In my / / does not meet the National Register criterial	ion / / request s for registering ets the procedur y opinion, the pr	for determination of properties in the al and professional operty / / meets nuation sheet.
Sall Oak 5H70 State or Federal agency or bureau		
In my opinion, the property / /meets / / does no		al Register Criteria. e continuation sheet.
Signature of commenting or other official	Date	
State or Federal agency or bureau		
5. National Park Service Certification I, hereby, certify that this property is:	Mation Byen	1/30/92
Signature	of the Keeper	Date

page 3: Hattie O. and Henry Drake Octagon House property name

, Beadle county

, SOUTH DAKOTA state

6. Function or Use (enter categories from instructions)

Historic functions:

Current Functions:

DOMESTIC/Single Dwelling

DOMESTIC/Single Dwelling

7. Description

Architectural Classification:

(enter categories from instructions)

Octagon Mode

Materials:

(enter categories from instructions)

foundation Concrete

walls Concrete

Stucco

roof Asphalt

other NA

Describe present and historic physical appearance: /XX/ see continuation sheet

8. Significance

Certifying official has considered the significance of this property in relation to other properties: / / /XX/

nationally statewide locally

Applicable National Register Criteria / / A / /B /XX/C / /D

Criteria Considerations / /A / /B / /C / /D / /E / /F / /G

Areas of Significance (enter from instructions)

Architecture

Period of Significance

circa 1893

Significant Dates

circa 1893

Significant Person

NA

Cultural Affiliation

Architect/Builder

Unknown

State significance of property, and justify criteria, criteria considerations, and periods of significance noted above /XX/ see continuation sheet

United States Department of the Interior National Park Service

National Register of Historic Places Continuation Sheet

Section	number	7	Page	1
Section	HUHIDE		raye	

Situated on a corner lot near the State Fair Grounds in Huron, South Dakota, the Hattie O. and Henry Drake Octagon House is a two-story eight-sided poured concrete masonry dwelling built about 1893. The exterior is covered with a stucco veneer scored to resemble brick construction. Rising from a poured concrete basement, the building is capped by a mansard roof that is covered with asphalt shingles. Four shallow shed-roofed dormers project from the mansard roof to light the upper story rooms. A square brick chimney rises from near the center of the roof. Fenestration is balanced consisting mostly of elongated one-over-one double hung sash windows with two-over-two storm windows.

The floor plan generally resembles that of a vernacular foursquare with the outside corners truncated due to the multi-sided configuration creating a less conventional format. In addition, the plan is interrupted by a multi-sided entrance foyer that causes irregular shapes and sizes of the adjoining rooms. A central stairway provides access to the upper level. (See floor plan sketch on continuation sheet 7.2.) Interior details are well executed with period authentic features including an entry door with a large oval beveled-glass light, hardwood pocket doors, a staircase with an ornate balustrade, and historic lighting fixtures and steam heat radiators. The kitchen was remodeled in the 1950s.


A few yards north of the house is a small square wood frame garage (noncontributing) that was built after 1916. It is capped by a pyramidal roof covered with tar paper.

United States Department of the Interior National Park Service

National Register of Historic Places Continuation Sheet

Section number ____7 Page ____2

DRAKE HOUSE FLOOR PLAN



United States Department of the Interior National Park Service

National Register of Historic Places Continuation Sheet

Section	number	8	Page	1

Under Criterion C of the National Register Criteria, the Hattie O. and Henry Drake Octagon House is significant in the area of architecture, because it is one of only two or three known octagon mode dwellings extant in South Dakota. Built in circa 1893, the house has been a longtime landmark to local residents. Under the South Dakota State Historical Preservation Plan the property relates to the historic context labeled: IV. Permanent Rural and Urban Pioneer Settlement, D.2. Urban Development/Residential Living.

The construction of octagonal or other multi-sided 1 houses is generally an anomaly in American building design of the mid-to-late 19th Century. thousands of examples of such dwellings, most of them unique designs, erected by would-be residents seeking a comfortable, efficient home. Although the use of multi-sided buildings in America dates back to Colonial times, it was not until the middle of the last century that the idea was popularized. At that time, theologian, phrenologist, lecturer, and publisher Orson Squire Fowler wrote a treatise in which he advocated the concept. First published in 1848, his work entitled A Home For All; or The Gravel Wall and Octagon Mode of Building argued that square or rectangular houses were inadequate for successful domesticity. As the title suggests, Fowler also encouraged the use of what he called "gravel" construction, which is actually primitive poured concrete masonry construction. Concrete had been known to the ancient Romans, but it was at that time very rare in America. Using his concepts, Fowler built his own home in Fishkill, New York, a massive four-story building equipped with the latest conveniences. Eventually, several other individuals built grand designs. However, with continued publication of Fowler's work meaner classes were also attracted to his concepts, and smaller, more modest eight-sided houses were built throughout the country. In many of these later examples, wood construction was substituted for masonry. By the end of the 19th Century, interest in the idea of multi-sided houses waned, in large part due to the complicated room arrangements often necessary in the smaller houses. Although round and multi-sided barns continued to enjoy limited popularity after the turn of the century, the notion of building multi-sided houses is for the most part confined to the last half of the 19th Century.

Built in circa 1893, the Drake house is a late example of an octagon house. It features poured concrete walls, just as Fowler had advocated, and a plethora of fine period appointments including an entry door with a large oval beveled-glass light, hardwood pocket doors, a staircase with an ornate balustrade, and historic lighting fixtures and steam heat radiators. Only one or two other octagon houses are believed to exist in the state.

^{1.} with more than four sides.

United States Department of the Interior National Park Service

National Register of Historic Places Continuation Sheet

Section	number	8	Page	2
360000	HUHHDEL		raye	

Beadle County, lying in the flat plain of the James River valley, was created in 1879 and officially organized a year later. Huron, the county seat, was established by the Chicago and Northwestern Railroad in 1879 and 1880 to serve as a hub for its expansive network in Dakota Territory. The city, which is located on the west bank of the James River, was incorporated in 1883. It quickly grew to be a major commercial and transportation center for the surrounding farming community. Huron was also a formidable candidate for state capital and became embroiled in several costly campaigns for that position, which eventually left the community financially hardshipped but without the desired prize. Nevertheless, the city persevered. One of its greatest attractions has been the annual State Fair that brings in thousands of vendors and patrons from across South Dakota.

It is in this community that Hattie O. and Henry Drake purchased a parcel of land in 1893. It is believed that they constructed their octagon house in about the same year. After 1914, ownership of the house passed through several hands until it was acquired by John and Elizabeth Eid in the 1940s. The current owner, Tamra Misner, a granddaughter of Elizabeth Eid, is in the process of restoring the house.

The period of significance of the nominated property does not extend beyond its date of construction in circa 1893.

page 4: Hattie O. and Henry Drake Octagon House , Beadle property name county state 9. Major Bibliographical References /XX/ see continuation sheet Previous documentation by NPS: / / preliminary determination of individual listing (36 CFR 67) has been requested / / previously listed in the National Register / / previously determined eligible by the National Register / / designated a National Historic Landmark / / recorded by Historic American Buildings Survey # _ / / recorded by Historic American Engineering Record # _____ Primary location of additional data: /XX/ State historic preservation office / / Other State agency / / Federal agency / / Local government / / University / / Other Specify repository: South Dakota Historical Preservation Center 10. Geographical Data Acreage of property: Less than one acre UTM References: A = /14/ /561-850/ /4912-340/ B = / / C = / /D = / / / / / / ZONE EASTING NORTHING ZONE EASTING NORTHING Quad: Huron Scale: 1:24000 / / see continuation sheet Verbal Boundary Description: The nominated property is bounded by the legal description as recorded in the Beadle County Register of Deeds Office: South 95 feet of Lots 9 and 10, and South 95 feet of the East 5 feet of Lot 11, Block 52, Fifth Railway Addition to the City of Huron, Beadle County, South Dakota. / / see continuation sheet

Boundary Justification: The boundaries of the nominated property are contained within

/ / see continuation sheet

the lot lines of the parcel historically associated with the property.

, SOUTH DAKOTA

United States Department of the InteriorNational Park Service

National Register of Historic Places Continuation Sheet

Section number ____9 Page ___1__

- Fowler, Orson Squire. The Octagon House: A Home For All. 1848. Rpt.: New York: Dover Publications, Inc., 1973.
- Huss, Dorothy, Robert S. Kuni, William Lampe, and Margaret Moxon. <u>Huron</u>
 <u>Revisited</u>. Huron, SD: East Eagle Co., 1988.
- Lancaster, Clay. Architectural Follies in America: or Hammer, Sawtooth, and Nail. Rutland, VT: Charles E. Tuttle Co., 1960.
- Map of Huron, South Dakota. New York: Sanborn Map Co., 1916.
- Massey, James C. and Shirley Maxwell. "Octagons and Hexagons and other Multi-Faceted Eccentricities." Old House Journal. XIV (n. 5, June 1986): pp. 228-231.
- Second Census of the State of South Dakota (1905). Manuscript Materials. State Historical Society, Pierre, SD.

Tax and Deed Records. Beadle County Courthouse, Huron, South Dakota.

Title Abstract.

Waybill, Opal (longtime Huron resident). Personal Interview with Tamra Misner, September 1991.

United States Department of the interior National Park Service

National Register of Historic Places Continuation Sheet

Section number Photos Page 1

```
Hattie O. and Henry Drake Octagon House
Huron, Beadle County, South Dakota
by Tamra Misner
May 1991
Neg.: Tamra Misner, Watertown, SD
South, east and northeast facades, camera facing northwest
(noncontributing garage visible in right background)
Photo No. 1
2.
Hattie O. and Henry Drake Octagon House
Huron, Beadle County, South Dakota
by Tamra Misner
May 1991
Neg.: Tamra Misner, Watertown, SD
West, southwest, and south facades, camera facing east-northeast
Photo No. 2
Hattie O. and Henry Drake Octagon House
Huron, Beadle County, South Dakota
by Tamra Misner
May 1991
Neg.: Tamra Misner, Watertown, SD
Interior, pocket doors
Photo No. 3
Hattie O. and Henry Drake Octagon House
Huron, Beadle County, South Dakota
by Tamra Misner
May 1991
Neg.: Tamra Misner, Watertown, SD
Interior, first floor room, southwest corner
Photo No. 4
Hattie O. and Henry Drake Octagon House
Huron, Beadle County, South Dakota
by Tamra Misner
May 1991
Neg.: Tamra Misner, Watertown, SD
Interior, second floor hallway
Photo No. 5
```

United States Department of the Interior National Park Service

National Register of Historic Places Continuation Sheet

National Register property file

Nominating Authority (without nomination attachment)

number	Page
	SUPPLEMENTARY LISTING RECORD
NRIS Referen	ce Number: 05000034
Property Nam	e: Drake, Hattie O. and Henry, Octagon (Additional Documentation)
County: Bead	lle State: South Dakota
Multiple Nam	e: N/A
nomination do	MCO///an/ February 10, 2005
Amended Iten	ns in Nomination:
	ne of Property: The phrase "(Additional Documentation)" hereby replaces the ge Classification)" to indicate the action being requested.
The South Dal	kota Historic Preservation Office provided the information for this amendment.
DISTRIBUT	ION:

United States Department of the Interior

National Park Service

NATIONAL REGISTER OF HISTORIC PLACES REGISTRATION FORM

This form is for use in nominating or requesting determinations for individual properties and districts. See instructions in How to Complete the National Register of Historic Places Registration Form (National Register Bulletin 16A). Complete each item by marking "x" in the appropriate box or by entering the information requested. If any item does not apply to the property being documented, enter "N/A" for "not applicable." For functions, architectural classification, materials, and areas of significance, enter only categories and subcategories from the instructions. Place additional entries and narrative items on continuation sheets (NPS Form 10-900a). Use a typewriter, word processor, or computer, to complete all items.

1. Name of Prope	erty						
historic name other names/site	Drake, Hattie C number). and Henry	y, Octagon I	House (Gara	ge Red	classification	n)
2. Location							
street & number city or town Huistate SD	*****************		Beadle		not for	oublication Vicinity _ zip code _	
3. State/Federal As the designated aut			Preservation A	Act of 1986, as	amende	d I hereby ce	rtify that this
x nomination rethe National Register 60. In my opinion, the property be considere comments.)	equest for determin of Historic Places a property x me	ation of eligibilind meets the ets does	ity meets the d procedural and not meet the	ocumentation : d professional r National Regist	standard equirem ter Criter	s for registering ents set forth in ia. I recomment	ng properties in n 36 CFR Part nd that this
Signature of certif	Voat ying official				<i>3 - 200</i> 0ate	9	
South Dakota S State or Federal a		au					
In my opinion, the pro additional comments.		does not	meet the Natio	nal Register cr	iteria. (_	See contin	uation sheet for
Signature of comm	nenting or other	official		D	ate		

Name of related multiple property listing (Enter "N/A" if property is not part of a multiple property

Beadle County, South Dakota

Drake Octagon House Garage

listing.) N/A

Drake Octagon House Garage Name of Property	Beadle County, South Dakota County and State	
6. Function or Use		
Historic Functions (Enter categories for Cat: Domestic Sub: Second	rom instructions) ondary Structure	
Current Functions (Enter categories from Cat: Domestic Sub: Sec	com instructions)	
7. Description Architectural Classification (Enter care	tegories from instructions)	
No Style		
Materials (Enter categories from instru	ctions)	
Foundation Concrete Roof Asphalt Walls Concrete; stucco		
Other N/A		
Narrative Description (Describe the hi continuation sheets.)	storic and current condition of the property on one or more	

See Continuation Sheets

8. Statement of Significance

Applicable National Reproperty for National Re	gister Criteria (Mark "x" in one or more boxes for the criteria qualifying the egister listing)
	ociated with events that have made a significant the broad patterns of our history.
B Property is asso	ociated with the lives of persons significant in our past.
period, or meth- master, or poss	dies the distinctive characteristics of a type, od of construction or represents the work of a sesses high artistic values, or represents a distinguishable entity whose components lack ction.
D Property has yie in prehistory or	elded, or is likely to yield information important history.
Criteria Consideration	s (Mark "X" in all the boxes that apply.)
A owned by a reli	gious institution or used for religious purposes.
B removed from it	s original location.
C a birthplace or a	a grave.
D a cemetery.	
E a reconstructed	building, object,or structure.
F a commemorati	ve property
G less than 50 year	ars of age or achieved significance within the past 50 years.
Areas of Significance	(Enter categories from instructions)
Architect	ure
Period of Significance	1893, 1916

Drake Octagon House C	3arage	Beadle County, South Dakota
Name of Property		County and State
Significant Dates	1893; 1916	
3		_
		-
		_
Significant Person	N/A	
Cultural Affiliation	N/A	
Architect/Builder	Unknown	
Namedica Ctatana	4 - 6 Ol : 61	
	•	e (Explain the significance of the property on one or more
continuation sheets.)		
See Continuation Sh	eets	
9. Major Bibliograpi	nical Reference	S
(Cite the books artic	les and other so	ources used in preparing this form on one or more continuation
sheets.)		areas assa in proparing the form of one of more continuation
,		
Previous document	ation on file (N	PS)
	•	ndividual listing (36 CFR 67) has been requested.
previously list	ed in the Nationa	al Register
previously det	ermined eligible	by the National Register
Designated a	National Historic	Landmark
recorded by H	listoric American	Buildings Survey #
recorded by H	listoric American	Engineering Record #
Primary Location of		
x State Historic	Preservation Of	iice
Other State a	gency	
Federal agend	У	
Local governn	nent	
University		
Other		
Name of repository:	N/A	

A sketch map for historic districts and properties having large acreage or numerous resources.

Photographs

Representative black and white photographs of the property.

Additional items (Check with the SHPO or FPO for any additional items)

Property Owner				
(Complete this item at the request of the SHPO or FPO.)				
name Scott Dorwart				
name Cook Borwart				
street & number 813 North Prairie Avenue	telephone 605-680-2828			

Drake Octagon House Garage

Name of Property

Beadle County, South Dakota

County and State

Paperwork Reduction Act Statement: This information is being collected for applications to the National Register of Historic Places to nominate properties for listing or determine eligibility for listing, to list roperties, and to amend existing listings. Response to this request is required to obtain a benefit in accordance with the National Historic Preservation Act, as amended (16 U.S.C. 470 et seq.).

Estimated Burden Statement: Public reporting burden for this form is estimated to average 18.1 hours per response including the time for reviewing instructions, gathering and maintaining data, and completing and reviewing the form. Direct comments regarding this burden estimate or any aspect of this form to the Chief, Administrative Services Division, National Park Service, P.O. Box 37127, Washington, DC 20013-7127; and the Office of Management and Budget, Paperwork Reductions Project (1024-0018), Washington, DC 20503.

Drake Octagon House	Э
Name of Property	

Beadle County, South Dakota
County and State

NPS FORM 10-900-A (8-86) OMB Approval No. 1024-0018

United States Department of the InteriorNational Park Service

National Register of Historic Places Continuation Sheet

Section number	7	_ Page #	1

NARRATIVE DESCRIPTION

BUILDING PREVIOUSLY LISTED

Situated on a corner lot near the State Fair Grounds in Huron, Beadle County, South Dakota, the Hattie O. and Henry Drake Octagon House is a two-story eight sided poured concrete masonry dwelling built about 1893. The exterior is covered with a stucco veneer scored to resemble brick construction. Rising from a poured concrete basement, the building is capped by a mansard roof that is covered with wood shingles.

The façade (southeast elevation) has a shallow shed dormer with two one-over-one double hung sash windows. On the main level is a single wood door with metal storm door on the exterior. This serves as the main entrance for the house. On each side of the door is an elongated two-over-two window and on either side of each window is a hexagonal wood pilaster. A concrete set of stairs with metal rails on each side runs up to the front entrance. The east elevation has a set of three adjacent elongated two-over-two windows that abut the eastern-most pilaster on the southeast elevation. To the north of these windows on the east elevation is a square window with two vertical panes.

The northeast elevation has a shallow shed dormer with three one-over-one double hung sash windows. Directly below the left-most of these windows is another one-over-one double hung sash window on the first story. Below the right-most window is a single wood door with a vinyl storm door on the exterior. The north side of the house has a small single-pane window in the center-top of the mansard roof. The main level of the north elevation has two one-over-one double hung sash windows. The northwest elevation has a shallow shed dormer with two one-over-one double hung sash windows. On the far left side of the first level is a one-over-one double hung sash window. There are two adjacent one-over-one double hung sash windows on the west elevation.

The southwest elevation also has a shallow shed dormer with two one-over-one double hung sash windows. On the left side of the main level is a four-pane casement window. On the right side of the elevation is a one-over-one double hung sash window. The south elevation has a square window with two vertical panes. To the east of this window is a set of three adjacent elongated two-over-two windows that abut the western-most pilaster on the southeast elevation.

The floor plan generally resembles that of a vernacular foursquare with the outside corners truncated due to the multi-sided configuration creating a less conventional format. In addition, the plan is interrupted by a multi-sided entrance foyer that causes irregular shapes and sizes of the adjoining rooms. A central stairway provides access to the upper level. Interior details are well executed with

Drake Octagon	House	Garage	
Name of Property			

NPS FORM 10-900-A (8-86)

Beadle County,	South	Dakota	
County and State			

OMB Approval No. 1024-0018

United States Department of the Interior National Park Service

National Register of Historic Places Continuation Sheet

period authentic features including an entry door with a large oval beveled-glass light, hardwood pocket doors, a staircase with an ornate balustrade, and historic lighting fixtures and steam heat radiators. The kitchen was remodeled in the 1950s.

BUILDING TO BE RECLASSIFIED AS CONTRIBUTING

A few yards north of the house is a small square wood frame garage that was built circa 1916. This garage was initially classified non-contributing. It is proposed that this garage be reclassified as a contributing resource.

The garage has a pyramidal roof with asphalt shingles. The north and the south elevations are clad with stucco while the east and the west elevations have wood shiplap siding. The east elevation has the original wood folding doors. Each door has three leaves and folds open to the sides of the garage. The south elevation has a single door on the far left side of the elevation. The north and west elevations each have a one-over-one double hung sash window in the center of the elevation.

Drake Octagon House	Beadle County, South Dakota
Name of Property	County and State

NPS FORM 10-900-A (8-86) OMB Approval No. 1024-0018

United States Department of the InteriorNational Park Service

National Register of Historic Places Continuation Sheet

Section number	8	Page #	1
Coolon nambor	•	. ago //	

Narrative Statement of Significance

The Octagon House garage is eligible under Criterion C and should be reclassified as a contributing building as it embodies the distinctive characteristics of a type and period. The garage represents a common design of secondary structures in South Dakota during the early twentieth century. It does, however, contain distinct elements that make it unique. While most secondary structures were simple wood gabled buildings, the Octagon House garage features a pyramidal roof and two stucco walls. It also retains its original three-leaved folding doors. Like Octagon Houses, historic secondary structures are a rare and threatened resource in South Dakota. The garage retains its historic integrity and is significant under Criterion C.

Beadle County was created in 1879 and officially organized a year later. Huron, the county seat, was established by the Chicago and Northwestern Railroad in 1879 and 1880 and incorporated in 1883. It quickly grew into a major commercial and transportation center for the surrounding farming community. Henry and Hattie O. Drake purchased a parcel of land in Huron in 1893 and shortly thereafter built the Octagon House.

The detached garage has been associated with the Octagon House and has undergone minimal alterations since it was constructed circa 1916. When automobiles first became popular in the 1910s and 1920s, they were housed in detached buildings, as had been done with horses and carriages. As the automobile gained importance in American society, garages were no longer constructed separately but instead designed as an extension of the house. (McAlester, 30) The Octagon House garage is thus eligible under Criterion C for its design and association with the Octagon House.

Drake Octagon	House		
Name of Property		 	

Beadle County, South Dakota
County and State

NPS FORM 10-900-

OMB Approval No. 1024-0018

United States Department of the InteriorNational Park Service

National Register of Historic Places Continuation Sheet

Section number

<u>9 & 10</u> Page # <u>1</u>

Bibliography

McAlester, Virginia and Lee. A Field Guide to American Houses. Alfred Knoff, Inc.: New York, 1984.

Verbal Boundary Description

The boundary for the property will remain the same as originally nominated. The property is bounded by the legal description as recorded in the Beadle County Register of Deeds Office: South 95 feet of Lots 9 and 10, and South 95 feet of the East 5 feet of lot 11, Block 52, Fifth Railway Addition to the City of Huron, Beadle County, South Dakota.

Boundary Justification

The boundary will continue to contain the lot lines of the parcel historically associated with both the octagon house and the garage.

	County, South Dakota
Name of Property	County and State
NPS FORM 10-900-A (8-88)	OMB Approval No.

United States Department of the Interior National Park Service

National Register of Historic Places Continuation Sheet

Section number	Photos	Page #			