

NATIONAL REGISTER OF HISTORIC PLACES
INVENTORY - NOMINATION FORM

(Type all entries - complete applicable sections)

STATE: Mississippi	
COUNTY: Jefferson	
FOR NPS USE ONLY	
ENTRY NUMBER	DATE
71. 11. 28. 0013	11/23/71

1. NAME

COMMON:
Springfield Plantation

AND/OR HISTORIC:

2. LOCATION

STREET AND NUMBER:
Section 33, T 9N, R 1W (near the South Fork of Coles Creek)

CITY OR TOWN:
8 miles west of Fayette, Mississippi, via State Route 553

STATE Mississippi	CODE 28	COUNTY: Jefferson	CODE 063
-----------------------------	-------------------	-----------------------------	--------------------

3. CLASSIFICATION

CATEGORY (Check One)	OWNERSHIP	STATUS	ACCESSIBLE TO THE PUBLIC
<input type="checkbox"/> District <input type="checkbox"/> Site <input type="checkbox"/> Object <input checked="" type="checkbox"/> Building <input type="checkbox"/> Structure	<input type="checkbox"/> Public <input checked="" type="checkbox"/> Private <input type="checkbox"/> Both	Public Acquisition: <input type="checkbox"/> In Process <input checked="" type="checkbox"/> Being Considered	<input type="checkbox"/> Occupied <input checked="" type="checkbox"/> Unoccupied <input type="checkbox"/> Preservation work in progress
PRESENT USE (Check One or More as Appropriate)			
<input type="checkbox"/> Agricultural <input type="checkbox"/> Commercial <input type="checkbox"/> Educational <input type="checkbox"/> Entertainment	<input type="checkbox"/> Government <input type="checkbox"/> Industrial <input type="checkbox"/> Military <input type="checkbox"/> Museum	<input type="checkbox"/> Park <input type="checkbox"/> Private Residence <input type="checkbox"/> Religious <input type="checkbox"/> Scientific	<input type="checkbox"/> Transportation <input type="checkbox"/> Other (Specify) <u>Vacant</u>
Yes: <input type="checkbox"/> Restricted <input type="checkbox"/> Unrestricted <input checked="" type="checkbox"/> No			

4. OWNER OF PROPERTY

OWNER'S NAME: **James H. Williams, Jr., and the estate of William Powell Williams**

STREET AND NUMBER:
Boatmen's Bank Building

CITY OR TOWN: St. Louis	STATE: Missouri	CODE 63102	CODE 24
-----------------------------------	---------------------------	----------------------	-------------------

5. LOCATION OF LEGAL DESCRIPTION

COURTHOUSE, REGISTRY OF DEEDS, ETC.:
Office of the Chancery Clerk, Jefferson County Courthouse

STREET AND NUMBER:
Box 145

CITY OR TOWN: Fayette	STATE: Mississippi	CODE 39069	CODE 28
---------------------------------	------------------------------	----------------------	-------------------

6. REPRESENTATION IN EXISTING SURVEYS

TITLE OF SURVEY:
Historic American Buildings Survey

DATE OF SURVEY: **1934** Federal State County Local

DEPOSITORY FOR SURVEY RECORDS:
Division of Prints and Photographs

STREET AND NUMBER:
Library of Congress

CITY OR TOWN: Washington	STATE: District of Columbia	CODE 0011
------------------------------------	---------------------------------------	---------------------

SEE INSTRUCTIONS

STATE: Mississippi
COUNTY: Jefferson

STATE:

COUNTY:

ENTRY NUMBER

DATE

FOR NPS USE ONLY

7. DESCRIPTION

CONDITION	(Check One)					
	<input type="checkbox"/> Excellent	<input type="checkbox"/> Good	<input type="checkbox"/> Fair	<input checked="" type="checkbox"/> Deteriorated	<input type="checkbox"/> Ruins	<input type="checkbox"/> Unexposed
	(Check One)			(Check One)		
	<input checked="" type="checkbox"/> Altered	<input type="checkbox"/> Unaltered		<input type="checkbox"/> Moved	<input checked="" type="checkbox"/> Original Site	

DESCRIBE THE PRESENT AND ORIGINAL (if known) PHYSICAL APPEARANCE

Springfield is a two-story residence with attic and basement, measuring 67 feet 10 inches in length and 55 feet 5 inches in depth. Handmade red brick are laid in Flemish bond on the facade (north elevation) and common bond on the side elevations. Interior chimneys project prominently above each gable of the broken-pitch roof, which on the north slopes to form a portico supported by six columns. The latter are approximations of the Tuscan order and made of triangular-shaped bricks covered with stucco. On the second floor of the portico is a balustrade of rectangular balusters, its railings inserted into the shafts of the intersecting columns. Fenestration on both floors of the facade is identical: a central doorway with eight-paned transom, flanked by detached side lights with twelve panes each, and four windows symmetrically spaced within the intercolumniation. There are six openings on each side elevation, all of them windows except the door on the first floor east, which appears to have formerly been a window also. A 1934 Historic American Buildings Survey photograph shows 6 over 6 sashes being installed on the side elevations; a number of those which remain in front and rear windows are 12 over 12 and presumably original. Paneled reveals range in depth from 20 inches to 26 inches, and two-part wooden shutters are held open by wrought-iron fasteners attached to blocks of wood set flush into the brick walls. The louvered walls of the second floor rear and sides were enclosed with brick before 1920, and partitioning for three rooms was probably added then also. On the southwest corner of the first floor an outside small frame kitchen was built in the late 1930s and passage between house and kitchen was provided by removing bricks beneath a window in the common wall. An earlier kitchen, also frame, was located approximately 25 feet southeast of the central rear door.

It is not known what other alterations, if any, have been made in the original floor plan. The present layout of the first floor consists of a large central hallway (14 feet by 38 feet 3 inches) flanked by two rooms on the west and three rooms and a stairwell (with rudimentary, winding stair) on the east, all areas being of varying dimensions. The second floor is similar, although the expanse of hallway to the rear is interrupted by the middle room of the three formed by partitioning. The rooms and hallways of the main block total thirteen, whereas it is believed that originally Springfield had eight rooms and two hallways. The interior construction of the house includes yellow poplar and cypress flooring, cypress jambs, and yellow poplar ceiling spans, all of which appear to be original materials. The six-inch boards of the planked ceiling are laid tongue and groove, and in the attic, beams are joined by the mortise and tenon method and pegged. The crossbars of the "H" type ceiling supports are centered with king posts to which rafters are secured by mortise and tenon. In addition, metal

SEE INSTRUCTIONS

8. SIGNIFICANCE

PERIOD (Check One or More as Appropriate)

- | | | | |
|--|---------------------------------------|--|---------------------------------------|
| <input type="checkbox"/> Pre-Columbian | <input type="checkbox"/> 16th Century | <input type="checkbox"/> 18th Century | <input type="checkbox"/> 20th Century |
| <input type="checkbox"/> 15th Century | <input type="checkbox"/> 17th Century | <input checked="" type="checkbox"/> 19th Century | |

SPECIFIC DATE(S) (If Applicable and Known) ca. 1800

AREAS OF SIGNIFICANCE (Check One or More as Appropriate)

- | | | | |
|--|--------------------------------------|---|--|
| <input type="checkbox"/> Aboriginal | <input type="checkbox"/> Education | <input checked="" type="checkbox"/> Political | <input type="checkbox"/> Urban Planning |
| <input type="checkbox"/> Prehistoric | <input type="checkbox"/> Engineering | <input type="checkbox"/> Religion/Phi- | <input type="checkbox"/> Other (Specify) |
| <input type="checkbox"/> Historic | <input type="checkbox"/> Industry | osophy | _____ |
| <input checked="" type="checkbox"/> Agriculture | <input type="checkbox"/> Invention | <input type="checkbox"/> Science | _____ |
| <input checked="" type="checkbox"/> Architecture | <input type="checkbox"/> Landscape | <input type="checkbox"/> Sculpture | _____ |
| <input type="checkbox"/> Art | Architecture | <input type="checkbox"/> Social/Human- | _____ |
| <input type="checkbox"/> Commerce | <input type="checkbox"/> Literature | itarian | _____ |
| <input type="checkbox"/> Communications | <input type="checkbox"/> Military | <input type="checkbox"/> Theater | _____ |
| <input type="checkbox"/> Conservation | <input type="checkbox"/> Music | <input type="checkbox"/> Transportation | _____ |

STATEMENT OF SIGNIFICANCE

Thomas Marston Green, Jr. (1758-1813), builder of Springfield, was a member of the first general assembly of the Territory of Mississippi and the second man to represent the territory in the U. S. Congress. He was a son of Colonel Thomas M. Green (1723-1805), who was instrumental in the establishment of the short-lived Bourbon County (which included the Natchez district) by Georgia in 1785. Thomas M. Green, Jr., was a brother of Abner Green, territorial treasurer of Mississippi, and brother-in-law of Cato West, acting governor of the territory, 1803-1805, and a Jefferson County delegate to the state constitutional convention of 1817. Colonel Thomas Hinds, who distinguished himself in the Pensacola and New Orleans campaigns with Jackson and was also active in the territorial period and early statehood of Mississippi, was a son-in-law of Thomas M. Green, Jr. The Springfield estate was retained by members of the Green family until 1850, and in 1914 the house and 533 acres were acquired by James H. Williams, father of the present owner. Thomas M. Green, Jr. and his first wife, Martha Kirkland Green (1759-1805), are buried in the Green family cemetery located south of Springfield house.

Local tradition maintains that Andrew Jackson and Rachel Donelson Robards were married at Springfield in the summer of 1791. One of the earliest known references to the event is in The Memories of Fifty Years (1870) by W. H. Sparks, whose own wife was a daughter of Abner Green: "Jackson came and married her [Rachel], in the house of Thomas M. Green." Sparks' relationship to the Green family would seemingly add credence to his account, but he diminishes his own reliability by such devices as attributing entire paragraphs of verbatim conversation to Jackson. In A History of Mississippi by Robert Lowry and William H. McCardle (1891), the tradition of the Springfield marriage was restated, as well as elaborated:

General Andrew Jackson was married at the home of the Hon. Thomas Marston Green, on the northern bank of Coles Creek, in what is now Jefferson County, in the summer of 1791, to Mrs. Rachel Robards....the ceremony was performed by Colonel Thomas Green,

SEE INSTRUCTIONS

9. MAJOR BIBLIOGRAPHICAL REFERENCES

Cox, William E. "Springfield Historic House." Natchez Trace Parkway: Resource Study Proposal NATR-H-18, 1968. Collections, Mississippi Department of Archives and History, Jackson, Mississippi.
 Historic American Buildings Survey. Springfield Plantation. 1 photograph, 1934.
 Interview with Mr. Carter H. Anderson, Jefferson County Historical Society, Fayette, Mississippi, April 25, 1971.

10. GEOGRAPHICAL DATA

LATITUDE AND LONGITUDE COORDINATES DEFINING A RECTANGLE LOCATING THE PROPERTY				O R	LATITUDE AND LONGITUDE COORDINATES DEFINING THE CENTER POINT OF A PROPERTY OF LESS THAN TEN ACRES				
CORNER	LATITUDE				LONGITUDE			LATITUDE	LONGITUDE
	Degrees	Minutes	Seconds	Degrees	Minutes	Seconds	Degrees	Minutes	Seconds
NW	31°	44'	53"	9P	11'	30"	0		
NE	31°	44'	53"	9P	11'	40"	0		
SE	31°	44'	40"	9P	11'	40"	0		
SW	31°	44'	40"	9P	11'	30"	0		

APPROXIMATE ACREAGE OF NOMINATED PROPERTY: **15 acres**

LIST ALL STATES AND COUNTIES FOR PROPERTIES OVERLAPPING STATE OR COUNTY BOUNDARIES

STATE:	CODE	COUNTY	CODE

11. FORM PREPARED BY

NAME AND TITLE:
Dawn Maddox, Architectural Historian

ORGANIZATION: **Mississippi Department of Archives and History** DATE: **Aug. 11, 1971**

STREET AND NUMBER:
Post Office Box 571

CITY OR TOWN: **Jackson** STATE: **Mississippi 39205** CODE: **28**

12. STATE LIAISON OFFICER CERTIFICATION

As the designated State Liaison Officer for the National Historic Preservation Act of 1966 (Public Law 89-665), I hereby nominate this property for inclusion in the National Register and certify that it has been evaluated according to the criteria and procedures set forth by the National Park Service. The recommended level of significance of this nomination is:

National State Local

Name *R. A. McLemore*
R. A. McLemore

Title Director, Miss. Dept. of Archives and History

Date August 11, 1971

NATIONAL REGISTER VERIFICATION

I hereby certify that this property is included in the National Register.

Ernest A. Connally
 Chief, Office of Archeology and Historic Preservation

NOV 23 1971

Date _____

ATTEST:

William J. ...
 Keeper of The National Register

NOV 8 1971

Date _____

SEE INSTRUCTIONS

NATIONAL REGISTER OF HISTORIC PLACES
INVENTORY - NOMINATION FORM

(Continuation Sheet)

STATE	
Mississippi	
COUNTY	
Jefferson	
FOR NPS USE ONLY	
ENTRY NUMBER	DATE
71-11-28-0013	11/23/71

(Number all entries)

7.
straps are bent around the rafters and bolted to the king posts, a braced peak arrangement which eliminates the need for a ridge-pole.

Interior finish, confined to wainscoting, chair rails, baseboards, cornices, and mantelpieces, is unmistakably provincial, yet imaginatively conceived and vigorously executed, a satisfying accent to the massive grace of the house itself. Mantelpieces, reflecting the Adam influence popularized in New England by McIntire and Bulfinch, feature such embellishments as pilasters, paterae, reeding, and grooving, while cornices in the hallway, parlor, and master chamber on the second floor west repeat the gougework patterns from the mantelpieces in a variety of combinations. (Its decorative woodcarving is one factor which suggests that Springfield was built at a later date than 1791, the year the Andrew Jackson-Rachel Robards marriage allegedly took place there. It seems unlikely that the Adamesque mode of interior architecture would have penetrated the Old Southwest a decade prior to its ascendancy in such centers of the au courant as Boston, Salem, and Charleston. On the other hand, it is possible that the woodwork is of a later period than the house itself.)

8.
who acted in his capacity of magistrate in and for Bourbon County.

No documentation for the above is given; in actuality, however, Bourbon County was officially abolished in 1788.

In 1937 a great-great-granddaughter of Thomas M. Green, Jr., Laura Lake Ihrle, wrote that "Jackson and Mrs. Robards were married in the great big downstairs room at Springfield. I have been told this many times, not only by my mother, but by other members of the family." The tradition had been questioned as early as 1910, however, when a letter written by E. R. Jones, a resident of Jefferson County, appeared in the Publications of the Mississippi Historical Society for that year:

I never heard that Mrs. Robards was married to General Jackson in the home of Thos. Marston Green until it came out in McCardle's History of Mississippi, such being contrary to tradition.

My father, Rev. Jno. G. Jones, was born in 1804 and resided for many years at Belle Grove, just across the Natchez Trace from Mrs. Robard's home, the site of which he

NATIONAL REGISTER OF HISTORIC PLACES
INVENTORY - NOMINATION FORM

(Continuation Sheet)

STATE	
Mississippi	
COUNTY	
Jefferson	
FOR NPS USE ONLY	
ENTRY NUMBER	DATE
71 11 28. 0013	11/23/71

(Number all entries)

8.

often pointed out to me as our farm was less than a mile off. He used this language: "I fear Major McCardle's vanity and his connection with the Green family has led him into an error. Mrs. Robards, so the old people of the time while I was growing up about Greenville [an extinct settlement several miles east of Springfield] told me, owned her own farm, near Greenville, and had on it a double log house with an open hall, and here they say she was married to General Jackson. I am as sure as can be from testimony, that McCardle is wrong. I will also say that for many years of my life I was often with Allen Colier (colored), who was a body servant of General Thomas Hinds and was once a slave of Thomas Marston Green, and went as such to General Hinds, who married Miss Laminda Green. When I informed him what McCardle's History has said about Jackson's being married at Green's house, his reply was: "Twan't so; Ole Master's house - the Great House warn't built at that time - I members it, and Miss Robards don't have to go over thar to be married, when she had a good house of her own right by what da call the Jackson Springs."

The account has a convincing ring to it but it obviously raises more questions than it answers.

Despite long and diligent search by Jackson historians, no incontrovertible evidence to support or refute the tradition that the Jackson marriage occurred at Springfield has yet come to light. The role of Springfield Plantation in the political, economic, and cultural history of the Old Southwest is a genuine one, however. The Greens and their connections were one of the most prominent families in the formation of Mississippi as a territory and a state. Thomas M. Green, Jr., in three decades of residence in Jefferson County, was a prototype of the antebellum planter whose fortune was based on the cultivation of extensive land holdings in a single crop - cotton. These associations, in addition to the intrinsic architectural significance of Springfield and its proximity to the Old Natchez Trace, have prompted negotiations currently underway whereby the National Park Service of the Department of the Interior anticipates incorporating the house and adjoining acreage into the Natchez Trace Parkway.

NATIONAL REGISTER OF HISTORIC PLACES
INVENTORY - NOMINATION FORM


(Continuation Sheet)

STATE	
Mississippi	
COUNTY	
Jefferson	
FOR NPS USE ONLY	
ENTRY NUMBER	DATE
71-11-28-0013	11/23/71

(Number all entries)

9.
Lowry, Robert, and McCardle, William H. A History of Mississippi.
Jackson, Mississippi: R. H. Henry & Co., 1891. Pp. 140-41.
Personal inspection by Dawn Maddox, April 25, 1971.
Rowland, Eron. "Marking the Natchez Trace." Publications of the
Mississippi Historical Society, XI (1910), 355-56.
Sparks, W. H. The Memories of Fifty Years. Philadelphia:
Claxton, Remsen, & Haffelfinger, 1870. P. 151.
"Springfield" Subject File. Collections, Mississippi Department
of Archives and History, Jackson, Mississippi.
Telephone interviews with Mr. James H. Williams, Jr., St. Louis,
Missouri, July 20, 1971, and August 5, 1971.

UNITED STATES
DEPARTMENT OF THE INTERIOR
GEOLOGICAL SURVEY



U.S.G.S.
Fayette Quadrangle
1962
Scale: 1:62,500

CANNONBURG

JEFFERSON CO.
ADAMS CO.



31°45'
3513000m N
3512
3511
3510
3508
3507
3506
3505
3504
3503
3502
3501
3500
T. 9 N
T. 8 N
T. 8 N

101140
101130
101120
101110
101100
101090
101080
101070
101060
101050
101040
101030
101020
101010
101000

91°15' 666000m E 667 668 669 670 671 672 673 674 R. 1 W. R. 1 E 676

2747 III (NATCHEZ)
PINE RIDGE

Form 10-301
(July 1969)

UNITED STATES DEPARTMENT OF THE INTERIOR
NATIONAL PARK SERVICE


**NATIONAL REGISTER OF HISTORIC PLACES
PROPERTY MAP FORM**

(Type all entries - attach to or enclose with map)


STATE	
Mississippi	
COUNTY	
Jefferson	
FOR NPS USE ONLY	
ENTRY NUMBER	DATE
71-11-28-0013	11/23/71

SEE INSTRUCTIONS

1. NAME			
COMMON: Springfield Plantation			
AND/OR HISTORIC:			
2. LOCATION			
STREET AND NUMBER:			
Section 33, T 9N, R 1W (near the South Fork of Coles Creek)			
CITY OR TOWN:			
8 miles west of Fayette, Mississippi, via State Route 553			
STATE:	CODE	COUNTY:	CODE
Mississippi	28	Jefferson	063
3. MAP REFERENCE			
SOURCE:			
U.S.G.S. 15' Fayette Quadrangle			
SCALE: 1:62500			
DATE: 1962			
4. REQUIREMENTS			
TO BE INCLUDED ON ALL MAPS			
1. Property boundaries where required.			
2. North arrow.			
3. Latitude and longitude reference.			



SPRINGFIELD
Comprehensive Report
Floor Plan




SPRINGFIELD PLANTATION HOUSE
Jefferson County, Mississippi

Floor Plan - First Floor - 1790

A.E. La Salle
May 1, 1978


SPRINGFIELD
Comprehensive Report
Floor Plan



SPRINGFIELD PLANTATION HOUSE
Jefferson County - Mississippi

Floor Plan - First Floor - After 1800

A. E. La Salle
May 1, 1978




* NOT OPEN BUT VISABLE

OLD MARYLAND SETTLEMENT (CHURCH HILL) AREA


- SPRINGFIELD
- MT. LOCUST
- CHRIST EP. CHURCH
- WAGNER'S STORE
- * OAK GROVE
- * LEGONIA
- EMERALD MOUND
- OLD TRACE



SPRINGFIELD
REAR — 1791



UNITED STATES
DEPARTMENT OF THE INTERIOR
GEOLOGICAL SURVEY



SCALE 1:62500

LOCUST RIDGE

2747 III (MATCHES)

Form 10-301
(Dec. 1968)

UNITED STATES DEPARTMENT OF THE INTERIOR
NATIONAL PARK SERVICE

**NATIONAL REGISTER OF HISTORIC PLACES
PROPERTY MAP FORM**

(Type all entries - attach to or enclose with map)

STATE Mississippi	
COUNTY Jefferson	
FOR NPS USE ONLY	
ENTRY NUMBER	DATE

SEE INSTRUCTIONS

1. NAME			
COMMON: Springfield		AND/OR HISTORIC:	
2. LOCATION			
STREET AND NUMBER: Route 4, Box 166			
CITY OR TOWN: Natchez			
STATE: Mississippi	CODE 39120	COUNTY: Jefferson	CODE
3. MAP REFERENCE			
SOURCE: U.S.G.S. Map, Fayette Quadrangle, Miss.			
SCALE: 1:62500			
DATE: 1962			
4. REQUIREMENTS			
TO BE INCLUDED ON ALL MAPS			
1. Property boundaries where required.			
2. North arrow.			
3. Latitude and longitude reference.			