


United States Department of the Interior
National Park Service

44

National Register of Historic Places Registration Form

This form is for use in nominating or requesting determinations for individual properties and districts. See instructions in National Register Bulletin, *How to Complete the National Register of Historic Places Registration Form*. If any item does not apply to the property being documented, enter "N/A" for "not applicable." For functions, architectural classification, materials, and areas of significance, enter only categories and subcategories from the instructions.



1. Name of Property

Historic name: Alexandria Union Station

Other names/site number: VDHR No. 100-0124

Name of related multiple property listing:
N/A

(Enter "N/A" if property is not part of a multiple property listing)

2. Location

Street & number: 110 Callahan Drive

City or town: Alexandria State: VA County: Independent City

Not For Publication: Vicinity:

3. State/Federal Agency Certification

As the designated authority under the National Historic Preservation Act, as amended,

I hereby certify that this x nomination ___ request for determination of eligibility meets the documentation standards for registering properties in the National Register of Historic Places and meets the procedural and professional requirements set forth in 36 CFR Part 60.

In my opinion, the property x meets ___ does not meet the National Register Criteria. I recommend that this property be considered significant at the following level(s) of significance:

___ national ___ statewide x local

Applicable National Register Criteria:

x A ___ B x C ___ D

	<u>12/19/12</u>
Signature of certifying official/Title:	Date
<u>Virginia Department of Historic Resources</u>	
State or Federal agency/bureau or Tribal Government	

In my opinion, the property ___ meets ___ does not meet the National Register criteria.	
Signature of commenting official:	Date
Title :	State or Federal agency/bureau or Tribal Government

Alexandria Union Station
Name of Property

City of Alexandria, VA
County and State

4. National Park Service Certification

I hereby certify that this property is:

- entered in the National Register
- determined eligible for the National Register
- determined not eligible for the National Register
- removed from the National Register
- other (explain:)

Joe Edward H. Beall
Signature of the Keeper

2.27.13
Date of Action

5. Classification

Ownership of Property

(Check as many boxes as apply.)

- Private:
- Public – Local
- Public – State
- Public – Federal

Category of Property

(Check only one box.)

- Building(s)
- District
- Site
- Structure
- Object

Alexandria Union Station
Name of Property

City of Alexandria, VA
County and State

Number of Resources within Property

(Do not include previously listed resources in the count)

Contributing	Noncontributing	
<u>2</u>	<u>0</u>	buildings
<u>0</u>	<u>0</u>	sites
<u>0</u>	<u>0</u>	structures
<u>0</u>	<u>2</u>	objects
<u>2</u>	<u>2</u>	Total

Number of contributing resources previously listed in the National Register N/A

6. Function or Use

Historic Functions

(Enter categories from instructions.)

TRANSPORTATION/rail-related

Current Functions

(Enter categories from instructions.)

TRANSPORTATION/rail-related

Alexandria Union Station
Name of Property

City of Alexandria, VA
County and State

7. Description

Architectural Classification

(Enter categories from instructions.)

LATE 19TH AND 20TH CENTURY REVIVALS/ Colonial Revival

Materials: (enter categories from instructions.)

Principal exterior materials of the property: STONE/schist fieldstone; BRICK;
SYNTHETIC/composition shingles

Narrative Description

(Describe the historic and current physical appearance and condition of the property. Describe contributing and noncontributing resources if applicable. Begin with a **summary paragraph** that briefly describes the general characteristics of the property, such as its location, type, style, method of construction, setting, size, and significant features. Indicate whether the property has historic integrity.)

Summary Paragraph

The Alexandria Union Station at 110 Callahan Drive in Alexandria, Virginia was built in 1905. Currently it sits on 3.514703 acres. The railroad tracks are not included in this acreage since they are no longer part of the station property. Two buildings—a passenger depot and a baggage building—comprise the one-story Colonial Revival-style station. A glass-enclosed breezeway, built in 1997, connects the two buildings. Although the station is defined as a two building unit, it reads as a single building. The station is constructed of brick laid in a Flemish-bond pattern. The passenger depot, located to the north, measures 95 feet, 10 inches by 33 feet, 7 inches. The baggage building is 41 feet, 7 inches by 33 feet, 7 inches. Both are contributing buildings. At the passenger depot, the hipped roof is accented by dormer windows while eyebrow vents punctuate the roof of the baggage building. The brick chimney at the north end of the roof is decorated with a recessed arch and a granite keystone. A Tuscan columned loggia frames three sides of the passenger building. Semi-circular fanlights inside an elliptical fanlight have spider-web tracery and flanking windows that draw attention to the four doorways. Windows are distinguished with granite lintels, decorated with carved keystones, and are recessed within blind arches. The building is constructed of masonry load-bearing walls. The passenger depot has a partially exposed rusticated schist fieldstone foundation. The foundation extends to a fieldstone-faced tunnel leading to the northbound tracks. A veterans' memorial monument and a station identification marker are two non-contributing objects on the property. The station sits within a

Alexandria Union Station

Name of Property

City of Alexandria, VA

County and State

densely developed commercial area, adjacent to a 20th century residential area and at the intersection of three major in-town roads. The Rosemont National Register Historic District, the Alexandria National Register Historic District, and the George Washington Masonic National Memorial are near the station. As host to Amtrak and the Virginia Railway Express, the Alexandria Union Station is part of a multi-modal transportation center with the subway and bus systems located at the neighboring King Street Metro Station. The dense, urban, mixed-use Carlyle Development borders the station to the south. In 1989, this development replaced a major railroad switching yard. Due to restoration work in 1997, the building provides an excellent representation of the 1905 original station. The buildings are in excellent condition and only have had modest alterations since the original period of construction. The glass enclosure of the breezeway in 1997 was designed to clearly read as distinct from the historic features.

Narrative Description

Site

When approaching the station from Callahan Drive, a circular asphalt-paved drive leads to short-term parking in front of the station. The drive exits onto King Street. The long-term passenger and employee gravel parking lot is located in an undeveloped area at the station's south end.

Front landscape features include a circular traffic island created in 1997 with a flagpole in the center. A concrete, limestone and granite Veterans of Foreign Wars memorial monument dating from 1940 sits to the west of the flagpole. Materials for the monument came from a column shaft damaged during the construction of the George Washington National Masonic Memorial.¹ The inscription on the memorial reads: "Donated by Mrs. Florence Angelo Cannaday; Richmond, VA; Erected in memory of Alexandria War Dead; by Russell Mitchell, Post No. 609; Veterans of Foreign Wars and Citizens of Alexandria; November 11, 1940."

At the intersection of Callahan Drive and King Street, a carved granite and brick marker reads "Alexandria Union Station." A hedge-lined, semi-circular brick walkway separates the memorial from the station marker and connects the sidewalks bordering Callahan Drive and King Street.

The Veterans of Foreign Wars monument and the Alexandria Union Station marker are non-contributing objects to the property because they were added after the period of significance.

The simple landscape design is dominated by five mature trees north of the Veterans of Foreign Wars memorial and along the northwest part of the property bordering King Street. Shrubs border the southbound track to the station's north and south. Another band of small trees separates the parking lot from the sidewalk lining Callahan Drive. Today's landscaping contrasts with the formal landscape plan portrayed on a 1920s postcard. At that time the front lawn featured flowering plants surrounded by groomed hedges.

According to the blueprints, only one drive accessed the station to and from King Street. However, on a 1908 map of Rosemont, two drives connected to King Street and bordered a triangular green space. This plot of land appears formally landscaped with bushes and flowers in

Alexandria Union Station

City of Alexandria, VA

Name of Property

County and State

an early postcard of the station. The front property was originally more expansive until the Alexandria Washington Masonic Association purchased some of the station's land in the early 1920s. Callahan Drive, previously known as Station Drive, was relocated closer to the station when the Masonic Association acquired land from the station in the 1940s.²

Colonial Revival-style light posts are found in front of the station. These replaced the original scrolled shepherd's crook head light stands. Colonial Revival-style light sconces are attached to the terminal buildings on the trackside and on the south side of the baggage building. Contemporary box lighting hangs under the southbound and west loggias. In a 1940 photo, schoolhouse globe lighting appeared along the edge of the west loggia.

A concrete walk leads from the front of the train station to the parking area, down stairs accessing the northbound track or leads to a sidewalk in the direction of the King Street Metro Station. A simple black iron railing borders the walkway.

Exterior

Alexandria Union Station today looks much like it did when originally constructed. However by 1982, years of deferred maintenance and changes to the building's features altered the station's original condition. Citing poor building conditions related to age, water damage, and termite infestation, Amtrak and the Richmond, Fredericksburg & Potomac (RF&P) Railroad initiated exterior renovations in 1982.³ These included removal of the original slate roof and addition of a new composition shingle roof; removal of the north and west loggias and reconfiguration of the east loggia; elimination of the stair canopy and colonnade at the northbound platform (part of the original site); and, disposal of the wrought iron fencing between the tracks.⁴ The alterations to the building were largely reversed when the City of Alexandria led a 1997 restoration, funded through ISTEAs. Based on original blueprints, the restoration returned the station to its 1905 appearance and addressed modern accessibility requirements.

The buildings have load bearing masonry walls. A Flemish-bond brick pattern with dark grey headers and red brick stretchers cover the buildings' exteriors. The low water table has a molded cap. Projecting brick quoins form the corners. The passenger depot foundation is partially exposed due to the northeast downward slope of the site. A rusticated schist fieldstone forms the depot's foundation, the walls of the stairs, and the tunnel. Below the station, mechanical rooms are at the half basement level. A rusticated stone arch capped by a keystone surrounds the tunnel entrance. Painted brick forms the tunnel's interior. The tunnel passageway leads to the northbound tracks.

A distinguishing element of the station is the Tuscan columned loggia on the west, north and east sides of the building. The loggia is continuous along the north and west sides, also connecting to a loggia on the eastern track-side of the building. Vented aluminum plinths support Tuscan wood columns, originally constructed of pine. The north and west loggias have bead-board ceilings and stainless-steel, standing-seam roofs. The roofs were originally constructed of standing-seam tin. A matching, free-standing loggia stood on the northbound platform. This was removed in 1982 and was replaced by a new wood pavilion between the tracks (currently not part of the station property).

Alexandria Union Station
Name of Property

City of Alexandria, VA
County and State

A wrought iron railing surrounds the façade and the northern sides of the station. The railing continues along the northbound track.

The four entryways are prominent design features. Each centers around wooden double doors with a natural finish. Two doors are located on the front (west elevation.) The doors are aligned with two, trackside doors. Each door is flanked by 9/1 double-hung-sash wood windows with transoms and decorative lights. Above each door entry is a door-width transom. A semi-circular, arched fanlight placed within an elliptical fanlight, also the width of the door, rests above the transom. The fanlight is positioned within a spider-web, elliptical fanlight that spans the width of the door and the 9/1 double-hung-sash wood side windows. Concrete handicap ramps lead to the doors.

Ten 9/1 double-hung-sash wood windows are recessed within blind arches accented with impostes. Granite lintels with carved keystones accent the windows. Bracketed modillions are below the cornice of the passenger depot and baggage building. Three 9/1 double-hung-sash wood windows and two smaller nine-light windows are on the west elevation. Three 9/1 double-hung-sash wood windows are located on the trackside elevation of the terminal. Two 9/1 double-hung-sash wood windows are located at both the north and south ends of the terminal building. The blueprints indicate the location of a grated, hinged, coal window below the northernmost window on the trackside. A bay window added in 1929 projects from the ticket office on the trackside elevation of the terminal. At the baggage building, two 9/1 double-hung-sash wood windows are placed at the north and west sides while one 9/1 double-hung-sash wood window is located on both the south and west elevations.

The glass enclosure of the breezeway, an addition during the 1997 renovation, now connects the passenger depot building to the baggage building. Originally, the breezeway was not enclosed to accommodate the movement of baggage between the storage area and the station's driveway. A concrete handicap ramp leads to the breezeway entrance. In addition to serving baggage needs, the building houses the station's new handicap accessible bathrooms, which were originally located in the main terminal. A wood paneled door with a simple transom at the north elevation of the baggage building connects the bathrooms to the breezeway. This door replaces a sliding wood utility door. To the opposite side of the breezeway, another wood paneled door with a simple transom allows for egress at the south elevation of the depot. The door, replacing an original window, was added in 1997 to provide access to the handicapped bathrooms. Colonial Revival-style sconces, coordinating with interior chandeliers, are found on either side of these breezeway doors.

Utility doors, originally used for baggage, freight, and mail handling and storage, are found on the remaining three walls of the building. Two are positioned along the southbound track, two on the building's west elevation, and one on the front elevation. Two windows flank the door at the front. The southernmost overhead steel roller door along the tracks is the only one operational today. Wood, duplicating the ridges of the steel door, covers the remaining four doors. The original tin, bracketed canopies that once shielded the utility doors on the south and west sides

Alexandria Union Station

Name of Property

City of Alexandria, VA

County and State

have been removed. Rusticated granite corner guards frame the sides of each utility door. Flat granite lintels embellished with carved keystones mark the tops of the doors.

Tuscan pilasters frame the pedimented wooden dormers on the main terminal building. Three dormers face the front, three face the tracks, and a single dormer is at the southern end of the passenger depot section. Bracketed modillions are along the eaves of the dormers' pediments.

Four louvered wood eyebrow vents punctuate the hipped roof of the baggage building, one on each of the roof's sides. Originally, the roof was slate with a copper ridge roll but the slate shingles were replaced with black composition shingles in 1982.

A prominent brick chimney located at the north side of the passenger depot's hipped roof originally served the coal fired boiler in the basement. The boiler provided hot water to the building's radiators. It is accented with a recessed arch and a granite keystone. A Victorian-styled wrought iron rod braces the chimney.

Interior

The interior of the passenger depot includes two public waiting rooms. Originally, the depot was constructed with three waiting rooms. The waiting room at the south end contains schedule information, a public phone, and a baggage check window. This space was formally the Women's Waiting Room. A small, attached vending machine room was originally the White Women's Toilet. An office sits opposite the vending machine area. The current office previously housed the White Women's Waiting Room. The hallway that leads through a door to the breezeway between the vending machine room and the office was constructed in 1997. After the 1905 construction, the White Women's Waiting Room became the agent's office.

The northernmost space is the main waiting room. This served as the General Waiting Room according to blueprint documents. Oak settees, thought to be originals, furnish this waiting room. A raised, closed, brick fireplace marks the north end of the room. Sometime between 1905 and 1997, bathrooms and two closets were added on either side of the fireplace. During the 1997 reconstruction, these rooms were removed and the waiting room was restored to its original size. A three-windowed ticket booth connects both of the waiting rooms. Originally, a wall divided the Women's Waiting Room and the General Waiting Room at the ticket booth area.

Across from the ticket booth is an enclosed area of offices, one now housing a satellite office for the Alexandria Sheriff. This set of rooms was the original location for the Colored Women's and the Men's Bathrooms.

The flooring of both waiting rooms has black and white ceramic tiling with a Greek key border, added in 1929. Original blueprints note that maple wood flooring covered the passenger depot at the time of construction. The bottom third of the walls is white glazed brick wainscoting culminating in a moulded enamel brick course. The upper two-thirds is cream painted brick. A decorative moulded brick cornice caps the walls. The rooms open to a vaulted and varnished wood ceiling above the corniced walls. The ceiling's wood scissor trusses are a major

Alexandria Union Station

City of Alexandria, VA

Name of Property

County and State

architectural feature. Light floods the passenger depot space through the seven dormer windows. Neo-classical chandeliers hang from the wood ceiling.

Radiators heated all rooms according to the station's blueprints. The original radiators are still in use today.

The baggage building consists of four rooms. Men's and women's bathrooms are accessed through the breezeway. Two storage rooms are located at the south side of the baggage building and are accessible through utility doors. Originally, the northern half of the baggage building, where bathrooms are currently located, was designed as a baggage room. The southern side was used for a mailroom and an express room. Room configuration and room use were changed sometime between 1905 and 1997. During this time the space was divided into four rooms. Three rooms were used for storage. Maintenance equipment was stored in the largest room on the east side.

Evaluation of Integrity

The integrity of Alexandria Union Station is confirmed by consistency in location, design, setting, materials, workmanship, feeling, and association. Overall, the station evokes an image identical to its 1905 original appearance. In addition, integrity is strengthened by the station's continued service as a rail depot.

Due to the 1997 restoration, the station has retained the same design, materials, and workmanship to support integrity. The enclosed glassed breezeway accounts for the most prominent alteration to the building's exterior. The aesthetics are not affected because of this change. The use of glass to enclose the breezeway offers the same view to the tracks as designed by the original plan. The rhythm of the building's façade is uninterrupted.

The interior space layout remains much the same as originally noted on the 1905 blueprints. Room uses have changed. With the court-ordered end to racial segregation, separations for White and Colored Bathrooms were removed. That influenced the relocation of bathroom locations to the baggage building during the 1997 restoration. Additionally, the changing perspectives on gender equality accounted for the separation of the Men's and Women's Waiting rooms. Today both waiting rooms in the passenger depot are open to all.

The change in setting as it relates to density has strengthened the station's position as a regional transportation center. The King Street Metro Station adds to the area's transportation theme. The mixed-use Carlyle Development took the place of a former commercial and residential neighborhood that also relied on Alexandria Union Station for transportation. When the station opened in a sparsely developed location at the confluence of major, established transportation routes, the area was predisposed to future economic expansion. The development that resulted over the years has enhanced the station's prominence as transportation hub, just as it was originally intended.

The feeling of the station continues to represent a time period in United States history when passenger travel by rail was commonplace. Today at the Alexandria Union Station, a traveler

Alexandria Union Station
Name of Property

City of Alexandria, VA
County and State

follows the same steps (excluding the racial and gender barriers) a rail passenger at a small city station encountered between 1905 and 1932. The design for efficiency and safety still applies.

The association with history continues as the station exemplifies a design relationship with other Pennsylvania Railroad (PRR) terminals built between 1903 and 1914 in the mid-Atlantic region. The continuity of location, design, setting, materials, workmanship, and feeling firmly establish the station's association with its historical past.

Alexandria Union Station
Name of Property

City of Alexandria, VA
County and State

8. Statement of Significance

Applicable National Register Criteria

(Mark "x" in one or more boxes for the criteria qualifying the property for National Register listing.)

- A. Property is associated with events that have made a significant contribution to the broad patterns of our history.
- B. Property is associated with the lives of persons significant in our past.
- C. Property embodies the distinctive characteristics of a type, period, or method of construction or represents the work of a master, or possesses high artistic values, or represents a significant and distinguishable entity whose components lack individual distinction.
- D. Property has yielded, or is likely to yield, information important in prehistory or history.

Criteria Considerations

(Mark "x" in all the boxes that apply.)

- A. Owned by a religious institution or used for religious purposes
- B. Removed from its original location
- C. A birthplace or grave
- D. A cemetery
- E. A reconstructed building, object, or structure
- F. A commemorative property
- G. Less than 50 years old or achieving significance within the past 50 years

Alexandria Union Station
Name of Property

City of Alexandria, VA
County and State

Areas of Significance

(Enter categories from instructions.)

TRANSPORTATION

ARCHITECTURE

Period of Significance

1905-1932

Significant Dates

N/A

Significant Person

(Complete only if Criterion B is marked above.)

N/A

Cultural Affiliation

N/A

Architect/Builder

Office of the Chief Engineer,
Pennsylvania Railroad, Philadelphia, PA

Alexandria Union Station
Name of Property

City of Alexandria, VA
County and State

Statement of Significance Summary Paragraph (Provide a summary paragraph that includes level of significance, applicable criteria, justification for the period of significance, and any applicable criteria considerations.)

The Alexandria Union Station, built in 1905, located in the City of Alexandria, Virginia, provides an intact representation of regional railroad planning and mid-Atlantic terminal design in the early 20th century. Associated with important regional and local transportation trends, the station meets Criterion A requirements. The City Beautiful movement, introduced in nearby Washington, D.C., in the early 1900s, influenced the station's development as a "union"⁵ station through the consolidation of rail lines in Alexandria. This marked a shift from the construction of utilitarian rail stations to architecturally significant stations that were planned as municipal gateways and provided efficient and safe rail travel. The station's ties to the Washington, D.C.'s City Beautiful Movement denote the Transportation significance of the property under Criterion A. The building's origins reflect the broader regional plan to reorder the railroad transportation corridor around Washington, D.C., as initiated by the McMillan Commission supported proposals. First applied in Washington, D.C., the City Beautiful philosophy became a national trend adopted by city planners in numerous American cities during the early 20th century. The Alexandria Union Station is the only local representation of this once popular national urban planning philosophy. Under Criterion C, Architecture is addressed since the building is an exceptional example of a Colonial Revival-style architectural design unique to Alexandria. In a city known for its late eighteenth and early nineteenth century Colonial and Federal architecture, the Alexandria Union Station is distinguished by its Colonial-Revival form and interpretive application of Federal style details. The Pennsylvania Railroad's design template for small city train stations constructed between 1903-1914 contributed to the distinct style. The rectangular and generally symmetrical profile along with columned loggias, hipped roof with dormers, and occasional paired windows mark the Colonial Revival aspects of the station. A liberal use of Federal style detailing is displayed around the main doors and the windows. The Flemish-bond brick pattern is not found elsewhere in the city. Additionally, the station was the only Colonial Revival-style public building constructed during that era in Alexandria. The station is the only remaining building representing the city's extensive railroad history. The period of significance begins with the station's construction in 1905 and concludes in 1932, when the George Washington Memorial Highway opening steered local passenger travel away from trains and toward the use of personal automobiles. Also in 1932 the Washington-Virginia Railway commuter train, providing transportation connections to the station, ceased operations. The current contextual setting for the station was established by 1932 with the construction of the George Washington Masonic National Memorial and the Rosemont neighborhood.

Narrative Statement of Significance (Provide at least **one** paragraph for each area of significance.)

Historical Background
City Beautiful Movement

Alexandria Union Station

City of Alexandria, VA
County and State

Name of Property

The construction of the Alexandria Union Station in Alexandria, Virginia, stemmed from changes in the Washington, D.C., railroad terminal and track structure as influenced by the City Beautiful movement in the early twentieth century. The movement's aim was to improve social and economic conditions in cities by creating beautiful civic spaces and buildings. In the early 1900s, interest in reconstructing a beautiful federal city emerged based on Pierre L'Enfant's original design for Washington, D.C. These plans not only impacted the District of Columbia's existing railroad infrastructure but also railroad operations throughout the region.

To commemorate the hundredth anniversary of L'Enfant's *Grand Plan*, the American Institute of Architects held its annual convention in Washington, D.C. Papers at the conference addressed L'Enfant's plan and its application to improve the quality of the National Mall. By 1900, railroad lines crossed the mall and a Pennsylvania Railroad station stood on one corner, compromising the vision of the L'Enfant Plan.⁶ Additionally, citizen safety at railroad crossings was a concern with numerous tracks intersecting pedestrian ways.⁷

Based on the design proposals presented at the AIA convention, Senator James McMillan of Michigan established the McMillan Commission in 1901 to restore the National Mall according to L'Enfant's Plan. The McMillan Commission was a subcommittee of the senator's Senate Committee on the District of Columbia. Daniel H. Burnham, Frederick Law Olmsted, Jr., Charles F. McKim, and Augustus Saint-Gaudens served on the commission along with McMillan's secretary and architectural advisor, Charles Moore.⁸

Commission members reinterpreted L'Enfant's plan by incorporating features from European architectural and landscape design. Their goals were to restore the National Mall; plan for the location of future public buildings, memorials, and monuments; and reorganize and connect the city's parks. One step toward accomplishing their objectives was to remove and relocate the railroad tracks and terminal from the National Mall. Daniel Burnham convinced Alexander Cassatt, Pennsylvania Railroad president, to move his company's rail facilities from the Mall. This entailed rerouting the tracks through a tunnel under the Mall to maintain rail connections with southern routes. It also called for the construction of a new terminal to the north of the Mall. In 1902, Congress approved construction of the new station and tracks, a project influenced by, but not included in, the McMillan Plan.⁹ Burnham began to design Washington, D.C.'s Union Station in 1903. The monumental station was opened in 1907 and completed in 1908. It was described as the "finest example of the City Beautiful movement, which promised briefly to make the American city something worth looking at."¹⁰ With the tracks and station removed, the Mall was clear for restoration. Implementation of the McMillan Plan commenced in 1921 when Congress formed the National Capital Park and Planning Commission.¹¹

Alexandria's Rail System

On a smaller scale, Alexandria's urban landscape experienced similar disruptions related to railroads. By 1900, four separate rail lines, terminating at five different terminals ran throughout the densely built center city. Travelers and businesses found it inefficient at times to coordinate personal and freight connections between the terminals at North Fairfax, North St. Asaph, North Henry, South Henry, and South Patrick streets. Congestion and dangerous conditions resulted on

Alexandria Union Station

City of Alexandria, VA

Name of Property

County and State

city streets with pedestrians and horse drawn vehicles competing with railroads for space along roads and intersections.

When its position as a major seaport faded, Alexandria turned to the development of five railroad projects in the late 1840s to regain its economic footing.¹² The Orange and Alexandria Railroad was the first successful line established in 1851. The railroad built Alexandria's two remaining railway structures. Hoofs Run Bridge (DHR File #100-0149) was constructed in the West End in 1856 and expanded in 1885-1895. It was listed in the Virginia Landmarks Register and the National Register of Historic Places in 2002 and 2003, respectively. Wilkes Street Tunnel (DHR File No. 100-0121) from 1856 is found within the Alexandria Historic District between Royal and Lee Streets. The historic district was listed in the National Register of Historic Places and declared a National Historic Landmark in 1966; the Virginia Landmarks Register designation occurred in 1968. The tunnel connected the Potomac River waterfront and its industries in Alexandria with Gordonsville, Virginia. Between 1900 and 1905, the Baltimore and Ohio, the Washington and Southern, the Southern, and the Pennsylvania Railroads traveled the Alexandria rails. Over the years, the names and ownership of these rail lines changed through eventual mergers and acquisitions.

The Richmond, Fredericksburg & Potomac Railroad (RF&P) and the Louisville and Nashville were two well-managed rail lines in the South during the post-Civil War era. At that time, the Southern railroad companies lacked the leadership of their northern peers to build a comprehensive and efficient rail transportation network. As exemplified in Alexandria, local communities wanted to maintain the independence of their lines and avoided mergers, resulting in short, fragmented routes. The RF&P linked northeastern railroads north of Washington, D.C., to a number of routes travelling south beyond Richmond.¹³

The reorganization of railroad lines and terminals in Washington, D.C., subsequently led to railroad changes in Alexandria. The Washington Southern Railway was an Alexandria passenger and freight railroad that connected a number of southern short lines with Washington, D.C. Washington Southern Railway was formed in 1890 through a series of mergers and acquisitions of various Alexandria rail lines beginning in 1854. Until 1901, it was a subsidiary of the Pennsylvania Railroad. Washington Southern then merged with the RF&P. As part of the RF&P, Washington Southern maintained its name and separate accounts.¹⁴

As plans to build Washington's Union Station emerged, six railroad companies established the Richmond-Washington Company in 1901 to coordinate and improve freight and passenger rail connections between Richmond and Washington. These rail companies were the Pennsylvania Railroad, the Atlantic Coast Line Railroad, the Southern Railway, the Chesapeake and Ohio Railway, the Seaboard Air Line Railway, and the Baltimore and Ohio Railroad. The Richmond-Washington Company was responsible for relocating the freight yards from Washington, D.C., another effort to beautify and restore the federal city's image. The District of Columbia's freight yards relocated to Potomac Yards, outside Alexandria's northern city limits. The 450-acre freight facility, considered at the time to be the largest U.S. rail freight classification yard, opened on August 1, 1906.¹⁵ To reduce track congestion and improve transportation efficiency, the Richmond-Washington Company planned for double tracking the Washington Southern

Alexandria Union Station

City of Alexandria, VA
County and State

Name of Property

Railroad.¹⁶ Double tracking would alleviate traffic congestion generated by Potomac Yards and the District of Columbia's Union Station. By 1907, the entire length of double tracking was completed, linking Quantico to the south of Alexandria with the Long Bridge that spanned the Potomac River crossing into Washington, D.C.¹⁷ The new double tracks moved outside the Alexandria central city. Eventually the inner city tracks of the Washington Southern Railroad became obsolete in later years.

The creation of Alexandria Union Station was the continuation of the Richmond-Washington Company's efforts to consolidate all rail traffic along efficient tracking, eliminating the need for multiple inner city tracks and stations. The Pennsylvania Railroad's Office of the Chief Engineer in Philadelphia developed the plans for the new passenger station.

As a result of the Potomac Yards and Alexandria Union Station plans, increases in real estate values and population were reported in the *Washington Post* on August 28, 1904. The newspaper reported "that fully 100 families who are now living in hotels, boarding houses, tenement houses, and in Washington are clamoring for houses of moderate size and with modern improvements." Real estate prices rose up to 100% around the union station site.¹⁸

In preparation for station and track construction, contractors Reiter, Curtis & Hill of Philadelphia built "temporary offices, stables, tool houses, and bunk houses ... about on the sight (sic) of the proposed new union depot."¹⁹ They cleared structural obstructions along the track right of way westward on Duke Street. To those not following the day-to-day railway progress, the new rail-dominated topography appeared unrecognizable.²⁰

The "modern station in every particular" opened on September 15, 1905.²¹ It stood outside Alexandria's western city limits, one and one-quarter miles from City Hall. The station, costing \$62,020.55, and its accompanying \$25,086.11 freight facility opened at the same time east of the tracks.²² The Washington Southern, the Southern Railway, and the Chesapeake and Ohio Railway operated through the new station. At the time of its construction, some Alexandrians were unhappy with the station's location, believing it to be "out in the country", but development soon followed.²³

The opening of the Alexandria Union Station contributed to westward commercial expansion in the state and nationally registered Alexandria Historic District along King Street.²⁴ Through history, King Street functioned as the primary commercial center for the city of Alexandria. The station received credit, along with the Washington-Virginia Railway's streetcar, for the construction of Rosemont. Construction began on the early-twentieth century middle-class suburb of Craftsman bungalows and Colonial Revival homes in 1908 and ended in 1940. The majority of development occurred by 1932 and Rosemont Historic District (DHR File #100-0137) was placed in the Virginia Landmarks Register and the National Register of Historic Places in 1991 and 1992, respectively. The neighborhood remains largely unchanged to this day.²⁵

The Alexandria Union Station set the scene for the first Virginia visit of Woodrow Wilson as President-elect on December 28, 1912. A crowd of nearly one thousand raced to the last train car

Alexandria Union Station

Name of Property

City of Alexandria, VA

County and State

and greeted Wilson with three cheers as the bells of city hall and the fire stations rang in his honor. Alexandria's mayor cancelled a celebratory bonfire near the station due to dangers associated with the day's high winds.²⁶

Alexandria annexed the train station area and surrounding suburbs in 1915. When Washington Southern merged with the Richmond, Fredericksburg & Potomac Railroad in 1920, the latter took ownership of the station and the tracks.²⁷ Due to its link with Washington's Union Station where northern passenger routes stopped before travelling south, the slogan for the RF&P was "Linking North with South."²⁸

To augment passenger travel, the Southern Railway offered the "Mystery Special" out of Alexandria Union Station on June 5, 1932. Five hundred passengers boarded the train on a three-hour ride to an undisclosed destination. Within minutes of the tour's end, leaflets announced the end of the line to be Fry's Springs near Charlottesville, Virginia. Passengers were met with sounds of an orchestra and the aroma of a Southern barbecue.²⁹

The Washington-Virginia Railway ceased operations in 1932 as a result of the opening of the George Washington Memorial Highway, connecting Washington, D.C., to Mount Vernon through Alexandria. Preference for the automobile diminished the popularity of the streetcar and the railroad as commuter options.

In 1971, Amtrak, the National Railroad Passenger Corporation, took over the passenger routes of the Chesapeake & Ohio, the Southern, and the RF&P railroads that ran through Alexandria Union Station. At that time, Amtrak began to lease the station from the RF&P.³⁰

By 1975, Amtrak reported that the physical condition of the station had deteriorated due to neglect. The rail line was reluctant to finance renovations due to uncertain lease terms with the RF&P Corporation. Consequently, Amtrak demolished building features in disrepair and altered others in 1982.³¹

The CSX Corporation, formed in 1980 to acquire and merge rail lines, took ownership of the RF&P in 1991.³² CSX divested of its real estate holdings and established the RF&P Corporation to manage and develop the Alexandria Union Station real estate. CSX continued to control the tracks. Amtrak maintained its lease agreement for the station and the southbound platform. Passenger train service expanded at the station when the Virginia Railway Express (VRE), a commuter rail line connecting Virginia cities with Washington, D.C., leased the northbound and southbound platforms around 1992.³³

Through Alexandria city planning efforts, restoration improvements in 1997 returned the station to its original design and condition.³⁴ After the station improvements, Atlantic Commonwealth Properties, the real estate division of RF&P gave the train station property to the City of Alexandria, the present owner.³⁵ Currently, the Alexandria Union Station operates within a multi-modal transportation center where Amtrak and commuter lines link to subway and bus systems at the adjacent King Street Metro Station.

Alexandria Union Station
Name of Property

City of Alexandria, VA
County and State

Historic Context: Place

The station stands in a densely built residential, commercial, and public transit area. Callahan Drive sits on a diagonal between King and Duke Streets, two heavily trafficked thoroughfares leading to major highways connecting with outlying suburbs and Washington, D.C.

The state and nationally registered Alexandria Historic District, incorporating commercial and residential buildings from the 18th–20th century, is located to the east of the station. To the north, the state and nationally registered Rosemont Historic District is the city's first streetcar suburb featuring homes constructed from 1908 to 1940. The 1922-1932 constructed George Washington Masonic National Memorial, to the west, stands on the highest point in the city at 333 feet tall.

An iron, below-grade railroad bridge spans the walkway from Alexandria Union Station and King Street. The Richmond-Washington Line built the through plate girder-type bridge with a concrete abutment and steel-pier substructure in 1904. The floor of the bridge was raised in 1965. It has two spans, carries four tracks and is 79 feet in length.³⁶ Trains travelling to and from the train station pass on the bridge now owned by the CSX Corporation.

Aboveground tracks, a platform, and the parking lot for the 1983 King Street Metro Station run parallel to Union Station. Being in close proximity, the two stations form a multi-modal transportation hub with connections to subways, buses, and the Alexandria trolley.

The 230-acre mixed-use Carlyle Development dominates the southeastern view. Construction first began in the late 1990s and continues today. The dense urban commercial, governmental, and residential center encourages the use of public transportation offered by the King Street Metro and the Alexandria Union Station.

At the time of construction, the station sat isolated, surrounded by mostly undeveloped land. What is today's Alexandria Historic District ended at West Street, about four blocks to the east. Open land marked the future Rosemont neighborhood. A golf course, a school, and two parks were perched on Shuter's Hill, currently the site of the George Washington Masonic National Memorial.³⁷ To the west of the golf course, a reservoir supplied Alexandria's water. A one-story, brick Railway Express Building used for package distribution stood to the south of the baggage building between 1943 and 1982.³⁸

An I.C.C. Valuation account book from 1917 indicates that a bunkhouse, a section tool house, and a four-man dwelling were built on the station property in the late 1900s. Exact locations are unknown.³⁹

A freight facility, also constructed in 1905, serviced the needs of the Alexandria Union Station. The Metro platform, constructed in the 1980s, now stands in its place. Due to frequent flooding of Hoofs Run, few buildings stood in the current parking lot area of the King Street Metro. Eventually underground conduits diverted Hoofs Run in the 1920s.⁴⁰ Automobile dealers and repair shops located at the edges of this lowland. A steam pump manufacturer conducted business nearby. To the manufacturer's north, a baseball field provided recreation in the 1920s.

Alexandria Union Station
Name of Property

City of Alexandria, VA
County and State

In 1922, construction began on the landmark George Washington Masonic National Memorial. Designed by Helmle and Corbett, the tall, neoclassical monument provides a commanding architectural presence and is visible from many regional vantage points. To house the Masonic belongings of George Washington, the National Masonic Lodge commissioned the building. The exterior achieved its final form in 1932. Today, it also serves as the group's national headquarters.

King and Duke Streets, bordering Alexandria Union Station, figured as major transportation routes throughout Alexandria's history. Due to its position on the Potomac River, Alexandria thrived as a port and trade city beginning in 1731 with its first settlement at the base of what is now Oronoco Street. Early settlers exported regionally produced tobacco brought to the port on these roads. From 1749 to 1798, the seaport thrived by exporting wheat, flour, and tobacco produced by inland farms. The early roads served commercial enterprises by delivering products to markets.⁴¹

Cattle from the Shenandoah Valley were driven down the Little River Turnpike (Duke Street) to West End slaughterhouses. Additionally, wheat was transported from the interior to mills.⁴² The site for Alexandria Union Station may have been chosen in part because of its relationship to these well-travelled and established transportation routes.

*Archaeological History*⁴³

The Alexandria Union Station site holds the potential to provide archeological information on Alexandria's pre-history and history. At the base of Shuter's Hill, the location of the George Washington Masonic National Memorial, evidence of Native American settlements has been discovered at the summit's peak as well as along the creek beds draining along the hillside. The station sits on a plain between Shuter's Hill, 190 feet above King Street, and Hoofs Run, sited below. Native American patterns indicate commonly placed settlements near water and upland environments that provided a variety of resources.

From the late-eighteenth century to the late-nineteenth centuries, Shuter's Hill was privately owned, used for residential, agricultural and pastoral purposes. The exception was during the Civil War, when the Union Army confiscated Shuter's Hill and placed a fort at this strategic point. A Civil War photograph reveals a soldiers' encampment near the current location of the train station.

Although construction of Alexandria Union Station and the King Street Metro Station may have disturbed artifacts relating to pre-history or Civil War history, the potential exists for the discovery of archaeological resources at the site.

Historic Context: Property Type and Architecture

The architecture of the Alexandria Union Station, constructed in 1905, clearly represents the general philosophy of train station design during the late-nineteenth and early-twentieth centuries. Its construction date places the station in the midst of the "Golden Age" of passenger

Alexandria Union Station

Name of Property

City of Alexandria, VA

County and State

travel that lasted until the Great Depression. Between the 1880s and 1910, passenger train route miles grew from 93,000 to 240,000.⁴⁴ To address the increased number of passengers, railway designers built new stations that followed proven guidelines for efficiency and safety. In Alexandria, the Pennsylvania Railroad applied these industry defined plans to the station's design as well as to other depots in the mid-Atlantic and Virginia between 1903 and 1914. These stations shared a Colonial Revival design that varied in the intricacy of architectural detailing and building size based on city or town size and level of rail activity. In Alexandria Union Station's case, the era's design beliefs extended to incorporating landscape improvements into the building's maintenance plans.

The overall form of Alexandria Union Station represented a mid-point in architectural thinking between the perpendicular silhouettes of the decorative Victorian stations and the horizontal outlines of the non-ornamented Modernist terminals. In *The Railroad Station: An Architectural History*, author Carroll Meeks explains this stage of station design as characterized by the symmetrical form, horizontal massing, classical architectural detail, restrained cornices, lowered rooflines, and heavy entablatures. If decorative features were removed, Meeks states that the modernist image would emerge.⁴⁵ Alexandria Union Station embodies architectural elements characteristic to the transitional era of train station design. It is symmetrical and horizontal in form. Colonial Revival detailing, a style common in the early 20th century, is evident.

Blueprints for Alexandria Union Station are stamped "Office of the Chief Engineer, Pennsylvania Railroad, Philadelphia, PA."⁴⁶ With no specific name attributed to the design, it is assumed that an engineer or a group within the office developed the plans. A Pennsylvania Railroad Technical & Historical Society representative believes William H. Brown, a PRR Chief Engineer, was the station's designer. During his career with the PRR, Brown was known for the construction of railroad bridges and tunnels.⁴⁷ Another theory is that a PRR Chief Engineer, Caspar Wistar Haines, designed Alexandria Union Station. A Richmond, Fredericksburg, and Potomac Historical Society historian concludes that Haines consulted with PRR civil engineers, Walter H. Washabaugh and Charles Edgar Dare, who were also working for Washington Southern in 1905 as they built the nearby Potomac Yards freight yard.⁴⁸

The PRR-designed station at Chester, Pennsylvania, built in 1903, may have served as a blueprint for Alexandria Union Station. Both share very similar architectural details. The Chester, Pennsylvania, station is also constructed with a Flemish-bond brick pattern, includes a wrap around loggia supported by Tuscan pillars, and bears the distinctive chimney with a recessed arch and keystone accent. Windows with granite lintels are set within blind arches and decorated with carved keystones. The hip roof features identical dormer windows and a cornice decorated with block modillions.

Matching architectural features are found at other PRR designed stations in the region, constructed between 1903 and 1914. Because of this, it is assumed the same engineers employed in the PRR's Engineering Department during those years were responsible for designing the railway's similarly styled stations. In addition to Chester, other PRR stations sharing design features with Alexandria Union Station are located at New Brunswick, New Jersey (1903), Duncannon, Pennsylvania (c. 1903), Perryville, Maryland (1905), Irwin, Pennsylvania (c. 1910),

Alexandria Union Station

City of Alexandria, VA

Name of Property

County and State

Fredericksburg, Virginia (1910), Northumberland, Pennsylvania (1910), and Salisbury, Maryland (1913-1914). They are all brick and each features a hip roof with dormer windows and block modillioned cornices. New Brunswick, Irwin, and Duncannon stations, like Chester, share the same pedimented dormer window pattern with the Alexandria station—two single windowed dormers flank a double-windowed dormer on the long access of the roof. Tuscan pilasters frame the dormers. A single windowed dormer is at the opposite ends of the Chester, Irwin, and New Brunswick stations while the Duncannon station features eyebrow windows (replicas of the eyebrow vents on the Alexandria station's baggage building). Additionally, the same decorative windows exist at these stations. Window features, like those found in Alexandria, are part of the Perryville station. Brick quoins decorate all the stations but the smallest stations at Duncannon and Irwin.

Railway companies used standard designs for stations as a common practice, especially in the American West. Standard styles saved money by reducing design and building costs. The practice reduced competition between towns for the “biggest and best” station since the size of station was predetermined based on a town's population. Stock styles also created a branded image for the railroad. A particular style or unique paint scheme served as a “company trademark” for passengers and rail employees.⁴⁹

Commenting on standard designs, Walter Gilman Berg, Civil Engineer and Principal Assistant Engineer for the Lehigh Valley Railroad, recommended that rail station designers vary their plans by altering details so stations did not appear redundant along the rail landscape.⁵⁰ Although the PRR's stations explored here share architectural features, they are not duplicative. Their signature details—brick structures with hipped roofs broken by dormer windows and windows framed with lintels and accented by carved keystones—implicitly communicate a rail company connection. Designs vary by size, color of brick, and level of architectural detailing, giving each station its own identity.

In addition to the standardization of architectural detailing common to the era's passenger train stations, the overall layout of stations became systemized to ensure ultimate business efficiency. In *Metropolitan Corridor: Railroads and the American Scene* by John R. Stilgoe and *Buildings and Structures of American Railroad: A Reference Book for Railroad Managers, Superintendents, Master Mechanics, Engineers, Architects, and Students* by Walter Gilman Berg, the authors outline defined schemes characteristic of different sized railroad stations. The level of train activity and the size of town or city determined the overall station plan. Country stations servicing few passengers and minimal freight were the smallest. They were one story tall, and often employed at most two workers. Baggage processing and claims tended to be found at an adjoining building location for all but the smallest stations. One waiting room accommodated passengers.

Stations providing rail transportation for towns or small cities were also one story. Separate waiting rooms were furnished for men, women, and in the south, African Americans. Still, one to two railway workers could handle the operations at this train station size.

Alexandria Union Station

Name of Property

City of Alexandria, VA

County and State

At locations in medium-sized cities with an increased level of train activity handled by more than two rail employees, two-story buildings were constructed. The second floor contained offices for railway workers. On the first floor, space was dedicated to a restaurant or café.

In major cities and transportation hubs, large terminals opened to a general waiting room of grand scale and elaborate ornament. In *The Railroad Station: An Architectural History*, author Carroll Meeks labels the era of “megalomania” for large city train station design between the years of 1890 and 1914.⁵¹ Station scale had dramatically increased as passenger service boomed. Multiple waiting rooms for gentlemen, ladies, smokers, readers, and emigrants were included in plans. During segregation in the South, separate waiting rooms for African Americans were designated. The stations were multi-storied and provided shoe shines, book stalls, barber shops, coat rooms, restaurants, physician’s rooms, and telegraph, telephone, and messenger services. The vast number of rail and station employees servicing the facility required space for offices, worker bathrooms, lunch rooms, and sleeping quarters. Hotels were attached to stations at some locations.⁵² Well-known architects were appointed to design the grand stations that served as decorated and sophisticated gateways to large cities. PRR stations of this category include Pennsylvania Station in New York City (1906-1910) by McKim, Mead, and White, Washington, D.C.’s Union Station (1903-1907) by Daniel H. Burnham, and the Philadelphia Broad Street Station (1892-1893) by Frank Furness.

The small- to medium-sized brick Colonial Revival-style train stations designed by the PRR illustrate the different characteristics associated with building size. The depots at Duncannon and Irwin represent styles for country stations. Both are one-story structures with no auxiliary baggage buildings. Judging by the size of the buildings from photographs, it is likely that one waiting room serviced the stations. Comparing the size and simple ornamentation of these two stations with Alexandria Union Station, it is clear that Alexandria is emblematic of the next largest tier of stations; one found in a small city. As noted on the PRR Chief Engineer’s blueprints for Alexandria’s one-story rail facility, a separate baggage building was attached to the station by a covered passageway. Three separate waiting rooms accommodated waiting passengers. The New Brunswick station is similar in size to the Alexandria station but is not as ornate.

Pennsylvania Railroad stations at Chester, Perryville, Fredericksburg, Northumberland, and Salisbury represent stations serving mid-sized cities. All are two stories. The architectural detailing is more ornate than the country station examples but closely matches the level of craftsmanship and decoration found at the Alexandria station. This could indicate that Alexandria Union Station did not process the passenger and freight levels of its larger neighboring cities but was considered a relatively important station location due to its level of architectural detailing. Because of its positions as the “Gateway to the South,”⁵³ and as a union station, possibly PRR builders believed the design should depict a more refined style than those of similar size.

Despite the size variances, all stations were planned for efficiency. The movement and processing of people, baggage, freight, vehicles, and trains according to strict time guidelines required a building layout that maximized safety, comfort, and employee effectiveness.⁵⁴ The

Alexandria Union Station

Name of Property

City of Alexandria, VA

County and State

activities that universally occurred at each depot location determined the comprehensive form. When railroad station builders discovered the design formula that worked, they rarely deviated from the plan.⁵⁵ With the exception of the largest city terminals, the building prototype followed standard layout guidelines.

Stations were long and rectangular, positioned parallel to the tracks. Side stations, as these were known, offered unsafe access to tracks on the far side of the building since passengers had to cross tracks to reach their trains.⁵⁶ In Alexandria, dangerous track crossing was eliminated by the construction of the tunnel on the north side of the station that crossed under the southbound tracks and emerged at the northbound platform.

A bay window protruded from the stations on the trackside of the buildings. The function of the bay window was to provide the agent with visual access to trains on the tracks. There they could signal trains and telegraph the rail line's progress while finishing paperwork.⁵⁷

In addition to the station agent's attention directed outside the station, they simultaneously addressed the needs inside the facility. They sold tickets, processed baggage and freight, offered travel advice, accommodated those using the telegraph, and monitored the behavior of loiterers or unruly passengers. On the interior, the ticket booth had windows that opened to the waiting room. If there were more than one waiting room, ticket windows were positioned on either side of the agent booth, facing both rooms. Bathrooms were located opposite the ticket office so rail agents could keep an eye on potentially dangerous or objectionable activities occurring around these areas.⁵⁸

Managing the flow of arriving and departing travelers and those meeting passengers influenced aspects of station design. Waiting rooms were intended for passengers planning to depart from the station or those meeting passengers. Doors to waiting rooms lined up with the street side of the station and the train platforms. With this layout, those entering the station could walk directly to the ticket window, purchase a ticket, drop off baggage, and then proceed straight through the trackside door to the train. Benches in waiting rooms lined up to create aisles to foster a smooth pedestrian flow through the station.⁵⁹ Travelers arriving at the locale were directed on walkways around stations so congestion would not result at the station's doors with those heading to departing trains. When picking up baggage after arrival, travelers were directed to the platform at the adjoining baggage building separate from the main station (although not typical at country stations where baggage was picked up in the terminal.) After baggage was retrieved, those leaving the station premises were led through the covered passageway that adjoined the main building with the baggage building to the street side. Again, arriving passengers were routed away from those departing the station. Doors from the baggage room also opened to the street side where luggage could be delivered directly to vehicles waiting at the curb.⁶⁰ Another accommodation to prevent congestion was a provision for large covered platforms that included seating. With this detail, stations with small waiting rooms could support the needs of more travelers and diminish the potential crowding inside the station.⁶¹ At Alexandria Union Station, the blueprints called for long expanses of covered platform around all sides of the building and along the northbound tracks opposite the station. Settees are noted in these outdoor waiting areas.

Alexandria Union Station

Name of Property

City of Alexandria, VA

County and State

The standard station plans addressing building layout, station agents' duties, passenger flow, and baggage handling were all applied to the Alexandria Union Station and extended to designs for the waiting rooms. Three separate waiting rooms—the General Waiting Room, the Women's Waiting Room, and the Colored Women's Waiting Room—were part of the station's original scheme as evident on the blueprints. The General Waiting Room contained a fireplace. Designers added fireplaces for heating, ventilation, and decoration.⁶²

A locality's status was determined on whether or not their station had a separate Women's Waiting Room. Since Alexandria's station had defined waiting rooms, this is another indicator of the station's prominence as a rail travel stop despite its relatively small size. Separate waiting rooms for women were designed since stations were considered dangerous places for women, especially those travelling alone. Distinct waiting areas kept women away from smoking areas and an "undesirable element, emigrants, laborers, hackman, and loungers."⁶³ Being a southern station, the original blueprints reflect a separation of waiting rooms by race. What is uncommon is the racial segregation only by sex. No adjustment in the stations waiting rooms or bathrooms is made to separate white from African American men; only white and African American women have separate spaces. Absolutist views about separating the races also did not apply since white women, if unaccompanied by a man, purchased tickets at the closest ticket window in the waiting area noted as the women's waiting room (assumed to be for African American women since the Colored Women's Bathrooms led off of it.) Although racial segregation applied to women at the station, it is interesting that another primary criterion for separating waiting rooms was employed: to disassociate men from women, regardless of a woman's race. The wall near the ticket office offered no male access to the women's wing of the building.

Whether the waiting room distinctions were actually used according to the blueprints when the station opened in 1905 is questionable. Public facilities were separated by race in Alexandria at that time. It is possible that the waiting room at the south end of the passenger depot was always used as a waiting room for African Americans as noted on blueprints acquired during the 1997 restoration. Here, the northern waiting room was designated for whites, both male and female.

Another important feature of waiting rooms was good interior lighting.⁶⁴ At the Alexandria Union Station the dormer windows provided additional natural light to illuminate the building during daylight hours.

The blueprints note that freight hauling was another part of the Alexandria station's responsibilities. The baggage room facility included a room for express freight and one for mail. Large shipments were processed through a separate freight building, built in 1905, located across the tracks where the platform for the current Metro station now stands. It was typical for larger stations to have separate freight facilities. Small, country stations had freight rooms within the main building.

The grounds of the Alexandria Union Station, as originally planned, reflected the importance of landscaping for train depots in the late 19th and early 20th centuries. In his 1893 book, Walter Gilman Berg recommended that railways should employ landscape architects to design pleasant grounds that included railings and paved walks and roads.⁶⁵ To encourage more passenger

Alexandria Union Station

Name of Property

City of Alexandria, VA

County and State

service, railways incorporated landscaping into their plans to soften the industrial image of the rail station.⁶⁶ Paul Huebner of the Reading Railroad System wrote in the 1906 issue of *Horticulture*, "A railroad company does not beautify its station grounds for 'philanthropic reasons.' The basic idea is to increase traffic, and to do this, surroundings are made as attractive as possible."⁶⁷ By 1905, the year of the Alexandria Union Station's construction, people expected rail station grounds to be maintained and landscaped. A postcard of the Alexandria Union Station dating from the 1920s shows formal landscaping on both sides of a paved drive at the front of the building.⁶⁸ The station's 1916 ICC valuation accounted for lattice fencing, grass, shrubs, hedges, and flowerbeds. Fencing, walks, grass and seed, flowers, sodding, and shrubs are noted in the 1925 ICC valuation.⁶⁹

By comparing the era's standard practices for station design and PRR stations built between 1903 and 1914, a better understanding of the position Alexandria Union Station held in the region emerges. Constructed to accommodate passenger and freight service for a small city, it was embellished with architectural detail typical for a larger urban area's station. Because of its rail connections to the south through the elegant Washington, D.C., Union Station and its local prominence as a union station, it is probable PRR engineers designed the station as a dignified and fashionable gateway for passengers travelling to and from the south.

Alexandria Union Station
Name of Property

City of Alexandria, VA
County and State

9. Major Bibliographical References

Bibliography (Cite the books, articles, and other sources used in preparing this form.)

Albro, Martin. *Railroads Triumphant: The Growth, Rejection, and Rebirth of a Vital American Force*. New York City, New York: Oxford University Press, 1992.

Alexander, Edwin P. *Down at the Depot: American Railroad Stations from 1831-1920*. New York City, New York: Bramhall House, 1970.

_____. *On the Main Line: The Pennsylvania Railroad in the 19th Century*. New York City, NY: Bramhall House, 1971.

Alexandria Chamber of Commerce. "Alexandria, Virginia: The Gateway to the South." Alexandria, VA, c. 1915.

Alexandria Gazette. May 2, 1957.

Archaeology Department, City of Alexandria.
<http://alexandriava.gov/uploadedFiles/historic/info/archaeology/ARShutersHillBrochure.pdf>
(accessed February 2011).

Baer, Christopher T., Assistant Curator, Manuscripts & Archives, Hagley Museum and Library, Greenville, DE. correspondence with Ann Horowitz. (March 10-11, 2011).

Berg, Walter Gilman. *Buildings and Structures of American Railroads, A reference book for railroad managers, superintendents, master mechanics, engineers, architects, and students*. New York, New York: J. Wiley & Sons, 1893.

Blardone, Chuck. email message to author, April 5, 2011.

Bushong, William. email message to author, June 8, 2011.

Chief Engineer, Pennsylvania Railroad. "Blueprints, Passenger Station at Alexandria, VA." Philadelphia, PA, June 22, 1905.

City of Alexandria. *City of Alexandria Transportation Map*. 1908.

_____, Office of the City Engineer, *City of Alexandria Map*, Alexandria, VA, 1948.

Cox, Al. "An Analysis of the Alexandria Union Station." Alexandria, VA: City of Alexandria Department of Transportation and Environmental Services, February 14, 1995.

_____. email message to author. February 4, 2011.

Alexandria Union Station

Name of Property

City of Alexandria, VA

County and State

_____. "The Alexandria Union Station." *Historic Alexandria Quarterly* (Historic Alexandria) 1, no. 1 (Winter 1996): 1-11.

Daniels, Rudolph L. *Trains Across the Continent: North American Railroad History*. Bloomington, IN: Indiana University Press, 2000.

Droppa, Dennis. "CSX Family of Rail Lines." *Piedmont Railroaders*. March 2010. <http://www.trainweb.org/PiedmontRR/railhst2.html#rfpr> (accessed February 9, 2011).

Duffee, Lawrence. *Track the History of City's Railroad Depot as it turns 100*. Fredericksburg.com. November 9, 2010.

Foley, James, Retired, Richmond, Fredericksburg & Potomac Railroad, Potomac Yard. correspondence with Ann Horowitz. (March 10, 2011).

Forgery, Benjamin. "In Alexandria, a Worthy Destination; The Area's Other Union Station Has Come a Long Way." *The Washington Post*, August 23, 1997: F.01.

Gerckens, Laurence. *Shaping the American City*. Hilliard, OH: The On-Call Faculty Program, Inc., 2002.

Griffin, William E., Jr. *One Hundred Fifty Years of History: Along the Richmond, Fredericksburg and Potomac Railroad*. Richmond, VA: Richmond, Fredericksburg and Potomac Railroad Company, 1984.

_____. correspondence with Ann Horowitz. (March 10, May 25, July 7, 2011).

Goodwin, Christopher & Associates. "Phase I and II: Archaeological Investigations at Cameron Farm and Cameron Mill." Hoffman Properties, Alexandria, Virginia, 2005. City of Alexandria. <http://alexandriava.gov/Carlyle-EE> (accessed March 3, 2011).

Harris, Cyril M., ed. *Illustrated Dictionary of Historic Architecture*. New York, NY: Dover Publications, 1977.

Holland, Kevin J. and Mike Schaefer. *The Complete Book of North American Railroad: Moving People*. Minneapolis, MN: Voyageur Press, 2009.

Macoll, John D., ed. *Alexandria: A Town in Transition, 1800-1900*. Alexandria, VA: Alexandria Bicentennial Commission, Alexandria Historical Society, 1977.

Massey, James C., Jere Gibber, and Barbara Ballentine. http://www.dhr.virginia.gov/registers/Cities/Alexandria/100-0149_OrangeAndAlexandriaRailroadHooff%92sRunBridge_2003_Final_Nomination.pdf (accessed February 2011).

Maxwell, Shirley and James C. Massey.

Alexandria Union Station

Name of Property

City of Alexandria, VA

County and State

[http://www.dhr.virginia.gov/registers/Cities/Alexandria/100-](http://www.dhr.virginia.gov/registers/Cities/Alexandria/100-0137_Rosemont_HD_1992_Final_Nomination.pdf)

[0137_Rosemont_HD_1992_Final_Nomination.pdf](http://www.dhr.virginia.gov/registers/Cities/Alexandria/100-0137_Rosemont_HD_1992_Final_Nomination.pdf) (accessed February 2011).

McAlester, Virginia and Lee. *A Field Guide to American Houses*. New York, NY: Alfred A. Knopf, 1984.

Meeks, Carroll. *The Railroad Station: An Architectural History*. New Haven, CT: Yale University Press, 1956.

Office of the Chief Engineer. "Station Conditions and Alternatives." Washington, DC: Amtrak, 1982.

Peterson, Jon A. *The Birth of City Planning in the United State, 1840-1917*. Baltimore, Maryland: John Hopkins University Press, 2003.

Richards, Jeffrey and John M. MacKenzie. *The Railway Station: A Social History*. New York City, NY: Oxford University Press, 1986.

Richmond, Fredericksburg & Potomac Railroad Historical Society Richmond Newsletters. Volume 2, Issue 1.

Sampson Collection, Local History Library. "Union Station postcard." Alexandria, VA, c. 1920.

Sanborn Fire Insurance Company. *Sanborn Fire Insurance Maps*. 1902, 1912, 1921, 1931, 1941.

Schweigert, Kurt. "West End." 1998.

<http://alexandriava.gov/uploadedFiles/historic/info/archaeology/ARSiteReportWestEnd.pdf> (accessed March 1, 2011).

Smith, William Francis and T. Michael Miller. *A Seaport Saga: Portrait of Old Alexandria, VA*. Virginia Beach, VA: The Donning Company Publishers, 1989.

Stilgoe, John R. *Metropolitan Corridor: Railroads and the American Scene*. New Haven, CT: Yale University Press, 1983.

Virginia Department of Historic Resources Archives. "VDHR Reconnaissance Survey Form." April 25, 1986.

Washington Post. "Alexandria is Astir." *The Washington Post*, August 28, 1904: 5.

_____ "Alexandria News in Brief," *The Washington Post*, July 19, 1904.

_____ "Changes in Railways," *The Washington Post*, September 17, 1905: 8.

Alexandria Union Station
Name of Property

City of Alexandria, VA
County and State

_____ "First Stop at Alexandria," *The Washington Post*, December 28,
1912: 3.

_____ " 'Mystery Special' Rail Excursion is Big Success," June 6, 1932: 3.

Previous documentation on file (NPS):

- _____ preliminary determination of individual listing (36 CFR 67) has been requested
- _____ previously listed in the National Register
- _____ previously determined eligible by the National Register
- _____ designated a National Historic Landmark
- _____ recorded by Historic American Buildings Survey # _____
- _____ recorded by Historic American Engineering Record # _____
- _____ recorded by Historic American Landscape Survey # _____

Primary location of additional data:

- State Historic Preservation Office
- _____ Other State agency
- _____ Federal agency
- _____ Local government
- _____ University
- _____ Other

Name of repository: Department of Historic Resources, Richmond, VA

Historic Resources Survey Number (if assigned): VDHR No. 100-0124

10. Geographical Data

Acreeage of Property 3.514703 acres

Use either the UTM system or latitude/longitude coordinates

Latitude/Longitude Coordinates

Datum if other than WGS84: _____

(enter coordinates to 6 decimal places)

- | | |
|--------------|------------|
| 1. Latitude: | Longitude: |
| 2. Latitude: | Longitude: |
| 3. Latitude: | Longitude: |
| 4. Latitude: | Longitude: |

Alexandria Union Station
Name of Property

City of Alexandria, VA
County and State

Or

UTM References

Datum (indicated on USGS map):

NAD 1927 or NAD 1983

- | | | |
|-------------|-----------------|-------------------|
| 1. Zone: 18 | Easting: 320870 | Northing: 4297090 |
| 2. Zone: | Easting: | Northing: |
| 3. Zone: | Easting: | Northing: |
| 4. Zone: | Easting : | Northing: |

Verbal Boundary Description (Describe the boundaries of the property.)

The boundaries are defined by King Street to the west, Callahan Drive to the south, the railroad tracks to the east, and the CSX railroad bridge to the north. This is illustrated on the City of Alexandria's Real Estate Assessment Map-Block-Lot Number of 073.01-03-04.

Boundary Justification (Explain why the boundaries were selected.)

The building and the 3.514703 acres historically associated with the property, excluding the railroad tracks, define the boundaries.

11. Form Prepared By

name/title: Ann D. Horowitz, assisted by Catherine Miliaras, (City of Alexandria,
Historic Preservation Office)

organization: _____

street & number: 313 North Royal Street

city or town: Alexandria state: VA zip code: 22314

e-mail annhorowitz@me.com

telephone: 703-739-6567

date: August 22, 2012

Additional Documentation

Submit the following items with the completed form:

Alexandria Union Station
Name of Property

City of Alexandria, VA
County and State

- **Maps:** A **USGS map** or equivalent (7.5 or 15 minute series) indicating the property's location.
- **Sketch map** for historic districts and properties having large acreage or numerous resources. Key all photographs to this map.
- **Additional items:** (Check with the SHPO, TPO, or FPO for any additional items.)

Photographs

Submit clear and descriptive photographs. The size of each image must be 1600x1200 pixels (minimum), 3000x2000 preferred, at 300 ppi (pixels per inch) or larger. Key all photographs to the sketch map. Each photograph must be numbered and that number must correspond to the photograph number on the photo log. For simplicity, the name of the photographer, photo date, etc. may be listed once on the photograph log and doesn't need to be labeled on every photograph.

Photo Log

The following information is common to all photographs:

Name of Property: Alexandria Union Station

City or Vicinity: Alexandria

County: Alexandria (Independent City) State: VA

Photographer: Ann D. Horowitz

Description of Photograph(s) and number, include description of view indicating direction of camera:

1 of 11 description: Union Station exterior, looking east
number: VA_Alexandria City_Union Station_0001
camera direction: east
date photographed: July 13, 2011

2 of 11 description: Union Station exterior, looking southeast
number: VA_Alexandria City_Union Station_0002
camera direction: southeast
date photographed: February 6, 2011

3 of 11 description: Union Station, trackside, looking west
number: VA_Alexandria City_Union Station_0003
camera direction: west
date photographed: February 6, 2011

4 of 11 description: Union Station baggage annex, looking north

Alexandria Union Station

Name of Property

City of Alexandria, VA

County and State

number: VA_Alexandria City_Union Station_0004

camera direction: north

date photographed: July 13, 2011

5 of 11 description: Union Station, looking south

number: VA_Alexandria City_Union Station_0005

camera direction: south

date photographed: July 13, 2011

6 of 11 description: Union Station, looking east, toward track

number: VA_Alexandria City_Union Station_0006

camera direction: east

date photographed: February 6, 2011

7 of 11 description: Union Station, trackside, looking south

number: VA_Alexandria City_Union Station_0007

camera direction: south

date photographed: February 6, 2011

8 of 11 description: Union Station, interior, looking south through lobby

number: VA_Alexandria City_Union Station_0008

camera direction: south

date photographed: February 10, 2011

9 of 11 description: Union Station, interior, looking south through small waiting room

number: VA_Alexandria City_Union Station_0009

camera direction: south

date photographed: July 13, 2011

10 of 11 description: Union Station, interior, looking north to entrance

number: VA_Alexandria City_Union Station_0010

camera direction:

date photographed: July 13, 2011

11 of 11 description: Union Station, interior, looking north through lobby

number: VA_Alexandria City_Union Station_0011

camera direction: north

date photographed: July 13, 2011

Additional Images Log

The following information is common to all images:

Name of Property: Alexandria Union Station

City or Vicinity: Alexandria

County: Alexandria (Independent City)

State: VA

Alexandria Union Station
Name of Property

City of Alexandria, VA
County and State

Description of Image (s) and number, include description of view indicating direction of camera:

- 1 of 7 description: Aerial view, Union Station and environs, 2012
source: GIS, Department of Planning & Zoning, City of Alexandria
- 2 of 7 description: Current floor plan, Union Station, 2012
source: 1997 renovation drawing with notes by author
- 3 of 7 description: Original floor plan, Union Station, 1904
source: Special Collections, Alexandria Library, Alexandria, Virginia
- 4 of 7 description: Original elevations, Union Station, 1904
source: Special Collections, Alexandria Library, Alexandria, Virginia
- 5 of 7 description: Color postcard, Union Station, looking east, 1920s
source: Special Collections, Alexandria Library, Alexandria, Virginia
- 6 of 7 description: Union Station, looking north, circa 1906
source: Sampson Collection, Special Collections, Alexandria Library, Alexandria, Virginia
- 7 of 7 description: Union Station, looking north, undated
source: Special Collections, Alexandria Library, Alexandria, Virginia

Paperwork Reduction Act Statement: This information is being collected for applications to the National Register of Historic Places to nominate properties for listing or determine eligibility for listing, to list properties, and to amend existing listings. Response to this request is required to obtain a benefit in accordance with the National Historic Preservation Act, as amended (16 U.S.C. 460 et seq.).

Estimated Burden Statement: Public reporting burden for this form is estimated to average 100 hours per response including time for reviewing instructions, gathering and maintaining data, and completing and reviewing the form. Direct comments regarding this burden estimate or any aspect of this form to the Office of Planning and Performance Management, U.S. Dept. of the Interior, 1849 C. Street, NW, Washington, DC.

Alexandria Union Station

Name of Property

City of Alexandria, VA

County and State

Endnotes

- ¹ VDHR Archives, "VDHR Reconnaissance Survey Form," April 25, 1986.
- ² Al Cox, "An Analysis of the Alexandria Union Station" (Alexandria, VA: City of Alexandria Department of Transportation and Environmental Services, February 14, 1995), 29.
- ³ Office of the Chief Engineer, "Station Conditions and Alternatives," (Washington, DC: Amtrak, 1982), 1.
- ⁴ William E. Griffin, Jr., *One Hundred Fifty Years of History: Along the Richmond, Fredericksburg & Potomac Railroad* (Richmond, VA: Richmond, Fredericksburg & Potomac Railroad Company, 1984), 126.
- ⁵ A union station serviced the passengers and freight for different rail lines at one central location.
- ⁶ Laurence Gerckens, *Shaping the American City* (Hilliard, OH: The On-Call Faculty Program, Inc., 2002), B-3.
- ⁷ Griffin, 123.
- ⁸ Gerckens, B-4.
- ⁹ *Ibid.*, B-4-5.
- ¹⁰ Martin Albro, *Railroads Triumphant: The Growth, Rejection, and Rebirth of a Vital American Force* (New York, NY: Oxford University Press, 1992), 117.
- ¹¹ William Bushong, correspondence with Ann Horowitz, (June 8, 2011).
- ¹² Cox, "An Analysis of the Alexandria Union Station," 22-24.
- ¹³ Albro, 79.
- ¹⁴ Cox, "An Analysis of the Alexandria Union Station," 33.
- ¹⁵ *Ibid.*, 25.
- ¹⁶ Rudolph L. Daniels, *Trains Across the Continent: North American Railroad History* (Bloomington, IN: Indiana University Press, 2000), 171, 182.
- ¹⁷ William E. Griffin, Jr., correspondence with Ann Horowitz, (May 25, 2011).
- ¹⁸ "Alexandria is Astir," *The Washington Post* (Washington, DC: The Washington Post Newspaper, August 28, 1904).
- ¹⁹ "Alexandria News in Brief," *The Washington Post* (Washington, DC: The Washington Post Newspaper, July 19, 1904).
- ²⁰ "Changes in Railways," *The Washington Post* (Washington, DC: The Washington Post Newspaper, September 17, 1905).
- ²¹ "Alexandria is Astir."
- ²² Griffin, 123.
- ²³ *Alexandria Gazette*, May 2, 1957.
- ²⁴ William Francis Smith and T. Michael Miller, *A Seaport Saga: Portrait of Old Alexandria, VA* (Virginia Beach, VA: The Donning Company Publishers, 1989). 150.
- ²⁵ James C. Massey, Shirley Maxwell, *Department of Historic Resources*, November 22, 1991, http://www.dhr.virginia.gov/registers/Cities/Alexandria/100-0137_Rosemont_HD_1992_Final_Nomination.pdf (accessed February 2011).
- ²⁶ "First Stop at Alexandria," *The Washington Post* (Washington, DC: The Washington Post Newspaper, December 28, 1912).
- ²⁷ Griffin, 124.
- ²⁸ Fredericksburg & Potomac Railroad Historical Society Richmond Newsletters.
- ²⁹ "Mystery Special" Rail Excursion is Big Success," *The Washington Post* (Washington, DC: The Washington Post Newspaper, June 6, 1932).
- ³⁰ Al Cox, "The Alexandria Union Station," *Historic Alexandria Quarterly* (Historic Alexandria) 1, no. 1 (Winter 1996): 5.
- ³¹ Cox, "An Analysis of the Alexandria Union Station," 79.
- ³² Dennis Droppa, "CSX Family of Rail Lines," *Piedmont Railroaders*, March 2010, <http://www.trainweb.org/PiedmontRR/railhst2.html#rfpr> (accessed February 9, 2011).
- ³³ Cox, "The Alexandria Union Station," 5.
- ³⁴ Benjamin Forgery, "In Alexandria, a Worthy Destination; The Area's Other Union Station Has Come a Long Way," *The Washington Post*, August 23, 1997: F.01.
- ³⁵ Al Cox, correspondence with Ann Horowitz, (February 4, 2011).
- ³⁶ William Griffin, correspondence with Ann Horowitz, (July 7, 2011).

Alexandria Union Station

City of Alexandria, VA
County and State

Name of Property

³⁷ Archaeology Department, *City of Alexandria*

<http://alexandriava.gov/uploadedFiles/historic/info/archaeology/ARShutersHillBrochure.pdf> (accessed February 2011).

³⁸ Cox, "An Analysis of the Alexandria Union Station," 44.

³⁹ *Ibid.*, 45.

⁴⁰ Cox, "The Alexandria Union Station," 5.

⁴¹ Christopher Goodwin & Associates, "Phase I and II: Archaeological Investigations at Cameron Farm and Cameron Mill," Hoffman Properties, Alexandria, Virginia (2005), 18.

⁴² Schweigert, Kurt P., "West End," 1998, B-5.

<http://alexandriava.gov/uploadedFiles/historic/info/archaeology/ARSiteReportWestEnd.pdf> (accessed March 1, 2011).

⁴³ Cox, "An Analysis of the Alexandria Union Station," 35-36.

⁴⁴ Holland and Shafer, 280-283.

⁴⁵ Carroll Meeks, *The Railroad Station: An Architectural History* (New Haven, CT: Yale University Press, 1956), 24.

⁴⁶ Chief Engineer, Pennsylvania Railroad, "Blueprints, Passenger Station at Alexandria, VA" (Philadelphia, PA, June 22, 1905).

⁴⁷ Check Blardone, Pennsylvania Railroad Technical & Historical Society, correspondence with Ann Horowitz, (April 5, 2011).

⁴⁸ James Foley, "Richmond, Fredericksburg & Potomac Railroad, Potomac Yard" (March 10, 2011).

⁴⁹ John R. Stilgoe, *Metropolitan Corridor: Railroads and the American Scene* (New Haven, CT: Yale University Press, 1983), 199-203.

⁵⁰ Walter Gilman Berg, *Buildings and Structures of American Railroads, A reference book for railroad managers, superintendents, master mechanics, engineers, architects, and students* (New York, New York: J. Wiley & Sons, 1893), 285.

⁵¹ Meeks, 109.

⁵² Berg, 340-346.

⁵³ Alexandria Chamber of Commerce, "Alexandria, Virginia: The Gateway to the South" (Alexandria, VA, c. 1915).

⁵⁴ Stilgoe, 195.

⁵⁵ *Ibid.*, 199.

⁵⁶ Berg, 344.

⁵⁷ Stilgoe, 197.

⁵⁸ *Ibid.*, 199.

⁵⁹ *Ibid.*, 195-197.

⁶⁰ Berg, 282.

⁶¹ *Ibid.*, 284.

⁶² *Ibid.*, 284.

⁶³ Berg, 323.

⁶⁴ *Ibid.*, 346.

⁶⁵ Stilgoe, 285.

⁶⁶ *Ibid.*, 243.

⁶⁷ *Ibid.*, 227.

⁶⁸ Sampson Collection, "Union Station postcard" (Alexandria, VA, c. 1920).

⁶⁹ Cox, "An Analysis of the Alexandria Union Station," 117-118.

⁷⁰ Cox, meeting with Ann Horowitz, June 21, 2011.




VDHR File Number 100-0124
Union Station, aerial view, 2012
VA_Alexandria City Union Station_Supplemental_0001
source: GIS, Department of Planning & Zoning, City of Alexandria




073-01-03-04

Legend

 Union Station
(c)

VDHR File Number 100-0124
Union Station, current floor plan, 2012
VA_Alexandria City_Union Station_Supplemental_0002
source: 1997 renovation drawing with notes by author



ALEXANDRIA UNION STATION
CITY OF ALEXANDRIA, VA
VDHR FILE NO. 100-0124


VDHR File Number 100-0124

Union Station, original floor plan; 1904

VA_Alexandria City_Union Station_Supplemental_0003

source: Special Collections,

Alexandria Library, Alexandria, Virginia



TRACK FLOOR PLAN.

58071
 PASSENGER STATION
 AT
 ALEXANDRIA VA.
 WASHINGTON SOUTHERN RY. CO.
 TRACK FLOOR PLAN.
 SCALE 1/8" = 1'-0"
 PHILA. SEPT. 1904
 SHEET NO. 3

ALEXANDRIA UNION STATION


CITY OF ALEXANDRIA, VA

VDHR: 100-0124


VDHR File Number 100-0124
Union Station, original elevations, 1904
VA_Alexandria City_Union Station_Supplemental_0004
source: Special Collections,
Alexandria Library,
Alexandria, Virginia




EAST OR TRACK ELEVATION.




WEST ELEVATION.



NORTH ELEVATION



CROSS SECTION



SOUTH ELEVATION

58071
PASSENGER STATION
AT
ALEXANDRIA VA.
WASHINGTON SOUTHERN RY. CO.
ELEVATIONS & SECTION
SCALE 1/8 IN. = 1 FT.
REVISED OCT. 1894
PHILA SEPT

ALEXANDRIA UNION STATION

CITY OF ALEXANDRIA, VA

VDHR: 100-0124

VDHR File Number 100-0124
Union Station, color postcard, looking east, 1920s
VA_Alexandria City_Union Station_Supplemental_0005
source: Special Collections, Alexandria Library, Alexandria, Virginia



ALEXANDRIA UNION STATION

CITY OF ALEXANDRIA, VA


VDHR : 100-0124

VDHR File Number 100-0124

Union Station, historic photograph, looking north, circa 1906

VA_Alexandria_City_Union_Station_Supplemental_0006

source: Sampson Collection, Special Collections, Alexandria Library, Alexandria, Virginia





ALEXANDRIA UNION STATION

CITY OF ALEXANDRIA, VA

VDHR: 100-0124




R. Station, Alexandria, Va.



To convert feet to meters multiply by 0.3048
To convert meters to feet multiply by 3.2808

ALEXANDRIA UNION
CITY OF ALEXANDRIA
VDHR: 100-0-
QAD: Alexandria, VA-
NAD 83
UTM: Zone 18
Easting
Northing



Maped, edited, and published by the Geological Survey and the National Ocean Service
Control by USGS, NOS/NOAA, USCE, NCPS, and WSSC
Topography by photogrammetric methods from aerial photographs taken 1955. Field checked 1956. Revised 1965
Bathymetry compiled by the National Ocean Service from tide-coordinated hydrographic surveys. This information is not intended for navigational purposes
Mean low water (dotted) line and mean high water (heavy solid) line compiled by NOS from tide-coordinated aerial photographs. Apparent shoreline (outer edge of vegetation) shown by light solid line
Polyconic projection. 10,000-foot grid ticks based on Virginia coordinate system, north zone, and Maryland coordinate system 1000-meter Universal Transverse Mercator grid, zone 18
To place on the predicted North American Datum 1983 move the projection lines 9 meters south and 26 meters west as shown by dashed corner ticks
Fine red dashed lines indicate selected fence and field lines where generally visible on aerial photographs. This information is unchecked
Red tint indicates areas in which only landmark buildings are shown
There may be private inholdings within the boundaries of the National or State reservations shown on this map
Revisions shown in purple and woodland compiled in cooperation with Commonwealth of Virginia agencies from aerial photographs taken 1981 and other sources. This information is unchecked
Map edited 1983
Purple tint indicates extension of urban areas

NATIONAL OCEAN SERVICE
HYDROGRAPHIC SURVEY INDEX

Survey Number	Survey Date	Survey Scale	Survey Line Spacing (Naut. Miles)
H-9478	1962	1:10,000	01-05
H-9477	1974	1:5,000	01-03
H-9476	1975	1:5,000	08-01
H-9475	1974	1:10,000	02-06

SCALE 1:24,000
CONTOUR INTERVAL 10 FEET
NATIONAL GEODETIC VERTICAL DATUM OF 1929
BATHYMETRIC CONTOUR INTERVAL 1 METER WITH SUPPLEMENTARY 0.5 METER CONTOURS-DATUM IS MEAN LOW WATER
THE RELATIONSHIP BETWEEN THE TWO DATUMS IS VARIABLE
THE MEAN RANGE OF TIDE IS APPROXIMATELY 0.9 METER

ROAD CLASSIFICATION
Heavy-duty — Light-duty
Medium-duty — Unimproved dirt
Interstate Route — U.S. Route — State Route

ALEXANDRIA, VA.—D.C.—MD.
38077-G1-TB-024
1965
PHOTOREVISED 1983
BATHYMETRY ADDED 1982
DMA 5561 1 S—SERIES V854

BASE MAP COMPLES WITH NATIONAL MAP ACCURACY STANDARDS
BATHYMETRIC SURVEY DATA COMPLES WITH INTERNATIONAL HYDROGRAPHIC ORGANIZATION (IHO) SPECIAL PUBLICATION 44 ACCURACY STANDARDS
AND/OR STANDARDS USED AT THE DATE OF THE SURVEY
FOR SALE BY U. S. GEOLOGICAL SURVEY, DENVER, COLORADO 80225, OR RESTON, VIRGINIA 22082
AND VIRGINIA DIVISION OF MINERAL RESOURCES, CHARLOTTESVILLE, VIRGINIA 22903
A FOLDER DESCRIBING TOPOGRAPHIC MAPS AND SYMBOLS IS AVAILABLE ON REQUEST

UTM GRID AND 1983 MAGNETIC NORTH DECLINATION AT CENTER OF SHEET



















PLEASE REUSE THESE BOTTLES
FOR RECYCLING PURPOSES

Quik-Trak







TRAVEL VOUCHER #1
TRAVEL VOUCHER #2



UNITED STATES DEPARTMENT OF THE INTERIOR
NATIONAL PARK SERVICE

NATIONAL REGISTER OF HISTORIC PLACES
EVALUATION/RETURN SHEET

REQUESTED ACTION: NOMINATION

PROPERTY NAME: Alexandria Union Station

MULTIPLE NAME:

STATE & COUNTY: VIRGINIA, Alexandria

DATE RECEIVED: 1/11/13 DATE OF PENDING LIST:
DATE OF 16TH DAY: DATE OF 45TH DAY: 2/27/13
DATE OF WEEKLY LIST:

REFERENCE NUMBER: 13000044

REASONS FOR REVIEW:

APPEAL: N DATA PROBLEM: N LANDSCAPE: N LESS THAN 50 YEARS: N
OTHER: N PDIL: N PERIOD: N PROGRAM UNAPPROVED: N
REQUEST: N SAMPLE: N SLR DRAFT: N NATIONAL: N

COMMENT WAIVER: N

ACCEPT RETURN REJECT 2-27-13 DATE

ABSTRACT/SUMMARY COMMENTS:

Entered in
The National Register
of
Historic Places

RECOM./CRITERIA _____

REVIEWER _____ DISCIPLINE _____

TELEPHONE _____ DATE _____

DOCUMENTATION see attached comments Y/N see attached SLR Y/N

If a nomination is returned to the nominating authority, the nomination is no longer under consideration by the NPS.

City of Alexandria, Virginia

MEMORANDUM

DATE: JULY 25, 2012

TO: CHAIRMAN AND MEMBERS OF OLD AND HISTORIC ALEXANDRIA DISTRICT BOARD OF ARCHITECTURAL REVIEW

FROM: AL COX, FAIA, HISTORIC PRESERVATION MANAGER

SUBJECT: ALEXANDRIA UNION STATION DRAFT NATIONAL REGISTER NOMINATION

BOARD ACTION, JULY 25, 2012: The Board endorsed the nomination, 5-0.

The Board acknowledged the efforts of Ann Horowitz, local resident and volunteer, for her work on drafting the National Register nomination for Alexandria Union Station. ON a motion by Mr. von Senden, seconded by Dr. Fitzgerald, the Board made a finding of support for the nomination of Alexandria Union Station to be listed on the National Register of Historic Places and Virginia Landmarks Register.

We propose to submit a draft nomination to the Virginia Department of Historic Resources (VDHR) to list Alexandria Union Station (110 Callahan Drive) on the National Register of Historic Places and the Virginia Landmarks Register. As a Certified Local Government (CLG), the Boards of Architectural Review are entitled to review and comment upon a draft National Register nomination and relay any comments or concerns to the Virginia Department of Historic Resources. The BAR's comments will be incorporated into the nomination prior to submission to the State Historic Preservation Office (SHPO) Director. Ann Horowitz, a local resident and graduate student, has spent the past two years researching the property and drafting the nomination before you at this time.

Once the nomination has been officially submitted, there will be additional opportunities for public comment as part of the Virginia State Review Board and Historic Resources Board processes. At this time, we request that the Board comment upon the draft nomination and endorse the listing of this architecturally significant building.

Staff Recommendation

Staff recommends that the BAR support the designation of this resource and find Alexandria Union Station eligible for listing on the Virginia Landmarks Register and the National Register of Historic Places.

Attachment: *Alexandria Union Station National Register Nomination (DRAFT).* Ann Horowitz, 2012.



COMMONWEALTH of VIRGINIA

Department of Historic Resources

2801 Kensington Avenue, Richmond, Virginia 23221

Douglas W. Domenech
Secretary of Natural Resources

Kathleen S. Kilpatrick
Director

Tel: (804) 367-2323
Fax: (804) 367-2391
TDD: (804) 367-2386
www.dhr.virginia.gov

January 4, 2013

Mr. Paul Loether
Chief, National Register of Historic Places and National Historic Landmarks Programs
National Park Service 2280
National Register of Historic Places
1201 "I" (Eye) Street, N.W.
Washington D.C. 20005

RE: Alexandria Union Station, City of Alexandria; Charlottesville Coca-Cola Bottling Works, City of Charlottesville; and First Baptist Church, Prince Edward County, Virginia

Dear Mr. Loether:

The enclosed nominations, referenced above, are being submitted for inclusion in the National Register of Historic Places. The nominations have been considered, and approved, by the State Review Board and the SHPO has recommended them for listing. Any letters of comment or objection have been copied at the end of the nomination material, along with any FPO notification letters.

Should you have any questions, please do not hesitate to contact me. My direct phone line is 804-482-6439.

Sincerely,

Lena Sweeten McDonald
National/State Register Historian

Enclosures

Administrative Services
10 Courthouse Ave.
Petersburg, VA 23803
Tel: (804) 862-6416
Fax: (804) 862-6196

Capital Region Office
2801 Kensington Avenue
Richmond, VA 23221
Tel: (804) 367-2323
Fax: (804) 367-2391

Tidewater Region Office
14415 Old Courthouse Way
2nd Floor
Newport News, VA 23608
Tel: (757) 886-2807
Fax: (757) 886-2808

Western Region Office
962 Kime Lane
Salem, VA 24153
Tel: (540) 387-5396
Fax: (540) 387-5446

Northern Region Office
5357 Main Street
P.O. Box 519
Stephens City, VA 22655
Tel: (540) 868-7030
Fax: (540) 868-7033



OFFICE OF THE CITY MANAGER
301 King Street, Suite 3500
Alexandria, Virginia 22314-3211

RASHAD M. YOUNG
City Manager

703.746.4300
Fax: 703.838.6343

October 24, 2012

Lena Sweeten McDonald
National/State Register Historian
Virginia Department of Historic Resources
2801 Kensington Avenue
Richmond, VA 23221

Subject: National Register Nomination for Alexandria Union Station, City of Alexandria


Dear Ms. McDonald:

I am in receipt of your letter dated October 11, 2012, to Mayor William D. Euille, Al Cox, Historic Preservation Manager, and myself regarding the proposed nomination of Alexandria Union Station to the National Register of Historic Places and the Virginia Landmarks Register. We understand that as a Certified Local Government (CLG) our local Board of Architectural Review (BAR) is entitled to comment on the proposed nomination.

As you may be aware, the listing of this property was initiated by the City, as the property owner, and has been fully endorsed by the Old and Historic Alexandria District BAR. At a regularly scheduled public hearing on July 25, 2012, the BAR made a finding of support for the nomination of Alexandria Union Station to be listed on the National Register of Historic Places and Virginia Landmarks Register by a vote of 5-0. The Board also commended the efforts of local resident and volunteer, Ann Horowitz, who wrote the nomination.

Please accept this letter and the Board of Architectural Review's endorsement on July 25, 2012, as the City of Alexandria's formal comment regarding the proposed nomination. We look forward to completing the designation process for this very important building.

Sincerely,



Rashad M. Young
City Manager

cc: The Honorable Mayor and Members of City Council
Faroll Hamer, Director, Department of Planning and Zoning
Al Cox, Historic Preservation Manager, Department of Planning and Zoning