UNITED STATES DEPARTMENT OF THE INTERIOR NATIONAL PARK SERVICE

NATIONAL REGISTER OF HISTORIC PLACES INVENTORY -- NOMINATION FORM

FOR NPS USE ONLY

RECEIVED SEP 1 0 1980

-al-

DATE ENTERED

SEE INSTRUCTIONS IN HOW TO COMPLETE NATIONAL REGISTER F	ORMS
TYPE ALL ENTRIES COMPLETE APPLICABLE SECTIONS	

1 NAME

HISTORIC Round Valley Flour Mills

AND/OR COMMON

2 LOCATION

STREET & NUMBER			$\sim 10^{-10}$ M \odot
Main and Greely Stre	ets (southwest corner)	NOT FOR PUBLICATION	
CITY, TOWN		CONGRESSIONAL DISTRI	СТ
Covelo	VICINITY OF	2nd	
STATE	CODE	COUNTY	CODE
California	00	Mendocino	045

3 CLASSIFICATION

CATEGORY	OWNERSHIP	STATUS	PRESE	ENTUSE
DISTRICT	PUBLIC	OCCUPIED	AGRICULTURE	MUSEUM
× BUILDING(S)	×PRIVATE		COMMERCIAL	PARK
STRUCTURE	вотн	WORK IN PROGRESS	EDUCATIONAL	PRIVATE RESIDENCE
SITE	PUBLIC ACQUISITION	ACCESSIBLE	ENTERTAINMENT	RELIGIOUS
OBJECT	IN PROCESS	X YES: RESTRICTED	GOVERNMENT	SCIENTIFIC
	BEING CONSIDERED	YES: UNRESTRICTED	INDUSTRIAL	TRANSPORTATION
		NO	MILITARY	X _{OTHER:} vacant

•

4 OWNER OF PROPERTY

NAME Round Valle	y Planning and Development	Corporation	n. c/o Ric	hard Wilson	
STREET & NUMBER					······
Buck Mounta	in Cattle Company				
CITY, TOWN			*****	STATE	· · · · · · · · · · · · · · · · · · ·
Covelo)F	. (California	95428
5 LOCATION	OF LEGAL DESCRIPTIO	DN			
COURTHOUSE, REGISTRY OF DEEDS, ET	c. Mendocino County Courth	nouse Record	ler's Offic	ce	
STREET & NUMBER	County Courthouse				
CITY, TOWN				STATE	
	Ukiah		Califo	rnia	
6 REPRESENT	ATION IN EXISTING S	URVEYS	#		
TITLE "Historic Bu	uildings File" - Mendocino	County Muse	um		
DATE					
1978-79		FEDERAL	_STATE + COU	NTYLOCAL	
DEPOSITORY FOR SURVEY RECORDS	endocino County Museum				
CITY, TOWN	illits		Ca	state lifornia	

7' DESCRIPTION

CON	DITION	CHECK ONE	СНЕСК С	DNE
EXCELLENT GOOD FAIR	DETERIORATED RUINS UNEXPOSED	UNALTERED X_ALTERED	X_ORIGINAL MOVED	SITE DATE

DESCRIBE THE PRESENT AND ORIGINAL (IF KNOWN) PHYSICAL APPEARANCE

Covered with weathered, wooden shiplap siding and a corrugated metal, gabled roof, the eastern rectangular section of the mill is aligned along an east-west axis. The prominent, eastern rectangular section of the mill is dominated by its decorative false-front facade and a gracefullly rounded cornice. The upper, rounded section of the facade is adorned with a rusty five-pointed star and raised wooden lettering which reads: "1888-1914." Below the star are three windows on the second story. The ground floor has a large sliding loading door, a conventional front entry door, and two windows. The eastern face of the building is approximately 45 feet in length. The facade added in 1914.

The northern wall, also of shiplap siding, consists of the two-story main building, plus a 1914 three-story addition on the west. The two-story section has five windows per story, while the three-story addition has two windows per story. The total length of this wall is approximately 68 feet. The western section with its gabled roof is topped at the northwest corner by a broken, wooden weathervane/flagpole. The weathervane visible in the photographs in <u>Underfoot</u>, has been removed for safekeeping.

The western shiplapped face of the mill includes nine windows, three per story. It is approximately 50 feet in length.

To help prevent fires from the engine room, corrugated tin was used in the construction of the south wall of the three-story section (Rohrbough 1979). The south tin wall has four windows. The south wooden wall of the main building has one window.

A wood-framed addition with shed roof and corrugated tin walls houses a steam engine room to the west, and encloses an open-air area to the east. The addition extends approximately 30 feet to the south of the three-story section. Vertically placed windows are on the western side of the addition. The south side of the engine room addition has one window and a sliding wooden door. The eastern face of the addition has seven closelyplaced windows.

A rusty, 42-foot smokestack lying near the engine room addition at the southwest corner fell from the building about ten or fifteen years ago (Rohrbough 1979).

A conjectural reconstruction of the original 1888 blacksmith shop suggests a two-story wooden structure with false front (see Appendix; Weitzman 19%; 98), altered to its present appearance in 1914.

The present and past owners of the mill have expressed concern about vandalism. John D. Rohrbough stated that the mill has always been the victim of local vandalism (Rohrbough 1979). Richard Wilson, present owner, worried that someday the mill's luck will run out and the mill will be FHR-8-300A (11/78) UNITED STATES DEPARTMENT OF THE INTERIOR HERITAGE CONSERVATION AND RECREATION SERVICE

NATIONAL REGISTER OF HISTORIC PLACES INVENTORY -- NOMINATION FORM

FOR HCRS USE ONLY RECEIVED SEP 1 0 1980 DATE ENTERED.

15

CONTINUATION SHEET

ITEM NUMBER 7 PAGE 2

destroyed by fire. He related that efforts to board the windows and to notify local authorities about the problems have not appreciably slowed the continued deterioration (Wilson 1979). Deterioration of the machinery, known at present to be minimal, has not been thoroughly assessed.

The mill has remained virtually unchanged since the remodeling in 1914. Vandalism, deterioration from the elements, or construction on surrounding land has not occurred to such a significant degree as to seriously affect the architectural or historic integrity of the structure.

The mill stands alone on the northeast corner of a one acre parcel. Five black walnut trees grow around the building: two at the northwest corner of the building; two in the opposite southeast corner, and one at the southeast corner of the engine room addition. The tree at the corner of the addition is growing quite close to the structure. To the north and east, the lot is bounded by light commercial district. The south and west districts are residential neighborhoods.

Until sometime in the 1930s, a house, a well, and orchard occupied the northwest corner of the lot. The house was situated at the northwest corner, the brick-lined well was south of the house, near the middle of the lot. The orchard included apple, cherry, and plum trees. According to John D. Rohrbough, a "negro woman" named Ann Mitchell lived in the house until the mid-1930s. She took in laundry and did domestic work (Rohrbough 1979). Rohrbough did not know when the house was built, but he related that when the house was torn down (ca. late 1930s), newpapers dating from the "Civil War period" were found lining the walls of the structure (see also "Statement of Significance").

8 SIGNIFICANCE

PERIOD	AF	REAS OF SIGNIFICANCE CH	IECK AND JUSTIFY BELOW	
PREHISTOHIC 1400-1499 1500-1599 1600-1699 1700-1799	ARCHEOLOGY-PREHISTORIC X_ARCHEOLOGY-HISTORIC X_AGRICULTURE X_ARCHITECTURE ART	COMMUNITY PLANNING CONSERVATION ECONOMICS EDUCATION ENGINEERING	LANDSCAPE ARCHITECTURE LAW LITERATURE MILITARY MUSIC	RELIGION SCIENCE SCULPTURE SOCIAL/HUMANITARIAN THEATER
X_1800-1899 X_1900-	X_COMMERCE COMMUNICATIONS	EXPLORATION/SETTLEMENT X_INDUSTRY INVENTION	PHILOSOPHY POLITICS/GOVERNMENT	TRANSPORTATION OTHER (SPECIFY)
SPECIFIC DAT	es 1888-1914	BUILDER/ARCH	HITECT 1914: Engineer Carpente	Spaulding r/builder-Long

STATEMENT OF SIGNIFICANCE

The Round Valley Mill continues to exist as a virtually unaltered example of a steam-powered, steel roller grain mill. Its weathered exterior, with functional structural characteristics and simple elements of decorative architectural style, conceals an interior fitted with the mill's original steam engine and redwood-spouted milling machinery.

The mill provided a seasonal food processing center for the rural Northern California town of Covelo in Round Valley, Mendocino County, from circa 1890-1940. The building's imposing size and central location allow it to continue to serve as a significant feature of Covelo's cultural setting.

The structure is a major focal point of the physical community; the machinery, some dating back to the 1880's, is a fascinating vestige of that period when Americans were entranced with rapid technological advance in the art of moving parts but still retained a strong sense of craftsmanship (Merritt 1979: 2).

A blacksmith shop (circa 1870-1880) originally occupied the present mill site and was housed in the older, surviving east wing of the building. Remaining evidence of this earlier historic use is a post with local cattle brands burned in the wood which still supports part of the east wing (Weitzman 1976: 97; Rohrbough 1979). In 1888, John S. Rohrbough (1859-1939), nephew of Round Valley cattle baron George E. White, developed the mill in Covelo as the town's major grain processing center (Carpenter 1914: 110; Weitzman 1976: 99; Rohrbough 1979). It replaced several smaller mills which had previously operated along local creeks (Rohrbough 1979). Rohrbough remodeled the mill in 1914. After a three story section was connected to the older structure, new machinery was introduced and older machinery was adapted to new demands (Weitzman 1976: 98, for conjectural reconstruction).

By the 1920s, Rohrbough's son, John D. Rohrbough (1900-living in Covelo, 1980), was assisting actively with the mill's operation (see Appendix "1924 Flow Diagram"). In 1937, the Rohrbough family ceased producing flour on a regular basis. Local lore suggests that the arrival of the "Wonder Bread" truck and its cargo from the "outside world," signaled the beginning of the end to locally processed grain-based foods (Rohrbough 1979). The mill's machinery was used irregularly to roll barley and wheat for hog feed until the 1960s (Rohrbough 1979). In July

9 MAJOR BIBLIOGRAPHICAL REFERENCES

1 001 11113 1105	eryday Guide to E	length by David	e of the Round Valley Weitzman in his book, <u>t</u> , (New York: Charles	
	nal bibliographic	sources see con	tinuation sheet.	
10 GEOGRAPHICAL D		ITM NOT VE	RED	
ACREAGE OF NOMINATED PROPER		_After and		
QUADRANGLE NAME Covel	• East	RUNEAUE NUI	QUADRANGLE SCALE 1:24000	
UTM REFERENCES	4494619	в, , , , ,		
ZONE EASTING	NORTHING		TING NORTHING	ļ
C L L L L L L L L L L L L L L L L L L L				
ELI		FL		Ì
GLILI		нЦц Ц		
VERBAL BOUNDARY DESCRI (200'x200') ''Lot	PTION : in Covelo on the	e southwest corne	er of Main and Greely	
streets, bounded	north by Greely s	street, east by N	fain Street, south by	
Grange street, we	est by Perry stree	et."		
LIST ALL STATES AND	COUNTIES FOR PROPER	TIES OVERLAPPING ST	ATE OR COUNTY BOUNDARIES	
STATE	CODE	COUNTY	CODE	
STATE	CODE	COUNTY	CODE	
11 FORM PREPARED	BV		******	
NAME/Mark Rawitsch/Dir				
Linda Wickert/Stu			February 1, 1980	
ORGANIZATION			DATE	
Mendocino County	Museum		707) 459-2736	
STREET & NUMBER 400 E. Commercial	۲+		TELEPHONE	
CITY OR TOWN	31.		STATE	
Willits			California	
12 STATE HISTORIC	DECEDVATIO	N OFFICED CI		
	•			
THE EVALU	IATED SIGNIFICANCE OF	_		
NATIONAL	STA	TE X	LOCAL	
-	inclusion in the National	Register and certify tha	vation Act of 1966 (Public Law 89-6) t it has been evaluated according to	
STATE HISTORIC PRESERVATION OFF	ICER SIGNATURE	2 mill		
TITLE	3		DATE ZILLISD	
FOR NPS USE ONLY I HEREBY CERTIFY THAT THIS	PROPERTY IS INCLUDED	IN THE NATIONAL RE	GISTER	
Muran Mar Du	ned		DATE 11/10/00	
AF KEEPER OF THE MATIONAL	RÉGISTER		11.1	
ATTEST: Jatuk Andress			DATE 11/2/80	

FHR-8-300A (11/78) UNITED STATES DEPARTMENT OF THE INTERIOR HERITAGE CONSERVATION AND RECREATION SERVICE

NATIONAL REGISTER OF HISTORIC PLACES INVENTORY -- NOMINATION FORM

FOR HERS USE ONLY RECEIVED SEP 1 0 1980 DATE ENTERED

2

CONTINUATION SHEET

ITEM NUMBER 8

PAGE

1975, the mill was again operated, by tractor instead of steam engine, to process a local harvest of soft white winter wheat (Weitzman 1976: 104).

David Weitzman, Covelo resident, expanded the social and historical significance of the mill when he used the building as an example for his discussion of American industrial history in <u>Underfoot: An Everyday Guide</u> to Exploring the American Past (see Chapter 5, 'Meetings with the Miller," pp. 91-111).

Of additional interest is the mention of the mill and its relationship to the character of Ann Mitchell in a novel by Percy Marks. Marks, a native of Covelo, used his Round Valley experiences in writing two of his novels, <u>Martha</u> and <u>No Steeper Walls</u>. While Marks never achieved great literary status, his works were popular and still provide some interesting insights into an isolated rural culture. While the mill is mentioned only once in the novel, <u>No Steeper Walls</u>, Marks did introduce and describe a character named Ann Mitchell, a former slave, who lived in a house behind the mill. The few comments made by Rohrbough (see "Description") support the conclusion that Marks based his character on Covelo resident, Ann Mitchell. Given the fact that Mendocino County was settled primarily by whites, and that there have been few blacks prominent in local history, Marks' selection and portrayal of Ann Mitchell is an interesting footnote to local history.

AREAS OF SIGNIFICANCE:

- Archaeology Historic: Archaeological evidence of the earlier historic use of the structure may still exist. As noted above, a blacksmith shop originally occupied the present mill site and was housed in the surviving east wing of the building. In addition, systematic archaeological investigation may also yield data relating to the location and possible cultural contents of a reported outhouse/ latrine which once occupied the south portion of the mill site. (Rohrbough 1979). An archaeological investigation at the site of Ann Mitchell's residence, located at the northwest corner of the property might also yield historical information.
- 2. Agriculture: The function of the mill as a grain processing center relates directly to local agricultural practices. A detailed investigation of the mill's machinery may also provide more significant

FHR-8-300A (11/78) UNITED STATES DEPARTMENT OF THE INTERIOR HERITAGE CONSERVATION AND RECREATION SERVICE

NATIONAL REGISTER OF HISTORIC PLACES INVENTORY -- NOMINATION FORM

FOR HCRS USE ONLY RECEIVED SEP 1 0 1980 DATE ENTERED

CONTINUATION SHEET	ITEM NUMBER	8	PAGE 3

information concerning late nineteenth century agricultural technology.

- 3. Commerce: The mill's sphere of commercial influence reached beyond its own Round Valley. Flour was reportedly shipped to Spyrock, Alder Point, Laytonville, and Branscomb (Rohrbough 1979).
- 4. Industry: The mill's machinery survives intact. It provides a complete and very clear picture of the workings of a steam powered steel roller mill. The 1914 alteration was based on plans developed in San Francisco (Weitzman 1976: 99). Evidence relating to manufacturing techniques which were developed in a nineteenth century American urban center may still survive in rural Covelo when comparable information in the San Francisco Bay region has long since been lost to the effects of rapid urban change.

FHR-8-300A (11/78) UNITED STATES DEPARTMENT OF THE INTERIOR HERITAGE CONSERVATION AND RECREATION SERVICE.


NATIONAL REGISTER OF HISTORIC PLACES INVENTORY -- NOMINATION FORM

FOR HCRS USE ONLY RECEIVED SEP 0 1980 DATE ENTERED ' 9

CONTINUATION SHEET, ITEM NUMBER 9 PAGE 4

Bibliography

- Carpenter, Aurelius O. <u>A History of Mendocino County</u>. Los Angeles: Historic Record Co., 1914; republished by Pacific Rim Research, Mendocino, Calif., 1977.
- <u>History of Mendocino County</u>. San Francisco: Alley, Bowen & Co., Publishers, 1880.
- Keller, John. <u>The Saqa of Round Valley, The Last of the West</u>. Ukiah, Calif.: Mendocino County Historical Society, 1976.
- Kunitz, Stanley J. and Howard Haycraft, eds. <u>Twentieth Century Authors</u>, <u>A Bibliographic Dictionary of Modern Literature</u>. New York: The H.H. Wilson Co., 1942.
- Levene, Bruce; Bradd, W.; Krasner, L.; Petrykowski, A.; and Zucker, R. <u>Mendocino County Remembered, An Oral History</u>. Volume 1. Ukiah, Calif.: Mendocino County Historical Society 1976.
- Merritt, John. "Trip Report." Report of National Trust for Historic Preservation representative's visit to the Round Valley Flour Mills in Covelo, Calif., 23 May 1979.
- Miller, Virginia P. <u>Ukomno'M: The Yuki Indians of Northern California</u>. Socorro, New Mexico: Ballena Press, 1977.
- Marks, Percy. <u>No Steeper Walls</u>. New York: Frederick A. Stokes, Company. 1940.
- Rohrbough, John D. Former owner of the Round Valley Flour Mills. Covelo, Calif. Interview. 24 May 1979; 3 December 1979.
- Weitzman, David. <u>Underfoot: An Everyday Guide to Exploring the</u> <u>American Past</u>. New York: Charles Scribner's Sons, 1976.
- Wilson, Richard, Owner of the Round Valley Flour Mills. Covelo, Calif. Interivew. 3 December 1979.



SKETCH MAP FOR ROUND VALLEY FLOUR


MILLS, COVELO, CALIFORNIA

MENDOCINO COUNTY



i.

i



Grange St.



NORTH

These sketches suggesting a conjectural reconstruction of the old mill ca. 1888 and subsequent additions ca. 1914 were based on John Rohrbough's tape recorded recollections. first façade extended to about third window of existing building The mill as it probably appeared before renovation. floor and front section from old blacksmith's shop arches added position of sheet in 1914 metal stack now lying. On the ground 40 licking mill south shed added in 1914 or later sear (west) section built in 1914, contains milling machinery post with brands just inside front this section used (east) door for storage, lagging, and weighing Approd X David Weitzman, Underfoot: An Emeryday Guide to Exploring the American Past (New York, 1976). Round Vally Flow Mill SEP 1 0 1980 Covele, Mandocine Co., California