

United States Department of the Interior
National Park Service

RECEIVED

OCT 13 1993

NATIONAL REGISTER OF HISTORIC PLACES
REGISTRATION FORM

NATIONAL
REGISTER

1. Name of Property

historic name: Bentonville Third Street Historic District

other name/site number: N/A

2. Location

street & number: First two-and-one-half blocks of S. E. Third Street

not for publication: N/A

city/town: Bentonville

vicinity: N/A

state: AR county: Benton code: AR 007 zip code: 72712

3. Classification

Ownership of Property: Private

Category of Property: District

Number of Resources within Property:

Contributing	Noncontributing	
<u>17</u>	<u>4</u>	buildings
<u> </u>	<u> </u>	sites
<u> </u>	<u> </u>	structures
<u> </u>	<u> </u>	objects
<u>17</u>	<u>4</u>	Total

Number of contributing resources previously listed in the National Register: 3

Name of related multiple property listing: Historic Resources of Benton County, Arkansas

=====

4. State/Federal Agency Certification

=====

As the designated authority under the National Historic Preservation Act of 1986, as amended, I hereby certify that this X nomination _____ request for determination of eligibility meets the documentation standards for registering properties in the National Register of Historic Places and meets the procedural and professional requirements set forth in 36 CFR Part 60. In my opinion, the property X meets _____ does not meet the National Register Criteria. _____ See continuation sheet.

Cathryn A. Slater

Signature of certifying official

10-4-93

Date

Arkansas Historic Preservation Program

State or Federal agency and bureau

In my opinion, the property _____ meets _____ does not meet the National Register criteria. _____ See continuation sheet.

Signature of commenting or other official

Date

State or Federal agency and bureau

=====

5. National Park Service Certification

=====

I, hereby certify that this property is:

Entered in the
National Register

- ☒ entered in the National Register
_____ See continuation sheet.
☐ determined eligible for the
National Register
_____ See continuation sheet.
☐ determined not eligible for the
National Register
☐ removed from the National Register
_____ other (explain): _____

Guy M. Lapley 11/12/93

for _____
Signature of Keeper Date
of Action

=====

6. Function or Use

=====

Historic: DOMESTIC

Sub: Single dwelling

Current: DOMESTIC

Sub: Single dwelling

=====

7. Description

=====

Architectural Classification:

Italianate

Folk Victorian

Colonial Revival

Craftsman

Other Description: N/A

Materials:	foundation	<u>Stucco/brick/stone</u>	roof	<u>Asphalt</u>
	walls	<u>Wood/Weatherboard</u>	other	<u>Wood shingles</u>
		<u>Wood/Novelty siding</u>		
		<u>Vinyl</u>		

Describe present and historic physical appearance. X See continuation sheet.

=====

8. Statement of Significance

=====

Certifying official has considered the significance of this property in relation to other properties: Locally.

Applicable National Register Criteria: C

Criteria Considerations (Exceptions): N/A

Areas of Significance: ARCHITECTURE

Period(s) of Significance: 1885-1926

Significant Dates: N/A

Significant Person(s): N/A

Cultural Affiliation: N/A

Architect/Builder: Unknown

State significance of property, and justify criteria, criteria considerations, and areas and periods of significance noted above.
X See continuation sheet.

United States Department of the Interior
National Park ServiceNational Register of Historic Places
Continuation SheetSection number 7 Page 1

Summary

Principally located along the first two blocks of southeast 3rd Street, the Bentonville Third Street Historic District is composed of a total of fourteen principal residences, eleven of which are contributing; also included are a total of ten outbuildings, nine of which are contributing. The construction dates range from 1885 to 1926 and the architectural styles, reflective of that period, include the Italianate, the Folk Victorian, the Colonial Revival, and the Craftsman. The three non-contributing residences were all originally built during the period of significance but have been inappropriately altered over time.

Elaboration

The following fourteen properties are included within this district:

CONTRIBUTING PROPERTIES

BE0001 *Elliott House* 303 SE Third St. (NR-listed 01/20/78)

A two-and-one-half story, brick masonry residence designed in a combination of the Italianate and French Second Empire styles. Constructed in 1887.

Also included is a contributing outbuilding, a single-story, gable roof garage building.

BE0002 *McAndrews-Pace House* 208 SE Third St.

A two-story, wood frame residence originally designed as a Folk Victorian style structure, but which has been updated with a Craftsman-style wrap-around porch. The northern and western elevations feature a rich assortment of ornament characteristic of the Folk Victorian style, including jig-sawn details at the beveled corners of both the dormer and the western gabled bay and an unusual jig-sawn screen door. The combination gable/hipped roof is covered with asphalt shingles, the wall surfaces are sheathed with both imbricated shingles and wood weatherboard, and the entire building rests upon a continuous stucco-over-brick foundation. Constructed in 1890.

Also included is a contributing outbuilding, a single-story, gable roof automobile garage building.

United States Department of the Interior
National Park ServiceNational Register of Historic Places
Continuation SheetSection number 7 Page 2

BE0003 *Simpson House* 209 SE Third St.

A one-and-one-half story, wood frame residence originally designed as a modest Folk Victorian residence, but which has been augmented with a later, Craftsman-style wrap-around porch on its southern and eastern elevations. Significant exterior details include the imbricated shingles in both the wall dormers and atop the projecting beveled bay on the eastern elevation, and the rather elegant wood brackets and stylized dentil decoration beneath the cornice and around certain windows. The combination gable/hipped roof is covered with asphalt singles, the walls are sheathed in both imbricated shingles and wood weatherboard, and a continuous brick foundation supports the building. Constructed c. 1900.

BE0004 *Rice-Williams House* 204 SE Third St. (NR-listed 11/01/84)

A two-and-one-half story, brick masonry residence designed in a relatively high-style version of the Italianate. Features decorative wood cornice brackets, arched window and door openings, and arched wood porch support decoration on the northeast corner porch. Constructed c. 1885.

BE0005 *Barnett House* 207 SE Third St.

A single-story, wood frame residence designed in a minimal version of the Colonial Revival. Characteristic features include the six-over-six wood sash windows, the friezeboards and cornice returns, and the slightly-projecting wood window crowns. The intersecting gable roof is covered with asphalt shingles, the walls are weatherboarded and a continuous stucco-over-brick foundation supports the building. Constructed in 1920.

BE0006 *Burns House* 108 SE Third St.

A one-and-one-half story, wood frame residence designed in a restrained version of the Folk Victorian style. Exterior details are largely limited to the use of imbricated wood shingles in the pediments of the gable ends and the large windows that were popular for many designs of this style. The combination gable/hipped roof is covered with asphalt shingles (as are the roofs of all additions and porches), the walls are sheathed in weatherboard and wood shingles, and a continuous stone foundation supports the building. Constructed in 1910.

Also included is a contributing outbuilding, a single-story, combination gable/shed roof

United States Department of the Interior
National Park ServiceNational Register of Historic Places
Continuation SheetSection number 7 Page 3

storage building.

BE0007 *Conner House* 205 SE Third St.

A one-and-one-half story, wood frame residence designed in an uncommon transitional style: Folk Victorian/Craftsman bungalow. The imbricated wood shingles and leaded glass panes of the roof dormers recalls the former style, while the decorative exposed rafters and the low, spreading cornices throughout recall the latter. The complex combination hipped roof is covered with asphalt shingles, the walls are sheathed with novelty siding and the entire building rests upon a continuous stone foundation. Constructed c. 1915.

Also included is a non-contributing outbuilding, a single-story, gable roof garage building.

BE0008 *Patton House #1* 106 SE Third St.

A one-and-one-half story, wood frame residence designed in a transitional Folk Victorian/Colonial Revival style. Significant exterior features include the employment of beveled projecting gables, jig-sawn decorative details and delicate Classical columns supporting the original wrap-around front porch. The combination hipped/gable roof is covered with asphalt shingles, the walls are weatherboarded and the main building is supported by a continuous brick foundation, while the porch rests upon brick piers. Constructed in 1905.

BE0013 *Patton House #2* 231 South Main St.

A one-and-one-half story, wood frame residence designed in a transitional Folk Victorian/Colonial Revival style. Significant exterior features include the stylized Classical vegetal ornament on the Classical porch frieze, the imbricated wood shingles adorning the front and side projecting gable arches, and the slightly-projecting Classical window crowns. The intersecting gable roof and the porch roofs are all covered with asphalt shingles, the walls are weatherboarded and the entire building rests upon a continuous stone foundation, with only the porch being supported by stone piers. Constructed in 1906.

Also included is a contributing outbuilding, a single-story, gable roof double automobile garage building.

United States Department of the Interior
National Park ServiceNational Register of Historic Places
Continuation SheetSection number 7 Page 4

BE0015 *Dr. C. E. Hurley House* 225 South Main St.

A one-and-one-half story, wood frame residence designed in the Stick Style, a relatively uncommon style in Arkansas (a relatively large addition at the northern end continues this style and is sympathetic to the original section). Significant exterior features include the imbricated wood shingles in the pediments of the projecting gables, the tall, narrow one-over-one wood sash windows, and, above all, the decorative applied stickwork that subdivides the exterior wall planes into smaller panels, lending the walls the textured and patterned appearance characteristic of this late nineteenth-century style. The combination gable/hipped/shed roof is covered with asphalt shingles, the walls are sheathed with wood weatherboard in addition to the afore-mentioned shingles and decorative stickwork, and the structure rests upon a continuous brick foundation. Constructed c. 1890.

Also included are two contributing outbuildings, a single-story, gable roof double automobile garage building and a small tenant building/servant's quarters.

BE0017 *Croon House* 223 South Main St.

A single-story, wood frame residence designed in a relatively high-style rendering of the Craftsman idiom. The significant exterior features include the typical gable-roof porch supported on combination brick piers, exposed rafters, knee braces, and the battered walls around the entire building. The gable roofs are covered with asphalt shingles, the walls are artificially-sided (though the new siding duplicates the form of the original siding exactly and the dimensions closely), and a continuous cast concrete foundation supports the building. Constructed in 1926.

Also included is a contributing outbuilding, a single-story, gable roof double automobile garage building.

NON-CONTRIBUTING PROPERTIES

BE0009 (Sisk House; 109 SE 3rd St.), BE0010 (McNelly House; 301 S. Main) and BE0011 (Crabtree House; 201 SE 3rd St.), all residences constructed around the turn of the century, have been artificially-sided in a manner insensitive to their historic appearance, and have therefore been determined to be non-contributing. However, they do preserve the residential scale and site character of the district and are not visually obtrusive.

It should also be noted that BE0009 and BE0011 each have contributing outbuildings, both of

**United States Department of the Interior
National Park Service**

**National Register of Historic Places
Continuation Sheet**

Section number 7 Page 5

which are single-story, gable roof, wood frame automobile garages.

United States Department of the Interior
National Park Service

National Register of Historic Places
Continuation Sheet

Section number 8 Page 1

Summary

Criterion C, local significance

As noted in the historic context for the *Historic Resources of Benton County (Partial Inventory: Historic and Architectural)* Multiple Property Nomination, Bentonville was the primary site of most of the high-style architecture being constructed within the county during the period of significance (c. 1855 - c. 1937), largely due to both its location on the Frisco Railroad line and its status as the county seat. The residential architecture within the Bentonville Third Street Historic District is reflective of both the prosperity and growth experienced within Bentonville after the Civil War, when the proliferation of the railroads and the explosion of the fruit growing industry throughout the county helped to make Bentonville the governmental, commercial, and transportation hub of the county. The arrival of the railroad in particular (1881) brought new architectural styles and tastes into the heart of a county that had previously experienced rather little of it. Such styles as the Italianate, Folk Victorian, Colonial Revival and Craftsman were all reflective of the effect of the railroad and the new cultural influences it introduced.

Yet the Bentonville Third Street Historic District is eligible under Criterion C with local significance by virtue of its status as the ensemble of historic residential architecture most reflective of the modest, stylistically-diverse building tradition that was far more common in such railroad communities during this period than the better-known collections of pure high-style design. The overall scale of these residences is more modest than elsewhere in Bentonville (such as the West Central Avenue Historic District, NR-listed 10/22/92) and the individual houses tend to reflect the evolution of popular styles during this period: some original designs reflect the influence of two or more styles, and other more pure designs were later modified with such "improvements" as porches and rear additions that reflect newer, more "modern" national styles. As such the Bentonville Third Street Historic District, instead of presenting a collection of undiluted, high-style residential architecture, reflects the architectural evolution of a relatively middle-class neighborhood from the late nineteenth to the early twentieth century.

9. Major Bibliographical References

See "Historic Resources of Benton County, Arkansas," Section 9.

___ See continuation sheet.

Previous documentation on file (NPS):

- preliminary determination of individual listing (36 CFR 67) has been requested.
- previously listed in the National Register
- previously determined eligible by the National Register
- designated a National Historic Landmark
- recorded by Historic American Buildings Survey # _____
- recorded by Historic American Engineering Record # _____

Primary Location of Additional Data:

- X State historic preservation office
- Other state agency
- Federal agency
- Local government
- University
- Other -- Specify Repository: _____

10. Geographical Data

Acreage of Property: Approximately ten

UTM References:	Zone	Easting	Northing	Zone	Easting	Northing	
A	<u>15</u>	<u>391580</u>	<u>4025450</u>	B	<u>15</u>	<u>391870</u>	<u>4025440</u>
C	<u>15</u>	<u>391860</u>	<u>4025340</u>	D	<u>15</u>	<u>391580</u>	<u>4025360</u>

___ See continuation sheet.

Verbal Boundary Description: ___ See continuation sheet.

Lots 6, 8 and 9, Block 2; the northern 2/3 of Lot 10 and all of Lot 11, Block 3; Lots 7 and 8, Block 4; Lots 1 and 2, Block 5; and Lots 4, 5 and 6, Block 6, Railroad Addition to the City of Bentonville, Arkansas.

Boundary Justification: ___ See continuation sheet.

This boundary includes all the property historically associated with these resources that retains its integrity.

11. Form Prepared By

Name/Title: Kenneth Story, Architectural Historian

Organization: Arkansas Historic Preservation Program Date: 10/01/93

Street & Number: 323 Center Street, Suite 1500 Telephone: (501) 324-9880

City or Town: Little Rock State: AR Zip: 72201

United States Department of the Interior
National Park Service

National Register of Historic Places
Continuation Sheet

Section number _____ Page _____

Benton County MRA ARKANSAS

101. Bella Vista Water Tank

8/14/92

102. Sunset Hotel

8/14/92

103. Bentonville West Central Avenue
Historic District

104. Bentonville Third Street Historic District

11/12/93

UNITED STATES DEPARTMENT OF THE INTERIOR
NATIONAL PARK SERVICE

NATIONAL REGISTER OF HISTORIC PLACES
EVALUATION/RETURN SHEET

REQUESTED ACTION: NOMINATION

PROPERTY NAME: Bentonville Third Street Historic District

MULTIPLE NAME: Benton County MPS

STATE & COUNTY: ARKANSAS, Benton

DATE RECEIVED: 10/13/93 DATE OF PENDING LIST: 10/26/93
DATE OF 16TH DAY: 11/11/93 DATE OF 45TH DAY: 11/27/93
DATE OF WEEKLY LIST:

REFERENCE NUMBER: 93001202

NOMINATOR: STATE

REASONS FOR REVIEW:

APPEAL: N DATA PROBLEM: N LANDSCAPE: N LESS THAN 50 YEARS: N
OTHER: N PDIL: N PERIOD: N PROGRAM UNAPPROVED: N
REQUEST: N SAMPLE: N SLR DRAFT: N NATIONAL: N

COMMENT WAIVER: N

☒ ACCEPT ☐ RETURN ☐ REJECT 11/12/93 DATE

ABSTRACT/SUMMARY COMMENTS:

RECOM./CRITERIA
REVIEWER
DISCIPLINE
DATE

DOCUMENTATION see attached comments Y/N see attached SLR Y/N

CLASSIFICATION

___count ___resource type

STATE/FEDERAL AGENCY CERTIFICATION

FUNCTION

___historic ___current

DESCRIPTION

___architectural classification
___materials
___descriptive text

SIGNIFICANCE

Period Areas of Significance--Check and justify below

Specific dates Builder/Architect
Statement of Significance (in one paragraph)

___summary paragraph
___completeness
___clarity
___applicable criteria
___justification of areas checked
___relating significance to the resource
___context
___relationship of integrity to significance
___justification of exception
___other

BIBLIOGRAPHY

GEOGRAPHICAL DATA

___acreage ___verbal boundary description
___UTMs ___boundary justification

ACCOMPANYING DOCUMENTATION/PRESENTATION

___sketch maps ___USGS maps ___photographs ___presentation

OTHER COMMENTS

Questions concerning this nomination may be directed to

Phone

Signed Date



ELLIOTT HOUSE; BENTONVILLE THIRD ST. H.D.
BENTONVILLE, BENTON Co., ARKANSAS
PHOTOGRAPHED BY K. STORY
JUNE, 1993

NEGATIVE ON FILE AT AHPP
VIEW FROM SOUTHEAST

#BE0001



MC ANDREWS-PACE HOUSE; BENTONVILLE THIRD ST. H.D.

BENTONVILLE, BENTON Co., ARKANSAS

PHOTOGRAPHED BY K. STORY

JUNE, 1993

NEGATIVE ON FILE AT AHPP

VIEW OF Assoc. GARAGE FROM NORTHWEST

BE0002



Mc ANDREWS - PACE HOUSE ; BENTONVILLE THIRD ST. H.D.

BENTONVILLE, BENTON Co, ARKANSAS

PHOTOGRAPHED BY K. STORY

JUNE, 1993

NEGATIVE ON FILE AT AHPP

VIEW FROM NORTHEAST

#BE0002



MC ANDREWS - PACE HOUSE; BENTONVILLE THIRD ST. N. D.

BENTONVILLE, BENTON CO., ARKANSAS

PHOTOGRAPHED BY K. STORY

JUNE, 1993

NEGATIVE ON FILE AT AHPP

VIEW FROM NORTH

BE0002



SIMPSON HOUSE; BENTONVILLE THIRD ST. H. D.

BENTONVILLE, BENTON CO., ARKANSAS

PHOTOGRAPHED BY K. STORY

DECEMBER, 1992

NEGATIVE ON FILE AT AHPP

VIEW FROM SOUTH

BE0003



SHIPSON HOUSE; BENTONVILLE THIRD STREET H. D.

BENTONVILLE, BENTON Co., ARKANSAS

PHOTOGRAPHED BY K. STORY

DECEMBER, 1992

NEGATIVE ON FILE AT ANPP

VIEW FROM SOUTHEAST

BE0003



RICE-WILLIAMS HOUSE; BENTONVILLE THIRD ST. H.D.
BENTONVILLE, BENTON Co., ARKANSAS
PHOTOGRAPHED BY K. STORY

JUNE, 1993

NEGATIVE ON FILE AT AHPP

VIEW FROM NORTHEAST

BE0004



BARNETT HOUSE; BENTONVILLE THIRD STREET HISTORIC DISTRICT

BENTONVILLE, BENTON CO., ARKANSAS

PHOTOGRAPHED BY R. STORY

DECEMBER, 1992

NEGATIVE ON FILE AT ANPP

VIEW FROM SOUTHWEST

BE0005



4
3
0
6

BURNS HOUSE; BENTONVILLE THIRD ST. H.D.

BENTONVILLE, BENTON CO., ARKANSAS

PHOTOGRAPHED BY K. STORY

JUNE, 1993

NEGATIVE ON FILE AT AHPP

VIEW FROM EAST OF OUTBUILDING

BE0006



BURNS HOUSE; BENTONVILLE THIRD ST. H. D.

BENTONVILLE, BENTON CO., ARKANSAS

PHOTOGRAPHED BY K. STORY

JUNE, 1993

NEGATIVE ON FILE AT AHPP

VIEW FROM NORTHEAST

#BE0006



CONNER HOUSE; BENTONVILLE THIRD STREET HISTORIC DISTRICT

BENTONVILLE, BENTON CO., ARKANSAS

PHOTOGRAPHED BY K. STORY

DECEMBER, 1992

NEGATIVE ON FILE AT ANPP

VIEW FROM SOUTHEAST

BE0007



RISK HOUSE; BENTONVILLE THIRD STREET H.D

BENTONVILLE, BENTON Co., ARKANSAS

PHOTOGRAPHED BY K. STORY

DECEMBER, 1992

NEGATIVE ON FILE AT AHPP

VIEW OF OUTBUILDING FROM EAST

BE0009



ISK House; BENTONVILLE THIRD STREET HISTORIC DIST.

BENTONVILLE, BENTON CO., ARKANSAS

PHOTOGRAPHED BY K. STORY

~~DECEMBER, 1992~~ JUNE, 1993

NEGATIVE ON FILE AT AHPP

VIEW FROM ~~South~~ EAST

BE0009



Mc NELLY HOUSE; BENTONVILLE THIRD St. H. D.

BENTONVILLE, BENTON Co., ARKANSAS

PHOTOGRAPHED BY K. STORY

JUNE, 1993

NEGATIVE ON FILE AT AHPP

VIEW FROM NORTH

BE0010



~~CRABTREE~~ ~~PATTON~~ House #2; BENTONVILLE THIRD STREET H. D.

BENTONVILLE, BENTON Co., ARKANSAS

PHOTOGRAPHED BY R. STORY

DECEMBER, 1992

NEGATIVE ON FILE AT AAPP

VIEW FROM ^{SOUTH} ~~EAST~~ OF ASSOC. OUTBUILDING

#~~BE0013~~ BE0011



PATTON HOUSE #2; BENTONVILLE THIRD ST. H.D.

BENTONVILLE, BENTON CO., ARKANSAS

PHOTOGRAPHED BY R. STORY

JUNE, 1993

NEGATIVE ON FILE AT AHPP

VIEW OF OUTBUILDING FROM EAST

BE0013



PATTON HOUSE #2; BENTONVILLE THIRD ST. H.D.

BENTONVILLE, BENTON CO., ARKANSAS

PHOTOGRAPHED BY K. STORY

JUNE, 1993

NEGATIVE ON FILE AT AHPP

WESTERN PORCH DETAIL

#BE0013



PATTON HOUSE #2; BENTONVILLE THIRD ST. H. D.

BENTONVILLE, BENTON CO., ARKANSAS

PHOTOGRAPHED BY K. STORY

JUNE, 1993

NEGATIVE ON FILE AT AHPP

VIEW FROM SOUTHWEST

BE 0013



DR. C. E. HURLEY HOUSE; BENTONVILLE THIRD ST. H.D.
BENTONVILLE, BENTON CO., ARKANSAS

PHOTOGRAPHED BY K. STORY

JUNE, 1993

NEGATIVE ON FILE AT AHPP

VIEW OF ASSOC. OUTBUILDING FROM SOUTHWEST

BE0015



DR. C. E. HURLEY HOWE; BENTONVILLE THIRD ST. H. D.

BENTONVILLE, BENTON CO., ARKANSAS

PHOTOGRAPHED BY K. STORY

JUNE, 1993

NEGATIVE ON FILE AT AHPP

VIEW FROM EAST

#BE0015



CROON HOUSE; BENTONVILLE THIRD ST. H. D.

BENTONVILLE, BENTON CO., ARKANSAS


PHOTOGRAPHED BY K. STORY

JUNE, 1993

NEGATIVE ON FILE AT AHPP

VIEW OF GARAGE FROM EAST

* BE0017



Maped, edited, and published by the Geological Survey
Control by USGS and USC&GS
Topography by photogrammetric methods from aerial
photographs taken 1968. Field checked 1970
Polyconic projection. 1927 North American datum
10,000-foot grid based on Arkansas coordinate system, north zone
1000-meter Universal Transverse Mercator grid ticks,
zone 15, shown in blue
Red tint indicates areas in which only landmark buildings are shown
To place on the predicted North American Datum 1983
move the projection lines 5 meters south and
17 meters east as shown by dashed corner ticks
Revisions shown in purple compiled from aerial photographs taken 1980
and other sources. This information not field checked. Map edited 1982
Purple tint indicates extension of urban area

UTM GRID AND 1982 MAGNETIC NORTH
DECLINATION AT CENTER OF SHEET

SCALE 1:24 000
1000 0 1000 2000 3000 4000 5000 6000 7000 FEET
5 10 15 20 25 30 KILOMETER
CONTOUR INTERVAL 10 FEET
NATIONAL GEODETIC VERTICAL DATUM OF 1929

THIS MAP COMPLIES WITH NATIONAL MAP ACCURACY STANDARDS
FOR SALE BY U. S. GEOLOGICAL SURVEY, DENVER, COLORADO 80225, OR RESTON, VIRGINIA 22092
AND ARIZONA-BENTON CO. 7.5 MINUTE SERIES (TOPOGRAPHIC)
A FOLDER DESCRIBING TOPOGRAPHIC MAPS AND SYMBOLS IS AVAILABLE ON REQUEST

ROAD CLASSIFICATION
Primary highway, all weather, hard surface
Secondary highway, all weather, hard surface
Light-duty road, all weather, improved surface
Unimproved road, fair or dry weather
U. S. Route
State Route

QUADRANGLE LOCATION
BENTONVILLE SOUTH, ARK.
N3615-W9407.5/7.5
1970
PHOTOREVISED 1982
DMA 7156 I SW-SERIES V884


Bentonville Third Street Historic District Bentonville, Benton County, Arkansas


Approximate Scale: 1" = 100'

Boundary: - - - - -

Contributing Resources: (C)

Non-Contributing Resources: NC





ARKANSAS
HISTORIC
PRESERVATION
PROGRAM

October 4, 1993

Carol D. Shull
Chief of Registration
United States Department of the Interior
National Register of Historic Places
National Park Service
800 North Capitol Street, Suite 250
Washington, DC 20002

RECEIVED

OCT 13 1993

NATIONAL
REGISTER

RE: Bentonville Third Street Historic District
Bentonville, Benton County

Dear Carol:

We are enclosing for your review the nomination of the above referenced property. The Arkansas Historic Preservation Program has complied with all applicable nominating procedures and notification requirements in the nomination process.

Thank you for your consideration in this matter.

Sincerely,

Cathy Buford Slater
State Historic Preservation Officer

CBS:kg

Enclosures

