RECEIVED

United States Department of the Interior National Park Service

National Register of Historic Places Registration Form

This form is for use in nominating or requesting determinations of eligibility for individual properties or districts. See instructions in Guidelines for Completing National Register Forms (National Register Bulletin 16). Complete each item by marking "x" in the appropriate box or by entering the requested information. If an item does not apply to the property being documented, enter "N/A" for "not applicable." For functions, styles, materials, and areas of significance, enter only the categories and subcategories listed in the instructions. For additional space use continuation sheets (Form 10-900a). Type all entries.

1. Name of Property

historic name

other names/site number Residencia Heygler

2. Location								
street & number Calle	Liceo	#51					not for publication	N/A
city, town Mayagüez	-						vicinity	N/A
state Puerto Rico	code	PR	county May	yagüez	code	097	zip code	00708

3. Classification

Ownership of Property	Category of Property	Number of Res	ources within Property
x private	🔀 building(s)	Contributing	Noncontributing
public-local	district	1	buildings
public-State	site	0	sites
public-Federal	structure structure	0	structures
	object	0	objects
		1	Total

Name of related multiple property listing: N/A

other, (explain:)

State/Federal Agency Certification 4.

As the designated authority under the National Historic Preservation Act of 1966, as an	ards for registering properties in the ments set forth in 36 CFR Part 60. See continuation sheet. • <u>April 11, 1988</u>
Signature of certifying official	Date
State Historic Preservation Officer	
State or Federal agency and bureau	
In my opinion, the property meets does not meet the National Register criteria.	See continuation sheet.
Signature of commenting or other official	Date
State or Federal agency and bureau	
5. National Park Service Certification	
I, hereby, certify that this property is:	
Image: Pentered in the National Register. Image: Pentered in the National Register. Image: Pentered in the National Register. Image: Pentered in the National Register. Image: Pentered in the National Register. Image: Pentered in the National Register. Image: Pentered in the National Register. Image: Pentered in the National Register. Image: Pentered in the National Register. Image: Pentered in the National Register. Image: Pentered in the National Register. Image: Pentered in the National Register.	7/12/88
determined not eligible for the	
National Register.	
removed from the National Register.	

JUN 3 1988

> NATIONAL REGISTER

Number of contributing resources previously

listed in the National Register ___0

Historic Functions (enter categories from instructions)	Current Functions (enter categories from instructions)			
Domestic/Single Dwelling	Dometic/Single Dwelling			
bomestic/single bwerring				
7. Description				
Architectural Classification	Materials (enter categories from instructions)			
(enter categories from instructions)	a second s			
	foundation Masonry Rubble			
Spanish Colonial/Neo-Classical	walls brick and stucco-exterior			
	brick, stucco, wood			
	roof clay tile and zinc			
	other wood doors, cast iron balustrad			

Describe present and historic physical appearance.

The Heygler Residence is an attached, one-level, plastered, masonry residential structure on the southeast corner of Calle Liceo and Calle Sol in the historic, urban center of Mayagüez. The general volume of the structure consists of an U-shape plan wrapping around an inner courtyard facing east and articulated by a massive arcaded loggia on the main facade facing west. The flat, masonry roof (covered with tin sheets in the early 20th century) pitches inward towards the inner courtyard on all sides, in the manner of Roman impluvia, an element typical of traditional Puerto Rican urban dwellings.

The main facade consits of two distinctly articulated sections: on the north by a six-bay arcade, and on the south by a two bay entrance. The arcade is supported by chamfered Tuscan pillars on pedestals, save the second pillar from the corner, which seems to have failed and has since been replaced by a non-contributing concrete post. A series of five simplified, Roman amphorae in bas relief articulates each pandrel of the arcade.

The loggia is accessed from the north through a smaller arch on the corner. Within the loggia a series of four flat arched doorways with planar surrounds and lintels access the interior. Each bay contains solid hardwood double-doors that open onto the loggia with louvered double-doors set behind them. The simpler, two-bay southern section of the house consists of openings similar to these within the arcade.

The facade composition is capped by a simple, continuous cornice which wraps around the structure, and a solid parapet which follows the rythmic modulation of the arcade.

The north facade rests on a plinth at the level of the main loggia. A series of simple pilasters creates wide bays, each containing one window. Each opening contains solid hardwood double-shutters with louvered casement windows within. Planar surrounds and molded cornice frame the windows, each composition supported by a pair of culvilinear relief "legs" at its base.

8. Statement of Significance		
Certifying official has considered the significance of this pro	perty in relation to other properties:	
Applicable National Register Criteria A B X C	; D	
Criteria Considerations (Exceptions)		
Areas of Significance (enter categories from instructions)	Period of Significance 1830,1898	Significant Dates c1830
	Cultural Affiliation N/A	
Significant Person	Architect/Builder N/A	

State significance of property, and justify criteria, criteria considerations, and areas and periods of significance noted above.

The Heyliger Residence is one of the oldest and best examples of the arcade-balcony house so prevalent in the urban areas of the western Puerto Rico, and especially characteristic of Mayagüez.

Current owners date the structure to the 1830's, although no official document has been found to provide a precise date of construction. The lot where it is located already appears as built upon on a map of the city compiled after the famous fire of 1841. The house may very easily be somewhat older than believed, and is perhaps one of the city's oldest houses.

The Heyliger house exhibits a very competent handling of classical ornamental mouldings (especially the upper cornice and the capitals of the pillars). The use of the amphorae motif in the spandrels of the arcade, although unusual, anticipates the use of similar, flowing, curvilinear shapes, rendered in different materials and applied in diverse locations, a trademark of Mayagüez architecture of the late 19th and early 20th centuries.

Although the interior has been altered somewhat, the exterior appears to be completely original.

An excellent example of the traditional Mayagüez house, the Heyliger Residence deserves preservation attention since it is one of a small number of prototype homes to survive the series of natural catastrophes (Fire 1841, Hurricane 1899, Earthquake, 1918) suffered by the city of Mayagüez.

. . . .

9. Major Bibliographical References

See enclosed site plan	
Verbal Boundary Description	
Lambert: 18° 12' 08" 67° 08' 08"	See continuation sheet
UTM References A	B L L L L L L L L L L L L L L L L L L L
10. Geographical Data Acreage of property less than one acre (507)	sq. mts.)
Previous documentation on file (NPS): preliminary determination of individual listing (36 CFR 67) has been requested previously listed in the National Register previously determined eligible by the National Register designated a National Historic Landmark recorded by Historic American Buildings Survey # recorded by Historic American Engineering Record #	 See continuation sheet Primary location of additional data: State historic preservation office Other State agency Federal agency X Local government University Other Specify repository: Mayagüez Archives
Rigau, Jorge. <u>Enigma y Permanencia d</u> <u>El Nuevo Día</u> , September 18, 1984.	<u>e la Sultana del Oeste</u> . Periódico
Gaudier y Cabassa, Martín. <u>El Mayagü</u> Puerto Rico, 1959.	ez de Ayer y Hoy. Mayagüez,
September, 1984.	nary Nat., Reg. Nom. Form. SHPO,

See continuation sheet

11. Form Prepared By

name/title _ Félix J. del Campo/Héctor Santiago	
organization Puerto Rico State Historic Preser. Office	date December, 1987
street & number San José 109 St.	
city or town <u>San Juan</u>	


United States Department of the Interior National Park Service

National Register of Historic Places Continuation Sheet

Section number ____7 Page __1

Once inside, it is evident that the original, massive, stuccoed-brick walls and claytile ceilings have been covered with early 20th century wooden partitions and lattice-work. What were probably originally brick floors were also re-tiled with late 19th century decorative ceramic floor tiles typical of most Puerto Rican houses of the period. The interior courtyard has also been altered, since its gallery is now concealed behind wooden lattices spanning the pillars.

Although the structure has suffered some alterations, these are mostly historic and of reversible character. Very little original material has been lost to time.



SCALE: 1:500

United States Department of the Interior National Park Service

National Register of Historic Places Continuation Sheet

Section number _____ Page _____

SUPPLEMENTARY LISTING RECORD

NRIS Reference Number: 88000962 Residencia Heygler Property Name

Date Listed: 7/12/88 Mayaquez PR County State

Multiple Name

This property is listed in the National Register of Historic Places in accordance with the attached nomination documentation subject to the following exceptions, exclusions, or amendments, notwithstanding the National Park Service certification included in the nomination documentation.

Amy chlagel Signature of the Keeper

Amended Items in Nomination:

The period of significance for this nomination reflects the period in which this building defined a specific architectural style on the island. United States possession of the island changed the architectural styles dramatically.

Discussed and concurred in by the Puerto Rico HPO on July 11, 1988.

DISTRIBUTION: National Register property file Nominating Authority (without nomination attachment)