


405

United States Department of the Interior
National Park Service



National Register of Historic Places Registration Form

This form is for use in nominating or requesting determinations for individual properties and districts. See instruction in How to Complete the National Register of Historic Places Registration Form (National Register Bulletin 16A). Complete each item by marking "x" in the appropriate box or by entering the information requested. If an item does not apply to the property being documented, enter "N/A" for "not applicable." For functions, architectural classifications, materials and areas of significance, enter only categories and subcategories from the instructions. Place additional entries and narrative items on continuation sheets (NPS Form 10-900a). Use a typewriter, word processor, or computer, to complete all items.

1. Name of Property

historic name Jorgensen, Victor H. and Marta, House

other names/site number _____

2. Location

street & number 2643 SW Buena Vista Drive not for publication

city or town Portland vicinity

state Oregon code OR county Multnomah code 5251 zip code 97201

3. State/Federal Agency Certification

As the designated authority under the National Historic Preservation Act, as amended, I hereby certify that this X nomination request for determination of eligibility meets the documentation standards for registering properties in the National Register of Historic Places and meets the procedural and professional requirements set forth in 36 CFR Part 60. In my opinion, the property X meets does not meet the National Register criteria. I recommend that this property be considered significant nationally statewide X locally.

[Signature] Signature of certifying official/Title Deputy SHPO Date 3-28-08

Oregon State Historic Preservation Office
State or Federal agency and bureau

4. National Park Service Certification

I hereby certify that the property is:	Signature of the Keeper	Date of
Action	<u>[Signature]</u>	<u>5-15-08</u>
<input checked="" type="checkbox"/> entered in the National Register <u> </u> See continuation sheet.		
<u> </u> determined eligible for the National Register <u> </u> See continuation sheet.		
<u> </u> determined not eligible for the National Register		
<u> </u> removed from the National Register		
<u> </u> other (explain):		

Jorgensen, Victor H. and Marta, House
Name of Property

Multnomah Co., OR
County and State

5. Classification

Ownership of Property
(check as many as apply)

- private
- public - local
- public - state
- public - Federal

Category of Property
(check only one box)

- building(s)
- district
- site
- structure
- object

Number of Resources within Property
(Do not include previously listed resources in the count)

Contributing	Noncontributing	
1		buildings
		sites
		structures
		objects
1	0	Total

Name of related multiple property listing
(enter "N/A" if property is not part of a multiple property listing)

N/A

Number of contributing resources previously listed in the National Register

0

6. Function or Use

Historic Functions
(enter categories from instructions)

DOMESTIC: Single Dwelling

Current Functions
(Enter categories from instructions)

DOMESTIC: Single Dwelling

7. Description

Architectural Classification
(Enter categories from instructions)

LATE 19TH AND EARLY 20TH CENTURY REVIVALS
MODERN MOVEMENT

Materials
(Enter categories from instructions)

foundation: CONCRETE

walls: STUCCO

roof: WOOD

Other: _____

Narrative Description
(Describe the historic and current condition of the property on one or more continuation sheets)

See continuation sheets.

United States Department of the Interior
National Park Service

National Register of Historic Places Continuation Sheet

Section number 7 Page 1

SUMMARY

The Jorgensen House is located at 2643 SW Buena Vista Drive in the Southwest Hills neighborhood of Portland. It was exactly designed by noted architect Herman Brookman. The asymmetrically arranged house is set on a very steep hillside lot overlooking the city of Portland. The house is hard to classify; the style is a mixture of Spanish Colonial Revival and Moderne, but distinctively Brookman in its impeccable design and detail. The main elevation is close to the street, with a welcoming entrance courtyard separated from the driveway by a well-integrated garage wing. The house appears to be only 1 ½ stories from the street, but in actuality it is a complex split-level assembly of six levels. Constructed of hand-troweled stucco with a cedar-shingle cross-gable roof, the house is understated from the front, but in the Brookman fashion, every detail was designed to work together seamlessly.

The Jorgensen House has many of Herman Brookman's signature elements. Brookman was very skilled at designing houses on steep lots like that of the Jorgensen House. The entrance is recessed, like that of the Baruh-Zell House. The windows are casement. Ornamental iron work decorates the façade. The front elevation has a more traditional look while the rear is distinctly more modern. The bay window is crowned by a ram's head, a Brookman hallmark. Brookman is well known for his architectural skill, unique and well thought-out plans, attention to detail, and unique blend of traditional and modern elements. The Jorgensen House is an excellent example of this.

Constructed in 1929, the Jorgensen House retains a very high degree of integrity. The house remains largely unchanged, with the exception of the kitchen and some bathrooms, and some other minor alterations.

SETTING

The Jorgensen House is located in the established and affluent neighborhood of Southwest Hills in Portland, Oregon. The neighborhood is characterized by its winding roads, lush green hills, and large, well-tended homes, many with spectacular views. Houses on Buena Vista Drive are set close together and close to the street, with narrow manicured gardens. There are no sidewalks. Lots on the east side of the street drop off precipitously to the east, affording a panoramic view of the city and the mountains beyond. The Jorgensen House is set at about 680 feet elevation and faces west. The house is set on a slight angle on the lot to take full advantage of the eastern views. The crest of the hill is just across Buena Vista Drive to the west.

The front of the house is close to the street, with mature shrubs in the narrow garden between the garage and the street. (see exterior for description of the entrance court).

The rear yard is very steep and has a naturalistic style. Brookman designed the original garden plan. A rounded terrace overlooks the yard. The garden level of the lot has a narrow grassy area bordered in shrubs. A path

United States Department of the Interior
National Park Service

National Register of Historic Places Continuation Sheet

Section number 7 Page 2

originally led down to a small pond at the foot of the slope. The current owner has reworked the stone steps and mulch paths that switch back down the hill, and added plantings. Stone retaining walls are located just below the garden level of the house. A large poured-concrete retaining wall is located about half way down the slope, anchored by steel tie bars.

The north and south walls of the house are very close to the property lines. Concrete steps fill the space between the north wall and the property line. The south property line is marked by a concrete retaining wall and a steep planted hillside along the house.

PLAN

The Jorgensen House has a split-level plan containing 4902 square feet of finished living space on six intersecting levels.

The irregular plan consists of long side gable volume intersected with several cross-gables, the largest of which houses the garage and projects from the front of the main block of the house. The primary elevation of the house faces west-southwest toward the street.

EXTERIOR DESCRIPTION

The exterior of the Jorgensen house is sheathed in "natural texture" stucco with a prominent cedar shingle roof. The main (west) elevation is asymmetrical and understated, consisting of two front gables projecting from a flanking-gable main volume (Drawing 6). The larger of the projecting front gables, which houses the garage, essentially divides the façade into two sections, the main entrance and the auto entrance. The house is best approached coming up Buena Vista Drive from the south, where the gabled main entrance is visible, tucked in between the garage wing and the main block of the house. The front door is accessed from a sunken entrance courtyard to the south of the garage wing. From the street, semi-circular stone steps lead down into the courtyard that contains a Japanese style garden and a flagstone walk, which replaced the original deteriorated cast concrete stones. In an example of the control Brookman exerted over his projects, he created a plan of the stones for the front walk in which the exact dimensions of each stone to be laid are noted. However, the original specifications were changed, and the original walk was of cast concrete instead of natural stone.

In typical Brookman fashion, the front door is recessed. Over the entrance is a rough carved wood lintel, decorated with a geometric diamond design. The courtyard is lit by a decorative wrought iron light fixture that is one of the distinctive elements of this house. The fixture consists of a delicate star-shaped escutcheon mounted over the door and holding an iron rod connected with brass finials to a filigree globe lantern. The lantern is not original. The front door is walnut, with an inlaid parquet pattern and a brass peephole.

United States Department of the Interior
National Park Service

National Register of Historic Places Continuation Sheet

Section number 7 Page 3

To the south of the entrance courtyard, the land drops away from the road steeply, showing the below-grade levels of the main block of the house. A projecting bay window extending into a wall dormer decorates this section of the facade. The bay has a curvilinear gable decorated with Brookman's signature ram's head and a garland. A set of six single-light casement windows marks the lower section of the cantilevered bay, surmounted by three blind panels and topped with a set of three more single-light casements. The windows and panels are divided by projecting molding.

The projecting gabled garage extends from the main block of the house almost to the street. The gable end of the garage is unembellished save for the circular window covered in a custom designed cast iron grille, providing an understated focal point.

The two-bay garage is accessed from the auto court on the north side of the garage wing, making it invisible from the main entrance of the house. The other houses on the street have very prominent and visible front-facing garages, seemingly inevitable given the steepness of the hillside lots. But in a display of truly thoughtful design, Brookman made the garage all but disappear, despite the fact that it projects from the main façade of the house. A secondary entrance is tucked into the corner of the auto court, under a bellcast conical roof topped with a tall, delicate wrought iron weathervane depicting two birds sitting on an arrow. This secondary entrance door has eight lights divided by narrow molded mullions and muntins.

Behind the conical roof of the entrance, a massive stucco chimney rises from the north gable end of the main block of the house (Drawing 9). Extending from the gable end is a smaller projecting gable, and extending from the end of this gable is a smaller gable still, which extends within approximately three feet of the north property line. A stairway along the north property line accesses the rear yard.

The rear (east) elevation of the Jorgensen House offers a much more modern appearance than the street facade, characteristic of Brookman designs (Drawing 8). It has expansive ribbons of casement windows, clean, unembellished surfaces, and geometric forms. From this side, the house shows its true size, appearing to be three and one half stories. Its position at the crest of the steeply sloping lot makes it appear even more massive.

Two cross-gables project from the south end of the main flanking-gable block of the house. The central portion of this elevation is recessed to the main volume of the building. It has a ribbon of five casement windows on the first and second floors, with another set of two casements to the north on each floor.

The southernmost cross-gable is three-stories in height, and contains a central, vertical panel of windows. The windows in this bay are in sets of three single-light casements. The lowest level contains one set of windows, the middle level has a vertical stack of two sets, and the third level has one set and a semi-circular stucco balcony.

United States Department of the Interior
National Park Service

National Register of Historic Places Continuation Sheet

Section number 7 Page 4

Just to the north of this cross-gable is a projecting, gabled bay. This bay is cantilevered over the basement level, with a stepped base. The second and third stories have triple casements, separated by a blind panel. The second story windows have single light transoms, and the third story window is lancet-shaped. Beneath the bay on the basement level is a set of glazed French doors opening to the garden. Beside the doors is a large round window. A door on the center level of the north side of this bay accesses stairs leading down to the terrace. Extending from the north end of the main volume is a large side-gabled rear-projecting wing. It has three casements on the lower level, a ribbon of five casements on the second level, and a rectangular bay window on the third level with another ribbon of five casements.

The rear terrace extends from the north end of the house in an arc to the central recessed portion of the elevation where it follows the line of the house. The entire terrace and the stairs to the porch are enclosed with a recently added wrought iron railing. Stairs lead from the terrace to the upper garden level.

The south elevation of the house is fairly unembellished (Drawing 7). A large interior chimney rises from the center of the gable end. To the west of the chimney is a set of French doors located on the garden level, which is surmounted by a round balcony with a recessed door on the main level. Directly above this door is a lancet-shaped window on the top story.

The north elevation of the house is similarly understated (Drawing 9). The gable-end wall has a set of two casement windows on the main story and a lancet window on the top story. A one-story gabled projection shelters the side entrance, with steps along the property line to the street and the garden below.

INTERIOR DESCRIPTION

The interior of the Jorgensen House showcases Brookman's innovative use of space and skill in design. Because of the slope of the lot, the house is constructed with several levels both above and below the grade of the street. The resulting layout of the house is charmingly complex.

The interior details of the house show Brookman's obsessive attention to detail. The style of the interior is vaguely Spanish Colonial, with parabolic arches and vaulted ceilings. The walls in the public areas are mostly a hand troweled, "California" plaster, originally pigmented instead of painted. Woodwork is predominantly unpainted walnut. The baseboards and window and door surrounds are narrow. The doors are primarily three-panel in the public areas, while the bedrooms have single-panel doors. The rooms are heated by radiators enclosed in wood covers. The floors throughout the house are oak.

Entry Hall

The front door opens into a spacious foyer with a high vaulted ceiling rising to a point. Originally walls in the public rooms of the house were specified to have "California" plaster, which was pigmented and did not require painting. The hand-textured walls are now painted. The front door is a rich stained walnut in an inlaid parquet

United States Department of the Interior
National Park Service

National Register of Historic Places Continuation Sheet

Section number 7 Page 5

pattern. It is flanked by walnut closet doors, each with three recessed panels. On the south wall of the entry hall is a triple casement window. In the southeast corner of the room is a quarter-round built in cabinet. The light fixture in the entry hall, hanging from the center point of the ceiling, is not original but is compatible.

Directly opposite the front door, stairs descend a half-story to the two-story living room. Over the living room entry is a small lancet-shaped opening giving a peek into the upper level hall. On the north wall of the entry hall, stairs rise a half-story to a lancet shaped opening to the main hall of the bedroom wing.

Living Room

From the entry hall one can look down the open stairs into the dramatic sunken living room. The staircase has a plastered knee-wall balustrade capped with walnut and topped with a curving walnut rail with an elliptical profile. Flanking the stairs in the northwest corner of the living room is a square, cantilevered turret with a quarter-round, conical base.

The living room receives natural light from very large, stacked, single-light casement windows on the east and west walls. The south wall of the living room has a centered fireplace with a marble hearth. The fireplace is simple, set directly into the plaster wall with no tile surround. Instead, it has a Brookman designed brass frame with a brass valence. The walnut mantle has been recently added. It was designed by the homeowner to reflect the cantilevered turret in the corner of the living room. To the west of the fireplace is a set of single-light French doors opening to a small, half-round balcony. The high ceiling is marked by a wide plaster crown molding.

Enclosed Porch

Directly opposite the stairs a door opens to a small, enclosed sun porch with a red clay tile floor. This porch, overlooking the rear yard, has a door in the north wall with stairs leading down to the terrace. The door has a half-light and is surrounded by large single-light windows with unembellished, painted frames.

Dining Room

In the north wall of the living room a wide arched opening leads to the formal dining room. This room has an expansive ribbon of five casement windows in the west wall. The east wall has a dramatic recessed arch richly paneled with mahogany. The panels are divided by stylized fluted pilasters and a simple chair rail. Cabinets are built into the end walls of the arch. The north wall of the dining room has two three-paneled mahogany doors. The east door leads to the butler's pantry, while the west door leads to the service hall.

Butler's Pantry

The butler's pantry is a narrow room between the dining room and the kitchen with cabinetry lining the east and west walls. The room has white octagonal tile countertops with black tile edging, and white subway tile backsplash with a narrow green accent tile. The east wall has a double sink under a casement window flanked

United States Department of the Interior
National Park Service

National Register of Historic Places Continuation Sheet

Section number 7 Page 6

by glass cabinets. The west wall has a narrow u-shaped counter topped with glass front cabinets. All the woodwork is painted.

Kitchen

The kitchen has been completely remodeled and contains no original fabric. The sink is located in along the east wall under a ribbon of four casement windows. An island with a cook top is located in the center of the room, with a large ventilation hood over it. A small eating area is located in the west end of the kitchen. A door in the north wall of the room leads to the side entrance, while another leads to an original storage pantry.

Service Hall/Powder Room

A door in the southwest corner of the kitchen leads to the service hall. The walls and ceiling of this room are completely paneled in pale blue translucent melamine, most likely in the 1950s. This room accesses an original dumbwaiter and a small quarter-round shaped powder room. The powder room has a single below-grade window, an original toilet and a new sink. A door in the south wall of the service hall leads back into the dining room.

Den

Just to the north of the staircase on the main level is a half-flight of stairs down to the den (located beneath the entrance hall). This comfortable room is completely paneled in vertical mahogany board paneling. The ceiling is covered in acoustical tiles. The east wall has convex curving walls leading to a center accordion door leading to stairs to the basement play room. A triple casement window is centered on the south wall of the den, while the north wall has a narrow built in bookcase. This bookcase is the secret door to a hidden room, the use of which is unknown. It is finished in concrete with no windows or fixtures. It is not noted on the original plans for the house.

Basement/Play Room

The basement level of the house contains a large, bright playroom and bar. This room, which occupies the south end of the house, has knotty wood paneling, which is not original, and an acoustic tile ceiling. A fireplace with a brick surround is centered on the south wall, under a narrow mantel shelf. A set of French doors located in the southwest corner of the room open to the garden level. The east wall has a set of three casement windows and a set of French doors to the rear garden.

To the north of the play room is the large boiler room/laundry room, which is utilitarian in nature, except for the large round window over the laundry area overlooking the garden. To the north of the boiler room is a service hall with access to a darkroom, the dumbwaiter, a storage area, and in the northeast corner of the house, the former maid's room, and bathroom.

United States Department of the Interior
National Park Service

National Register of Historic Places Continuation Sheet

Section number 7 Page 7

Just north of the stairs to the den is another half flight of stairs leading to the work room, a utilitarian area beneath the den with windows looking out toward the south.

Upper Hall

Up the short staircase from the entry hall is the main hall accessing the bedrooms for the Jorgensen family. Accessed through a lancet-arch opening, this hall is just as dramatic as the rest of the house. It is rounded at the north end, and has a continuous barrel vaulted ceiling. Stained walnut cabinetry runs the length of the west wall of the hall. Two doors are set into the curving north end of the hall, one eight-light glazed door accesses the car court, and the other accesses the master bedroom. The east wall of the hall has two doors, one accessing the dumbwaiter and the other accessing a bedroom. The south end of the hall has a pair of lancet shaped openings, one leading to the entry hall, another up a half-flight to the girls' bedroom wing.

Master Suite

The master suite is located at the north end of the main hall. It has rounded-vault ceiling and picture molding. The east wall has a rectangular bay with a ribbon of seven casements. The master bath, accessed from a door in the southeast corner of the room, has been completely remodeled and contains no historic fabric.

Victor's Room

The second bedroom on this level is labeled "Victor's Room" on the plans, for the Jorgensen's son, Victor Jr. It is most notable for the ribbon of five casement windows with the spectacular view of the valley below. This room also has a private full bath, which has original tile walls but new tile floor and fixtures.

Marita's and Pollyann's Rooms and Bathroom

Up the stairs at the south end of the main hall is a secondary hall with access to the rooms that originally belonged to the Jorgensen's daughters, Marita and Pollyann. Both rooms are charming for their quaint irregular dormered ceilings. Pollyann's room, in the southeast corner of the house, has French doors to a half-round balcony on the east wall of the room. Marita's room has a lancet shaped window in a bay on the south wall. The two girls shared a bathroom at the east end of the hall. This bathroom is in nearly original condition and it is particularly beautiful. It has a vaulted ceiling following the shape of the large three-part lancet-shaped window overlooking the valley. The walls are covered in square celadon tiles, and the floor is tiled in tiny square celadon-mosaic tiles. The porcelain sink, toilet and tub match the celadon-green tiles.

ALTERATIONS

The Jorgensen House has a very high level of integrity. It retains a high degree of character defining elements with the usually expected alterations. The kitchen and master bathroom have been completely renovated and contain little historic fabric.

Jorgensen, Victor H. and Marta, House
Name of Property

Multnomah Co., OR
County and State

NPS Form 10-900-a

OMB Approval No. 1024-0018

United States Department of the Interior
National Park Service

National Register of Historic Places Continuation Sheet

Section number 7 Page 8

The current owner is in the process of correcting some deferred maintenance issues. A new cedar shingle roof has been installed. The entrance court has been renovated to repair damage caused by settling, but the character and style of the original courtyard was maintained. A new railing has been added along the street for safety. The original windows on the house have been replaced with exact matching wood casement windows with energy-efficient double-pane glass. The original retractable screens have been replaced in kind wherever feasible. The rear terrace has new wrought-iron railings for safety. The rear garden has been rehabilitated and the original stone stairs rebuilt with existing material.

Changes which likely occurred in the 1950s -60s include the paneling of the den and play room and the addition of the acoustical tile ceilings, and the melamine paneling in the service hall on the main level.

Jorgensen, Victor H. and Marta, House

Name of Property

Multnomah Co, OR

County and State

8. Statement of Significance

Applicable National Register Criteria

(Mark "x" in one or more boxes for the criteria qualifying the property for National Register listing).

- A Property is associated with events that have made a significant contribution to the broad patterns of our history.
- B Property is associated with the lives of persons significant in our past.
- C Property embodies the distinctive characteristics of a type, period, or method of construction or represents the work of a master, or possesses high artistic values, or represents a significant and distinguishable entity whose components lack individual distinction.
- D Property has yielded, or is likely to yield, information important in prehistory or history.

Areas of Significance

(Enter categories from instructions)

ARCHITECTURE

Period of Significance

1929

Significant Dates

1929

Criteria Considerations

(Mark "x" in all the boxes that apply)

Property is:

- A owned by a religious institution or used for religious purposes
- B removed from its original location
- C a birthplace or grave
- D a cemetery
- E a reconstructed building, object, or structure
- F a commemorative property
- G less than 50 years of age or achieved significance Within the past 50 years

Significant Person

(Complete if Criterion B is marked above)

Cultural Affiliation

Architect/Builder

Brookman, Herman, Architect

Narrative Statement of Significance

(Explain the significance of the property on one or more continuation sheets)

9. Major Bibliographical References

Bibliography (Cite books, articles, and other sources used in preparing the form on one or more continuation sheets) See continuation sheets

Previous documentation on file (NPS):

- preliminary determination of individual listing (36CFR67) has been requested
- previously listed in the National Register
- previously determined eligible by the National Register
- designated a National Historic Landmark
- recorded by Historic American Buildings Survey
- recorded by Historic American Engineering Record

Primary location of additional data:

- State Historic Preservation Office
- Other State agency
- Federal agency
- Local government
- University
- Other

Name of repository: U. of Oregon Library

United States Department of the Interior
National Park Service

National Register of Historic Places Continuation Sheet

Section number 8 Page 1

SUMMARY

The Victor H. and Marta Jorgensen House is significant under Criterion C as an excellent example of the masterful work of Herman Brookman. Constructed in 1929, the asymmetrical, split level house is set into a steep hillside lot on a narrow winding hillside road overlooking the city. The house exhibits many of the hallmarks of Brookman's work, including curving walls, ornamental ironwork, and extraordinary attention to detail. Brookman is well-known for his architectural skill, unique and well thought out plans, and seamless blend of traditional and modern elements. The Jorgensen House is an excellent example of Herman Brookman's residential design, and has many of the signature elements that are reflective of his attention to detail and fine craftsmanship.

HERMAN BROOKMAN

Herman Brookman was born July 2, 1891 in Brooklyn New York, the son of Russian Jewish immigrants, Joseph and Dora Brookman. Brookman's first job after high school was as an office boy with the New York architecture firm of Albro and Lindeberg, a prestigious firm that specialized in building estates and mansions for wealthy Long Islanders. Brookman worked for the firm from 1909-1914, learning the practice of architecture along the way.¹ After the firm dissolved in 1914, Brookman continued to design fine houses and estates with Harrie T. Lindeberg until 1922. Lindeberg was known to use only the best of materials and artisans in his work. He epitomized the emphasis on craftsmanship that was the hallmark of the Arts & Crafts and Beaux Arts philosophies of his time. Lindeberg was skilled at integrating the interior and exterior spaces of a building through patios, gardens, and vistas relating directly to his interiors. Undoubtedly, Brookman was greatly influenced by his early training with Lindeberg.

Brookman married his wife, Sophie, in 1911, and had three children, Bernard, Emanuel, and Dorothy. The family moved to White Plains, New York, in 1917, and Brookman commuted by train to Lindeberg's office in New York City. After a disagreement, Brookman left Lindeberg's office around 1919 and began working on his own. In 1921 Brookman and his family embarked on a two-year tour of Europe, where Brookman spent much of his time observing architecture.² He was touring Europe when he was contacted by Lloyd Frank, an owner of Meier and Frank, to design his house on a 60-acre property south of Portland.

Brookman was recommended to Frank by Oscar B. Bach, a fine metal artist who Frank, a department store magnate, was acquainted with through his many connections in the decorative arts world in New York. Brookman completed the M. Lloyd Frank house, named Fir Acres, on Palatine Hill in 1924. Many of his colleagues believed that the Frank house was a masterpiece of design. Portland architect Saul Zaik calls the Frank estate a small masterpiece: "All architects have the quest for making something perfect. I think

¹ Ritz, Richard Ellison. *Architects of Oregon*. Lair Hill Publishing, Portland, Oregon 2002.

² Donovan, Sally, and Rob Dortignacq. *Goldsmith, Alan and Barbara House National Register Nomination*. 2006.

United States Department of the Interior
National Park Service

National Register of Historic Places Continuation Sheet

Section number 8 Page 2

Brookman came close to that with Frank's house."³ Fir Acres is now the centerpiece of the Lewis and Clark College campus. After completing Fir Acres, the Brookmans decided to stay in Portland where Herman Brookman easily procured many more wealthy clients.

Lloyd Frank helped Brookman obtain another prestigious commission, Temple Beth Israel, completed in 1927. The congregation also hired the firm of M.H. Whitehouse and Associates and the architect Harry Herzog, a member of the congregation, although Brookman was the chief designer. This arrangement was especially difficult for Brookman, who preferred to work alone.⁴ Brookman began to gain a reputation for being difficult to work with. He insisted on control, and he would make corrections and ask for re-orders of materials if he didn't get precisely what he was looking for. Despite these difficulties with his temperament, Brookman developed a reputation for having a remarkable sensitivity to detail and craftsmanship. Robert Wilmsen worked on several projects with Brookman, including the Pharmacy Building at Oregon State University and consulted with Brookman on the long-range master plan for the formal mall of the state capitol building. Wilmsen said of Brookman: "I'll bet you that if there was a bird house on the Frank Estate, it was designed by Herman Brookman. Herman Brookman *designed*."⁵

Throughout his career, Brookman relied on his reputation and referrals from his wealthy clients to procure new projects. He was a perfectionist who preferred working alone in order to maintain control over his designs. As a result, his practice remained small. Gene Westberg, an architect who worked as a draftsman for Brookman for two years, stated that in forty years of practice, he (Westberg) was the only draftsman who lasted more than 6 months. Brookman was an intimidating and critical master and offered very little in the way of encouragement or praise. Yet, Westberg felt that his time with Brookman was beneficial. "If your blood-pressure could stand it, it was a marvelous way to learn."⁶

Brookman did not like to base his designs on a budget, preferring instead to design as he saw fit without being encumbered by financial restraints. He felt that if a client sought him out in the first place, they would have sufficient finances for a commission.⁷ He viewed each of his commissions as his project, not his clients. Not surprisingly, this furthered his reputation as difficult to work with. Westberg states that Brookman maintained that he regarded only two of his many clients as ideal, undoubtedly meaning that they gave him free reign to do as he pleased. This frequently meant redoing elements of the construction repeatedly until it was perfect. "Rip it out" was Brookman's favorite phrase.⁸

³ Van Cleve, Jane. *Brookman Designed with Passion*, Willamette Week, 19 April 1976 p9 c1

⁴ Donovan, Sally, and Rob Dortignacq. *Goldsmith, Alan and Barbara House National Register Nomination*. 2006.

⁵ Ibid

⁶ Westberg, Gene G. Herman Brookman Tour. November 12 1978.

⁷ Ibid

⁸ Westberg, Gene G. Herman Brookman Tour. November 12 1978.

United States Department of the Interior
National Park Service

National Register of Historic Places Continuation Sheet

Section number 8 Page 3

The Great Depression of the 1930s was a difficult time for Brookman, as clients were few. His income declined to the point that he almost lost the home he had designed for himself. He was forced to market himself for the first time, and took whatever small commission came his way. His business picked up again after the economy recovered, and he again relied on referrals for his large residential commissions.

Brookman did not work on many high profile architectural projects, focusing instead on detailed, intimate house designs for his clients. Focusing on residential architecture did not, however, prevent him from exploring new design and forms. As Hawkins and Willingham stated: "By the mid-1930's, Herman Brookman, of all the Portland architects, had explored the furthest in developing new forms of architectural expression."⁹ Gene Westburg, who worked for Brookman from 1953-55 recalls: "Everything was designed in those days. They didn't have catalogues then. Much of his sources were from the East but he had a style with some Northwest flavor, though always more elaborate. Basically, he worked in a Georgian style, but with innovations."¹⁰

Brookman had an office downtown until about 1940 when he decided to work out of his home, which he designed himself. The Brookmans sold this home in 1941 and bought a two-story Queen Anne house in the Westover Terrace development of Southwest Portland. The Southwest Hills neighborhood grew rapidly after WWII, and Brookman had many commissions there. Brookman went on to practice from his home studio until 1965, when he closed his practice.

Brookman served as Treasurer of the Oregon Chapter of the American Institute of Architects from 1933-1935. He became Vice President in 1937, then Director in 1941. He was elected Director again from 1944-46, and from 1951-53. In 1950 he was elected Chapter President of the local AIA. Brookman became a Fellow of the AIA in 1951. He retired to California in 1965, where he died November 6, 1973, at the age of 82.¹¹

VICTOR H. JORGENSEN

Victor Hugo Jorgensen was born in 1884 to Emil C. Jorgensen, a Danish immigrant, and his wife, Pauline. Emil Jorgensen was a self-made businessman in wholesale liquor. In 1907, he built the Hotel Lenox, an 80-room first-class hotel at Southwest Third Avenue and Main Street. Jorgensen's sons, Edwin D. and Victor H., managed the hotel beginning in 1909. The successful and popular hotel was billed as a "select family hotel." It boasted hot and cold water, long-distance phones in every room, private baths, steam heat, and a bus that picked up guests at the train station.

Edwin and Victor inherited the hotel from their father after Emil Jorgensen's death in 1923. The brothers continued to cater to families, and the hotel prospered. The Jorgensen's ran the hotel from an office in the NE

⁹ Hawkins, William J. III and William F. Willingham, Classic Houses of Portland: 1850-1950. (Timber Press, Portland, OR; 1999)

¹⁰ Pintarich, Paul. *Brookman: Masterworks Remain*. The Oregonian. June 6, 1974. Sec. 2 p14, c5

¹¹ Ritz, Richard Ellison. Architects of Oregon. Lair Hill Publishing, Portland, Oregon 2002.

United States Department of the Interior
National Park Service

National Register of Historic Places Continuation Sheet

Section number 8 Page 4

corner of the first floor until 1937. That year the name of the hotel changed to the "New Lenox Hotel," and the Jorgensens turned over management to Peter Kosturos. After the Jorgensen's ceased to actively manage the hotel, it gradually declined in quality and reputation, eventually becoming a low cost residential hotel. The Lenox finally closed in 1970, although the first floor was used for retail stores until 1980. Upon Victor Jorgensen's death in 1977, his son, Victor H. Jr.¹², inherited the building. Victor Jr. sold the building to the Portland Development Commission in 1979, ending 73 years of family ownership.¹³ The Portland Development Commission demolished the building in 1980.¹⁴ The Justice Center is now located where the Lenox once stood.

Victor H. Jorgensen and his first wife, Marta, had three children, Victor, Jr., Marita, and Polly Ann, who grew up in the house. Marta died in 1941 from complications of abdominal surgery at the age of 54. Victor remarried and moved to Santa Cruz California in 1947, where he lived the rest of his life. He died at the age of 93 in 1977.

THE JORGENSEN HOUSE: UNIQUELY BROOKMAN

In Classic Houses of Portland, Hawkins and Willingham describe a trend in the 1920's and 1930's which ultimately led to the Moderne, International and Northwest styles.¹⁵ They describe this as a transitional period, where Portland's residential architects like Herman Brookman, Morris H. Whitehouse, Richard Sundeleaf and Sutton, Whitney and Aandahl explored simplified traditional architectural forms with minimal ornamentation. The Jorgensen House reflects this transitional period. It is a unique house that is difficult to fit into a single stylistic classification. Instead, it reflects the confidence with which Brookman melded various styles to create a unique design of his own vision. Even among his own designs, the Jorgensen House is a unique expression of a mix of revival and forward thinking design, and a relaxed and comfortable adaptation to a very difficult site.

Although it does not fit into any single style, references to several styles can be seen in the Jorgensen House, including Arts and Crafts, Spanish Eclectic, and Moderne. The fine materials and impeccable craftsmanship reflect the Arts and Crafts style. The stucco, carved wood lintel, interior plasterwork, and parabolic interior arches reflect the Spanish Eclectic style. The rear of the house has a definite Moderne feeling. It has several intersecting geometric forms, a cantilevered bay, banks of single-light casement windows, and half-round balconies. The overall impression from this side is quite contemporary, especially for a house designed in 1929.

¹² Victor H. Jorgensen Jr. married Barbara Price, the daughter of O.L. Price. The Jorgensen and Price families were neighbors on Buena Vista Drive. The O.L. Price House is listed in the National Register.

¹³ Johnson, Chris. *Hotel Lenox, A Historical Documentation*. 1980.

¹⁴ MacHaffie, Ingeborg Nielsen. Danish in Portland. 1982.

¹⁵ Hawkins, William J. and William F. Willingham. Classic Houses of Portland, Oregon, 1850-1950. Timber Press, Portland, 1999.

United States Department of the Interior
National Park Service

National Register of Historic Places Continuation Sheet

Section number 8 Page 5

The interior of the Jorgensen House is a unique arrangement of varying levels rarely seen in a house of this vintage. The entry is at mid-level, between the sunken living room and the private upper hall leading to the bedrooms. The public spaces convey Brookman's attention to detail, with the vaulted ceilings, subtly textured plaster walls, and the finely crafted mahogany paneled niche in the dining room. Expansive windows take in the valley view. The private spaces also reflect Brookman's touch, from the walnut cabinetry in the hall to the rounded vaulting ceiling in the master bedroom and the pointed arch window in the celadon tiled bathroom. Like so many Brookman designs, the Jorgensen House seamlessly integrates many unique design elements to create a fresh, contemporary architectural masterpiece.

Herman Brookman was a prolific designer of houses in Portland, primarily for affluent clients. His designs are scattered throughout Portland, but the largest concentration of his houses are in the Southwest Hills area of the city. There are currently five Brookman designed structures on the National Register of Historic Places: Fir Acres (Lewis and Clark College), the Commodore Hotel, Temple Beth Israel, the Baruh-Zell House (3131 SW Talbot Rd), and the Alan and Barbara Goldsmith House (4140 SW Greenleaf Ct). Additionally, nineteen of his structures are on the Portland Cultural Resource Inventory.

Brookman was known for his artistry and attention to detail, and he designed buildings in a number of styles popular when he practiced. Each of Brookman's designs was entirely unique and a work of art in its own right, so comparing them to each other is challenging, but there were certain elements that Brookman frequently used.

From 1924, when he designed his first house in Portland, Fir Acres, the huge estate of M. Lloyd Frank, until about 1940, Brookman designed primarily in traditional revival styles such as Colonial, Tudor and Mediterranean, with his characteristic attention to detail and propensity for stripping his designs down. After 1940, he began designing in more contemporary styles, such as Early Modern and Northwest Regional variations. Whatever style he worked in, no two Brookman designs were the same. Each was designed to suit the particular client and site he was working with.

The Jorgensen House is difficult to categorize architecturally. It was constructed during Brookman's revival period, but its split-level plan and artful, relaxed blend of stylistic elements do not necessarily fit in any revival style. The house must have appeared very modern for its time, when split-levels were uncommon and traditional styles were the norm.

Brookman had a number of signature elements which appear on many of his designs including the Jorgensen House. These include designing houses perfectly situated on difficult sites, recessed entrances, curving design elements, casement and leaded glass windows, and masterful wrought iron work.

Many Brookman-designed houses are set on difficult or awkward sites, which tend to provide spectacular views. But as with the Jorgensen House, Brookman managed to not only fit the house to the setting but site it in such a way as to take maximum advantage of both the view and the lot. The Lee S. Elliot House, at 1475 Vista

United States Department of the Interior
National Park Service

National Register of Historic Places Continuation Sheet

Section number 8 Page 6

Avenue, while a masterpiece of design, is set on a difficult site, which required that the façade face inward toward a private lane. The lot of the Eliot House slopes steeply down to the rear, a situation that is remedied with a massive retaining wall. The Grace Kern House, on SW Westpoint Court, is also sited on an awkward sloping lot. In that case, a massive concrete retaining wall on the rear of the lot raised the entire lot to a more workable level.

Like many Brookman houses, the Jorgensen has a recessed entrance. Other houses with this element include the Baruh-Zell House, and the much more Moderne Keith Gilbert Powers House (287 NW Cumberland Rd) built in 1947.

Brookman's unique use of curving elements lent a modern air to his more traditionally styled houses. Throughout his career, curves played a major part in many of his designs, from traditional to contemporary style houses. Curves do not play as prominent a role on the exterior of the Jorgensen House as on some other Brookman houses, but they are present. A round tower entrance with a bellcast roof is tucked into the corner of the auto court. On the rear and south side elevations, half-round balconies contribute to the Moderne feel, and foretold of Brookman's evolution towards that style. The Moderne Keith Gilbert Powers House, located at 287 NW Cumberland Road, has several curving walls reflective of Brookman's earlier work.

The interior of the Jorgensen house has soft and subtle curves, from the rounded edges of the walls to the rounded vault ceilings in many rooms. Other Brookman houses are less subtle in their use of curves; the 1955 Kern House is unique in that the entire façade is a single concave curve.

Another signature Brookman element was his use of decorative wrought iron. He worked frequently with the noted metal artist Oscar B. Bach, of New York, whose work adorns the Empire State Building and the Chrysler Building, among many others. Nowhere is Brookman's use of decorative wrought iron more evident than in the Mediterranean style Harry A. Green House, at 3316 SE Ankeny, which has an over-the-top wrought iron entrance gate complete with a peacock, and a gracefully curving interior staircase. Most of his other commissions had more restrained wrought iron elements, such as those on the Jorgensen House. The Jorgensen House has a beautiful decorative wrought iron light fixture over the front door, a tall, delicate rooftop weathervane, and a cast iron decorative screen over the round window in the east wall of the garage. All of these elements are understated, but are also important character defining elements of the façade of the house.

Brookman was partial to casement windows and used them on most of his designs regardless of style. In some cases, such as on the Baruh-Zell House, the Green House, and the Adrienne Arnsberg House (1136 SW Davenport Street), three-light casements lent an air of modernity to traditional designs. Indeed, banks of casement windows are one element that can be seen on almost every Brookman house from the Frank House all the way through to the Grace Kern House. The Jorgensen house has primarily single light casement windows set in banks of two to five.

Jorgensen, Victor H. and Marta, House
Name of Property

Multnomah Co. OR
County and State

NPS Form 10-900-a

OMB Approval No. 1024-0018

United States Department of the Interior
National Park Service

National Register of Historic Places Continuation Sheet

Section number 8 Page 7

CONCLUSION

In summary, the Jorgensen House is a hard to categorize but masterfully designed house. It is perfectly situated on its lot to take advantage of the view and allow for an intimate and elegant entrance from the street. The interior is a forward-thinking split level plan with exceptionally detailed spaces featuring fine finishes, vaulted ceilings, banks of windows, and seamless transitions. It is unmistakably the work of a skilled artist.

United States Department of the Interior
National Park Service

National Register of Historic Places Continuation Sheet

Section number 9 Page 1

BIBLIOGRAPHY

- Death Claims Oregon Native: Mrs. Jorgensen Dies Suddenly.* Oregonian February 26, 1941.
- Donovan, Sally, and Rob Dotignacq. *Goldsmith, Alan and Barbara House National Register Nomination.* 2006.
- Fitzgerald, Kimberli, and Amy McFeeters-Krone. *Baruh-Zell House National Register Nomination.* 2006.
- Hawkins, William J. and William F. Willingham. Classic Houses of Portland, Oregon, 1850-1950. Timber Press, Portland, Oregon. 1999.
- Johnson, Chris. *Hotel Lenox, A Historical Documentation.* Inventoried for Portland Historical Landmarks Commission, February 4, 1980.
- Jorgensen, V.H. House,* Herman Brookman Photographs, PH114, Special Collections & University Archives, University of Oregon Libraries, Eugene, OR.
- Lakin, Kimberly and Kimberly Demuth. *Price, O.L. House National Register Nomination.* 1987.
- Mantia, Patty. *Wrecking crew to claim piece of Portland history.* Oregonian. January 27, 1980.
- McHaffie, Ingeborg Nielsen. Danish in Portland. 1982.
- Photograph Collection. Oregon Historical Society. Portland Oregon.
- Pintarich, Paul. *Brookman: Masterworks Remain.* Oregonian. June 6, 1974, Sec. 2 p14, c5
- Portland Historic Inventory* City of Portland, 1983.
- Residence for V. H. Jorgensen, Portland, Ore. Architectural Plans, Herman Brookman Architecture Files, Ax 330, Special Collections & University Archives, University of Oregon Libraries, Eugene, Oregon.
- Ritz, Richard Ellison. Architects of Oregon. Lair Hill Publishing, Portland Oregon. 2002.
- Van Cleve, Jane. *Brookman Designed with Passion.* Willamette Week. April 19, 1976, p9 c1.
- Vaughn, Thomas and Virginia Guest Ferriday, eds. Space, Style and Structure: Building in Northwest America. Oregon Historical Society Press, Portland OR, 1974.

Jorgensen, Victor H. and Marta, House
Name of Property

Multnomah Co., OR
County and State

NPS Form 10-900-a

OMB Approval No. 1024-0018

United States Department of the Interior
National Park Service

National Register of Historic Places Continuation Sheet

Section number 9 Page 2

Vertical Files. Oregon Historical Society, Portland Oregon.

Victor Hugo Jorgensen Obituary. Oregon Journal. November 7, 1977.

Westberg, Gene G. Herman Brookman Tour. November 12 1978. (Unpublished, from collection of Jane Turville).

Jorgensen, Victor H. and Marta, House
Name of Property

Multnomah Co., OR
County and State

10. Geographical Data

Acreeage of Property Less than 1

UTM References

(Place additional UTM references on a continuation sheet)

1 10 523192 5039358
Zone Easting Northing
2 _____

3 _____
Zone Easting Northing
4 _____

Verbal Boundary Description

(Describe the boundaries of the property on a continuation sheet)

Boundary Justification

(Explain why the boundaries were selected on a continuation sheet)

11. Form Prepared By

name/title Amy McFeeters-Krone, Historic Preservation Consultant

organization Building History date October 2007

street & number 1831 NE Thompson St telephone (503) 493-0477

city or town Portland state OR zip code 97212

Additional Documentation

Submit the following items with the completed form:

Continuation sheets

Maps: A USGS map (7.5 or 15 minute series) indicating the property's location.
A sketch map for historic districts and properties having large acreage or numerous resources.

Photographs: Representative black and white photographs of the property.

Additional items (check with the SHPO or FPO for any additional items)

Property Owner

name Gary and Cynthia Crose

street & number 2643 SW Buena Vista Drive telephone (503) 227-1501

city or town Portland state OR zip code 97201

Paperwork Reduction Act Statement: This information is being collected for applications to the National Register of Historic Places to nominate properties for listing or determine eligibility for listing, to list properties, and to amend existing listings. Response to this request is required to obtain a benefit in accordance with the National Historic Preservation Act, as amended (16 U.S.C.460 et seq.).

Estimated Burden Statement: Public reporting burden for this form is estimated to average 18.1 hours per response including time for reviewing instructions, gathering and maintaining data, and completing and reviewing the form. Direct comments regarding this burden estimate or any aspect of this form to the Chief, Administrative Services Division, National Park Service, PO Box 37127, Washington, DC 20013-7127; and the Office of Management and Budget, Paperwork Reductions Project (1024-0018), Washington, DC 20503.

Jorgensen, Victor H. and Marta, House

Name of Property

Multnomah Co., OR

County and State

NPS Form 10-900-a

OMB Approval No. 1024-0018

United States Department of the Interior
National Park Service

National Register of Historic Places Continuation Sheet

Section number 10 Page 1

VERBAL BOUNDARY DESCRIPTION

2643 SW Buena Vista Drive encompasses Lot 11 of the Altavista plat, Multnomah County, Oregon. The parcel is .38 acres and rectilinear in shape.

BOUNDARY JUSTIFICATION

The boundary encompasses the entire urban tax lot, and is the legally recorded boundary for 2643 SW Buena Vista Drive.

United States Department of the Interior
National Park Service

National Register of Historic Places Continuation Sheet

Section number Photographs Page 1

PHOTOGRAPHS

Address: Jorgensen, Victor H. and Marta, House
2643 SW Buena Vista Dr.
Portland, OR 97201

Photographer: Margaret Marcusen

Date: October 2007

Ink and Paper: Cannon Photo Paper Plus Glossy and Cannon Chromalife 100 inks

Location of Negatives: Digital images held by photographer

1 of 36	Exterior View:	West façade, facing SE
2 of 36	Exterior View:	West façade, facing E
3 of 36	Exterior View:	West façade iron work detail, facing E
4 of 36	Exterior View:	West façade entrance and vestibule, facing E
5 of 36	Exterior View:	West façade iron work detail, facing E
6 of 36	Exterior View:	West façade carving detail, facing SE
7 of 36	Exterior View:	South façade, facing N
8 of 36	Exterior View:	East façade, facing W and up
9 of 36	Exterior View:	North façade, facing SE
10 of 36	Interior View:	2 nd floor, entrance hall, facing E
11 of 36	Interior View:	2 nd floor, entrance hall, facing NE and up
12 of 36	Interior View:	2 nd floor, hall, facing S
13 of 36	Interior View:	2 nd floor, master bedroom, facing SW
14 of 36	Interior View:	2 nd floor, master bath, facing SW
15 of 36	Interior View:	2 nd floor, Victor's room, facing NE
16 of 36	Interior View:	2 nd floor, Victor's bathroom, facing SW
17 of 36	Interior View:	2 nd floor, upper level hall, facing E
18 of 36	Interior View:	2 nd floor, top level, Marita's room, facing SW
19 of 36	Interior View:	2 nd floor, top level. Pollyann's room, facing SE
20 of 36	Interior View:	2 nd floor, top level, daughter's bath, facing NE
21 of 36	Interior View:	1 st floor, living room, facing SE and down
22 of 36	Interior View:	1 st floor, living room, facing NW
23 of 36	Interior View:	1 st floor, living room, fireplace detail, facing SW
24 of 36	Interior View:	1 st floor, porch, facing E
25 of 36	Interior View:	1 st floor, dining room, facing NW
26 of 36	Interior View:	1 st floor, pantry, facing NW
27 of 36	Interior View:	1 st floor, kitchen, facing E
28 of 36	Interior View:	1 st floor, dumbwaiter and bathroom, facing N
29 of 36	Interior View:	1 st floor, lower level, Den, facing SE

Jorgensen, Victor H. and Marta House
Name of Property

Multnomah County, Oregon
County and State


NPS Form 10-900-a

OMB Approval No. 1024-0018

United States Department of the Interior
National Park Service

National Register of Historic Places Continuation Sheet

Section number 2, 7, 8, 10, 11 Page Amendment



Jorgensen, Victor H. and Marta House
2643 SW Buenavista Drive
Portland, OR 97201

NRIS #08000405
Listed Date: 5/15/2008

The purpose of this continuation sheet is to correct the spelling of the street address for the Jorgensen, Victor H. and Marta, House. Previous documentation identified the street name as Buena Vista Drive. The correct spelling of the street address is Buenavista Drive.


The proposed relocation requires amending and resubmitting Sections 2 and 11 of the National Register of Historic Places Form and Section 7, pages 1 and 2; Section 8, page 4; and Section 10, page 1 of the continuation sheets. The corrected documents are included in this submission.



Deputy State Historic Preservation Officer

5-30-08
Date

08000405



United States Department of the Interior
National Park Service

National Register of Historic Places Registration Form

This form is for use in nominating or requesting determinations for individual properties and districts. See instruction in How to Complete the National Register of Historic Places Registration Form (National Register Bulletin 16A). Complete each item by marking "x" in the appropriate box or by entering the information requested. If an item does not apply to the property being documented, enter "N/A" for "not applicable." For functions, architectural classifications, materials and areas of significance, enter only categories and subcategories from the instructions. Place additional entries and narrative items on continuation sheets (NPS Form 10-900a). Use a typewriter, word processor, or computer, to complete all items.

1. Name of Property

historic name Jorgensen, Victor H. and Marta, House

other names/site number _____

2. Location

street & number 2643 SW Buenavista Drive

not for publication

city or town Portland

vicinity

state Oregon

code OR

county Multnomah

code 52

zip code 97201

3. State/Federal Agency Certification

As the designated authority under the National Historic Preservation Act, as amended, I hereby certify that this X nomination _____ request for determination of eligibility meets the documentation standards for registering properties in the National Register of Historic Places and meets the procedural and professional requirements set forth in 36 CFR Part 60. In my opinion, the property X meets _____ does not meet the National Register criteria. I recommend that this property be considered significant _____ nationally _____ statewide X locally.

Signature of certifying official/Title - Deputy SHPO

Date

5-30-08

Oregon State Historic Preservation Office
State or Federal agency and bureau

4. National Park Service Certification

I hereby certify that the property is:
Action

Signature of the Keeper

Date of

_____ entered in the National Register
_____ See continuation sheet.

_____ determined eligible for the National Register
_____ See continuation sheet.

_____ determined not eligible for the National Register

_____ removed from the National Register

other (explain): Additional Documentation Accepted

Edson H. Beall 7-2008

United States Department of the Interior
National Park Service

National Register of Historic Places Continuation Sheet

Section number 7 Page 1

SUMMARY

The Jorgensen House is located at 2643 SW Buenavista Drive in the Southwest Hills neighborhood of Portland. It was exactly designed by noted architect Herman Brookman. The asymmetrically arranged house is set on a very steep hillside lot overlooking the city of Portland. The house is hard to classify; the style is a mixture of Spanish Colonial Revival and Moderne, but distinctively Brookman in its impeccable design and detail. The main elevation is close to the street, with a welcoming entrance courtyard separated from the driveway by a well-integrated garage wing. The house appears to be only 1 ½ stories from the street, but in actuality it is a complex split-level assembly of six levels. Constructed of hand-troweled stucco with a cedar-shingle cross-gable roof, the house is understated from the front, but in the Brookman fashion, every detail was designed to work together seamlessly.

The Jorgensen House has many of Herman Brookman's signature elements. Brookman was very skilled at designing houses on steep lots like that of the Jorgensen House. The entrance is recessed, like that of the Baruh-Zell House. The windows are casement. Ornamental iron work decorates the façade. The front elevation has a more traditional look while the rear is distinctly more modern. The bay window is crowned by a ram's head, a Brookman hallmark. Brookman is well known for his architectural skill, unique and well thought-out plans, attention to detail, and unique blend of traditional and modern elements. The Jorgensen House is an excellent example of this.

Constructed in 1929, the Jorgensen House retains a very high degree of integrity. The house remains largely unchanged, with the exception of the kitchen and some bathrooms, and some other minor alterations.

SETTING

The Jorgensen House is located in the established and affluent neighborhood of Southwest Hills in Portland, Oregon. The neighborhood is characterized by its winding roads, lush green hills, and large, well-tended homes, many with spectacular views. Houses on Buenavista Drive are set close together and close to the street, with narrow manicured gardens. There are no sidewalks. Lots on the east side of the street drop off precipitously to the east, affording a panoramic view of the city and the mountains beyond. The Jorgensen House is set at about 680 feet elevation and faces west. The house is set on a slight angle on the lot to take full advantage of the eastern views. The crest of the hill is just across Buenavista Drive to the west.

The front of the house is close to the street, with mature shrubs in the narrow garden between the garage and the street. (see exterior for description of the entrance court).

The rear yard is very steep and has a naturalistic style. Brookman designed the original garden plan. A rounded terrace overlooks the yard. The garden level of the lot has a narrow grassy area bordered in shrubs. A path

United States Department of the Interior
National Park Service

National Register of Historic Places Continuation Sheet

Section number 7 Page 2

originally led down to a small pond at the foot of the slope. The current owner has reworked the stone steps and mulch paths that switch back down the hill, and added plantings. Stone retaining walls are located just below the garden level of the house. A large poured-concrete retaining wall is located about half way down the slope, anchored by steel tie bars.

The north and south walls of the house are very close to the property lines. Concrete steps fill the space between the north wall and the property line. The south property line is marked by a concrete retaining wall and a steep planted hillside along the house.

PLAN

The Jorgensen House has a split-level plan containing 4902 square feet of finished living space on six intersecting levels.

The irregular plan consists of long side gable volume intersected with several cross-gables, the largest of which houses the garage and projects from the front of the main block of the house. The primary elevation of the house faces west-southwest toward the street.

EXTERIOR DESCRIPTION

The exterior of the Jorgensen house is sheathed in "natural texture" stucco with a prominent cedar shingle roof. The main (west) elevation is asymmetrical and understated, consisting of two front gables projecting from a flanking-gable main volume (Drawing 6). The larger of the projecting front gables, which houses the garage, essentially divides the façade into two sections, the main entrance and the auto entrance. The house is best approached coming up Buenavista Drive from the south, where the gabled main entrance is visible, tucked in between the garage wing and the main block of the house. The front door is accessed from a sunken entrance courtyard to the south of the garage wing. From the street, semi-circular stone steps lead down into the courtyard that contains a Japanese style garden and a flagstone walk, which replaced the original deteriorated cast concrete stones. In an example of the control Brookman exerted over his projects, he created a plan of the stones for the front walk in which the exact dimensions of each stone to be laid are noted. However, the original specifications were changed, and the original walk was of cast concrete instead of natural stone.

In typical Brookman fashion, the front door is recessed. Over the entrance is a rough carved wood lintel, decorated with a geometric diamond design. The courtyard is lit by a decorative wrought iron light fixture that is one of the distinctive elements of this house. The fixture consists of a delicate star-shaped escutcheon mounted over the door and holding an iron rod connected with brass finials to a filigree globe lantern. The lantern is not original. The front door is walnut, with an inlaid parquet pattern and a brass peephole.

United States Department of the Interior
National Park Service

National Register of Historic Places Continuation Sheet

Section number 8 Page 4

corner of the first floor until 1937. That year the name of the hotel changed to the "New Lenox Hotel," and the Jorgensens turned over management to Peter Kosturos. After the Jorgensen's ceased to actively manage the hotel, it gradually declined in quality and reputation, eventually becoming a low cost residential hotel. The Lenox finally closed in 1970, although the first floor was used for retail stores until 1980. Upon Victor Jorgensen's death in 1977, his son, Victor H. Jr.¹², inherited the building. Victor Jr. sold the building to the Portland Development Commission in 1979, ending 73 years of family ownership.¹³ The Portland Development Commission demolished the building in 1980.¹⁴ The Justice Center is now located where the Lenox once stood.

Victor H. Jorgensen and his first wife, Marta, had three children, Victor, Jr., Marita, and Polly Ann, who grew up in the house. Marta died in 1941 from complications of abdominal surgery at the age of 54. Victor remarried and moved to Santa Cruz California in 1947, where he lived the rest of his life. He died at the age of 93 in 1977.

THE JORGENSEN HOUSE: UNIQUELY BROOKMAN

In Classic Houses of Portland, Hawkins and Willingham describe a trend in the 1920's and 1930's which ultimately led to the Moderne, International and Northwest styles.¹⁵ They describe this as a transitional period, where Portland's residential architects like Herman Brookman, Morris H. Whitehouse, Richard Sundeleaf and Sutton, Whitney and Aandahl explored simplified traditional architectural forms with minimal ornamentation. The Jorgensen House reflects this transitional period. It is a unique house that is difficult to fit into a single stylistic classification. Instead, it reflects the confidence with which Brookman melded various styles to create a unique design of his own vision. Even among his own designs, the Jorgensen House is a unique expression of a mix of revival and forward thinking design, and a relaxed and comfortable adaptation to a very difficult site.

Although it does not fit into any single style, references to several styles can be seen in the Jorgensen House, including Arts and Crafts, Spanish Eclectic, and Moderne. The fine materials and impeccable craftsmanship reflect the Arts and Crafts style. The stucco, carved wood lintel, interior plasterwork, and parabolic interior arches reflect the Spanish Eclectic style. The rear of the house has a definite Moderne feeling. It has several intersecting geometric forms, a cantilevered bay, banks of single-light casement windows, and half-round balconies. The overall impression from this side is quite contemporary, especially for a house designed in 1929.

¹² Victor H. Jorgensen Jr. married Barbara Price, the daughter of O.L. Price. The Jorgensen and Price families were neighbors on Buenavista Drive. The O.L. Price House is listed in the National Register.

¹³ Johnson, Chris. *Hotel Lenox, A Historical Documentation*. 1980.

¹⁴ MacHaffie, Ingeborg Nielsen. Danish in Portland. 1982.

¹⁵ Hawkins, William J. and William F. Willingham. Classic Houses of Portland, Oregon, 1850-1950. Timber Press, Portland, 1999.

Jorgensen, Victor H. and Marta, House
Name of Property

Multnomah Co., OR
County and State

10. Geographical Data

Acreage of Property Less than 1

UTM References

(Place additional UTM references on a continuation sheet)

1	<u>10</u>	<u>523192</u>	<u>5039358</u>	3			
	Zone	Easting	Northing		Zone	Easting	Northing
2				4			

Verbal Boundary Description

(Describe the boundaries of the property on a continuation sheet)

Boundary Justification

(Explain why the boundaries were selected on a continuation sheet)

11. Form Prepared By

name/title Amy McFeeters-Krone, Historic Preservation Consultant

organization Building History date October 2007

street & number 1831 NE Thompson St telephone (503) 493-0477

city or town Portland state OR zip code 97212

Additional Documentation

Submit the following items with the completed form:

Continuation sheets

Maps: A USGS map (7.5 or 15 minute series) indicating the property's location.

A sketch map for historic districts and properties having large acreage or numerous resources.

Photographs: Representative black and white photographs of the property.

Additional items (check with the SHPO or FPO for any additional items)

Property Owner

name Gary and Cynthia Crose

street & number 2643 SW Buenavista Drive telephone (503) 227-1501

city or town Portland state OR zip code 97201

Paperwork Reduction Act Statement: This information is being collected for applications to the National Register of Historic Places to nominate properties for listing or determine eligibility for listing, to list properties, and to amend existing listings. Response to this request is required to obtain a benefit in accordance with the National Historic Preservation Act, as amended (16 U.S.C.460 et seq.).

Estimated Burden Statement: Public reporting burden for this form is estimated to average 18.1 hours per response including time for reviewing instructions, gathering and maintaining data, and completing and reviewing the form. Direct comments regarding this burden estimate or any aspect of this form to the Chief, Administrative Services Division, National Park Service, PO Box 37127, Washington, DC 20013-7127; and the Office of Management and Budget, Paperwork Reductions Project (1024-0018), Washington, DC 20503.

Jorgensen, Victor H. and Marta, House
Name of Property

Multnomah Co., OR
County and State

NPS Form 10-900-a

OMB Approval No. 1024-0018

United States Department of the Interior
National Park Service

National Register of Historic Places Continuation Sheet

Section number 10 Page 1

VERBAL BOUNDARY DESCRIPTION

2643 SW Buenavista Drive encompasses Lot 11 of the Altavista plat, Multnomah County, Oregon. The parcel is .38 acres and rectilinear in shape.

BOUNDARY JUSTIFICATION

The boundary encompasses the entire urban tax lot, and is the legally recorded boundary for 2643 SW Buenavista Drive.

United States Department of the Interior
National Park Service

National Register of Historic Places Continuation Sheet

Section number Photographs Page 1

PHOTOGRAPHS

Address: Jorgensen, Victor H. and Marta, House
2643 SW Buenavista Dr.
Portland, OR 97201

Photographer: Margaret Marcusen

Date: October 2007

Ink and Paper: Cannon Photo Paper Plus Glossy and Cannon Chromalife 100 inks

Location of Negatives: Digital images held by photographer

- 1 of 36 Exterior View: West façade, facing SE
- 2 of 36 Exterior View: West façade, facing E
- 3 of 36 Exterior View: West façade iron work detail, facing E
- 4 of 36 Exterior View: West façade entrance and vestibule, facing E
- 5 of 36 Exterior View: West façade iron work detail, facing E
- 6 of 36 Exterior View: West façade carving detail, facing SE
- 7 of 36 Exterior View: South façade, facing N
- 8 of 36 Exterior View: East façade, facing W and up
- 9 of 36 Exterior View: North façade, facing SE
- 10 of 36 Interior View: 2nd floor, entrance hall, facing E
- 11 of 36 Interior View: 2nd floor, entrance hall, facing NE and up
- 12 of 36 Interior View: 2nd floor, hall, facing S
- 13 of 36 Interior View: 2nd floor, master bedroom, facing SW
- 14 of 36 Interior View: 2nd floor, master bath, facing SW
- 15 of 36 Interior View: 2nd floor, Victor's room, facing NE
- 16 of 36 Interior View: 2nd floor, Victor's bathroom, facing SW
- 17 of 36 Interior View: 2nd floor, upper level hall, facing E
- 18 of 36 Interior View: 2nd floor, top level, Marita's room, facing SW
- 19 of 36 Interior View: 2nd floor, top level. Pollyann's room, facing SE
- 20 of 36 Interior View: 2nd floor, top level, daughter's bath, facing NE
- 21 of 36 Interior View: 1st floor, living room, facing SE and down
- 22 of 36 Interior View: 1st floor, living room, facing NW
- 23 of 36 Interior View: 1st floor, living room, fireplace detail, facing SW
- 24 of 36 Interior View: 1st floor, porch, facing E
- 25 of 36 Interior View: 1st floor, dining room, facing NW
- 26 of 36 Interior View: 1st floor, pantry, facing NW
- 27 of 36 Interior View: 1st floor, kitchen, facing E
- 28 of 36 Interior View: 1st floor, dumbwaiter and bathroom, facing N
- 29 of 36 Interior View: 1st floor, lower level, Den, facing SE

Jorgensen, Victor H. and Marta, House

Name of Property

Multnomah Co., OR

County and State

NPS Form 10-900-a

OMB Approval No. 1024-0018




United States Department of the Interior
National Park Service

National Register of Historic Places Continuation Sheet

Section number Photographs Page 2

30 of 36	Interior View:	Terrace level, family room, facing N
31 of 36	Interior View:	Terrace, family room, facing SE
32 of 36	Interior View:	Terrace, shop, facing W
33 of 36	Interior View:	Terrace, furnace, facing NW
34 of 36	Interior View:	Terrace, laundry, facing SE
35 of 36	Interior View:	Terrace, hall, facing N
36 of 36	Interior View:	Terrace, bedroom, facing SE


Property & Location



THIS MAP WAS PREPARED FOR
ASSESSMENT PURPOSE ONLY

NE 1/4 SEC. 5 T.1S. R.1E. W.M.
MULTNOMAH COUNTY
1" = 100'


IS IE 5DA
PORTLAND



IS IE 5DA
PORTLAND


SEE MAP IS IE 500

Victor & Marta Jorgensen House
1929




SECOND FLOOR

Victor & Marta Jorgensen House
1929




FIRST FLOOR

Victor & Marta Jorgensen House
1929



BASEMENT




LOT II
 ALTAVISTA
 SCALE 1" = 10'-0"

REVISED 100.26.1919
 PILOT PLAN
 HOUSE FOR V. E. JOLGERSEN, I/O.
 PORTLAND, OREGON
 HERBIE BLOOMER ARCHITECT
 1301 YEON BLDG. - PORTLAND, OREGON

①

Fig. 1




NOTE: -
 ALL DIMENSIONS OF TERRACE WALLS ARE GIVEN
 TO FRAME LINE, INTERIOR PARTITION TO CENTER OF FLOOR.
 ALL TERRACE WALLS SHALL BE BUILT 2 1/2" OVER
 FINISH. OTHERWISE INDICATED. ALL INTERIOR PARTITIONS
 TO BUILT 3/4" OVER FINISH. OTHERWISE INDICATED.
 ALL DIMENSIONS REFERRED TO AS PER THESE INDICATED
 INDICATED


FIRST FLOOR PLAN
 SCALE 1/8" = 1'-0"
 HOUSE FOR V. H. JORGENSEN - PORTLAND, ORE.
 HERMAN STUCKENBROCK ARCHT. - PORTLAND, ORE.
 PORTLAND, ORE.

1/10/29


1929/29 MAY 30, 1929
 MAY 7, 1929

3







SOUTH-EAST ELEVATION
 SCALE 1/8" = 1'-0"
 HOUSE FOR V. BJORGENSEN - 1/22 - PORTLAND - ORE.



LEV. 100.00
 H. J. ...
 FOUR ...
 ...





ELEVATION







SECTION



DETAIL OF WINDOW ON MAIN WALL





LIVING ROOM DETAILS







LIVING ROOM DETAILS



LIVING ROOM DETAILS



ENTRANCE LOOK DETAILS



ENTRANCE LOOK DETAILS

HOUSE FOR Y. A. NOLAN, INC.
 PORTLAND, OREGON
 EDGAR BLOOMER ARCHITECT
 1501 TOWN BLDG. - PORTLAND, OREGON

NOV 20 1934