
United States Department of the Interior Heritage Conservation and Recreation Service

# National Register of Historic Places Inventory—Nomination Form

See instructions in *How to Complete National Register Forms* Type all entries—complete applicable sections



Type all entries—co	omplete applica	ble sections					
1. Name					_		
historic	Fairy Hill,	Henry W. Car	ville Farm	or Conditions			
and/or common	Brampton (	preferred)					
2. Locati	on	MDZ	o	**************************************			
street & number		of Rt. <del>20, 2/</del> 1 (Airport) R		west	n/a	∟ not for publ	cation
city, town	Chestertown	vic. xvi	icinity of	congressional	district	First	
state	Maryland	code 24	county	Kent		code	029
3. Classi	fication						
district	nership public private both blic Acquisition in process being considere	Accessib _X_ yes: red yes: u	cupied in progress le	Present Use agriculte commer educatio entertain governn industria	ure cial onal nment nent	museum park X private r religious scientific transpor	esidence
4. Owner	of Prop	erty					
name	Mr. and Mrs	. Robert H. S <sub>l</sub>	parre				
street & number	R.D. 2, Box	107					
city, town	Chestertown	<u>X</u> vi	icinity of		state	Maryland	21620
5. Locati	on of Le	egal Des	criptic	n			
courthouse, registry c	of deeds, etc. K	ent County Co	urthouse				
city, town	C	nestertown			state	Maryland	21620
6. Repres	sentatio	n in Exi	sting \$	Surveys			
<del>-</del>	Historical T Sites Survey	rust	has this prop	perty been deter	mined eleg	ible? ye	s <u>X</u> no
late May 22, 19	981			federal	X state	county	local
lepository for survey	records	aryland Histon	rical Trust	t, 21 State	Circle		
city, town	Aı	napolis			state	Maryland	21401

Condition excellentdeterioratedX good	Check one unaltered X altered	Check one  X original site moved date
---------------------------------------	-------------------------------	---------------------------------------

Describe the present and original (if known) physical appearance

#### SUMMARY DESCRIPTION

Brampton is a ca. 1860 transitional Greek Revival/Italianate-influenced dwelling located near Chestertown in Kent County, Maryland. The main section of the house is constructed of brick, three stories high, with a symmetrical five-bay-wide facade and a depth of two bays. A two story frame wing, three bays wide by one bay deep, forms an ell at the rear. The entrance is located in the central bay of the principal (north) facade, and consists of double paneled doors with transom and sidelights in a crossetted surround. A three-bay-wide porch with chamfered posts and a bracketed cornice (probably a late-19th-century renovation) shelters the entrance. All first-floor windows are floor-to-ceiling 6/9 sash; second-story windows are 6/6 with bold bracketed cornices; the third story is lighted by smaller 6/6 windows in plain surrounds. The shallow-pitched, metal-clad gable roof is detailed with a bracketed cornice and a shallow crossgable above the central bay. Interior chimneys rise from either gable end. The building's interior is organized in a center-hall plan, and retains all its original trim and finishes in pristine condition, including walnut doors, moldings, slate fireplace surrounds, plaster ceiling medallions, and threestory spiral stair.

### GENERAL DESCRIPTION

Brampton is a large ca. 1860 transitional Greek Revival/Italianate-influenced dwelling located on the south side of Maryland Route 20 near Chestertown in Kent County, Maryland. The main block of the house, which faces north, is of brick construction, three stories high, five bays wide and two bays deep. The entrance is located in the central bay of the north facade, and consists of double doors, each with two raised and molded panels, and a 7-light transom and 4-pane sidelights in a crossetted surround. Two floor-to-ceiling 6/9 windows flank the entrance on either side. On the second story, five 6/6 windows with bold bracketed cornices are aligned above the first-floor openings. (Evidence suggests that similar cornices once graced the first-story windows.) On the third floor, slightly lower 6/6 sash appear above the second-story windows. Louvered shutters on all levels are probably replacements. The building has a shallow-pitched gable roof, clad in standing-seam metal and detailed with a bracketed cornice and a shallow cross-gable above the central bay. A one-story porch, with chamfered posts and bracketed cornice, spans the three central bays; this porch may represent a late 19th century addition.

The two gable end elevations are identical to each other, two bays wide, with windows on each floor matching those on the front facade. An interior chimney rises from each gable end.

At the intersection of the roof ridge and the front-facing cross gable, a platform formerly held a lantern or cupola.

### 8. Significance

Period prehistoric 1400–1499 1500–1599 1600–1699 1700–1799 1800–1899 1900–	Areas of Significance—C archeology-prehistoric archeology-historic agricultureX architecture art commerce communications		law literature military music	e religion science sculpture social/ humanitarian theater transportation other (specify)
Specific dates	ca. 1860	Builder/Architect	unknown	

Statement of Significance (in one paragraph)

Applicable Criterion: C

#### SIGNIFICANCE SUMMARY

Brampton is significant for its architecture, as a virtually unaltered example of the transitional Greek Revival Italianate style as expressed in a formal dwelling on the Eastern Shore of Maryland. This type of structure is uncommon in the rural agricultural contexts of the Eastern Shore. Important features include the formal symmetry and refined proportions of the large, vertical brick structure; fine masonry construction; ornate bracketed cornice and window hoods; and elegant interior.

### HISTORY AND SUPPORT

The brick main section of the house is believed to date to ca. 1860, based on architectural and documentary evidence and local tradition. The probable owner/builder was Henry W. Carville, whose name is associated with the property on the 1877 Kent County Atlas. Carville was known in the County as a gentleman farmer; he and his wife raised fruit trees on the property. Carville acquired a great deal of land in the County, but finally was forced to sell much of it, including Fairy Hill, to settle his debts. A local Democrat, he was not an active politician or civic leader, but did serve as vestryman to St. Paul's Parish, Kent.

Harrison W. Vickers purchased the property in 1896. There is no record that Vickers ever occupied the house; his family resided at a town house in Chestertown and at Laurentum, Vickers' Gothic mansion near the junction of Route 20 and the present Flatland Road. Vickers, an attorney, served as State's Attorney for Kent County from 1875 to 1883, and was a Visitor and Governor of Washington College in Chestertown.

Upon Vickers' death in 1911, the property passed to his wife, Jennie B. Y. Vickers. Dr. Frank B. Hines acquired the property from Mrs. Vickers' estate in 1934, by which time the house had fallen into disrepair. Hines served as Commander of the First National Guard Unit of Kent County, instructing in first aid and wound care. He was abroad during World War I with the Kent Medical Unit, part of Maryland's 29th Infantry Division, AEF.

# 9. Major Bibliographical References

Usilton, Wm. B., <u>History of Kent County</u>, Chestertown, MD.

10. Ge	ographical Data	a	
Acreage of nomin	nated property Approximately	4.3 acres	
Quadrangle name	Chestertown, MD.		Quadrangle scale 1:24,000
	51/ 0 01 1/ 01/ 01/ 5 01	<b>B</b> l l l	
A 1 8 4 0 Zone Eastin	5 4 2 0 4 3 4 0 6 5 0 Northing	ا لبنا	Easting Northing
c	• 	D L L	
E		F L	
<b>G</b>		н	
Verbal boundar	y description and justification	1	
See cor	ntinuation Sheet #2		
,	and counties for properties ov		
state n/a	code	county	code
state	code	county	code
11. For	m Prepared By		
name/title	Kathleen B. White		
organization		date	October 1982
street & number	107 South Mill Street	tele	301-778-2363
city or town	Chestertown	stat	Maryland 21620 e
12. Sta	te Historic Pre	servation O	fficer Certification
	nificance of this property within th		
	_ national state	X local	
665), I hereby nom		n the National Register an	C Preservation Act of 1966 (Public Law 89– and certify that it has been evaluated on and Recreation Service.
State Historic Pres	servation Officer signature	Mith	6-30-83
title	STATE HISTORIC PRESER	VATION OFFICER	date
For HCRS use of		···· News I Pagista	
I nereby cert	tify that this property is included i	in the National Hegister  Intered in Register  Register	date 8/4/83
Keeper of the Na	ational Register	# # # # # # # # # # # # # # # # # # #	date 3/1/00 ema
Attest:	· ·		date
Chief of Registra	ation # -		

## **United States Department of the Interior National Park Service**

# National Register of Historic Places Inventory—Nomination Form

K-465
For NPS use only received data entered

Continuation sheet

Brampton
Kent County, Maryland

Item number

7

**Page** 

1

GENERAL DESCRIPTION (Continued)

A two-story frame wing extends to the rear, at the southeast corner of the building. This wing - possibly once an independent structure of somewhat earlier date - is three bays wide by one bay deep, clad in narrow weatherboards. A one-story enclosed entry porch across the central bay of the east facade is a mid-20th-century alteration, replacing the original formal entrance with transom and sidelights shown in photographs taken in 1936 in possession of the owners. Above the entrance is a tripartite window consisting of a 6/6 sash flanked by vertical 2/2 elements. The outlying bays hold 6/6 sash on both stories. At the rear of the ell, a one-bay two-story porch abuts the main house; this porch has been enclosed post-1936. The 1936 photographs also depict a lower and narrower two-bay gable-roofed frame section, with exterior brick chimney, against the south end of the ell; this section has vanished. The ell has a shallow, hipped roof with a bracketed cornice; a chimney rises from the ridge between the central and southern bays.

The interior of the main block remains essentially unaltered, retaining almost all its original plan, finishes, and ornament. The building exhibits a center-hall plan, with one room on either side. The principal stair is of the open-string type, with elaborate scrolled stair brackets, and rises in three curving flights from the entrance hallway. A heavy turned walnut newel post with an octagonal base and carved acanthus and rope motifs anchors the stair; its general shape is echoed by the turned walnut balusters, two per step, which support the heavy walnut handrail.

Door and window strim and baseboards throughout the main block are of walnut with complex molding profiles. Doors are also of walnut, with four panels defined by Greek-ogee-and-bevel molding. Slate mantel with round-headed openings appears in each first- and second-floor room; those on the first floor feature carved pilasters, and the living room mantel has a carved cartouche-like central element. Interior walls are finished in plaster; first floor rooms have cornices consisting of a large cyma reversa above a cove molding, and elaborate floral ceiling medallions of plaster.

A frame garage and adjacent tool shed are located behind the house; these outbuildings do not contribute to the significance of the property.

NPS Form 10-900-a

### **United States Department of the Interior National Park Service**

## **National Register of Historic Places Inventory—Nomination Form**

Brampton

Continuation sheet Kent County, Maryland Item number

10

K-465

OMB No. 1024-0018 Exp. 10-31-84

For NPS use only received date entered

Page


2

### BOUNDARY DESCRIPTION:

The boundaries of the nominated property are shown on the attached plat.

### BOUNDARY JUSTIFICATION:

The 4.3 acres included in this nomination were selected from the surrounding open agricultural land as the minimum property necessary to encompass the house and convey its historic setting. As indicated on the attached plat, boundaries were determined primarily by the visual and physical barriers of a line of trees on the west and a line of utility poles on the east; the nominated acreage was also intended to maintain the historic relationship of the house to Maryland Route 20 on the north.



Mr.+ Mrs. Robert Sparre Rt. 20, w of Chesterrown, MJ.

Brampton, K-465