



National Register of Historic Places Registration Form

This form is for use in nominating or requesting determinations for individual properties and districts. See instructions in National Register Bulletin, *How to Complete the National Register of Historic Places Registration Form*. If any item does not apply to the property being documented, enter "N/A" for "not applicable." For functions, architectural classification, materials, and areas of significance, enter only categories and subcategories from the instructions. **Place additional certification comments, entries, and narrative items on continuation sheets if needed (NPS Form 10-900a).**

1. Name of Property

historic name Maysville Historic District
other names/site number _____

2. Location

street & number Bounded by Virginia St., Ann St., Duval St., and Houston St. See PP. 3-4 for a complete list of addresses not for publication
city or town Mobile vicinity
state Alabama code AL county Mobile code 097 zip code 36604&05

3. State/Federal Agency Certification

As the designated authority under the National Historic Preservation Act, as amended,
I hereby certify that this x nomination ___ request for determination of eligibility meets the documentation standards for registering properties in the National Register of Historic Places and meets the procedural and professional requirements set forth in 36 CFR Part 60.
In my opinion, the property x meets ___ does not meet the National Register Criteria. I recommend that this property be considered significant at the following level(s) of significance:
 national statewide x local
[Signature] /Executive Director _____ Date November 7, 2013
Alabama Historical Commission
State or Federal agency/bureau or Tribal Government

In my opinion, the property ___ meets ___ does not meet the National Register criteria.
Signature of commenting official _____ Date _____
Title _____ State or Federal agency/bureau or Tribal Government

4. National Park Service Certification

I hereby certify that this property is:

entered in the National Register

determined eligible for the National Register

determined not eligible for the National Register

removed from the National Register

other (explain:)


Signature of the Keeper

12/25/13
Date of Action

5. Classification

Ownership of Property

(Check as many boxes as apply.)

- private
- public - Local
- public - State
- public - Federal

Category of Property

(Check only one box.)

- building(s)
- district
- site
- structure
- object

Number of Resources within Property

(Do not include previously listed resources in the count.)

Contributing	Noncontributing	
585	472	buildings
		district
1		site
		structure
		object
586	472	Total

Name of related multiple property listing

(Enter "N/A" if property is not part of a multiple property listing)

N/A

Number of contributing resources previously listed in the National Register

N/A

6. Function or Use

Historic Functions

(Enter categories from instructions.)

Domestic: Single Dwelling

Domestic: Multiple Dwelling

Commerce/Trade: Business

Recreation & Culture: Sports Facility

Current Functions

(Enter categories from instructions.)

Domestic: Single Dwelling

Domestic: Multiple Dwelling

Commerce/Trade: Business

Recreation & Culture: Sports Facility

Landscape: Park

Religion: Religious Facility

Education: School

7. Description

Architectural Classification

(Enter categories from instructions.)

Late Victorian

Classical Revival

Bungalow/Craftsman

Modern Movement

OTHER: Shotgun; Minimal Traditional

Materials

(Enter categories from instructions.)

foundation: Brick, Concrete

walls: Brick, Concrete, Asbestos,

Stucco

roof: Asphalt, Metal

other: Wood: weatherboard

The Maysville Historic District is bounded to the north by Virginia Street, Houston Street to the west, Duval Street to the south, and S. Ann Street to the east. This boundary includes all or part of the following streets:

Amsterdam Street, S. Ann Street, Antwerp Street, Arlington Street, Bay Avenue, Belfast Street, Booker Street, Brussels Street, Buck Street, California Street, Cloverleaf Circle North, Cloverleaf Circle South, Colgin Street, Dexter Avenue, Dominick Street, Douglas Street, Dublin Street, Dublin Street East, Duval Street, Elliot Street, Flint Street, Gaynor Street, Ghent Street, Grove Street, Houston Street, Illinois Street, Lemon Street, Leo Street, Lomeroy Street, Lott Street, McArthur Street, Melrose Street, Michigan Avenue, Midway Avenue, Old Canal Street, Olive Street, Opal Street, Orange Street, Partridge Street, Plover Street, Quail Street, Quita Street, Rev Rt. Days Street, Rev Rt. Thomas Drive, Rotterdam Street, Sligo Street, Sunset Avenue, Tennessee Street, Tisdale Street, Tuttle Avenue, Virginia Street, Waterford Street, Weinacker Avenue, Wexford Street, and Wisconsin Avenue.

The Maysville Historic District Addresses

Amsterdam Street: 1009, 1011, 1057, 1059, 1107, 1109, 1115, 1160, 1205;

S. Ann Street: 508, 510, 512, 1050, 1054, 1060, 1064, 1100, 1110, 1152, 1154, 1156, 1200, 1204, 1206, 1208, 1210, 1250, 1252, 1254, 1256, 1258, 1260, 1300, 1302, 1304, 1306

Antwerp Street: 903, 906, 909, 950, 1004, 1008A, 1008B, 1073, 1075, 1077, 1103, 1108, 1109, 1151, 1200, 1207, 1252, 1256

Arlington Street: 1360

Bay Avenue: 1304, 1307, 1308, 1310, 1311, 1312, 1313, 1315, 1316, 1317, 1318, 1319, 1320, 1321, 1323, 1324, 1325, 1326, 1327, 1328, 1329, 1333, 1456

Belfast Street: 1600, 1602, 1604, 1608, 1611, 1651, 1652, 1653, 1654, 1655, 1656, 1657, 1658, 1659, 1703, 1705, 1707, 1709, 1711, 1753, 1756, 1757, 1758

Booker Street: 405, 406, 407, 408, 409, 410, 411, 412, 451, 452, 456, 457, 458, 459, 461, 463, 503, 507, 551

Brussels Street: 1054, 1056, 1057, 1059, 1102, 1104, 1105, 1106, 1107, 1157, 1158, 1160, 1161, 1162, 1201, 1202, 1203, 1206, 1250, 1255

Buck Street: 1652, 1659, 1701, 1703, 1704, 1705, 1706, 1707

California Street: 1454, 1457, 1507, 1509, 1557, 1559, 1561

Cloverleaf Circle North: 1304, 1305, 1306, 1307, 1308, 1309, 1310, 1311, 1350, 1351, 1352, 1353, 1354, 1355, 1356, 1357, 1358, 1400, 1401, 1402, 1403, 1404, 1405, 1406, 1407, 1409, 1456, 1457, 1458, 1460, 1462

Cloverleaf Circle South: 1304, 1305, 1306, 1307, 1308, 1309, 1310, 1311, 1350, 1351, 1352, 1353, 1354, 1355, 1356, 1357, 1359, 1400, 1401, 1402, 1403, 1404, 1405, 1406, 1407, 1408, 1409, 1451, 1456, 1459, 1461, 1463

Colgin Street: 1501, 1503, 1504, 1506, 1507, 1508, 1509, 1510, 1511, 1512, 1516, 1517, 1518, 1519, 1521, 1524, 1525, 1550, 1553, 1554, 1555, 1557, 1558, 1559, 1560, 1561, 1562, 1563, 1565, 1566, 1569, 1572, 1573

Dexter Avenue: 500, 504, 505, 506, 508, 509, 510, 511, 512, 513, 514, 515, 550, 551, 552, 553, 554, 555, 556, 557, 558, 559, 560, 562, 563, 564, 565, 600, 602, 604, 606, 607, 608, 609, 610, 611, 612, 613, 614, 615

Dominick Street: 1500, 1503, 1505, 1506, 1507, 1508, 1509, 1510, 1512, 1514, 1515, 1516, 1517, 1518, 1519, 1520, 1521, 1523, 1550, 1551, 1551 ½, 1552, 1553, 1555, 1556, 1557, 1559, 1561, 1563, 1565, 1567, 1569, 1570, 1572, 1574, 1655, 1659, 1660, 1661, 1700, 1701, 1702, 1704, 1750, 1753, 1754, 1755, 1756

Douglas Street: 1305, 1307, 1309, 1311, 1351, 1353, 1355, 1357, 1359, 1401, 1403, 1405, 1451, 1453, 1455, 1460, 1462, 1464, 1466

Dublin Street: 1605, 1607, 1608, 1610, 1612, 1650, 1651, 1653, 1654, 1656, 1658, 1660, 1661, 1700, 1701, 1702, 1703, 1705, 1751, 1752, 1753, 1754, 1755, 1757, 1759, 1760, 1762, 1766, 1768

Dublin Street East: 1567, 1576, 1588, 1596, 1600, 1602

Duval Street: 1520, 1552, 1556, 1558, 1560, 1562, 1564, 1566, 1582, 1606, 1614, 1654, 1658, 1760

Elliot Street: 1651, 1655, 1656, 1702, 1704, 1705, 1706

Flint Street: 500, 501, 502, 503, 504, 505, 506, 507, 509, 510, 511, 512, 513, 514, 515, 550, 551, 552, 553, 554, 555, 556, 557, 558, 559, 560, 561, 562, 563, 564, 565

Gaynor Street: 1501, 1507, 1509, 1511, 1513, 1515, 1517, 1519, 1521, 1523, 1551, 1553, 1555, 1557, 1561, 1563, 1567, 1575

Ghent Street: 954, 955, 957, 958, 959, 960, 961, 962, 963, 964, 1002, 1004, 1006, 1007, 1008, 1009, 1015, 1054, 1056, 1058, 1102, 1106, 1150, 1156, 1157, 1158, 1159, 1163, 1203, 1204, 1205, 1207, 1210, 1211, 1212, 1251, 1253, 1256, 1259

Grove Street: 1355, 1357, 1358, 1404, 1405, 1406, 1407, 1408, 1409, 1410, 1411

Houston Street: 1003, 1005, 1009, 1011, 1013, 1015, 1017, 1051, 1053, 1055, 1057, 1059, 1061, 1063, 1065, 1101, 1103, 1105, 1107, 1109, 1111, 1113, 1117, 1153, 1163, 1203, 1205, 1207, 1211, 1213, 1215, 1251

Illinois Street: 1300, 1302, 1352, 1555, 1556, 1558, 1561, 1562, 1605, 1606, 1607

Lemon Street: 1500, 1503, 1506, 1507, 1508, 1512, 1515, 1516, 1518, 1520, 1522, 1550, 1552, 1554, 1556, 1558, 1563, 1565, 1567, 1568, 1570, 1571, 1572, 1574

Leo Street: 1250, 1251, 1252, 1253, 1254, 1255, 1256, 1257, 1258, 1259, 1260, 1261, 1300, 1301, 1302, 1303, 1304, 1306

Lomeroy Street: 1700, 1701, 1702, 1703, 1704, 1705, 1706, 1707

Lott Street: 452, 454, 502, 504, 506, 508

McArthur Street: 1304, 1305, 1306, 1307, 1308, 1309, 1310, 1311, 1350, 1351, 1352, 1354, 1355, 1356, 1357, 1358, 1359, 1400, 1401, 1402, 1403, 1404, 1405, 1407, 1450, 1451, 1452, 1454, 1455, 1457

Melrose Street: 1304, 1308, 1310, 1312, 1314, 1316, 1318, 1354, 1356, 1357, 1358, 1359, 1360, 1400, 1404, 1405, 1406, 1407, 1408, 1410

Michigan Avenue: 500, 501, 502, 503, 505, 506, 508, 509, 510, 512, 513, 514, 550, 551, 552, 553, 554, 555, 556, 557, 558, 559, 560, 561, 562, 563, 565, 1146, 1148, 1161, 1200, 1201, 1203, 1207, 1210, 1214, 1250, 1258, 1260

Midway Avenue: 1553, 1555, 1566, 1574, 1601, 1606, 1651, 1653, 1655, 1657, 1659, 1660, 1700, 1701, 1705, 1756, 1758

Old Canal Street: 1700, 1701

Olive Street: 1250, 1251, 1252, 1253, 1254, 1255, 1256, 1259, 1260, 1261, 1300, 1301, 1302, 1303, 1304, 1305, 1307, 1308, 1309

Opal Street: 903, 907, 913

Orange Street: 1501, 1503, 1505, 1506, 1507, 1509, 1510, 1511, 1512, 1513, 1515, 1516, 1517, 1518, 1519, 1521, 1522, 1523, 1524, 1550, 1551, 1553, 1554, 1556, 1557, 1558, 1559, 1560, 1561, 1562, 1563, 1564, 1567, 1568, 1569, 1570, 1571, 1572, 1573, 1575

Partridge Street: 1104, 1120, 1122, 1124, 1150, 1152, 1154, 1204, 1250, 1252, 1254, 1256, 1260

Plover Street: 1504, 1505, 1508, 1509, 1510, 1511, 1513, 1514, 1515, 1517, 1518, 1519, 1521, 1550, 1551, 1552, 1555, 1556, 1557, 1558, 1560, 1561, 1562, 1563, 1564, 1565, 1566, 1567, 1568, 1569, 1570, 1571, 1575

Quail Street: 1252, 1255

Quita Street: no addresses, see inventory

Rev Rt Days Street: 1255, 1257

Rev Rt Thomas Drive: 1402

Rotterdam Street: 1002, 1003, 1004, 1006, 1010, 1051, 1053, 1055, 1056, 1057, 1058, 1060, 1062, 1066, 1100, 1102, 1107, 1108, 1109, 1113, 1115, 1117, 1150, 1151, 1156, 1159, 1200, 1203, 1205, 1206, 1207, 1210, 1212

Sligo Street: 1610, 1611, 1613, 1652, 1653, 1654, 1657, 1700, 1704, 1705, 1756

Sunset Avenue: 957, 961, 962, 964, 969

Tennessee Street: no addresses, see inventory

Tisdale Street: 400, 402, 405, 451, 453, 455, 456, 457, 458, 459, 505, 507, 509, 551, 553, 555, 556

Tuttle Avenue: 503, 504, 505, 507, 508, 509, 510, 512, 550, 554, 556, 558, 559, 561, 562, 564, 565, 600, 602, 604, 605, 606, 608, 609, 611, 613

Virginia Street: 1301, 1303, 1457, 1459, 1551, 1553, 1555, 1557, 1559, 1561, 1563, 1565, 1603, 1605, 1607, 1621, 1653, 1655, 1657, 1659, 1759

Waterford Street: 1653, 1654, 1656, 1658, 1700, 1701, 1704, 1705, 1706, 1707, 1708, 1710, 1712, 1754, 1756, 1757, 1759

Weinacker Avenue: 410, 412, 414, 453, 456, 457, 458, 460, 500, 501, 502, 504, 505, 507, 509, 553, 555, 557, 559, 909, 911, 913, 915, 928, 950, 952, 953, 954, 955, 956, 967, 969, 970, 972, 974, 975, 981, 982

Wexford Street: 1601, 1603, 1604, 1605, 1609, 1616, 1652, 1653, 1654, 1655, 1660, 1703, 1705, 1707, 1709, 1711, 1714, 1716, 1717, 1718, 1719

Wisconsin Avenue: 505, 506, 507, 508, 509, 511, 512, 513, 515, 552, 553, 554, 555, 556, 557, 558, 559, 561, 562, 563, 564, 565, 600, 602, 604, 605, 606, 607, 608, 609, 610, 611, 613, 615, 617

Narrative Description

(Describe the historic and current physical appearance of the property. Explain contributing and noncontributing resources if necessary. Begin with a **summary paragraph** that briefly describes the general characteristics of the property, such as its location, setting, size, and significant features.)

Summary Paragraph

The Maysville Historic District is located approximately 2 ¼ miles west of Downtown Mobile. A late 19th and early 20th century neighborhood, the district is representative of such developments in Mobile during that period. Maysville continues the 19th century grid pattern that characterizes most of the city. The area is well shaded with oaks and pines and contains approximately 451 acres.

Narrative Description

The Maysville Historic District is located 2 ¼ miles west of the downtown area and consists of 1121 primary buildings covering an area of approximately 451 acres. The district is bounded on the north by Virginia Street, on the east by S. Ann Street, on the south by Duval and Arlington Street, and on the west by Houston Street.

The Maysville Historic District (1871-1960) was settled as a late 19th and early 20th century working and lower-middle class neighborhood in close proximity to the Government and Ann Street trolley lines. The development of the area follows typical late 19th and early 20th century planning. Blocks follow a mostly grid-like pattern and average approximately 250 feet by 600 feet. The streets are asphalt paved and mostly concrete curbed. Many of the streets are flanked by concrete sidewalks. Most streets in Maysville average a width of 30 feet, although Michigan Avenue is a major commercial corridor that is approximately 45 feet, widening to 70 feet near the southern boundary of the district at Duval Street. The streets are lined with rectangular lots averaging a frontage of 50 feet by 150 feet deep. Occasionally, lots have been doubled or subdivided. Houses in the district are set back 15 to 20 feet and with informally landscaped yards, although a few are more heavily planted and well shaded.

Housing forms and styles throughout the district reflect the range of styles and forms popular from 1900 to 1960. Most of the housing forms found in the district include one story bungalows, contemporary, Foursquare, irregular, L-plan, Massed plan, Minimal Traditional, Ranch, rectangular plan and shotgun. Because of the working class nature of the district, these forms, which are often very modest, appear in a variety of styles such as Late Victorian, Classical Revival, Colonial Revival and Craftsman.

The district is primarily residential, with 1034 (92%) out of 1121 resources constructed as housing. Residences are concentrated throughout the district except along Michigan Avenue, which is a major commercial corridor, and portions of Duval, Houston and Old Canal Street. Most of the residential buildings are one story in height with a few divided between one-and-one half story and two story examples. The majority of all resources are frame construction. The remainder are typically brick or brick veneer.

The contributing archaeological site in the district consists of all the vacant lots. Historically, some of these once had dwellings, while others have never been developed.

The vacant lots are mostly overgrown with grass, and some have trees. These lots, particularly where buildings have been razed, have the potential to yield information about the growth and development of the neighborhood.

Inventory

The following information was compiled from historic research and field surveys by Mr. Shaun Wilson, a Preservation Consultant with the Mobile Historic Development Commission. Beginning in October 2010 and progressing through September 2011, Mr. Wilson did a thorough survey of the entire district, photographing and describing both the contributing and noncontributing buildings.

Most construction dates are circa, based on the period of development of the particular street on which the building is located and the architectural characteristics of the building itself. In the case of exact dates, these were obtained by city directory references, title and tax record research.

Other sources include published material from the Municipal Archives and unpublished material maintained in the files of the Mobile Historic Development Commission. The majority of outbuildings were not counted as they are small, utilitarian in design and located at the rear of the properties, where they could not be clearly seen from the street. However, garage/apartments located near the street were counted. Buildings in which porches have been enclosed for additional living space have been counted as noncontributing; whereas those with screened porches have been counted as contributing.

Inventory Key

Each property description begins with an inventory number, which runs sequentially upwards. The address follows, then the date, then the name of the business or church if relevant, then the architectural description. Finally, the NR photo number of the photograph depicting the property where appropriate, followed by a "C" for contributing and "NC" for noncontributing.

Building Inventory:

Amsterdam Street

1. 1009 Amsterdam Street. Circa 1980. 1 story brick veneered building of contemporary design, gable roof, concrete slab foundation, three bay facade, entrance under projecting gabled porch supported by brick columns, lattice screens at entrance, metal frame 9/6 windows and picture window. NC
2. 1011 Amsterdam Street. Circa 1965. 1 story vinyl sided building of contemporary styling, side gable, brick foundation, four bay facade, entrance under projecting shed roof supported by decorative iron posts, 2/2 metal frame windows, building brick veneered to window sills. NC
3. 1057 Amsterdam Street. Circa 1970. 1 story vinyl sided building of contemporary design, concrete slab foundation, three bay facade, entrance under projecting gabled porch supported by decorative iron posts, metal frame and awning windows, carport under portion of projecting gable, louvered vent in porch gable, building brick veneered to window sills. NC
4. 1059 Amsterdam Street. Circa 1940. 1 story asbestos sided Minimal Traditional with gable roof, brick foundation, three bay facade, entrance within recessed corner porch now infilled, wood frame windows, awnings over windows and porch, louvered vent in gable. C
5. 1107 Amsterdam Street. Circa 1975. 1 story brick veneer building of contemporary design, gable roof, concrete slab foundation, four bay facade, entrance under attached gabled porch supported by decorative iron posts, metal frame windows, second entrance to addition added along north elevation. NC

6. 1109 Amsterdam Street. Circa 1980. 1 story brick veneer Ranch style house with gable roof, concrete slab foundation, three bay facade, entrance under attached gabled porch supported by square posts, metal frame 2/2 windows, louvered vent in main gable, carport under main roof supported by iron post. NC
7. 1115 Amsterdam Street. Circa 1985. 1 story vinyl sided building of contemporary design, hip roof, concrete slab foundation, three bay facade, entrance with door hood, metal frame 1/1 windows. NC
8. 1160 Amsterdam St. Circa 1975. 1 story brick veneer building of contemporary styling, concrete foundation, hip roof, three bay facade, central entrance under recessed porch supported by brick columns, metal frame windows. NC
9. 1205 Amsterdam Street. Circa 1945. 1 story asbestos sided Minimal Traditional with gable roof, brick pier foundation, three bay facade, central entrance under attached shed roofed porch supported by square posts, tripled 1/1 window and 3/1 window with awning. C

S. Ann Street

10. 508 S. Ann Street. Circa 1970. 1 story brick veneer free standing 20th century commercial building with flat roof, concrete slab foundation, four bay facade, double door entrance, metal frame windows, paved parking in front. NC
11. 510 S. Ann Street. Circa 1965. 1 story brick veneer free standing 20th century commercial building with flat roof, concrete slab foundation, three bay facade, double door entrance, metal frame windows, gabled portico supported by circular columns, paved parking in front. NC
12. 512 S. Ann Street. Circa 1970. 1 story brick veneer free standing 20th century commercial building with flat roof, concrete slab foundation, four bay facade, two entrances, windows covered. NC
13. 1050 S. Ann Street. Circa 1955. 1 story brick veneer Minimal Traditional with side gable roof, raised brick foundation, three bay facade, central entrance under attached shed roofed porch with decorative iron supports, metal frame windows, chimney at facade, intersecting front gabled bay, garage attached to south elevation at later date. NC
14. 1054 S. Ann Street. Circa 1950. 1 story wood frame Minimal Traditional with side gable roof, raised brick foundation, three bay facade, intersecting front gabled bays with entrance within smaller bay, metal frame 8/8 windows, louvered vent in larger front gabled bay, brick chimney at facade. C [Photo #15]
15. 1060 S. Ann Street. Circa 1970. 1 story vinyl sided and brick veneer contemporary style building with side gable roof, concrete slab foundation, five bay facade, entrance under recessed porch supported by square columns, porch abuts intersecting gabled bay, metal frame windows. NC
16. 1064 S. Ann Street. Circa 1975. 1 story perma-stone contemporary style building with side gable roof, concrete slab foundation, five bay facade, windows and doors covered by plywood, recessed porch across facade, intersecting front gabled bay, attached garage converted into living space, interior chimney. NC
17. 1100 S. Ann Street. Circa 1970. 1 story brick veneer contemporary style building with side gable roof, concrete foundation, five bay facade, entrance under recessed porch supported by square columns, metal frame windows, intersecting front gabled bay. NC
18. 1110 S. Ann Street. Circa 1970. 1 story brick veneer contemporary style building with side gable roof, concrete foundation, three bay facade, entrance under recessed porch supported by brick columns, paired metal frame windows, side chimney. NC

19. 1152 S. Ann Street. Circa 1950. 1 story brick veneer Minimal Traditional with side gable roof, raised brick foundation, four bay facade, central entrance, paired and single 1/1 metal frame windows, intersecting front gabled bay, addition added to south elevation at later date. NC
20. 1154 S. Ann Street. Circa 1955. 1 story wood frame Minimal Traditional with side gable roof, raised brick foundation, three bay facade, central entrance under attached door hood with decorative iron supports, 8/8 metal frame windows, chimney at facade. C
21. 1156 S. Ann Street. Circa 1970. 1 story brick veneer contemporary style building with hip roof, concrete slab foundation, three bay facade, central entrance in projecting hipped bay, metal frame windows and picture window, interior chimney. NC
22. 1200 S. Ann Street. Circa 1945. 1 story wood frame Minimal Traditional with side gable roof, raised brick foundation, five bay facade, central entrance with door hood supported by decorative iron, 6/6 metal frame windows, side chimney. C
23. 1204 S. Ann Street. Circa 1945. 1 story wood frame Minimal Traditional with side gable roof, raised brick foundation, three bay facade, central entrance with door hood supported by decorative iron, paired metal frame windows with awnings, side chimney. C
24. 1206 S. Ann Street. Circa 1940. 1 story wood frame Minimal Traditional with side gable roof, raised brick foundation, three bay facade, central entrance under projecting gable supported by brick arch, metal frame windows, side chimney, awnings over windows. C
25. 1208 S. Ann Street. Circa 1925. 1 story wood frame bungalow with gable roof, raised brick foundation, three bay facade, entrance under attached gabled porch supported by battered posts on brick piers, paired 3/1 windows, 4 pane light in main gable. C
26. 1210 S. Ann Street. Circa 1965. 1 story brick building of contemporary style, side gable roof, concrete foundation, four bay facade, offset entrance, metal frame windows. NC
27. 1250 S. Ann Street. Circa 1940. 1 story asbestos sided duplex with side gable roof, raised brick foundation, four bay facade, entrance either end with projecting gables over stoops, wood frame windows. C
28. 1252 S. Ann Street. Circa 1945. 1 story wood frame Minimal Traditional with side gable roof, raised brick foundation, three bay facade, entrance under recessed porch supported by classical columns, paired 6/6 metal frame windows, interior and side chimney. C
29. 1254 S. Ann Street. Circa 1925. 1 story wood frame bungalow with side gable roof, raised brick foundation, two bay facade, entrance at infilled attached gabled porch supported by posts on brick piers, awning windows, exposed rafters, side chimney. C
30. 1256 S. Ann Street. Circa 1930. 1 story wood frame bungalow with gable roof, raised brick foundation, five bay facade, central entrance in infilled porch, brick columns still visible at corners, metal frame windows, side chimney, louvered vent in gable, exposed rafters. NC
31. 1258 S. Ann Street. Circa 1935. 1 story wood frame Minimal Traditional with side gable roof, raised brick foundation, three bay facade, entrance at intersecting facing gable, 8/8 windows and paired 6/6 wood frame windows, exposed rafters, louvered vent in facing gable. C

32. 1260 S. Ann Street. Circa 1950. 1 story wood frame Minimal Traditional with side gable roof, raised brick foundation, three bay facade, entrance with door hood over stoop, paired 6/6 windows and bank of 6/6 metal frame windows. C
33. 1300 S. Ann Street. Circa 1935. 1 story wood frame Minimal Traditional with side gable roof, raised brick foundation, three bay facade, central entrance with projecting gable over stoop with decorative iron supports, paired 6/6 windows and casement windows, exposed rafters, side chimney. C
34. 1302 S. Ann Street. Circa 1940. 1 story wood frame Minimal Traditional with side gable roof, raised brick foundation, three bay facade, central entrance with projecting gable supported by battered brick arch over stoop, paired 3/1 wood frame windows, side chimney. C
35. 1304 S. Ann Street. Circa 1930. 1 story wood frame bungalow with gable roof, raised brick foundation, three bay facade, entrance under projecting gabled porch supported by square posts on brick piers, paired and single 3/1 windows, side chimney. C
36. 1306 S. Ann Street. Circa 1915. 1 story wood frame cottage with side gable roof, raised brick foundation, three bay facade, entrance under gabled porch supported by square posts, picture windows. C

Antwerp Street

37. 903 Antwerp Street. Circa 1940. 1 story wood frame Minimal Traditional with side gable roof, raised brick foundation, three bay facade, entrance under projecting hip roof porch supported by turned posts, metal frame windows. C
38. 906 Antwerp Street. Circa 1925. 1 story wood frame bungalow with gable roof, raised brick foundation, three bay facade, entrance under projecting gabled porch supported by columns, paired 3/1 wood frame windows, exposed rafters. C
39. 909 Antwerp Street. Circa 1930. 1 story wood frame bungalow with gable roof, raised brick foundation, three bay facade, entrance under gabled porch supported by turned posts, metal frame 2/2 windows, louvered vent in main gable. C
40. 950 Antwerp Street. Circa 1965. 1 story concrete block 20th century commercial building with flat roof, concrete foundation, offset entrance with door hood, windows covered. NC
41. 1004 Antwerp Street. Circa 1920. 1 story wood frame bungalow with hip roof, raised brick foundation, three bay facade, entrance under recessed corner porch supported by battered columns on brick piers, windows covered, addition added south elevation at later date, interior chimney. NC
42. 1008A Antwerp Street. Circa 1910. 1 story wood frame cottage with gable roof, raised brick foundation, two bay facade, entrance in recessed corner porch covered by plywood, window covered by plywood. C
43. 1008B Antwerp Street. Circa 1950. 1 story wood frame duplex with gable roof, raised brick foundation, 1 bay facade, entrances along north elevation, picture window with flanking sidelights, louvered vent in gable, exposed rafters, brick veneer applied up to window sills along façade at later date. NC
44. 1073 Antwerp Street. Circa 1950. 1 story brick veneer Minimal Traditional with side gable roof, raised brick foundation, three bay facade, entrance under projecting gable over stoop with decorative iron supports, paired metal frame 1/1 windows and picture window. C

45. 1075 Antwerp Street. Circa 1930. 1 story wood frame bungalow with gable roof, raised brick foundation, three bay facade, entrance under gabled porch supported by round columns, paired wood frame 3/1 windows, louvered vents in gables, exposed rafters. C
46. 1077 Antwerp Street. Circa 1955. 1 story wood frame Minimal Traditional with side gable roof, raised brick foundation, six bay facade, entrance under recessed porch with decorative iron supports, metal frame 2/2 windows. C
47. 1103 Antwerp Street. Circa 1930. 1 story wood frame bungalow with gable roof, raised brick foundation, three bay facade, entrance under gabled porch with decorative iron supports, paired 3/1 windows and 1/1 wood frame windows, exposed rafters, louvered vents in gables. C
48. 1108 Antwerp Street. Circa 1960. Brick veneered 20th century Institutional style building, flat roof, concrete foundation, banks of windows along facade, inset central entrance. C
49. 1109 Antwerp Street. Circa 1930. 1 story wood frame bungalow with gable roof, raised brick foundation, three bay facade, entrance at gabled porch, brick knee wall and piers, brick veneer to window sills, metal frame windows, louvered vents in gables. C
50. 1151 Antwerp Street. Circa 1960. 1 story brick veneer 20th century commercial building with hip roof and front parapet, entrance at north end of facade, windows covered. NC
51. 1200 Antwerp Street. Circa 1910. 1 story wood frame cottage with hip roof, raised foundation, three bay facade, entrance under projecting gable with decorative iron supports, windows and door covered, porch lowered to grade. NC
52. 1207 Antwerp Street. Circa 1970. 1 story brick veneer building of contemporary style, side gable roof, four bay facade, concrete foundation, entrance under projecting gable with decorative iron supports, metal frame windows, chimney at facade. NC
53. 1252 Antwerp Street. Circa 1965. 1 story brick veneer ecclesiastical building with gable roof, concrete foundation, three bay facade, inset entrance with double doors, narrow single pane windows. NC
54. 1256 Antwerp Street. Circa 1930. 1 story wood frame bungalow with side gable roof, raised brick foundation, four bay facade, entrance located at infilled porch, brick pier still visible, 4/4 windows and picture window with sidelights, intersecting gable rises above apex of side gable. NC

Arlington Street

55. 1360 Arlington Street. Circa 1955. 1 story stucco ecclesiastical building with gable roof, concrete foundation, double door entrance in corner bell tower with pyramidal tower, louvered vent in gable. C

Bay Avenue

56. 1304 Bay Avenue. Circa 1970. 1 story vinyl sided building of contemporary style, hip roof, concrete foundation, four bay facade, recessed entry, metal frame windows and picture window, attached carport. NC

57. 1307 Bay Avenue. Circa 1950. 1 story vinyl sided Minimal Traditional with side gable roof, raised brick foundation, three bay facade, entrance under recessed porch supported by square posts, metal frame windows, side chimney, awning across porch. C
58. 1308 Bay Avenue. Circa 1950. 1 story wood frame Minimal Traditional with side gable roof, raised brick foundation, three bay facade, front facing gabled bay, entrance under attached shed roofed porch supported by square posts, interior chimney, addition at west elevation added at later date. NC
59. 1310 Bay Avenue. Circa 1950. 1 story brick veneer Minimal Traditional with side gable roof, raised brick foundation, three bay facade, entrance under projecting gable supported by square posts over stoop, paired and single metal frame 2/2 windows. C
60. 1311 Bay Avenue. Circa 1940. 1 story wood frame Minimal Traditional with gable roof, raised brick foundation, three bay facade, entrance with projecting gable over stoop with decorative iron supports, paired wood frame 3/1 windows, later alteration to include garage with roll door western portion of facade. NC
61. 1312 Bay Avenue. Circa 1965. 1 story brick veneer building of contemporary style, hip roof, raised brick foundation, entrance at attached hipped porch supported by brick columns, metal frame 6/6 windows, side chimney. NC
62. 1313 Bay Avenue. Circa 1930. 1 story wood frame bungalow with gable roof, raised brick foundation, three bay facade, entrance under projecting gabled porch supported by paired posts on brick piers, paired metal frame 6/6 windows, exposed rafters, louvered vent in main gable. C
63. 1315 Bay Avenue. Circa 1945. 1 story wood frame Minimal Traditional with gable roof, raised brick foundation, three bay facade, entrance under projecting gabled porch supported by square posts, wood frame 1/1 windows. C
64. 1316 Bay Avenue. Circa 1930. 1 story vinyl sided bungalow with gable roof, raised brick foundation, two bay facade, entrance at gabled porch now infilled, brick piers still visible, metal frame 2/2 windows, awning across porch and windows, exposed rafters. NC
65. 1317 Bay Avenue. Circa 1925. 1 story wood frame bungalow with gable roof, raised brick foundation, two bay facade, entrance at infilled porch supported by brick columns, brick knee wall, metal frame 1/1 windows, knee braces and exposed rafters, louvered vents in gables. C
66. 1318 Bay Avenue. Circa 1965. 1 story brick veneer building of contemporary style, concrete slab foundation, three bay facade, hip roof, entrance under projecting hip over stoop supported by decorative iron, metal frame picture window and metal frame 6/6 window. NC
67. 1319 Bay Avenue. Circa 1930. 1 story wood frame bungalow with gable roof, raised brick foundation, two bay facade, entrance at infilled projecting gabled porch, metal frame windows, octagonal louvered vent in main gable, exposed rafters. NC
68. 1320 Bay Avenue. Circa 1960. 1 story wood frame Minimal Traditional with side gable roof, concrete foundation, four bay facade, entrance under projecting shed roofed porch supported by square posts, porch abuts facing gabled bay, metal frame windows, awnings across windows and porch, side chimney. C
69. 1321 Bay Avenue. Circa 1965. 1 story brick veneer building of contemporary style with hip roof, concrete foundation, four bay facade, entrance under projecting hip over stoop with decorative iron supports, metal frame 9/6 windows and 6/6 windows. NC

70. 1323 Bay Avenue. Circa 1970. 1 story brick veneer building of contemporary style with side gable roof, concrete foundation, four bay facade, entrance under shed roof porch supported by posts, metal frame 6/6 windows and 9/6 windows. NC
71. 1324 Bay Avenue. Circa 1915. 1 story vinyl sided cottage with hip roof, raised brick foundation, three bay facade, entrance under recessed porch supported by square paired posts, paired metal frame windows, exposed rafters. C
72. 1325 Bay Avenue. Circa 1980. 1 story brick veneer building of contemporary style, concrete foundation, hip roof, three bay facade, entrance under projecting hipped porch supported by square brick columns, metal frame paired and single 6/6 windows. NC
73. 1326 Bay Avenue. Circa 1955. 1 story vinyl sided Minimal Traditional with side gable roof, concrete foundation, three bay facade, entrance under projecting shed roofed porch with decorative iron supports, metal frame picture window and paired 2/2 windows. C
74. 1327 Bay Avenue. Circa 1970. 1 story brick veneer building of contemporary style, gable on hip roof, concrete foundation, three bay facade, entrance under projecting gabled porch with iron supports, one window covered and metal frame picture window in remaining bay, louvered vent in gable, attached shed roof used as carport. NC
75. 1328 Bay Avenue. Circa 1940. 1 story wood frame Minimal Traditional with side gable roof, raised brick foundation, three bay facade, central entrance, metal frame 6/6 windows, addition added west elevation. NC
76. 1329 Bay Avenue. Circa 1940. 1 story wood frame Minimal Traditional with side gable roof, raised brick foundation, four bay facade, offset entrance, wood frame 6/6 windows. C
77. 1333 Bay Avenue. Circa 1925. 1 story wood frame bungalow with gable roof, raised brick foundation, three bay facade, entrance under recessed porch supported by square brick columns, brick knee wall, paired wood frame 3/1 windows, exposed rafters. C
78. 1456 Bay Avenue. Circa 1965. 1 story 20th century commercial building with flat roof, concrete slab foundation, three bay facade, three auto bays, building in poor condition. NC

Belfast Street

79. 1600 Belfast Street. Circa 1930. 1 story vinyl sided bungalow with gable roof, raised brick foundation, two bay facade, entrance inside projecting gabled porch with decorative iron supports on brick piers, metal frame 1/1 windows, brick veneer applied up to window sills, louvered vent covered. NC
80. 1602 Belfast Street. Circa 1930. 1 story wood frame bungalow with gable roof, raised brick foundation, two bay facade, entrance inside recessed porch supported by square columns on brick piers, picture window and 2/2 metal frame, louvered vent in gable. C
81. 1604 Belfast Street. Circa 1970. 1 story wood frame building of contemporary style with hip roof, raised brick foundation, three bay facade, entrance with gable supported by turned posts over stoop, metal frame paired and single 6/6 windows. NC
82. 1608 Belfast Street. Circa 1965. 1 story brick veneer building of contemporary style with hip roof, concrete foundation, four bay facade, entrance under projecting hip with decorative iron supports, metal frame paired and single 6/6 windows, projecting hipped bay, original carport infilled. NC

83. 1611 Belfast Street. Circa 1985. 1 story brick veneer recreational facility with flat roof, concrete slab foundation, corner entrance with double plate glass doors, metal frame window. NC
84. 1651 Belfast Street. Circa 1925. 1 story wood frame bungalow with gable roof, raised brick foundation, three bay facade, entrance under recessed porch with decorative iron supports on brick piers, brick knee wall, metal frame paired windows, knee braces and exposed rafters. C
85. 1652 Belfast Street. Circa 1940. 1 story wood frame Minimal Traditional with side gable roof, raised brick foundation, three bay facade, entrance under projecting gable supported by posts on brick piers, paired and single metal frame 6/6 windows, brick veneer applied up to window sills at facade, carport added along east elevation. NC
86. 1653 Belfast Street. Circa 1950. 1 story concrete block duplex with hip roof, concrete foundation, four bay facade, entrances at either end of facade under projecting hip roofs with decorative iron supports over stoops, metal frame windows. C
87. 1654 Belfast Street. Circa 1940. 1 story asbestos sided Minimal Traditional with gable roof, raised brick foundation, two bay facade, entrance set within recessed porch with decorative iron supports, porch abuts gabled bay, metal frame windows, awning over windows, louvered vents in gables. C
88. 1655 Belfast Street. Circa 1925. 1 story asbestos sided bungalow with side gable roof, raised brick foundation, three bay facade, entrance under projecting gabled porch supported by battered columns on piers, metal frame windows, louvered vent in gable. C
89. 1656 Belfast Street. Circa 1940. 1 story wood frame Minimal Traditional with hip roof, raised brick foundation, three bay facade, entrance under recessed gabled porch with decorative iron supports, metal frame 2/2 windows, louvered vent in porch gable, exposed rafters. C
90. 1657 Belfast Street. Circa 1960. 1 story brick veneer building of contemporary design with gable roof, concrete foundation, three bay facade, entrance under recessed porch supported by turned posts, balustrade, metal frame 6/6 windows. C
91. 1658 Belfast Street. Circa 1960. 1 story brick veneer Ranch style house with side gable roof, raised brick foundation, three bay facade, entrance with projecting gable with decorative iron supports over stoop, metal frame picture window and paired 2/2 windows. C
92. 1659 Belfast Street. Circa 1960. 1 story brick veneer building of contemporary design with gable roof, concrete foundation, three bay facade, entrance under attached gabled porch supported by columns, metal frame windows. C
93. 1703 Belfast Street. Circa 1965. 1 story brick veneer building of contemporary design with gable roof, concrete slab foundation, entrance under recessed porch with decorative iron supports, metal frame paired 6/6 windows, attached carport east elevation. NC
94. 1705 Belfast Street. Circa 1955. 1 story asbestos sided building of contemporary design, raised brick foundation, entrance at recessed corner porch supported by corner post, metal frame 2/2 windows and picture window with sidelights, louvered vent in gable. C
95. 1707 Belfast Street. Circa 1930. 1 story wood frame bungalow with gable roof, raised brick foundation, three bay facade, entrance under recessed porch supported by turned posts, metal frame paired 6/6 windows, louvered vent in gable, carport attached east elevation. C

96. 1709 Belfast Street. Circa 1940. 1 story wood frame duplex with gable roof, raised brick foundation, four bay facade, entrances under recessed porch with decorative iron supports, metal frame picture windows, louvered vent in gable. C
97. 1711 Belfast Street. Circa 1950. 1 story wood frame building of contemporary design with hip roof, raised brick foundation, three bay facade, entrance under hipped porch supported by square posts, paired and single metal frame 6/6 windows. C
98. 1753 Belfast Street. Circa 1965. 1 story brick veneer building of contemporary style with hip roof, concrete foundation, three bay facade, entrance under projecting hipped porch supported by square posts, metal frame windows. NC
99. 1756 Belfast Street. Circa 1970. 1 story brick veneer building of contemporary style with hip roof, concrete foundation, three bay facade, entrance under projecting hipped porch with decorative iron supports, metal frame picture windows, attached carport east elevation. NC
100. 1757 Belfast Street. Circa 2000. 1 story brick veneer building of contemporary design with multiple hip roofs, concrete foundation, five bay facade, entrance under recessed porch supported by square posts, single and paired metal frame 9/6 windows. NC
101. 1758 Belfast Street. Circa 1930. 1 story wood frame bungalow with gable roof, raised brick foundation, three bay facade, entrance under recessed gabled porch supported by posts on brick piers, metal frame 1/1 windows, louvered vent in peak of gable. C

Booker Street

102. 405 Booker Street. Circa 1935. 1 story wood frame Minimal Traditional with gable roof, raised brick foundation, three bay facade, entrance under projecting gabled porch with decorative iron supports, metal frame 2/2 windows. C
103. 406 Booker Street. Circa 1930. 1 story wood frame bungalow with gable roof, raised brick foundation, two bay facade, entrance at recessed corner porch, wood frame 4/4 windows, exposed rafters, building in state of disrepair. C
104. 407 Booker Street. Circa 1915. 1 story wood frame cottage with gable roof, raised brick foundation, two bay facade, porch infilled as sunroom, metal frame windows, exposed rafters. NC
105. 408 Booker Street. Circa 1930. 1 story wood frame bungalow with gable roof, raised brick foundation, three bay facade, entrance under projecting gabled porch supported by square posts, 2/2 metal frame windows, louvered vent in porch gable. C
106. 409 Booker Street. Circa 1910. 1 story wood frame L-shaped cottage with a complex gable roof, raised brick foundation, two bay facade, entrance at infilled porch, metal frame picture window, metal frame windows in ell. NC [Photo #3]
107. 410 Booker Street. Circa 1930. 1 story wood frame bungalow with gable roof, raised brick foundation, two bay facade, entrance at projecting gabled porch with decorative iron supports on brick piers, metal frame 2/2 windows, louvered vent in main gable. C
108. 411 Booker Street. Circa 1965. 1 story brick veneer building of contemporary style with side gable roof, four bay facade with offset entrance, metal frame 1/1 windows, shed roofed carport added to north elevation. NC
109. 412 Booker Street. Circa 1930. 1 story wood frame bungalow with gable roof, raised brick foundation, three bay facade, entrance under projecting gabled porch supported by square posts, wood frame windows, exposed rafters. NC

110. 451 Booker Street. Circa 1930. 1 story asbestos sided bungalow with gable roof, raised brick foundation, three bay facade, entrance under recessed corner porch supported by post, paired wood frame 3/1 windows and picture window with 2/1 sidelights, louvered vent in gable, exposed rafters. C
111. 452 Booker Street. Circa 1930. 1 story wood frame bungalow with gable roof, raised brick foundation, three bay facade, entrance under projecting gabled porch supported by posts, porch screened with clapboard knee wall, metal frame 6/6 windows, louvered vent in main gable. C
112. 456 Booker Street. Circa 1965. 1 story brick veneer building of contemporary style with gable roof, two bay facade, entrance under recessed porch with decorative iron supports on brick piers, two story rear addition with side gable roof, louvered vent in gable. NC
113. 457 Booker Street. Circa 1930. 1 story wood frame bungalow with gable roof, raised brick foundation, two bay facade, entrance at recessed corner porch supported by square post on brick pier, paired and single wood frame 6/6 windows, louvered vent in gable, brick veneer applied up to window sills. NC
114. 458 Booker Street. Circa 1930. 1 story asbestos sided bungalow with gable roof, raised brick foundation, two bay facade, entrance with transom in one bay with paired wood frame 3/1 windows in other, louvered vent, brick veneer added up to window sills. NC
115. 459 Booker Street. Circa 1925. 1 story wood frame bungalow with gable roof, raised brick foundation, two bay facade, converted into apartments with entrances along south elevation, paired 3/1 windows, porch infilled, louvered vent in gable. NC
116. 461 Booker Street. Circa 1910. 1 story wood frame cottage with gable roof, raised brick foundation, three bay facade, entrance with transom under recessed porch supported by square columns, paired Craftsman style windows and metal frame 1/1 windows, louvered vent in gable, addition added south elevation. NC
117. 463 Booker Street. Circa 1940. 1 story asbestos sided Minimal Traditional with side gable roof, raised brick foundation, three bay facade, entrance with projecting gable over stoop supported by round columns, scalloped bargeboard along projecting gable, paired wood frame windows with metal awnings, exposed rafters. C
[Photo #16]
118. 503 Booker Street. Circa 1935. 1 story wood frame Minimal Traditional with gable roof, raised brick foundation, three bay facade, entrance under projecting gabled porch supported by square posts, metal frame 2/2 windows, louvered vent in main gable covered. C
119. 507 Booker Street. Circa 1930. 1 story wood frame bungalow with gable roof, raised brick foundation, two bay facade, entrance under recessed porch supported by square posts, porch screened with stucco knee wall, wood frame 6/6 window, louvered vent in gable, interior chimney. C
120. 551 Booker Street. Circa 1910. 1 story wood frame cottage with hip roof, three bay facade, entrance with transom under recessed porch supported by square posts, wood frame windows, lattice covers porch. C

Brussels Street

121. 1054 Brussels Street. Circa 1990. 1 story brick veneer building of contemporary design, gable roof, concrete slab foundation, two bay facade, entrance within recessed porch supported by unusual circular archway, 8 spoke circular window

in remaining bay under porch, carport south elevation supported by arch and crenellated at roof. NC

122. 1056 Brussels Street. Circa 1965. 1 story brick veneer building with gable roof, raised brick foundation, two bay facade, entrance within recessed corner porch supported by post, tripled 6/6 metal frame windows, octagonal louvered vent in gable, vinyl siding applied to gable and along eaves. NC
123. 1057 Brussels Street. Circa 1950. 1 story wood frame Minimal Traditional with gable roof, raised brick foundation, three bay facade, entrance under projecting gabled porch supported by square columns, metal frame 2/2 windows, brick veneer applied up to window sills at a later date. NC
124. 1059 Brussels Street. Circa 1965. 1 story concrete block building of contemporary style, hip roof, concrete foundation, four bay facade, entrance under projecting hipped porch supported by posts, metal frame 1/1 window and picture window, carport attached north elevation. NC
125. 1102 Brussels Street. Circa 1930. 1 story brick veneer bungalow with gable roof, raised brick foundation, three bay facade, entrance under attached shed roofed porch supported by turned posts on brick piers, paired wood frame 3/1 windows, louvered vent in gable, brick veneer applied at a later date. NC
126. 1104 Brussels Street. Circa 1930. 1 story wood frame bungalow with gable roof, raised brick foundation, three bay facade, entrance under projecting gabled porch supported by square posts on brick piers, porch screened, metal frame 1/1 windows, exposed rafters. C
127. 1105 Brussels Street. Circa 1930. 1 story wood frame bungalow sided with brick paper, gable roof, raised brick foundation, two bay facade, entrance under recessed corner porch, porch infilled with screening, paired metal frame 1/1 windows, louvered vent in gable. C
128. 1106 Brussels Street. Circa 1950. 1 story brick veneered Minimal Traditional with gable roof, raised brick foundation, three bay facade, entrance under recessed porch supported by square columns, metal frame 6/6 windows. NC
129. 1107 Brussels Street. Circa 1955. 1 story brick veneer Minimal Traditional with side gable roof, concrete foundation, three bay facade, entrance under projecting gabled porch supported by columns, metal frame picture windows. C
130. 1157 Brussels Street. Circa 1970. 1 story brick veneer building of contemporary style, hip roof, concrete slab foundation, three bay facade, entrance under projecting hip roof supported by turned posts over stoop, metal frame 6/6 windows. NC
131. 1158 Brussels Street. Circa 1965. 1 story brick veneer building of contemporary style with hip roof, concrete foundation, three bay facade, entrance under recessed corner porch with decorative iron support, metal frame picture window with sidelights, carport attached south elevation. NC
132. 1160 Brussels Street. Circa 1960. 1 story brick veneer building of contemporary style with gable roof, concrete foundation, three bay facade, entrance under projecting gabled porch with decorative iron supports, metal frame picture window. C
133. 1161 Brussels Street. Circa 1930. 1 story wood frame bungalow with gable roof, raised brick foundation, three bay facade, entrance under recessed porch supported by square columns on brick piers, paired metal frame 1/1 windows, addition at rear of south elevation, louvered vent in gable. C
134. 1162 Brussels Street. Circa 1940. 1 story wood frame Minimal Traditional with gable roof, raised brick foundation, three bay facade, entrance under

projecting gabled porch supported by square posts, porch partially enclosed, metal frame 2/2 windows, louvered vent in gable. NC

135. 1201 Brussels Street. Circa 1960. 1 story vinyl sided Minimal Traditional with gable roof, concrete foundation, five bay facade, entrance with gable over stoop supported by decorative ironwork, metal frame windows, addition to south with attached carport. NC
136. 1202 Brussels Street. Circa 1975. 2 story brick veneered building of contemporary style, combination side gable with hipped second story, concrete slab foundation, four bay facade, entrance under recessed porch with decorative iron supports, metal frame windows, attached garage with metal door. NC
137. 1203 Brussels Street. Circa 1970. 1 story brick veneer building of contemporary style with hip roof, concrete foundation, facade obscured, slightly offset central entrance. NC
138. 1206 Brussels Street. Circa 1965. 1 story brick veneer building of contemporary style with hip roof, concrete foundation, three bay facade, entrance under projecting gabled porch with decorative iron supports, metal frame picture window. NC
139. 1250 Brussels Street. Circa 1920. 1 story wood frame cottage with gable roof, raised brick foundation, three bay facade, entrance with transom under recessed porch supported by turned posts, paired metal frame 6/6 window and metal frame 2/2, louvered vent in gable. C
140. 1255 Brussels Street. Circa 1935. 1 story wood frame Minimal Traditional with gable roof, raised brick foundation, three bay facade, entrance with shed roof supported by post over stoop, paired wood frame 6/6 windows. C

Buck Street

141. 1652 Buck Street. Circa 1965. 1 story brick veneered building of contemporary style, gable roof, concrete foundation, three bay facade, entrance slightly offset from center, metal frame windows. NC
142. 1659 Buck Street. Circa 1990. 1 story brick veneer building of contemporary style, side gable roof, 8 bay facade, entrance under projecting gabled porch supported by columns, metal frame windows. NC
143. 1701 Buck Street. Circa 1925. 1 story asbestos sided bungalow with hip roof, raised brick foundation, three bay facade, entrance under recessed corner porch supported by brick column, paired and single metal frame 6/6 windows. C
144. 1703 Buck Street. Circa 1945. 1 story vinyl sided Minimal Traditional with gable roof, three bay facade, entrance under recessed corner porch supported by square posts, paired and single metal frame 6/6 windows. C
145. 1704 Buck Street. Circa 1945. 1 story wood frame Minimal Traditional with gable roof, raised brick foundation, three bay facade, entrance under projecting gabled porch supported by columns, paired and single 6/6 wood frame windows. C
146. 1705 Buck Street. Circa 1915. 1 story wood frame cottage with hip roof, raised brick foundation, three bay facade, entrance with gable over stoop supported by decorative ironwork, paired metal frame 6/6 windows and picture window with sidelights, exposed rafters. C
147. 1706 Buck Street. Circa 1900. 1 story wood frame cottage with hip roof, raised brick foundation, four bay facade, entrance under recessed porch of projecting gabled bay, wood frame windows covered, louvered vent in gable, awning across porch. C

148. 1707 Buck Street. Circa 1930. 1 story wood frame bungalow with gable roof, raised brick foundation, three bay facade, entrance at recessed corner porch with decorative iron supports, porch screened, paired and single 6/6 wood frame windows, louvered vent in gable. C

California Street

149. 1454 California Street. Circa 1945. 2 story Masonite sided garage/apartment with gable roof, concrete slab foundation, two auto bays first floor, entrance with stairs second floor, wood frame 6/6 windows, exposed rafters, louvered vent in gable. C
150. 1457 California Street. Circa 1980. 1 story brick veneered building of contemporary style with side gable roof, five bay facade, concrete slab foundation, entrance under projecting gabled porch supported by posts, metal frame windows and picture window with sidelights, circular louvered vent in facing gable. NC
151. 1507 California Street. Circa 1970. 1 story brick veneer building of contemporary style with hip roof, concrete foundation, three bay facade, entrance under projecting hip over stoop supported by posts, metal frame 9/6 windows. NC
152. 1509 California Street. Circa 1970. 1 story brick veneer building of contemporary style, hip roof, concrete foundation, entrance under projecting hip porch with decorative iron supports, metal frame 6/6 windows. NC
153. 1557 California Street. Circa 1930. 1 story wood frame bungalow with side gable roof, raised brick foundation, four bay facade, entrance under recessed corner porch in projecting gabled bay supported by square post on brick pier, wood frame 6/1 windows, side chimney. C
154. 1559 California Street. Circa 1910. 1 1/2 story asbestos sided cottage with side gable roof, raised brick foundation, three bay facade, entryway west end of facade with transom and sidelights under recessed porch supported by classical columns on piers, front facing gable with paired window, knee braces, windows covered, fire damaged but salvageable. C
155. 1561 California Street. Circa 1925. 1 story wood frame bungalow with gable roof, raised brick foundation, three bay facade, entrance under projecting gabled porch supported by battered columns on stucco piers, paired wood frame 3/1 windows, louvered vents in gables, knee braces, interior chimney, awning across porch. C

Clover Leaf Circle North

156. 1304 Clover Leaf Circle North. Circa 1980. 1 story perma-stone clad building of contemporary style, hip roof, raised foundation, entrance with shed roof over stoop, metal frame windows with awnings, interior chimney. NC
157. 1305 Clover Leaf Circle North. Circa 1955. 1 story wood frame Minimal Traditional with side gable roof, raised brick foundation, four bay facade, entrance at facing gabled bay with awning over stoop, metal frame 6/6 windows. C
158. 1306 Clover Leaf Circle North. Circa 1950. 1 story asbestos sided Minimal Traditional with side gable roof, raised brick foundation, four bay facade, entrance under recessed porch with decorative iron supports, metal frame 6/6 windows, side chimney, addition added to east elevation. NC
159. 1307 Clover Leaf Circle North. Circa 1960. 1 story wood frame Minimal Traditional with side gable roof, raised brick foundation, three bay facade, entrance under intersecting gabled porch supported by square posts, metal frame windows, side chimney. C
160. 1308 Clover Leaf Circle North. Circa 1955. 1 story asbestos sided Minimal Traditional with side gable roof, raised brick foundation, four bay facade, entrance

at front facing projecting gabled bay, metal frame windows with awnings, later attached garage now infilled to provide additional living space. NC

161. 1309 Clover Leaf Circle North. Circa 1955. 1 story wood frame Minimal Traditional with side gable roof, raised brick foundation, four bay facade, entrance under projecting gabled porch with decorative iron supports, metal frame 6/6 windows. C
162. 1310 Clover Leaf Circle North. Circa 1960. 1 story stucco Minimal Traditional with side gable roof, raised brick foundation, four bay facade, double door entrance under recessed corner porch supported by iron supports on brick piers, variety of metal frame windows. C
163. 1311 Clover Leaf Circle North. Circa 1960. 1 story wood frame Masonite sided building of contemporary style with hip roof, entrance located in intersecting facing gabled bay, metal frame windows and picture window, interior chimney, louvered vent in facing gable. C
164. 1350 Clover Leaf Circle North. Circa 1955. 1 story asbestos sided Minimal Traditional with hip roof, raised brick foundation, three bay facade, entrance located in infilled porch, metal frame windows. NC
165. 1351 Clover Leaf Circle North. Circa 1960. 1 story wood frame building of contemporary style with hip roof, raised brick foundation, four bay facade, entrance under shed roof with decorative iron supports over stoop, metal frame single and paired 6/6 windows, side chimney, addition east elevation. NC
166. 1352 Clover Leaf Circle North. Circa 1955. 1 story wood frame Minimal Traditional with side gable roof, raised brick foundation, three bay facade, central entrance, metal frame 2/2 windows and picture window, attached garage. C
167. 1353 Clover Leaf Circle North. Circa 1955. 1 story wood frame Minimal Traditional with side gable roof, raised brick foundation, five bay facade, entrance under projecting eave of roof over stoop, metal frame 6/6 windows, addition east elevation, interior chimney. C
168. 1354 Clover Leaf Circle North. Circa 1950. 1 story wood frame Minimal Traditional with side gable roof, raised brick foundation, three bay facade, entrance under shed roofed porch supported by posts, metal frame 6/6 windows, side chimney, intersecting facing gable above porch, addition added to east elevation. NC
169. 1355 Clover Leaf Circle North. Circa 1960. 1 story wood frame building of contemporary style with hip roof, raised brick foundation, four bay facade, entrance under projecting gabled porch screened, metal frame 6/6 windows with awnings, side chimney. C
170. 1356 Clover Leaf Circle North. Circa 1955. 1 story wood frame Minimal Traditional with side gable roof, raised brick foundation, four bay facade, entrance located at projecting central bay with facing gable, metal frame 6/6 windows, interior chimney. C
171. 1357 Clover Leaf Circle North. Circa 1945. 1 story wood frame Minimal Traditional with side gable roof, raised brick foundation, three bay facade, entrance at infilled porch, metal frame 6/6 windows. NC
172. 1358 Clover Leaf Circle North. Circa 1960. 1 story wood frame Minimal Traditional with side gable roof, raised brick foundation, five bay facade, entrance under projecting gabled porch supported by brick columns, metal frame picture windows and casement windows, interior chimney. C
173. 1400 Clover Leaf Circle North. Circa 1955. 1 story asbestos sided Minimal Traditional with side gable roof, raised brick foundation, 6 bay facade, entrance

with awning over stoop, metal frame windows with awnings and picture window with sidelights, interior chimney. C

174. 1401 Clover Leaf Circle North. Circa 1945. 1 story asbestos sided Minimal Traditional with side gable roof, raised brick foundation, four bay facade, entrance at facing gable, metal frame 2/2 windows and 6/6 windows, addition added east elevation. NC
175. 1402 Clover Leaf Circle North. Circa 1960. 1 story wood frame building of contemporary design with hip roof, raised brick foundation, three bay facade, entrance under projecting gabled porch supported by posts, metal frame windows and picture window with transom, side chimney. C
176. 1403 Clover Leaf Circle North. Circa 1960. 1 story brick veneer Minimal Traditional with side gable roof, raised brick foundation, four bay facade, entrance located in intersecting facing gabled bay, metal frame 1/1 windows, interior chimney. C
177. 1404 Clover Leaf Circle North. Circa 1955. 1 story asbestos sided Minimal Traditional with side gable roof, raised brick foundation, three bay facade, entrance set within projecting gabled bay with facing gable, metal frame 2/2 windows, attached garage. C
178. 1405 Clover Leaf Circle North. Circa 1965. 1 story wood frame building of contemporary style with hip roof, raised brick foundation, five bay facade, centered entrance, metal frame windows, carport attached east elevation. NC
179. 1406 Clover Leaf Circle North. Circa 1960. 1 story wood frame Minimal Traditional with side gable roof, raised brick foundation, four bay facade, entrance under projecting gable supported by posts over stoop, metal frame windows, intersecting facing gable, side chimney, addition east elevation. NC
180. 1407 Clover Leaf Circle North. Circa 1955. 1 story wood frame Minimal Traditional with side gable roof, raised brick foundation, four bay facade, entrance located at projecting intersecting gabled bay under recessed corner porch with decorative iron support, metal frame window, addition added east elevation. NC
181. 1409 Clover Leaf Circle North. Circa 1955. 1 story wood frame Minimal Traditional with side gable roof, raised brick foundation, three bay facade, offset central entrance, metal frame picture window and 2/2 windows, interior chimney, attached garage infilled, carport added east elevation. NC
182. 1456 Clover Leaf Circle North. Circa 1950. 1 story wood frame building of contemporary design with hip roof, raised brick foundation, four bay facade, entrance under shed roof, metal frame windows with awnings, addition east elevation. NC
183. 1457 Clover Leaf Circle North. Circa 1960. 1 story wood frame Minimal Traditional with side gable roof, raised brick foundation, four bay facade, entrance under projecting gable with decorative iron supports, paired and single metal frame 6/6 windows. C
184. 1458 Clover Leaf Circle North. Circa 1955. 1 story wood frame Minimal Traditional with side gable roof, raised brick foundation, seven bay facade, entrance under projecting gable with decorative iron supports, metal frame windows with awnings, addition north elevation. NC
185. 1460 Clover Leaf Circle North. Circa 1960. 1 story wood frame building of contemporary style with hip roof, raised brick foundation, entrance under recessed porch supported by posts, metal frame windows. C
186. 1462 Clover Leaf Circle North. Circa 1960. 1 story wood frame building of contemporary style with hip roof, raised brick foundation, four bay facade, entrance

under projecting shed roof porch supported by posts, porch added at later date, metal frame single and paired 6/6 windows, interior chimney. NC

Clover Leaf Circle South

187. 1304 Clover Leaf Circle South. Circa 1960. 1 story brick veneer building of contemporary style with side gable roof, raised brick foundation, three bay facade, entrance within recessed corner porch of intersecting facing gabled bay, metal frame 6/6 windows, side chimney, addition east elevation. NC
188. 1305 Clover Leaf Circle South. Circa 1960. 1 story wood frame Minimal Traditional with side gable roof, raised brick foundation, three bay facade, entrance under projecting gabled porch screened, metal frame 6/6 windows, side chimney. C
189. 1306 Clover Leaf Circle South. Circa 1960. 1 story wood frame building of contemporary style with side gable roof, raised brick foundation, three bay facade, entrance under projecting gabled porch screened, metal frame windows, interior chimney. C
190. 1307 Clover Leaf Circle South. Circa 1960. 1 story wood frame Minimal Traditional with side gable roof, raised brick foundation, four bay facade, entrance in facing gabled bay with awning, metal frame 6/6 windows, chimney. C
191. 1308 Clover Leaf Circle South. Circa 1960. 1 story wood frame Minimal Traditional with side gable roof, raised brick foundation, four bay facade, entrance under shed roof with decorative iron supports, paired and single metal frame 1/1 windows, interior chimney. C
192. 1309 Clover Leaf Circle South. Circa 1955. 1 story wood frame Minimal Traditional with side gable roof, raised brick foundation, four bay facade, entrance under projecting gable supported by posts over stoop, facing gabled bay, windows covered, interior chimney. C
193. 1310 Clover Leaf Circle South. Circa 1980. 1 story brick veneer building of contemporary style with side gable roof, concrete foundation, five bay facade, entrance under projecting gable supported by brick columns, metal frame windows, interior chimney. NC
194. 1311 Clover Leaf Circle South. Circa 1960. 1 story wood frame building of contemporary style with hip roof, raised brick foundation, four bay facade, entrance under shed roof, paired metal frame 6/6 windows, interior chimney. C
195. 1350 Clover Leaf Circle South. Circa 1970. 1 story brick veneer building of contemporary style, side gable roof, raised brick foundation, five bay facade, entrance under projecting gable supported by brick columns over stoop, metal frame 6/6 windows, intersecting facing gable, interior chimney. NC
196. 1351 Clover Leaf Circle South. Circa 1950. 1 story wood frame Minimal Traditional with side gable roof, raised brick foundation, four bay facade, offset entrance, metal frame 1/1 windows, interior chimney, addition east elevation. NC
197. 1352 Clover Leaf Circle South. Circa 1960. 1 story wood frame Minimal Traditional with side gable roof, raised brick foundation, five bay facade, entrance under projecting gable porch supported by classical columns, metal frame 6/6 windows and awning windows, side chimney. C
198. 1353 Clover Leaf Circle South. Circa 1960. 1 story wood frame Minimal Traditional with side gable roof, raised brick foundation, four bay facade, entrance under shed roof supported by posts over stoop, facing gabled bay, metal frame 6/6 windows with awnings, interior chimney, addition east elevation. NC

199. 1354 Clover Leaf Circle South. Circa 1960. 1 story wood frame building of contemporary style, hip roof, raised brick foundation, three bay facade, entrance at infilled gabled porch, metal frame 1/1 windows, interior chimney. NC
200. 1355 Clover Leaf Circle South. Circa 1955. 1 story wood frame Minimal Traditional with side gable roof, raised brick foundation, four bay facade, entrance under projecting gabled porch supported by posts, metal frame windows, interior chimney. C
201. 1356 Clover Leaf Circle South. Circa 1960. 1 story brick veneer building of contemporary style with hip roof, raised brick foundation, six bay facade, entrance at infilled gable porch, metal frame windows with awnings, interior chimney. NC
202. 1357 Clover Leaf Circle South. Circa 1960. 1 story brick veneer building of contemporary style with hip roof, concrete foundation, four bay facade, central entrance at intersection of projecting hipped bay, metal frame 1/1 windows, interior chimney, two story rear addition. NC
203. 1359 Clover Leaf Circle South. Circa 1975. 1 story brick veneer house of contemporary style with side gable roof, concrete foundation, four bay facade, entrance under shed roofed porch supported by brick columns, metal frame 6/6 windows, interior chimney. NC
204. 1400 Clover Leaf Circle South. Circa 1955. 1 1/2 story Masonite sided Minimal Traditional with side gable roof, raised brick foundation, four bay facade, entrance under projecting gable supported by posts over stoop, metal frame 2/2 windows, side chimney. C
205. 1401 Clover Leaf Circle South. Circa 1960. 1 story wood frame building of contemporary style with side gable roof, raised brick foundation, three bay facade, entrance at projecting facing gabled bay, paired and single metal frame 6/6 windows, side chimney, addition added east elevation. NC
206. 1402 Clover Leaf Circle South. Circa 1960. 1 story Masonite sided building of contemporary style with hip roof, raised brick foundation, four bay facade, entrance under projecting gabled porch with decorative iron supports, metal frame windows, interior chimney. C
207. 1403 Clover Leaf Circle South. Circa 1960. 1 story wood frame building of contemporary style with hip roof, raised brick foundation, three bay facade, entrance under infilled projecting gabled porch, metal frame 9/6 windows, chimney, addition east elevation. NC
208. 1404 Clover Leaf Circle South. Circa 1960. 1 story Masonite sided Minimal Traditional with side gable roof, raised brick foundation, four bay facade, entrance under projecting shed roofed porch supported by brick columns, intersecting gabled bay, metal frame windows with awnings, attached garage infilled, interior chimney. NC
209. 1405 Clover Leaf Circle South. Circa 1960. 1 story wood frame building of contemporary style with side gable roof, raised brick foundation, four bay facade, entrance under shed roof over stoop, metal frame 6/6 windows and picture window. C
210. 1406 Clover Leaf Circle South. Circa 1960. 1 story wood frame building of contemporary style with hip roof, raised brick foundation, four bay facade, entrance under projecting shed roof supported by turned posts, metal frame 6/6 windows, interior chimney. C
211. 1407 Clover Leaf Circle South. Circa 1960. 1 story wood frame building of contemporary style with side gable roof, raised brick foundation, three bay facade,

entrance under pent roof of projecting facing gabled bay, metal frame 2/2 windows and 6/6 windows, side chimney. C

212. 1408 Clover Leaf Circle South. Circa 1960. 1 story Masonite sided Minimal Traditional with side gable roof, raised brick foundation, four bay facade, entrance at projecting gabled bay, metal frame 1/1 windows, interior chimney, addition east elevation. NC
213. 1409 Clover Leaf Circle South. Circa 1960. 1 story wood frame Minimal Traditional with side gable roof, raised brick foundation, four bay facade, entrance under projecting gable with decorative iron supports over stoop, metal frame 6/6 windows, projecting central facing gabled bay. C
214. 1451 Clover Leaf Circle South. Circa 1950. 1 story asbestos sided Minimal Traditional with side gable roof, raised brick foundation, four bay facade, entrance under projecting gable supported by posts over stoop paired and single metal frame 6/6 windows. C
215. 1456 Clover Leaf Circle South. Circa 1975. 1 story brick veneer Ranch style house with side gable roof, concrete foundation, entrance under projecting gabled porch, metal frame windows. NC
216. 1459 Clover Leaf Circle South. Circa 1960. 1 story Masonite sided building of contemporary style with hip roof, raised brick foundation, four bay facade, entrance under projecting eave of roof, metal frame 2/2 windows, projecting hipped bay, interior chimney. C
217. 1461 Clover Leaf Circle South. Circa 1960. 1 story wood frame building of contemporary style with hip roof, raised brick foundation, four bay facade, entrance under projecting eave of roof, paired and single metal frame windows with awnings. C
218. 1463 Clover Leaf Circle South. Circa 1960. 1 story Masonite sided Minimal Traditional with side gable roof, raised brick foundation, three bay facade, entrance under recessed porch at projecting facing gable, metal frame 6/6 windows, side chimney, addition added north elevation. NC

Colgin Street

219. 1501 Colgin Street. Circa 1940. 1 story asbestos sided Minimal Traditional with gable roof, raised brick foundation, two bay facade, entrance at recessed corner porch supported by post, paired and single metal frame 6/6 windows, louvered vent in gable. C
220. 1503 Colgin Street. Circa 1950. 1 story wood frame building of contemporary design with hip roof, raised foundation, two bay facade, entrance along west elevation with projecting gable supported by turned posts over stoop, attached carport at rear wraps around to west elevation, metal frame windows. NC
221. 1504 Colgin Street. Circa 1950. 1 story wood frame Minimal Traditional with side gable roof, raised brick foundation, four bay facade, entrance under projecting gabled porch supported by posts, metal frame 6/6 windows, louvered vent in porch gable, exposed rafters. C
222. 1506 Colgin Street. Circa 1950. 1 story wood frame Minimal Traditional with gable roof, raised brick foundation, two bay facade, entrance under pent roof porch supported by posts, paired metal frame 1/1 windows, louvered vent in gable. C
223. 1507 Colgin Street. Circa 1950. 1 story wood frame Minimal Traditional with side gable roof, raised brick foundation, three bay facade, entrance under projecting gabled porch with decorative iron supports, paired and single metal frame 2/2 windows, louvered vent in porch gable. C

224. 1508 Colgin Street. Circa 1960. 1 story brick veneer building of contemporary style, gable roof, raised brick foundation, four bay facade, entrance at infilled projecting gabled porch, metal frame windows. NC
225. 1509 Colgin Street. Circa 1930. 1 story wood frame bungalow with gable roof, raised brick foundation, two bay facade, entrance located at infilled porch, paired metal frame 1/1 windows, louvered vent in gable. NC
226. 1510 Colgin Street. Circa 1960. 1 story brick veneer building of contemporary style with gable roof, raised brick foundation, three bay facade, entrance at projecting gable supported by brick columns, metal frame louvered window and picture window, louvered vent in main gable. C
227. 1511 Colgin Street. Circa 1930. 1 story wood frame bungalow with gable roof, raised brick foundation, three bay facade, entrance under projecting gabled porch with decorative iron supports on brick piers, paired wood frame 3/1 windows. C
228. 1512 Colgin Street. Circa 1935. 1 story wood frame bungalow with gable roof, raised brick foundation, three bay facade, entrance under projecting gabled porch with decorative iron supports, metal frame picture window and paired 6/6 windows, exposed rafters, louvered vent in porch gable. C
229. 1516 Colgin Street. Circa 1935. 1 story wood frame Minimal Traditional with gable roof, raised brick foundation, three bay facade, entrance under pent roofed porch supported by turned posts, porch abuts projecting gabled bay with metal frame bay window, louvered vent in gable, exposed rafters. NC
230. 1517 Colgin Street. Circa 1970. 1 story brick veneer building of contemporary style with gable roof, concrete slab foundation, three bay facade, entrance under recessed corner porch supported by slender classical columns, porch at grade, metal frame picture window and 8/8 window. NC
231. 1518 Colgin Street. Circa 1960. 1 story brick veneer building of contemporary style with hip roof, raised brick foundation, three bay facade, entrance under projecting gable porch supported by posts, metal frame 2/2 windows and picture window, addition west elevation. NC
232. 1519 Colgin Street. Circa 1970. 1 story brick veneer building of contemporary style with side gable roof, concrete slab foundation, three bay facade, entrance under projecting gabled porch with decorative iron supports, metal frame 9/6 windows. NC
233. 1521 Colgin Street. Circa 1945. 1 story wood frame Minimal Traditional with side gable roof, raised brick foundation, three bay facade, entrance under recessed corner porch supported by posts, porch abuts projecting gabled bay, wood frame windows covered. C
234. 1524 Colgin Street. Circa 1940. 1 story wood frame Minimal Traditional with gable roof, raised brick foundation, three bay facade, entrance under recessed corner porch supported by posts, metal frame windows, infill eastern half of facade, louvered vent in gable. NC
235. 1525 Colgin Street. Circa 1930. 1 story wood frame bungalow with gable roof, raised brick foundation, three bay facade, entrance under projecting gabled porch supported by posts on brick piers, brick knee wall, porch screened, paired wood frame 3/1 windows, tripled louvered vent in main gable. C
236. 1550 Colgin Street. Circa 1950. 1 story wood frame Minimal Traditional with gable roof, raised brick foundation, three bay facade, entrance under projecting gabled porch supported by square posts, windows covered. C

237. 1553 Colgin Street. Circa 1935. 1 story wood frame Minimal Traditional with gable roof, raised brick foundation, two bay facade, entrance at recessed corner porch supported by square post, metal frame 1/1 windows and picture window. C
238. 1554 Colgin Street. Circa 1955. 1 story wood frame Minimal Traditional with side gable roof, raised brick foundation, four bay facade, entrance under cantilevered shed roof, windows covered, gabled dormer with octagonal louvered vent, addition east elevation. NC
239. 1555 Colgin Street. Circa 1935. 1 story wood frame Minimal Traditional with gable roof, raised brick foundation, two bay facade, entrance at recessed corner porch supported by square post, metal frame 6/6 windows, louvered vent in gable. C
240. 1557 Colgin Street. Circa 1910. 1 story wood frame shotgun with gable roof, raised brick foundation, characteristic two bay facade with entrance under recessed porch with decorative iron supports, metal frame 6/6 window, small addition at rear. C
241. 1558 Colgin Street. Circa 1950. 1 story concrete block building of contemporary style with side gable on hip roof, three bay facade, entrance within projecting gabled porch, paired metal frame 2/2 windows. C
242. 1559 Colgin Street. Circa 1960. 1 story brick veneer building of contemporary style with gable roof, raised brick foundation, three bay facade, entrance under attached gable with decorative iron supports over stoop, metal frame windows and picture window with sidelights, carport attached along length of eastern elevation. NC
243. 1560 Colgin Street. Circa 1935. 1 story wood frame bungalow with side gable roof, raised brick foundation, three bay facade, entrance under infilled porch, paired metal frame window and picture window, exposed rafters, attached carport east elevation. NC
244. 1561 Colgin Street. Circa 1930. 1 story wood frame bungalow with gable roof, raised brick foundation, three bay facade, entrance under recessed gabled porch supported by posts on altered brick knee wall, paired wood frame 3/1 windows. NC
245. 1562 Colgin Street. Circa 1930. 1 story wood frame bungalow with gable roof, raised brick foundation, three bay facade, entrance under recessed corner porch with decorative iron support, paired wood frame 3/1 window and picture window with sidelights, louvered vent in gable, brick veneer applied up to window sills. NC
246. 1563 Colgin Street. Circa 1915. 1 story wood frame cottage with gable roof, raised brick foundation, two bay facade, entrance under screened recessed porch supported by posts, paired metal frame 6/6 windows, exposed rafters, louvered vent in gable. C
247. 1565 Colgin Street. Circa 1965. 1 story brick veneer building of contemporary style with hip roof, concrete slab foundation, three bay facade, entrance under recessed corner porch with decorative iron supports, windows covered. NC
248. 1566 Colgin Street. Circa 1940. 1 story wood frame Minimal Traditional with side gable roof, raised brick foundation, three bay facade, entrance under attached gabled porch supported by posts, metal frame 2/2 windows, exposed rafters. C
249. 1569 Colgin Street. Circa 1950. 1 story vinyl sided Minimal Traditional with gable roof, raised brick foundation, two bay facade, entrance at recessed corner porch supported by square post, metal frame 6/6 windows and 8/8 windows. C
250. 1572 Colgin Street. Circa 1980. 1 story vinyl sided building of contemporary style, side gable roof, concrete foundation, four bay facade, entrance under

projecting gable supported by posts over stoop, metal frame 6/6 windows, attached garage. NC

251. 1573 Colgin Street. Circa 1960. 1 story brick veneer building of contemporary style with gable roof, raised brick foundation, three bay facade, entrance at infilled corner porch, metal frame 6/6 window. NC

Dexter Avenue

252. 500 Dexter Avenue. Circa 1930. 1 story wood frame bungalow with gable roof, raised brick foundation, three bay facade, entrance at infilled porch with pierced brick supports on brick piers still visible, paired wood frame 3/1 windows, open vent in gable, side chimney. NC
253. 504 Dexter Avenue. Circa 1920. 1 story wood frame bungalow with hip roof, raised brick foundation, three bay facade, entrance under projecting gabled porch supported by paired posts on knee wall, paired 4/1 wood frame windows, tripled louvered vent in front-facing gable. C
254. 505 Dexter Avenue. Circa 1935. 1 story wood frame bungalow with side gable roof, raised brick foundation, two bay facade, entrance at recessed corner porch supported by gently battered columns on brick piers, paired wood frame 3/1 windows and picture window, exposed rafters, louvered vent in gable. C
255. 506 Dexter Avenue. Circa 1935. 1 story wood frame and brick veneer Minimal Traditional with side gable roof, raised brick foundation, four bay facade, entrance under projecting gable over stoop supported by battered columns, chimney at facade at larger intersecting gable, arched windows in corner porch and metal frame 6/6 window in remaining bay, shed roofed carport added south elevation. C
256. 508 Dexter Avenue. Circa 1940. 1 story wood frame Minimal Traditional with side gable roof, raised brick foundation, four bay facade, entrance under projecting cantilevered gable over stoop, paired metal frame 6/6 windows and wood frame casements at solarium, exposed rafters. C
257. 509 Dexter Avenue. Circa 1930. 1 story wood frame bungalow with gable roof, raised brick foundation, four bay facade, entrance under projecting gabled porch supported by columns on brick piers, wood frame windows, louvered vent in main gable, exposed rafters. C
258. 510 Dexter Avenue. Circa 1890. 1 story wood frame Victorian cottage with hip roof, raised brick foundation, four bay facade, entrance with transom under recessed porch supported by turned posts with brackets, drop frieze and balustrade (not original), porch abuts semi-octagonal gabled bay, majority of windows are wood frame 2/2 double hung sash. C [Photo #1]
259. 511 Dexter Avenue. Circa 1945. 1 story wood frame Minimal Traditional with side gable roof, raised brick foundation, four bay facade, entrance under projecting gabled porch supported by columns, wood frame 6/6 windows, exposed rafters. C
260. 512 Dexter Avenue. Circa 1910. 1 story wood frame cottage with hip roof, raised brick foundation, four bay facade, entrance under recessed porch supported by posts, metal frame 1/1 windows, gabled dormer with louvered vent, interior chimney, exposed rafters. C
261. 513 Dexter Avenue. Circa 1925. 1 story wood frame bungalow with hip roof, raised brick foundation, three bay facade, entrance under gabled projecting porch supported by brick columns, paired and single metal frame windows with awnings. C
262. 514 Dexter Avenue. Circa 1925. 1 story wood frame bungalow with gable roof, raised brick foundation, three bay facade, entrance under projecting gabled porch supported by short columns on brick piers, paired wood frame 3/1 windows. C

263. 515 Dexter Avenue. Circa 1930. 1 story wood frame bungalow with gable roof, raised brick foundation, two bay facade, entrance under projecting gabled porch supported by square columns on brick piers, paired metal frame windows, awning across porch. C
264. 550 Dexter Avenue. Circa 1925. 1 story wood frame bungalow with gable roof, raised brick foundation, three bay facade, entrance under projecting gabled porch supported by brick columns, brick knee wall, paired wood frame 3/1 windows, knee braces in gable and exposed rafters. C
265. 551 Dexter Avenue. Circa 1930. 1 story wood frame bungalow with gable roof, raised brick foundation, three bay facade, entrance under projecting gabled porch supported by slender columns, paired and single wood frame 3/1 windows, louvered vent in main gable, exposed rafters, side chimney. C
266. 552 Dexter Avenue. Circa 1960. 1 story brick veneer building of contemporary style with gable roof, concrete foundation, four bay facade, entrance under gabled porch with decorative iron supports, metal frame windows. C
267. 553 Dexter Avenue. Circa 1930. 1 story wood frame bungalow with gable roof, raised brick foundation, three bay facade, entrance under recessed corner porch supported by brick columns, paired metal frame windows, porte-cochere north elevation, louvered vent in gable. C
268. 554 Dexter Avenue. Circa 1930. 1 story wood frame bungalow with gable roof, raised brick foundation, three bay facade, entrance under recessed porch supported by paneled columns on brick piers, porch screened, paired metal frame 6/6 windows, small louvered vent in gable, side chimney. C
269. 555 Dexter Avenue. Circa 1925. 1 story wood frame bungalow with gable on hip roof, raised brick foundation, three bay facade, entrance under recessed gabled porch supported by battered columns on brick piers, paired wood frame 3/1 windows, porte-cochere north elevation, exposed rafters. C
270. 556 Dexter Avenue. Circa 1930. 1 story wood frame bungalow with gable roof, raised brick foundation, three bay facade, entrance under recessed porch supported by battered columns on brick piers, paired wood frame 3/1 windows, louvered vent in gable, exposed rafters, side chimney. C
271. 557 Dexter Avenue. Circa 1910. 1 story wood frame cottage with hip roof, raised brick foundation, three bay facade, entrance with transom under later bungalow style recessed porch supported by battered columns on brick piers, paired metal frame 6/6 windows. C
272. 558 Dexter Avenue. Circa 1930. 1 story wood frame bungalow with gable roof, raised brick foundation, three bay facade, entrance under projecting gabled porch supported by brick columns, paired and single metal frame 2/2 windows, louvered vent in porch gable, exposed rafters, side chimney. C
273. 559 Dexter Avenue. Circa 1910. 1 story wood frame cottage with hip roof, raised brick foundation, three bay facade, centered entrance under recessed porch supported by slender columns, paired and single metal frame 6/6 windows. C
274. 560 Dexter Avenue. Circa 1965. 1 story brick veneer building of contemporary style with side gable roof, concrete slab foundation, four bay facade, entrance under projecting eave of roof with decorative iron supports, paired metal frame 6/6 windows and single 2/2 window. NC
275. 562 Dexter Avenue. Circa 1925. 1 story wood frame bungalow with jerkin headed roof, raised brick foundation, three bay facade, entrance under attached jerkin headed porch supported by brick columns, porch screened, paired metal frame windows, exposed rafters, side chimney. C

276. 563 Dexter Avenue. Circa 1970. 1 story brick veneer building of contemporary style with hip roof, concrete slab foundation, three bay facade, entrance set within recessed corner porch of projecting gabled bay, metal frame windows, circular louvered vent in gable. NC
277. 564 Dexter Avenue. Circa 1930. 1 story asbestos sided bungalow with gable roof, raised brick foundation, two bay facade, entrance at infilled recessed corner porch, paired metal frame 6/6 windows with interior burglar bars, louvered vent in gable peak. NC
278. 565 Dexter Avenue. Circa 1930. 1 story asbestos sided bungalow with gable roof, raised brick foundation, two bay facade, entrance at screened projecting gabled porch with awning, paired metal frame windows with awning, exposed rafters, louvered vent in main gable. C
279. 600 Dexter Avenue. Circa 1925. 1 story wood frame bungalow with gable roof, raised brick foundation, three bay facade, entrance under projecting gabled porch supported by battered columns on brick piers, porch screened, paired wood frame 3/1 windows, knee braces, exposed rafters, side chimney. C
280. 602 Dexter Avenue. Circa 1940. 1 story wood frame Minimal Traditional with side gable roof, raised brick foundation, three bay facade, entrance within gabled archway with brick supports, single shouldered chimney at facade, recessed corner porch screened, metal frame 6/6 windows, exposed rafters. C
281. 604 Dexter Avenue. Circa 1930. 1 story wood frame bungalow with gable roof, raised brick foundation, three bay facade, entrance at infilled porch, metal frame windows, louvered vent in gable, knee braces. NC
282. 606 Dexter Avenue. Circa 1940. 1 story wood frame Minimal Traditional with side gable roof, raised brick foundation, four bay facade, entrance under projecting gabled porch with decorative iron supports, metal frame 6/6 windows, exposed rafters. C
283. 607 Dexter Avenue. Circa 1930. 1 story wood frame bungalow with gable roof, raised brick foundation, three bay facade, entrance under projecting gabled porch with decorative iron supports on brick piers, porch lowered to grade, metal frame windows with awnings, louvered vents in gables, exposed rafters. NC
284. 608 Dexter Avenue. Circa 1965. 1 story wood frame building of contemporary style with gable on hip roof, raised brick foundation, three bay facade, entrance under projecting gabled porch with decorative iron supports, metal frame 6/6 windows and 8/8 windows. NC
285. 609 Dexter Avenue. Circa 1955. 1 story wood frame building of contemporary style, raised brick foundation, three bay facade, entrance at infilled shed roofed porch, porch is later addition, metal frame windows. NC
286. 610 Dexter Avenue. Circa 1940. 1 story wood frame Minimal Traditional with side gable roof, raised brick foundation, three bay facade, entrance under projecting gable supported by posts over stoop, metal frame 8/8 windows, exposed rafters. C
287. 611 Dexter Avenue. Circa 1940. 1 story asbestos sided Minimal Traditional with side gable roof, raised brick foundation, three bay facade, entrance under projecting gable over stoop, metal frame 1/1 windows, exposed rafters. C
288. 612 Dexter Avenue. Circa 1940. 1 story wood frame Minimal Traditional with side gable roof, raised brick foundation, three bay facade, entrance under projecting gable supported by posts over stoop, paired and single wood frame 6/6 windows. C

289. 613 Dexter Avenue. Circa 1945. 1 story wood frame Minimal Traditional with gable roof, raised brick foundation, four bay facade, entrance under projecting gabled porch supported by posts, metal frame 1/1 windows, louvered vents in gables, exposed rafters. C
290. 614 Dexter Avenue. Circa 1930. 1 story wood frame building of no particular style, gable roof, raised brick foundation, two bay facade, entrance at projecting gabled bay with abutting corner porch deck, paired and single metal frame 1/1 windows. C
291. 615 Dexter Avenue. Circa 1945. 1 story asbestos sided Minimal Traditional with gable roof, raised brick foundation, three bay facade, entrance under projecting gabled porch supported by posts, 3/1 wood frame windows. C

Dominick Street

292. 1500 Dominick Street. Circa 1950. 1 story wood frame building of no particular style with gable on hip roof, raised brick foundation, four bay facade, entrance with door hood, wood frame windows with awnings, corner porch infilled. NC
293. 1503 Dominick Street. Circa 1940. 1 story wood frame Minimal Traditional with side gable roof, raised brick foundation, three bay facade, entrance under projecting gabled porch with decorative iron supports on brick piers, metal frame awning windows with sidelights, louvered vent in porch gable. C
294. 1505 Dominick Street. Circa 1940. 1 story wood frame building of contemporary style with hip roof, raised brick foundation, three bay facade, entrance west end of facade, metal frame windows. C
295. 1506 Dominick Street. Circa 1950. 1 story wood frame Ranch style house with side gable roof, raised brick foundation, three bay facade, entrance under projecting eave of roofline, metal frame windows, attached carport east elevation, building brick veneered to window sills at later date. NC [Photo #17]
296. 1507 Dominick Street. Circa 1940. 1 story wood frame building of contemporary style with hip roof, raised brick foundation, three bay facade, entrance under projecting gabled porch supported by posts, metal frame paired and single 6/6 windows, exposed rafters. C
297. 1508 Dominick Street. Circa 1970. 1 story brick veneer building of contemporary style with gable roof, concrete slab foundation, three bay facade, entrance under attached gabled porch supported by posts, metal frame 2/2 windows. NC
298. 1509 Dominick Street. Circa 1940. 1 story wood frame building of contemporary style with hip roof, raised brick foundation, three bay facade, entrance within gabled bay, metal frame 2/2 windows. C
299. 1510 Dominick Street. Circa 1920. 1 story wood frame of no particular style with gable on hip roof, raised brick foundation, four bay facade, entrance under projecting gable with decorative iron supports, metal frame windows, addition east elevation, exposed rafters. NC
300. 1512 Dominick Street. Circa 1950. 1 story wood frame Minimal Traditional with gable roof, raised brick foundation, four bay facade, entrance under projecting gabled porch supported by posts, metal frame 2/2 windows, louvered vent in main gable, addition east elevation. NC
301. 1514 Dominick Street. Circa 1950. 1 story wood frame Minimal Traditional with gable roof, raised brick foundation, four bay facade, entrance under projecting gable with decorative iron supports over stoop, metal frame windows and picture window with awnings, addition east elevation, louvered vent in gable. NC

302. 1515 Dominick Street. Circa 1965. 1 story brick veneer building of contemporary style with side gable roof, concrete slab foundation, three bay facade, entrance under projecting roofline, metal frame windows. NC
303. 1516 Dominick Street. Circa 1980. 1 story brick veneer building of contemporary style with hip roof, concrete slab foundation, three bay facade, entrance under projecting hipped porch with decorative iron supports, metal frame windows. NC
304. 1517 Dominick Street. Circa 1960. 1 story brick veneer building of contemporary style with side gable roof, raised brick foundation, three bay facade, entrance under projecting gabled porch supported by posts, metal frame windows. C
305. 1518 Dominick Street. Circa 1975. 1 story brick veneer building of contemporary style with gable roof, concrete slab foundation, two bay facade, entrance along east elevation, metal frame 6/6 windows. NC
306. 1519 Dominick Street. Circa 1955. 1 story wood frame Minimal Traditional with side gable roof, raised brick foundation, three bay facade, entrance under projecting gabled porch with decorative iron supports, metal frame paired 6/6 windows and picture window, brick veneer to window sills, carport added east elevation. NC
307. 1520 Dominick Street. Circa 1980. 1 story brick veneer building of contemporary style with side gable roof, brick foundation, six bay facade, entrance under projecting gable supported by columns over three bays of facade, metal frame 9/6 windows. NC
308. 1521 Dominick Street. Circa 1950. 1 story concrete block building of contemporary style with gable roof, concrete block foundation, three bay facade, entrance under projecting gabled porch with decorative iron supports, metal frame picture window and paired metal frame window, louvered vent in main gable. C
309. 1523 Dominick Street. Circa 1945. 1 story wood frame Minimal Traditional with gable roof, raised brick foundation, three bay facade, entrance under projecting gabled porch supported by pierced brick columns on brick knee wall, wood frame multi-paned picture window and paired 6/6 windows, side chimney. C
310. 1550 Dominick Street. Circa 1945. 1 story wood frame Minimal Traditional with gable roof, raised brick foundation, three bay facade, entrance under projecting gabled porch with decorative iron supports, metal frame picture window and paired 6/6 windows, louvered vent in main gable. C
311. 1551 Dominick Street. Circa 1965. 1 story brick veneer building of contemporary style with hip roof, raised brick foundation, three bay facade, entrance under projecting hipped roof with decorative iron supports over stoop, metal frame 6/6 windows and 8/8 windows. NC
312. 1551 1/2 Dominick Street. Circa 1900. 1 story wood frame shotgun with gable roof, raised brick foundation, characteristic two bay facade, entrance with transom under recessed gabled porch supported by posts, wood frame window, louvered vent in gable, exposed rafters. C [Photo #21]
313. 1552 Dominick Street. Circa 1945. 1 story brick veneer Minimal Traditional with gable roof, raised brick foundation, three bay facade, entrance under projecting gabled porch supported by posts on brick knee wall, paired 3/1 windows. C
314. 1553 Dominick Street. Circa 1950. 1 story concrete block building of contemporary design with gable roof, concrete foundation, three bay facade, entrance under recessed gabled porch supported by concrete block columns, metal frame windows, louvered vent in gable. C

315. 1555 Dominick Street. Circa 1950. 1 story concrete block duplex with gable roof, concrete foundation, four bay facade, entrances under recessed gabled porch supported by concrete block columns, metal frame windows, louvered vent in gable. C
316. 1556 Dominick Street. Circa 1930. 1 story wood frame building of contemporary style with hip roof, raised brick foundation, three bay facade, entrance under projecting gabled porch supported by posts, paired and single wood frame 3/1 windows, louvered vent in porch gable. C
317. 1557 Dominick Street. Circa 1945. 1 story Masonite sided Minimal Traditional with gable roof, raised brick foundation, two bay facade, entrance set within projecting gabled bay with recessed corner porch supported by posts, metal frame 2/2 windows, louvered vent in main gable. C
318. 1559 Dominick Street. Circa 1930. 1 story wood frame bungalow with gable roof, raised brick foundation, three bay facade, entrance under projecting gabled porch supported by posts on brick piers, brick knee wall, porch screened, wood frame 3/1 windows, brick veneer up to window sills. NC
319. 1561 Dominick Street. Circa 1950. 1 story concrete block duplex with gable roof, concrete foundation, four bay facade, entrances under recessed gabled porch supported by concrete block columns, windows and doors covered, louvered vent in gable. C
320. 1563 Dominick Street. Circa 1950. 1 story concrete block duplex with gable roof, concrete foundation, four bay facade, entrances under recessed gabled porch supported by concrete block columns, windows and doors covered, louvered vent in gable. C
321. 1565 Dominick Street. Circa 1950. 1 story concrete block duplex with gable roof, concrete foundation, four bay facade, entrances under recessed gabled porch supported by concrete block columns, windows and doors missing, louvered vent in gable. C
322. 1567 Dominick Street. Circa 1950. 1 story wood frame barracks style apartment building with gable roof, raised brick foundation, two bay facade, entrances along west elevation, windows boarded, louvered vent in gable. C
323. 1569 Dominick Street. Circa 1955. 1 story concrete block barracks style apartment building with gable roof, concrete slab foundation, 1 bay facade, entrances along east elevation, metal frame 2/2 windows, exposed rafters. C
324. 1570 Dominick Street. Circa 1950. 1 story wood frame Minimal Traditional with gable roof, raised brick foundation, three bay facade, entrance under projecting gabled porch supported by posts, paired and single metal frame 6/6 windows, louvered vent in main gable. C
325. 1572 Dominick Street. Circa 1955. 1 story wood frame building of contemporary style with gable roof, four bay facade, entrance under projecting gabled porch supported by posts, metal frame 1/1 windows, exposed rafters, louvered vent in gable. C
326. 1574 Dominick Street. Circa 1940. 1 story wood frame Minimal Traditional with side gable roof, raised brick foundation, three bay facade, entrance under projecting gable with decorative iron supports over stoop, paired and single metal frame 1/1 windows, exposed rafters, louvered vent in intersecting gable. C
327. 1655 Dominick Street. Circa 1915. 1 story wood frame cottage with gable roof, raised brick foundation, three bay facade, entrance under recessed gabled porch supported by square posts, wood frame 6/6 windows and 4/4 windows, exposed rafters. C

328. 1659 Dominick Street. Circa 1940. 1 story wood frame Minimal Traditional with hip roof, raised brick foundation, three bay facade, entrance under projecting gabled porch supported by posts, metal frame paired and single 1/1 windows, exposed rafters, louvered vent in gable. C
329. 1660 Dominick Street. Circa 1955. 1 story brick ecclesiastical building with gable roof, concrete foundation, three bay facade, central entrance under portico with square columns, metal frame stain glass windows, steeple with cross, addition east elevation with metal frame 9/6 windows. NC
330. 1661 Dominick Street. Circa 1925. 1 story wood frame building of no particular style with hip roof, raised brick foundation, four bay facade, entrance in projecting hipped bay, metal frame paired 6/6 windows and 1/1 windows. NC
331. 1700 Dominick Street. Circa 1930. 1 story wood frame bungalow with gable roof, raised brick foundation, three bay facade, entrance under gabled porch supported by columns on brick piers, paired 6/6 windows, louvered vent in main gable. C
332. 1701 Dominick Street. Circa 1985. 1 story brick veneer building of contemporary style with hip roof, concrete foundation, seven bay facade, entrance at intersection of projecting gabled bay and under projecting eave of hip roof with decorative iron supports, metal frame windows. NC
333. 1702 Dominick Street. Circa 1950. 1 story wood frame Minimal Traditional with side gable roof, raised brick foundation, three bay facade, entrance under gabled porch with iron supports, metal frame 1/1 window and single pane window, brick veneer up to window sills. C
334. 1704 Dominick Street. Circa 1960. 1 story wood frame building of contemporary style with hip roof, raised brick foundation, four bay facade, entrance under projecting gabled porch supported by posts, metal frame 6/6 windows, carport added west elevation. NC
335. 1750 Dominick Street. Circa 1940. 1 story wood frame building of no particular style with gable roof, raised brick foundation, three bay facade, entrance at western end of facade, metal frame 2/2 windows, louvered vent in gable, addition east elevation. NC
336. 1753 Dominick Street. Circa 1965. 1 story brick veneer building of contemporary style with hip roof, raised brick foundation, three bay facade, entrance with door hood, metal frame awning windows, carport east elevation. NC
337. 1754 Dominick Street. Circa 1940. 1 story wood frame Minimal Traditional with side gable roof, raised brick foundation, three bay facade, entrance under projecting gabled porch with decorative iron supports, metal frame 2/2 windows and picture window with 2/2 sidelights. C
338. 1755 Dominick Street. Circa 1960. 1 story brick veneer building of contemporary style with gable roof, raised brick foundation, three bay facade, entrance under attached gabled porch with decorative iron supports, porch lowered to grade, metal frame paired 6/6 windows, carport west elevation. NC
339. 1756 Dominick Street. Circa 1965. 1 story brick veneer building of contemporary style with hip roof, concrete foundation, three bay facade, entrance under projecting hipped porch supported by posts, metal frame 2/2 windows, carport east elevation. NC

Douglas Street

340. 1305 Douglas Street. Circa 1955. 1 story brick veneer Minimal Traditional with side gable roof, raised brick foundation, four bay facade, entrance at

- intersecting gabled bay with cantilevered shed roofed door hood over stoop, metal frame 6/6 windows, side chimney, addition added east elevation. NC
341. 1307 Douglas Street. Circa 1945. 1 story wood frame building of contemporary style with hip roof, raised brick foundation, five bay facade, entrance offset from center, metal frame 2/2 windows, interior chimneys. C
342. 1309 Douglas Street. Circa 1950. 1 story Masonite sided Minimal Traditional with side gable roof, raised brick foundation, four bay facade, entrance at intersecting gabled bay, metal frame 2/2 windows, side and interior chimney. C
343. 1311 Douglas Street. Circa 1940. 1 story wood frame building of contemporary style with hip roof, raised brick foundation, three bay facade, entrance under screened projecting gabled porch with decorative iron supports, metal frame 6/6 windows, side chimney. C
344. 1351 Douglas Street. Circa 1950. 1 story Masonite sided Minimal Traditional with side gable roof, raised brick foundation, five bay facade, entrance under shed roof supported by posts, metal frame 6/6 windows, side chimney. C
345. 1353 Douglas Street. Circa 1960. 1 story Masonite sided Minimal Traditional with side gable roof, raised brick foundation, four bay facade, entrance under projecting gabled porch supported by posts, metal frame single and paired 2/2 windows and 1/1 windows, interior chimneys, addition added at east elevation. NC
346. 1355 Douglas Street. Circa 1945. 1 story wood frame Minimal Traditional with side gable roof, raised brick foundation, four bay facade, entrance offset, metal frame 6/6 windows, side chimney. C
347. 1357 Douglas Street. Circa 1955. 1 story wood frame Minimal Traditional with side gable roof, raised brick foundation, three bay facade, entrance under intersecting gabled porch supported by posts, awning across porch, metal frame windows. C
348. 1359 Douglas Street. Circa 1945. 1 story wood frame building of contemporary style with hip roof, raised brick foundation, four bay facade, entrance under extension of roof eave, paired metal frame 2/2 windows, interior chimneys. C
349. 1401 Douglas Street. Circa 1955. 1 story wood frame Minimal Traditional with side gable roof, raised brick foundation, four bay facade, entrance under intersecting gabled porch with decorative iron supports, metal frame 6/6 windows, interior chimneys. C
350. 1403 Douglas Street. Circa 1955. 1 story wood frame Minimal Traditional with side gable roof, raised brick foundation, five bay facade, entrance under extension of roof eave over stoop, metal frame 6/6 windows, interior chimney. C
351. 1405 Douglas Street. Circa 1940. 1 story wood frame building of contemporary style with hip roof, raised brick foundation, five bay facade, entrance under recessed porch supported by posts, wood frame 6/6 windows. C
352. 1451 Douglas Street. Circa 1955. 1 story Masonite sided Minimal Traditional with side gable roof, raised brick foundation, four bay facade, entrance under extension of roof eave over stoop, metal frame 2/2 windows. C
353. 1453 Douglas Street. Circa 1950. 1 story wood frame Minimal Traditional with side gable roof, raised brick foundation, four bay facade, entrance under projecting shed roofed porch supported by posts, metal frame 1/1 windows, side and interior chimneys. C
354. 1455 Douglas Street. Circa 1950. 1 story wood frame Minimal Traditional with side gable roof, raised brick foundation, three bay facade, entrance located at screened gabled porch with awning, metal frame 6/6 windows, addition added east elevation, side and interior chimneys. C

355. 1460 Douglas Street. Circa 1945. 1 story wood frame building of contemporary style with hip roof, raised brick foundation, five bay facade, entrance under recessed porch supported by turned posts, metal frame 6/6 windows, interior chimney. C
356. 1462 Douglas Street. Circa 1955. 1 story wood frame Minimal Traditional with side gable roof, raised brick foundation, four bay facade, entrance under projecting gabled porch supported by posts, metal frame windows, side and interior chimneys, later attached garage south elevation. NC
357. 1464 Douglas Street. Circa 1950. 1 story wood frame Minimal Traditional with side gable roof, raised brick foundation, four bay facade, entrance under extension of roof eave over stoop, metal frame 1/1 windows, side and interior chimneys. C
358. 1466 Douglas Street. Circa 1945. 1 story wood frame building of contemporary style with hip roof, raised brick foundation, three bay facade, entrance located under extension of roof eave with decorative iron supports over stoop, multi-pane metal frame picture windows. C

Dublin Street

359. 1605 Dublin Street. Circa 1960. 1 story brick veneer Ranch style house with side gable roof, raised concrete foundation, four bay facade, entrance at front facing gabled bay, paired metal frame 6/6 windows. C [Photo #18]
360. 1607 Dublin Street. Circa 1965. 1 story brick veneer building of contemporary style with gable roof, three bay facade, entrance under pent roofed porch supported by posts, porch extends into attached carport, metal frame awning windows. NC
361. 1608 Dublin Street East. Circa 1940. 1 story wood frame Minimal Traditional with gable roof, raised brick foundation, two bay facade, entrance set within recessed corner porch with decorative iron support, paired metal frame 2/2 windows, louvered vent in gable, exposed rafters. C
362. 1610 Dublin Street East. Circa 1940. 1 story wood frame Minimal Traditional with gable roof, raised brick foundation, two bay facade, entrance set within recessed corner porch supported by posts, single and paired metal frame 2/2 windows, louvered vent in gable, later garage on east elevation. NC
363. 1612 Dublin Street East. Circa 1945. 1 story wood frame Minimal Traditional with gable roof, raised brick foundation, three bay facade, entrance at infilled projecting gabled porch, metal frame 2/2 windows, louvered vent in gable. NC
364. 1650 Dublin Street. Circa 1955. 1 story wood frame commercial building with gable roof, concrete slab foundation, three bay facade, entrance slightly offset from center, multi-pane metal frame window, louvered vent in gable. C
365. 1651 Dublin Street. Circa 1950. 1 story vinyl sided Minimal Traditional with gable roof, raised brick foundation, three bay facade, entrance within infilled porch, arched metal frame window. NC
366. 1653 Dublin Street. Circa 1945. 1 story brick veneer Minimal Traditional, roof collapsed, raised brick foundation, 3 bay facade, entrance under projecting gable, metal frame windows. NC
367. 1654 Dublin Street. Circa 1965. 2 story brick veneer building of contemporary style with hip roof, concrete slab foundation, three bay facade, entrance at recessed corner porch, metal frame windows. NC
368. 1656 Dublin Street. Circa 1950. 1 story asbestos sided Minimal Traditional with gable roof, raised brick foundation, three bay facade, entrance under recessed

corner porch supported by corner post, metal frame 6/6 windows, louvered vent in gable. C

369. 1658 Dublin Street. Circa 1995. 1 story brick veneer building of contemporary style with hip roof, concrete slab foundation, three bay facade with attached garage, entrance with sidelights under recessed porch supported by posts, paired metal frame 6/6 windows, interior chimney. NC
370. 1660 Dublin Street. Circa 1955. 1 story concrete block duplex with gable roof, concrete slab foundation, four bay facade, entrances under recessed porch supported by paired posts, porch screened, windows and doors boarded. C
371. 1661 Dublin Street. Circa 1970. 1 story brick veneer building of contemporary style with hip roof, concrete foundation, six bay facade, entrance under recessed corner porch with decorative iron supports, metal frame awning windows and picture window with sidelights. NC
372. 1700 Dublin Street. Circa 1960. 1 story brick veneer and asbestos sided building of contemporary style with gable roof, entrance under recessed porch supported by posts on brick piers, brick knee wall, porch screened, windows covered. C
373. 1701 Dublin Street. Circa 1975. 1 story brick veneer building of contemporary style with hip roof, concrete foundation, nine bay facade, inset entrance with sidelights, metal frame 1/1 windows. NC
374. 1702 Dublin Street. Circa 1970. 1 story brick veneer building of contemporary style with gable roof, concrete foundation, three bay facade, entrance under projecting gabled porch supported by brick columns, metal frame multi-paned picture window and 6/6 window, louvered vents in gable. NC
375. 1703 Dublin Street. Circa 1965. 1 story wood frame building of contemporary style with hip roof, raised concrete foundation, three bay facade, entrance under projecting gable with decorative iron supports over stoop, metal frame multi-pane picture windows, brick veneer to window sills. NC
376. 1705 Dublin Street. Circa 1965. 1 story brick veneer ecclesiastical building with gable roof, concrete foundation, three bay facade, centered double door entrance with plate glass, narrow metal frame windows. NC
377. 1751 Dublin Street. Circa 1940. 1 story wood frame Minimal Traditional with side gable roof, raised brick foundation, three bay facade, entrance under projecting gable with decorative iron supports, metal frame window and picture window, exposed rafters. C
378. 1752 Dublin Street. Circa 1965. 1 story concrete block commercial building with gable roof, concrete slab foundation, two bay facade, entrance at one side of facade with boarded windows opposite. NC
379. 1753 Dublin Street. Circa 1930. 1 story stucco bungalow with gable roof, raised brick foundation, two bay facade, entrance under recessed porch supported by battered columns on stucco piers, metal frame picture window with sidelights, louvered vent in gable. C
380. 1754 Dublin Street. Circa 1980. 1 story concrete block commercial building with spraddle roof, concrete slab foundation, four bay facade, two entrances under recessed porch supported by classical columns on brick piers, windows boarded, drop frieze. NC
381. 1755 Dublin Street. Circa 1905. 1 story wood frame cottage with hip roof, raised brick foundation, four bay facade, entrance under recessed shed roofed porch supported by turn posts, projecting semi-octagonal gabled bay with wood frame 2/2

windows, 2/2 window under porch, semi-octagonal gabled bay added with metal frame 6/6 windows, interior chimney. NC

382. 1757 Dublin Street. Circa 1905. 1 story wood frame cottage with gable roof, raised brick foundation, two bay facade, entrance under recessed porch supported by square columns, windows and doors boarded. C
383. 1759 Dublin Street. Circa 1945. 1 story wood frame Minimal Traditional with gable roof, raised brick foundation, three bay facade, entrance under recessed corner porch supported by posts, metal frame picture window and paired 2/2 windows. C
384. 1760 Dublin Street. Circa 1945. 1 story wood frame Minimal Traditional with gable roof, raised brick foundation, three bay facade, entrance under recessed porch supported by posts on brick piers, paired and single metal frame 1/1 windows. C
385. 1762 Dublin Street. Circa 1945. 1 story wood frame duplex with side gable roof, raised brick foundation, four bay facade, entrances under recessed gabled porch supported by posts, metal frame 6/6 windows. C
386. 1766 Dublin Street. Circa 1910. 1 story wood frame cottage with gable roof, raised brick foundation, 1 bay facade, entrance re-oriented to east elevation, original porch now infilled with wood frame 3/1 window. NC
387. 1768 Dublin Street. Circa 1965. 1 story brick veneer building of contemporary style with hip roof, concrete foundation, two bay facade, entrance set within recessed corner porch with decorative iron supports, metal frame picture windows with 2/2 sidelights, carport added west elevation. NC

Dublin Street East

388. 1567 Dublin Street East. Circa 1965. 2 story brick and stuccoed 20th century institutional building with flat roof, concrete slab foundation, double metal door main entrance, banks of metal frame plate glass windows. C
389. 1576 Dublin Street East. Circa 1965. 1 story brick veneer 20th century commercial building with flat roof, concrete slab foundation, windows and doors covered. NC
390. 1588 Dublin Street East. Circa 1975. 1 story concrete block commercial building with hip roof, concrete slab foundation, two bay facade, entrance and window with burglar screening. NC
391. 1596 Dublin Street East. Circa 1945. 1 story wood frame Minimal Traditional with gable roof, raised brick foundation, three bay facade, entrance under attached gabled porch supported by posts, entrance and windows covered, louvered vents in gables. C
392. 1600 Dublin Street East. Circa 1935. 1 story wood frame bungalow with jerkin head roof, raised brick foundation, three bay facade, entrance at screened recessed corner porch with decorative iron corner support, awning over metal frame window. C
393. 1602 Dublin Street East. Circa 1930. 1 story wood frame bungalow with gable roof, raised brick foundation, three bay facade, entrance under projecting gabled porch supported by posts on brick piers, metal frame 6/6 windows, louvered vent in main gable, knee braces. C

Duval Street

394. 1520 Duval Street. Circa 1930. 1 story Masonite sided bungalow with gable roof, raised brick foundation, three bay facade, entrance under projecting gable

porch supported by posts on brick piers, brick knee wall, metal frame 2/2 windows, louvered vent in main gable. C

395. 1552 Duval Street. Circa 1970. 1 story brick veneer commercial building with gable roof, two bay facade, entrance with burglar door, metal roll door at auto bay, concrete foundation. NC
396. 1556 Duval Street. Circa 1950. 1 story wood frame asbestos sided building of contemporary style with gable roof, raised brick foundation, 1 bay facade, entrance under gable supported by posts over stoop along west elevation, metal frame paired 6/6 windows. C
397. 1558 Duval Street. Circa 1950. 1 story wood frame building of contemporary style with gable roof, raised brick foundation, three bay facade, entrance under recessed corner porch supported by posts, clapboard knee wall with diamond cutouts, semi-circular metal frame windows. NC
398. 1560 Duval Street. Circa 1950. 1 story wood frame Minimal Traditional with side gable roof, raised brick foundation, four bay facade, entrance under gable supported by posts over stoop, metal frame 6/6 windows. C
399. 1562 Duval Street. Circa 1950. 1 story wood frame building of contemporary style with gable roof, raised brick foundation, three bay facade, entrance under recessed corner porch supported by posts, metal frame multi-pane windows, louvered vent in gable. C
400. 1564 Duval Street. Circa 1965. 1 story brick veneer and structural tile commercial building with shed roof, concrete slab foundation, entrance located along projecting bay with multi-pane metal frame windows. NC
401. 1566 Duval Street. Circa 1955. 1 story wood frame Minimal Traditional with gable roof, raised brick foundation, three bay facade, entrance under projecting gabled porch with decorative iron supports, metal frame picture window with sidelights, awnings. C
402. 1582 Duval Street. Circa 1960. 1 story wood frame building of contemporary style with side gable roof and front facing gabled dormer, raised brick foundation, three bay facade, entrance under recessed porch supported by posts, wood frame 1/1 windows, side chimney, louvered vent in front facing gable. C
403. 1606 Duval Street. Circa 1960. 1 story wood frame building of contemporary style with gable roof, raised brick foundation, four bay facade, entrance under recessed porch supported by square classical columns, metal frame windows. C
404. 1614 Duval Street. Circa 1950. 1 story wood frame building of contemporary style with gable roof, raised brick foundation, four bay facade, entrance under cantilevered pent roof, metal frame 6/6 windows, interior chimney. C
405. 1654 Duval Street. Circa 1945. 1 story wood frame building of contemporary style with gable roof, raised brick foundation, two bay facade, entrance under recessed porch supported by brick columns, brick knee wall, multi-pane metal frame picture window with sidelights, louvered vent in gable, exposed rafters. C
406. 1658 Duval Street. Circa 1940. 1 story wood frame building of contemporary style with gable roof, raised brick foundation, two bay facade, entrance at recessed partially infilled porch, wood frame 8/8 window, knee braces and exposed rafters. NC
407. 1760 Duval Street. Circa 1945. 1 story wood frame building of contemporary style with gable roof, raised brick foundation, three bay facade, entrance under projecting gabled porch supported by posts, metal frame 2/2 windows. C

Elliot Street

408. 1651 Elliot Street. Circa 1920. 1 story wood frame bungalow with gable roof, raised brick foundation, two bay facade, entrance with transom under recessed porch supported by battered columns on brick piers, paired 1/1 wood frame windows, louvered vent in gable, exposed rafters. C
409. 1655 Elliott Street. Circa 1955. 1 story stuccoed Minimal Traditional with side gable roof, raised brick foundation, three bay facade, entrance under projecting gable supported by columns over stoop, metal frame paired and single 6/6 windows, attached carport east elevation. NC
410. 1656 Elliott Street. Circa 1930. 1 story wood frame bungalow with gable roof, raised brick foundation, two bay facade, entrance under recessed corner porch supported by square column, paired metal frame 2/2 windows, exposed rafters. C
411. 1702 Elliott Street. Circa 1940. 1 story Masonite sided Minimal Traditional with side gable roof, three bay facade, raised brick foundation, entrance under projecting gable over stoop, paired metal frame 2/2 windows and picture window with sidelights, intersecting gable rises above apex of side gable roof. C
412. 1704 Elliott Street. Circa 1950. 1 story wood frame building of contemporary style with gable roof, raised brick foundation, altered projecting gabled bay with recessed porch, window boarded. NC
413. 1705 Elliott Street. Circa 1965. 1 story wood frame building of contemporary style with hip roof, raised concrete foundation, four bay facade, entrance with narrow transom under projecting hipped roofed porch with decorative iron supports on brick piers, paired and single metal frame 2/2 windows. NC
414. 1706 Elliott Street. Circa 1940. 1 story wood frame building of contemporary style with gable roof, raised brick foundation, three bay facade, entrance under projecting gabled porch supported by posts, paired wood frame 3/1 windows. C

Flint Street

415. 500 Flint Street. Circa 1935. 1 story wood frame Minimal Traditional with side gable roof, raised brick foundation, two bay facade, entrance at projecting gabled porch supported by square columns, porch screened, paired wood frame windows with awning, louvered vent in projecting gable, exposed rafters. C
416. 501 Flint Street. Circa 1945. 1 story brick veneered Minimal Traditional with side gable roof, raised brick foundation, two bay facade, entrance under recessed gabled porch with decorative iron supports, paired wood frame 3/1 windows, awning across porch. NC
417. 502 Flint Street. Circa 1930. 1 story wood frame bungalow with gable roof, raised brick foundation, three bay facade, entrance under projecting gabled porch supported by posts on brick piers, brick knee wall, paired wood frame 3/1 windows, exposed rafters, knee braces, louvered vent in porch gable. C
418. 503 Flint Street. Circa 1950. 1 story wood frame Minimal Traditional with side gable roof, raised brick foundation, three bay facade, entrance under projecting gable supported by posts over stoop, metal frame 9/9 windows, pair of gabled dormers with 4 light windows, side chimney. C
419. 504 Flint Street. Circa 1930. 1 story brick veneered bungalow with gable roof, raised brick foundation, three bay facade, entrance under recessed porch supported by brick columns on iron supports between, wood frame 3/1 windows, 3/1 light with flanking louvered vents in porch gable. NC
420. 505 Flint Street. Circa 1935. 1 story wood frame Minimal Traditional with side gable roof, raised brick foundation, four bay facade, entrance under projecting shed roofed porch supported by pierced brick columns, paired and single wood frame

3/1 windows, intersecting gabled bay with louvered vent in gable, exposed rafters.
C

421. 506 Flint Street. Circa 1940. 1 story wood frame Minimal Traditional with side gable roof, raised brick foundation, three bay facade, entrance under projecting gable over stoop, flat roofed porch supported by square posts a later addition, paired metal frame 6/6 windows. NC
422. 507 Flint Street. Circa 1930. 1 story wood frame bungalow with gable roof, raised brick foundation, three bay facade, entrance under projecting gabled porch supported by columns on brick piers, paired wood frame 3/1 windows and 1/1 windows, single light with flanking louvers in porch gable, knee braces, exposed rafters. C
423. 509 Flint Street. Circa 1940. 1 story asbestos sided Minimal Traditional with side gable roof, raised brick foundation, three bay facade, entrance at projecting gabled bay, awning over stoop, wood frame 3/1 windows. C
424. 510 Flint Street. Circa 1930. 1 story wood frame bungalow with gable roof, raised brick foundation, three bay facade, entrance at projecting gabled porch that has been infilled, paired and tripled metal frame 1/1 windows, louvered vent in porch gable, knee braces, exposed rafters. NC
425. 511 Flint Street. Circa 1925. 1 story wood frame bungalow with hip roof, raise brick foundation, three bay facade, entrance under projecting gabled porch supported by brick columns, wood frame paired 6/6 windows, exposed rafters, louvered vent in gable. C
426. 512 Flint Street. Circa 1940. 1 story wood frame Minimal Traditional with side gable roof, raised brick foundation, three bay facade, entrance under projecting gable supported by brick arch, paired and wood frame windows with awnings, exposed rafters. C
427. 513 Flint Street. Circa 1940. 1 story asbestos sided Minimal Traditional with side gable roof, four bay facade, offset entrance with cantilevered door hood over stoop, metal frame 3/3 windows. C
428. 514 Flint Street. Circa 1910. 1 story wood frame cottage with hip roof, raised brick foundation, three bay facade, entrance in recessed bay, original porch infilled to either side of entrance with metal frame windows and bay window, attached carport north elevation, early house heavily altered. NC
429. 515 Flint Street. Circa 1915. 1 story wood frame cottage with hip roof, raised brick foundation, three bay facade, entrance in infilled porch with square columns and brick piers still visible, metal frame 1/1 window, gabled dormer with multi-pane light and flanking louvered vents. NC
430. 550 Flint Street. Circa 1930. 1 story wood frame bungalow with gable roof, raised brick foundation, three bay facade, entrance under recessed porch supported by brick columns, wood frame 3/1 windows, awning across porch, side chimney. C
431. 551 Flint Street. Circa 1955. 1 1/2 story wood frame Minimal Traditional with gable roof, raised brick foundation, two bay facade, entrance in north bay, projecting gabled bay with wood frame windows with burglar bars and awning, wood frame 6/6 window in gable. C
432. 552 Flint Street. Circa 1970. 1 story brick veneer building of contemporary style with hip roof, concrete slab foundation, three bay facade, entrance under projecting hipped porch supported by posts, metal frame 6/6 windows. NC
433. 553 Flint Street. Circa 1935. 1 story wood frame Minimal Traditional with side gable roof, raised brick foundation, three bay facade, entrance set within

- projecting gable supported by battered archway, wood frame paired 3/1 windows, exposed rafters, peak of rear intersecting gable rises above main roof roofline. C
434. 554 Flint Street. Circa 1930. 1 story wood frame bungalow with gable roof, raised brick foundation, three bay facade, entrance under recessed porch supported by short posts on stucco piers, stucco knee wall, paired wood frame 3/1 windows, louvered vent in gable, side chimney. C
435. 555 Flint Street. Circa 1970. 1 story brick veneer building of contemporary style with hip roof, raised brick foundation, three bay facade, entrance set within recessed corner porch with decorative iron supports, metal frame multi-pane picture window with sidelights. NC
436. 556 Flint Street. Circa 1940. 1 story wood frame building of contemporary style with spraddle roof, raised brick foundation, three bay facade, entrance at infilled porch, paired wood framed windows, side chimney. NC
437. 557 Flint Street. Circa 1945. 1 story asbestos sided Minimal Traditional with side gable roof, four bay facade, entrance under recessed porch with decorative iron supports, porch abuts projecting gabled bay, metal frame windows with burglar bars, awnings across porch and window in gabled bay, exposed rafters, louvered vent in projecting gabled bay, side chimney. C
438. 558 Flint Street. Circa 1925. 1 story wood frame bungalow with gable roof, raised brick foundation, three bay facade, entrance under recessed porch supported by battered columns on brick piers, paired wood frame 3/1 windows, porte-cochere supported by battered columns on brick piers, Craftsman light in gable, knee braces. C
439. 559 Flint Street. Circa 1930. 1 story wood frame bungalow with gable roof, raised brick foundation, three bay facade, entrance under recessed porch supported by square columns on brick piers with posts between, paired metal frame 6/6 windows, louvered vent in gable. C
440. 560 Flint Street. Circa 1930. 1 story wood frame bungalow with gable roof, raised brick foundation, two bay facade, entrance at side of projecting gabled porch supported by brick columns on brick knee wall, multi-pane metal frame window and 1/1 windows infill porch, louvered vent in porch gable, exposed rafters, side chimney. NC
441. 561 Flint Street. Circa 1930. 1 story wood frame bungalow with gable roof, raised brick foundation, three bay facade, entrance under projecting gabled porch supported by brick columns, brick knee wall, paired metal frame 1/1 windows, side chimney. C
442. 562 Flint Street. Circa 1925. 1 story wood frame bungalow with gable roof, raised brick foundation, three bay facade, entrance under projecting gabled porch supported by battered columns on brick piers, paired wood frame 3/1 windows, pent roof extends from projecting gabled porch across facade and forms porte-cochere supported by battered columns on brick piers, louvered vent in main gable, exposed rafters. C
443. 563 Flint Street. Circa 1970. 1 story brick veneer building of contemporary style with hip roof, concrete slab foundation, three bay facade, entrance under recessed porch supported by square columns, metal frame 9/6 windows. NC
444. 564 Flint Street. Circa 1930. 1 story wood frame bungalow with gable roof, raised brick foundation, three bay facade, entrance located at infilled porch under metal door hood with decorative iron supports over stoop, battered columns on brick piers of infilled porch still visible, windows with burglar bars and transoms across infilled porch, louvered vent in gable, knee braces, side chimney. NC

445. 565 Flint Street. Circa 1985. 1 story brick veneer building of contemporary style with gable roof, concrete foundation, three bay facade, entrance under projecting gabled porch supported by square columns, metal frame picture window and 6/6 windows with burglar bars. NC

Gaynor Street

446. 1501 Gaynor Street. Circa 1965. 1 story concrete block apartment building with flat roof, concrete foundation, multiple entrance and metal frame windows across 14 bay facade. NC
447. 1507 Gaynor Street. Circa 1960. 1 story brick veneer building of contemporary style with gable roof, three bay facade, entrance under projecting gabled porch with decorative iron supports, metal frame windows with burglar bars, addition added to west elevation. NC
448. 1509 Gaynor Street. Circa 1960. 1 story brick veneer building of contemporary style with gable roof, raised brick foundation, three bay facade, entrance under corner porch of projecting gabled bay, paired metal frame 6/6 windows. C
449. 1511 Gaynor Street. Circa 1960. 1 story brick veneer building of contemporary style with gable roof, concrete slab foundation, five bay facade, entrance in projecting gabled bay, metal frame windows and bay window with burglar bars. C
450. 1513 Gaynor Street. Circa 1970. 1 story brick veneer building of contemporary style with hip roof, concrete slab foundation, three bay facade, entrance under projecting gable with decorative iron supports over stoop, paired and single metal frame windows with burglar bars. NC
451. 1515 Gaynor Street. Circa 1970. 1 story brick veneer building of contemporary style with hip roof, three bay facade, concrete slab foundation, entrance under recessed porch with decorative iron supports, metal frame 1/1 windows. NC
452. 1517 Gaynor Street. Circa 1960. 1 story brick veneer building of contemporary style with gable roof, concrete slab foundation, three bay facade, entrance under projecting gabled porch supported by posts, metal frame 6/6 windows, louvered vent in peak of main gable. C
453. 1519 Gaynor Street. Circa 1965. 1 story brick veneer building of contemporary style with gable on hip roof, concrete slab foundation, two bay facade, entrance at side elevation, metal frame 6/6 windows. NC
454. 1521 Gaynor Street. Circa 1965. 1 story brick veneer building of contemporary style with hip roof, concrete slab foundation, three bay facade, central entrance with flanking metal frame 6/6 windows, carport added along east elevation. NC
455. 1523 Gaynor Street. Circa 1965. 1 story brick veneer building of contemporary style with hip roof, concrete slab foundation, three bay facade, entrance under projecting hipped porch with decorative iron supports, metal frame 6/6 windows. NC
456. 1551 Gaynor Street. Circa 1960. 1 story brick veneer building of contemporary style with gable roof, raised brick foundation, three bay facade, entrance under projecting gabled porch supported by brick columns on piers, metal frame windows, circular louvered vents in gables. C
457. 1553 Gaynor Street. Circa 1945. 1 story wood frame Minimal Traditional with gable roof, raised brick foundation, three bay facade, entrance under projecting

gabled porch with decorative iron supports, multi-pane metal frame picture windows, louvered vents in gables, exposed rafters. C

458. 1555 Gaynor Street. Circa 1945. 1 story wood frame Minimal Traditional with side gable roof, raised brick foundation, three bay facade, entrance under projecting gabled porch with decorative iron supports, metal frame picture window and 6/6 windows, exposed rafters and louvered vent in porch gable. C
459. 1557 Gaynor Street. Circa 1945. 1 story wood frame building of no particular style with side gable roof, raised brick foundation, three bay facade, entrance in westernmost bay, paired and single metal frame 6/6 windows, intersecting gable above easternmost bay. NC
460. 1561 Gaynor Street. Circa 1955. 1 story brick veneer Minimal Traditional with side gable roof, raised brick foundation, three bay facade, entrance under projecting gable with decorative iron supports over stoop, paired metal frame 1/1 window and picture window with sidelights, carport added west elevation. NC
461. 1563 Gaynor Street. Circa 1945. 1 story wood frame Minimal Traditional with side gable roof, raised brick foundation, three bay facade, entrance under projecting gabled porch supported by square classical columns, paired and single metal frame 6/6 windows. C
462. 1567 Gaynor Street. Circa 1960. 1 story brick veneer building of contemporary style with gable roof, raised brick foundation, three bay facade, entrance under projecting gabled porch with decorative iron supports, metal frame 2/2 windows. C
463. 1575 Gaynor Street. Circa 1940. 1 story wood frame building of no particular style with side gable roof, raised brick foundation, five bay facade, entrance under projecting shed roof supported by posts, metal frame paired and single 2/2 windows, brick veneer to window sills, second entrance boarded. NC

Ghent Street

464. 954 Ghent Street. Circa 1965. 1 story brick veneer building of contemporary style with gable roof, concrete foundation, two bay facade, entrance at projecting gabled bay under recessed corner porch with decorative iron support, metal frame 8/8 windows, two story rear addition with hip roof, carport added south elevation. NC
465. 955 Ghent Street. Circa 1965. 1 story wood frame building of contemporary style with gable roof, concrete slab foundation, four bay facade, entrance under recessed porch supported by posts, metal frame 6/6 windows. NC
466. 957 Ghent Street. Circa 1930. 1 story wood frame bungalow with gable roof, raised brick foundation, three bay facade, entrance under recessed porch supported by battered columns on brick piers, knee wall, paired metal frame 2/2 windows, doubled louvered vent in gable. C
467. 958 Ghent Street. Circa 1960. 1 story brick veneer building of contemporary style with gable roof, concrete foundation, two bay facade, entrance under recessed corner porch with decorative iron support, paired metal frame 6/6 windows. C
468. 959 Ghent Street. Circa 1945. 1 story wood frame building of contemporary style with gable roof, raised brick foundation, three bay facade, entrance under attached gabled porch with decorative iron supports, paired metal frame 2/2 windows, louvered vent in main gable. C
469. 960 Ghent Street. Circa 1950. 1 story wood frame Minimal Traditional with gable roof, raised brick foundation, three bay facade, offset central entrance, paired and single frame 2/2 windows, louvered vent in gable, porch removed. NC

470. 961 Ghent Street. Circa 1965. 1 story brick veneer building of contemporary style with hip roof, raised concrete foundation, three bay facade, entrance under projecting hip with decorative iron supports over stoop, metal frame windows with burglar bars. NC
471. 962 Ghent Street. Circa 1950. 1 story wood frame Minimal Traditional with gable roof, raised brick foundation, two bay facade, entrance under recessed corner porch with decorative iron support, metal frame 8/8 windows and 6/6 windows, louvered vent in gable. C
472. 963 Ghent Street. Circa 1940. 1 story wood frame Minimal Traditional with gable roof, raised brick foundation, three bay facade, entrance under projecting gabled porch supported by posts and decorative iron support, windows covered. C
473. 964 Ghent Street. Circa 1970. 1 story brick veneer building of contemporary style with hip roof, concrete foundation, two bay facade, entrance at infilled corner porch, metal frame 6/6 windows. NC
474. 1002 Ghent Street. Circa 1945. 1 story wood frame Minimal Traditional with side gable roof, raised brick foundation, three bay facade, entrance at screened projecting porch supported by posts, paired and metal frame 1/1 windows, exposed rafters. C
475. 1004 Ghent Street. Circa 1915. 1 story wood frame shotgun with gable roof, raised brick foundation, characteristic two bay facade with entrance under projecting gabled roof with decorative iron supports, metal frame multi-pane picture window adjacent, exposed rafters. C
476. 1006 Ghent Street. Circa 1910. 1 story wood frame shotgun with gable roof, raised brick foundation, three bay facade, entrance under recessed gabled porch with decorative iron supports, multi-pane metal frame picture window and 2/2 windows, addition added south elevation. NC
477. 1007 Ghent Street. Circa 1960. 1 story brick veneer Ranch style house with side gable roof, concrete foundation, three bay facade, entrance under projecting gabled porch with decorative iron supports, metal frame paired awning windows and picture window with sidelights. C [Photo #19]
478. 1008 Ghent Street. Circa 1960. 1 story wood frame building of contemporary style with hip roof, raised concrete foundation, four bay facade, entrance under projecting gable with decorative iron supports over stoop, metal frame single pane and 2/2 windows. C
479. 1009 Ghent Street. Circa 1940. 1 story wood frame Minimal Traditional with gable roof, raised brick foundation, three bay facade, entrance under recessed corner porch supported by posts, metal frame paired and single 2/2 windows, louvered vent in gable. C
480. 1015 Ghent Street. Circa 1990. 1 story brick veneer building of contemporary design with hip roof, concrete foundation, five bay facade, entrance under recessed corner porch in larger of two projecting gabled bays, metal frame 9/6 windows. NC
481. 1054 Ghent Street. Circa 1950. 1 story wood frame Minimal Traditional with side gable roof, raised brick foundation, three bay facade, entrance under projecting eave of roof over stoop, paired metal frame 1/1 windows. C
482. 1056 Ghent Street. Circa 1910. 1 story wood frame cottage with hip roof, raised brick foundation, entrance under partially infilled recessed porch with decorative iron supports on piers, windows covered by plywood. NC
483. 1058 Ghent Street. Circa 1975. 1 story brick veneer Ranch style house with hip roof, raised concrete foundation, three bay facade, entrance at recessed corner porch with decorative iron supports, multi-pane metal frame picture window, other windows shuttered. NC

484. 1102 Ghent Street. Circa 1965. 1 story brick veneer building of contemporary style with side gable roof, three bay facade, entrance located at projecting gabled bay, windows covered. NC
485. 1106 Ghent Street. Circa 1965. 1 story brick veneer building of contemporary style with hip roof, concrete foundation, three bay facade, entrance under projecting hip roof with decorative iron supports over stoop, metal frame 2/2 window and picture window covered by plywood. NC
486. 1150 Ghent Street. Circa 1890. 1 story wood frame cottage with side gable roof, raised brick foundation, three bay facade, entrance under recessed porch supported by square posts, metal frame 1/1 windows. C
487. 1156 Ghent Street. Circa 1940. 1 story stucco building of contemporary style with gable roof, raised brick foundation, three bay facade, entrance under projecting gabled porch with decorative iron supports, paired wood frame 3/1 windows, stucco applied at later date. NC
488. 1157 Ghent Street. Circa 1910. 1 story asbestos sided cottage, gable roof with return cornice, raised brick foundation, three bay facade, entrance under recessed porch supported by turned posts, wood frame 2/2 windows, 3 light window in gable. C
489. 1158 Ghent Street. Circa 1955. 1 story brick veneer building of contemporary style with gable roof, raise brick foundation, two bay facade, entrance at recessed corner porch supported by brick columns, metal frame 6/6 windows with burglar bars, louvered vent in gable, brick veneer applied at later date. NC
490. 1159 Ghent Street. Circa 1960. 1 story wood frame Minimal Traditional with gable roof, raised brick foundation, two bay facade, entrance under recessed corner porch with decorative iron supports, metal frame 8/8 windows and picture windows with sidelights, louvered vent in peak of gable. C
491. 1163 Ghent Street. Circa 1940. 1 story stucco building of contemporary style with hip roof, raised brick foundation, three bay facade, entrance under infilled projecting gable porch paired wood frame 6/6 windows, louvered vent in gable. NC
492. 1203 Ghent Street. Circa 1945. 1 story wood frame Minimal Traditional with gable roof, raised brick foundation, three bay facade, entrance under projecting gabled porch supported by square posts, metal frame 2/2 windows. C
493. 1204 Ghent Street. Circa 1945. 1 story wood frame Minimal Traditional with gable roof, raised brick foundation, three bay facade, entrance under recessed corner porch supported by square posts with brackets, single and paired metal frame 6/6 windows. C
494. 1205 Ghent Street. Circa 1945. 1 story wood frame Minimal Traditional with gable roof, raised brick foundation, three bay facade, entrance under recessed porch supported by square columns, wood frame 1/1 windows, louvered vent in gable. C
495. 1207 Ghent Street. Circa 1940. 1 story asbestos sided Minimal Traditional with gable roof, raised brick foundation, two bay facade, entrance under recessed corner porch supported by posts, paired metal frame 2/2 windows. C
496. 1210 Ghent Street. Circa 1945. 1 story wood frame Minimal Traditional with gable roof, raised brick foundation, two bay facade, entrance under recessed corner porch supported by square posts with brackets, paired metal frame 6/6 windows, awning. C
497. 1211 Ghent Street. Circa 1950. 1 story wood frame building of contemporary style with gable roof, raised brick foundation, 1 bay facade, entrance along south elevation under shed roofed porch supported by posts, later attached carport, paired wood frame 6/6 windows with awning, louvered vent in gable. NC

498. 1212 Ghent Street. Circa 1900. 1 story wood frame cottage with gable roof, raised brick foundation, two bay facade, entrance at recessed gabled porch supported by turned post, windows boarded, louvered vent in gable, two additions north elevation. NC
499. 1251 Ghent Street. Circa 1940. 1 story wood frame building of contemporary style with gable roof, raised brick foundation, two bay facade, entrance under projecting gable supported by turned posts over stoop, metal frame 2/2 windows, addition south elevation. NC
500. 1253 Ghent Street. Circa 1960. 1 story brick veneer Ranch style house with side gable roof, raised concrete foundation, four bay facade, entrance under recessed corner porch with iron support in projecting gabled bay, metal frame 2/2 paired windows and picture window with sidelights. C
501. 1256 Ghent Street. Circa 1940. 1 story wood frame Minimal Traditional with side gable roof, three bay facade, raised brick foundation, entrance under projecting eave of roofline, metal frame 2/2 windows. C
502. 1259 Ghent Street. Circa 1965. 1 story brick veneer building of contemporary style with hip roof, concrete slab foundation, three bay facade, central inset entryway, metal frame 6/6 windows. NC

Grove Street

503. 1355 Grove Street. Circa 1945. 1 story wood frame Minimal Traditional with gable roof, raised brick foundation, three bay facade, entrance under attached gable supported by posts over stoop, metal frame 1/1 windows, exposed rafters, louvered vent in gable. C
504. 1357 Grove Street. Circa 1940. 1 story wood frame Minimal Traditional with side gable roof, raised brick foundation, three bay facade, entrance under projecting eave of roof with decorative iron supports, metal frame 2/2 and picture window with sidelights. C
505. 1358 Grove Street. Circa 1955. 1 story wood frame building of contemporary style with gable roof, concrete foundation, entrance under projecting gable with decorative iron supports, metal frame windows with burglar bars, carport added east elevation. NC
506. 1404 Grove Street. Circa 1945. 1 story wood frame Minimal Traditional with side gable roof, raised brick foundation, four bay facade, entrance under projecting gable with iron supports over stoop, wood frame windows with awnings. C
507. 1405 Grove Street. Circa 1940. 1 story wood frame cottage with hip roof, raised brick foundation, two bay facade, entrance at west elevation, paired wood frame 6/6 windows. C
508. 1406 Grove Street. Circa 1945. 1 story wood frame Minimal Traditional with side gable roof, raised brick foundation, three bay facade, entrance at infilled projecting gabled porch, wood frame 1/1 windows, addition added east elevation. NC
509. 1407 Grove Street. Circa 1940. 1 story wood frame Minimal Traditional with side gable roof, raised brick foundation, three bay facade, entrance under projecting gable with decorative iron supports over stoop, metal frame 8/8 windows, porch east elevation with decorative iron supports, exposed rafters. C
510. 1408 Grove Street. Circa 1950. 1 story wood frame Minimal Traditional with hip roof, raised brick foundation, three bay facade, entrance under projecting gabled porch supported by turned posts, metal frame multi-pane picture window and 6/6 windows, louvered vent in gable. C

511. 1409 Grove Street. Circa 1940. 1 story wood frame Minimal Traditional with gable roof, raised brick foundation, four bay facade, entrance in infilled gabled porch, paired 4/4 windows and single 6/6 metal frame windows, carport and addition at west elevation. NC
512. 1410 Grove Street. Circa 1945. 1 story wood frame Minimal Traditional with side gable roof, raised brick foundation, three bay facade, entrance under projecting shed roofed porch supported by turned posts, metal frame 6/6 windows, addition east elevation with carport. NC
513. 1411 Grove Street. Circa 1970. 1 story brick veneer building of contemporary style with gable on hip roof, raised concrete foundation, three bay facade, entrance at recessed corner porch in projecting hipped bay, paired metal frame 6/6 windows. NC

Houston Street

514. 1003 Houston Street. Circa 1950. 1 story wood frame Minimal Traditional with side gable roof, raised brick foundation, five bay facade, entrance at intersection of projecting gabled bay, paired and single metal frame 6/6 windows. C
515. 1005 Houston Street. Circa 1960. 1 story brick veneer Minimal Traditional with side gable roof, raised brick foundation, three bay facade, entrance at infilled projecting gabled porch, metal frame 8/8 windows, attached garage south elevation. NC
516. 1009 Houston Street. Circa 1930. 1 story wood frame bungalow with gable roof, entrance under bungalow styled porch supported by brick columns, metal frame 6/6 windows. C
517. 1011 Houston Street. Circa 1960. 1 story brick veneer Minimal Traditional with side gable roof, raised brick foundation, three bay facade, entrance under gabled porch supported by classical columns, awning across porch, metal frame 6/6 windows. C
518. 1013 Houston Street. Circa 1940. 1 story wood frame Minimal Traditional with side gable roof, raised brick foundation, two bay facade, entrance located at recessed gabled corner porch with decorative iron support, metal frame multi-pane picture windows. C
519. 1015 Houston Street. Circa 1940. 1 story wood frame Minimal Traditional with side gable roof, raised brick foundation, three bay facade, entrance under gable over stoop, paired and single metal frame 6/6 windows with awnings. C
520. 1017 Houston Street. Circa 1945. 1 story wood frame Minimal Traditional with side gable roof, raised brick foundation, three bay facade, entrance located at projecting gabled bay with later attached semi-octagonal bay, paired and single wood frame 6/6 windows, exposed rafters. NC
521. 1051 Houston Street. Circa 1940. 1 story wood frame Minimal Traditional with side gable roof, raised brick foundation, two bay facade, entrance under recessed porch supported by posts, wood frame single and paired 6/6 windows, exposed rafters. C
522. 1053 Houston Street. Circa 1960. 1 story brick veneer building of contemporary style with gable roof, raised brick foundation, three bay facade, entrance under projecting gable porch with decorative iron supports, metal frame 3/1 windows, louvered vent in peak of main gable. C
523. 1055 Houston Street. Circa 1940. 1 story wood frame Minimal Traditional with side gable roof, raised brick foundation, four bay facade, entrance under projecting gable over stoop, single and paired metal frame 2/2 windows, corner porch infilled to create additional living space. NC

524. 1057 Houston Street. Circa 1965. 1 story brick veneer building of contemporary style with hip roof, raised brick foundation, four bay facade, entrance southern most bay, metal frame picture window with sidelights and awning windows in projecting hipped bay. NC
525. 1059 Houston Street. Circa 1950. 1 story wood frame Minimal Traditional with side gable roof, raised brick foundation, three bay facade, entrance under projecting gable with decorative iron supports over stoop, paired metal frame 1/1 windows. C
526. 1061 Houston Street. Circa 1970. 1 story stucco building of contemporary style with side gable roof, concrete foundation, three bay facade, entrance under projecting eave of roof with decorative iron supports, metal frame 12/12 windows, carport attached south elevation. NC
527. 1063 Houston Street. Circa 1970. 1 story brick veneer building of contemporary style with hip roof, concrete foundation, four bay facade, two entrances in both outermost bays, one entrance under projecting hipped roof with decorative iron supports, metal frame single and tripled 6/6 windows. NC
528. 1065 Houston Street. Circa 1935. 1 story wood frame Minimal Traditional with side gable roof, raised brick foundation, entrance under projecting gabled roof supported by posts over stoop in intersecting facing gabled bay, secondary gabled bay with paired wood frame 6/6 windows, chimney at facade, exposed rafters. C
529. 1101 Houston Street. Circa 1940. 1 story wood frame Minimal Traditional with side gable roof, raised brick foundation, four bay facade, entrance under projecting gable over stoop, wood frame windows with burglar bars and awnings, exposed rafters. C
530. 1103 Houston Street. Circa 1940. 1 story wood frame Minimal Traditional with side gable roof, raised brick foundation, three bay facade, entrance under projecting gable with decorative iron supports over stoop, paired metal frame 1/1 windows and picture window. C
531. 1105 Houston Street. Circa 1940. 1 story asbestos sided Minimal Traditional with side gable roof, raised brick foundation, three bay facade, entrance under projecting gable over stoop, windows with awnings. C
532. 1107 Houston Street. Circa 1940. 1 story wood frame Minimal Traditional with side gable roof, raised brick foundation, three bay facade, entrance under projecting gable supported by post over stoop, wood frame 8/8 windows, exposed rafters, attached carport supported by posts on brick piers. C
533. 1109 Houston Street. Circa 1955. 1 story asbestos sided building of contemporary style with hip roof, raised brick foundation, three bay facade, entrance located at recessed corner porch with decorative iron support, paired metal frame 6/6 windows, interior chimney, gable dormer. C
534. 1111 Houston Street. Circa 1950. 1 story brick veneer Minimal Traditional with side gable roof, raised brick foundation, four bay facade, entrance under projecting gable supported by posts over stoop, metal frame windows with burglar bars and awnings, interior chimney. C
535. 1113 Houston Street. Circa 1970. 1 story brick veneer building of contemporary style with hip roof, concrete foundation, three bay facade, entrance under projecting hipped roof supported by decorative iron supports over stoop, metal frame windows with burglar bars and awnings, attached carport north elevation. NC
536. 1117 Houston Street. Circa 1945. 1 story Masonite sided Minimal Traditional with side gable roof, raised brick foundation, four bay facade, entrance under gable over stoop, metal frame 6/6 windows with awnings. C

537. 1153 Houston Street. Circa 1955. 1 story wood frame Minimal Traditional with side gable roof, raised brick foundation, three bay facade, entrance under projecting gabled porch supported by battered columns on brick piers, side chimney, addition added to north elevation, awnings over metal frame windows. NC
538. 1163 Houston Street. Circa 1940. 1 story wood frame duplex with side gable roof, raised brick foundation, four bay facade, both central entrances under projecting gabled porch supported by posts, wood frame 3/1 windows, exposed rafters. C
539. 1203 Houston Street. Circa 1950. 1 story Masonite sided Minimal Traditional with side gable roof, raised brick foundation, three bay facade, entrance under projecting gabled porch supported by posts, paired metal frame 6/6 windows, facing gabled bay, exposed rafters, carport attached to north elevation. C
540. 1205 Houston Street. Circa 1930. 1 story wood frame bungalow with gable roof, raised brick foundation, two bay facade, entrance at infilled projecting gabled porch, metal frame paired 6/6 windows, awnings across infilled porch and windows, 3 pane light in porch gable and louvered vent in main gable. NC
541. 1207 Houston Street. Circa 1955. 1 story Masonite sided building of no particular style with hip roof, raised brick foundation, four bay facade, entrance under projecting gable with decorative iron supports over stoop, metal frame multi-pane window and 2/2 windows, later attached porch south elevation with awning. NC
542. 1211 Houston Street. Circa 1950. 1 story Masonite sided Minimal Traditional with side gable roof, raised brick foundation, three bay facade, entrance under projecting gable with decorative iron supports over stoop, wood frame 6/6 windows. C
543. 1213 Houston Street. Circa 1930. 1 story wood frame bungalow with gable roof, raised brick foundation, three bay facade, entrance under projecting gabled porch with decorative iron supports, wood frame 8/8 windows, louvered vent in main gable. C
544. 1215 Houston Street. Circa 1940. 1 story wood frame Minimal Traditional with side gable roof, raised brick foundation, three bay facade, entrance under projecting gable supported by posts over stoop, wood frame 3/1 windows. C
545. 1251 Houston Street. Circa 1945. 1 story wood frame Minimal Traditional with side gable roof, raised brick foundation, three bay facade, entrance under projecting gable with decorative iron supports over stoop, metal frame 6/6 windows with awnings. C

Illinois Street

546. 1300 Illinois Street. Circa 1950. 2 story wood frame Colonial Revival apartment building with hip roof, raised brick foundation, five bay facade, entrance with classical surround at projecting two storied gabled bay with classical cornice and pilasters, paired and single metal frame 2/2 windows. C [Photo #7]
547. 1302 Illinois Street. Circa 1945. 2 story asbestos sided garage/apartment with side gable roof, concrete slab foundation, four bay facade, entrances along both east and west elevation at second story reached by staircases, four open auto bays at first floor, metal frame 2/2 windows. C
548. 1352 Illinois Street. Circa 1945. 2 story asbestos sided garage/apartment with side gable roof, concrete slab foundation, four bay facade, entrance at second floor reached by staircase, metal frame 6/6 windows. C

549. 1555 Illinois Street. Circa 1950. 2 story wood frame apartment building with side gable roof, concrete foundation, four bay facade, two entrances under attached shed roofed porch supported by square columns, metal frame semi-circular windows, later attached gabled carport. NC
550. 1556 Illinois Street. Circa 1965. 1 story brick veneer building of contemporary style with side gable roof, raised concrete foundation, five bay facade, entrance under projecting gable with decorative iron supports over stoop, intersecting gabled bay with recessed porch with decorative iron supports, metal frame paired windows with burglar bars. NC
551. 1558 Illinois Street. Circa 1965. 1 story brick veneer building of contemporary style with side gable roof, concrete foundation, four bay facade, entrance slightly offset from center, metal frame 1/1 windows and picture window, attached carport east elevation. NC
552. 1561 Illinois Street. Circa 1900. 2 story wood frame Neo-classical with hip roof, raised brick foundation, two bay facade, entrance with transom and sidelights under two story recessed porch supported by paneled columns on brick piers on the first floor and panelled columns on the second, wood frame casement windows with transoms, French doors lead onto second story of porch. Small, 1 story addition on side elevation. C [Photo #4]
553. 1562 Illinois Street. Circa 1930. 1 story wood frame bungalow with gable roof, raised brick foundation, three bay facade, entrance under recessed porch supported by brick columns at outer corners and square columns on brick piers between, wood frame Craftsman windows, louvered vent in gable. C
554. 1605 Illinois Street. Circa 1950. 1 story wood frame Minimal Traditional with side gable roof, raised brick foundation, three bay facade, entrance at intersection of ell with front facing gabled bay, metal frame 6/6 windows with burglar bars and awnings, addition added east elevation. NC
555. 1606 Illinois Street. Circa 1905. 1 story wood frame Neo-classical with hip roof, raised brick foundation, three bay facade, entrance with transom under recessed porch with gabled portico supported by square classical columns on piers, wood frame windows with transoms, exposed rafters, side chimney, louvered vent in gable. C
556. 1607 Illinois Street. Circa 1905/drastically renovated c. 2010. 1 story recently stuccoed Neo-classical with hip roof, raised brick foundation, three bay facade, entrance with semi-circular transom under recessed porch supported by columns, paired metal frame 6/6 windows, gabled dormer with 3 light window, new front door and windows. NC [Photo #6]

Lemon Street

557. 1500 Lemon Street. Circa 1965. 1 story brick veneer building of contemporary style with gable roof, concrete slab foundation, two bay facade, entrance under recessed corner porch with iron supports, metal frame windows. NC
558. 1503 Lemon Street. Circa 1915. 1 story wood frame building with hip roof, raised brick foundation, four bay facade, entrance under projecting hip with decorative iron supports, metal frame 6/6 windows and 1/1 windows, paired 1/1 windows, exposed rafters. C
559. 1506 Lemon Street. Circa 1945. 1 story wood frame Minimal Traditional with side gable roof, raised brick foundation, four bay facade, entrance under projecting gabled porch with decorative iron supports, wood frame 1/1 windows and 3/1 windows. C

560. 1507 Lemon Street. Circa 1915. 1 story wood frame building with hip roof, raised brick foundation, three bay facade, entrance under projecting hip roof with decorative iron supports over stoop, metal frame awning windows and 2/2 windows. C
561. 1508 Lemon Street. Circa 1940. 1 story wood frame Minimal Traditional with side gable roof, raised brick foundation, three bay facade, entrance under projecting gable porch with decorative iron supports, wood frame 1/1 windows, exposed rafters, louvered vent in porch gable. C
562. 1512 Lemon Street. Circa 1935. 1 story wood frame Minimal Traditional with side gable roof, raised brick foundation, three bay facade, entrance in easternmost bay, single and paired metal frame 6/6 windows, exposed rafters. C
563. 1515 Lemon Street. Circa 1945. 1 story wood frame Minimal Traditional with side gable roof, raised brick foundation, four bay facade, entrance under projecting eave of roofline, paired metal frame awning windows, attached carport west elevation. C
564. 1516 Lemon Street. Circa 1940. 1 story wood frame Minimal Traditional with side gable roof, raised brick foundation, three bay facade, entrance under projecting gable, wood frame 1/1 windows. C
565. 1518 Lemon Street. Circa 1965. 1 story brick veneer building of contemporary style with gable roof, raised brick foundation, two bay facade, entrance at recessed corner porch supported by brick column, bay window with metal frame 6/6 windows. NC
566. 1520 Lemon Street. Circa 1960. 1 story brick veneer building of contemporary style with gable roof, raised brick foundation, three bay facade, entrance under attached gabled porch with decorative iron supports, metal frame picture windows, brick knee wall. C
567. 1522 Lemon Street. Circa 1940. 1 story wood frame Minimal Traditional with side gable roof, raised brick foundation, three bay facade, entrance slightly offset from center, paired metal frame 2/2 windows and picture window with sidelights, exposed rafters. C
568. 1550 Lemon Street. Circa 1965. 1 story brick veneer building of contemporary style with gable on hip roof, concrete foundation, two bay facade, entrance under recessed corner porch supported by brick column, burglar bars cover porch, paired metal frame 6/6 windows. NC
569. 1552 Lemon Street. Circa 1950. 1 story wood frame building of contemporary style with gable roof, raised brick foundation, three bay facade, inset central entryway, wood frame picture windows, facade altered by infill of porch. NC
570. 1554 Lemon Street. Circa 1960. 1 story wood frame building of contemporary style with gable roof, concrete foundation, three bay facade, entrance and windows covered by burglar bars. C
571. 1556 Lemon Street. Circa 1970. 1 story wood frame building of no particular style with hip roof, concrete foundation, one bay facade with paired metal frame windows, entrance under large recessed corner porch with decorative iron supports. NC
572. 1558 Lemon Street. Circa 1900. 1 story wood frame shotgun with hip roof, raised brick foundation, characteristic two bay facade, entrance under recessed porch supported by posts, window covered by plywood. C [Photo #22]
573. 1563 Lemon Street. Circa 1940. 1 story wood frame Minimal Traditional with side gable roof, raised brick foundation, three bay facade, entrance under projecting gable with decorative iron supports over stoop, wood frame 3/1 windows, exposed rafters. C

574. 1565 Lemon Street. Circa 1945. 1 story wood frame Minimal Traditional with side gable roof, raised brick foundation, three bay facade, entrance under gabled porch, wood frame 6/6 windows, exposed rafters, louvered vent in gable. C
575. 1567 Lemon Street. Circa 1940. 1 story wood frame Minimal Traditional with side gable roof, raised brick foundation, three bay facade, entrance under projecting gabled porch supported by posts, metal frame 1/1 windows. C
576. 1568 Lemon Street. Circa 1900. 1 story wood frame shotgun with hip roof, raised brick foundation, characteristic two bay facade, entrance under recessed porch supported by posts on brick piers, metal frame 6/6 window, scalloped drop frieze. C
577. 1570 Lemon Street. Circa 1965. 1 story brick veneer building of contemporary style with hip roof, concrete foundation, three bay facade, entrance under projecting hip with decorative iron supports over stoop, metal frame multi-pane picture window, attached carport east elevation. NC
578. 1571 Lemon Street. Circa 1940. 1 story wood frame duplex with gable roof, raised brick foundation, four bay facade, both entrances in outer bays under projecting gables, metal frame 2/2 window and wood frame 6/6 windows, one entrance closed, louvered vent in gable. C
579. 1572 Lemon Street. Circa 1905. 1 story wood frame cottage with hip roof, raised brick foundation, three bay facade, entrance under recessed porch supported by posts, single and paired metal frame 6/6 windows, addition added east elevation, brick veneer applied up to window sills. NC
580. 1574 Lemon Street. Circa 1940. 1 story wood frame Minimal Traditional with gable roof, raised brick foundation, two bay facade, entrance at projecting gabled infilled porch, paired metal frame 1/1 windows, louvered vent in main gable. C

Leo Street

581. 1250 Leo Street. Circa 1945. 1 story wood frame Minimal Traditional with side gable roof, raised brick foundation, three bay facade, entrance under projecting gable with decorative iron supports over stoop, paired metal frame 2/2 windows, louvered vent in intersecting facing gable. C
582. 1251 Leo Street. Circa 1930. 1 story wood frame bungalow with gable roof, raised brick foundation, three bay facade, entrance under recessed porch supported by battered columns on brick piers, wood frame 3/1 windows, louvered vent in gable, exposed rafters. C
583. 1252 Leo Street. Circa 1975. 1 story brick veneer building of contemporary style with gable roof, concrete slab foundation, three bay facade, entrance under recessed corner porch supported by iron posts, multi-pane metal frame picture window and 8/8 windows, octagonal louvered vent in gable. NC
584. 1253 Leo Street. Circa 1940. 1 story wood frame Minimal Traditional with side gable roof, raised brick foundation, four bay facade, entrance under projecting gable with decorative iron supports over stoop, metal frame 8/8 windows, exposed rafters. C
585. 1254 Leo Street. Circa 1940. 1 story wood frame Minimal Traditional with side gable roof, raised brick foundation, three bay facade, entrance under projecting gable with decorative iron supports over stoop, wood frame windows with awnings, exposed rafters. C

586. 1255 Leo Street. Circa 1930. 1 story wood frame bungalow with hip roof, raised brick foundation, two bay facade, entrance under projecting gabled porch, porch screened, paired wood frame 1/1 windows, side chimney, louvered vent in gable, exposed rafters. C
587. 1256 Leo Street. Circa 1940. 1 story wood frame building of contemporary style with gable roof, raised brick foundation, two bay facade, entrance at corner porch in projecting gable bay, metal frame 2/2 windows and 1/1 windows, louvered vent in gables. C
588. 1257 Leo Street. Circa 1945. 1 story wood frame Minimal Traditional with side gable roof, raised brick foundation, four bay facade, entrance under projecting gable with decorative iron supports over stoop, metal frame 4/4 windows, exposed rafters. C
589. 1258 Leo Street. Circa 1945. 1 story asbestos sided Minimal Traditional with gable roof, raised brick foundation, three bay facade, entrance under projecting gable porch supported by posts, wood frame 6/6 windows. C
590. 1259 Leo Street. Circa 1950. 1 story wood frame building of no particular style with gable roof, raised brick foundation, three bay facade, entrance under gabled porch at south elevation, wood frame 6/6 windows. C
591. 1260 Leo Street. Circa 1940. 1 story asbestos sided Minimal Traditional with side gable roof, raised brick foundation, three bay facade, entrance under projecting gabled porch supported by posts, wood frame single and paired 3/1 windows. C
592. 1261 Leo Street. Circa 1950. 1 story wood frame building of no particular style with side gable roof, raised brick foundation, two bay facade, entrance under shed roofed porch supported by posts, porch abuts projecting gabled bay, metal frame 6/6 windows and 12 pane windows, addition added north elevation. NC
593. 1300 Leo Street. Circa 1945. 1 story wood frame Minimal Traditional with side gable roof, raised brick foundation, three bay facade, entrance under projecting gable with decorative iron supports, paired wood frame 3/1 windows, exposed rafters, louvered vent in porch gable. C
594. 1301 Leo Street. Circa 1940. 1 story wood frame Minimal Traditional with side gable roof, raised brick foundation, three bay facade, entrance under projecting gable with decorative iron supports over stoop, exposed rafters, metal frame 2/2 windows. C
595. 1302 Leo Street. Circa 1940. 1 story wood frame building of contemporary style with gable roof, raised brick foundation, three bay facade, entrance under projecting gable porch supported by turned posts, metal frame 6/6 windows. C
596. 1303 Leo Street. Circa 1940. 1 story wood frame Minimal Traditional with side gable roof, raised brick foundation, three bay facade, entrance under projecting gable with decorative iron supports over stoop, exposed rafters, metal frame 2/2 windows. C
597. 1304 Leo Street. Circa 1950. 1 story wood frame building of contemporary style with gable roof, raised brick foundation, three bay facade, entrance under projecting gabled porch supported by posts, metal frame 8/8 windows and paired 6/6 windows, louvered vent in porch gable. C
598. 1306 Leo Street. Circa 1950. 1 story wood frame Minimal Traditional with gable roof, raised brick foundation, three bay facade, entrance under projecting gable porch supported by posts on brick piers, metal frame 8/8 windows and 6/6 windows. C

Lomeroy Street

599. 1700 Lomeroy Street. Circa 1965. 1 story brick veneer building of contemporary style with hip roof, concrete foundation, three bay facade, entrance under shed roof with iron supports over stoop, metal frame paired 6/6 windows and 1/1 windows. NC
600. 1701 Lomeroy Street. Circa 1900. 1 story wood frame cottage with hip roof, raised brick foundation, three bay facade, entrance under recessed corner porch with decorative iron supports, metal frame picture window in gabled bay and 2/2 windows under porch, louvered vent in gable. C
601. 1702 Lomeroy Street. Circa 1955. 1 story vinyl sided building of contemporary style with gable roof, raised brick foundation, three bay facade, entrance under attached gable with decorative iron supports over stoop, wood frame paired and single 6/6 windows, louvered vent in gable. C
602. 1703 Lomeroy Street. Circa 1930. 1 story wood frame bungalow with gable roof, raised brick foundation, two bay facade, entrance with transom and sidelights, under projecting gabled porch supported by square columns, paired wood frame 3/1 windows, knee braces. C
603. 1704 Lomeroy Street. Circa 1920. 1 story vinyl sided bungalow with hip roof, raised brick foundation, three bay facade, entrance under recessed corner porch supported by square columns, paired and single metal frame 1/1 windows. C
604. 1705 Lomeroy Street. Circa 1900. 1 story wood frame Victorian cottage with hip roof, raised brick foundation, four bay facade, entrance with sidelights under recessed porch supported by posts, porch abuts semi-octagonal gabled bay, majority of windows are wood frame 2/2 double hung sash. C [Photo #2]
605. 1706 Lomeroy Street. Circa 1945. 1 story wood frame building of contemporary style with gable roof, raised brick foundation, three bay facade, entrance under screened recessed corner porch supported by posts, paired metal frame 2/2 windows, brick veneer applied up to window sills. NC
606. 1707 Lomeroy Street. Circa 1930. 1 story wood frame bungalow with gable roof, raised brick foundation, three bay facade, entrance with sidelights and transom under recessed porch with decorative iron supports on brick piers, paired and single wood frame 3/1 windows, knee braces, louvered vent in gable covered. C

Lott Street

607. 452 Lott Street. Circa 1915. 1 story wood frame bungalow with hip roof, raised brick foundation, three bay facade, entrance under recessed porch supported by battered columns on brick piers, porch screened, paired wood frame 3/1 windows, interior chimney. C
608. 454 Lott Street. Circa 1960. 1 story brick veneer Minimal Traditional with side gable roof, raised concrete foundation, two bay facade, entrance under projecting gable porch with decorative iron supports, metal frame picture window with 1/1 sidelights, addition added south elevation. NC
609. 502 Lott Street. Circa 1950. 2 story wood frame garage/apartment with side gable roof, concrete slab foundation, three bay facade, stairways at north and south elevation to second floor entrances, centered entrance first floor with attached shed roof supported by posts, metal frame awning windows, building converted into apartments. NC
610. 504 Lott Street. Circa 1965. 1 story brick veneer building of contemporary style with hip roof, concrete foundation, four bay facade, entrance in projecting hipped bay, metal frame picture window with sidelights, attached gabled carport northern half of facade. NC

611. 506 Lott Street. Circa 1930. 1 story wood frame bungalow with gable roof, raised brick foundation, three bay facade, entrance under recessed corner porch supported by posts, paired metal frame 1/1 windows, louvered vent in gable, attached carport north elevation. NC
612. 508 Lott Street. Circa 1920. 1 story stucco cottage with hip roof, raised brick foundation, two bay facade, entrance at infilled recessed corner porch, paired wood frame 3/1 windows. NC

McArthur Street

613. 1304 McArthur Street. Circa 1950. 1 story wood frame Minimal Traditional with side gable roof, raised brick foundation, four bay facade, entrance under projecting eave of roof supported by posts over stoop, metal frame 6/6 windows, interior chimney. C
614. 1305 McArthur Street. Circa 1950. 1 story vinyl sided Minimal Traditional with side gable roof, raised brick foundation, five bay facade, entrance under projecting eave of roofline, metal frame 2/2 windows. C
615. 1306 McArthur Street. Circa 1950. 1 story wood frame Minimal Traditional with side gable roof, raised brick foundation, five bay facade, entrance under projecting eave of roofline, metal frame 6/6 windows with awnings and paired 1/1 windows, addition added east elevation. NC
616. 1307 McArthur Street. Circa 1955. 1 story wood frame Minimal Traditional with side gable roof, raised brick foundation, four bay facade, entrance under screened gabled porch supported by posts, awning across porch, metal frame 1/1 windows, attached carport east elevation, side chimney. NC
617. 1308 McArthur Street. Circa 1955. 1 story asbestos sided Minimal Traditional with side gable roof, raised brick foundation, three bay facade, entrance under projecting gabled porch with decorative iron supports, wood frame 6/6 windows, interior and side chimneys, garage added east elevation. NC
618. 1309 McArthur Street. Circa 1960. 1 story Masonite sided building of contemporary style with hip roof, raised brick foundation, five bay facade, entrance under recessed porch with decorative iron supports, metal frame 6/6 windows, interior chimneys. C
619. 1310 McArthur Street. Circa 1990. 1 story brick veneer building of contemporary style with multiple hip roofs, raised concrete foundation, four bay facade, entrance under projecting hip roof with decorative iron supports over stoop, metal frame multi-pane picture windows, interior chimney. NC
620. 1311 McArthur Street. Circa 1955. 1 story wood frame Minimal Traditional with side gable roof, raised brick foundation, four bay facade, entrance at facing gable bay, metal frame 6/6 windows, side and interior chimneys. C
621. 1350 McArthur Street. Circa 1960. 1 story wood frame Ranch style house with side gable roof, raised brick foundation, five bay facade, entrance under projecting gabled porch with decorative iron supports, metal frame 1/1 windows, brick veneer applied up to window sills and under porch. NC
622. 1351 McArthur Street. Circa 1960. 1 story wood frame building of contemporary style with hip roof, raised brick foundation, three bay facade, entrance under screened gabled porch, metal frame 8/8 windows, side and interior chimneys. C
623. 1352 McArthur Street. Circa 1950. 1 story wood frame Minimal Traditional with side gable roof, raised brick foundation, four bay facade, entrance at infilled projecting gabled porch, wood frame 6/6 windows, side and interior chimney, garage added east elevation. NC

624. 1354 McArthur Street. Circa 1960. 1 story wood frame building of contemporary style with hip roof, raised brick foundation, five bay facade, entrance under recessed porch supported by posts, wood frame 6/6 windows, interior chimneys. C
625. 1355 McArthur Street. Circa 1950. 1 story wood frame Minimal Traditional with side gable roof, raised brick foundation, four bay facade, entrance under projecting gable with decorative iron supports over stoop, wood frame 6/6 windows, side chimney. C
626. 1356 McArthur Street. Circa 1960. 1 story wood frame building of contemporary style with side gable roof, raised brick foundation, four bay facade, metal frame 1/1 windows, entrance under screened gabled porch. NC
627. 1357 McArthur Street. Circa 1950. 1 story wood frame Minimal Traditional with side gable roof, raised brick foundation, five bay facade, entrance under projecting eave of roofline, wood frame 6/6 windows, side and interior chimney. C
628. 1358 McArthur Street. Circa 1950. 1 story asbestos sided building of contemporary style with hip roof, raised brick foundation, three bay facade, entrance under projecting gable porch with decorative iron supports, metal frame 6/6 windows, building in state of demolition. NC
629. 1359 McArthur Street. Circa 1955. 1 story asbestos sided Minimal Traditional with side gable roof, raised brick foundation, four bay facade, entrance under projecting gabled porch with decorative iron supports, wood frame 6/6 windows, awnings over windows, interior chimney. C
630. 1400 McArthur Street. Circa 1960. 1 story wood frame building of contemporary style with side gable roof, raised brick foundation, inset central entrance in projecting hipped addition at facade, paired metal frame 6/6 windows, carport added east elevation, side and interior chimneys. NC
631. 1401 McArthur Street. Circa 1955. 1 story asbestos sided building of contemporary style with hip roof, raised brick foundation, four bay facade, entrance under projecting gable with decorative iron supports over stoop, paired and single wood frame 6/6 windows, interior chimney. C
632. 1402 McArthur Street. Circa 1955. 1 story wood frame Minimal Traditional with side gable roof, raised brick foundation, four bay facade, entrance under shed roof with decorative iron supports over stoop, metal frame 1/1 windows, side and interior chimney. C
633. 1403 McArthur Street. Circa 1950. 1 story wood frame Minimal Traditional with side gable roof, raised brick foundation, five bay facade, entrance under projecting eave of roofline, wood frame 6/6 windows, side and interior chimneys. C
634. 1404 McArthur Street. Circa 1955. 1 story wood frame Minimal Traditional with side gable roof, raised brick foundation, five bay facade, entrance under projecting eave of roofline, metal frame 2/2 windows. C
635. 1405 McArthur Street. Circa 1965. 1 story brick veneer building of contemporary style with side gable roof, concrete foundation, four bay facade, entrance at projecting gabled bay, metal frame 1/1 windows and picture windows. NC
636. 1407 McArthur Street. Circa 1955. 1 story wood frame building of contemporary style with hip roof, raised brick foundation, five bay facade, entrance under recessed porch supported by posts, metal frame multi-pane picture window and 6/6 windows, interior chimney. C
637. 1450 McArthur Street. Circa 1950. 1 story wood frame Minimal Traditional with side gable roof, raised brick foundation, four bay facade, entrance at infilled gabled porch, wood frame windows with awnings, attached garage east elevation. NC

638. 1451 McArthur Street. Circa 1950. 1 story asbestos sided Minimal Traditional with side gable roof, raised brick foundation, three bay facade, entrance under shed roof supported by posts, wood frame 6/6 windows with burglar bars, side and interior chimneys. C
639. 1452 McArthur Street. Circa 1960. 1 story wood frame building of contemporary style with hip roof, raised brick foundation, five bay facade, entrance under recessed porch supported by posts, wood frame 6/6 windows, interior chimneys. C
640. 1454 McArthur Street. Circa 1960. 1 story wood frame Minimal Traditional with side gable roof, raised brick foundation, five bay facade, entrance in facing gable bay, metal frame multi-pane picture window and 6/6 windows, side and interior chimneys. C
641. 1455 McArthur Street. Circa 1950. 1 story wood frame Minimal Traditional with side gable roof, raised brick foundation, four bay facade, entrance under projecting eave of roofline, wood frame 6/6 windows, side and interior chimneys. C
642. 1457 McArthur Street. Circa 1960. 1 story wood frame Minimal Traditional with side gable roof, raised brick foundation, three bay facade, entrance infilled gabled porch, wood frame 1/1 windows, side and interior chimney, attached garage east elevation. NC

Melrose Street

643. 1304 Melrose Street. Circa 1970. 1 story brick veneer building of contemporary style with gable roof, raised concrete foundation, two bay facade, inset entryway, paired metal frame 6/6 windows. NC
644. 1308 Melrose Street. Circa 1910. 1 story wood frame cottage with hip roof, raised brick foundation, entrance at screened porch to which a concrete block knee wall has been added, shed roof dormer with louvered vent. C
645. 1310 Melrose Street. Circa 1970. 1 story brick veneer building of contemporary style with hip roof, concrete foundation, three bay facade, entrance under projecting gable with decorative iron supports, metal frame multi-pane picture window and 6/6 windows. NC
646. 1312 Melrose Street. Circa 1950. 1 story brick veneer Minimal Traditional with side gable roof, raised brick foundation, three bay facade, entrance under shed roof porch with decorative iron supports, porch abuts gabled bay, paired metal frame 1/1 windows and awning windows, side chimney, brick veneer added at later date. NC
647. 1314 Melrose Street. Circa 1935. 1 story wood frame building of contemporary style with hip roof, raised brick foundation, three bay facade, entrance at recessed corner porch with decorative iron support, hipped porch partially infilled for additional living space, paired wood frame 1/1 windows and tripled plate glass in infill. NC
648. 1316 Melrose Street. Circa 1960. 1 story brick veneer Ranch home with side gable roof, concrete foundation, four bay facade, entrance under projecting gable supported by posts, metal frame 6/6 windows. C
649. 1318 Melrose Street. Circa 1960. 1 story brick veneer Ranch with side gable roof, concrete foundation, four bay facade, entrance under projecting gable supported by posts, metal frame 6/6 windows and multi-pane picture window. C
650. 1354 Melrose Street. Circa 1930. 1 story wood frame bungalow with gable roof, raised brick foundation, three bay facade, entrance under recessed porch supported by brick columns, paired wood frame 3/1 windows, louvered vent in gable, knee braces, side chimney. C

651. 1356 Melrose Street. Circa 1960. 1 story brick veneer Minimal Traditional with side gable roof, raised brick foundation, three bay facade, entrance under gable porch supported by posts with smaller gable over stoop, paired metal frame 1/1 windows. C
652. 1357 Melrose Street. Circa 1930. 1 story asbestos sided bungalow with gable on hip roof, raised brick foundation, three bay facade, entrance under projecting gabled porch with decorative iron supports, metal frame paired 6/6 windows and multi-pane picture window, louvered vents in gables. C
653. 1358 Melrose Street. Circa 1930. 1 story wood frame bungalow with gable roof, raised brick foundation, three bay facade, entrance under projecting gabled porch supported by brick columns, paired and single wood frame 3/1 windows. C
654. 1359 Melrose Street. Circa 1930. 1 story wood frame bungalow with gable roof, raised brick foundation, three bay facade, entrance with transom at infilled recessed porch, awning across entrance, wood frame windows. NC
655. 1360 Melrose Street. Circa 1950. 1 story asbestos sided building of contemporary style with gable roof, raised brick foundation, three bay facade, entrance under projecting gable porch with decorative iron supports, paired metal frame windows and picture window, burglar bars and awnings, single lights in gables. C
656. 1400 Melrose Street. Circa 1930. 1 story wood frame bungalow with gable roof, raised brick foundation, three bay facade, entrance under projecting gabled porch supported by battered columns on brick piers, wood frame 3/1 windows, louvered vents in peak of gables, exposed rafters. C
657. 1404 Melrose Street. Circa 1965. 1 story wood frame building of contemporary style with gable roof, concrete foundation, three bay facade, entrance under attached gable supported by posts over stoop, metal frame multi-pane picture windows. NC
658. 1405 Melrose Street. Circa 1955. 1 story brick veneer building of contemporary style with gable roof, raised brick foundation, three bay facade, entrance under recessed porch supported by brick columns, metal frame multi-pane picture windows, side chimney, addition west elevation. NC
659. 1406 Melrose Street. Circa 1965. 1 story wood frame building of contemporary style with gable roof, concrete foundation, two bay facade, entrance at recessed corner porch with decorative iron supports, metal frame awning windows, roofline projects along west elevation forming carport. NC
660. 1407 Melrose Street. Circa 1965. 1 story brick veneer building of contemporary style with hip roof, concrete slab foundation, three bay facade, entrance under projecting hip roof with decorative iron supports over stoop, metal frame awning windows. NC
661. 1408 Melrose Street. Circa 1950. 1 story concrete block building of contemporary style with gable roof, raised concrete foundation, three bay facade, entrance under recessed porch with decorative iron supports, paired and single wood frame 6/6 windows. C
662. 1410 Melrose Street. Circa 1950. 1 story concrete block building of contemporary style with hip roof, raised concrete foundation, two bay facade, entrance at recessed corner porch supported by paired arches, metal frame windows with awnings. C

Michigan Avenue

663. 500 Michigan Avenue. Circa 1930. 1 story wood frame bungalow with gable roof, raised brick foundation, three bay facade, entrance under projecting gabled

porch supported by brick columns, paired and single wood frame 3/1 windows, tripled louvered vent in main gable, exposed rafters and purlins, interior chimney. C

664. 501 Michigan Avenue. Circa 1940. 1 story wood frame Minimal Traditional with side gable roof, raised brick foundation, four bay facade, entrance under projecting gable supported by posts over stoop, paired wood frame 6/6 windows and plate glass window in outer most bay, expose rafters, gabled dormers with 6 pane lights. C
665. 502 Michigan Avenue. Circa 1930. 1 story wood frame bungalow with gable roof, raised brick foundation, three bay facade, entrance under recessed porch supported by stucco columns, paired and single wood frame Craftsman style windows, knee braces, exposed rafters, interior chimney, louvered vent in gable. C
666. 503 Michigan Avenue. Circa 1930. 1 story wood frame bungalow with jerkin head roof with ridge parallel to street, raised brick foundation, two bay facade, entrance at infilled jerkin head porch, paired wood frame 3/1 windows and plate glass windows at porch, exposed rafters, side chimney. NC
667. 505 Michigan Avenue. Circa 1925. 2 story wood frame Craftsman with side gable roof, raised brick foundation, four bay facade, entrance and French door under projecting shed roofed porch supported by paired posts on brick knee wall, shed roofed dormer with wood frame casement windows, wood frame casement windows first floor, sunroom north elevation. C [Photo #10]
668. 506 Michigan Avenue. Circa 1935. 1 story wood frame Minimal Traditional with side gable roof, raised brick foundation, three bay facade, entrance under projecting gabled porch supported by brick columns, wood frame 4/1 windows and picture window with sidelights and transom, knee braces, exposed rafters, side chimney, porte-cochere north elevation supported by brick columns. C
669. 508 Michigan Avenue. Circa 1930. 1 story wood frame bungalow with gable roof, raised brick foundation, three bay facade, entrance under gabled porch supported by brick columns, side chimney, exposed rafters. C
670. 509 Michigan Avenue. Circa 1925. 2 story brick veneer apartment building with hip roof, raised brick foundation, four bay facade, entrance with sidelights and transom, paired wood frame 9/1 windows and picture window with 6/1 sidelights, casement windows, projecting hipped porch open at first floor and enclosed at second. C
671. 510 Michigan Avenue. Circa 1930. 1 story wood frame bungalow with side gable roof, raised brick foundation, three bay facade, entrance at infilled corner porch in projecting gabled bay, columns still visible, paired wood frame 4/1 windows and tripled 3/1 windows, exposed rafters, interior chimneys, 4 light window with flanking louvered vents in gable. NC
672. 512 Michigan Avenue. Circa 1930. 1 story vinyl sided bungalow with gable roof, raised brick foundation, two bay facade, entrance at infilled gable porch with pierced brick columns still visible, paired wood frame 3/1 windows and 1/1 windows with transoms, side chimney, attached carport north elevation. NC
673. 513 Michigan Avenue. Circa 1925. 1 story wood frame bungalow with hip roof, raised brick foundation, three bay facade, entrance under projecting gabled porch supported by columns on brick piers, wood frame windows, interior chimney. C
674. 514 Michigan Avenue. Circa 1930. 2 story wood frame Colonial Revival with side gable roof, raised brick foundation, three bay facade, entrance with semi-circular door hood supported by posts over stoop, metal frame 6/6 windows, attached hipped porch infilled at later date for additional living space on south elevation. NC [Photo #9]

675. 550 Michigan Avenue. Circa 1925. 1 story wood frame bungalow with hip roof, raised brick foundation, four bay facade, entrance under wrap-around stucco porch supported by stucco columns, paired and single wood frame casement windows, interior chimney, porte-cochere north elevation, exposed rafters. C
676. 551 Michigan Avenue. Circa 1930. 1 story wood frame bungalow with side gable roof, raised brick foundation, three bay facade, entrance under attached gable over stoop, paired wood frame 3/1 windows, porch infilled but brick support still visible, side chimney, peak of gable rises above apex of main roof, exposed rafters. NC
677. 552 Michigan Avenue. Circa 1965. 1 story wood frame building of no particular style with gable roof, raised brick foundation, three bay facade, centered entrance, wood frame 1/1 windows, louvered vent in gable peak. NC
678. 553 Michigan Avenue. Circa 1930. 1 story wood frame building of contemporary style with hip roof, raised brick foundation, four bay facade, entrance in infilled projecting gabled porch, wood frame casement windows, awnings over windows, half-moon louvered vent in gable. NC
679. 554 Michigan Avenue. Circa 1925. 1 story wood frame bungalow with side gable roof, raised brick foundation, three bay facade, entrance with sidelights and transom under recessed porch supported by brick columns, wood frame Craftsman windows, gabled dormer with 4 Craftsman windows, knee braces, side chimney, porte-cochere south elevation. C
680. 555 Michigan Avenue. Circa 1930. 1 story wood frame bungalow with gable roof, raised brick foundation, three bay facade, entrance at partially infilled projecting gabled porch, wood frame windows with burglar bars, louvered vent in gable, exposed rafters. NC
681. 556 Michigan Avenue. Circa 1935. 1 story wood frame Minimal Traditional with side gable roof, raised brick foundation, entrance slightly off center, wood frame casement windows, projecting gabled bay, exposed rafters. C
682. 557 Michigan Avenue. Circa 1970. 1 story brick veneer building of contemporary style with hip roof, concrete slab foundation, three bay facade, entrance under projecting hip porch supported by posts, metal frame 9/6 windows. NC
683. 558 Michigan Avenue. Circa 1940. 1 story wood frame Minimal Traditional with side gable roof, raised brick foundation, two bay facade, entrance in facing gabled bay with battered archway, wood frame picture window, exposed rafters, side chimney, corner porch with battered column. C
684. 559 Michigan Avenue. Circa 1930. 1 story wood frame bungalow with gable roof, raised brick foundation, three bay facade, entrance under projecting gabled porch supported by columns on brick piers, wood frame windows, awnings over windows and porch, louvered vents in gables, exposed rafters, side chimney. C
685. 560 Michigan Avenue. Circa 1940. 1 story wood frame Minimal Traditional with side gable roof, raised brick foundation, three bay facade, entrance at projecting gable supported by battered archway, wood frame windows with burglar bars, recessed corner porch screened. C
686. 561 Michigan Avenue. Circa 1930. 1 story wood frame bungalow with gable roof, raised brick foundation, three bay facade, entrance under projecting gable porch with decorative iron supports on brick piers, wood frame 2/1 windows, exposed rafters, carport added north elevation. C
687. 562 Michigan Avenue. Circa 1905. 2 story wood frame American Four Square with hip roof, raised brick foundation, three bay facade, entrance under attached gabled porch with partially infilled bay, porch supported by posts, metal frame 6/6 windows, interior chimney, building damaged by fire. NC [Photo #14]

688. 563 Michigan Avenue. Circa 1955. 1 1/2 story wood frame Minimal Traditional with side gable roof, raised brick foundation, entrance under shed roofed porch supported by posts, porch lowered to grade along part of its length, porch abuts altered hipped bay, paired and single wood frame 1/1 windows. NC
689. 565 Michigan Avenue. Circa 1910. 1 story wood frame cottage with hip roof, raised brick foundation, two bay facade, entrance at recessed corner porch supported by square column on brick pier, windows missing, fire damage. C
690. 1146 Michigan Avenue. Circa 1975. 1 story wood frame commercial building with gable roof, concrete foundation, two bay facade, entrances and two auto bays with metal roll doors along north elevation, windows covered by plywood. NC
691. 1148 Michigan Avenue. Circa 1965. 1 story concrete block commercial building with flat roof, concrete slab foundation, five bay facade, modern entrance with plate glass door, windows partially boarded with plywood, auto bays at northern half of facade. NC
692. 1161 Michigan Avenue. Circa 1960. 1 story brick veneer ecclesiastical building with gable roof, concrete foundation, 1 bay facade with double door entrance and gothic arch above, cross at peak of central tower, 2 story ell at rear. C
693. 1200 Michigan Avenue. Circa 1965. 1 story concrete block commercial building with flat roof, concrete slab foundation, two bay facade, entrance with plate glass door in northern bay in facade, metal frame windows. NC
694. 1201 Michigan Avenue. Circa 1965. 1 story structural tile commercial building with flat roof, concrete slab foundation, three bay facade, entrance and windows boarded. NC
695. 1203 Michigan Avenue. Circa 1970. 1 story brick veneer commercial building with gable roof, concrete slab foundation, two bay facade, entrance and window boarded, building partially demolished. NC
696. 1207 Michigan Avenue. Circa 1970. 1 story brick commercial building with flat roof, concrete slab foundation, seven bay facade, windows and doors boarded. NC
697. 1210 Michigan Avenue. Circa 1970. 1 story corrugated metal and brick commercial building with flat roof, two bay facade, entrances in both bays with plate glass doors and sidelights. NC
698. 1214 Michigan Avenue. Circa 1975. 1 story brick veneer commercial building with pseudo-Mansard roof, concrete slab foundation, entrance with plate glass door and solid bank of flanking metal frame plate glass windows. NC
699. 1250 Michigan Avenue. Circa 1985. 1 story brick veneer commercial building with pseudo-Mansard roof, concrete slab foundation, entrance with plate glass door, metal frame plate glass windows. NC
700. 1258 Michigan Avenue. Circa 1965. 1 story brick veneer commercial building with side gable roof, concrete slab foundation, three bay facade, auto bays in all three bays. NC
701. 1260 Michigan Avenue. Circa 1970. 1 story concrete block commercial building, concrete slab foundation, building partially demolished. NC

Midway Avenue

702. 1553 Midway Avenue. Circa 1940. 1 story brick veneered Minimal Traditional with gable roof, raised brick foundation, entrance at infilled porch, paired metal frame 8/8 windows, awnings over windows, louvered vent in gable. NC

703. 1555 Midway Avenue. Circa 1940. 1 story wood frame Minimal Traditional with gable roof, raised brick foundation, two bay facade, entrance under recessed corner porch with decorative iron support, metal frame multi-pane picture window and 1/1 windows, louvered vent in gable. C
704. 1566 Midway Avenue. Circa 1980. 1 story brick veneer commercial building with flat roof, concrete foundation, 1 bay facade indicating entrance. NC
705. 1574 Midway Avenue. Circa 1980. 1 story corrugated metal pre-fab warehouse, concrete slab foundation, 1 bay facade with large metal roll door under projecting flat roof, gable roof. NC
706. 1601 Midway Avenue. Circa 1930. 1 story wood frame bungalow with gable roof, raised brick foundation, two bay facade, entrance at recessed corner porch with square columns on brick piers, metal frame multi-pane picture window and 6/6 windows. C
707. 1606 Midway Avenue. Circa 1980. 1 story concrete block commercial building with gable roof, seven bay facade, concrete slab foundation, entrance under projecting gable with iron supports over stoop, metal frame windows, attached warehouse with flat roof at rear. NC
708. 1651 Midway Avenue. Circa 1930. 1 story wood frame bungalow with gable roof, raised brick foundation, three bay facade, entrance under projecting gabled porch supported by columns on brick piers, paired wood frame 6/6 windows, louvered vents in gables. C
709. 1653 Midway Avenue. Circa 1945. 1 story wood frame building of contemporary style with gable roof, raised brick foundation, three bay facade, entrance in recessed corner porch supported by post, metal frame paired 6/6 windows, paired louvered vents in gable, picture window and entrance boarded. C
710. 1655 Midway Avenue. Circa 1940. 1 story wood frame building of contemporary style with gable roof, raised brick foundation, three bay facade, entrance at infilled gabled porch, paired metal frame 2/2 windows, louvered vent in porch gable. NC
711. 1657 Midway Avenue. Circa 1910. 1 story wood frame cottage with gable roof, raised brick foundation, three bay facade, entrance under screened recessed porch supported by classical columns, paired wood frame 4/1 windows, exposed rafters, louvered vent in gable, siding in gable peak. C
712. 1659 Midway Avenue. Circa 1960. 1 story wood frame Minimal Traditional with side gable roof, raised brick foundation, four bay facade, entrance under projecting eave of roofline supported by posts, metal frame single and paired 6/6 windows. C
713. 1660 Midway Avenue. Circa 1950. 1 story wood frame Minimal Traditional with side gable roof, raised brick foundation, four bay facade, entrance under projecting gable with decorative iron supports on brick piers, metal frame 2/2 windows, additions and carport at east elevation. NC
714. 1700 Midway Avenue. Circa 1980. 1 story corrugated metal pre-fab commercial building with gable roof, two bay facade, concrete slab foundation, entrance and large metal roll door northern half of facade. NC
715. 1701 Midway Avenue. Circa 1965. 1 story brick veneer building of contemporary style with side gable roof, concrete foundation, four bay facade, entrance in western most bay, paired metal frame 2/2 windows, carport west elevation. NC
716. 1705 Midway Avenue. Circa 1985. 1 story brick veneer building of contemporary style with side gable roof, concrete foundation, five bay facade,

entrance under projecting gable supported by columns over stoop, paired and single metal frame 9/6 windows. NC

717. 1756 Midway Avenue. Circa 1945. 1 story concrete block duplex with gable roof, raised concrete foundation, four bay facade, two entrances located under attached gabled porch supported by posts, metal frame 1/1 windows. C
718. 1758 Midway Avenue. Circa 1945. 1 story concrete block duplex with gable roof, raised concrete foundation, three bay facade, entrance under attached gabled porch supported by post, other entrance now infilled, wood frame 4/4 windows, louvered vent in porch gable. C

Old Canal Street

719. 1700 Old Canal Street. Circa 1970. 1 story corrugated metal pre-fab commercial building with gable roof, concrete slab foundation, 1 bay facade with metal roll door at auto bay. NC
720. 1701 Old Canal Street. Circa 1930. 2 story brick warehouse with flat roof, concrete foundation, metal doors and windows. C

Olive Street

721. 1250 Olive Street. Circa 1955. 1 story wood frame Minimal Traditional with side gable roof, raised brick foundation, three bay facade, entrance under recessed porch supported by posts, metal frame single pane windows, gable over porch at northern end of facade. C
722. 1251 Olive Street. Circa 1950. 1 story vinyl sided Minimal Traditional with side gable roof, raised brick foundation, three bay facade, entrance under projecting gable with decorative iron supports over stoop, paired and tripled metal frame windows with awning, side chimney. C
723. 1252 Olive Street. Circa 1930. 1 story wood frame bungalow with gable roof, raised brick foundation, two bay facade, entrance under projecting gabled porch supported by paired posts on brick piers, porch screened, paired metal frame 1/1 windows, side chimney, louvered octagonal vent in main gable, exposed rafters. C
724. 1253 Olive Street. Circa 1940. 1 story asbestos sided Minimal Traditional with side gable roof, raised brick foundation, two bay facade, entrance at screened porch with awning, paired wood frame windows with awning, exposed rafters. C
725. 1254 Olive Street. Circa 1930. 1 story wood frame bungalow with gable roof, raised brick foundation, two bay facade, entrance at screened porch with decorative iron supports, octagonal louvered vent in porch gable, metal frame 6/6 windows. C
726. 1255 Olive Street. Circa 1930. 1 story wood frame bungalow with gable roof, raised brick foundation, three bay facade, entrance at screened recessed porch supported by brick columns, paired wood frame windows, partial width awning across porch, louvered vent in gable, exposed rafters, side chimney. C
727. 1256 Olive Street. Circa 1930. 1 story wood frame bungalow with gable roof, raised brick foundation, three bay facade, entrance under recessed porch supported by brick columns, porch screened and clapboard knee wall added, wood frame 6/6 windows, octagonal louvered vent in gable, exposed rafters. C
728. 1259 Olive Street. Circa 1955. 1 story brick veneered building of contemporary style with gable roof, raised brick foundation, three bay facade, entrance under smaller of two facing gables with decorative iron supports over stoop, metal frame 6/6 and picture window, louvered vent in peak of main gable. NC
729. 1260 Olive Street. Circa 1945. 1 story wood frame Minimal Traditional with side gable roof, raised brick foundation, four bay facade, entrance at ell of projecting gabled bay with shed roof supported by decorative iron post over stoop,

paired wood frame 6/6 windows and metal frame 8/8 windows, side chimney, addition added north elevation with recessed porch with decorative iron supports. NC

730. 1261 Olive Street. Circa 1960. 1 story brick veneer building of contemporary style with side gable roof, raised brick foundation, four bay facade, entrance under attached shed roofed corner porch with iron support, metal frame awning windows, addition added along northern half of facade. NC
731. 1300 Olive Street. Circa 1930. 1 story wood frame bungalow with gable roof, raised brick foundation, three bay facade, entrance under recessed porch supported by posts, paired and single metal frame 1/1 windows, louvered vent in gable, exposed rafters. C
732. 1301 Olive Street. Circa 1955. 1 story asbestos sided building of contemporary style with gable roof, raised brick foundation, two bay facade, entrance under attached gable with decorative iron supports over stoop, paired metal frame 6/6 windows, louvered vent in gable, brick veneer to window sills. C
733. 1302 Olive Street. Circa 1990. 1 story brick veneer building of contemporary style with hip roof, concrete slab foundation, three bay facade, entrance under projecting hipped porch supported by posts, metal frame picture window and 6/6 windows. NC
734. 1303 Olive Street. Circa 1955. 1 story wood frame apartment building with gable roof, raised brick foundation, 1 bay facade, entrance at south elevation under projecting gabled porch supported by posts, metal frame awning windows, louvered vent in gable, porch added at later date. NC
735. 1304 Olive Street. Circa 1925. 1 story wood frame Craftsman with gable roof, raised brick foundation, two bay facade, entrance at ell of intersecting gabled bay, metal frame 2/2 windows, exposed rafters, knee braces. C
736. 1305 Olive Street. Circa 1950. 1 story wood frame building of contemporary style with gable roof, raised brick foundation, two bay facade, entrance along north elevation, paired and single wood frame 6/6 windows, awnings over windows, covered vent in gable. C
737. 1307 Olive Street. Circa 1955. 1 story brick veneer Minimal Traditional with side gable roof, raised brick foundation, two bay facade, entrances under projecting gable with decorative iron supports over stoop, metal frame picture window with 2/2 sidelights, carport added south elevation. NC
738. 1308 Olive Street. Circa 1955. 2 story wood frame building of contemporary style with gable roof, concrete foundation, two bay facade, entrance at intersection of projecting shed roof brick veneered bay, bay is later addition, paired metal frame picture windows, louvered vent in gable. NC
739. 1309 Olive Street. Circa 1955. 1 story concrete block Minimal Traditional with side gable roof, concrete foundation, four bay facade, entrance under gable with decorative iron support over stoop, metal frame paired 6/6 windows with burglar bars. C

Opal Street

740. 903 Opal Street. Circa 1940. 1 story wood frame Minimal Traditional with side gable roof, raised brick foundation, three bay facade, entrance under projecting gable supported by posts over stoop, metal frame 1/1 windows, carport added north elevation. NC
741. 907 Opal Street. Circa 1940. 1 story wood frame building of no particular style with gable roof, raised brick foundation, 1 bay facade, entrance at south elevation, windows boarded, addition added at rear of south elevation and clapboard siding added. NC

742. 913 Opal Street. Circa 1975. 1 story corrugated metal warehouse with flat roof, concrete slab foundation, two large bays for vehicles. NC

Orange Street

743. 1501 Orange Street. Circa 1940. 1 story wood frame building of contemporary style with gable roof, raised brick foundation, three bay facade, entrance under screened corner porch supported by post, metal frame 2/2 windows covered by plywood, louvered vent in gable. C
744. 1503 Orange Street. Circa 1965. 1 story brick veneer duplex with gable roof, concrete slab foundation, four bay facade, entrance under recessed porch supported by iron posts, metal frame 6/6 windows, louvered vent in peak of gable. NC
745. 1505 Orange Street. Circa 1930. 1 story wood frame bungalow with gable roof, raised brick foundation, two bay facade, entrance under recessed corner porch supported by battered column, wood frame 4/4 windows, exposed rafters, louvered vent in gable. C
746. 1506 Orange Street. Circa 1940. 1 story wood frame Minimal Traditional with gable roof, raise brick foundation, two bay facade, entrance under recessed corner porch supported by post, metal frame 1/1 windows, louvered vent in gable. C
747. 1507 Orange Street. Circa 1945. 1 story wood frame building of contemporary style with gable roof, raised brick foundation, three bay facade, entrance under projecting gable porch with decorative iron supports, metal frame 6/6 windows and multi-pane picture window, carport added along west elevation. NC
748. 1509 Orange Street. Circa 1935. 1 story asbestos sided bungalow with gable roof, raised brick foundation, two bay facade, entrance under recessed corner porch supported by fluted classical column on brick pier, metal frame 6/6 windows, louvered vent in gable. C
749. 1510 Orange Street. Circa 1965. 1 story wood frame building of contemporary style with gable roof, concrete foundation, three bay facade, entrance under recessed gable porch supported by turned posts, metal frame single and paired 6/6 windows, ell at rear. NC
750. 1511 Orange Street. Circa 1940. 1 story wood frame building of contemporary style with gable roof, raised brick foundation, two bay facade, entrance under recessed corner porch supported by brick column, metal frame 2/2 window, awning over porch. C
751. 1512 Orange Street. Circa 1970. 1 story brick veneer building of contemporary style with gable roof, concrete foundation, four bay facade, entrance in projecting gabled bay with flanking paired metal frame picture windows, metal frame 8/8 window in remaining bay, carport east elevation. NC
752. 1513 Orange Street. Circa 1940. 1 story asbestos sided building of contemporary style with gable roof, raised brick foundation, two bay facade, entrance at infilled corner porch, metal frame multi-pane picture window, louvered vent in gable, brick veneer applied up to window sill, carport added east elevation. NC
753. 1515 Orange Street. Circa 1940. 1 story wood frame building of contemporary style with gable roof, raised brick foundation, two bay facade, entrance under projecting gabled porch supported by posts, metal frame picture window with sidelights, exposed rafters, louvered vent in gable. C
754. 1516 Orange Street. Circa 1935. 1 story wood frame bungalow with gable roof, raised brick foundation, two bay facade, entrance under recessed corner porch

supported by battered column on brick pier, paired and single metal frame 6/6 windows, louvered vent in gable. C

755. 1517 Orange Street. Circa 1945. 1 story asbestos sided Minimal Traditional with side gable roof, raised brick foundation, three bay facade, entrance under projecting gabled porch with decorative iron supports, metal frame 2/2 windows and picture window with sidelights. C
756. 1518 Orange Street. Circa 1940. 1 story wood frame Minimal Traditional with side gable roof, raised brick foundation, four bay facade, entrance under projecting gabled porch with decorative iron supports, metal frame 2/2 windows and picture window, intersecting gable rises above apex of roofline. C
757. 1519 Orange Street. Circa 1955. 1 story wood frame building of contemporary style with gable roof, raised brick foundation, 1 bay facade, entrance at projecting gabled porch with decorative iron supports, multi-pane metal frame picture window, octagonal louvered vent in porch gable, brick veneer applied up to window sills. NC
758. 1521 Orange Street. Circa 1970. 1 story brick veneer building of contemporary style with gable on hip roof, concrete foundation, three bay facade, entrance under recessed corner porch with decorative iron support, metal frame casement windows. NC
759. 1522 Orange Street. Circa 1950. 1 story wood frame building of contemporary style with gable roof, raised brick foundation, three bay facade, entrance under projecting gabled porch with decorative iron supports, metal frame multi-pane picture windows with sidelights, louvered vent in main gable. C
760. 1523 Orange Street. Circa 1955. 1 story brick veneered building of contemporary style with gable roof, raised brick foundation, two bay facade, entrance under projecting gabled porch with decorative iron supports, metal frame picture window and 2/2 windows, louvered vent in main gable. NC
761. 1524 Orange Street. Circa 1950. 1 story wood frame building of contemporary style with gable roof, raised brick foundation, three bay facade, entrance inset, infill east portion of facade and bay window added west elevation, metal frame windows. NC
762. 1550 Orange Street. Circa 1965. 1 story concrete block duplex with side gable roof, concrete foundation, four bay facade, entrances under projecting eave of roofline, metal frame 2/2 windows. NC
763. 1551 Orange Street. Circa 1950. 1 story wood frame building of contemporary style with hip roof, concrete foundation, two bay facade, entrance under recessed porch with decorative iron supports, metal frame picture window with sidelights, carport added east elevation. NC
764. 1553 Orange Street. Circa 1930. 1 story wood frame bungalow with gable roof, raised brick foundation, three bay facade, entrance under projecting gabled porch supported by posts, paired and single metal frame 3/1 windows, louvered vent in porch gable. C
765. 1554 Orange Street. Circa 1970. 1 story wood frame building of no particular style with flat roof, concrete foundation, 1 bay facade, entrance at attached carport east elevation, wood frame 6/6 windows. NC
766. 1556 Orange Street. Circa 1960. 1 story wood frame Minimal Traditional with side gable roof, concrete foundation, three bay facade, entrance under projecting gable porch supported by posts, metal frame 2/2 windows with burglar bars. C
767. 1557 Orange Street. Circa 1990. 1 story wood frame building of contemporary style with hip roof, concrete foundation, three bay facade, entrance under recessed corner porch supported by posts, metal frame 9/6 windows, projecting hipped bay. NC

768. 1558 Orange Street. Circa 1930. 1 story wood frame bungalow with gable roof, raised brick foundation, three bay facade, entrance under recessed porch supported by square classical columns, paired and single wood frame 3/1 windows, louvered vent in gable, exposed rafters. C
769. 1559 Orange Street. Circa 1940. 1 story wood frame Minimal Traditional with side gable roof, raised brick foundation, three bay facade, entrance under projecting gabled porch supported by posts, porch screened, wood frame 6/6 windows, carport added east elevation, exposed rafters. NC
770. 1560 Orange Street. Circa 1940. 1 story wood frame Minimal Traditional with side gable roof, raised brick foundation, three bay facade, entrance at screened projecting gabled porch supported by posts, wood frame 3/1 windows, exposed rafters. C
771. 1561 Orange Street. Circa 1930. 1 story wood frame building of contemporary style with hip roof, raised brick foundation, two bay facade, entrance at recessed corner porch with decorative iron support, paired and single metal frame 2/2 windows. C
772. 1562 Orange Street. Circa 1950. 1 story asbestos sided Minimal Traditional with side gable roof, raised brick foundation, three bay facade, entrance under projecting shed roofed porch supported by turned posts, wood frame 2/2 windows, side chimney. C
773. 1563 Orange Street. Building of indeterminate age or design damaged by fire. NC
774. 1564 Orange Street. Circa 1955. 1 story wood frame building of contemporary style with gable roof, raise brick foundation, three bay facade, entrance under recessed porch with decorative iron supports, windows and entrance covered, perma-stone applied to portion of facade. NC
775. 1567 Orange Street. Circa 1945. 1 story wood frame Minimal Traditional with side gable roof, raised brick foundation, four bay facade, entrance under projecting gabled porch supported by posts on brick piers, metal frame 6/6 windows. C
776. 1568 Orange Street. Circa 1910. 1 story wood frame shotgun with gable roof, raised brick foundation, characteristic two bay facade, entrance under recessed porch supported by posts with brackets, metal frame 1/1 windows, louvered vent in gable, exposed rafters. C
777. 1569 Orange Street. Circa 1940. 1 story wood frame Minimal Traditional with gable roof, raised brick foundation, three bay facade, entrance under recessed porch with decorative iron supports, metal frame paired 2/2 windows, louvered vent in gable. C
778. 1570 Orange Street. Circa 1950. 1 story wood frame building of no particular style with gable roof, raised brick foundation, three bay facade, entrance in western most bay boarded with plywood, wood frame windows boarded, louvered vent in gable, paneling used as siding. NC
779. 1571 Orange Street. Circa 1910. 1 story wood frame cottage with side gable roof, raised brick foundation, four bay facade, entrance with transom under recessed porch supported by posts and facing gable above, added entrance boarded, windows boarded, louvered vent in gable. NC
780. 1572 Orange Street. Circa 1900. 1 story wood frame shotgun with gable roof, raised brick foundation, two bay facade, entrance under recessed porch supported by square classical columns, windows boarded, addition with two bays and shed roof added to east elevation, louvered vent in gable. NC [Photo #23]

781. 1573 Orange Street. Circa 1935. 1 story wood frame Minimal Traditional with side gable roof, raised brick foundation, three bay facade, entrance under shed roofed porch supported by posts, metal frame 1/1 windows. C
782. 1575 Orange Street. Circa 1940. 1 story wood frame Minimal Traditional with side gable roof, raised brick foundation, three bay facade, entrance under projecting gable supported by posts over stoop, windows and doors boarded, gable rises above apex of roofline. C

Partridge Street

783. 1104 Partridge Street. Circa 1970. 1 story concrete block duplex with gable roof, concrete slab foundation, four bay facade, two central entrances and windows covered with plywood in outer bays. NC
784. 1120 Partridge Street. Circa 1975. 1 story wood frame building of contemporary style with hip roof, concrete foundation, four bay facade, entrance at projecting gabled bay, metal frame picture window and plate glass windows, brick veneer up to window sills, interior chimney, carport added along southern portion of facade. NC
785. 1122 Partridge Street. Circa 1925. 1 story wood frame bungalow with gable on hip roof, raised brick foundation, three bay facade, entrance under attached gabled porch with decorative iron supports on brick piers, metal frame 2/2 windows and 6/6 windows, louvered vent in porch gable, exposed rafters. C
786. 1124 Partridge Street. Circa 1930. 1 story wood frame building of contemporary style with hip roof, raised brick foundation, three bay facade, entrance under gable supported by posts over stoop, paired and single metal frame 1/1 windows. C
787. 1150 Partridge Street. Circa 1935. 1 story wood frame Minimal Traditional with side gable roof, raised brick foundation, three bay facade, entrance under projecting gabled porch supported by posts, paired metal frame 1/1 windows, exposed rafters, louvered vent in porch gable. C
788. 1152 Partridge Street. Circa 1960. 1 story wood frame building of contemporary style with gable roof, raised concrete foundation, three bay facade, entrance under attached gable with iron supports over stoop, metal frame 1/1 windows and picture window with awnings, attached carport north elevation, louvered vent in main gable. NC
789. 1154 Partridge Street. Circa 1965. 1 story wood frame and brick veneer building of contemporary style with hip roof, raised brick foundation, two bay facade, entrance under projecting hip with decorative iron supports over stoop, metal frame picture window with 1/1 sidelights. NC
790. 1204 Partridge Street. Circa 1970. 1 story brick veneer building of contemporary style with side gable roof, concrete foundation, four bay facade, entrance at recessed corner porch with decorative iron support, metal frame casement windows, interior chimney. NC
791. 1250 Partridge Street. Circa 1930. 1 story asbestos sided building of contemporary style with hip roof, raised brick foundation, three bay facade, entrance under recessed porch supported by posts, metal frame picture window and 1/1 window. C
792. 1252 Partridge Street. Circa 1965. 1 story brick veneer building of contemporary style with hip roof, concrete slab foundation, three bay facade, entrance under projecting hip roof with decorative iron supports over stoop, metal frame picture window and 1/1 window. NC

793. 1254 Partridge Street. Circa 1965. 1 story brick veneer building of contemporary style with hip roof, concrete foundation, three bay facade, central entrance, metal frame windows. NC
794. 1256 Partridge Street. Circa 1940. 1 story wood frame building of contemporary style with gable roof, raised brick foundation, two bay facade, entrance at screened projecting gabled porch, wood frame windows, louvered vent in porch gable. C
795. 1260 Partridge Street. Circa 1945. 1 story wood frame building of contemporary style with gable roof, raised brick foundation, three bay facade, entrance under projecting gabled porch with decorative iron supports, paired and single metal frame 6/6 windows, louvered vents in gables. C

Plover Street

796. 1504 Plover Street. Circa 1910. 1 story wood frame cottage with hip roof, raised brick foundation, three bay facade, entrance with classical surround under recessed porch supported by posts, metal frame 6/6 windows in bay window, bay window later alteration. NC
797. 1505 Plover Street. Circa 1965. 1 story wood frame building of contemporary style with gable roof, concrete foundation, three bay facade, entrance in westernmost bay, metal frame awning windows. NC
798. 1508 Plover Street. Circa 1965. 1 story brick veneer building of contemporary style with hip roof, concrete foundation, three bay facade, entrance under projecting hipped porch supported by brick columns, porch screened, metal frame windows, awnings. NC
799. 1509 Plover Street. Circa 1935. 1 story wood frame bungalow with gable roof, raised brick foundation, three bay facade, entrance under projecting gabled porch supported by columns on brick piers, metal frame windows with burglar bars and awnings, louvered vents in gables, side chimney, exposed rafters. C
800. 1510 Plover Street. Circa 1940. 1 story wood frame building of contemporary style with gable roof, raised brick foundation, two bay facade, entrance at infilled recessed corner porch supported by square columns, metal frame multi-pane picture window, awnings over porch and entrance, louvered vent in gable, attached carport east elevation. NC
801. 1511 Plover Street. Circa 1930. 1 story wood frame bungalow with side gable roof, raised brick foundation, two bay facade, entrance under recessed corner porch supported by short columns on brick piers, wood frame 6/6 windows and casement windows, intersecting gable rises above apex of main roof. C
802. 1513 Plover Street. Circa 1940. 1 story wood frame Minimal Traditional with side gable roof, raised brick foundation, three bay facade, entrance under projecting gable with decorative iron supports over stoop, metal frame single and paired 2/2 windows. C
803. 1514 Plover Street. Circa 1955. 1 story wood frame Minimal Traditional with gable roof, raised brick foundation, three bay facade, entrance under projecting gabled porch supported by posts, metal frame 1/1 windows, louvered vent in gable. C
804. 1515 Plover Street. Circa 1920. 1 story wood frame shotgun with gable roof, raised brick foundation, characteristic two bay facade with entrance under projecting gable over stoop, decorative iron supports, metal frame 2/2 window. C
805. 1517 Plover Street. Circa 1945. 1 story wood frame building of contemporary style with gable roof, raised brick foundation, three bay facade, entrance under projecting gabled porch supported by posts, wood frame single and paired 1/1 windows. C

806. 1518 Plover Street. Circa 1950. 1 story brick veneer Minimal Traditional with side gable roof, raised brick foundation, three bay facade, entrance under projecting gabled porch supported by posts on brick knee wall, porch screened, metal frame paired 2/2 windows, brick veneer added at later date. NC
807. 1519 Plover Street. Circa 1940. 1 story wood frame building of contemporary style with gable roof, raised brick foundation, three bay facade, entrance at infilled gabled porch, metal frame awning windows and 1/1 windows, louvered vent in smaller gable, addition added west elevation, exposed rafters. NC
808. 1521 Plover Street. Circa 1940. 1 story wood frame Minimal Traditional with side gable roof, raised brick foundation, two bay facade, entrance at infilled projecting gabled porch, porch infilled with lattice and clapboard knee wall, metal frame 1/1 window, exposed rafters, attached carport east elevation. NC
809. 1550 Plover Street. Circa 1965. 1 story structural tile commercial building with stepped gabled roof, concrete block foundation, three bay facade, entrance under attached gable supported by posts, paired and single metal frame awning windows. NC
810. 1551 Plover Street. Circa 1940. 1 story wood frame Minimal Traditional with side gable roof, raised brick foundation, three bay facade, entrance under projecting infilled gabled porch supported by posts, wood frame 3/1 windows. C
811. 1552 Plover Street. Circa 1965. 1 story brick veneer building of contemporary style with hip roof, raised concrete foundation, three bay facade, entrance under projecting gabled porch with decorative iron supports, metal frame 2/2 window and picture window, circular louvered vent in porch gable. NC
812. 1555 Plover Street. Circa 1940. 1 story Masonite sided building of contemporary style with gable roof, raised brick foundation, three bay facade, entrance under projecting gabled porch with decorative iron supports, metal frame picture window, awnings over window and across porch, brick veneered to window sill, louvered vents in gables. NC
813. 1556 Plover Street. Circa 1935. 1 story wood frame bungalow with side gable roof, raised brick foundation, three bay facade, entrance under projecting gabled porch supported by brick columns, brick knee wall, paired and single metal frame 6/6 windows, louvered vent in gable. C
814. 1557 Plover Street. Circa 1955. 1 story brick veneer Minimal Traditional with gable roof, raised brick foundation, three bay facade, entrance under projecting gabled porch with decorative iron supports on brick piers, brick knee wall, paired and single metal frame 6/6 windows. C
815. 1558 Plover Street. Circa 1950. 1 story structural tile shotgun with gable roof, raised brick foundation, characteristic two bay facade with entrance under projecting gabled porch supported by posts, wood frame 3/1 windows, exposed rafters. C
816. 1560 Plover Street. Circa 1955. 1 story wood frame building of contemporary style with gable roof, raised brick foundation, three bay facade, entrance under attached shed roofed porch supported by iron posts, metal frame 6/6 window and picture window, porch wraps around facade and forms carport along east elevation. NC
817. 1561 Plover Street. Circa 1965. 1 story brick veneer building of contemporary style with hip roof, raised concrete foundation, three bay facade, entrance under recessed corner porch with decorative iron supports, metal frame casement windows and picture window with sidelights. NC
818. 1562 Plover Street. Circa 1950. 1 story wood frame building of no particular style with side gable roof, raised brick foundation, three bay facade, entrance

under projecting gabled porch supported by posts, metal frame 2/2 windows, attached gable bay along facade later addition. NC

819. 1563 Plover Street. Circa 1940. 1 story wood frame Minimal Traditional with side gable roof, raised brick foundation, three bay facade, entrance under projecting gable supported by posts over stoop, metal frame 6/6 windows, intersecting rear gable rises above apex of main roof, exposed rafters. C
820. 1564 Plover Street. Circa 1950. 1 story wood frame building of contemporary style with gable roof, raised brick foundation, three bay facade, entrance under attached gabled porch supported by posts at corners and posts on brick piers between wood frame 6/6 windows. C
821. 1565 Plover Street. Circa 1935. 1 story wood frame bungalow with gable roof, raised brick foundation, three bay facade, entrance under projecting gabled porch supported by brick columns, brick knee wall, metal frame 2/2 windows, louvered vents in gables covered. C
822. 1566 Plover Street. Circa 1930. 1 story wood frame building of contemporary style with hip roof, raised brick foundation, two bay facade, entrance at infilled hipped roofed porch, metal frame 6/6 windows. NC
823. 1567 Plover Street. Circa 1935. 1 story structural tile Minimal Traditional with gable roof, raised brick foundation, two bay facade, entrance at screened projecting gabled porch, metal frame windows, awnings across porch and windows, louvered vent in gable. C.
824. 1568 Plover Street. Circa 1965. 1 story brick veneer building of contemporary style with hip roof, raised concrete foundation, two bay facade, entrance at projecting hipped porch, porch infilled with metal frame awning windows, metal frame 6/6 window in remaining bay, carport supported by brick columns at west elevation. NC
825. 1569 Plover Street. Circa 1965. 1 story brick veneer building of contemporary style with gable roof, raised brick foundation, two bay facade, entrance along east elevation, metal frame 6/6 window and picture window with sidelights. NC
826. 1570 Plover Street. Circa 1940. 1 story wood frame Minimal Traditional with side gable roof, raised brick foundation, two bay facade, entrance at addition along facade, metal frame slide-by windows. NC
827. 1571 Plover Street. Circa 1940. 1 story wood frame building of contemporary style with spraddle roof, raised brick foundation, three bay facade, entrance under recessed corner porch supported by posts, windows and entrance boarded, building damaged by fire. NC
828. 1575 Plover Street. Circa 1940. 1 story wood frame Minimal Traditional with side gable roof, raised brick foundation, two bay facade, entrance at infilled projecting gabled porch, paired wood frame 3/1 windows. NC

Quail Street

829. 1252 Quail Street. Circa 1950. 1 story wood frame building of contemporary style with gable roof, raised brick foundation, three bay facade, entrance at recessed corner porch with missing support, wood frame windows with awnings, brick veneer applied up to window sills, louvered vent in gable. NC
830. 1255 Quail Street. Circa 1970. 1 story brick veneer building of contemporary style with side gable roof, concrete foundation, three bay facade, metal frame windows, entrance under projecting gable with decorative iron supports. NC

Quita Street

No addresses, however it lies within the central area of the historic district.

Reverend AT Days Street

831. 1255 Reverend AT Days Street. Circa 1960. 1 story brick ecclesiastical building with gable roof, concrete foundation, 1 bay facade, entrance centered with plate glass doors, circular window above entrance, two story brick addition added at north side with flat roof, concrete foundation, centered double door entrance, metal frame windows. NC
832. 1257 Reverend AT Days Street. Circa 1925. 1 story asbestos sided bungalow with gable on hip roof, raised brick foundation, three bay facade, entrance under projecting gabled porch supported by post, wood frame paired 3/1 window and picture window, louvered vent in gable, exposed rafters. C

Reverend RT Thomas Drive

833. 1402 Reverend RT Thomas Drive. Circa 1940. 1 story wood frame Minimal Traditional with side gable roof, raised brick foundation, three bay facade, entrance under projecting gabled porch supported by posts, French doors and wood frame paired 6/6 windows with awning, louvered vent in secondary facing gable, exposed rafters. C

Rotterdam Street

834. 1002 Rotterdam Street. Circa 1970. 1 story brick veneer building of contemporary style with hip roof, concrete foundation, three bay facade, entrance under projecting hipped porch with decorative iron supports, metal frame 1/1 windows. NC
835. 1003 Rotterdam Street. Circa 1960. 1 story brick veneer institutional building with side gable roof, raised concrete foundation, nine bay facade, entrance at intersecting gabled bay, paired metal frame 6/6 windows. C
836. 1004 Rotterdam Street. Circa 1925. 1 story wood frame bungalow with gable roof, raised brick foundation, two bay facade, entrance at infilled hipped porch with posts on brick piers, metal frame windows. NC
837. 1006 Rotterdam Street. Circa 1910. 1 story wood frame shotgun with gable roof, raised brick foundation, characteristic two bay facade with entrance under recessed porch supported by post, flanking wood frame 1/1 window. C
838. 1010 Rotterdam Street. Circa 1940. 1 story stucco Minimal Traditional with side gable roof, raised brick foundation, two bay facade, entrance under projecting gable with decorative iron supports over stoop, metal frame multi-pane picture window, louvered vent in larger facing gable. C
839. 1051 Rotterdam Street. Circa 1905. 1 story wood frame cottage with gable roof, raised brick foundation, three bay facade, entrance under recessed gable porch supported by posts, wood frame 6/6 windows and 2/2 windows, exposed rafters, rear ell. C
840. 1053 Rotterdam Street. Circa 1945. 1 story asbestos sided building of no particular style with gable roof, raised brick foundation, two bay facade, entrance under attached gable over stoop, metal frame 6/6 window, louvered vent in gable, exposed rafters. C
841. 1055 Rotterdam Street. Circa 1950. 1 story wood frame building of contemporary style with gable roof, raised brick foundation, two bay facade, entrance at recessed corner porch with decorative iron support, wood frame picture window with sidelights and paired 6/6 windows, louvered vent in gable, exposed rafters. C

842. 1056 Rotterdam Street. Circa 1925. 1 story wood frame bungalow with hip roof, raised brick foundation, two bay facade, entrance in screened corner porch, wood frame picture window with burglar bars. C
843. 1057 Rotterdam Street. Circa 1950. 1 story brick veneered building of contemporary style with gable roof, raised brick foundation, three bay facade, entrance at infilled gabled porch, metal frame picture window with sidelights and 2/2 windows. NC
844. 1058 Rotterdam Street. Circa 1955. 1 story wood frame building of contemporary style with gable roof, raised brick foundation, two bay facade, entrance along north elevation, infilled gabled porch, metal frame 2/2 windows and 1/1 windows, louvered vent in gable. NC
845. 1060 Rotterdam Street. Circa 1935. 1 story wood frame building of contemporary style with gable roof, raised brick foundation, two bay facade, entrance at screened projecting gabled porch, metal frame 2/2 window, louvered vent in smaller gable, exposed rafters and purlins. C
846. 1062 Rotterdam Street. Circa 1970. 1 story brick veneer building of contemporary style with gable roof, concrete foundation, three bay facade, entrance under projecting gabled porch with decorative iron supports, metal frame paired 8/8 windows and 2/2 window. NC
847. 1066 Rotterdam Street. Circa 1960. 1 story concrete block commercial building with gable roof, concrete foundation, three bay facade, double door entrance boarded, paired storefront windows boarded, louvered vent in gable. NC
848. 1100 Rotterdam Street. Circa 1930. 1 story wood frame bungalow with gable roof, raised brick foundation, three bay facade, entrance under projecting gabled porch supported by posts on brick piers, paired wood frame 3/1 windows, louvered vent in gables. C
849. 1102 Rotterdam Street. Circa 1940. 1 story wood frame building of contemporary style with gable roof, raised brick foundation, two bay facade, entrance at recessed corner porch, window boarded. NC
850. 1107 Rotterdam Street. Circa 1965. 1 story brick veneer building of contemporary style with hip roof, concrete foundation, three bay facade, entrance under projecting hipped porch with decorative iron supports, metal frame single and paired 6/6 windows. NC
851. 1108 Rotterdam Street. Circa 1990. 1 story brick veneer building of contemporary style with hip roof, concrete foundation, six bay facade, entrance slightly off center, metal frame 9/6 windows. NC
852. 1109 Rotterdam Street. Circa 1955. 1 story wood frame building of contemporary style with gable roof, raised brick foundation, three bay facade, entrance under recessed porch supported by posts, paired and single metal frame 1/1 windows, three light window in gable with flanking louvered vents. C
853. 1113 Rotterdam Street. Circa 1915. 1 story wood frame cottage with gable on hip roof, raised brick foundation, three bay facade, entrance under recessed porch supported by posts, metal frame 2/2 windows and wood frame picture window with sidelights, awning across porch, louvered vent in gable. C
854. 1115 Rotterdam Street. Circa 1930. 1 story wood frame bungalow with gable roof, raised brick foundation, two bay facade, entrance under projecting gabled porch, porch infilled, paired wood frame 3/1 windows and metal frame picture window with sidelights, louvered vent in main gable. NC

855. 1117 Rotterdam Street. Circa 1950. 1 story wood frame Minimal Traditional with side gable roof, raised brick foundation, two bay facade, entrance under recessed porch with decorative iron supports, paired metal frame 6/6 windows and picture window with 4/4 sidelights. C
856. 1150 Rotterdam Street. Circa 1960. 1 story concrete block building of contemporary style with hip roof, concrete foundation, four bay facade, entrance under projecting hipped porch with decorative iron supports, metal frame paired 1/1 windows, carport south elevation. C
857. 1151 Rotterdam Street. Circa 1925. 2 story wood frame Craftsman with gable roof, raised brick foundation, two bay facade, entrance at recessed corner porch with decorative iron supports, metal frame paired and tripled 6/6 windows, exposed rafters, louvered vent in gable, 2 story rear addition added at later date. NC
[Photo #12]
858. 1156 Rotterdam Street. Circa 1945. 1 story wood frame Minimal Traditional with side gable roof, raised brick foundation, three bay facade, entrance under projecting eaves of roofline supported by posts over stoop, wood frame 3/1 windows boarded, addition added south elevation. NC
859. 1159 Rotterdam Street. Circa 1965. 1 story brick veneer building of contemporary style with hip roof, concrete foundation, four bay facade, entrance under projecting gable supported by posts over stoop, metal frame windows with burglar bars. NC
860. 1200 Rotterdam Street. Circa 1985. 1 story brick veneer building of contemporary style with gable roof, concrete slab foundation, entrance under recessed porch supported by brick columns, brick knee wall, windows covered. NC
861. 1203 Rotterdam Street. Circa 1945. 1 story Masonite sided Minimal Traditional with side gable roof, raised brick foundation, three bay facade, entrance under projecting gable supported by turned posts over stoop, metal frame single and paired 6/6 windows, carport added north elevation. NC
862. 1205 Rotterdam Street. Circa 1940. 1 story wood frame Minimal Traditional with side gable roof, raised brick foundation, three bay facade, entrance under projecting gable supported by posts over stoop, windows boarded, exposed rafters. C
863. 1206 Rotterdam Street. Circa 1975. 1 story brick veneer building of contemporary style with side gable roof, concrete foundation, five bay facade, entrance under projecting eave of roofline supported by posts, metal frame 6/6 windows. NC
864. 1207 Rotterdam Street. Circa 1950. 1 story wood frame Minimal Traditional with gable roof, raised brick foundation, four bay facade, entrance in infilled gabled porch, metal frame 6/6 windows and awning windows, louvered vent in infilled gable. NC
865. 1210 Rotterdam Street. Circa 1975. 1 story brick veneer building of contemporary style with side gable roof, concrete foundation, two bay facade, entrance under recessed porch with decorative iron supports, metal frame multi-pane picture window, gabled dormers with 2/2 windows. NC
866. 1212 Rotterdam Street. Circa 1940. 1 story wood frame Minimal Traditional with side gable roof, raised brick foundation, three bay facade, entrance with transom under recessed porch supported by posts, metal frame 2/2 windows, exposed rafters. C

Sligo Street

867. 1610 Sligo Street. Circa 1970. 1 story brick veneer Ranch style house with side gable roof, concrete foundation, four bay facade, entrance at slightly

projecting central bay, metal frame picture windows and awning windows, carport east elevation. NC [Photo #20]

868. 1611 Sligo Street. Circa 1940. 1 story wood frame duplex with gable roof, raised brick foundation, four bay facade, entrances under recessed porch supported by posts on brick piers, metal frame 2/2 windows, louvered vent in gable, exposed rafters. C
869. 1613 Sligo Street. Circa 1940. 1 story wood frame duplex with gable roof, raise brick foundation, five bay facade, entrances under recessed porch supported by posts, windows boarded, louvered vent in gable, addition added west elevation. NC
870. 1652 Sligo Street. Circa 1960. 1 story concrete block building of contemporary style with hip roof, concrete foundation, three bay facade, entrance under recessed porch with decorative iron supports, metal frame picture window with sidelights and awning window, carport added east elevation. NC
871. 1653 Sligo Street. Circa 1975. 1 story brick veneer building of contemporary style with side gable roof, concrete foundation, five bay facade, entrance under projecting gable with decorative iron supports, metal frame picture window and 2/2 windows. NC
872. 1654 Sligo Street. Circa 1965. 1 story brick veneer building of contemporary style with hip roof, concrete foundation, three bay facade, entrance under projecting hip porch with decorative iron supports, metal frame picture window and slide-by window. NC
873. 1657 Sligo Street. Circa 1980. 1 story brick veneer building of contemporary style with gable roof, concrete foundation, three bay facade, entrance under pent roof supported by post, paired and single metal frame 1/1 windows, side gable roof intersects main roof and extends to form carport supported by posts. NC
874. 1700 Sligo Street. Circa 1945. 1 story wood frame duplex with side gable roof, raised brick foundation, six bay facade, entrances under projecting gables with decorative iron supports, wood frame paired and single 6/6 windows, brick veneer up to window sills. C
875. 1704 Sligo Street. Circa 1955. 1 story wood frame building of contemporary style with gable roof, concrete foundation, three bay facade, entrance under recessed porch supported by square columns, metal frame multi-pane picture window and paired 6/6 window. C
876. 1705 Sligo Street. Circa 1930. 1 story wood frame duplex with gable roof, raised brick foundation, four bay facade, entrances under recessed porch supported by posts, wood frame 3/1 windows, louvered vents in gable, knee braces, exposed rafters. C
877. 1756 Sligo Street. Circa 1970. 1 story brick veneer building of contemporary style with hip roof, concrete foundation, three bay facade, entrance under projecting hip roof supported by post over stoop, metal frame 1/1 windows. NC

Sunset Avenue

878. 957 Sunset Avenue. Circa 1945. 1 story wood frame building of contemporary style with gable roof, raised brick foundation, two bay facade, entrance at screened porch, multi-pane metal frame picture window. C
879. 961 Sunset Avenue. Circa 1930. 1 story asbestos sided bungalow with gable roof, raised brick foundation, two bay facade, entrance under projecting gable porch supported by brick columns, wood frame windows boarded, louvered vents in gables, exposed rafters. C

880. 962 Sunset Avenue. Circa 1930. 1 story wood frame bungalow with gable roof, raised brick foundation, two bay facade, entrance under screened recessed porch supported by battered columns on brick piers, clapboard knee wall, louvered vent in gable, exposed rafters. C
881. 964 Sunset Avenue. Circa 1950. 1 story wood frame building of contemporary style with gable roof, concrete foundation, three bay facade, entrance under projecting gabled porch supported by posts, metal frame 6/6 windows, louvered vent in main gable covered. C
882. 969 Sunset Avenue. Circa 1915. 1 story wood frame cottage with hip roof, raised brick foundation, three bay facade, entrance under attached shed roofed porch supported by posts, metal frame 6/6 windows, alterations at either end of facade. NC

Tisdale Street

883. 400 Tisdale Street. Circa 1955. 1 story brick veneer building of contemporary style with gable roof, concrete foundation, three bay facade, entrance under projecting gable porch with decorative iron supports, metal frame single and paired 2/2 windows, carport added south elevation. NC
884. 402 Tisdale Street. Circa 1925. 1 story wood frame bungalow with hip roof, raised brick foundation, three bay facade, entrance at screened porch supported by paneled columns, paired metal frame 6/6 window. C
885. 405 Tisdale Street. Circa 1945. 1 story asbestos sided building of contemporary style with gable roof, raised brick foundation, two bay facade, entrance at south elevation with cantilevered door hood, porch extends along north elevation, metal frame 2/2 windows, rear addition at south elevation, louvered vent in gable. NC
886. 451 Tisdale Street. Circa 1970. 1 story brick veneer building of contemporary style with gable roof, concrete foundation, three bay facade, entrance under recessed corner porch with decorative iron support, metal frame multi-pane picture window and paired awning windows. NC
887. 453 Tisdale Street. Circa 1920. 1 story wood frame bungalow with hip roof, raised brick foundation, three bay facade, entrance with transom under recessed porch supported by battered columns on brick piers, wood frame paired and single 1/1 windows, centered facing gable, exposed rafters. C
888. 455 Tisdale Street. Circa 1945. 1 story vinyl sided building of contemporary style with gable roof, raised brick foundation, three bay facade, entrance at screened attached gable porch supported by posts, metal frame 2/2 windows, louvered vent in porch gable. C
889. 456 Tisdale Street. Circa 1905. 1 story wood frame shotgun with hip roof, raised brick foundation, characteristic two bay facade, entrance with transom under recessed porch supported by posts, metal frame 2/2 windows. C
890. 457 Tisdale Street. Circa 1955. 1 story brick veneer building of contemporary style with side gable roof, raised brick foundation, four bay facade, entrance at infilled projecting gabled porch, metal frame 2/2 windows, interior chimney. NC
891. 458 Tisdale Street. Circa 1905. 1 story wood frame shotgun with gable roof, raised brick foundation, two bay facade, entrance with transom under recessed porch with decorative iron supports, metal frame 6/6 window, ell added at rear. NC
892. 459 Tisdale Street. Circa 1910. 1 story wood frame cottage with hip roof, raised brick foundation, two bay facade, entrance under recessed porch with

decorative iron supports, metal frame 1/1 windows, exposed rafters, ell and carport added south elevation, entrance and paired 6/6 windows in ell. NC

893. 505 Tisdale Street. Circa 1925. 1 story stucco bungalow with side gable roof, raised brick foundation, three bay facade, entrance with transom and sidelights under recessed porch supported by stuccoed columns, facing gable in southernmost bay, paired wood frame 1/1 windows, side gable roof extends to form porte-cochere at north elevation. C
894. 507 Tisdale Street. Circa 1945. 1 story wood frame Minimal Traditional with side gable roof, raised brick foundation, three bay facade, entrance at recessed corner porch in projecting gabled bay supported by post, semi-octagonal bay window added northernmost bay, carport added south elevation. NC
895. 509 Tisdale Street. Circa 1930. 1 story wood frame bungalow with gable roof, raised brick foundation, three bay facade, entrance under projecting gabled porch supported by posts on brick piers, wood frame paired and single 3/1 windows, louvered vent in main gable, exposed rafters. C
896. 551 Tisdale Street. Circa 1955. 1 story brick veneer building of contemporary style with gable roof, raised brick foundation, two bay facade, entrance under recessed corner porch with decorative iron supports, metal frame 6/6 windows and picture window with sidelights, louvered vent in gable, additions at rear. NC
897. 553 Tisdale Street. Circa 1940. 1 story wood frame building of contemporary style with gable roof, raised brick foundation, three bay facade, entrance at infilled projecting gabled porch, wood frame picture window and paired 1/1 windows, awnings across projecting gabled bay, louvered vent covered. NC
898. 555 Tisdale Street. Circa 1965. 1 story brick veneer building of contemporary style with gable roof, concrete foundation, three bay facade, entrance under projecting gable with decorative iron supports over stoop, metal frame 6/6 windows and picture window. NC
899. 556 Tisdale Street. Circa 1955. 1 story wood frame building of contemporary style with gable roof, concrete foundation, three bay facade, entrance under attached gabled porch supported by classical columns, multi-pane metal frame picture window and 1/1 window. C

Tuttle Avenue

900. 503 Tuttle Avenue. Circa 1945. 1 story wood frame Minimal Traditional with side gable roof, raised brick foundation, two bay facade, entrance under recessed corner porch supported by posts, gable above porch, wood frame picture window, awnings, side chimney. C
901. 504 Tuttle Avenue. Circa 1930. 1 story wood frame bungalow with gable roof, raised brick foundation, three bay facade, entrance under recessed porch supported by brick columns, brick knee wall, paired wood frame 1/1 windows, louvered vent in gable, exposed rafters. C
902. 505 Tuttle Avenue. Circa 1930. 1 story wood frame bungalow with gable roof, raised brick foundation, two bay facade, entrance at screened projecting gabled porch supported by brick columns, paired wood frame 3/1 windows. C
903. 507 Tuttle Avenue. Circa 1940. 1 story wood frame Minimal Traditional with side gable roof, raised brick foundation, three bay facade, entrance under projecting gable with decorative iron supports over stoop, paired and tripled metal frame 6/6 windows and 1/1 windows, awnings over entrance and windows. C
904. 508 Tuttle Avenue. Circa 1930. 1 story wood frame bungalow with jerkin head roof, raised brick foundation, two bay facade, entrance at infilled projecting

- gabled porch supported by battered columns on brick piers, metal frame 6/6 windows, paired 4 pane light in porch gable, knee braces, exposed rafters. NC
905. 509 Tuttle Avenue. Circa 1930. 1 story wood frame bungalow with gable roof, raised brick foundation, three bay facade, entrance under projecting gabled porch that has been screened, porch supported by posts, paired wood frame 3/1 windows, awnings over windows and porch, louvered vent in porch gable, exposed rafters. C
906. 510 Tuttle Avenue. Circa 1915. 1 story wood frame Four Square with hip roof, raised brick foundation, two bay facade, entrance with transom and sidelights under recessed porch supported by paired columns on brick piers, wood frame 1/1 window with sidelights, hip roofed dormer with paired 6 pane lights. C [Photo #13]
907. 512 Tuttle Avenue. Circa 1925. 1 1/2 story wood frame Craftsman with side gable roof, raised brick foundation, three bay facade, entrance with transom and sidelights under recessed porch supported by battered columns on brick piers, Craftsman windows, gabled dormer with Craftsman windows, side chimney, exposed rafters. C [Photo #11]
908. 550 Tuttle Avenue. Circa 1940. 1 story asbestos sided Minimal Traditional with side gable roof, raised brick foundation, three bay facade, entrance under recessed porch supported by posts, porch abuts facing gabled bay, wood frame 8/8 windows. C
909. 554 Tuttle Avenue. Circa 1930. 1 story wood frame bungalow with side gable roof, raised brick foundation, four bay facade, entrance in infilled gabled porch, paired metal frame 1/1 windows, exposed rafters, interior chimney, awning across gabled bay. NC
910. 556 Tuttle Avenue. Circa 1930. 1 story wood frame bungalow with side gable roof, raised brick foundation, two bay facade, entrance at infilled porch with brick columns still visible, wood frame 3/1 windows, interior chimney. NC
911. 558 Tuttle Avenue. Circa 1915. 1 story wood frame cottage with hip roof, raised brick foundation, three bay facade, entrance inset between infill to either side of original porch, metal frame paired 6/6 windows, gabled dormer with 6/6 window. NC
912. 559 Tuttle Avenue. Circa 1930. 1 story wood frame bungalow with side gable roof, raised brick foundation, three bay facade, entrance under recessed corner porch supported by battered post on brick pier, paired wood frame 6/1 windows, side chimney, louvered vent in intersecting gable. C
913. 561 Tuttle Avenue. Circa 1955. 1 story wood frame Minimal Traditional with side gable roof, raised brick foundation, five bay facade, entrance in southernmost bay with gable over entrance, metal frame 2/2 windows, addition south elevation, interior chimney. NC
914. 562 Tuttle Avenue. Circa 1940. 1 story wood frame Minimal Traditional with side gable roof, raised brick foundation, three bay facade, entrance under projecting gable supported by battered arch, metal frame 6/6 windows, recessed porch southern half of facade, supported by arches, larger facing gable with chimney at facade. C
915. 564 Tuttle Avenue. Circa 1930. 1 story perma-stone bungalow with gable roof, raised brick foundation, two bay facade, entrance under recessed gabled corner porch supported by post, paired wood frame 3/1 windows, louvered vent in main gable, exposed rafters, perma-stone applied at later date. NC
916. 565 Tuttle Avenue. Circa 1930. 1 story wood frame bungalow with gable roof, raised brick foundation, three bay facade, entrance under projecting gabled porch

supported by battered columns on brick piers, paired wood frame 3/1 windows, louvered vent in main gable, knee braces, exposed rafters. C

917. 600 Tuttle Avenue. Circa 1940. 1 story brick veneered building of contemporary style with gable roof, raised brick foundation, two bay facade, entrance at projecting gabled porch that has been infilled, wood frame 3/1 windows, side chimney. NC
918. 602 Tuttle Avenue. Circa 1930. 1 story wood frame bungalow with hip roof, raised brick foundation, two bay facade, entrance at screened projecting gabled porch supported by battered columns on brick piers, wood frame windows with awning, awning across porch, exposed rafters, braces in porch gable, interior chimney. C
919. 604 Tuttle Avenue. Circa 1945. 1 story asbestos sided Minimal Traditional with gable roof, raised brick foundation, three bay facade, entrance under projecting gabled porch supported by posts, windows and entrance boarded, louvered vents in peak of gables. C
920. 605 Tuttle Avenue. Circa 1960. 1 story brick veneer building of contemporary style with gable roof, concrete foundation, entrance recessed in northernmost bay, projecting gabled bay is a recent addition, metal frame 6/6 windows. NC
921. 606 Tuttle Avenue. Circa 1970. 1 story brick veneer building of contemporary style with hip roof, concrete foundation, two bay facade, entrance at recessed corner porch with decorative iron supports along south elevation, metal frame awning windows, projecting hipped carport south elevation supported by brick columns. NC
922. 608 Tuttle Avenue. Circa 1945. 1 story asbestos sided duplex with side gable roof, raised brick foundation, four bay facade, entrances under shed roofs with decorative iron supports at projecting gabled bay, paired and single wood frame 6/6 windows, louvered vent in projecting gabled bay. C
923. 609 Tuttle Avenue. Circa 1930. 1 story wood frame bungalow with gable roof, raised brick foundation, three bay facade, entrance at infilled projecting gable porch supported by brick columns, paired wood frame 3/1 windows and louvered windows at porch, awnings across windows and porch, louvered vents in gables, exposed rafters and braces in porch gable. C
924. 611 Tuttle Avenue. Circa 1940. 1 story wood frame building of contemporary style with gable roof, raised brick foundation, three bay facade, entrance at infilled recessed porch, brick knee wall still visible, metal frame paired and tripled 1/1 windows, louvered vent in gable. NC
925. 613 Tuttle Avenue. Circa 1940. 1 story wood frame building of contemporary style with gable roof, raised brick foundation, three bay facade, entrance under projecting gable porch supported by posts, paired metal frame 2/2 windows. C

Virginia Street

926. 1301 Virginia Street. Circa 1925. 1 story brick commercial building with flat roof with stepped gabled false front, concrete foundation, three bay facade, central double door entrance, metal frame storefront windows, transoms with glass block, awning across facade. C [Photo #35]
927. 1303 Virginia Street. Circa 1970. 1 story brick commercial building with flat roof, concrete slab foundation, three bay facade, windows and entrance boarded. NC
928. 1457 Virginia Street. Circa 1925. 1 story wood frame Craftsman with side gable roof, raise brick foundation, three bay facade, entrance under projecting gabled porch supported by battered columns on brick piers, porch is screened, paired metal frame 1/1 windows and 6/6 windows, side chimney, knee braces. C

929. 1459 Virginia Street. Circa 1930. 1 story wood frame duplex with gable roof, raised brick foundation, four bay facade, entrance under recessed porch supported by paired posts with clapboard knee wall, metal frame 1/1 windows, light in gable, knee braces, exposed rafters. C
930. 1551 Virginia Street. Circa 1890. 1 story wood frame cottage with gable on hip roof, raised brick foundation, four bay facade, entrance under recessed porch supported by turned posts, porch abuts semi-octagonal gabled bay, wood frame 2/2 windows, louvered vent in gables. C
931. 1553 Virginia Street. Circa 1935. 1 story wood frame bungalow with side gable roof, raised brick foundation, four bay facade, entrance under projecting gabled porch with decorative iron supports on brick piers, paired and single wood frame 3/1 windows, exposed rafters. C
932. 1555 Virginia Street. Circa 1940. 1 story wood frame building of contemporary style with gable roof, raised brick foundation, four bay facade, entrance under projecting gabled porch supported by posts, porch screened, metal frame 6/6 windows, side chimney. C
933. 1557 Virginia Street. Circa 1945. 1 story brick veneer Minimal Traditional with side gable roof, raised brick foundation, three bay facade, entrance at infilled projecting gable porch supported by brick columns, projecting bay window, metal frame 6/6 windows, awnings over windows, louvered vent in porch gable. NC
934. 1559 Virginia Street. Circa 1950. 1 story wood frame Minimal Traditional with side gable roof, raised brick foundation, three bay facade, entrance at projecting gable porch supported by posts, porch screened, paired metal frame 6/6 windows, exposed rafters, interior chimney. C
935. 1561 Virginia Street. Circa 1950. 1 story wood frame building of contemporary style with gable roof, raised brick foundation, two bay facade, entrance under attached shed roof with iron supports, shed roof wrap-around to form carport, metal frame 6/6 windows. NC
936. 1563 Virginia Street. Circa 1880. 2 story wood frame cottage with gable roof, raised brick foundation, two bay facade, entrance under pent roof supported by posts, attached pent roof abuts projecting gabled bay, metal frame 6/6 windows. C
937. 1565 Virginia Street. Circa 1910. 1 story brick veneered cottage with hip roof, raised brick foundation, four bay facade, entrance with transom at infilled porch, brick columns still visible, wood frame 6/6 windows, shed roof addition east elevation. NC
938. 1603 Virginia Street. Circa 1950. 1 story wood frame Minimal Traditional with side gable roof, raised brick foundation, four bay facade, entrance at infilled recessed corner porch with shed roof door hood, metal frame 6/6 windows and picture window. NC
939. 1605 Virginia Street. Circa 1950. 1 story wood frame Minimal Traditional with side gable roof, raised brick foundation, four bay facade, entrance under projecting gable supported by posts over stoop, metal frame 6/6 windows and picture window with sidelights, addition east elevation with metal frame 1/1 window. NC
940. 1607 Virginia Street. Circa 1910. 1 story wood frame cottage with hip roof, raised brick foundation, three bay facade, entrance under recessed porch supported by square posts, windows boarded. C
941. 1621 Virginia Street. Circa 1950. Ladd Peebles Stadium. Modern sports stadium with grass playing surface surrounded by open air seating and lighting for evening events, numerous additions made through the years to increase seating capacity including skyboxes. C [Photo #36]

942. 1653 Virginia Street. Circa 1930. 1 story brick veneer bungalow with gable roof, raised brick foundation, three bay facade, entrance under recessed porch supported by battered columns on brick piers, paired and single metal frame 1/1 windows, louvered vent covered, brick veneer applied at later date. NC
943. 1655 Virginia Street. Circa 1940. 1 story wood frame building of contemporary style with gable roof, raised brick foundation, three bay facade, entrance under projecting gabled porch supported by turned posts, metal frame 6/6 windows. C
944. 1657 Virginia Street. Circa 1920. 1 story wood frame cottage with hip roof, raised brick foundation, three bay facade, entrance under recessed porch supported by square posts, paired wood frame 2/2 windows. C
945. 1659 Virginia Street. Circa 1935. 1 story asbestos sided bungalow with side gable roof, raised brick foundation, three bay facade, entrance under recessed porch supported by battered column on brick pier, paired wood frame 6/6 windows, exposed rafters, side chimney. C
946. 1759 Virginia Street. Circa 1940. 1 story wood frame Minimal Traditional with side gable roof, raised brick foundation, three bay facade, entrance under projecting gabled porch supported by brick columns, paired wood frame 3/1 windows, gables over windows in outer bays, side chimney. C

Waterford Street

947. 1653 Waterford Street. Circa 1970. 1 story brick veneer building of contemporary style with side gable roof, concrete foundation, four bay facade, entrance under recessed gabled corner porch, metal frame paired 9/6 windows and 2/2 windows, carport east elevation. NC
948. 1654 Waterford Street. Circa 1945. 1 story wood frame building of contemporary style with gable roof, raised brick foundation, three bay facade, entrance under projecting gabled porch with decorative iron supports, metal frame 6/6 windows, carport added east elevation. C
949. 1656 Waterford Street. Circa 1945. 1 story wood frame Minimal Traditional with side gable roof, raised brick foundation, three bay facade, entrance under projecting eave of roofline with decorative iron supports, metal frame awning windows and picture window with sidelights, brick veneer to window sills. C
950. 1658 Waterford Street. Circa 1915. 1 story wood frame cottage with hip roof, raised brick foundation, three bay facade, entrance under recessed porch supported by square posts, paired metal frame 6/6 windows. C
951. 1700 Waterford Street. Circa 1960. 1 story brick veneer Minimal Traditional with hip roof, raised brick foundation, five bay facade, entrance under projecting gable porch supported by brick columns, metal frame Craftsman style windows, addition western portion of facade with metal frame picture window. NC
952. 1701 Waterford Street. Circa 1970. 1 story brick veneer building of contemporary style with gable roof, concrete foundation, four bay facade, entrance under recessed corner porch, metal frame awning and 2/2 windows. NC
953. 1704 Waterford Street. Circa 1940. 1 story asbestos sided Minimal Traditional with gable roof, raised brick foundation, three bay facade, entrance under projecting gabled porch with decorative iron supports, wood frame 3/1 windows and picture window. C
954. 1705 Waterford Street. Circa 1945. 1 story wood frame duplex with gable roof, raised brick foundation, three bay facade, entrances under recessed porch supported by posts, easternmost entrance now infilled, metal frame 2/2 windows, brick veneer applied up to window sills, louvered vent in gable. NC

955. 1706 Waterford Street. Circa 1945. 1 story wood frame Minimal Traditional with side gable roof, raised brick foundation, two bay facade, entrance at infilled gabled porch, addition eastern half of facade, metal frame 8/8 windows and paired 1/1 windows. NC
956. 1707 Waterford Street. Circa 1945. 1 story wood frame Minimal Traditional with side gable roof, raised brick foundation, three bay facade, entrance under projecting gabled porch with decorative iron supports, paired wood frame 3/1 windows and metal frame picture window. C
957. 1708 Waterford Street. Circa 1950. 1 story wood frame building of contemporary style with gable roof, raised brick foundation, three bay facade, entrance under attached gable with decorative iron supports over stoop, metal frame 6/6 windows. C
958. 1710 Waterford Street. Circa 1950. 1 story asbestos sided building of contemporary style with gable roof, raised brick foundation, three bay facade, entrance under attached gable with decorative iron supports over stoop, wood frame picture windows, awnings over stoop and windows. C
959. 1712 Waterford Street. Circa 1965. 1 story brick veneer building of contemporary style with gable roof, concrete foundation, three bay facade, entrance under projecting gabled porch supported by posts, metal frame picture window and 9/6 windows, two story hipped addition at rear. NC
960. 1754 Waterford Street. Circa 1965. 1 story brick veneer building of contemporary style with hip roof, concrete foundation, three bay facade, entrance under projecting hipped porch with decorative iron supports, metal frame 8/8 windows. NC
961. 1756 Waterford Street. Circa 1940. 1 story wood frame Minimal Traditional with gable roof, raised brick foundation, three bay facade, entrance under projecting gabled porch supported by posts, metal frame 1/1 windows, louvered vent in gable, interior chimney, exposed rafters. C
962. 1757 Waterford Street. Circa 1940. 1 story wood frame duplex with gable roof, raised brick foundation, four bay facade, entrance under pent roofed porch supported by posts, porch screened, wood frame 6/6 windows in outer bays, building converted into single family residence. C
963. 1759 Waterford Street. Circa 1955. 1 story wood frame building of no particular style with sloping shed roof, raised concrete foundation, two bay facade, entrance at infilled porch along western portion of facade, metal frame 1/1 window. NC

Weinacker Avenue

964. 410 Weinacker Avenue. Circa 1910. 1 story wood frame shotgun with gable roof, raised brick foundation, two bay facade with entrance under screened recessed porch supported by posts, metal frame 6/6 windows, addition added south elevation, exposed rafters. NC
965. 412 Weinacker Avenue. Circa 1950. 1 story concrete block Minimal Traditional with side gable roof, raised concrete foundation, three bay facade, centered entrance with flanking paired metal frame 6/6 windows. C
966. 414 Weinacker Avenue. Circa 1940. 1 story wood frame building of contemporary style with gable roof, raised brick foundation, two bay facade, entrance at screened projecting gabled porch, metal frame picture window, louvered vent in main gable. C

967. 453 Weinacker Avenue. Circa 1960. 2 story brick veneer building of contemporary design with gable roof, concrete foundation, five bay facade, entrance at projecting gabled bay with double door entrance, metal frame 6/6 windows, building connected to 457 Weinacker Avenue. NC
968. 456 Weinacker Avenue. Circa 1950. 1 story wood frame building of contemporary style with gable roof, raised brick foundation, three bay facade, entrance under projecting gabled porch with decorative iron supports, metal frame 2/2 windows and paired 1/1 windows, louvered vents in gables. C
969. 457 Weinacker Avenue. Circa 1995. 1 story brick veneer ecclesiastical building with gable roof, concrete slab foundation, centered entrance, windowless facade, spire. NC
970. 458 Weinacker Avenue. Circa 1920. 1 story wood frame cottage with hip roof, raised brick foundation, three bay facade, entrance under recessed porch supported by columns on brick piers and decorative iron supports, wood frame multi-pane picture window, awning over entrance. C
971. 460 Weinacker Avenue. Circa 1905. 1 story wood frame cottage with gable roof, raised brick foundation, three bay facade, entrance under pent roofed porch supported by battered columns on brick piers, drop frieze, metal frame 2/2 windows, louvered vent in gable. C
972. 500 Weinacker Avenue. Circa 1900. 1 story wood frame cottage with hip roof, raised brick foundation, three bay facade, entrance under attached shed roofed porch with decorative iron supports, metal frame 2/2 windows and multi-pane picture window in projecting gabled bay. C
973. 501 Weinacker Avenue. Circa 1915. 1 story wood frame cottage with hip roof, raised brick foundation, three bay facade, entrance under recessed corner porch supported by brick column, paired and single wood frame 6/6 windows, side chimney, shed roofed addition south elevation. NC
974. 502 Weinacker Avenue. Circa 1905. 1 story wood frame cottage with hip roof, raised brick foundation, three bay facade, entrance with sidelights under recessed porch supported by iron posts, paired metal frame 1/1 windows. C
975. 504 Weinacker Avenue. Circa 1925. 1 story wood frame bungalow with side gable roof, raised brick foundation, four bay facade, entrance with transom under projecting gable supported by battered columns on brick piers over stoop, recessed corner porch screened, paired wood frame 6/6 windows in larger gabled bay. C
976. 505 Weinacker Avenue. Circa 1915. 1 story wood frame cottage with hip roof, raised brick foundation, three bay facade, entrance at infilled recessed corner porch supported by brick column, column still visible, metal frame 2/2 windows and 6/6 windows. NC
977. 507 Weinacker Avenue. Circa 1930. 1 story wood frame bungalow with gable roof, raised brick foundation, two bay facade, entrance at screened recessed corner porch, wood frame 3/1 windows, louvered vent in gable. C
978. 509 Weinacker Avenue. Circa 1930. 1 story wood frame bungalow with gable roof, raised brick foundation, three bay facade, entrance under recessed porch supported by battered columns on brick piers, paired wood frame 3/1 windows. C
979. 553 Weinacker Avenue. Circa 1990. 1 story brick veneer building of contemporary style with hip roof, concrete slab foundation, three bay facade, entrance under projecting gabled porch supported by posts, metal frame 1/1 windows. NC
980. 555 Weinacker Avenue. Circa 1965. 1 story brick veneer building of contemporary style with hip roof, concrete foundation, three bay facade, entrance under projecting hipped porch supported by posts, metal frame 1/1 windows. NC

981. 557 Weinacker Avenue. Circa 1940. 1 story wood frame Minimal Traditional with side gable roof, raised brick foundation, three bay facade, entrance under projecting gabled porch with decorative iron supports, metal frame 1/1 window and wood frame picture window. C
982. 559 Weinacker Avenue. Circa 1960. 1 story brick veneer building of contemporary style with gable roof, raised concrete foundation, three bay facade, entrance under projecting gabled porch with decorative iron supports, metal frame 2/2 windows and picture window. C
983. 909 Weinacker Avenue. Circa 1960. 1 story brick veneer building of contemporary style with gable roof, raised concrete foundation, three bay facade, entrance under projecting gabled porch with decorative iron supports, metal frame 1/1 windows and picture window. C
984. 911 Weinacker Avenue. Circa 1940. 1 story wood frame Minimal Traditional with side gable roof, raised brick foundation, three bay facade, entrance at projecting gable supported by posts over stoop but has been enclosed, recessed corner porch infilled, paired metal frame 1/1 windows. NC
985. 913 Weinacker Avenue. Circa 1940. 1 story wood frame Minimal Traditional with side gable roof, raised brick foundation, three bay facade, entrance under projecting gabled porch with decorative iron supports, paired metal frame 1/1 windows, building covered with brick paper. C
986. 915 Weinacker Avenue. Circa 1975. 1 story concrete block and metal frame commercial building with flat roof partially collapsed, concrete slab foundation, two bay facade. NC
987. 928 Weinacker Avenue. Circa 1920. 1 story wood frame cottage with hip roof, raised brick foundation, three bay facade, entrance under recessed corner porch with decorative iron supports, metal frame picture windows and awning windows. C
988. 950 Weinacker Avenue. Circa 1955. 1 story brick veneer ecclesiastical building with gable roof, raised concrete foundation, three bay facade, entrance in central bell tower with pyramidal roof, flared eaves, stained glass windows. C
[Photo #34]
989. 952 Weinacker Avenue. Circa 1930. 1 story wood frame building of contemporary style with gable roof, raised brick foundation, three bay facade, entrance under recessed porch supported by posts, paired and single metal frame 6/6 windows, louvered vent in gable, exposed rafters, side chimney. C
990. 953 Weinacker Avenue. Circa 1965. 1 story brick veneer building of contemporary style with gable roof, raised brick foundation, three bay facade, entrance under projecting gabled porch supported by posts, metal frame awning windows. NC
991. 954 Weinacker Avenue. Circa 1940. 1 story brick veneer Minimal Traditional with side gable roof, raised brick foundation, three bay facade, entrance set within projecting gable supported by battered arch over stoop, metal frame 1/1 windows in facing gabled bay, recessed corner porch screened. C
992. 955 Weinacker Avenue. Circa 1900. 1 story wood frame cottage with side gable roof, raised brick foundation, three bay facade, entrance with transom under recessed porch supported by posts, paired and single metal frame 6/6 windows, porch screened, exposed rafters. C
993. 956 Weinacker Avenue. Circa 1920. 1 story wood frame cottage with hip roof, raised brick foundation, three bay facade, entrance under recessed porch with decorative iron supports, metal frame paired 6/6 windows and 9/6 windows. C

994. 967 Weinacker Avenue. Circa 1935. 1 story wood frame bungalow with gable roof, raised brick foundation, three bay facade, entrance under projecting gabled porch with decorative iron supports on brick piers, paired wood frame 3/1 windows and metal frame picture window with sidelights, louvered vents in gables. C
995. 969 Weinacker Avenue. Circa 1965. 1 story brick veneer ecclesiastical building with gable roof, raised concrete foundation, three bay facade, double door entrance, metal frame 2/2 windows. NC
996. 970 Weinacker Avenue. Circa 1930. 1 story wood frame bungalow with gable roof, raised brick foundation, three bay facade, entrance under projecting gabled porch supported by posts, paired and single wood frame 3/1 windows, louvered vent in main gable, exposed rafters, knee braces. C
997. 972 Weinacker Avenue. Circa 1945. 1 story wood frame building of contemporary style with gable roof, raised brick foundation, three bay facade, entrance under projecting gabled porch with decorative iron supports, clapboard knee wall added to porch, wood frame 6/6 window and metal frame picture window. C
998. 974 Weinacker Avenue. Circa 1940. 1 story concrete block duplex with gable roof, raised concrete foundation, three bay facade, entrance under recessed porch supported by battered columns on brick piers, paired metal frame 2/2 windows, one entrance now infilled, building converted to single family residence, louvered vent in gable. C
999. 975 Weinacker Avenue. Circa 1925. 1 story wood frame bungalow with gable roof, raised brick foundation, three bay facade, entrance under recessed porch supported by battered columns on brick piers, paired wood frame 3/1 windows, awning across facade, louvered vent in gable. C
1000. 981 Weinacker Avenue. Circa 1930. 1 story wood frame bungalow with gable roof, raised brick foundation, three bay facade, entrance under projecting gabled porch supported by square columns, paired and single wood frame 3/1 windows, louvered vent in porch gable, exposed rafters. C
1001. 982 Weinacker Avenue. Circa 1965. 1 story brick veneer commercial building with stepped roof, concrete foundation, three bay facade, metal frame storefront windows and double door entrance. NC

Wexford Street

1002. 1601 Wexford Street. Circa 1950. 1 story wood frame building of contemporary style with gable roof, raised brick foundation, three bay facade, entrance under projecting gabled porch with decorative iron supports, metal frame 2/2 window and picture window with sidelights. C
1003. 1603 Wexford Street. Circa 1965. 1 story brick veneer building of contemporary style with gable roof, concrete foundation, three bay facade, entrance under attached gable with decorative iron supports over stoop, metal frame 2/2 windows and picture window with 2/2 sidelights. NC
1004. 1604 Wexford Street. Circa 1965. 1 story brick veneer building of contemporary style with hip roof, concrete slab foundation, three bay facade, centered entrance, metal frame picture window and 2/2 windows. NC
1005. 1605 Wexford Street. Circa 1940. 1 story wood frame Minimal Traditional with side gable roof, raised brick foundation, three bay facade, entrance under screened recessed corner porch supported by posts, paired metal frame 2/2 windows. C
1006. 1609 Wexford Street. Circa 1945. 1 story concrete block building of contemporary style with gable roof, raised concrete foundation, three bay facade, entrance at screened projecting gabled porch supported by concrete block columns, paired metal frame 6/6 windows, louvered vent in gable. C

1007. 1616 Wexford Street. Circa 1950. 1 story brick veneer building of contemporary style with gable roof, raised brick foundation, one bay facade, entrance at projecting gabled bay, wood frame window. C
1008. 1652 Wexford Street. Circa 1970. 1 story brick veneer building of contemporary style with hip roof, concrete foundation, three bay facade, entrance under projecting gable supported by massive brick columns over stoop, metal frame picture window and 2/2 window. NC
1009. 1653 Wexford Street. Circa 1945. 1 story wood frame building of contemporary style with side gable roof, raised brick foundation, three bay facade, entrance at projecting gabled addition, metal frame 2/2 windows. NC
1010. 1654 Wexford Street. Circa 1945. 1 story wood frame building of contemporary style with gable roof, raised brick foundation, two bay facade, entrance at screened recessed corner porch, paired metal frame 1/1 windows, louvered vent in gable. C
1011. 1655 Wexford Street. Circa 1940. 1 story wood frame Minimal Traditional with side gable roof, raised brick foundation, three bay facade, entrance under projecting gable with decorative iron supports over stoop, wood frame 2/2 windows and picture window with sidelights. C
1012. 1660 Wexford Street. Circa 1970. 1 story concrete block ecclesiastical building with gable roof, raised concrete foundation, three bay facade, entrance under attached gable supported by posts over stoop, metal frame 6/6 windows, louvered vent in gable. NC
1013. 1703 Wexford Street. Circa 1940. 1 story asbestos sided Minimal Traditional with side gable roof, raised brick foundation, three bay facade, entrance under projecting shed roof supported by posts over stoop, metal frame 1/1 window and multi-paned picture window. C
1014. 1705 Wexford Street. Circa 1940. 1 story wood frame Minimal Traditional with side gable roof, raised brick foundation, three bay facade, entrance under projecting shed roof supported by posts over stoop, paired wood frame 3/1 windows and picture window. C
1015. 1707 Wexford Street. Circa 1940. 1 story wood frame building of contemporary style with gable roof, raised brick foundation, three bay facade, entrance under recessed corner porch supported by square posts, metal frame 2/2 windows, louvered vent in gable. C
1016. 1709 Wexford Street. Circa 1955. 1 story wood frame building of contemporary style with gable roof, raised brick foundation, three bay facade, entrance under attached gabled porch with decorative iron supports, metal frame awning and picture window. C
1017. 1711 Wexford Street. Circa 1980. 1 story brick veneer ecclesiastical building with gable roof, raised concrete foundation, five bay facade, centered double door entrance, metal frame awning windows. NC
1018. 1714 Wexford Street. Circa 1970. 1 story concrete block building of contemporary style with hip roof, concrete foundation, three bay facade, entrance in easternmost bay, metal frame 2/2 windows. NC
1019. 1716 Wexford Street. Circa 1960. 1 story wood frame building of contemporary style with gable roof, raised brick foundation, 1 bay facade, entrance with sidelights, addition eastern half of facade, deck across rest of facade. NC
1020. 1717 Wexford Street. Circa 1950. 1 story wood frame Minimal Traditional with gable roof, raised brick foundation, three bay facade, projecting gabled porch infilled, entrance located in infill, wood frame 6/6 windows. NC

1021. 1718 Wexford Street. Circa 1960. 2 story brick veneer Colonial Revival with hip roof, raised concrete foundation, three bay facade, entrance under attached gabled porch supported by paired, attenuated Tuscan columns, metal frame 1/1 windows second floor, windows first floor boarded, brick quoins at corners of front facade. C [Photo #8]
1022. 1719 Wexford Street. Circa 1945. 1 story wood frame Minimal Traditional with side gable roof, raised brick foundation, four bay facade, entrance under projecting gabled porch supported by posts, metal frame 2/2 windows, louvered vent in porch gable. C

Wisconsin Avenue

1023. 505 Wisconsin Avenue. Circa 1945. 1 story wood frame building of contemporary style with gable roof, raised brick foundation, five bay facade, entrance under attached gable supported by posts over stoop, wood frame 6/1 windows and paired metal frame 1/1 windows, louvered vent in gable, addition north elevation. NC
1024. 506 Wisconsin Avenue. Circa 1965. 1 story wood frame building of contemporary style with gable roof, raised brick foundation, two bay facade, entrance under recessed gabled porch with decorative iron supports, metal frame picture window with 6/6 sidelights. NC
1025. 507 Wisconsin Avenue. Circa 1940. 1 story asbestos sided Minimal Traditional with side gable roof, raised brick foundation, entrance under projecting gable supported by posts over stoop, metal frame 8/8 windows with awnings, porch south elevation screened, interior chimney. C
1026. 508 Wisconsin Avenue. Circa 1970. 1 story brick veneer building of contemporary style with side gable roof, concrete slab foundation, four bay facade, entrance under recessed porch with decorative iron supports, metal frame picture windows, attached garage with metal door. NC
1027. 509 Wisconsin Avenue. Circa 1930. 1 story wood frame bungalow with gable roof, raised brick foundation, three bay facade, entrance at screened projecting gabled porch supported by battered columns on brick piers, paired metal frame 1/1 windows, braces and exposed rafters, louvered vents in gables. C
1028. 511 Wisconsin Avenue. Circa 1930. 1 story wood frame bungalow with gable roof, raised brick foundation, three bay facade, entrance at screened projecting gable porch supported by battered columns on brick piers, paired wood frame 1/1 windows, exposed rafters, awnings across porch and windows. C
1029. 512 Wisconsin Avenue. Circa 1890. 1 story wood frame Neo-classical cottage with hip roof, raised brick foundation, five bay facade, entrance with sidelights and transom under projecting gabled porch supported by columns, 2/2 wood frame windows, single light in porch gable, interior chimney. C [Photo #5]
1030. 513 Wisconsin Avenue. Circa 1930. 1 story wood frame bungalow with gable roof, raised brick foundation, three bay facade, entrance at screened recessed porch supported by stucco columns, paired wood frame 3/1 windows, exposed rafters. C
1031. 515 Wisconsin Avenue. Circa 1925. 1 story wood frame bungalow with side jerkin head roof, raised brick foundation, three bay facade, entrance under projecting jerkin head porch supported by decorative iron posts, paired wood frame 3/1 windows, louvered vent in porch gable, side chimney. C
1032. 552 Wisconsin Avenue. Circa 1900. 1 story wood frame cottage with hip roof, raised brick foundation, five bay facade, entrance under recessed corner porch supported by columns, wood frame tripled 3/1 windows and 2/2 windows, centered intersecting gable above porch, additions along facade and north elevation. NC

1033. 553 Wisconsin Avenue. Circa 1930. 1 story wood frame bungalow with gable roof, raised brick foundation, four bay facade, entrance under projecting gabled porch supported by turned posts, metal frame awning windows, louvered vent in gables, exposed rafters. C
1034. 554 Wisconsin Avenue. Circa 1900. 1 story wood frame cottage with side gable roof, raised brick foundation, three bay facade, entrance under recessed porch supported by paired posts, paired wood frame 3/1 windows, gabled dormers with paired lights, side chimney. C
1035. 555 Wisconsin Avenue. Circa 1930. 1 story wood frame bungalow with gable roof, raised brick foundation, two bay facade, entrance with side lights under recessed porch supported by posts, porch lowered to grade, metal frame multi-pane picture window, knee braces, expose drafters, brick veneer applied up to window sills. NC
1036. 556 Wisconsin Avenue. Circa 1940. 1 story wood frame Minimal Traditional with side gable roof, raised brick foundation, three bay facade, entrance in projecting gabled bay with battered arch, wood frame 3/1 windows, exposed rafters, corner porch infilled but still identifies as a porch. C
1037. 557 Wisconsin Avenue. Circa 1930. 1 story asbestos sided bungalow with gable roof, raised brick foundation, three bay facade, entrance under screened projecting gabled porch supported by square columns, wood frame paired 6/6 windows, louvered vent in main gable, exposed rafters. C
1038. 558 Wisconsin Avenue. Circa 1940. 1 story wood frame Minimal Traditional with side gable roof, raised brick foundation, three bay facade, entrance under projecting gable supported by battered arches, paired metal frame 2/2 windows, exposed rafters. C
1039. 559 Wisconsin Avenue. Circa 1940. 1 story wood frame Minimal Traditional with side gable roof, raised brick foundation, four bay facade, entrance under projecting gable supported by posts over stoop, paired and single metal frame 6/6 windows. C
1040. 561 Wisconsin Avenue. Circa 1915. 1 story wood frame cottage with hip roof, raised brick foundation, three bay facade, entrance under projecting gable supported by brick arch, metal frame windows with burglar bars, attached hipped porch southern half of facade, side chimney. NC
1041. 562 Wisconsin Avenue. Circa 1935. 1 story wood frame Minimal Traditional with side gable roof, raised brick foundation, three bay facade, entrance under recessed corner porch in projecting gabled bay, paired wood frame 3/1 windows and 6/6 windows, exposed rafters, side chimney. C
1042. 563 Wisconsin Avenue. Circa 1940. 1 story wood frame Minimal Traditional with side gable roof, raised brick foundation, two bay facade, entrance at screened recessed corner porch, metal frame windows with awnings, side chimney. C
1043. 564 Wisconsin Avenue. Circa 1960. 1 story wood frame building of contemporary style with gable roof, raised brick foundation, three bay facade, entrance under attached gable supported by posts over stoop, metal frame multi-pane picture window and 6/6 windows, attached carport north elevation is later. NC
1044. 565 Wisconsin Avenue. Circa 1940. 1 story wood frame building of contemporary style with gable roof, raised brick foundation, four bay facade, entrance at infilled projecting gabled porch, metal frame 2/2 windows, awnings over windows. NC

1045. 600 Wisconsin Avenue. Circa 1970. 1 story brick veneer building of contemporary style with hip roof, raised concrete foundation, three bay facade, entrance under recessed corner porch supported by brick columns, metal frame 6/6 windows and picture window. NC
1046. 602 Wisconsin Avenue. Circa 1940. 1 story wood frame building of contemporary style with gable roof, raised brick foundation, two bay facade, entrance under recessed corner porch supported by post, paired metal frame 6/6 windows. C
1047. 604 Wisconsin Avenue. Circa 1970. 1 story brick veneer building of contemporary style with hip roof, concrete slab foundation, three bay facade, entrance under projecting hipped roof supported by posts over stoop, metal frame 9/6 windows. NC
1048. 605 Wisconsin Avenue. Circa 1930. 1 story wood frame bungalow with gable roof, raised brick foundation, three bay facade, entrance under projecting gabled porch supported by battered columns on brick piers, porch extends across facade to form porte-cochere, metal frame windows. C
1049. 606 Wisconsin Avenue. Circa 1940. 1 story brick veneered Minimal Traditional with side gable roof, raised brick foundation, three bay facade, entrance under shed roofed porch with decorative iron supports, porch lowered to grade, metal frame 6/6 windows, peak of intersecting gable rises above apex of side gable. NC
1050. 607 Wisconsin Avenue. Circa 1955. 1 story brick veneer building of contemporary style with gable roof, raised brick foundation, four bay facade, entrance under projecting gabled porch supported by battered columns on brick piers, metal frame 1/1 windows, louvered vents in gables, brick veneer applied at later date. NC
1051. 608 Wisconsin Avenue. Circa 1940. 1 story wood frame building of contemporary style with gable roof, raised brick foundation, three bay facade, entrance under attached gabled porch supported by brick columns, wood frame paired and single 1/1 windows, knee braces. C
1052. 609 Wisconsin Avenue. Circa 1945. 1 story wood frame house of contemporary style with gable roof, raised brick foundation, three bay facade, entrance slightly off center, metal frame 1/1 windows, new deck across facade. NC
1053. 610 Wisconsin Avenue. Circa 1940. 1 story wood frame Minimal Traditional with gable roof, raised brick foundation, three bay facade, entrance under projecting gabled porch supported by posts, wood frame 1/1 windows. C
1054. 611 Wisconsin Avenue. Circa 1940. 1 story wood frame Minimal Traditional with side gable roof, raised brick foundation, three bay facade, entrance under projecting gabled porch supported by posts on brick piers, metal frame paired 2/2 windows. C
1055. 613 Wisconsin Avenue. Circa 1995. 1 story wood frame contemporary style house with hip roof, concrete foundation, three bay facade, entrance under recessed porch supported by posts, metal frame 6/6 windows. NC
1056. 615 Wisconsin Avenue. Circa 1970. 1 story brick veneer building of contemporary style with hip roof, concrete slab foundation, three bay facade, entrance under projecting gabled porch supported by posts, metal frame picture windows with burglar bars. NC
1057. 617 Wisconsin Avenue. Circa 1940. 1 story wood frame building of contemporary style with gable roof, raised brick foundation, three bay facade, entrance under screened projecting gabled porch supported by posts, metal awning windows. C

Archaeological Sites

1058. All of the area encompassed within the district boundaries, including the vacant lots where buildings have been demolished, comprise one archaeological site for its potential to yield information about the growth and development of the neighborhood. C

8. Statement of Significance

Applicable National Register Criteria

(Mark "x" in one or more boxes for the criteria qualifying the property for National Register listing.)

- A Property is associated with events that have made a significant contribution to the broad patterns of our history.
- B Property is associated with the lives of persons significant in our past.
- C Property embodies the distinctive characteristics of a type, period, or method of construction or represents the work of a master, or possesses high artistic values, or represents a significant and distinguishable entity whose components lack individual distinction.
- D Property has yielded, or is likely to yield, information important in prehistory or history.

Criteria Considerations

(Mark "x" in all the boxes that apply.)

Property is:

- A Owned by a religious institution or used for religious purposes.
- B removed from its original location.
- C a birthplace or grave.
- D a cemetery.
- E a reconstructed building, object, or structure.
- F a commemorative property.
- G less than 50 years old or achieving significance within the past 50 years.

Period of Significance (justification)

Areas of Significance

(Enter categories from instructions.)

Architecture
 Archaeology: Historic/Non-Aboriginal

Period of Significance

1880-1962

Significant Dates

1880

Significant Person

(Complete only if Criterion B is marked above.)

N/A

Cultural Affiliation

African-American
 European-American

Architect/Builder

The period of significance begins in 1880, the year of the oldest identifiable building in the district, and ends with the 50 year cut-off date of 1962.

Criteria Considerations (explanation, if necessary)

N/A

Statement of Significance Summary Paragraph (Provide a summary paragraph that includes level of significance and applicable criteria.)

The Maysville Historic District (1880-1962) is locally significant under National Register Criteria C for its large, mostly intact collection of late 19th and early 20th century architecture. The buildings in Maysville have not been significantly altered, and the district retains a strong sense of time and place. The appearance of the district has not been significantly altered, and it retains much of its historic character.

Maysville is also locally significant under Criterion D: Archaeology. Although no formal archaeological survey has been made of this neighborhood, the potential for subsurface remains is high. The ground level remains, Sanborn maps and City Directories indicate that buried remains within the boundaries of the proposed district may yield useful information on the historic buildings that once occupied these lots and the history of the people who inhabited this neighborhood.

Narrative Statement of Significance (Provide at least one paragraph for each area of significance.)

The Maysville Historic District is locally significant under Criterion C for architecture for its large concentration of late 19th and early to mid-20th century houses. Late 19th century architectural styles include Late Victorian and Classical Revival. Early to mid-20th century styles include the Four Square, Colonial Revival, Craftsman/bungalow, Minimal Traditional and early Ranch homes. The diversity of styles reflects national tastes, but also illustrates regional influences. Raised brick foundations, large recessed or projecting porches, low pitched roofs with wide eaves and extensive use of windows and doors for light and ventilation are common local features. This did not change until the advent of central air and heating, which resulted in housing styles and forms that more closely followed housing in the rest of the country regardless of geographic location.

Maysville was developed during the same period as a number of surrounding districts, namely the Leinkauf Historic District, which borders Maysville along its northern boundary, and a proposed Oakdale Historic District, which borders Maysville along its eastern boundary. These areas to the south and west of downtown Mobile were particularly noted for their new development in the 1903 *Mobile Register Trade Edition*. It is in this regard that Maysville serves as a valuable local example of the evolution of architectural styles during the late 19th to mid-20th centuries in Mobile.

The district is also locally significant under Criterion D for archaeology. The entire district encompassed within the boundaries of Maysville comprises one archaeological site. Archaeology in Maysville has the potential to assist in addressing several key issues pertaining to the district. First, archaeology can help in identifying the construction and developmental phases of the district. Secondly, it can identify social factors affecting change in the neighborhood. Third, archaeology can show how the district was interrelated to the neighborhoods surrounding it and how its development affected the history of the evolution of those neighborhoods. Finally, it can support efforts in identifying significant individuals and events important to Mobile. Archaeology, therefore, has the potential to add another dimension to the investigation into the development of Maysville and the lives of its inhabitants.

Developmental history/additional historic context information (if appropriate)

The Maysville Subdivision (Deed Book 98,125) was platted in 1871 by D.M. Ross, county surveyor. The earliest map of the area, kept at the Mobile Municipal Archives, is the 1878 City Atlas. It shows a few buildings of which none are extant. An 1880 Sanborn Map shows some streets but no buildings. Although platted in 1871, this area of Mobile remained relatively unsettled until the very late 19th century. The period immediately

following the Civil War saw a decline in Mobile's fortunes. The port silted up and trade dwindled. Cotton was no longer king and failed speculative ventures resulted in the City of Mobile being bankrupt by 1875. Having borrowed heavily to finance various improvement programs, the city's debt had climbed to a staggering \$5 million dollars (Thomason 10/23/2003). It was not until the latter half of the 1890's that Mobile began to recover. The port diversified with timber and fruit being important products. By World War One the City was again prospering and it is reflected in census data. The population of the City in 1890 was some 30,000. By 1920 the population had doubled to 60,000. The population growth resulted in new housing developments to the west and to the south, including Maysville.

Maysville eventually came to encompass thirteen subdivisions that include: Glendale Park(Deed Book 61,316)(1890); Smith-Overall Tract(Deed Book 67,160)(1891); Porter's Second Addition(Deed Book 99,23)(1902); Tropical Place(Deed Book 117,81)(1905); Sunset Place(Deed Book 135,35)(1907); Melrose Place(Deed Book 134,562)(1908); Zimlich and Strauss Subdivision(Deed Book 153,32)(1912); Gaynor Tract(Deed Book 156,127)(1915); Maysville Resubdivision(Deed Book 2,261)(1928); the Houston Street Extension(Deed Book 3,351)(1939); and Cloverleaf Park(Deed Book 3,560)(1941).

The streets are set to right angles with each other in straight lines, running north-south and east-west. These streets appear to be an extension of Mobile's original grid plan running from the urban core to the rural countryside and are typical of residential planning of that period. The lots have also been divided into typical, residential size lots. The downtown area was easily reached by means of public transportation with the streets within walking distance of the trolley lines along Government and South Ann Street (Mobile Light & R.R Company Map, 2005).

City Directories from 1903-1951 reveal a mostly working to lower-middle class neighborhood. Occupations typically found in the area include: laborer, carpenter, machinist, barber, and clerk. They also reveal the area to be split between African-Americans, mostly living in the western section platted as Maysville, and whites, mostly living in the eastern section platted as Glendale Park. This resulted in an understandable disparity in housing between the two sections when one considers the socio-economic condition of both groups. A few modest, late 19th century Victorian cottages located in the western sections of Maysville (1705 Lomeroy Street c. 1900 Photo #2) are contrasted by more decorative examples located in Glendale Park (510 Dexter Avenue c. 1890 Photo #1). However, all of these cottages exhibit typical regional characteristics found throughout Mobile's older neighborhoods. These features include: raised brick pier foundations, recessed or projecting porches, and large windows (Gould 1988, 117-118). A few relatively prosperous residents lived in the Glendale Park section as evidenced by their homes which reflect the larger late 19th-early 20th century house forms and popular styles, such as 512 Wisconsin Avenue (c. 1890 Photo #5) and 1561 Illinois Street (c. 1900 Photo #4). Shotguns are well represented and are scattered throughout the district (1551 1/2 Dominick Street c. 1900 Photo #21 and 1558 Lemon Street c. 1900 Photo #22).

Demographic information is not available after 1951, as the City Directories stopped identifying race after that date. It should be noted that, just prior to 1951, a population shift was already beginning to occur in the district with whites beginning to leave the Glendale Park area and the African-American population increasing. This pattern increased and accelerated during the 1960's into the 1970's. This is beyond the period of significance for this nomination; however, it does account for the eventual identification of the entire area as Maysville.

The district grew steadily through the early 20th century. World War One and World War Two saw a rapid increase in Maysville's population as workers entered the city to work at the shipyards (McLaurin & Thomason 1981, 95 & 106). The area's African-American population was significant enough so that Williamson High School was opened in 1948 (Bivens 2004, 103). The school is listed on the 1955 Sanborn Fire Insurance Map as "colored". The architecture of the early 20th century turned to less elaborate styles than those of the late Victorian period (Baker 1994, 117). Craftsman style houses, which promoted a respect and aesthetic for the natural qualities of wood, brick, stone, stucco, and tile, comprise a large part of the district's early 20th century architecture (512 Tuttle Avenue c. 1925 Photo #11)(Gould 1988, 247 & Baker 1994, 114). The bungalow was one

of the more popular building forms constructed in the area after World War I (Baker 1994, 117). Bungalows in Maysville are most frequently modest buildings and continued to remain popular until 1940 (505 Michigan Avenue c. 1925 Photo #10). Additionally, a few Period Revival style houses, such as 1300 Illinois Street (c. 1950) and 1718 Wexford Street (c. 1960) were constructed in Maysville during this same time frame. Four Squares are also scattered throughout the district but are few in number (510 Tuttle Avenue c. 1915 Photo #13).

Minimal Traditional houses began to appear in the years just prior to World War II and remained popular until 1960 (1054 S. Ann Street c. 1950 Photo #15 and 463 Booker Street c. 1940 Photo #16). A section of worker housing was constructed during World War II near Williamson High School consisting of several barracks type concrete block apartment buildings (1924 Sanborn Fire Insurance Map). However, these have long since been demolished. An empty field now exists where they once stood. Michigan Avenue developed around this same time as a commercial corridor with businesses located along its widest point. This section is still a commercial corridor, but no historic buildings remain along its length. Early Ranch homes were built in the late 1950's, and they continue to be popular today (1605 Dublin Street c. 1960 Photo #18 and 1007 Ghent Street c. 1960 Photo #19). These were built on the few remaining vacant lots that were available, and sometimes replaced older houses in the neighborhood. However, they are no less important as they demonstrate the continued viability of the district.

9. Major Bibliographical References

Bibliography (Cite the books, articles, and other sources used in preparing this form.)

Baker, John Milnes. American House Styles: A Concise Guide. New York: W.W. Norton and Company, 1994.

Bivens, Shawn. Mobile, Alabama's People of Color: A Tricentennial History:1702-2002. Victoria, Canada: Trafford Publishing, 2004.

City Directories(1903-1951). Municipal Archives. Mobile, Alabama.

Deed Books. Probate Court. Mobile, Alabama.

Gould, Elizabeth. From Fort to Port: An Architectural History of Mobile, Alabama, 1711-1918. Tuscaloosa, Alabama: University of Alabama Press, 1988.

Hamilton, Peter J. Colonial Mobile. Alabama: University of Alabama Press, 1976.

Hoffman, Bert. Mobile Light & R.R Company Map. Mobile Historic Development Commission files. 2005

The Mobile Register 1903 Trade Edition. Library of Local History. Mobile, Alabama.

Peavy, John R., Jr. Peavy's Map of the City of Mobile. Mobile Historic Development Commission files. 1911.

Sanborn Fire Insurance Maps of Mobile, Alabama, 1878, 1880, 1904, 1925 and 1955. Municipal Archives. Mobile, Alabama.

Thomason, Michael (ed.). Mobile: The New History of Alabama's First City. Alabama: University of Alabama Press, 2001.

Previous documentation on file (NPS):

preliminary determination of individual listing (36 CFR 67 has been requested)
 previously listed in the National Register
 previously determined eligible by the National Register
 designated a National Historic Landmark
 recorded by Historic American Buildings Survey # _____
 recorded by Historic American Engineering Record # _____
 recorded by Historic American Landscape Survey # _____

Primary location of additional data:

State Historic Preservation Office
 Other State agency
 Federal agency
 Local government
 University
 Other
Name of repository: Mobile Historic Development Commission

Historic Resources Survey Number (if assigned): _____

10. Geographical Data

Acreage of Property 451
(Do not include previously listed resource acreage.)

UTM References
(Place additional UTM references on a continuation sheet.)

1	<u>16</u> Zone	<u>396335</u> Easting	<u>3393980</u> Northing	3	<u>16</u> Zone	<u>397675</u> Easting	<u>3392260</u> Northing
2	<u>16</u> Zone	<u>397680</u> Easting	<u>3393770</u> Northing	4	<u>16</u> Zone	<u>396340</u> Easting	<u>3392450</u> Northing

Verbal Boundary Description (Describe the boundaries of the property.)

The boundary of the Maysville Historic District is shown on the accompanying map, entitled "The Maysville Historic District". The scale is 1" equals 250'. All non-contributing resources are marked by cross-hatching over the building.

Boundary Justification (Explain why the boundaries were selected.)

The boundary of the Maysville Historic District was drawn to include the largest concentration of historic resources in the area known as "Maysville" by local tradition and which can be verified through historical research.

11. Form Prepared By

name/title Shaun Wilson/ Preservation Consultant, reviewed by Susan Enzweiler, AHC NR
Coordinator

organization Mobile Historic Development Commission date _____

street & number P.O. Box 1827 telephone 251-208-7281

city or town Mobile state AL zip code 36633

e-mail mhdc@cityofmobile.org

Additional Documentation

Submit the following items with the completed form:

- **Maps:** A **USGS map** (7.5 or 15 minute series) indicating the property's location.
A **Sketch map** for historic districts and properties having large acreage or numerous resources. Key all photographs to this map.
- **Continuation Sheets**
- **Additional items:** (Check with the SHPO or FPO for any additional items.)

Photographs:

Submit clear and descriptive photographs. The size of each image must be 1600x1200 pixels at 300 ppi (pixels per inch) or larger. Key all photographs to the sketch map.

Name of Property: Maysville Historic District

City or Vicinity: Mobile

County: Mobile County

State: Alabama

Photographer: Shaun Wilson

Date Photographed: November, 2010 - February, 2011

Description of Photograph(s) and number:

1. 510 Dexter Avenue, camera facing west
(AL_MobileCounty_MaysvilleHistoricDistrict_00001.tif)
2. 1705 Lomeroy Street, camera facing south
(AL_MobileCounty_MaysvilleHistoricDistrict_00002.tif)
3. 409 Booker Street, camera facing east
(AL_MobileCounty_MaysvilleHistoricDistrict_00003.tif)
4. 1561 Illinois Street, camera facing south
(AL_MobileCounty_MaysvilleHistoricDistrict_00004.tif)
5. 512 Wisconsin Avenue, camera facing west
(AL_MobileCounty_MaysvilleHistoricDistrict_00005.tif)
6. 1607 Illinois Street, camera facing south
(AL_MobileCounty_MaysvilleHistoricDistrict_00006.tif)
7. 1300 Illinois Street, camera facing north
(AL_MobileCounty_MaysvilleHistoricDistrict_00007.tif)
8. 1718 Wexford Street, camera facing north
(AL_MobileCounty_MaysvilleHistoricDistrict_00008.tif)
9. 514 Michigan Avenue, camera facing west
(AL_MobileCounty_MaysvilleHistoricDistrict_00009.tif)
10. 505 Michigan Avenue, camera facing east
(AL_MobileCounty_MaysvilleHistoricDistrict_00010.tif)
11. 512 Tuttle Avenue, camera facing west
(AL_MobileCounty_MaysvilleHistoricDistrict_00011.tif)
12. 1151 Rotterdam Street, camera facing east
(AL_MobileCounty_MaysvilleHistoricDistrict_00012.tif)
13. 510 Tuttle Avenue, camera facing west
(AL_MobileCounty_MaysvilleHistoricDistrict_00013.tif)
14. 562 Michigan Avenue, camera facing east
(AL_MobileCounty_MaysvilleHistoricDistrict_00014.tif)
15. 1054 S. Ann Street, camera facing west
(AL_MobileCounty_MaysvilleHistoricDistrict_00015.tif)

- 16.463 Booker Street, camera facing west
(AL_MobileCounty_MaysvilleHistoricDistrict_00016.tif)
- 17.1506 Dominick Street, camera facing north
(AL_MobileCounty_MaysvilleHistoricDistrict_00017.tif)
- 18.1605 Dublin Street, camera facing south
(AL_MobileCounty_MaysvilleHistoricDistrict_00018.tif)
- 19.1007 Ghent Street, camera facing east
(AL_MobileCounty_MaysvilleHistoricDistrict_00019.tif)
- 20.1610 Sligo Street, camera facing north
(AL_MobileCounty_MaysvilleHistoricDistrict_00020.tif)
- 21.1551 ½ Dominick Street, camera facing south
(AL_MobileCounty_MaysvilleHistoricDistrict_00021.tif)
- 22.1558 Lemon Street, camera facing north
(AL_MobileCounty_MaysvilleHistoricDistrict_00022.tif)
- 23.1572 Orange Street, camera facing north
(AL_MobileCounty_MaysvilleHistoricDistrict_00023.tif)
- 24.Streetscape, south side of 1600 block Virginia Street,
camera facing east (AL_MobileCounty_MaysvilleHistoricDistrict_00024.tif)
- 25.Streetscape, east side of 600 block Houston Street,
camera facing north (AL_MobileCounty_MaysvilleHistoricDistrict_00025.tif)
- 26.Streetscape, east side of 1000 block Houston Street,
camera facing south (AL_MobileCounty_MaysvilleHistoricDistrict_00026.tif)
- 27.Streetscape, north side of 1500 block Duval Street,
camera facing east (AL_MobileCounty_MaysvilleHistoricDistrict_00027.tif)
- 28.Streetscape, south side of 1500 block Orange Street,
camera facing west (AL_MobileCounty_MaysvilleHistoricDistrict_00028.tif)
- 29.Streetscape, west side of 1100 block S. Ann Street,
camera facing south (AL_MobileCounty_MaysvilleHistoricDistrict_00029.tif)
- 30.Streetscape, south side of 1300 block Clover Leaf Circle South,
camera facing west (AL_MobileCounty_MaysvilleHistoricDistrict_00030.tif)
- 31.Streetscape, west side of 550 block Michigan Avenue,
camera facing south (AL_MobileCounty_MaysvilleHistoricDistrict_00031.tif)
- 32.Streetscape, west side of 500 block Flint Street,
camera facing north (AL_MobileCounty_MaysvilleHistoricDistrict_00032.tif)
- 33.vacant lot, north side of 1750 block Belfast Street, camera facing north
(AL_MobileCounty_MaysvilleHistoricDistrict_00033.tif)
- 34.950 Weinacker Avenue, camera facing west
(AL_MobileCounty_MaysvilleHistoricDistrict_00034.tif)
- 35.1301 Virginia Street, camera facing south
(AL_MobileCounty_MaysvilleHistoricDistrict_00035.tif)
- 36.1621 Virginia Street, camera facing south
(AL_MobileCounty_MaysvilleHistoricDistrict_00036.tif)

Property Owner:

(Complete this item at the request of the SHPO or FPO.)



name Multiple Owners
street & number N/A telephone N/A
city or town Mobile state AL zip code 36610

Paperwork Reduction Act Statement: This information is being collected for applications to the National Register of Historic Places to nominate properties for listing or determine eligibility for listing, to list properties, and to amend existing listings. Response to this request is required to obtain a benefit in accordance with the National Historic Preservation Act, as amended (16 U.S.C.460 et seq.).

Estimated Burden Statement: Public reporting burden for this form is estimated to average 18 hours per response including time for reviewing instructions, gathering and maintaining data, and completing and reviewing the form. Direct comments regarding this burden estimate or any aspect of this form to the Office of Planning and Performance Management, U.S. Dept. of the Interior, 1849 C. Street, NW, Washington, DC.

MAYSVILLE HISTORIC DISTRICT

CITY OF MOBILE





Maysville Historic District
 Contributing Building
 Noncontributing Building
437 Maysville Addresses
 Parcels
 Rail Road
 Road Centerlines

September 5, 2013

0 500 1,000 1,500 Feet

[g:\specialproj\histdev\proposedMaysvilleHistoricDistrict.mxd](#)



Maysville Historic District
Mobile, Mobile County

1)16	396335	3393980
2)16	397680	3393770
3)16	397675	3392260
4)16	396340	3392450

Mapped, edited, and published by the Geological Survey
Control by USGS, USC&GS and Alabama Geodetic Survey
Culture and drainage in part compiled from aerial photographs
Topography by plane-table surveys 1938-39. Revised 1953
Hydrography from USC&GS Chart 1266 (1:80,000)
Polyconic projection. 1927 North American datum
10,000-foot grid based on Alabama coordinate system,
west zone
Red tint indicates areas in which only
landmark buildings are shown
Dashed land lines indicate approximate locations
1000-meter Universal Transverse Mercator grid ticks,
zone 16, shown in blue
To place on the predicted North American Datum 1983
move the projection lines 17 meters south and
1 meter east as shown by dashed corner ticks

UTM GRID AND 1982 MAGNETIC NORTH
DECLINATION AT CENTER OF SHEET
There may be private inholdings within
the boundaries of the National or
State reservations shown on this map

SCALE 1:24,000
CONTOUR INTERVAL 10 FEET
NATIONAL GEODETIC VERTICAL DATUM OF 1929
DEPTH CURVES AND SOUNDINGS IN FEET-GULF COAST LOW WATER DATUM
THE RELATIONSHIP BETWEEN THE TWO DATUMS IS VARIABLE
SHORELINE SHOWN REPRESENTS THE APPROXIMATE LINE OF MEAN HIGH WATER
THE MEAN RANGE OF TIDE IS APPROXIMATELY 1 FOOT
THIS MAP COMPLIES WITH NATIONAL MAP ACCURACY STANDARDS
FOR SALE BY U.S. GEOLOGICAL SURVEY
DENVER, COLORADO 80225, OR RESTON, VIRGINIA 22092
A FOLDER DESCRIBING TOPOGRAPHIC MAPS AND SYMBOLS IS AVAILABLE ON REQUEST

ROAD CLASSIFICATION
Heavy-duty ——— Light-duty ———
Medium-duty ——— Unimproved dirt ———
Interstate Route U.S. Route State Route

MOBILE, ALA.
NE/4 MOBILE 15' QUADRANGLE
N 3037.5—W 8800/7.5
1953
PHOTOREVISED 1982
DMA 3345 II NE—SERIES 9544

Revisions shown in purple compiled from aerial
photographs taken 1981 and other sources
This information not field checked. Map edited 1982
Purple tint indicates extension of urban area





1705



409



1561

1561





1607





1300



1718



514





505







MARDI GRAS

510

Happy Mardi Gras

ACR



HEIDI HALL
251-442-5506
FOR SALE
KELLER
WILLIAMS
REALTY
251-662-5660





463



1506

A 16099









1551



755



M.V.S.



















KEITH BREWER
251-751-3077

PREMIERE REALTY &
MANAGEMENT
Property Mgmt. &
Real Estate Sales
251-643-1801
www.premiere-realty.com



Weinacker

NEW
BAYSIDE
BAPTIST
CHURCH
REV. A. CLEVELAND, JR.
PASTOR

NEW BAYSIDE
BAPTIST CHURCH
WAS BUILT BY THE
MEMBERS OF THE
CHURCH IN
1912. THE CHURCH
IS A MEMBER OF THE
SOUTHERN BAPTIST
CONVENTION.
REV. A. CLEVELAND, JR.
PASTOR



**Neighbors Market
Grocery Store**
251-694-6992



adium P e

GROCERIES
MILK
WE
ACCEPT
EBT



WE
ACCEPT
EBT



WE
ACCEPT
EBT



BUILDING AND/OR BUSINESS
FOR SALE
7700+ SQ. FT.
EXCELLENT RETAIL LOCATION
422-0142

GROCERIES
MILK
WE
ACCEPT
EBT





LADD - PEEBLES STADIUM

LADD - PEEBLES STADIUM

National Register of Historic Places
Memo to File

Correspondence

The Correspondence consists of communications from (and possibly to) the nominating authority, notes from the staff of the National Register of Historic Places, and/or other material the National Register of Historic Places received associated with the property.

Correspondence may also include information from other sources, drafts of the nomination, letters of support or objection, memorandums, and ephemera which document the efforts to recognize the property.

UNITED STATES DEPARTMENT OF THE INTERIOR
NATIONAL PARK SERVICE

NATIONAL REGISTER OF HISTORIC PLACES
EVALUATION/RETURN SHEET

REQUESTED ACTION: NOMINATION

PROPERTY NAME: Maysville Historic District

MULTIPLE NAME:

STATE & COUNTY: ALABAMA, Mobile

DATE RECEIVED: 11/08/13 DATE OF PENDING LIST: 12/09/13
DATE OF 16TH DAY: 12/24/13 DATE OF 45TH DAY: 12/25/13
DATE OF WEEKLY LIST:

REFERENCE NUMBER: 13000959

REASONS FOR REVIEW:

APPEAL: N DATA PROBLEM: N LANDSCAPE: N LESS THAN 50 YEARS: N
OTHER: N PDIL: N PERIOD: N PROGRAM UNAPPROVED: N
REQUEST: Y SAMPLE: N SLR DRAFT: N NATIONAL: N

COMMENT WAIVER: N

ACCEPT RETURN REJECT 12/25/13 DATE

ABSTRACT/SUMMARY COMMENTS:

*local level - Architecture & Archeology
1880-1962*

RECOM./CRITERIA C & D

REVIEWER W. S. Deane

DISCIPLINE Historic

TELEPHONE _____

DATE 12/25/13

DOCUMENTATION see attached comments Y/N see attached SLR Y/N

If a nomination is returned to the nominating authority, the nomination is no longer under consideration by the NPS.



STATE OF ALABAMA
ALABAMA HISTORICAL COMMISSION
468 SOUTH PERRY STREET
MONTGOMERY, ALABAMA 36130-0900



FRANK W. WHITE
EXECUTIVE DIRECTOR

TEL: 334-242-3184
FAX: 334-240-3477

November 7, 2013

Ms. Carol Shull
Keeper of the National Register
U. S. Department of the Interior, NPS
Cultural Resources
National Register, History & Education Programs
1201 "I" Street NW (2280)
Washington, D. C. 20005

Dear Ms. Shull:

Enclosed please find the nomination and supporting documentation to be considered for listing the following Alabama resource in the National Register of Historic Places:

Maysville Historic District
Mobile, Mobile County, Alabama

Your consideration of the enclosed National Register of Historic Places nomination is appreciated.

Truly Yours,

Frank W. White
Executive Director

FWW/sme/nw

Enclosures

August 31, 2013

Ms. Susan M. Enzweiler
National Register Coordinator
PreserveALA
Alabama Historical Commission
468 South Perry Street
PO Box 300900
Montgomery, Alabama 36130-0900



RE: 1703 Lomeroy, 1705 Lomeroy, 1705 Buck Street, 1657 Virginia Street, 1559 Plover Street and Parcel #R022910281002036

Dear Ms. Enzweiler:

I am writing this letter to submit my vote and positive support for placing the above named properties which are located within the boundaries of the Maysville Historic District in Mobile (Mobile County), Alabama for consideration by the Alabama National Register Review Board for nomination to the National Register of Historic Places on September 26, 2013. These properties meet the criteria and should be nominated.


I look forward to your favorable response.

Sincerely yours,

A handwritten signature in blue ink that reads "Inell Gilmore".

Inell Gilmore
PO Box 18221
Kansas City, Missouri 64133-18221
816-358-9517

Saadia 9/5/13



MURRAY

Elizabeth Rushing Murray

1345 Oakcrest Dr SW

Atlanta, GA 30311

August 18, 2013

Susan M. Enziweiler

National Register Coordinator

P. O. Box 300900

Montgomery, Al 36130-0900



Dear Ms. Enziweiler:

I received correspondence from your office regarding the placement of the Maysville Community, of Mobile, AL, on the national historic register. I fully support this effort. As the owner of two properties in the Maysville Community –

1523 Orange Street Mobile, AL

1659 Virginia Street, Mobile, AL

I am elated about this project. Please, add my name to the let's move forward list.

Sincerely,

A handwritten signature in blue ink that reads "Elizabeth Rushing Murray".

Elizabeth Rushing Murray



3720 Holly Ridge Circle
Mobile, AL 36693

Ms. Susan M Enzweiler
National Register Coordinator
PO Box 300900
Montgomery, AL 36130-0900

RE: Maysville Historical District

August 19, 2013



Dear Ms. Enzweiler:

This letter serves as supporting documentation to be included with the application for the Maysville Community to be included in the National Register of Historic Districts. I am in complete agreement of the proposed designation for the Maysville Community. I am the owner of 1651 Elliott ST and co-owner of 454 Lott ST, 457 Booker ST and a lot at 458 Lott ST.

Please let me know if additional information is needed. This letter is notarized as requested.

Sincerely,

A handwritten signature in cursive that reads "Jerryln Rushing London".

Jerryln Rushing London
251-666-2963
Bridge28@aol.com

State of Alabama County of Mobile

On this 19th day August, 2013 before me, the undersigned authority, a Notary Public in and for said County and State, personally appeared before me, the above named individual, known to me to be the person who subscribed to the foregoing instrument.

Signature of Notary Public Dinaw Coleman

My Commission Expires 3/12/2014

17 September 2013

Ms. Susan M. Enzweiler
National Register Coordinator
State of Alabama
Alabama Historical Commission
468 South Perry Street
Montgomery, Alabama 36130-0900



Subject: Nomination of the Following Properties to the National Register: 1703 Lomeroy, 1705 Lomeroy, 1705 Buck Street, 1657 Virginia Street, 1559 Plover Street and Parcel # R022910281002036

Dear Ms. Susan Enzweiler:

I am writing this letter to submit my vote and positive support for placing the above named properties that are located within the boundaries of the Maysville Historic District in Mobile (Mobile County), Alabama for consideration by the Alabama National Register Review Board for nomination to the National Register of Historic Places on September 26, 2013. These properties met the criteria and should be nominated. I look forward to your favorable response.

Sincerely,

A handwritten signature in cursive script that reads "Alice L. Davis-Hall".

Alice L. Davis-Hall
5809 Fincastle Drive
Manassas, VA 20112

Sept. 17, 2013
Prince William Co, Va.
Sandra L. Carrichal
#172142

Don Davis

Judge of Probate

Joe McEarchern, Jr.

Chief Clerk/Administrator

C. Mark Erwin

Chief of Staff



Judicial Division - (251) 574-6001
Recording Division - (251) 574-6040
Records Division - (251) 574-6070
Elections Division - (251) 574-6080
Accounts Division - (251) 574-6101
Facsimile - (251) 574-6003

PROBATE COURT OF MOBILE COUNTY, ALABAMA

September 17, 2013

Ms. Susan Enzweiler
Alabama Historical Commission
468 South Perry Street
Montgomery, AL 36130-0900

RE: National Register Nomination for the Maysville Historic District

Dear Ms. Enzweiler:

We have received and reviewed the nomination of the Maysville Historic District to be included in the National Register of Historic Places. Based upon recommendations received from our staff, the Probate Court of Mobile County has no objection to this nomination.

Should you need anything further, please do not hesitate to contact Mike Avery, Records Supervisor, at (251)574-6063.

Sincerely,

Don Davis
Judge of Probate

/kt





08/29/2013

We, Frank Pace and Barbara Pace,
support the Maysville, Historic District
in Mobile, Al nomination to the
National Register of Historic Places.

Sincerely,

Property:
1300 Leo St.
Mobile, Al

~~Frank Pace~~
Frank Pace

~~Barbara Pace~~
Barbara Pace