National Register of Historic Places Continuation Sheet

Section n	umber Page	·	
	SUPPLEMENTARY I	LISTING RECORD	
	NRIS Reference Number: 91001796	Date Listed:	12/20/91
	Herrick, Lemuel D., House Property Name	Jackson County	MISSISSIPPI State
	Historic Resources of Pascagoula, Multiple Name	MS	
for	This property is listed in the Na Places in accordance with the att subject to the following exceptio notwithstanding the National Park in the nomination documentation. Signature of the Keeper	ached nominations, exclusions,	n documentation or amendments,
	Amended Items in Nomination:	=======================================	
	Section No. 8		
	This nomination was amended to ad Commerce as areas of significance as the period of significance. B to reflect the building's importa Lemuel D. Herrick.	and to show the oth of these ch	e years 1899-1904 anges were made
	These changes were confirmed by p $(1/9/92)$.	hone with the M	ississippi SHPO

DISTRIBUTION:

National Register property file Nominating Authority (without nomination attachment)

National Register of Historic Places Registration Form

This form is for use in nominating or requesting determinations of eligibility for individual properties or districts. See instructions in *Guidelines* for Completing National Register Forms (National Register Bulletin 16). Complete each item by marking "x" in the appropriate box or by entering the requested information. If an item does not apply to the property being documented, enter "N/A" for "not applicable." For functions, styles, materials, and areas of significance, enter only the categories and subcategories listed in the instructions. For additional space use continuation sheets (Form 10-900a). Type all entries.

1. Name of Property			
nistoric name	Herrick, Lemuel D H	louse	
ther names/site number Ertz-Berger, Elizabeth House			
2. Location			
street & number	2503 Pascagoula Str	eet N	not for publication
city, town	Pascagoula		vicinity
state Mississippicode	MS county J	ackson code s	9 zip code 3956
3. Classification			
Ownership of Property	Category of Property	Number of Res	ources within Property
x private	X building(s)	Contributing	Noncontributing
public-local	district	_1	3 buildings
public-State	site		sites
public-Federal	structure		structures
	object		objects
			3 Total
Name of related multiple property li	etina:	Number of con	tributing resources previously
Name of related multiple property li Historic Resources of Pa	sung. Scagoula, MS		
		listed in the Na	tional Register0
4. State/Federal Agency Certif	ication		
Signature of certifying official Deputy State Histo State or Federal agency and bureau	ric Preservation Of	ficer	Date
In my opinion, the property In m	neets does not meet the Nation	nal Register criteria. 🔲 See	continuation sheet.
Signature of commenting or other off	icial		Date
State or Federal agency and bureau			
5. National Park Service Certif	ication		
, hereby, certify that this property is	3:	0.1	
entered in the National Register See continuation sheet. determined eligible for the Natio Register. See continuation sheet determined not eligible for the National Register.	nal	Afhier	/2-20-9
removed from the National Regi	ster		
	Signa	ture of the Keeper	Date of Action

6. Function or Use			
Historic Functions (enter categories from instructions) Domestic/Single Dwelling	Current Functions (enter categories from instructions Domestic/Single Dwelling		
DOMESTIC/ DINGLE DWOLLING			
7. Description			
	Matairle (and an annia de annia de annia de annia		
Architectural Classification (enter categories from instructions)	Materials (enter categories from instructions)		
	foundation Brick		
Queen Anne	walls Weatherboard		
	roof		
	other N/A		

Describe present and historic physical appearance.

The Lemuel D. Herrick house is situated facing east near the southeast corner of a large, slightly irregular and slightly sloping lot. There is a stream entering the lot on the west side, just in from the southwest corner, and angling over to the north property line about four—tenths of the way down from the northwest corner. There are three frame outbuildings, one small and two good—sized, on the south side of the lot, about two—thirds of the way back. The front lawn is somewhat above sidewalk level, access to the house being up a few concrete steps to the front walk. Large, old live oaks are on each side of the front yard, and a bank of large azaleas follows the south property line.

A relatively ambitious two-story frame house set about three feet off grade, it has many typical elements of the Queen Anne style. The house is clad with weatherboards, except for a flaring band of shingles that runs around most of the house between first floor ceiling level and the bottom of the second floor window sills. It sits on brick piers, the spaces between these under the front porch infilled with brick. Typical sash is one-over-one.

The basic massing is a gable end facing the street, joining a cross gable at about the center of the building. The east and west walls of the cross dormer extend down from attic to first floor. At the front, however, only the top of the gable is exposed. About seven feet down, a roof pitches down, its eave projecting slightly over the front two-story wall of the house. On the north end of this front wall is a gabled open porch on the first and second floor; at the southeast corner, an octagonal tower extends from second floor up to a third floor level; it becomes free-standing as it rises past the roof. The tower extends down to the first floor. A front porch starts at the entry porch on the north end, running in a circular pattern around the tower, and then into the south gable end mass.

On the south, a set of masonry steps goes up to the front porch, the steps butting flared masonry retaining walls whose top surfaces curve down. The wood porch floor probably rests on brick piers; a screen of lattice runs from porch floor to grade, concealing the fascias and piers. At the top of the stairs, an entry bay is framed by columns set on a boxed, paneled wood base; the columns are paired, except that at the northeast corner there are three on an L-shaped base. A handrail with heavy turned balusters is set onto the column bases. Going south from the entry bay, the paired columns repeat at various varying spacings, supporting the roof above.

National Register of Historic Places Continuation Sheet

Section number Page	

Above the entry bay, the soffit beam is a deep, simply boxed element, and projecting above it is the boxed eave, which receives a flaring shingle roof above. The soffit beam continues south a short bay to a pair of columns, where it miters into a bracketed soffit that follows the curving porch around the tower. The roof above the entry is flared to meet the railing of the porch above the entry. The flaring shingles come down from the north and south sides of this porch, and continue along the front wall of the house, around the base of the tower, and on. Over the bracket porch fascia there is a flat roof area, probably clad with sheet metal. A railing might well have run along the outside of this roof.

The second floor porch above the entry has paneled bases with paired and triple columns and railing matching those below, and lining up with them but all truncated, as the flaring shingled roof band terminates above the level of the second floor porch. The roof above this porch is supported on a simple soffit beam. On the front gable, a drip extends across the top of the soffit beam and above, the gable is covered with woodwork with a large, very low relief sunburst design occupying most of the field. Verge boards, with half-circular jigsaw shape at the bottom corners, are set out a foot or so, and project past the eaves. The eave line of the porch is maintained on the main front pitching roof, at the bottom of another band of flaring shingles at the tower, and around the building to the side of the south cross gable. At the tower, the top story is slightly smaller than the second, and the flaring shingle band again rises above the attic floor level. The roof of the tower is circular, in plane from the projecting eave fascia up to the ornamental metal weather vane which caps this conical form, the cone itself flaring out slightly at the bottom.

The front wall of the house is clad with weatherboards; the millwork of the tower on first and second floors is simple flat wood surrounding the sash, except that at the top level, recessed panels have low relief swag ornaments.

At the small exposed front gable of the main ridge, the verge projects and is simply boxed. The wall surface is flat boards, making a paneled effect on each side of a louvered opening with a peaked top.

The front door has a single-light transom over a pair of doors, each with a single light over wood panels below. Openings to the porch are one-over-one double-hung sash. On the second floor porch there is a door with top glass panel. On the front wall of the house between the porch and tower is an opening making a perfect circle, except for a sill across the bottom. It has two mullions with a one-over-one double-hung sash in-between and fixed glass side lights. The tower has one-over-one double-hung sash on the second floor, and on the third, sash with border of small panes next to the frames and large panes within.

National Register of Historic Places Continuation Sheet

0		7		3
Section	number		Page	

On the south side of the house, behind the angled, southwest face of the tower, the mass of the main house runs west twelve feet or so, with above it the south pitch of the main roof. It then is met by a clipped gable projecting south. The angled sides are the width of a typical one-over-one double-hung sash with frame; the south face has three similar double-hung sash, except that the two outside sash are about half the width of the center. Above a large fascia runs the width of the gable, joining the eave boxing that goes around the house. The gable verges project, and the verge board projects down past the boxed verge and terminates at the bottom in a round shape. There is a round-headed frame set with louver slats at the attic level. Past the clipped gable end, the main house continues west ten feet or so, then turns north a short distance, then turns west again a little, then turns north, making the southwest corner of the house.

At the south side first floor level, the porch, making its circle around the tower, runs straight west and then turns to run north to meet the east side of the clipped gable mass. The exterior of this portion of the porch is filled in with weatherboards from porch soffit and porch floor, and has two small variant double-hung sash. There is another wall of later infill on the porch, running from the joint at curved and straight porch roof to the west side of the southwest tower sash.

At the clipped gable end, running from below the second floor sash sills is a flaring shingled projection, similar to that on the open porch above the front door. It dies on a slightly projecting boxed eave, and runs following the projections at the house mass, to the southwest corner of the building, where it turns and extends north. Typical double-hung windows are at the first floor level of the bay window created by the clipped gable form. No sash occurs past this.

On the second floor level, turning the southwest corner, the wall of the house extends about half the width of the elevation, turns east about seven feet, then north again twelve feet or so, and turns east. The south half of this wall has a simple hipped roof with ridge lower than the roof above. The north half again is under a hipped roof, here the back pitch of the main roof. A later infill in this once-open corner has a shed roof, modern six-over-six double sash facing west, and four-over-two double-hung sash facing west. Along this wall, the tapered shingled band continues across the entire wall in a northerly direction, then turns and runs east. It butts the southwest mass and the new infill at the northwest corner, suggesting that there was a small open porch at the corner. The first floor back wall, which has areas of weatherboards removed, has a four-panel wood door near the northwest corner.

The building is simplest on its north side. The main house walls run straight from northwest to northeast corners, the side of front porch continuing this line. The main roof is above, with its projecting eaves, and the flared shingled band set below second floor sash continues. However, this is interrupted by a slightly projecting mass about fifteen feet wide, which runs from the first floor up through the second. It is roofed by

National Register of Historic Places Continuation Sheet

Section number	Page 4	

an extension of the main roof, which falls over typical eave projections that return to die against the weatherboarded walls on the east and west sides. Below the eaves, the second floor wall surface is clad with shingles that flare out like the adjacent band and line up at the bottom with this band. Close to the corners on the north wall of this projection at second floor level, there are two small round frames, clipped at the bottom for sills and with slightly recessed window sash. Lining up with these are two small sash of colored glass with a border of small panes, resembling the third floor tower sash.


The complexity of the exterior details is carried throughout the interior. Entrance is into an elaborate living/stair hall containing a complex patterned ceiling, a high wainscot, wood mantel, elaborate wood stairs, and narrow wood floors. To the south of the hall is the living room with its tower and dining room, joined by a pair of sliding doors. Ceilings in these rooms are pressed tin with relief metal leaves in the corners. The two rooms have different wood wainscots, and that in the dining room is higher than in the living room. The living room mantel is on the wall common to the hall, and the dining room mantel is on the west or rear wall, abutting a built-in cupboard. The front porch where it wraps down the south side of the house abutting the living room was enclosed during the 1920s and converted into a bathroom. Across the rear of the house is the kitchen, pantry, laundry, and access to the rear stairs, which are integral with the main front stairs.

Upstairs are bedrooms. The hall has a very low wainscot, almost like a base. Ceilings are wood.

The three Craftsman/Bungalows in the rear of the property are in very poor condition. The largest of the three is centered in the lot. It has wood siding, brick piers, a gable roof with knee braces, six-over-six double-hung windows, and various types of doors (fifteen-light, flush, etc.). The other two bungalows are located along the south property. The smallest one, closest to Pascagoula Street, is wood frame set on concrete piers, and has a shallow gable roof, and six-over-six double-hung windows. The other bungalow has wood siding, a gable roof, aluminum replacement windows, and brick piers. The three houses appear to date from the 1930s, and are non-contributing elements.

National Register of Historic Places Continuation Sheet

Section number ____7 Page ____5



2503 PASCAGOLLA

8. Statement of Significance		
Certifying official has considered the significance of this prop	erty in relation to other properties:	
Applicable National Register Criteria A B C	D	
Criteria Considerations (Exceptions)	□D □E □F □G	
Areas of Significance (enter categories from instructions) Architecture	Period of Significance 1899	Significant Dates 1899
	Cultural Affiliation N/A	
Significant Person Lemuel D. Herrick	Architect/Builder John Stone	·

State significance of property, and justify criteria, criteria considerations, and areas and periods of significance noted above.

2503 Pascagoula is significant within the context of Pascagoula's residential elements, being the most elaborate remaining example of the Queen Anne style in the city, and one of the best in Jackson County. The house is also significant for its association with Lemuel D. Herrick, postmaster of Scranton.

Old photographs indicate there were once quite a few very elaborate Queen Anne homes in Pascagoula, but most have been lost over the years. This house is one of only six surviving two-story Queen Anne houses in the city, and is by far the most complex and ostentatious example of the style. The elaborate wooden architectural details of the Queen Anne were tailor-made to the area's lumber industry. The complex roof with its multiple gables, tall slender chimney and conical roof tower; the variety of windows-Queen Anne, double-hung, and circular; the decorative wood shingles, garlands, and porch railing with its paired columns set on pedestal, combine to create an outstanding example of domestic Queen Anne architecture and a showpiece of the products of local lumber industry.

The house was designed by John Stone and built for Capt. Lemuel D. Herrick, who acquired this lot in 1899. The Southern Manufacturer in 1899 carried an illustration of the house with the following caption: "The above is a fair cut of Captain L.D. Herrick's handsome home to be erected in the suburbs of Scranton on Pascagoula street. This part of town is rapidly building up with handsome homes. Mr. Hughes, Captain Herrick's business partner, is also to have a handsome home built very much on the same style as Captain Herrick's, on the adjoining piece of land." The same publication wrote of Herrick:

One of the most liberal minded thinkers in regard to the future prospects of the Pascagoulas is Capt. Herrick. He has been the Deputy Clerk at this point since October 1898. For eight successive years he was Post Master here. He is a member of the firm of Hughes & Herrick and a Director of the Scranton State Bank. A prominent Mason, K. of P. [Knights of Pythian], Odd Fellow, and one of the first officers of the Commercial Club. Capt. Herrick came to Scranton in 1887 from the North. He was one of the most active members of the Deep Water Commission that did such good work at Washington securing the appropriation [\$317,600 for port improvements—see cover nomination]."

National Register of Historic Places Continuation Sheet

Section number _	8	Page .	2	

An 1897 advertisment lists Hughes & Herrick as purveyors of dry goods, notions, boots and shoes, groceries, feed and grain, and offering furniture on the installment plan. The company was described in The Southern Manufacturer:

Though only three years in existence this firm has forged to the front as one of the most prominent factors in the commercial world of the Pascagoulas. . . . They deal extensively in general supplies, for mill men, bay men, and fisher men, using a warehouse adjoining their store and one of the river front which is convenient to their schooner trade."

By 1904 Herrick had changed associates, and the clothing store of Herrick & Jacobs on Delmas Avenue was listed as a "Merchant Tailor" and "Men's and Boy's Outfitters." Herrick's business ventures were obviously very successful, based on the unparalleled stature of his house. He owned the house but a short time, however, selling it to a family member, C.L. Lendinger, in 1904. Subsequent owners include Belle F. Griffin, 1942; Jacob J. Geraci, Jr., 1973; Peter Ertz-Berger, 1977; and Jordan Daughtery, 1982.

9. Major Bibliographical References	
For Bibliography See Context Statement.	:
	<u>.</u>
	:
	· ·
	:
	NA See continuation sheet
Previous documentation on file (NPS):	M/EL Oco continuation sheet
preliminary determination of individual listing (36 CFR 67)	Primary location of additional data:
has been requested	State historic preservation office
previously listed in the National Register	Other State agency
previously determined eligible by the National Register	Federal agency
designated a National Historic Landmark	Local government
recorded by Historic American Buildings	University Other
Survey # recorded by Historic American Engineering	Specify repository:
Record #	Specify repository.
10. Geographical Data	
Acreage of propertyLess than one acre.	
UTM References	
A 11,6 35,04,7,5 3,35,96,7,5	$B \bigsqcup \bigsqcup_{i} \bigsqcup_{$
Zone Easting Northing	Zone Easting Northing
	N/A See continuation sheet
	- Coo Continuation Sheet
Verbal Boundary Description	
Lot 3, part lot 2, SQ 3, V. Delmas Heirs Tr	act.
	N/A See continuation sheet
Boundary Justification	hat has historically been associated with
The boundary includes the entire city lot the property.	nat has historically been associated with
	[№] 74See continuation sheet
11. Form Prepared By	·
name/title Robert J. Cangelosi, Jr., Architect	
organization Koch and Wilson Architects, A Prof.	Corp. date 3 June 1991
street & number 1100 Jackson Avenue	telephone504/581-7023
city or town New Orleans	state LA zip code 701