United States Department of the Interior National Park Service

National Register of Historic Places Inventory—Nomination Form

See instructions in How to Complete National Register Forms Type ali entries—complete applicable sections

1. Name

historic	Union H	Banking Comp	any Bu	ilding						
and/or con	nmon	Coffee (County	Bank						
2. L	ocat	ion								
street & n	umber 1	02 Peterson	Avenue	-			N	/A	not for public	cation
city, town	Dougla	S		N/A vi	cinity of	ooni	gressional district			
state	Georgi	а	code	013	county	(Coffee		code	069
3. C	lassi	ficatio	n							
Category distric X buildi struct site object	ct ng(s) <u></u> ture N /A	wnership public private both ublic Acquisiti in process being conside		Status X occup unocc work in Accessibl X yes: re yes: u no	upied n progress e estricted	<u> </u>	esent Use _ agriculture _ commercial _ educational _ entertainment _ government _ industrial _ military	· -	museum park private re religious scientific transport other:	:
4. 0	wne	r of Pro	peri	tv						
		······································					<u> </u>			
name	Coffee	County Bank,	Ken B	. Lanier	, Presider	nt				
street & nu	umber	Lock Drawer	: 431					·	ran	
city, town	De	ouglas		N <u>/A</u> vie	cinity of		state	Geo	orgia 3153	3
5. Le	ocati	ion of L	ega	I Des	criptie	on				
courthouse	e. reaistrv	of deeds, etc.	Supe	rior Cour	ct					
street & nu		Coffee Cou	inty Co	urthouse						
city, town		Douglas					state	Ge	eorgia 315:	33
	enre	sentati	on i	n Exis	stina 9	Sur				
					<u>sting</u>		10,5			
title Nor	ne				has this pro	perty b	een determined e	ligib	le? yes	<u>x</u> 1
date						N/A	_ federal sta	ite	county	loc
			None	e						

city, town

4.....

1982

7. Description

Condition		Check one
excellent	deteriorated	unaitered
x good	ruins	$\underline{\mathbf{x}}$ altered
fair	unexposed	

Check one _____ original site ____ moved date _

Describe the present and original (if known) physical appearance

The Union Banking Company Building, constructed in 1910-1911, is a three-story commercial building with a parapet roof, located on a corner lot in downtown Douglas, Coffee County, Georgia. Retail stores and a bank are located on the first floor with office space above.

The structure is rectangular, framed with reinforced concrete posts and beams, with poured concrete floors and a brick facing laid in Flemish bond. The bank has two finished facades facing the street with the main entrance to the bank at the curved southwest corner of the building. Walls are detailed with groups of windows outlined with bricks and brick spandrels highlighted with decorative brick work in the shape of circles and diamonds. The main trabeated entrance has double doors with an entablature and tall, narrow side lights formed by decorated pilaster-like supports, all of cast concrete. A segmentally arched entrance providing street access to the second floor is located near the building's northwest corner. The bank's brick parapet-cornice is highlighted with a terra-cotta shield at the rounded corner and ten terra-cotta gargoyles with garlands delineating the building's The original storefronts have been remodeled, and all windows on the bank's street bays. fronts have been replaced, those in the bank lobby with large aluminum frame windows and those on the second and third floors (originally three-over-one double hung wood sash) with one-over-one aluminum sash. The original double wood doors at the main entrance have been replaced with aluminum frame doors.

The interior spaces of the building are arranged around the concrete structural system. The bank lobby is a large room in the southwest corner. In recent renovations (1968-69 and 1973-74) it was extensively remodeled, but the original exposed ceiling beams, pier capitals and deep molded cornice are still in place under the new dropped accoustical tile ceiling. During the same remodeling, the first floor bank area was expanded to include two of the four store spaces and the second floor offices were also adapted for use by the bank. An elevator and a dropped accoustical tile ceiling on the second floor were added at this time. Some rearrangement of space has occurred on the second floor, but the basic layout of offices opening off a central stairhall remainsnearly intact. On the presently unused third floor, many of the original finish details are still in place. Offices have ceilings with exposed concrete beams, plaster walls with chair and picture rails, and hallway doors with transoms above. The eastern section of the third floor was originally one large room, approximately 40' by 60', used as a meeting area by various clubs. At some point it was subdivided with frame partitions.

The bank is located on a corner lot in the historic commercial area of downtown Douglas. It has an alley along its northside and abuts the building to the east. The Union Banking Company Building extends to the sidewalk line and has no landscaping. It is situated at an important corner, diagonally across from the courthouse.

8. Significance

	Areas of Significance—C archeology-prehistoric archeology-historic agriculture architecture art commerce communications	community planning conservation economics education engineering exploration/settlement	Iiterature military music philosophy politics/government	 religion science sculpture social/ humanitarian theater transportation other (specify)
Specific dates	1910-1911	Builder/Architect	R. N. McEachren, bui	lder

Statement of Significance (in one paragraph)

The Union Banking Company Building is historically significant in the areas of architecture and commerce. Architecturally, the bank is a fine example of an early-twentieth century commercial structure in Douglas. It combines typical commercial style design elements of the period with unique decorative features, in particular the unusual terracotta gargoyles. The very early use of reinforced concrete for the building's framing system makes it technically innovative. In terms of commercial history, the building is significant as the home of two banks important to the development of Douglas and Coffee County. A bank has been located on this important corner across from the courthouse since 1899 when the Union Banking Company built its first structure on the site.

The bank is an excellent example in Douglas of the type of commercial style building which was becoming popular nationwide in the early years of the twentieth century. Its restrained, rather streamlined exterior detailing which accentuates its underlying structure, its use of brick facing and terra-cotta ornament, and its interior finish details are all typical of this style. However, the main corner entrance and the unique gargoyles, although fabricated of modern materials, are somewhat reminiscent of late-Victorian commercial architecture. The building is stylistically an interesting transitional building. Structurally, the bank is innovative. Its concrete skeleton and poured concrete floors document a construction technique that first came into general use during the ten years before it was employed here. The bank was the first building so designed in the surrounding area, and it attracted widespread interest while under construction. The choice to use this new method of construction resulted from the burning of the previous bank building and the desire of the Union Banking Company's officers to replace it with a fireproof structure.

The Union Banking Company Building is associated with two banks important to the economic development of Coffee County and is therefore significant to the commercial history of the area. Douglas, until the arrival of two railroads in 1895 and 1898, was a country hamlet. With the railroads came business, schools and general development. The Union Banking Company, established in 1897 as Douglas's first bank, served Douglas as it expanded from a village to a prosperous railroad town. The original bank building constructed in 1899 burned and was replaced by the present structure in 1911. In 1930 the Union Banking Company closed its doors, a victim, along with many other banks across the country, of the Depression. The Coffee County Bank was established in 1931 to provide the community once again with needed banking services. Located in the Union Banking Company Building, which it later bought, the Coffee County Bank grew steadily during the Depression years and continues to serve the area today.

9. Major Bibliographical References

1

Shipp, William R. "Historic Property Information Form: Coffee County Bank." November 1981. On file Historic Preservation Section, Georgia Department of Natural Resource, Atlanta.

10. Geog	raphical Data			÷		
	l property 0.16 acres Douglas North, Georgia		Quadrangle	șçale <u>1:24000</u>		
UMT References A 1 7 3 2 4 2 Zone Easting C 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	9 0 3 4 8 7 2 8 0 Northing	B Zone D	Easting	Northing		
		┍ ┍ ┍				
	escription and justification lot presently and histo	rically associa	d property inclu ated with the bar	nk building.		
		••••	· ·	I		
	counties for properties over	lapping state or c	ounty boundaries			
state N/A	code	county		code		
state	code	county		code		
11. Form	Prepared By	·				
name/title Caroly	yn Brooks, National Reg	ister Researche	er			
	ric Preservation Sectio ia Dept. of Natural Res		ate October 12.	. 1982		
	0 Washington St. S. W.		elephone - 404-656-	-2840		
city or town At	lanta	S	tate Georgia	30334		
12. State	Historic Pres	ervation	Officer Ce	rtification		
The evaluated significa	ance of this property within the	state is:				
nat	tional state	_x local				
As the designated State Historic Preservation Officer for the National Historic Preservation Act of 1966 (Public Law 89– 665), I hereby nominate this property for inclusion in the National Register and certify that it has been evaluated according to the criteria and procedures set forth by the National Park Service.						
State Historic Preserva	ation Officer signature 🛛 🔎	1: LH C	? Lun			
	Elizabeth A. Lyon ric Preservation Office	r	date / d	129/82		
For NPS use only						
I hereby certify th	hat this property is included in t	Entered in the	data	12/10/82		
Receiver of the Natio	Jogen	National Regist	date or			
			•			
Attest: Chief of Registration			date			

NPS Form 10-900-a (3-82)				o. 1024-0018)-31-84
United States Departme National Park Service	nt of the Interior		For NPS use only	
National Registe Inventory—Nom	er of Historic Plac ination Form	ces	received date entered	
Continuation sheet Significan	ce Item number	8	Page	2

The architectural and commercial significance of the Union Banking Company Building supports its National Register eligibility under National Register Criteria A and C. The establishment of banking services, first at a time when the community was expanding from a village to a prosperous town and later in response to desperately needed banking services during the Depression, were important events in Douglas' commercial history. They support eligibility in terms of Criteria A. The building is a good representative example in Coffee County of the type of commercial style architecture which became popular in the early years of the twenetieth century. It is a transitional building, advanced in its early use of a reinforced concrete framework yet harking back to late Victorian styles in some of its exterior detailing. These features support its eligibility in terms of Criteria C.

UNION BANKING COMPANY BUILDING Douglas, Coffee County, Georgia

FIRST FLOOR PLAN

Scale: Not to scale North: **^**



UNION BANKING COMPANY BUILDING Douglas, Coffee County, Georgia

SECOND FLOOR PLAN

Scale: Not to scale North:



UNION BANKING COMPANY BUILDING Douglas, Coffee County, Georgia

THIRD FLOOR PLAN

Scale: Not to scale North: **↑**



SELLERS STREET



WARD STREET (U.S. HWY 221)

COFFEE COUNTY COURTHOUSE (U.S. HWY 441)

PETERSON AVENUE

UNION BANKING COMPANY BUILDING Douglas, Coffee County , Georgia PLAT MAP

Source: Tax Map D-1 Scale: 1" = 50' North: Property Boundary: MADISON AVENUE