United States Department of the Interior National Park Service

National Register of Historic Places Inventory—Nomination Form

See instructions in How to Complete National Register Forms Type all entries—complete applicable sections

Name 1.

historic Galloway - Williams House

and or common

Location 2.

427 East Fortification Steet street & number

same

code

N/A not for publication

code

49

city, town Jackson N/A_ vicinity of

county

state Mississippi

3. Classification

Ownership

Category							
	district						
<u>X</u>	building(s)						
	structure						

_ site

_ object

_ public _X_ private both **Public Acquisition** in process $\overline{N/A}$ being considered Status ____ occupied ____ unoccupied X__ work in progress Accessible _X_ yes: restricted ____ yes: unrestricted

no

28

Present Use agriculture X commercial educational _ entertainment _ government __ industrial _ military

Hinds

. . .

__ museum __ park _ private residence _ religious _ scientific transportation ____ other:

4. **Owner of Property**

Kenneth G. Humer name

KLH Indus., Suite 360, Deposit Guaranty Plaza, 210 E. Capitol Street street & number

city, t	own Jackson	N/A vicinity of	state	Mississippi
5.	Location of	Legal Description		

courthouse, registry of deeds, etc. Hinds County Courthouse - Office of Chancery Clerk

Pascagoula Street street & number

city, town

Jackson

Representation in Existing Surveys 6,

has this property been determined eligible? title yes _X_ no Statewide Survey of Historic Sites


date 1983

depository for survey records Mississippi Department of Archives & History

city, town Jackson federal ____ state ___ county ___ local

Mississippi

state



s Barra a statut a como

received SEP | 2 1985 date entered

7. Description

Describe the present and original (if known) physical appearance

The exterior form of the Galloway-Williams House consists of a hip-roofed block with chamfered bays projecting from the main mass and fronted with gables displaying fine jigsawn verge boards. Exterior walls are covered with novelty siding; gables are filled with alternate rows of staggered butt shingles and vertical reeded board. Two gables have circular punch work gable vents. The porches are supported by turned columns and have an abundance of Eastlake-inspired spindles at the eave line and turned balusters at the hand rail. The entry doors on the east and south sides are especially notable, showing Queen Anne detailing in an aedicula motif surrounding the door glass, with a horizontal raised panel having similar detailing located below it. Windows have louvered shutters except in rooms added at rear.


The house has been enlarged several times by additions to the rear, as is shown in the enclosed sketches based on Sanborn Insurance maps. These additions are generally compatible. Only one set of aluminum casement sash is objectionable.

Significant interior features are the Eastlake-inspired spindle work and Colonial Revival motifs of the framed opening with paneled wainscot level dividers located in the central hall (and shown in photograph number 4 of 4). Also notable are the fine Colonial Revival fireplace surrounds, mantles, and over-mantles, paneled doors, door and window casings, and base molding.

A turn-of-the-century iron fence still remains at the southeast corner of the site as does an iron hitching post.

The Galloway-Williams House is currently undergoing a rehabilitation.

8. Significance



Statement of Significance (in one paragraph)

The Galloway-Williams House is one of Jackson's finest examples of a Queen Anne Style cottage with Eastlake-inspired ornament. Both its external and internal integrity are almost completely intact. It is one of only a very few such structures remaining in an area of Jackson which was once dominated by similar late-ninteenth-century residences. Its site is an especially important one, directly across Fortification Street from the fastidiously restored, Gothic Revival Manship House, one of Jackson's most notable historic structures.

The Queen Anne Style was popular during the last two decades of the nineteenth century. Salient features are irregular massing, steep roofs, and a wide variety of highly textured materials. The Eastlake mode was a Queen Anne variation which arrived from England and was characterized by the spindle-work and other wood details popularized by Charles Eastlake in his furniture designs. The Galloway-Williams house exhibits form and detail which place it in the mainstream of both of these developments.

The Galloway-Williams House was built as the home of Annie Jane Jones Manship and her husband, Albert Galloway. They were the parents of Effie Lee Galloway, who later became Mrs. Frank Scott. The Galloways, the Scotts, and members of their families have been notable in the building and development of Jackson <u>(Jackson Landmarks,</u> compiled by the Junior League of Mississippi [Jackson, Mississippi], 80).

9. Major Bibliographical References

۲

Jackson Landmarks. Compiled by the Junior League of Jackson, Mississippi. Jackson, Mississippi, 1982.

10. Geog	graphica	l Data				
Acreage of nominate	ed property2	2 acres				
Quadrangle nameJackson, Mississippi UTM References		sissippi	Quadrangle scale 1:24000			
A 115 Zone Easting	4 17 19 3 15 7 Northin		B Zone	Easting	Northing	
			▫∟∟			
E└──┘└╵╵└			F L			
G L J L J L			н			
/erbal boundary d	lescription and	justification			en i standi	
See Continua	tion Sheet	المراجع والمعار	; .*		ene ona carto	
List all states and	counties for pr	operties overla	apping state or co	ounty boundaries		
state N/	А	code	county		code	
state N/	A	code(county		code	
	Prepar	ed By				
				<u></u>		
name/title Mich	ael Fazio					
rganization N/A			date August 28, 1985			
treet & number	P. O. Box 28	70	tel	lephone (601) 3	23-3451	
ity or town ^{Missis}	sippi State		sta	ate MS		
2. State	e Histori	c Prese	ervation (Officer C	ertification	
he evaluated signifi	cance of this prop	erty within the s	tate is:			
n	ational	state	X_ local			
As the designated St (65), I hereby nomina (ccording to the crite (tate Historic Preser	ate this property for eria and procedure	or inclusion in th es set forth by th . /	e National Register	and certify that it ha vice.	t of 1966 (Public Law 89– Is been evaluated	
itle Deputy Sta	ate Historic]	Preservation	Officer	date S	September 4, 1985	
For NPS use only						
I hereby certify	that this property	is included in th	e National Register			
Xu	loug	yen_	Entered in the National Regist	date	10-10-85	
Keeper of the Na	tional Register	V				
Attest:				date		
Chief of Registra	tion					

United States Department of the Interior National Park Service

National Register of Historic Places Inventory—Nomination Form

For fills sum only received Sale antipres


Galloway - Williams House Continuation sheet Geographical Data Item number 10 Page

VERBAL BOUNDARY DESCRIPTION AND JUSTIFICATION

Commence at the point of intersection of the East R.O.W. of West Street and the South R.O.W. of Fortification Street; run thence East along Fortification Street 246.5 feet to the Point of Beginning; run thence East 54.46 feet to a point at the beginning of a curve; run thence 26.07 feet along a curve to the right; said curve having a radius of 15 feet; run thence along the West line of Congress Street. South 09 degrees 34 minutes West 126.66 feet to an iron pin; thence run North 82 degrees 23 minutes West 70.16 feet to an iron pin; thence run North 09 degrees 07 minutes East and parallel with the East R.O.W. of West Street 134.79 feet to the Point of Beginning.



1918 1946 & 1968 UPDATE SIMILAR - BASED UPON SANBORN MAPS



GALLOWAY-WILLIAMS HOUSE . JACKSON, MS.