Resource #

53

1. Name of Resource: Venable-Chase House

James Venable or James Chase

x Building

northeast of Shelbyville

Rte. 1, Box 56, Shelbyville, KY 40065

KY Landmark Certificate 3-11-71

Mult.Resource Area: Shelby County

8. Evaluation: National Register

Structure

West side of Ky 43, 2 1/2 miles

Local Landmark HABS/HAER

**KY Inventory** 12-21-70

[030]

Object

Other

2. Original Owner:

**Historic Site** 

6. Owner's Name:

7. Owner's Address:

9. Recognition & Date: Nat.Landmark

> Nat.Register Highway Marker

10. N.R.Status & Date:

District Name:

Thematic Name: 12. Historical Theme:

Secondary: Other:

Inventory forms.

Primary: Architecture

13. Statement of Significance:

11. N.R.Group:

Dr. Ronald Waldridge

5. Location:

3. Other Names:
Chevy Chase
4. Prehistoric Site

## KENTUCKY HISTORIC RESOURCES Individual Inventory Form

entor	y Form	Shelby	County
16.	Original Building Addition	ca. 1803 ?	[8]
17.	•		
	Antebellum Ver	nacular	[ 3V ]
18.	Architect/Builder:		
10	Unknown	· <del></del>	
19.	No. of Stories: 2	<del></del>	[2.0]
20.	Original Floor Plan:		[ ~~ ]
$\overline{21.}$	Center passage	) 	[CP]
	Single Pile Do	ouble Pile N.A	
44.			
$\overline{23}$	Gable, asphal Structural Material	t shing or Original	
20.	Brick	•	[B]
$\overline{24.}$	Exterior Material:		+
2 1.	Brick, Flemish	hond facade	l B i
25.	Foundation Materia	l:	
		d rubble (stuccoe	a0s 1
26.	Major Alterations:	None	<u> </u>
	Moved/Rebuilt	Other	
	$_{\rm X}$ Additions		
27.	Special Features:		
	None		
28.	Outbuildings:		
	Non-contribut:	ing	[NC]
29.	Original Function:		
	Residential/Do	omestic, sin, dw.	101A J
30.	Present Use:		f 1
01	As above Condition:	····	[01A]
31.			r - 1
20	Excellent	Yes	[ E ]
34.	Endangered:	No.	<del>x</del> _
		NO	
33.	Attach Photos:	and the second	
	Roll: Photo No	os: No. of Slide	es:
	13 15 - 1	9 1	
		- <b>-</b>	

County. It is the earliest recorded such structure in the county. The only other recorded earlier double-pile structure is the 14. History: Date of construction of original brick 1-story, 5-bay, single-pile, center-passage house is unknown. Land purchased by James Venable from John Pope in 1803. Capt. William Q. Morton owned property in 1833. Assumed that first brick house built between 1803-1833. James and Salvisa Chase probably transformed the 1-story house into a 2-story, double-pile house ca. 1840. This date appears in metal scrolls at the two front corners of the house at the eaves. Chases named property "Chevy 15. Source of historical information and/or contact

person: 1970 and 1979 Ky. Historic Resources

"Lovely Old Brick 'Chevy Chase' Once Drovers Inn." The Sentinel-News, Shelbyville, K-Y n.d.

This property is significant under criterion C as a well-preserved example of the 2-story, double-pile, center-passage plan in Shelby

34. Prepared by: C. Worsham
35. Organization: V. Shelby Co. Hist. Society
36. Date: April 1986
37. New Survey \_\_\_\_\_ Resurvey \_\_\_\_

# KENTUCKY HISTORIC RESOURCES Individual Inventory Form


Resource # 53

38.	UTM Point of Primary Building:	Zone	Easting	Northing	39. G	.I.S. Mod.	一一
	Quadrant: Shelbyville	<u>16</u>	<u>659190</u>	4233320	40. Co	oordi.Accuracy	[ ]
41.	UTM Points of Boundary (for N. R.	. eligibl	e sites only):		· ··· // / / · · · · · · · · · · · · ·		
	Α.		E	`			
	B	_	E				
	C	_	F				
42.	Total Acreage in Present Property	- ': 4 8	4 43. Acre	age included in	proposed N	I.R. boundary:	4 16
44.	Site Plan (and boundary description					wee 3	A
В	eginning at A, south 550' along	g a fen	ce & fenceli	ine to D	ZE-SWINC E	ZZ W. Same I	
	he northwest side of KY 43, the					non house Mike 1	Fence III
	long the north side of said road			11.	reg.	Postio 1	1 .
t	hence north along a fence 550'	to D,	thence				://,-
е	east along a fence 330! to the p	oint of	•	7	}		/:/:
С	origin. The boundaries were cho	sen to	•	1	1_		/: }
i	nclude the house and domestic	space		N			
е	nclosed by fences and set apar	t from					1
S	urrounding fields. There are 3	non-co	on-		Sal (C)		
	ributing outbuildings			}	0)/(3	(0)	
	though the nominated area contains	thron	non-contribut	} on a rank	3/1		
	buildings (ofmuch more recent con				120	1125	[ ]
	ese are located a short distance beh					1/ 08	ferm
	t be excluded from the boundaries w				7 6 3/ /		
	ationship of the house to its setting		1		\dn	ve /	
				( *	7 \		
	nt A is at the intersection of two f				·		>
	tern corner of the yard, and is 22 f	-	330 -				
the	northeastern corner of the barn.			cl	)	1	1.
							JB

### 45. Description and House Plan:

### Exterior:

Originally a 1 1/2-story, 5-bay, centerpassage, single-pile plan, raised to 2 stories and made double-pile ca. 1840, joint visible in west gable end, exterior chimneys on both gable ends, later 2story, 2-bay brick addition on east end, Flemish bond principal (south) facade, common bond on sides and rear, jack arches over 6/6 sash windows, stucco over coursed rubble foundation, 2story double portico on square posts, covered in aluminum siding, transom over panel tabet first floor door, transom and sidelights at second floor door, early stone steps leading up to concrete porch, horizontal barred cellar vents with stone jack arches, additions to rear (north) include modern 1-story porch over door and 1-story frame wing appended to the east wing and ex-



us.55

Resource #53

13. Statement of Significance:

(continued)

Old Stone Inn (Sh-1), a 1-story, stone double-pile building of ca. 1827. The house is also noteworthy as it illustrates the transformation of a 1-story, single-pile, center-passage plan into a major 2-story double-pile structure. The alterations and additions to the house have not affected its significance as a form in its period of significance: 1800-1840

14. History:

(continued)

Chase." A log structure to the north of the house (now demolished) and believed to pre-date the brick structure is said to have served as a "drovers inn." The site is located on the old Shelbyville-Christiansburg Road which was an early north-south pioneer route through the county. Later this became an important transportation route for livestock and other produce that was shipped by train from Christiansburg in northern Shelby County.

45. Description and House Plan:

(continued)

tending beyond the house to the north.

#### Interior:

Little but the plan and the opening locations remains of the original interior with some moldings around doors. Mantels have been removed from east wing, mantel in northwest & south east room has plain pilasters and panelled tablet, mantel in southwestroom has fluted Ionic pilasters and a panelled central tablet, pair of doors located in original rear wall of passage retain transom and give access to rear passage of double-pile which contains a spiral staircase in the northwest corner, windows have splayed reveals and panelled aprons, unusual Greek molding with bull's eye corner blocks in ca. 1840 addition, no connection between east wing and main block at second floor level.

#### Outbuildings:

Non-contributing outbuildings consist of a barn, a hen house, and a storage building of recent construction.

The nominated property includes one contributing building and three non-contributing buildings.