United States Department of the Interior National Park Service

National Register of Historic Places Inventory—Nomination Form

For NPS use only received APR 1 1 1984 date entered

See instructions in *How to Complete National Register Forms* Type all entries—complete applicable sections

1. Name

historic	Hall	1 Octago	nal Hou	se		7		
and/or common	Walter Cr	ull Farm	ı					
2. Locat		NOTR	inshi	ille				
street & number	R.R. 3 (C Road 300)	county Rd	. 900,	1/4 mile e	east of County	<u>N/A</u>	not for pub	lication
city, town	Rushville	Vic.	_X_ vic	inity of			<u></u>	
state	Indiana	code	018	county	Rush		code	139
3. Class	ificatio	n						
district _X_ building(s) structure	wnership public { private both ublic Acquisit in process being consid N/A		itatus X_ occupi unoccu work ir ccessible X_ yes: re yes: ur no	upied 1 progress 2 stricted	Present Use agriculture commercial educational entertainmer government industrial military		museur park private religiou scientif transpo other:	residence s ic
4. Owne		perty	/					
name	Gary Crul	1						
street & number	1332 Bron	wyn Aven	ue					
city, town	Columbus		N/Avic	inity of	st	ate	Ohio	43204
5. Locat	ion of L	.egal	Dese	criptio	n			
courthouse, registry	of deeds, etc.	County	Recorder	's Office				
street & number		Rush Co	unty Cou	irthouse				
city, town		Rushvil	le		st	ate	Indiana	46173
6. Repre	sentati	ion in	Exis	sting S	Surveys			
title		N/A		has this prop	perty been determine	d eligibl	e? y	es <u>X</u> no
date				·	federal	state _	county	local
depository for surve	ey records	N/A						
city, town					st	ate		

7. Description

Condition

excellent	deteriorated	unaltered
X_good	ruins	X altered
fair	unexposed	

Check one

X original site

__ moved

N/A

date ____

.....

Check one


Describe the present and original (if known) physical appearance

The Hall-Crull House is a two story frame structure located in a rural area near Rushville, Indiana. The original section of the home was constructed in 1855 and featured an octagonal plan. A later addition to the house, located towards the rear of the structure, was constructed in 1865 along more conventional lines. Although currently covered with aluminum siding, the building's most important features, its octagonal style and its porch, remain plainly visible.

The main (south) facade of the house is given over completely to the recessed two-story porch. Both levels of this porch feature octagonal porch columns and balustrades with flat, paddle-like balusters. All of the other original facades not obscured by the 1865 addition contain a single pair of rectangular double-hung windows on each floor level. Historic photographs show that the building originally featured a plain frieze and modest scroll-cut cornice brackets, but these elements were lost when the siding was applied.

The four main rooms are located on each floor of the original octagonal section of the house. The living room, dining room, and first floor bedroom still feature fireplaces, as do two of the second-floor bedrooms. The 1865 addition contains the kitchen, bathroom, washroom, and a back porch. The home is situated on a heavily-wooded lot approximately 1/2 acre in area. A garage and barn are also located on this lot but both are relatively modern structures and are not included in this nomination.

8. Significance



Specific dates Circa 1855

Builder/Architect Unknown

Statement of Significance (in one paragraph)

The Hall-Crull House is architecturally important as a rare example of the octagonal style of domestic architecture which found favor for a brief period during the mid-19th century. The octagon style was popularized by Orton Squire Fowler's book, <u>A House for All, or the Gravel Walland Octagonal Mode of Building</u>, published in 1848, but the style was short-lived and had largely died out by 1860. The Hall-Crull House is one of less than a dozen of this type known to be extant in Indiana.

Beyond the rarity of its octagonal style, the Hall-Crull House is unusual because of its recessed porches. In his book, Fowler advocated large porches, preferably encircling the octagonal house. While most Indiana octagons were more restrained in this regard, it was normally the practice to build the porches as projecting elements. The unique recessed porches of the Hall-Crull House, while not in keeping with Fowler's suggestions, help make the unusual shape of the structure more apparent.

The Hall-Crull House was built around 1855 by William S. Hall, a cabinetmaker who was also involved in local politics. Although born in Rush County, Hall spent much of his youth in Cincinnati, working as an apprentice with his uncle, Joseph Hall. He returned to Rush County late in 1836 and established himself in business. In February, 1839, he was elected Justice of the Peace for Washington Township, serving in that capacity until 1847. In 1853 he was elected Trustee of Washington Township, and continued to hold this office until 1878, except for a short period during the mid-1860's when he served as a member of the State Legislature. As Trustee, he was instrumental in the development of the local school system, and caused the construction of many new school buildings.

In 1928, this structure became the residence of the Walter Crull family. Although in recent years the home has been used as a rental property, it is still owned by a descendant of Walter Crull.

9. Major Bibliographical References

See continuation sheet

<u>10. Geo</u>	ograpi	nical Data					
Acreage of nomin			ne acre				
Quadrangle name	<u>Mays Qu</u>	<u>adrangl</u> e		Quadrangle scale 1:24000			
JT M References							
Zone Eastin		4 4 0 0 3 9 0 Northing	B L L Zone Ea	asting	Northing		
			▫└⊥┘└				
			FLL				
			┍				
erbal boundar	y descriptio	on and justification	1				
		See continu	ation sheet				
ist all states a	and countie	s for properties ov	erlapping state or coun	ty boundaries			
state N/A		code	county		code		
tate		code	county		code		
1 For	m Pre	pared By			· · · · · · · · · · · · · · · · · · ·		
		parea by					
ame/title	Gary Cru	11					
rganization	N/A		date	Febru	ary 1, 1982		
treet & number	1332 Bro	nwyn Avenue	telep	hone 614/2	79-4983		
ity or town	Columbus		state	Ohio	43204		
2. Sta	te His	toric Pres	servation O	fficer C	ertification		
he evaluated sig	nificance of t	his property within th	ne state is:				
	n®ional	X state	local				
s the designated	State Histor	ic Preservation Office	er for the National Historic	Preservation Act	of 1966 (Public Law 89-		
			n the National Register and y the National Park Servic		s been evaluated		
	interna antu pi	ocedules sectoral b					
ccording to the c		icer signature	J. M. fide	m			
-	servation Off						
tate Historic Pre			n Officer	date	4-3-84		
itate Historic Pre	tate Histo	ric Preservatio	n Officer	date	4-3-84		
state Historic Pre ^{itle} Indiana St For NPS use c	tate Histo Daly	ric Preservatio	n the National Register	date			
state Historic Pre t ^{le} Indiana St For NPS use c	tate Histo only tify that this	ric Preservatio	n the National Register				
tate Historic Pre tle Indiana St For NPS use of I hereby cer	tate Histo only tify that this out	property is included i	n the National Register	date date	4-3-84 5/14/84		
tate Historic Pre ^{tle} Indiana St For NPS use c	tate Histo only tify that this out	property is included i	n the National Register				

NATIONAL REGISTER OF HISTORIC PLACES INVENTORY-NOMINATION FORM

Continuation Sheet Hall-Crull House Item No. 9

Page 1

An Architectural and Historical Study of Washington, Union, and Noble Townships, Rush County, Indiana. Indianapolis: Indiana Junior Historical Society, 1970.

History of Rush County, Indiana. Chicago: Brant and Fuller, 1888.

Peat, Wilbur. <u>Indiana Houses of the 19th Century</u>. Indianapolis: Indiana Historical Society, 1962, Plate 95.

Waggener, Bob and Emy. <u>A Sampler Book of Rush County Landmarks</u>, Homer, Indiana: Bob and Emy Waggener, 1966.

Hall-Crull House

Item No. 10

Beginning at a point 30' due east of the southernmost corner of the east facade, then proceeding north to a point 235' north of the north right-of-way line of County Road 900; thence west 100'; thence south to the north right-of-way line of County Road 900; thence east along that right-of-way line to a point 30' east of said house; thence north to the point of beginning.