

**United States Department of the Interior  
National Park Service**

For NPS use only

**National Register of Historic Places  
Inventory—Nomination Form**

received

date entered

See instructions in *How to Complete National Register Forms*  
Type all entries—complete applicable sections

**1. Name**

historic Le Conte Memorial Lodge

and/or common Le Conte Memorial Lodge

**2. Location**

street & number Yosemite Valley

\_\_\_ not for publication

city, town Yosemite National Park \_\_\_ vicinity of

state California

code 06

county Mariposa

code 043

**3. Classification**

Category	Ownership	Status	Present Use	
___ district	<input checked="" type="checkbox"/> public	<input checked="" type="checkbox"/> occupied	___ agriculture	___ museum
<input checked="" type="checkbox"/> building(s)	___ private	___ unoccupied	___ commercial	___ park
___ structure	___ both	___ work in progress	<input checked="" type="checkbox"/> educational	___ private residence
___ site	<b>Public Acquisition</b>	<b>Accessible</b>	___ entertainment	___ religious
___ object	___ in process	<input checked="" type="checkbox"/> yes: restricted	___ government	___ scientific
	___ being considered	___ yes: unrestricted	___ industrial	___ transportation
		___ no	___ military	___ other:

**4. Owner of Property**

name Sierra Club

street & number 530 Bush Street

city, town San Francisco \_\_\_ vicinity of

state California 94108

**5. Location of Legal Description**

courthouse, registry of deeds, etc. National Park Service Western Regional Office

street & number 430 Golden Gate Avenue, Box 36063

city, town San Francisco

state California

**6. Representation in Existing Surveys**

1) List of Classified Structures Inventory  
 title 2) National Register of Historic Places has this property been determined eligible? \_\_\_ yes \_\_\_ no  
 date 1) 1975  
 2) 1975 \_\_\_ federal \_\_\_ state \_\_\_ county \_\_\_ local

depository for survey records National Park Service

city, town Washington

state D. C.

---

## 7. Description

---

<b>Condition</b>		<b>Check one</b>	<b>Check one</b>	
<input type="checkbox"/> excellent	<input type="checkbox"/> deteriorated	<input type="checkbox"/> unaltered	<input type="checkbox"/> original site	
<input type="checkbox"/> good	<input type="checkbox"/> ruins	<input checked="" type="checkbox"/> altered	<input checked="" type="checkbox"/> moved	date 1919
<input checked="" type="checkbox"/> fair	<input type="checkbox"/> unexposed			

---

### **Describe the present and original (if known) physical appearance**

LeConte Memorial Lodge is a small Tudor revival building at the base of the cliffs in Yosemite Valley. The plan of the building is a "Y" shape. The main portion of the building is rectangular in plan. Two small wings, each 8'x12', radiate out from the main section at 45 degree angles from the northeast and northwest corners. A small concrete porch at the entrance to the building fills in the space at the top of the "Y"--the area between the two wings and the main section of the building. The porch is hexagonal in plan and is bordered by two stone walls that extend out from the gable end walls of the wings. The parapet walls and the low stone walls bordering the porch are finished with concrete caps.

The building is constructed of rough-cut granite laid in cement mortar in a roughly coursed ashlar pattern. The foundation is stone. The roof of the main section is predominantly a gable roof, but formed into a three-sided hip on the front elevation emphasizing the entrance to the symmetrical building. The two wings flanking the entrance have gable roofs, well-defined at the gable ends by tall parapet walls. The roofs of the wings are considerably lower than that of the main section. All roofs have broken pitches at the eaves and are finished with wood shingles.

The interior of the building is divided into the central meeting room with a small room in each of the two wings. The upper level of the meeting room takes up the largest space. The lower level, several steps down, forms an inviting nook in front and to the sides of the fireplace. The massive fireplace is centered on the south wall, opposite the entrance. Benches and bookshelves flank both sides of the fireplace. The two small rooms to the northeast and northwest of the central meeting room are used for storage and office space. All floors are concrete.

The interior of this building has a highly unusual exposed roof structure of hammer beams supporting scissors trusses. The hammer beams rest on engaged stone piers built into the walls. The roof is the dominant architectural feature on both the interior and exterior. The steep pitches and shapes of the roofs, and the parapet walls all emphasize the extreme verticality of the structure. On the interior the verticality is reinforced by the exposed roof structure and the chimney that extends from the fireplace to the roof.

The casement windows throughout the structure are wood frame with original brass hardware. Windows in the main room are nine-light, paired casements with three-light transoms above.

# 8. Significance

Period	Areas of Significance—Check and justify below			
<input type="checkbox"/> prehistoric	<input type="checkbox"/> archeology-prehistoric	<input type="checkbox"/> community planning	<input type="checkbox"/> landscape architecture	<input type="checkbox"/> religion
<input type="checkbox"/> 1400–1499	<input type="checkbox"/> archeology-historic	<input checked="" type="checkbox"/> conservation	<input type="checkbox"/> law	<input type="checkbox"/> science
<input type="checkbox"/> 1500–1599	<input type="checkbox"/> agriculture	<input type="checkbox"/> economics	<input type="checkbox"/> literature	<input type="checkbox"/> sculpture
<input type="checkbox"/> 1600–1699	<input checked="" type="checkbox"/> architecture	<input type="checkbox"/> education	<input type="checkbox"/> military	<input type="checkbox"/> social/
<input type="checkbox"/> 1700–1799	<input type="checkbox"/> art	<input type="checkbox"/> engineering	<input type="checkbox"/> music	<input type="checkbox"/> humanitarian
<input type="checkbox"/> 1800–1899	<input type="checkbox"/> commerce	<input type="checkbox"/> exploration/settlement	<input type="checkbox"/> philosophy	<input type="checkbox"/> theater
<input checked="" type="checkbox"/> 1900–	<input type="checkbox"/> communications	<input type="checkbox"/> industry	<input type="checkbox"/> politics/government	<input type="checkbox"/> transportation
		<input type="checkbox"/> invention		<input type="checkbox"/> other (specify)

**Specific dates** 1919 - Present      **Builder/Architect** John White

**Statement of Significance (in one paragraph)**

LeConte Memorial Lodge is a highly unusual structure for a national park setting. Its Tudor revival architecture and strong European tendencies are found in no other building in the National Park System. John White, the architect of the building, was greatly influenced by the work of his brother-in-law, Bernard Maybeck. Both believed that a building's site and choice of construction materials had a strong influence on the building's design. To them, buildings were designed to be a part of the landscape in which they were constructed. The emphasis on verticality in LeConte Memorial Lodge, for instance, reflected the steep pitches of the cliffs surrounding Yosemite Valley. Also, White and Maybeck both believed that the architectural design of a building was determined by the materials of which it was built. If a building were to be constructed of stone, for instance, the building should look like a substantial stone structure. If the roof structure were wood, the natural materials should be exposed on the interior. To them, architectural interest was derived not from decorative detail, but from exposed structure. Whatever was of structural importance became the feature of ornament. White, Maybeck, and others of the Bay Area school also agreed with English critic and aesthete John Ruskin's interpretation of architecture as frozen music. The repetition of architectural elements--such as the engaged piers, hammer beams, and scissors trusses--were like the rhythm in music or meter in poetry. White's LeConte Lodge is a unique building for a national park: it is a transitional structure of strong European roots combined with the revolutionary way that Bay Area environmental designers used building materials.

The building is of regional significance in the area of conservation as the principal foothold of the Sierra Club in the mountains from which they took their name. The Sierra Club was first conceived as an informal mountaineering club for people connected with the University of California, Stanford University, and other interested parties who wanted to explore the Sierra Nevada and mountainous regions of the world. When the Sierra Club was formally chartered in 1892, its directors discussed locating Club headquarters in Yosemite Valley. They finally decided on a San Francisco headquarters, but were allowed by the

# 9. Major Bibliographical References

See attached.

# 10. Geographical Data

Acreeage of nominated property Less than 1

Quadrangle name Map of Yosemite Valley

Quadrangle scale 1:24,000

### UTM References

A 

1	1	2	7	2	8	4	0	4	1	7	9	8	9	1
Zone			Easting				Northing							

B 

Zone			Easting				Northing							

C 

Zone			Easting				Northing							

D 

Zone			Easting				Northing							

E 

Zone			Easting				Northing							

F 

Zone			Easting				Northing							

G 

Zone			Easting				Northing							

H 

Zone			Easting				Northing							

### Verbal boundary description and justification

The boundary is shown as the dotted line on the enclosed map.

### List all states and counties for properties overlapping state or county boundaries

state N/A code county code

state N/A code county code

# 11. Form Prepared By

name/title Laura Soulliere Harrison, Architectural Historian

organization National Park Service

date 1985

street & number P. O. Box 728

telephone 505-988-6787

city or town Santa Fe

state New Mexico

# 12. State Historic Preservation Officer Certification

The evaluated significance of this property within the state is:

national  state  local

As the designated State Historic Preservation Officer for the National Historic Preservation Act of 1966 (Public Law 89-665), I hereby nominate this property for inclusion in the National Register and certify that it has been evaluated according to the criteria and procedures set forth by the National Park Service.

State Historic Preservation Officer signature

title date

For NPS use only

I hereby certify that this property is included in the National Register

date

Keeper of the National Register


Attest:

date

Chief of Registration

**United States Department of the Interior  
National Park Service**

**National Register of Historic Places  
Inventory—Nomination Form**



Continuation sheet

Item number 7

Page 2

Small windows in the parapet walls have shutters, with half moons sawn into them to allow in some daylight. The centered entrance door is wood and shaped to fit the Tudor arch in the stonework. The door is flanked by nine-light casement windows.

The building was first constructed during the summer and fall of 1903 at the base of Glacier Point, adjacent to Camp Curry. Approximately fifteen years later Mother Curry, proprietress of Camp Curry, approached the Sierra Club about the possibility of moving the structure at her own expense so that she could expand her camp operation. She proudly provided reasonably priced tent frame cabins for visitors to the Valley. Demand for inexpensive accommodations had far outstripped the numbers she could accommodate in the available space she had. The Sierra Club finally agreed to moving the building to a site a short distance west of the original location. Gutleben Brothers Construction Company, hired to move the building, dismantled the roof structure and as much of the original stonework as they could. Their German stonemason and a few other workers rebuilt the lodge according to the original plans on the new site. The building reopened during the summer of 1919.

New doors were added to the wings in 1921, and shelves were constructed for storage in one of the side rooms that same year. In recent years, new lights were suspended from the roof beams. The Boston Ivy which grew on the stone masonry was either removed or died over the years.

**United States Department of the Interior  
National Park Service**

**National Register of Historic Places  
Inventory—Nomination Form**

For NPS use only  
received  
date entered

Continuation sheet

Item number 8

Page 2

California State Commission to establish a public reading room and information center in Yosemite Valley where people could get information on the mountains-- how to reach them, flora and fauna, etc. They set up headquarters in a small wood frame cottage in the Yosemite Valley in 1898. Following the death of charter member Joseph LeConte--noted geologist, original member of the University of California faculty, and sponsor of Sierra club outings to the Yosemite region--the Club decided to build a structure in his memory. LeConte Memorial Lodge was constructed with contributions raised from the faculty and staff and the University of California and Stanford University. Architect John White donated his services.

The building was moved in 1919, as noted in Section 7. In both locations it functioned as the location of the Sierra Club's LeConte Memorial lectures and other naturalist activities preceding the development of National Park Service programs. It also served as the place where the Sierra Club disseminated information to the public and garnered support for their conservationist activities. Part of the Sierra Club Library was placed in the building. The building is still used as a meeting place for programs sponsored both by the National Park Service and the Sierra Club. The Sierra Club still maintains the mountain library and club information bureau for use by park visitors.

**United States Department of the Interior  
National Park Service**

**National Register of Historic Places  
Inventory—Nomination Form**

For NPS use only  
received  
date entered

Continuation sheet

Item number 9

Page 1

Adams, Ansel, "LeConte and Parsons Memorial Lodges," Sierra Club Bulletin, Volume XI, Number 2 (January, 1921).

Adams, Ansel, "LeConte Memorial Lodge -- Season 1921," Sierra Club Bulletin, Volume XI, Number 3.


Phil Gutleben to Superintendent John C. Preston, Yosemite National Park, June 12, 1964, from Yosemite National Park Research Library.

"Reports of Committees," Sierra Club Bulletin, Volume XII, Number 4 (1927).

"Secretary's Report," Sierra Club Bulletin, Volume V, Number 2.

Sierra Club Bulletin, Volume V, Number 1 (January, 1904).

Sierra Club Bulletin, Volume XI, Number 1 (January, 1920).



HOUSKEEPING  
CAMP

Le Conte  
Lodge

--- LANDMARK BOUNDARY  
LE CONTE MEMORIAL LODGE  
YOSHITE NATIONAL PARK