
National Register of Historic Places Inventory—Nomination Form



See instructions in *How to Complete National Register Forms*Type all entries—complete applicable sections

1. Nam	<u>e</u>			j	
historic	Montgomery	Street	School School		
and/or common	Emma Dolfin	ger Sch	001		
2. Loca	ation				
street & number	2500-06 Montgomery Street			_NA not for publication	
city, town	Louisville		NA_ vicinity of	congressional district	3 & 4
state	Kentucky	code	021 county	Jefferson	${\sf code}^{-111}$
3. Clas	sification	1			
Category districtX building(s) structure site object	Ownership public private both Public Acquisition NA in process being consider	on .	Status XX occupied unoccupied work in progress Accessible XX yes: restricted yes: unrestricted no	Present Use agriculture commercial _XX educational entertainment government industrial military	museum park private residence religious scientific transportation other:
4. Own	er of Pro	pert	у		
name	Trustees of	Portla	nd Avenue Church	of Christ	
street & number	2500 Portla	nd Aven	ue		
city, town	Louisville		NA vicinity of	state	Kentucky 40212
5. Loca	ition of L	ega	Descripti	on	
courthouse, regis	stry of deeds, etc.	Jeff	erson County (Ky	.) Courthouse	
street & number		531	W. Jefferson St.		
city, town		Loui	sville	state	Kentucky 40202
6. Repr	esentati	on ir	n Existing	Surveys	
title Kentucky	Historic Resou	rces In	ventory has this pr	operty been determined e	elegible? yes _X no
	st 1980				ate county local
depository for su	rvey records	eritage	Division, Depar	tment of the Arts	27. 20.010
city, town	F	rankfor	t	state	Kentucky 40601

7. Description

excellent deteriorated unaltered X	eck one _ original site _ moved date
------------------------------------	--

Describe the present and original (if known) physical appearance

Montgomery Street School is located on a residential street in the Portland area of Louisville's West End. About one mile west of the school is the Portland Historic District (National Register, February 1980). Most of the houses near the school are modest, one or two-story residences dating from the nineteenth century. Though many of the homes are in poor condition, a concentrated effort has been made recently by the neighborhood to rehabilitate homes in the immediate area.

The school is a two-story, red brick, Renaissance Revival building which was painted brown years ago. All four walls are pierced by round-arched openings with brick voussoirs, evenly spaced and slightly recessed behind the wall surface. They number one per bay in both stories, except above the main entry where there is a pair of arched openings. The original, double-hung windows had wooden frames, rounded upper sashes and multiple panes. These were replaced in 1977 by metal-frame rectangular windows and the arches were covered over. However, the original openings are intact both inside and out.

The main entry is located in the center of the five-bay facade facing Montgomery Street. Originally, tall double doors were topped by a fanlight. Probably in the early 1900s, shorter doors, sidelights and a multi-light transom were added. The fanlight still remains.

Stone belt courses encircle the building below both stories. A simple frame cornice is accented by brick corbeling below it.

A two-story arch on the east side of the building contains a side entry and a fixed, multi-pane window above. The rear wall has two arched entries. A concrete fire escape has been constructed at the rear of the building.

When first built, the school was nearly square, with four rooms of equal size on each floor. Additions made to the rear before 1900 increased the number of rooms to twelve. The new additions closely matched the original building in exterior appearance.

A large addition on the west side dates from 1912. Also two stories and constructed of red brick, this addition is similar in style to the older building, but its arches are somewhat wider and now contain paired windows. It is attached to the original school building by a narrow corridor.

The school underwent extensive renovation in 1977. The original floor plan is largely intact, as are the floors and tongue-and-groove wainscoting. The walls have been stuccoed.

A long, one-story frame building is attached to the rear of the 1912 addition. It is a former World War II barracks that now contains the school cafeteria. (See Map 3.)

There are five other frame buildings and a brick boiler room on the school property, but they are not part of this nomination.

8. Significance

Period prehistoric 1400–1499 1500–1599 1600–1699 1700–1799 _X 1800–1899 _X 1900–	Areas of Significance—C archeology-prehistoric agriculture architecture art commerce communications		ng landscape architectur law literature military music nent philosophy politics/government	science sculpture social/ humanitarian theater
Specific dates	1857; 1912	Builder/Architect	Zeigler and Seaman-bui	lders

Statement of Significance (in one paragraph)

the state of the state of the state of

Montgomery Street School is one of two remaining antebellum schoolhouses in the city of Louisville. Designed in a modified Renaissance Revival style popular during this period, the school is a significant example of the educational facilities in Louisville in the mid-nineteenth century.

Construction of the school began late in 1856 and was completed in the spring or summer of 1857. The fact that a new school was needed so near the Portland School (some ten blocks away) is an indication of the population growth of this area following the incorporation of the town of Portland into the city in 1837. Originally called the High Street (Northwestern Parkway) School, by 1870 it was known by the name of the street where it really stands. The school was renamed for Emma Dolfinger, a teacher in the school system, in the 1920s. Since 1977, it has been used as a private grade school.

It is possible that the school was designed by Isaiah Rogers and Henry Whitestone, well known architectural partners who executed numerous works during this period, including the other surviving schoolhouse, the Fifth Ward School. There are certainly enough stylistic similarities between the two structures to suggest a common architect. The recorded minutes of the School Board meetings of 1855-57 refer to plans submitted by Rogers and Whitestone for a number of proposed schoolhouses. But it is not entirely clear from these records that Montgomery Street building was among the Rogers and Whitestone proposals. The minutes do give the carpenters of the project as Zeigler and Seaman, who also worked on the Fifth Ward School about the same time.

The state of the s

9. Majo	or Bibliographic	al Referen	ces	
First Re	eport of the Board of Educ hn P. Morton & Co. (1913). of the School Board Meeti	ation of Louisvil	lle, Kentucky.	
10. Ge	ographical Data	UM NOT V		
Acreage of nomi Quadrangle nam UMT References	nated property 0.59 acres New Albany, Ind.	ACTEAGE NOT	VIII Dangle	scale 1:24000
	5 9 6 0 4 2 3 6 4 4 0	B Zone D H H	Easting	Northing
Verbal bounda	ry description and justification - see co	ntinuation sheet	-	÷
List all states	and counties for properties ove	erlapping state or co	unty boundaries	
state	code	county		code
state	code	county		code
11. For	m Prepared By			
name/title	Hugh B. Foshee / Arc	hitectural Histon	rian	
organization .	Louisville Landmarks C	ommission dat	te November 1,	, 1981
street & number	727 W. Main Street	tei	ephone (502) 58	37-3501
city or town	Louisville	sta	te Kentucky 40)202 .
12. Sta	te Historic Pres	ervation (Officer Co	ertification
The evaluated sig	gnIficance of this property within the	_		
665), i hereby no according to the	national state d State Historic Preservation Office minate this property for inclusion in criteria and procedures set forth by eservation Officer signature	the National Register a	and certify that it has	s been evaluated
For HCRS used I hereby de	Alstane formationly that this property is included in least the property is included in least 1990 and	The state of the s	date 3	131/83 5/4/82

Form No 10-300a (Hev. 10-74)

UNITED STATES DEPARTMENT OF THE INTERIOR NATIONAL PARK SERVICE

NATIONAL REGISTER OF HISTORIC PLACES INVENTORY -- NOMINATION FORM

FOR NOOLIGE ONLY	146
FOR NPS USE ONLY	
RECEIVED	
RECEIVED	
DATE ENTERED	

Montgomery Street School Louisville, Jefferson County, **CONTINUATION SHEET Kentucky**


ITEM NUMBER

PAGE

10

Beginning at a point on the southwest corner of 25th and Montgomery Streets, thence west following the south right-of-way line of Montgomery Street 160' to a point, thence south and parallel to 25th Street 90' to a point, thence west and parallel to Montgomery Street 65' to a point in the west property line of City Block 5-F, Lot 55, thence south following said property line 50' to a point, thence east and parallel to Montgomery Street 225' to a point in the west right-of-way line of 25th Street, thence north following said line 140° to the point of beginning, being a part of City Block 5-F, Lots 55 and 56 of the City of Louisville. (See Sanborn Map 3)


The boundary as described comprises the original schoolhouse, the 1912 addition and the cafeteria building. Three other "portable" classrooms and a brick boiler house, all detached structures, are located on the school property but are not included within the boundary of this nomination.



MONTGOMERY STREET SCHOOL 1870

Montgomery Street School Louisville, Jefferson County, Kentucky


Photo 5. Copy of engraving of school in 1870, original source unknown.



PLAN OF PORTLAND - D.B. Y. P. 188 - (E 185,180,184 & 185 CHANGED PLAN OF PORTLAND - 1828) Montgomery Street School Louisville, Jefferson County, Kentucky

Jefferson County Real Estate Atlas (1968)

Map 2. Real Estate Atlas



Montgomery Street School Louisville, Jefferson County, Kentucky

Sanborn Map Co. Pelham, N.Y. (1974)

Map 3. Sanborn Map, vol. 3,
p. 372.
Scale: 1"=100'
Nominated area shown in red.