

United States Department of the Interior
National Park Service

For NPS use only

National Register of Historic Places
Inventory—Nomination Form

received OCT 19 1987

date entered

NOV 20 1987

See instructions in *How to Complete National Register Forms*
Type all entries—complete applicable sections

1. Name

historic Levi B. Frost House

and or common Barnes Tavern

2. Location

street & number 1089 Marion Avenue NA not for publication

city, town Southington — vicinity of Marion

state CT code 09 county Hartford code 003

3. Classification

Category	Ownership	Status	Present Use
<input type="checkbox"/> district	<input type="checkbox"/> public	<input checked="" type="checkbox"/> occupied	<input type="checkbox"/> agriculture
<input checked="" type="checkbox"/> building(s)	<input checked="" type="checkbox"/> private	<input type="checkbox"/> unoccupied	<input type="checkbox"/> commercial
<input type="checkbox"/> structure	<input type="checkbox"/> both	<input type="checkbox"/> work in progress	<input type="checkbox"/> educational
<input type="checkbox"/> site	Public Acquisition	Accessible	<input type="checkbox"/> entertainment
<input type="checkbox"/> object	<input type="checkbox"/> in process	<input checked="" type="checkbox"/> yes: restricted	<input type="checkbox"/> government
	<input type="checkbox"/> being considered	<input type="checkbox"/> yes: unrestricted	<input type="checkbox"/> industrial
	NA	<input type="checkbox"/> no	<input type="checkbox"/> military
			<input type="checkbox"/> museum
			<input type="checkbox"/> park
			<input checked="" type="checkbox"/> private residence
			<input type="checkbox"/> religious
			<input type="checkbox"/> scientific
			<input type="checkbox"/> transportation
			<input type="checkbox"/> other:

4. Owner of Property

name Joyce L. & William P. Yelenak

street & number 1089 Marion Avenue

city, town Southington — vicinity of Marion state CT

5. Location of Legal Description

courthouse, registry of deeds, etc. Southington Land Records, Town Clerk, Town Hall

street & number 75 Main Street

city, town Southington state CT

6. Representation in Existing Surveys

title See continuation sheet. has this property been determined eligible? yes no

date federal state county local

depository for survey records

7. Description

Condition		Check one	Check one
<input type="checkbox"/> excellent	<input type="checkbox"/> deteriorated	<input type="checkbox"/> unaltered	<input checked="" type="checkbox"/> original site
<input checked="" type="checkbox"/> good	<input type="checkbox"/> ruins	<input checked="" type="checkbox"/> altered	<input type="checkbox"/> moved date _____
<input type="checkbox"/> fair	<input type="checkbox"/> unexposed		

Describe the present and original (if known) physical appearance

The Levi B. Frost House is a Greek Revival frame 2-story 3-bay structure with its gable end facing east toward the street. (Photograph 1) It is located on Marion Avenue in the southwest corner of the Town of South-ington, where the neighborhood still retains a semblance of its rural character. Judd Brook runs easterly along the southern boundary of the property. The house, popularly called Barnes Tavern, is on the site of a tavern conducted by Asa Barnes¹ where Comte de Rochambeau twice was entertained.


The exterior of the house is covered by white clapboards and has narrow corner boards. Windows are fitted with black blinds. In the front elevation the recessed doorway, in the left bay, is flanked by plain pilasters that support a plain entablature with projecting cyma cornice. (Photograph 2) The two first-floor front windows, which are placed closer to one another than to the door, are tall, having nine tiers of four lights in single fixed sashes. At the second floor are three 12-over-12 windows. The windows have flat surrounds. The gable end is treated as a pediment with deeply recessed tympanum of clapboards in which there is a rectangular window. The peripheral glazing bars of the attic window are close to the frame, creating a pattern of two rows of four horizontal lights surrounded by a border of small lights. Two brick chimneys rise from the roof line, one about one-third of the way back, the second close to the rear wall.

The south elevation has six 12-over-12 windows on the first floor and six on the second, although they are differently spaced. A historic photograph shows, at the first floor, a door between the first and second windows from the rear, and, at the second floor, the absence of the second window from the front. (Photograph 3) On the north elevation, there are five windows at the first floor and four at the second. (Photograph 4) There is a 1-story ell at the rear, partially covering one of the second-floor windows while leaving two 12-over-12 windows clear. The rear gable end is not treated as a pediment and has two small windows. (Photographs 4, 5)

On the interior the front entrance has 5-paneled door and panels under the side lights, the whole in a molded surround. (Photograph 6) In the stairway rising against the south wall square pickets support a simple handrail that terminates in a volute. While the north front room does not have a fireplace, the room behind the hall does. (See floor plan.) This fireplace and its chimney were removed at an unknown date by a former owner and replaced in 1985. Floor boards in front of the fireplace show signs of fire damage as does the beam in the chimney base below. (Photograph 7)

In the south wall of the third room the surround is still in place for the former exterior door. Its band molding is different from that of the front door. (Compare Photographs 6 and 8.) The rear room has a

**United States Department of the Interior
National Park Service**



**National Register of Historic Places
Inventory—Nomination Form**

Levi B. Frost House, Southington, CT

Continuation sheet

Surveys

Item number 6

Page 1

Historical and Architectural Survey
of the Town of Southington

1986

x local

Connecticut Historical Commission
59 South Prospect Street
Hartford

CT

Census of Old Buildings

c. 1930s

x state

State Library
231 Capitol Avenue
Hartford

CT

State Register of Historic Places

1987

x state

Connecticut Historical Commission
59 South Prospect Street
Hartford

CT

United States Department of the Interior
National Park Service

National Register of Historic Places
Inventory—Nomination Form

Levi B. Frost House, Southington, CT

Continuation sheet

Description

Item number 7

Page 1

For NPS use only

received

date entered

wainscotting of horizontal boards, much nicked and gouged, and a well-worn chestnut floor. The stone hearth of the fireplace is partially covered at one end by a floor cut on the diagonal for the entrance to the kitchen in the ell. (Photograph 9) Since more than a foot of the hearthstone is covered, the covering floor with the diagonal cut presumably is an alteration. At the same time a related alteration may have removed a section of the chimney stack that included an oven with front wall opening; the possible existence of an oven is consistent with the original length of the hearthstone and the size of the chimney base.

On the second floor the plan does not provide a hall, with the consequence that the circulation pattern is heavy in the central room. There are no fireplaces on the second floor. At the top of the front stairway pine floor boards run east-west and the trim has a band molding. In the central room chestnut floor boards run north-south. (Photograph 10) In the rear room the floor boards, chestnut, again are laid east-west, but the trim is flat. (Photograph 11) Most doors have four recessed panels but one has four raised panels and shows the scars from strap hinges. On the north wall in the second room there is a post visible. In the basement, the walls are fieldstone, apparently all laid at the same time. There is no vertical joint line to suggest otherwise. There is sign of a wide former basement entry on the south wall east of the former first-floor door, and there is an existing door leading to stone steps at the southwest corner. There is a narrow cellar under the ell, connected to and part of the main basement. Supporting joists for the ell are tree trunks with bark intact, indicating that the narrow ell is old. The attic is one long space over the entire house. Roof framing uses purlins and diagonal braces. (Photograph 12) The south purlin is one continuous beam, 50 feet long. The north purlin was the same, but has been broken and repaired. Shingles originally were wood, then slate, and now wood again.

In the rear there is a 2-story frame barn, old, with vertical siding (Photograph 13), which contributes to the historic significance of the property.

The house was badly damaged by a fire in 1836. In careful examination it has proven to be impossible to determine with assurance what if any existing fabric pre-dates 1836.

1. Barns was the 18th-century spelling. Barnes with an e is first noted in Southington Land Records of 1825, volume 12, page 72.

8. Significance

Period	Areas of Significance—Check and justify below			
<input type="checkbox"/> prehistoric	<input type="checkbox"/> archeology-prehistoric	<input type="checkbox"/> community planning	<input type="checkbox"/> landscape architecture	<input type="checkbox"/> religion
<input type="checkbox"/> 1400-1499	<input type="checkbox"/> archeology-historic	<input type="checkbox"/> conservation	<input type="checkbox"/> law	<input type="checkbox"/> science
<input type="checkbox"/> 1500-1599	<input type="checkbox"/> agriculture	<input type="checkbox"/> economics	<input type="checkbox"/> literature	<input type="checkbox"/> sculpture
<input type="checkbox"/> 1600-1699	<input checked="" type="checkbox"/> architecture	<input type="checkbox"/> education	<input type="checkbox"/> military	<input type="checkbox"/> social/
<input type="checkbox"/> 1700-1799	<input type="checkbox"/> art	<input type="checkbox"/> engineering	<input type="checkbox"/> music	humanitarian
<input checked="" type="checkbox"/> 1800-1899	<input type="checkbox"/> commerce	<input type="checkbox"/> exploration/settlement	<input type="checkbox"/> philosophy	<input type="checkbox"/> theater
<input type="checkbox"/> 1900-	<input type="checkbox"/> communications	<input type="checkbox"/> industry	<input type="checkbox"/> politics/government	<input type="checkbox"/> transportation
		<input type="checkbox"/> invention		<input type="checkbox"/> other (specify)

Specific dates 1836

Builder Architect Unknown

Statement of Significance (in one paragraph)

Criterion C - Architecture

Criterion C - Architecture

The Levi B. Frost House is architecturally significant in Southington because it embodies the salient characteristics of the Greek Revival style, including recessed doorway flanked by side lights and pilasters, 3-bay front elevation, and pedimented gable in the temple form. It has been little altered since assuming its present form in 1836.

Architecture

In the Town of Southington there are some 46 Greek Revival-style houses. While all share the characteristics of being rectangular blocks with low pitched roofs, like temple roofs, with trabeated doors and windows and classical trim, they may be roughly divided into three types: the modest 1½-story structure, the conventional 2-story house with gable end toward the street in temple form, and the more elaborate 2-story house with pyramidal roof. The Levi B. Frost House is an example of the middle type.

Examples of the first and third types are relatively few in number. 1577 West Street, 1848, is a 1½-story house with gable end toward the street but the gable end is not treated as a pediment. The door is recessed with side lights in a fashion similar to that found in the Frost House. There are corner pilasters and, along the side elevations, rectangular windows in the frieze to light the low second story.

The more elaborate 2-story house with low pyramidal roof is represented by several examples. The Samuel Clark House, 67 West Street, 1840, has a 4-bay front elevation of flush boarding with hipped-roof portico to the left. The roof overhangs slightly, a feature which, with the hipped framing of the roof and the square bulk of the house, foreshadows the oncoming Italianate style. The Captain Samuel S. Woodruff House, 23 Old State Road, 1840, similar in mass and roof framing but with three bays, has lost some of its integrity through installation of replacement windows and the addition of a wide front porch. The Charles Cowles House, 1860, 131 West Main Street, is perhaps the most elaborate, having Corinthian columns in its front portico and tall Ionic columns in the porch of a recessed wing.

The Greek Revival-style type that is most common in Southington has a 3-bay front elevation under gable end treated as a pediment, such as the Levi B. Frost House. One of these structures, the Horace Webster Farmhouse, 577 South End Road, 1837, already is listed on the National Register of Historic Places (August 24, 1977). It differs from the Frost House in that

9. Major Bibliographical References

See Continuation Sheet.

10. Geographical Data

Acreage of nominated property 1.77

Quadrangle name Southington

Quadrangle scale 1 : 24000

UTM References

A

18	473020	4603680
Zone	Easting	Northing

B

Zone	Easting	Northing

C

--	--	--

D

--	--	--

E

--	--	--

F

--	--	--

G

--	--	--

H

--	--	--

Verbal boundary description and justification The nominated property is described at Southington Land Records, volume 352, page 281. The land is the land that has gone with the house for decades.

List all states and counties for properties overlapping state or county boundaries

state NA code NA county NA code A

state NA code NA county NA code NA

11. Form Prepared By

name/title David F. Ransom/Architectural Historian, National Register Coordinator edited by John Herzan,

organization _____ date March 24, 1987

street & number 33 Sunrise Hill Drive telephone 203 521-2518

city or town West Hartford state CT

12. State Historic Preservation Officer Certification

The evaluated significance of this property within the state is:

national state local

As the designated State Historic Preservation Officer for the National Historic Preservation Act of 1966 (Public Law 89-665), I hereby nominate this property for inclusion in the National Register and certify that it has been evaluated according to the criteria and procedures set forth by the National Park Service.

State Historic Preservation Officer signature 

title Director, Connecticut Historical Commission date October 14, 1987

For NPS use only

I hereby certify that this property is included in the National Register

National Register

date 11-20-87

Keeper of the National Register

Attach:

date

United States Department of the Interior
National Park Service

**National Register of Historic Places
Continuation Sheet**

Levi B. Frost House, Southington, CT

Section number 8 Page 1

it has corner pilasters and, in its tympanum, a semi-elliptical fanlight, which is a reminder of the outgoing Federal style.

The front elevation of the Frost House is a fine example of its type. The proportions of the components, the pitch of the roof, and the spacing of the fenestration all clearly bespeak the Greek Revival. While the house does not have corner pilasters nor columned portico, it does have a deeply recessed tympanum and rectangular window with stylistically correct muntin pattern. The recessed doorway is flanked by the expected plain pilasters and side lights, under plain frieze and projecting cornice cap. The tall first-floor windows are an anomaly since each is a single fixed sash. All the windows appear to be old but probably are replacements because 6-over-6 configuration would be expected in the 1830s, rather than the small panes of 12-over-12.

The interior of the front part of the house also demonstrates the characteristic Greek Revival plan of a hall in which the stairway rises on the left and a large front room is on the right. The detailing of the stairway treads, risers, railing, and handrail all appears to be original.

In the proportions of its ground plan the Frost House is not characteristic of the Greek Revival style nor of domestic architecture generally. It is too long for its width. The circumstance probably is somehow related to the earlier existence of the house as Barnes' Tavern. The gouged dado and separate exterior door of the rear room make it a strong candidate to have been the taproom of a tavern, but the structural relationship in time of one part of the house to another, or its growth, is not clear. Suffice it to say that the Levi D. Frost House in the form it assumed after the 1836 fire is characteristic of the Greek Revival style and a significant example of the type in Southington.

Historical Note

Asa Barnes operated a tavern in his home on this site. Since he married Phebe Adkins in 1765 and, according to local legend, received his tavern license at about the same time, it may be that he built the structure, c. 1765. In any event, the tavern made its mark in history by virtue of visits that occurred in 1781 and 1782.

United States Department of the Interior
National Park Service

National Register of Historic Places
Continuation Sheet

Levi B. Frost House, Southington, CT

Section number 8 Page 2

While en route from Newport to join General Washington in North Castle, New York, troops led by Comte de Rochambeau arrived at French Hill, as it is still known, near Asa Barnes' Tavern on June 26, 1781. Rochambeau used the tavern as his headquarters. The main encampment was across the street to the north. The stop was recorded in the journal of an officer, who drew a map (copy attached) of the neighborhood showing the camp, Barnes' Tavern, and Judd Brook. Rochambeau remained on French Hill until June 30.¹

On the return journey from Yorktown Rochambeau again used the facilities of Barnes' Tavern on October 27, 1782.

After the Revolutionary War Asa Barnes continued to live in the house until his death on March 3, 1819. His son and heir, Philo Barnes, leased the property in August of that year to Micah Rugg and Levi B. Frost, both of whom were to become famous as pioneers in the development of the bolt industry, a field in which Southington led the nation. The specific purpose Rugg and Frost had in mind when leasing the Barnes property is not clear. Whether the tavern was still in operation is not known. Since the two men in the same year also leased land across the street on which to erect a dam on Judd Brook,³ the inference is that their intention was industrial. In 1820, Frost, alone, bought the house.⁴

Frost was a blacksmith by trade. His smithy stood south of the brook. There he specialized in shoeing oxen, but also fabricated hand-forged products, including bolts. In addition, he conducted a general mercantile business in farmers' supplies. In 1839 Rugg, with another partner, established a shop for the production of bolts in the neighborhood, further south on Marion Avenue. While in business for himself, he secured the first patent for mechanically trimming bolt heads.⁵ In 1842 Frost began the manufacture of bolts in a shop across the street from his house, doing business as L. B. Frost & Son.⁶ The firm originated the first lathe for turning bolt heads. In 1844 nuts made from old boiler plates processed cold without heat were added to the line. Its 1855 price list, copy attached, shows the growth in variety of products manufactured by the Frost shop. The firm continued in business until early in the 20th century.

There was a fire in the house in 1836, but the extent of the damage is unknown.⁷ After the fire the house was re-built for Levi B. Frost and assumed its present Greek Revival-style appearance. Frost died in 1865, but his family owned the house to 1913. An account of the dedication in 1912 of a monument erected to Rochambeau on French Hill, after which the principals fittingly enough were entertained at the Frost House on the site of Barnes' Tavern, reported that "The Frost [sic] house still retains the framework of the ancient tavern...."⁸ The WPA Census of Old Buildings form carries the comment "Front part burned at one time."

United States Department of the Interior
National Park Service

**National Register of Historic Places
Continuation Sheet**

Levi B. Frost House, Southington, CT

Section number 8 Page 3

1. One evening festivities were held at the tavern, which an officer also recorded, saying, "We found many Americans and some pretty women in our camp. The Comte de Charlus gave a big dinner for the prettiest ones, followed by a ball that lasted all night." See Harold C. Rice, Jr., and Anne S.K. Brown, eds., The American Campaigns of Rochambeau's Army, 1780, 1781, 1782, 1783, c vols. (Princeton: Princeton University Press, 1972), 1:248.
2. Southington Land Records, volume 10, page 563.
3. SLR 10/566.
4. In 1825 Frost bought from Barnes adjoining land with sawmill. (SLR 12/72) The sawmill with dam was still standing in 1925. (Snapshot in possession of W. P. Yelenak) The dam further confirms the interest in controlling the power source on this section of Judd Brook.
5. The nature of the relationship between Frost and Rugg is not clear, but in any event Rugg started out on his own. His business failed, and he went to work for Clark Bros. Bolt Co., which is still in business. The Frost company, then managed by Levi B. Frost's son Ira, bought Rugg's shop building, causing a family row. See E. S. Todd, Looking Back 100 Years in Southington (Southington, Clark Bros. Bolt Co., nd). Apparently Levi B. Frost and Rugg came to a disagreement. The front elevation of Rugg's shop, considered to be the first building constructed in the United States for the manufacture of bolts, is now at the Southington Historical Society.
6. One of the buildings of the company remains standing. Masonry along the brook for the dam also still is in place.
7. Heman R. Timlow, Sketches of Southington, Conn. (Hartford: Case, Lockwood & Brainard Co., 1875; reprint ed., Southington: Southington Historical Society, 1976) p. 563.
8. Minnie E. Wrinn, "Rochambeau Monument," The Southington News, August 23, 1935, pp. 1, 6.


**United States Department of the Interior
National Park Service**

**National Register of Historic Places
Inventory—Nomination Form**

Levi B. Frost House, Southington, CT

Continuation sheet Bibliography Item number 9

Page 1



Farmington Probate Records 8/18, 8/19.

Kitsen, Mary Lou, "Frenchman's Hill Remembered," Yankee, August 1969,
pp. 45-49.

100th Anniversary, 1854-1954. Southington: Clark Bros. Bolt Co., 1954 .

Rice, Harold C., and Brown, Anne S. K., eds. The American Campaigns of
Rochambeau's Army, 1780, 1781, 1782, 1783, 2 vols. Princeton:
Princeton University Press, 1972 .

Southington Land Records 8/506, 10/249, 10/563, 10/566, 12/73, 54/537,
67/158, 84/878a, 86/533, 193/454, 211/454, 218/165, 229/703, 352/281.

Southington Probate Records 7/270, 7/277, 26/540, 26/560.


Timlow, Heman R. Sketches of Southington, Conn. Hartford: Case, Lock-
wood & Brainard Co., 1875; reprint ed., Southington: Southington
Historical Society, 1976 .

Todd, E. S. Looking Back 100 Years in Southington. Southington, Clark
Bros. Bolt Co., nd .

Wilbur, W. R. History of the Bolt and Nut Industry of America. Cleveland
1905 .


Wrinn, Minnie E. "Rochambeau Monument," The Southington News, August 23,
1935.

8.^e Camp à Barnes's Tavern, le 26. Jan 1781. 13. mil de Français.



34 EIGHTH CAMP AT BARNES'S TAVERN, 1781

Harold C. Rice, Jr., and Anne S.K. Brown, eds., The American Campaigns of Rochambeau's Army, 1780, 1781, 1782, 1783, 2 vols. (Princeton: Princeton University Press, 1972), 1:232.





Measured drawing by
 Henry Ciccone
 March 1987



Levi B. Frost House
 Southington, CT
 First Floor Plan
 Photo key

N





Measured drawing by
 Henry Ciccone
 March 1987

10 ft.

N

↑

Levi B. Frost House
 Southington, CT
 Second Floor Plan
 Photo key ○➔

PRICE LIST OF CARRIAGE, TIRE & SPRING BOLTS,

MANUFACTURED FROM BEST REFINED IRON, BY
L. B. FROST & SONS,
(SOUTHINGTON, CONN.)
Post Office Address, MARION, CT.

1-4 Inch Carriage Bolts, TURNED HEADS.	5-16 Inch Carriage Bolts, TURNED HEADS.	3-8 Inch Carriage Bolts, TURNED HEADS.	7-16 Inch Carriage Bolts, TURNED HEADS.	1-2 Inch Carriage Bolts, TURNED HEADS.	1-3 Inch Fire Bolts, per 100	3-8 Inch Fire Bolts, per 100
1 1/2 in. \$2.00pr.100	1 1/2 in. \$2.35pr.100	2 in. \$3.30pr.100	2 1/2 in. \$5.25pr.100	2 1/2 in. \$7.75pr.100	1 1/2 in. \$1.05	2 in. \$2.50
1 3/4 " 2.00	1 3/4 " 2.35	2 1/4 " 3.40	3 " 5.50	3 " 8.00	1 3/4 " 1.05	2 1/4 " 2.65
1 7/8 " 2.05	1 7/8 " 2.40	2 3/4 " 3.50	3 1/4 " 5.75	3 1/4 " 8.35	2 " 1.10	2 3/4 " 2.60
2 " 3.10	2 " 2.45	3 " 3.60	4 " 6.00	4 " 8.70	2 1/2 " 1.15	3 " 2.70
2 1/4 " 2.15	2 1/4 " 2.53	3 1/2 " 3.70	4 1/2 " 6.25	4 1/2 " 9.05	3 " 1.20	3 1/2 " 2.80
2 1/2 " 2.20	2 1/2 " 2.60	3 3/4 " 3.80	5 " 6.50	5 " 9.40	3 1/2 " 1.25	4 " 2.90
2 3/4 " 2.25	2 3/4 " 2.68	4 " 3.90	5 1/2 " 6.75	5 1/2 " 9.75	3 3/4 " 1.30	4 1/2 " 3.00
3 " 2.30	3 " 2.75	4 1/4 " 4.00	6 " 7.00	6 " 10.10	3 3/4 " 1.35	5 " 3.10
3 1/4 " 2.35	3 1/4 " 2.83	4 1/2 " 4.10	6 1/2 " 7.25	6 1/2 " 10.45	4 " 1.40	5 1/2 " 3.20
3 1/2 " 2.40	3 1/2 " 2.90	4 3/4 " 4.20	7 " 7.50	7 " 10.80		6 " 3.30
3 3/4 " 2.45	3 3/4 " 2.98	5 " 4.30	7 1/4 " 7.75	7 1/4 " 11.15		6 1/2 " 3.40
4 " 2.50	4 " 3.05	5 1/4 " 4.40	8 " 8.00	8 " 11.50	5-16 In. Fire Bolts, per 100	
4 1/4 " 2.55	4 1/4 " 3.20	5 1/2 " 4.50	8 1/2 " 8.25	8 1/2 " 11.85	1000	
4 1/2 " 2.60	4 1/2 " 3.35	6 " 4.60	9 " 8.50	9 " 12.20	5-16 In. Bolts.	
4 3/4 " 2.65	4 3/4 " 3.50	6 1/4 " 4.70	9 1/2 " 8.75	9 1/2 " 12.55	REGULAR	
5 " 2.70	5 " 3.65	6 1/2 " 4.80	10 " 9.00	10 " 12.90	ASSORTMENT.	
5 1/4 " 2.75	5 1/4 " 3.80	7 " 4.90	10 1/2 " 9.25	10 1/2 " 13.25	400-2 in. \$2.45-9.80	
5 1/2 " 2.80	5 1/2 " 3.95	7 1/4 " 5.00		11 " 13.60	300-2 1/2 " 2.60-7.80	
5 3/4 " 2.85	5 3/4 " 4.10	7 1/2 " 5.10		11 1/2 " 13.95	200-3 " 2.75-5.80	
6 " 2.90	6 " 4.25	8 " 5.20		12 " 14.30	100-3 1/2 " 2.90-5.90	
		8 1/4 " 5.30			\$26.00	

Spring Bolt				WROUGHT CUT NUTS.				WROUGHT AXLE CLIPS.			
3-16 In. CENTER	3-8 In. CENTER	3-10 In. END	3-8 In. END	1-2 in. to 3 1-4 in. Diameter.				(With Nuts—Warranted.)			
per 100	per 100	per 100	per 100	No. 0 Clip is 1/2 by 5 1/2 inch, 50				cta. per doz.			
1 in. \$2.25	1 1/4 in. \$3.20	1 1/2 in. \$2.50	2 in. \$3.50	1/2 by 1/2 inch \$10.00				1 " 1/2 6 1/2 " 50			
1 1/4 " 2.25	1 1/2 " 3.25	1 3/4 " 2.55	2 1/4 " 3.60	3/4 by 3/4 " 9.00				2 " 1/2 6 1/2 " 50			
1 1/2 " 2.25	1 3/4 " 3.30	2 " 2.62	2 1/2 " 3.70	1 by 1 " 8.50				3 " 1/2 7 1/2 " 56			
1 3/4 " 2.30	2 " 3.40	2 1/4 " 2.70	3 " 3.80	1 1/4 by 1 1/4 " 8.50				Discount per cent.			
2 " 2.35	2 1/4 " 3.50	2 3/4 " 2.78	3 1/2 " 3.90	1 1/2 by 1 1/2 " 8.00							
2 1/4 " 2.42	2 3/4 " 3.60	3 " 2.85	4 " 4.00	1 3/4 by 1 3/4 " 8.00							
2 3/4 " 2.50	3 " 3.70	3 1/4 " 2.92	4 1/2 " 4.10	2 " 7.50							
3 " 2.58		3 1/2 " 3.00	5 " 4.20	2 1/4 " 7.50							
3 1/4 " 2.65		4 " 3.00	5 1/2 " 4.30	2 3/4 " 7.50							
				Larger Nuts, up to 2 1/2 inch diameter, 7.50							

PRICE OF COACH SCREWS.				PLOW BOLTS.		
(SQUARE HEADS, WITHOUT NUTS.)				With Round or Square Countersunk Heads, and with Right or Left Hand Thread, as may be ordered.		
5-16 Inch Coach Screws, per 100	3-8 Inch Coach Screws, per 100	7-16 Inch Coach Screws, per 100	1-2 Inch Coach Screws, per 100	3-8 Inch Plow Bolts, per 100	7-16 Inch Plow Bolts, per 100	1-2 Inch Plow Bolts, per 100
1 1/2 in. \$1.70	1 1/2 in. \$1.80	2 1/2 in. \$2.70	2 1/2 in. \$3.50	1 1/2 in. \$2.00	1 1/2 in. \$2.85	1 1/2 in. \$3.25
1 3/4 " 1.75	1 3/4 " 1.85	3 " 2.90	3 " 3.65	1 3/4 " 2.18	1 3/4 " 3.20	2 " 4.00
2 " 1.80	2 " 1.92	3 1/4 " 3.10	3 " 3.80	2 " 2.38	2 " 3.35	2 1/2 " 4.50
2 1/4 " 1.88	2 1/4 " 2.00	4 " 3.30	3 1/2 " 4.10	2 " 2.58	2 1/2 " 3.50	3 " 5.00
2 1/2 " 1.93	2 1/2 " 2.08	4 1/4 " 3.50	4 " 4.40	2 1/2 " 2.78	2 1/2 " 3.75	3 1/2 " 5.75
2 3/4 " 2.03	3 " 2.24	4 1/2 " 3.62	4 1/2 " 4.70	2 3/4 " 3.00	3 " 4.00	4 " 6.50
3 " 2.10	3 1/4 " 2.40	5 " 3.75	5 " 5.00	Discount per cent.		

Machine Bolts, (With Square Heads) furnished to order, of every size and length, at the same List Price of Carriage Bolts.
Bolts for R. R. Cars, of every description.

Countersunk Heads.—Carriage Bolts with Countersunk Heads furnished to order, at prices same as for the regular kinds of Carriage Bolts.
Extra or intermediate lengths of Bolts furnished at proportional prices.
The foregoing is a revised Price List of Carriage, Tire and Spring Bolts, established and agreed to by the different makers, January, 1853.

Orders solicited and executed with promptness, on the most reasonable terms.
L. B. FROST & SONS,
MARION, CONN. January, 1855.
Manufactury on the Canal R. R. one mile West of Hitchcock's Station.