


2000000000
79



NATIONAL REGISTER OF HISTORIC PLACES REGISTRATION FORM

This form is for use in nominating or requesting determinations of eligibility for individual properties or districts. See instructions in "Guidelines for Completing National Register Forms" (National Register Bulletin 16). Complete each item by marking "x" in the appropriate box or by entering the requested information. If an item does not apply to the property being documented, enter "N/A" for "not applicable." For functions, styles, materials, and areas of significance, enter only the categories and subcategories listed in the instructions. For additional space use continuation sheets (Form 10-900a). Type all entries.

1. Name of Property

historic name Riegel Hospital
other names/site number N/A

2. Location

street & number 194 Allgood Street
city, town Trion () vicinity of
county Chattooga code GA 055
state Georgia code GA zip code 30753

() not for publication

3. Classification

Ownership of Property:

- () private
- (X) public-local
- () public-state
- () public-federal

Category of Property:

- (X) building(s)
- () district
- () site
- () structure
- () object

Number of Resources within Property:

Contributing

Noncontributing

buildings	3	0
sites	0	0
structures	0	0
objects	0	0
total	3	0

Contributing resources previously listed in the National Register: N/A

Name of previous listing: N/A

Name of related multiple property listing: N/A

4. State/Federal Agency Certification

As the designated authority under the National Historic Preservation Act of 1966, as amended, I hereby certify that this nomination meets the documentation standards for registering properties in the National Register of Historic Places and meets the procedural and professional requirements set forth in 36 CFR Part 60. In my opinion, the property meets the National Register criteria. () See continuation sheet.

Richard Coover

Signature of certifying official

1-23-02

Date

W. Ray Luce
Division Director and Deputy State Historic Preservation Officer

In my opinion, the property () meets () does not meet the National Register criteria. () See continuation sheet.

Signature of commenting or other official

Date

State or Federal agency or bureau

5. National Park Service Certification

I, hereby, certify that this property is:

entered in the National Register

Edson A. Beall 2/20/02

() determined eligible for the National Register

() determined not eligible for the National Register

() removed from the National Register

() other, explain:

() see continuation sheet

[Signature]

Keeper of the National Register

Date

6. Function or Use

Historic Functions:

HEALTH CARE/HOSPITAL

Current Functions:

HEALTH CARE/MEDICAL BUSINESS/OFFICE
VACANT/NOT IN USE

7. Description

Architectural Classification:

LATE 19TH AND EARLY 20TH CENTURY REVIVALS/COLONIAL REVIVAL

Materials:

foundation	Brick
walls	Brick
roof	Asphalt
other	N/A

Description of present and historic physical appearance:

Riegel Hospital, constructed in 1934, is centrally located in the Trion mill community in northwest Georgia. It is a long, narrow, two-story, brick building with Colonial Revival details including symmetrical facade, with nine-bay central block and three-bay pavilions at each end; flat roof with parapet; balconied entry portico featuring entablature supported by pilasters and fluted, Doric columns; and brick quoins emphasizing pavilion corners (photograph 1). Other features include a brick foundation; wooden windows, main entrance, and rear porch painted white; single and paired six-over-six double-hung sash windows; brick lintels with brick keystones (single lintel over paired windows); brick water tables at first floor level and above second story windows; brick bonding pattern consisting of five stretcher rows per row of alternating headers and stretchers; and a one-story rear entry porch supported by square columns (photograph 2). The foundation is assumed to be strip footing under the walls and spread footings under the piers.

The main entrance is on cross-axis with the double-loaded corridor that runs from one end of the building to the other. The main entrance of the hospital opens into a lobby which leads to a double-loaded corridor. The corridor extends to the south end into a smaller lobby or vestibule. It opens into small rooms on each side which served as doctors' offices, patient rooms, and treatment rooms. The corridor extends to the north end and opens into the remodeled portion of the building which includes the former African-American section. The stair lobby is in the center of the building at the rear. The second floor contains a double-loaded corridor. Rooms on each side include patient rooms, wards, and auxiliary rooms. The operating room is centrally located across from the stair lobby and nurses' station. Walls are plaster on brick or lath; ceilings are plaster on lath; and floors and baseboards are ceramic or composition tile. The interior is generally void of stylistic details or ornamentation with the exception of arched openings that are a repeated interior design feature. Mechanical systems and

United States Department of the Interior
National Park Service

National Register of Historic Places Continuation Sheet

Section 7--Description

services include an elevator, radiators, numerous plumbing fixtures, some lighting fixtures, and skylights above the second-story corridor.

Several alterations have been made to the building. The main entrance doors have been replaced with windows, and both side entrances have been altered from their original appearances (photograph 4). Several windows have been bricked in and several others have been replaced with windows that do not fit the original openings or with metal storm windows. A one-story frame addition has been built on the north side of the building (photograph 3-background).

The first floor has dropped ceilings, artificial wood paneling, and carpeted floors (photographs 7, 8, and 9). Most or all of these changes are believed to have occurred since 1975. The former African-American section at the south end has been renovated into a single doctor's office. The second floor retains its plaster walls, tile floors and walls (photographs 10-14), and arched openings (photograph 11). A nurses' station (photograph 11), operating room (photograph 12), and patient rooms (photographs 13 and 14) remain intact.

Two historic outbuildings are located on the property (photograph 6). The balloon-framed, front-gable ambulance garage and cross-gable storage building are located directly behind the main building. The buildings are wood sided and painted white with asphalt roofs and exposed rafter tails. Both buildings are believed to have been built c.1934.

South of the Chattooga River and surrounded by mostly historic residential buildings on the east, south, and west, Riegel Hospital is set back approximately 175 feet from Park Avenue on a wide expanse of lawn. Earlier foundation plantings no longer exist. A concrete walk extends from Park Avenue on the entry axis and a concrete walk on the cross-axis extends from Park Street to Town Hall on the north. A paved parking area is located at the rear of the main building.

8. Statement of Significance

Certifying official has considered the significance of this property in relation to other properties:

nationally statewide locally

Applicable National Register Criteria:

A B C D

Criteria Considerations (Exceptions): N/A

A B C D E F G

Areas of Significance (enter categories from instructions):

Architecture
Medicine

Period of Significance:

1934-1945

Significant Dates:

1934-Construction of hospital building, ambulance garage, and storage building

Significant Person(s):

N/A

Cultural Affiliation:

N/A

Architect(s)/Builder(s):

W.W. Cox

United States Department of the Interior
National Park Service

National Register of Historic Places Continuation Sheet

Section 8--Statement of Significance

Narrative statement of significance (areas of significance)

The town of Trion developed as a mill village surrounding the Trion Manufacturing Company cotton mill. The company, established in 1845, employed the majority of the residents in the area and provided services for its employees as well as the community at large, including providing a hospital for medical care. Riegel Hospital was constructed in 1934 by the Trion Company to enhance the welfare of the company's employees and the greater community, including the African-American community in a segregated section of the building until the mid-1960s. This section consisted of two rooms with three beds and was accessed by a separate rear entrance in the northwest corner on the first floor, but was remodeled recently for a dentist's office. Named in respect for Benjamin D. Riegel, president of the Trion Company from 1912-1941 and considered Trion's greatest benefactor, Riegel Hospital was later operated by the Trion Community foundation, a non-profit arm of the company, chartered for the promotion of health, education, recreation, civic improvement, and charities for the Trion community. The hospital operated continuously until 1975 at which time Chattooga County Hospital opened to serve the county. Riegel Hospital is significant in the area of architecture as an excellent example of a mid-20th century institutional building with Colonial Revival details. The character-defining features include the symmetrical facade; entry portico supported by Doric columns; double-hung sash windows; flat roof with parapet wall; brick lintels, keystones, and quoins; and the brick-bonding pattern. This type of design is characteristic of smaller institutional buildings built during the 1930s and 1940s when traditional revival architectural design and newer ideas of modern architecture were frequently juxtaposed. Character-defining interior features include the double-loaded corridors and limited ornamentation, typical of institutional buildings. The hospital is significant in the area of health/medicine for the typical activities that would have occurred at a community hospital in the mid-20th century. Riegel Hospital was the only hospital in the community and represents the paternalism of the mill owners attempting to look after the health and welfare of their workers. It was a true community asset at a time when many small Georgia communities had only limited healthcare facilities such as the traditional doctor's office (often part of the doctor's house) and drug store. This resource is a rare historic property type. It is one of only 45 hospitals in the statewide survey (40% coverage), and one of only seven in a town setting.

National Register Criteria

Riegel Hospital is eligible under Criterion A in the area of health/medicine for its significant function as a hospital and Criterion C in the area of architecture as a good and intact example of a Colonial Revival style building constructed for use as a hospital.

Criteria Considerations (if applicable)

N/A

United States Department of the Interior
National Park Service

National Register of Historic Places Continuation Sheet

Section 8--Statement of Significance

Period of significance (justification)

The period of significance represents the period in which the hospital and supporting buildings were constructed and functioned as the sole hospital in the Trion community. The period represents Trion Company ownership of the hospital and the role the company played in the community and the lives of its employees.

Contributing/Noncontributing Resources (explanation, if necessary)

The hospital building, ambulance garage, and storage building are the three contributing resources on the nominated property. There are no noncontributing resources on the property.

Developmental history/historic context (if appropriate)

****NOTE: The following history was compiled by Dan Latham, Preservation Planner, Coosa Valley Regional Development Center, July, 2000. On file at the Historic Preservation Division, Georgia Department of Natural Resources, Atlanta, Georgia.**

The town of Trion developed as a mill village around the cotton factory at Trion that was organized in 1845 by A.P. Allgood, Spencer Marsh, and W.K. Briers. It began operations in 1847. According to the census of 1850, 70 persons were employed in manufacturing in Chattooga County. George White, in *Historical Collections of Georgia* (1854), indicates that "Tryon Factory" had 864 spindles and 10 looms and employed 45 operatives. Other manufacturing operations in Chattooga County at that time consisted mostly of sawmills and grist and flour mills.

According to census records Trion Manufacturing Company accounted for a majority of Chattooga County's manufacturing employment during the last half of the 19th century. The factory escaped destruction during the Civil War but was destroyed by fire in 1875. A new brick factory was constructed in 1876. In 1888, the Chattanooga, Rome, and Columbus Railroad was built through the center of the county passing through Raccoon Mills, Summerville, and Trion. The construction of the railroad allowed for the expansion of the mill with the addition of two buildings between 1889 and 1900.

The town of Trion was incorporated on February 20, 1869, but included only the land owned by Trion Manufacturing Company. Over the next several decades, Trion's population grew steadily and the corporate limits were expanded and eventually included lands outside the control of the mill. During the 1890s, Trion experienced one of its two greatest periods of growth. The town's population increased 139 percent from 807 in 1890 to 1,926 in 1900. A 1901 article in *The Summerville News* described Trion as having two churches—Methodist and Baptist—one school, a fire protection system, one department store, one ice plant, one brick plant, one saw mill, one weekly newspaper,

United States Department of the Interior
National Park Service

National Register of Historic Places Continuation Sheet

Section 8--Statement of Significance

one ginney, one large farm, 500 houses, six warehouses, two hotels, five physicians, one livery stable, one meat market, three blacksmith shops, and one coal yard.

On August 22, 1907, Trion's corporate limits were extended to include nineteen land lots together with all roads, streets, approaches, and property used for railroad purposes lying within a radius of one mile. During the 1900s, however, Trion's population declined 10.6 percent to 1,721 in 1910. In June, 1912, the assets of the Trion Manufacturing Company were sold by order of bankruptcy court. The property was purchased by a syndicate and sold to Benjamin D. Riegel of New York. A new company, The Trion Company, was chartered under the laws of Georgia on August 31, 1912. Benjamin D. Riegel became its president.

By the mid-1920s, Trion Cotton Mills had expanded to 61,000 spindles. The 1920s were Trion's second period of rapid population growth. Its population jumped 107 percent during that decade, reaching 3,289 in 1930. In 1932, The Trion Company added a glove factory, and in 1938, a dyeing and finishing plant was built. The Dixie National highway, running north-south through the county through Trion, Summerville, and Gore, was paved in 1932-33.

It was during this period of growth and development in Trion that the Trion Company established the local hospital named after the company's president, Benjamin D. Riegel. The construction of the hospital was indicative of the importance of the mill company's role in the lives of its employees and in the community.

Chattooga County's first hospital was established in nearby Summerville in August, 1927, by Dr. W.B. Hair. Dr. N.A. Funderburk was a partner to Dr. Hair until he became head of Riegel Hospital in Trion in 1934. Dr. Funderburk was head of the hospital until September, 1942, after which Dr. William U. Hyden became head of the staff. The 18-bed hospital in Summerville was known as the Summerville-Trion Hospital until about 1945. After Dr. Hair sold his interest in the hospital, it was renamed the Summerville Hospital until it closed in November, 1948, due to low occupancy. In May, 1949, Chattooga County voters approved hospital bonds in the amount of \$110,000 toward the construction of a county hospital. The Chattooga County Hospital, located in Summerville, opened in January, 1952. The Chattooga County Hospital Authority was advised regarding the plans to close Trion Community Hospital in 1975, and the 42-bed capacity of the county facility was believed sufficient to meet the hospital needs of the county. Patients of the Trion hospital were transferred to the county facility by March 1, 1975, and the Trion doctors joined the medical staff of the Chattooga County Hospital. The Chattooga County Hospital closed on May 30, 1997. There are currently no hospital facilities in Chattooga County.

Riegel Hospital provided services to the greater Trion community and surrounding area, not just mill employees. Patients came from as far away as Dalton, Georgia and northwestern Alabama. Company employees could pay for services through payroll deductions.

United States Department of the Interior
National Park Service

National Register of Historic Places Continuation Sheet

Section 8--Statement of Significance

Riegel Hospital served the African-American community in a segregated section of the hospital prior to the facility being integrated in the mid-1960s. This segregated section consisted of little more than two rooms and three beds in the northwest corner of the first floor accessed by an outside rear entry. This section of the historic hospital was later remodeled into a dentist's office.

Benjamin D. Riegel, generally considered Trion's greatest benefactor, died on November 6, 1941. His death marked the end of an era defined by a long list of community improvements. These included paved streets, modern recreational facilities, new schools, new and improved housing (including a large dormitory and a row of brick apartments along Park Avenue), a beautiful landscaped plaza constructed between the mills, and of course the community hospital. In addition, Riegel acquired a herd of prized Guernsey cattle and built a large, modern dairy that he named Riegeldale Farm. He also built the Riegeldale Tavern and gardens across from the dairy at the south end of town on the Dixie Highway. It was operated as a restaurant and an outlet for his dairy products. Trion had all the conveniences needed for its people, including its own modern department store, service station, saw mill, ice plant, bank, library, barber shop, and beauty parlor.

Two of the aforementioned improvements, the Riegel Hospital and Leila Riegel Hall dormitory (no longer extant), were opened to the public for inspection at ten o'clock on the morning of April 12, 1934. The Summerville News declared that Saturday to be "one of the greatest days the people of Trion have ever seen" and that it "will be long-remembered by the citizens of this town."

The two-story, thirty-bed hospital was situated in "South Trion," called an "ideal location that will assure quietness to patients." Immediately north of the hospital was the three-story Leila Riegel Hall, a dormitory built to house some 300 girls. The new buildings were described as being of "old Colonial architecture." The hospital was "modern equipped in every respect" and "as fireproof as any building can be made." The land on which the hospital and dormitory were built had been used originally as a community pasture. The hospital's medical staff was said to be "well-trained in the diagnosis of physical ailments and also in surgical work," and the hospital was said to offer its patients "the best in medical knowledge that can be had in this part of the country.: Dr. N.A. Funderburk was head of the staff of physicians that included Doctors Mitchell, Baker, and Chunn.

A few years after Benjamin D. Riegel's death, on August 14, 1945, The Trion Community Foundation, Inc., was chartered. Incorporators were John L. Riegel, a cousin of Benjamin, and G.H.H. Emory, both of New York, and E.W. Reid and N.B. Murphy, president of The Trion Company, both of Trion. The sole purpose of this new nonprofit corporation was "to provide, acquire, maintain, and operate facilities for the promotion of health, education, recreation, civic improvement and charities for the Trion community." It was expressly given the power and authority to acquire and operate any hospital, clinic, or other facility for the promotion and protection of the health of the community; to acquire and operate recreational facilities, such as community centers, athletic fields, and parks; and to provide funds for other charitable and humanitarian purposes, including providing student loan

United States Department of the Interior
National Park Service

National Register of Historic Places Continuation Sheet

Section 8--Statement of Significance

funds for education. On December 26, 1945, The Trion Company donated the Riegel Community Hospital property to the Trion Community Foundation.

In June, 1946, The Trion Company and the Ware Shoals (South Carolina) Manufacturing Company were combined into a new corporation, Riegel Textile Corporation, organized under the laws of Delaware. Trion's population declined by 20 percent during the 1940s, and it lost its status as the county's largest town. Summerville's corporate limits were greatly expanded in 1945, and its 1950 population of 3,973 surpassed Trion's 3,028.

The Trion Community Foundation, Inc., operated the hospital, then called Trion Community Hospital, for almost 30 years. By the 1970s, the hospital building did not meet standards for Medicare and Medicaid or state fire regulations. Fearing that the state would not continue to grant the hospital a certificate to operate due to the building's obsolescence and deficiencies, the Trion Community Foundation decided to close the facility. The Trion Community Hospital officially closed on March 1, 1975. At that time, there were three doctors on staff. The doctors continued to use their offices on the first floor of the building, which then became known as the Trion Doctors' Building.

The Trion Community Foundation, Inc., sold the old hospital property in April, 1986. Portions of the building continued to be used for medical offices. In November, 1999, the Trion Town Council voted to purchase the property. The acquisition was completed in March, 2000.

9. Major Bibliographic References

Chattooga County Cooperative Joint Planning Committee and Coosa Valley Regional Development Center. Chattooga County, Georgia, Comprehensive Plan, 1995-2001, Including the Cities of Lyerly, Menlo, Summerville, and Trion. N.p., 1995.

Chattooga County, Georgia. Superior Court. Clerk's Office. Charter Record Book 2, pp. 84-86, 95-99.

Chattooga County Deed Book 34, 9. 347.

Chattooga County Deed Book 207, p. 528.

Latham, Dan. Historic Property Information Form. On file at the Historic Preservation Division, Georgia Department of Natural Resources, Atlanta, Georgia. With supplemental information.

Nunn, T. Emmet. One Way to See It. N.p., [1998].

"Opening Day at Trion Great Success; Sen. Russell Speaks." *The Summerville News*, April 26, 1934, p. 1.

Trion: Our Favored Land. Summerville, Georgia: Espy Publishing Company, Inc., 1976.

Previous documentation on file (NPS): () N/A

- preliminary determination of individual listing (36 CFR 67) has been requested**
- preliminary determination of individual listing (36 CFR 67) has been issued**
date issued:
- previously listed in the National Register**
- previously determined eligible by the National Register**
- designated a National Historic Landmark**
- recorded by Historic American Buildings Survey #**
- recorded by Historic American Engineering Record #**

Primary location of additional data:

- State historic preservation office**
- Other State Agency**
- Federal agency**
- Local government**
- University**
- Other, Specify Repository:**

Georgia Historic Resources Survey Number (if assigned): N/A

10. Geographical Data

Acreage of Property 1.7 acres

UTM References

A) Zone 16 Easting 654826 Northing 3823338

Verbal Boundary Description

The boundary of the nominated property follows the current legal boundary and is indicated on the attached map by a heavy black line.

Boundary Justification

The boundary of the nominated property includes the intact parcel of land historically associated with the hospital. It includes the historic hospital and its two small auxiliary buildings.

11. Form Prepared By

State Historic Preservation Office

name/title Holly L. Anderson, National Register Historian
organization Historic Preservation Division, Georgia Department of Natural Resources
street & number 156 Trinity Avenue, SW, Suite 101
city or town Atlanta **state** Georgia **zip code** 30303
telephone (404) 656-2840 **date** August 13, 2001

Consulting Services/Technical Assistance (if applicable) () not applicable

name/title Dan Latham, Preservation Planner
organization Coosa Valley Regional Development Center
street and number P.O. Box 1793
city or town Rome **state** Georgia **zip code** 30162-1793

() **consultant**
(X) **regional development center preservation planner**
() **other:**

(HPD form version 02-24-97)

United States Department of the Interior
National Park Service

National Register of Historic Places
Continuation Sheet

Photographs

Name of Property: Riegel Hospital
City or Vicinity: Trion
County: Chattooga
State: Georgia
Photographer: James R. Lockhart
Negative Filed: Georgia Department of Natural Resources
Date Photographed: January, 2001

Description of Photograph(s):


- 1 of 15: Front facade; photographer facing west.
- 2 of 15: Original front entrance; photographer facing west.
- 3 of 15: Front facade and south facade; photographer facing northwest.
- 4 of 15: South facade; photographer facing north.
- 5 of 15: Rear facade; photographer facing northeast.
- 6 of 15: Ambulance garage and storage building; photographer facing northwest.
- 7 of 15: Interior, first floor, treatment room; photographer facing east.
- 8 of 15: Interior, first floor; photographer facing south.
- 9 of 15: Interior, first floor, laboratory; photographer facing west.
- 10 of 15: Interior, second floor; photographer facing south.
- 11 of 15: Interior, second floor, nurses' station; photographer facing east.
- 12 of 15: Interior, second floor, operating room; photographer facing south.
- 13 of 15: Interior, second floor, patient room; photographer facing east.
- 14 of 15: Interior, second floor, patient room; photographer facing east.

United States Department of the Interior
National Park Service

National Register of Historic Places
Continuation Sheet


Photographs

15 of 15: Front facade, site; photographer facing southwest.



Riegel Hospital
 Trion, Chattooga County, Georgia
 Chattooga County Tax Map 14, City of Trion
 National Register Boundary: **——**
 Scale: 1"=100'
 North: ↑


Riegel Hospital
 Trion, Chattooga County, Georgia
 Site Plan/Exterior Photograph Key
 Photograph Direction/Number: \triangle
 Scale: Not to scale
 North: \rightarrow



RIEGEL COMMUNITY HOSPITAL
 DRAWN BY: Dan Latham, CVRDC
 DATE: 11-22-2000

PARK AVENUE


Riegel Hospital
 Trion, Chattooga County, Georgia
 First Floor Plan/Interior Photograph Key
 Photograph Direction/Number: \blacktriangle
 Scale: On map
 North: \blacktriangleright



First Floor

Coosa Valley Regional Development Center	
Riegel Community Hospital	
Drawn By: M. Busby Date: 11-15-00 Scale: $\frac{3}{32}'' = 1'-0''$	First Floor

Riegel Hospital
 Trion, Chattooga County, Georgia
 Second Floor Plan/Interior Photograph Key
 Photograph Direction/Number: \triangle
 Scale: On map
 North: \rightarrow



Second Floor

Coosa Valley Regional Development Center	
Riegel Community Hospital	
Drawn By: M. Busby Date: 11-15-00 Scale: $\frac{3}{32}'' = 1'-0''$	Second Floor